


408 978

N-63-4-2

CATALOGED BY DDC
AS AD NO. 408978

BOEING



RECEIVED
JUL 24 1963
TIAA D

SEATTLE, WASHINGTON

THE **BOEING** COMPANY

CODE IDENT NO. 81205

NUMBER D2-14826

TITLE TECHNICAL FACILITY CRITERIA FOR THE MINUTEMAN LAUNCH
FACILITIES - FRANCIS E. WARREN AFB, WYOMING (U)

MODEL NO. WS-133A CONTRACT NO. AFO4(694)-107

ISSUE NO. 34 ISSUED TO IdC

Specification: S-133-30-15

SPECIAL LIMITATIONS ON ASTIA DISTRIBUTION

ASTIA may distribute this report to requesting agencies subject to their security agreement, approved fields of interest, and the following:

☒ UNLIMITED—To all agencies of the Department of Defense and their contractors.

☐ LIMITED—To U. S. Military organizations only.

This report may be distributed to nonmilitary agencies not approved above subject to Boeing approval of each request.

NOTE: the LIMITED category may be checked only because of actual or potential patent, proprietary, ethical, or similar implications.

PREPARED BY

D. E. Dougald
D. E. Dougald

6-17-63

SUPERVISED BY

R. O. Smith
R. O. Smith

6-19-63

APPROVED BY

G. A. Gutkowski
G. A. Gutkowski

6/19/63

APPROVED BY

H. N. Stuveruse
H. N. Stuveruse

6/19/63

CLASS & DISTR
APPROVED BY

G. A. Gutkowski
G. A. Gutkowski

6/19/63

(DATE)

REV SYM _____

U3 4287 8038 ORIG. 8/62

VOL. NO.

OF

SECT.

PAGE 1 of 38

2-8142-2

ACTIVE PAGE RECORD

SECTION	ORIG REL PAGE NO.	REV SYM	ADDED PAGES					SECTION	ORIG REL PAGE NO.	REV SYM	ADDED PAGES				
			PAGE NO.	REV SYM	PAGE NO.	REV SYM	PAGE NO.				PAGE NO.	REV SYM	PAGE NO.	REV SYM	PAGE NO.
	1														
	2														
	3														
	4														
	5														
	6														
	7														
	8														
	9														
	10														
	11														
	12														
	13														
	14														
	15														
	16														
	17														
	18														
	19														
	20														
	21														
	22														
	23														
	24														
	25														
	26														
	27														
	28														
	29														
	30														
	31														
	32														
	33														
	34														
	35														
	36														
	37														
	38														

U3 4801 0600 ORIG. 8/82

2-8142-2

REV SYM _____

BOEING

NO. D2-14826

SECT.

PAGE

2

FOREWORD

The original requirements for the WS-133A Launch Facilities were initially presented in STL document GM 60-A001-04702 (S-133-30-10). The STL document covered facilities design criteria as well as the form, fit, and function requirements of the Associate Contractors' equipment for Minuteman Wing I at Malmstrom AFB, Montana.

State of the art progress has dictated numerous changes and improvements to the original Launch Facility requirements. A large number of these variations were incorporated into Wing I by a revised and updated GM 60-A001-04702 (S-133-30-10) issued as Boeing document D2-14324. Variations peculiar to Minuteman Wing II at Ellsworth AFB, South Dakota, were included in Boeing document D2-10692 which was issued as a supplement to the Wing I criteria document and was limited to changes and additions thereto.

Subsequent revisions to the Launch Facility requirements and improvements to the Weapon System, dictated the need for an original documentation of the facilities criteria for Wing III, North Dakota, in Boeing Document D2-13797. The first revision to Boeing Document D2-13797 incorporated criteria variations peculiar to Wing IV facilities at Whiteman AFB, Missouri.

Normal sequence of events would have placed the facilities design criteria in the hands of the Air Force agency awarding the facility contracts prior to the start of facilities design. Because of the Minuteman program concept of design and construction concurrency and also due to compressed schedules, this action did not occur for Wings III, IV and V. Nevertheless, the necessity for this document, as a base line for control of the form, fit, and function of the Associate Contractors' equipment, is most significant if existing facilities are to be used to the maximum extent practical.

Wing III criteria has been modified and updated to indicate Wing V requirements as a result of the following actions:

1. Collation of facility requirements which were developed through MIL-D-9412c Functional Analysis of the Wing V Weapon System (S-133-11-0-5) and S-133-12-0-5);
2. Incorporation of basic design and equipment compatibility changes as designated by the Configuration Control Board;
3. Incorporation of MCL/FCR changes through 15 May 1963.
4. Incorporation of facility design improvements resulting from criteria and concept review meetings;
5. Review and Analysis of existing plans and specifications and "Basis of Design" for Wing V.

FOREWORD

(Continued)

This specification describes the facility requirements necessary to make the Weapon System operable within established goals, with due consideration given to the existing facilities and associated conditions.

TABLE OF CONTENTS

	PAGE
TITLE PAGE	1
REVISION PAGE	2
FOREWORD	4
CONTENTS	6
LIST OF FIGURES	7
<u>SECTION</u>	<u>TITLE</u>
1.0	<u>SCOPE</u> 8
2.0	<u>APPLICABLE DOCUMENTS</u> 9
3.0	<u>GENERAL CRITERIA</u> 10
3.1.3	Physical Description 10
3.3.1	Geographical 10
3.6	Summary of Changes to Section 3 Figures 10
5.0	<u>INTEGRATED CRITERIA</u> 11
5.10	Table 5-1 Launch Facility AGE 11
5.11	Summary of Changes to Section 5 Figures 11
6.0	<u>SERVICE AREA AND ACCESS ROAD CRITERIA</u> 14
6.10	Summary of Changes to Section 6 Figures 14
7.0	<u>LAUNCHER SUPPORT BUILDING CRITERIA</u> 17
7.7	Security 17
7.8	Summary of Changes to Section 7 Figures 17
9.0	<u>LAUNCHER EQUIPMENT ROOM CRITERIA</u> 25
9.2.4	Sight Tube 25
9.8	Summary of Changes to Section 9 Figures 25
10.0	<u>LAUNCH TUBE CRITERIA</u> 32
10.2.1	Layout 32
10.8	Summary of Changes to Section 10 Figures 32

U3 4288 2000 REV. 8/62

2-5142-2

REV SYM _____

BOEING

NO. D2-14826

SECT.

PAGE 6

LIST OF FIGURES

<u>FIGURE NO.</u>	<u>TITLE</u>	<u>PAGE</u>
5-3.1	Intrasite Cabling and Conduit	12
5-4	Grounding Locations	13
6-7.4	Conduit Routing and Passive Reflector Location	15
6-7.6	Security Pole and J-Box Details	16
7-1	Environmental Control Equipment	18
7-1.1	Environmental Control Equipment Sections and Details	19
7-2	Electrical Equipment	20
7-2.1	Electrical Conduit Details	21
7-2.2	Platform Openings for Equipment Attachment	22
7-2.3	Switchboard Elevation	23
7-3	Interface Cabinet Connection Diagram	24
9-1.4	Umbilical Retract Details	26
9-1.6	Second Level Plumbing and Electrical Layout	27
9-1.7	Pipe Section and Details	28
9-2	Personnel Access System and Sight Tube	29
9-2.3	Developed View of CPF Enclosure	30
9-6	Telephone Jack Mounting	31
10-1	Plan and Section	33
10-3	Equipment and Service Lines	34
10-3.1	Location of Service Lines	35
10-4	Sections and Details	36
10-6	Missile Support Loads	37
10-6.1	Missile Support Plates and Details	38

1.0 SCOPE

The technical facility criteria document for the Minuteman Launch Facilities at Francis E. Warren AFB is issued as a supplement to the Wing III Launch Facility criteria presented in Boeing Document D2-13797. The complete Wing V Launch Facility criteria consists of the following:

- a. Sections one (1) through ten (10) of Document D2-13797 applicable to Wing III and Wing V.

Section eleven (11) of Document D2-13797 identifies Wing IV peculiar criteria only, and is not applicable to Wing V.

- b. Document D2-14826 which identifies the revised or additional requirements to site adapt and upgrade the Minuteman Launch Facilities for Francis E. Warren AFB in accordance with the latest Weapon System improvements. These requirements are identified by Paragraph and Figure notations corresponding to those in Document D2-13797. Where necessary, flagnote indicators are included on the Figures to assist in identifying FWAAB peculiar variations.

2.0 APPLICABLE DOCUMENTS

- p. Change to read "Master Change Log updated as of 15 May 1963."

3.0 GENERAL / CRITERIA

3.1.3 Physical Description

Change reference from "Minot Air Force Base (MTAFB)" to read "Francis E. Warren Air Force Base (FWAFB)".

3.3.1 Geographical

Change paragraph to read "Wing V, the fifth Minuteman Operational Deployment Area, shall be sited in the vicinity of Francis E. Warren Air Force Base, (FWAFB) at Cheyenne, Wyoming."

3.5 Table 3-1, "RPIC Sub-System Failure Rates"

Failure Rates are based on 150 missile wing. Values should be proportioned to reflect failure rates for 200 missile wing.

3.6 SUMMARY OF CHANGES TO SECTION 3 FIGURES.

3.6.1 Title of Figure 3-1 should read Francis E. Warren Air Force Base, Wyoming.

5.0 INTEGRATED CRITERIA

5.10 Table 5-1 Launch Facility AGE


The following Wing V peculiar Launch Facility AGE should be entered in the corresponding item numbers of Table 5-1. These Wing V peculiar Figure "A" numbers are applicable throughout Document D2-13797 wherever corresponding equipment is referenced.

<u>Item No.</u>	<u>Fig. "A"</u>	<u>Equipment</u>
4	1248.5	Cable Assembly Set
8	1322.5	Support, Missile, Suspension and Alignment System GSU-112/E
14	1228.5	Status - Command Message Processing Group OA-3594/GYK-2
15	1251.5	Digital Data Group OA-3593/GYK-2
25	1374.5	Arrestor Set, Electrical Surge MX /GSW-4
27	1377.5	Interconnecting Box J-1386/GSW-4

5.11 SUMMARY OF CHANGES TO SECTION 5 FIGURES.

5.11.1 Figure 5-3.1 is revised to indicate the FWAFFB peculiar layout of intra-site cabling and conduits between the Launcher and LSB.

5.11.2 Figure 5-4 is revised to show peculiar conduit layout to grounding points for FWAFFB.



SITE PLAN


FWAFB LAUNCH FACILITY	02-14826	PAGE	13
INTEGRATED CRITERIA	FIG. 5-4		
GROUNDING LOCATIONS			
THE BOEING COMPANY			
DATE			
REVISED			
CALC			
CHECK			
APP			
APP			

6.0 SERVICE AREA AND ACCESS ROAD CRITERIA

6.10 SUMMARY OF CHANGES TO SECTION 6 FIGURES

6.10.1 Figure 6-7.4 deletes Security J-Box located near XMTR antenna and also the 2" c.o. extending between the Security J-Box and the S/R RCVR. A conduit is added between the Launcher and the S/R RCVR.


6.10.2 Figure 6-7.6 deletes Detail 1 and Section A of the Security J-Box.



SITE PLAN — CONDUIT ROUTING

SITE PLAN — PASSIVE REFLECTOR LOCATION

CALC	REVIS	DATE	FWAFB LAUNCH FACILITY SERVICE AREA & ACCESS ROADS CONDUIT ROUTING & PASSIVE REFLECTOR LOCATION THE BOEING COMPANY	D2-14826
CHECK				FIG. S-74
APP				PAGE
APP				15



DATE	REVISED	DATE	FWAFB LAUNCH FACILITY SERVICE AREA & ACCESS ROADS SECURITY POLE & J-BOX DETAILS	D2-14826
CALC				
CHECK				
APP				FIG. 6-76
APP			THE BOEING COMPANY	PAGE 16

7.0 LAUNCHER SUPPORT BUILDING CRITERIA

7.7 SECURITY

Delete reference to "Security J-Box" in last sentence of paragraph. Sentence should read "An interface cabinet shall be installed, with provision for termination of all security system wiring herein, as shown in Figures 7-2.3 and 7-3".

7.8 SUMMARY OF CHANGES TO SECTION 7 FIGURES

7.8.1 Figure 7-1 indicates the change in size of hydraulic lines from $\frac{1}{4}$ " to $\frac{1}{2}$ ", and relocates penetration of the 1" sump pump drain line.

7.8.2 Figure 7-1.1 shows relocation of 2" air relief line in Detail 1, and changes horizontal dimension from 5'-0" to 6" from fresh air intake to exterior surface of LSB wall in Section B.


7.8.3 Figure 7-2 indicates modifications to the electrical equipment layout in plan and section.


7.8.4 Figure 7-2.1 relocates the intrasite cable penetrations at the LSB exterior wall.

7.8.5 Figure 7-2.2 specifies the variations to the location of openings and J-boxes in the LSB shock mounted floor.


7.8.6 Figure 7-2.3 is added to show the switchboard panel elevation and necessary details.

7.8.7 Figure 7-3 shows the wiring connection schematic for the Interface Cabinet. In lieu of a separate Security Terminal Cabinet as used in Wing III, the necessary security terminals shall be incorporated in the Interface Cabinet for Wing V.





CALC	REVISED	DATE	FWAFB LAUNCH FACILITY	D2-14826
CHECK			LAUNCHER SUPPORT BUILDING	FIG. 7-2.1
APP			ELECTRICAL CONDUIT DETAILS	PAGE 21
APP			THE BOEING COMPANY	



FLOOR PLATE PLAN

SHOCK PROOF J-BOX

DETAIL 1


SECTION A

SECTION B

SECTION 1


FWAFB PECULIAR

[illegible]



SECTION A
7-2

CALC		REVISED	DATE	F W A F B LAUNCH FACILITY	D2-14826
CHECK				LAUNCHER SUPPORT BUILDING	
APP				SWITCHBOARD ELEVATION	FIG. 7-2.3
APP				THE BOEING COMPANY	PAGE 23



CAIC	R.L. ORNESS	5/30/3	REVISED	DATE	FWAFB LAUNCH FACILITY LAUNCHER SUPPORT BUILDING INTERFACE CABINET CONNECTION DIAGRAM	D2-14826
CHECK						FIG. 7-3
APR						PAGE
APR						24
					THE BOEING COMPANY	

9.0 LAUNCHER EQUIPMENT ROOM CRITERIA

9.2.1 Sight Tube

Change dimension in Sentence "A Sight Tube, 24 inches maximum diameter ..." to read "A sight tube, 12 inches maximum inside diameter...".

9.8 SUMMARY OF CHANGES TO SECTION 9 FIGURES

9.8.1 Figure 9-1.4 changes configuration of stiffener plates at umbilical retraction unit, Detail 1.


9.8.2 Figure 9-1.6 shows changes to electrical conduit arrangement and conduit sizes at MER wall penetration.

9.8.3 Figure 9-1.7 shows interface change at brine supply and return lines, Section A; and indicates a change in requirements for conduit penetration of line, Detail 2.


9.8.4 Figure 9-2 shows the Sight Tube inside diameter change from 24" to 12".

9.8.5 Figure 9-2.3 indicates the changes in stub-out locations and configuration of 4" copper plate grounding bus.

9.8.6 Figure 9-6 shows azimuth change from 168° to 166° for telephone jack mount location in the launch tube.




SECTION A



DETAIL 2
9-16


TYPICAL LAUNCH TUBE LINER PENETRATION




DETAIL 1
9-L6

TYPICAL HARDENED CABLE PENETRATION

FWAFB LAUNCH FACILITY	D2-14826
LAUNCHER EQUIPMENT ROOM	FIG. 9-1.7
PIPE SECTION & DETAILS	PAGE 28
THE BOEING COMPANY	



PARTIAL PLAN - SIGHT TUBE




SECTION A-A

1 FWAFB PECULIAR

DATE	REVIS	CHK	APP	DATE	REVIS	CHK	APP

FWAFB LAUNCH FACILITY
LAUNCHER EQUIPMENT ROOM
PERSONNEL ACCESS
SYSTEM & SIGHT TUBE
THE BOEING COMPANY



10.0 LAUNCH TUBE CRITERIA

10.2.1 Layout

Item b, change dimension in statement "length from flame deflector to the Autocollimator line-of-sight: 65'-2" to read "75'-2".

10.8 SUMMARY OF CHANGES TO SECTION 10 FIGURES

10.8.1 Figure 10-1 indicates the change in Launch Tube length measured from bottom of Closure to top of deflector plate from 77'-0" to 87'-0"; and adds the 10'-0" allowance for missile growth.


10.8.2 Figure 10-3 deletes the 14'-0" dimension from deflector plate to centerline of sump pump discharge line horizontal run; and indicates embedment and modification to layout of sump pump discharge line and battery drain line. Dimensional changes are shown from deflector plate to MPT J-Boxes.

10.8.3 Figure 10-3.1 deletes Detail 1 showing minimum attachment and proximity relationships between MPT J-Box and sump pump discharge line; and shows requirement for embedding sump pump discharge line in launch tube wall.

10.8.4 Figure 10-4. Details of typical butt joint in monorail track are changed to show increased "faired to match" requirement from 2 $\frac{1}{2}$ " to 4".

10.8.5 Figure 10-6 shows increased dimension range from deflector plate to load point at upper missile support plate from "20'-3" to 26'-3" to "30'-3" to 36'-3".

10.8.6 Figure 10-6.1 modifies dimension from deflector plate to top of upper support plate from 29'-1" to 39'-1". At Section A the dimension from centerline to outside edge of upper support plate is changed from 1'-0" to 1'-0 5/16".




SECTION A
10-3


FWAFB PECULIAR

CALC	REVISED	DATE	FWAFB LAUNCH FACILITY	D2-14826
CHECK			LAUNCH TUBE	FIG. 10-3.1
APR			LOCATION OF SERVICE LINES	PAGE 35
APR			THE BOEING COMPANY	


- 1 FORCE DUE TO 2.0 LOAD ON MISSILE & MOUNT.
- 2 FORCE DUE TO GROUND SHOCK ON HARDWARE=WT.X30
LOAD MAY ACT IN ANY HORIZONTAL OR VERTICAL
DIRECTION EITHER SIMULTANEOUSLY OR INDEPENDENTLY
IN ANY HORIZONTAL OR VERTICAL DIRECTION
COMBINED WITH VERTICAL LOAD FROM 1
- 3 FORCE DUE TO GROUND SHOCK ON HARDWARE=WT.X30
LOAD MAY ACT IN ANY HORIZONTAL OR VERTICAL
DIRECTION EITHER SIMULTANEOUSLY OR INDEPENDENTLY
IN ANY HORIZONTAL OR VERTICAL DIRECTION
COMBINED WITH VERTICAL LOAD FROM 1
- 4 MAXIMUM ACTUAL LOAD DUE TO SNUBBING
DURING FLIGHT. DOES NOT OCCUR WITH OTHER LOADS SHOWN.
- 5 FORCE DUE TO GROUND SHOCK ON HARDWARE=WT.X30
LOAD MAY ACT IN EITHER DIRECTION OF ARROW
ONLY THRU C.G.
- 6 FORCE DUE TO GROUND SHOCK ON HARDWARE=WT.X30
LOAD MAY ACT IN ANY HORIZONTAL OR VERTICAL
DIRECTION EITHER SIMULTANEOUSLY OR INDEPENDENTLY
WHICHEVER IS MORE SEVERE. GROUND SHOCK LOAD
DOES NOT COMBINE WITH LOAD FROM 4
- 7 80 K-IN. TORQUE AT FLOOR LEVEL ACTING WITH
57 KIP MISSILE LOAD AND LOAD FROM 5
- 8 FORCE DUE TO GROUND SHOCK ON HARDWARE=WT.X30.
LOAD MAY ACT IN ANY HORIZONTAL DIRECTION ONLY THRU C.G.
- 9 LOADS MAY ACT SEPARATELY
OR SIMULTANEOUSLY WHICHEVER
IS MORE SEVERE.
- 10 FWAAS PECULIAR



SECTION B



SECTION C



TYPICAL SECTION AT LOAD POINTS

CALC	REVIS	DATE	102-14826
CHECK			LAUNCH TUBE
APP			MISSILE SUPPORT LOADS
APP			THE BOEING COMPANY
			PAGE 37

