

UNCLASSIFIED

AD - 4 2 5 5 5 2

DEFENSE DOCUMENTATION CENTER

FOR

SCIENTIFIC AND TECHNICAL INFORMATION

CAMERON STATION, ALEXANDRIA, VIRGINIA



UNCLASSIFIED

NOTICE: When government or other drawings, specifications or other data are used for any purpose other than in connection with a definitely related government procurement operation, the U. S. Government thereby incurs no responsibility, nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any way be related thereto.

AD NO. 426552



(5) 446500

OK

1


Technical Documentary Report
No. RTD-TDR-63-4069

CRITICAL COMPILATION OF CERAMIC
FORMING METHODS

Final Report

A. G. Pincus, project coordinator

Report No. MT-63-12
Contract AF 33(657)-10574
September 1963



INSTITUTE OF ENGINEERING RESEARCH

UNIVERSITY OF CALIFORNIA

Berkeley, California

\$22.25

(5) 446 500

(18) RTD (19) TDR 63-4069

(6) CRITICAL COMPILATION OF CERAMIC FORMING METHODS /

(9) Final report Apr - Sep 63.

Technical Documentary Report No. RTD-TDR-63-4069

(11) September 1963,

(14) Rept. no. MT 63-12

AF Materials Laboratory
Research and Technology Division
Air Force Systems Command
Wright-Patterson Air Force Base, Ohio

(16) Project No. 7381 (17) Task No. 738105

(15)
(Prepared under Contract AF 33(657)-10574
by the University of California, Berkeley, California;
College of Engineering, Department of Mineral Technology;
A. G. Pincus, project coordinator

J.C.

NOTICES

When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Qualified requesters may obtain copies of this report from the Defense Documentation Center (DDC), (formerly ASTIA), Arlington Hall Station, Arlington 12, Virginia.

This report has been released to the Office of Technical Services, U. S. Department of Commerce, Washington 25, D.C., for sale to the general public.

Copies of this report should not be returned to the Aeronautical Systems Division unless return is required by security considerations, contractual obligations, or notice on a specific document.

FOREWORD

(21) Byrd on

This report was prepared by the University of California, under USAF Contract No. AF 33(657)-10574. This contract was initiated under Project No. 7381, "Materials Application," Task No. 738105, "Ceramic and Graphite Technical Information". The project and report have been the responsibility of the Department of Mineral Technology, College of Engineering, University of California at Berkeley with Professor D. W. Fuerstenau as faculty investigator, A. G. Pincus as project coordinator, and an active staff of consultants and specialists as acknowledged on the following page. In addition more than 110 experts in the forming of ceramics volunteered advice to the project by attendance at intensive day-long conferences, private discussions, and submission of memos and literature. They represent an extensive cross-section of companies active in the forming of ceramics by the variety of techniques described in the report, as well as specialists from universities, government laboratories, and publications. It is regretted that they can not each be cited by name.

The work was administered under the direction of the AF Materials Laboratory, Research and Technology Division, with Mr. C. E. Butler as acting chief, Ceramics and Graphite Technical Evaluation section during the early stages of the contract and Mr. S. W. Bradstreet as chief starting May 15, 1963. Mr. Lawrence Kopell has been project engineer.

This report covers work done from April 1963 to September 1963.

PROJECT STAFF

Alexis G. Pincus, Ph.D. - Research Engineer, project coordinator, and editor.
Douglas W. Fuerstenau, Sc.D. - Professor of Metallurgy, and principal investigator.
Joseph A. Pask, Ph.D. - Professor of Ceramic Engineering; consultant.
Richard M. Fulrath, Ph.D. - Associate Professor of Ceramic Engineering; consultant.
Alfred W. Allen, M.S. - Professor of Ceramic Engineering, University of Illinois; consultant and co-editor.
Alfred R. Cooper, Sc.D. - Assistant Professor of Ceramics, Massachusetts Institute of Technology; consultant.
Donald J. Bowers, M.S. - Assistant Chief, Ceramic Division, Battelle Memorial Institute; consultant.
Winston H. Duckworth, M.S. - Chief Ceramic Division, Battelle Memorial Institute; consultant.
Ralph E. Rose, B.S. Junior Specialist.
Virginia A. Mae, A.B. Bibliographer.
Andrew L. Mular, M.S. Junior Research Engineer.
Diane Peters, Senior Clerk-Typist.
Susan Farnsworth, Senior Clerk-Typist.
Dennis Allison, Engineering Aide.
Richard G. Fulton, Laboratory Helper.
Leslie D. Vliet, Laboratory Helper.


ACKNOWLEDGMENTS

The staff wishes to acknowledge the special help so graciously contributed by Mr. W. J. Tonkin and his entire office staff of the Institute of Engineering Research, University of California, Berkeley. Also Mr. John V. Kauffman, Contracting Officer, Aeronautical Systems Command, Wright-Patterson Air Force Base. Thanks are due to various members of the Inorganic Materials Research Division Lawrence Radiation Laboratory, University of California. Professor Pask and Dr. Pincus served on the Ad Hoc Committee on Processing of Ceramic Materials of the Materials Advisory Board, National Academy of Science/National Research Council from October 1962 to September 1963 and acknowledgements are made for the abundant information and ideas from the activities of the committee and from its report which have aided this project.

ABSTRACT

↙
A first phase study is presented on methods for forming and characterizing ceramics. Five reviews by individual authors appraise the state of the art in characterizing the raw materials and batches and forming by cold, hot, melt, and miscellaneous processes. The derived fundamentals contributing to control over forming are briefly summarized. Initial bibliographies arranged on a specially evolved classification scheme introduce the literature on characterization of particles and assemblies of particles, and on forming of ceramics. ↗

This technical documentary report has been reviewed and is approved.



D. A. SHINN
Chief, Materials Information Branch
Materials Applications Division
AF Materials Laboratory

TABLE OF CONTENTS

I. General Introduction	Page 1
II. Surveys of Methods of Forming Ceramics	5
Notes on procedures	
A. Characterization of Particulate Systems-	
D. W. Fuerstenau and A. L. Mular	6
Properties of particles and assemblies of particles	6
Preparation of particles	9
Properties dependent upon the physical nature of particles	10
Properties dependent upon the chemical nature of particles	14
Need for careful characterization of Powders	17
B. Cold Forming Processes-	
A. W. Allen, University of Illinois	18
1. Compaction response in Cold Forming	18
2. Progression of material characterization in cold forming processes	22
3. Characterized particulate base materials	25
4. Characterized stable agglomerate base material	27
5. Forming system design: general comments	29
6. Geometric characterization of finished ceramic shapes	31
C. Hot Forming Processes-	
R. M. Fulrath	33
1. Hot forming methods	33
2. Uniaxial hot pressing	34
3. Other hot forming methods	40
4. Summary of hot forming methods	42
D. Melt Forming Processes-	
A. R. Cooper, Massachusetts Institute of Technology	44
Introductory remarks	
1. Glass forming processes	47
2. Crystallization of articles originally made as glasses	51
3. Melting and solidification of non-glassy ceramics in bulk (Fusion casting)	53
4. Melting particles individually (melt spraying)	57
E. Miscellaneous Forming Methods-	
D. J. Bowers, Batelle Memorial Institute	66
1. Forming from vapors	66
2. Foamed ceramics	68
3. Forming from fibers	69
4. Bulk placement and molding	70
5. Impregnation	71
6. Reaction sintering	71
7. High energy rate forming	72
8. Electrophoretic forming	74
9. Machining and grinding	74

TABLE OF CONTENTS (continued)

III. Fundamentals of Forming	Page 77
IV. Summary and Conclusions	80
V. Bibliographies	81
1. Procedures	81
2. Storage and retrieval of technical literature	81
3. Coding scheme adopted for these bibliographies	84
4. Initial bibliography on "Characterization of Particles and Assemblies of Particles"-- A. L. Mular and V. A. Mee	91
5. Initial bibliography on "Forming of Ceramics"-- A. G. Pincus, R. E. Rose, and V. A. Mee	212

I. GENERAL INTRODUCTION

When the need arises for a specific design of a ceramic in a specific composition, a great number of competing methods are advanced for forming the shape required. The purpose of this study has been to initiate a critical study of the alternative forming methods in order to permit a selection based on reasoned judgments rather than on the grounds of familiarity, emotion, or traditions.

The report and the accompanying bibliographic and reference material provide a basis for the assembly of a uniform source of information on the forming of ceramic articles.

Forming must first be seen in perspective as one step in the total processing sequence for making ceramics comprising:

- Batch Preparation
- Forming
- Heat Treatment
- Finishing and Assembly
- Inspection

Alternative terms for the forming operations include: shaping, molding, consolidation, and compaction.

The objective of processing as a whole is to produce ceramic or composite materials with a specified and reproducible characterization as to:

- (1) chemical and mineral composition
- (2) physical structure
- (3) dimensions
- (4) surface finish
- (5) pertinent properties

The forming step plays an integral and significant part in achieving this objective.

The functions of forming are:

- (1) To obtain a specified shape and size within dimensional tolerances yielding uniformity (This piece may be a blank, subject to further shaping and dimensional truing in the as-shaped, dried, partially fired, or fully matured stages.);
- (2) To achieve a uniform composition and density throughout the structure producing homogeneity;
- (3) To contribute to a controlled microstructure and properties in the final produce promoting reproducibility.

These functions are attained by consolidating discrete particles into a compact coherent enough to permit handling during further shaping or during setting for heat treatment. Implicit is the attainment during forming of:

- (1) controlled density
- (2) freedom from gross flaws
- (3) minimized contamination
- (4) safety with regard to such factors as toxicity, radioactivity, and die strengths.

A subsidiary function of consolidation may be to accelerate reaction to final composition and structure during subsequent heat treatment. The final surface finish may be established by the forming, or modified during a subsequent heat treatment or finishing stage.

Since throughout this survey ceramics are being defined to include all materials which are nonmetallic and inorganic (including composites), forming has been considered in its broadest sense to include not only the familiar powder techniques, but also forming from melts, vapors, and solid bodies of varying degrees of porosity and bond strengths. The concept of "powders" has been broadened to include all particulate matter whether equiaxed, filamentary or sheet-like.

Classifications of forming can be developed according to a diversity of approaches as follows.*

Sequential Operations.-- Feed material from the preparation stage in the form of a granulated powder batch, a preform, or a homogenized, controlled viscosity glass is (1) filled into a die cavity; and then (2) compacted, usually by pressure applied at a controlled rate. The formed part is then (3) ejected and (4) transported to the next operation.

During filling there are usually performed some auxiliary operations, such as removing excess feed material or de-airing. During compaction, the accompanying operations may include air release, lubrication of die walls, control of the pressure loading cycle, control of the degree of compaction, and multiple movements to form holes or re-entrants. Sometimes the simple application of the load by pressure is modified by introducing vibration, oscillation, or repetition of load.

The objective in each of these operations is maximum uniformity in structure throughout the compact, particularly with respect to density. Deviations at any stage may lead to more serious defects in subsequent processing.

* This classification and discussion as well as other ideas embodied in other classifications have been derived from contributions of E. R. Stover to the Materials Advisory Board, Ad Hoc Committee on Processing of Ceramic Materials.

Method of Loading at Compact Boundaries. - The characteristics of the forming container are the basis of this classification: (1) elastic container, no shear-- corresponds to isostatic pressing, (2) rigid container, low shear-- corresponds to die pressing, (3) porous, rigid container, no shear-- slip casting, (4) powder is its own container, low shear-- powder rolling and strip compaction, (5) rigid container, high shear-- extrusion.

Operational Technique. - General operations or processes can be listed as: (1) pressing (compression), (2) drawing (tension), (3) gas pressure (blowing), (4) vibrating, (5) impacting, (6) leaching, (7) impregnating (8) weaving, (9) felting, (10) turning, (11) grinding, (12) casting and solidification, (13) chemical reactions (cement bonding, reaction sintering), (14) absorption (slip casting in porous molds). Combinations of these techniques may also be employed.

Material Response.- Previous classifications have emphasized operational features and effects on the material. Another method of classification might be based on the deformation response in the material during forming. This is discussed at length in the section of this report on Cold Forming Processes.

Type of Energy Utilized. - The method of energy utilization during forming may be listed as: (1) mechanical, (2) mechanical assisted by heat, (3) sonically assisted, (4) electrically assisted, (5) radiation induced, (6) magnetically assisted, (7) chemically-assisted, etc.

State of Matter from which Formed. - The states of matter from which ceramics are formed include: (1) particulates in varying solid-liquid ratios (actually a ternary: solid-air-liquid), (2) melts, (3) vapors, (4) bulk solids (including single crystals and glasses), (5) films, fibers, whiskers (i.e. solids with one or two dimensions dominating), (6) solutions.

Utilization. - The environment characteristic of a particular application may dictate properties required and the design of the component may specify the shape. Thus another basis for classification of forming methods may be defined by the end use of the ceramic. A typical example may be taken from the glass industry where the shape of the product determines the forming process (see table I of the section of this report on Melt Forming). Similar considerations have determined the evolution of forming processes in the whitewares industry for such products as dinnerware, bathtubs, and sparkplugs. Military requirements have begun to dictate the choice of forming methods for specific product categories like radomes, nose cones, rocket nozzles, and nuclear fuel elements. The influence of classification by this criterion is evident in the coding scheme and bibliography accompanying this report.

It is apparent from the diversity in scope of these classifications of forming methods that it is difficult to isolate and identify the science fundamentals underlying ceramic processing. However, two broad groups of fundamentals are suggested: those relating to the materials to be formed and those relating to the processing itself. If a true "science of processing" is to be generated, the detailed role of fundamentals in each of these groups and the relationships between the two groups must be discriminated and exploited. These concepts are introduced in the section of this report entitled Fundamentals of Forming, as well as being an integral part of the five individual survey reports which follow.

II. SURVEYS OF METHODS OF FORMING CERAMICS

For the purposes of this survey the forming processes have been broken down into the four arbitrary divisions:

Cold Forming
Hot Forming
Melt Forming
Miscellaneous Forming Methods.

Although any break down is bound to present borderline areas, the above groupings have been investigated without confusion both by discussions with experts and by a literature search. A more detailed classification of these groups of forming methods is presented in Section V.

Each of the four divisions were assigned to the responsible individual as set forth in the Table of Contents. These sought the information needed by means of individual and group conferences with recognized specialists in the several fields. Based on their findings and on the availability of the literature searched for their division, each of the leaders has prepared a summarizing report which is presented as a separate chapter substantially as written by them.

Because of this importance of the characterization of powders to subsequent forming operations was recognized from the beginning, and re-emphasized at all of the conferences, Professor D. W. Fuerstenau was asked to be responsible for the preparation of a special report and bibliography on this topic.

A. CHARACTERIZATION OF PARTICULATE SYSTEMS

by D. W. Fuerstenau and A. L. Mular

The basic idea behind the term particle characterization is simply that the engineer must accumulate a sufficient amount of data on the basic properties of the powder or particles which comprise a batch so as to be able to predict its behavior after a forming treatment. These same properties will be of consequence to the forming operation itself.

One forming operation may demand that a batch exhibit certain desirable properties which may not be of importance when another forming method is used. However, particles and assemblies of particles will always be characterized by such basic physical and chemical properties as size, color, shape, density, surface energy, and defect structure. The purpose of this section is to summarize the present state of knowledge regarding particle characterization and to show that properties which characterize batching materials pertain not only to forming but to most other subsequent operations.

PROPERTIES OF PARTICLES AND ASSEMBLIES OF PARTICLES

It is difficult to make a clear distinction between properties of a particle and properties of an assembly of particles. For example, a particle may be porous, yet when a pore size distribution is measured, it is done with an assembly of particles. Table I summarizes properties of particles which serve to determine their behavior in fluid environments. This table has served as the basis for a scheme of documentation entitled Particle Technology as noted in the Bibliography.

Table II presents a number of physico-chemical effects which are important in particle technology. The table lists the physico-chemical principle involved and some examples of its application. It is apparent that fundamental properties have a direct influence in a wide variety of areas which involve the use of powders. All of the principles listed in Table II may be regrouped and classified to fit into one of the general categories of Table I.

A considerable amount of work remains to determine those properties of particles which are uniquely related to specific forming methods, although in large part these properties will be important to all forming methods. Many of these properties which generally characterize particles are briefly discussed in the subsequent paragraphs.

TABLE I. Categories for Properties of Particles Which Determine Their Behavior in Fluid Environments

Properties dependent upon the physical nature of the particles

Size, shape, density, crystal structure
Surface area
Size distribution of powders
Porosity, pore size distribution
Particle packing, packing and tap density
Flow properties, angle of repose
Permeability of packed beds
Thermal conductivity, expansion

Properties dependent upon the chemical nature of the particles

Electrical and magnetic
Stoichiometry, impurity content
Reactivity of solids
Surface energy, solid-fluid interfaces
Rheology of solid-fluid systems
Thermochemical

TABLE II. Physico-chemical Effects Important in Particle Technology

<u>Physico-chemical Principles</u>	<u>Application</u>
Rate of a diffusion-controlled reaction is proportional to surface area (Fick's law)	Cement hydration; sintering reactions
Small particles exhibit higher vapor pressure than larger ones (Kelvin's equation)	Sintering; ageing of crystalline precipitates
Adsorption of vapors by solids due to chemical or van der Waals forces	Surface hydration of MgO; surface oxidation of metals
Capillary condensation in pores or at points of contact between particles	Agglomeration of particles in humid atmosphere; cementation of crystals
Spreading and non-spreading related to surfaces of tension at three phase interfaces (Theory of Wetting)	Strength of compacts; metal-glass seals; wetting agents
Contact charging of dry powders of high surface area	Clogging during flow; friction; angle of repose
Electrical double layer theory	Flocculation and dispersion of fine particle suspensions; slips; cation exchange
Theories of rheological suspensions	Thixotropy and dilatancy; filtration; slip casting

PREPARATION OF PARTICLES

Because the production method may profoundly influence important properties of particles such as size, shape, and reactivity, the more common methods employed to produce fine powders will be discussed briefly. Common production methods include: (1) comminution, (2) precipitation, (3) atomization, (4) thermal decomposition, (5) vapor deposition and (6) thermal quenching. The first three of these will be discussed.

1) Comminution. - Comminution is the size reduction of solids through the application of mechanical forces. Powders that are produced by crushing and grinding are characterized by a size distribution, with the finest particles being but a few Angstroms in diameter. Several recent papers have been concerned with the dependence of size distributions on loading methods, fracture mechanisms, and flaw distributions. A number of size distributions have been proposed for comminuted products.

Theories of comminution are at present inadequate to account for the energy used in grinding processes. The efficiency of industrial grinding equipment is assessed by empirical relationships based mainly on performance of laboratory models. A number of size distribution equations are available to describe the products from grinding devices. The various "laws" of breakage, however, are presently considered to be less important than the application of computers to describe size distributions and rates of size reduction. Modern milling trends include the revival of interest in autogeneous grinding, improvements in mechanical and fluid energy mills embodying high speed and extreme turbulence, fresh studies of ball mill operation at super-critical speeds, and the improvement of the vibratory ball mill. Precautions must be taken to avoid contamination of powders during the comminution of ceramic raw materials.

Milling not only affects particle size and shape, depending upon particle cleavage and flaw density, but also will change the reactivity of the milled product in a subsequent sintering step. Just why the reactivity is affected is highly speculative.

2) Precipitation from solution. - The processes by which precipitation from solution occurs may be divided into two primary stages: nucleation, and the growth of the nuclei to macroscopic dimensions. Present theories of nucleation have their origin in the theory of spontaneous nucleation developed for crystals nucleating from a super-saturated vapor. Once a crystal has nucleated in saturated solution, its rate of growth depends upon several factors which include number and kind of imperfections, kinetics, and mass transfer at interfaces, and the presence of foreign impurities. By suitably controlling the important variables in crystallization, different particle size ranges may be obtained. To a large

extent, the shape of the resulting crystals is determined by kinetic factors. Shapes may also be modified by controlling the supersaturation or by adding hydrocarbons which preferentially adsorb to certain crystallographic faces.

3) Atomization. - The processes occurring during atomization are complicated. There is the problem of the determination and control of the original drop-size distribution. The quality of the product will depend on the residence time of the particles, their temperature and humidity history, frequency of collisions, and other factors. A given set of conditions produces a certain kind of powder. Much remains to be done in a study of these conditions.

PROPERTIES DEPENDENT UPON THE PHYSICAL NATURE OF PARTICLES

The physical as well as the chemical properties of an assembly of particles are important to the ultimate goal of any forming method, namely to achieve uniformity of properties and a reproducible microstructure. It is important to know which characteristics are of specific interest to forming in general and how these are measured. These have been listed in Table I and are discussed in the following paragraphs.

1) Particle size, shape, size distribution and surface area. - The influence of shape, size, and surface area of particulate materials on their behavior is not well understood. This is partly because the problems of the precise definition of size, shape, and surface area have yet to be satisfactorily resolved and partly because of the problems encountered in measuring these quantities. The state of knowledge relating to these subjects is far from satisfactory and much remains to be learned.

Particle size is usually defined by a single dimension. However, actual particles are irregular in shape so that any size designation becomes quite arbitrary. The average linear measure of the projection of many particles in a fixed direction is statistically a measure of the size range of the particles if the orientation is random and a large number of particles are involved. This is sometimes impractical so particle size is defined by the method used in its determination. Three common definitions of equivalent diameter are a) the diameter measured microscopically, b) the sieve aperture diameter measured with standard size sieves, and c) the sedimentation diameter measured by sedimentation methods. When the shape of the particles deviates greatly from a sphere, the three definitions do not correspond, and in fact may differ by as much as a factor of ten.

One of the most abortive searches yet made is for a means of defining the shape of a particle. To date, the most common definition of particle

shape is probably that which is based on the equivalent diameter, the surface area, and the volume. If d is the equivalent diameter, the surface area and volume of the particle are then πd^2 and πd^3 respectively. The ratio of f/k is then a measure of the shape of the particle.

Particle shape is important not only in forming, but also in packing, mixing, rheology, flow from bins, sintering reactions, and the ultimate microstructure of products.

Of extreme importance to characterization of powders is the size distribution of particles comprising the assembly. Particles formed by chemical means are characterized by a fairly narrow range of sizes. However, comminuted products have a distribution of sizes ranging from the upper limit down to a few multiples of the unit crystal. Numerous size distribution equations have been used to describe the weight-size relationship for a system of particles. Some have theoretical bases; others are strictly empirical.

A minimum of two parameters is necessary to characterize size distributions. However, often an average diameter is used in an attempt to describe a system of particles of different sizes and shapes by one number. Average diameters are based on linear, surface, or volume measures, and should be used by taking into account the exact phenomenon of interest, i.e., average surface diameter is generally used in studies of surface phenomena and permeability of packed particles. Such average diameters should be used with caution since the same average diameter can be obtained from a variety of distributions.

Table III lists several of the common techniques used to determine the size of a system of particles. The ranges of particle sizes applicable to the method are also shown.

TABLE III. Methods of Sizing and Range of Applicability.

Method	Size Range, Microns
Optical microscope	0.25 - 250
Electron microscope	0.0005 - 5
Sieves	5 - upward (generally above 37)
Fluid sedimentation	0.5 - 300
Centrifugal sedimentation	0.0005 - 50
Light scattering and transmission	0.1 - 30
X-ray scattering	0.005 - 0.05

Measurement of the surface area to characterize a powder is of great importance to most succeeding processing. Adsorption, solubility, kinetics, and many other phenomena are functions of surface area. As a first approximation, it would appear that in connection with properties of powders, such as the density of packing or the strength of an aggregate, the geometrical surface, as obtained by microscopy, permeability, sieving, or any other form of direct measurement, is adequate. For systems which require a measure of internal surface, gas adsorption techniques must be used. Several new methods to measure surface area have been introduced, of which the BET method of nitrogen or krypton adsorption is widely discussed in the literature.

It should be pointed out that different methods of measuring surface area do not give the same results. Thus, the reported value of the surface area is dependent on the method used for the measurement.

2) Porosity and pore size distributions in particles.- Porosity and pore size distribution is of interest to the reactivity of a granule and, in particular, to the coherence of a formed piece. A number of problems regarding the porous nature of particles exist, such as how to measure the closed pore volume. Several ways to measure open pore volume are available; usually closed pore volume is obtained by a suitable difference method.

The simplest way to measure the distribution of large pores is by optical microscopy. The electron microscope has been used for smaller pores. The difficulty with these methods lies in sectioning techniques and the need to view large numbers of particles.

Pore volumes may be obtained, for example, by a mercury intrusion technique. By applying graduated pressures, mercury may be squeezed into a porous solid and from the change in mercury volume a pore size distribution is calculated. Other methods involve gas flow analyses and the determination of adsorption-desorption isotherms. Mercury displacement is of value for macropore distributions; the filling of pores with condensed gas is useful for pores in the 300 Angstrom and smaller range.

3) Particle packing, apparent density, tap density.- Particle packing may be defined as the science and technique of mixing together particles of sizes and shapes so voidage is kept to a minimum. The best measure of efficient packing is probably a measure of the void space of the compact. In many instances, void space is used synonymously with porosity of the compact although the porosity of the particles is not considered. The important bulk properties are a) apparent density, b) tap density, and c) compression ratio.

The apparent density of a powder is the mass of a unit bulk volume of the powder. Tap density is simply the apparent powder density after it is vibrated or shaken down by a standardized procedure. Compression ratio is given by the ratio of the height of the uncompressed powder to the height of the pressed compact again by a standardized procedure. These terms have been most useful to the control of pressure compaction methods.

Theoretical models using particles of known geometry have been useful for predicting the behavior of irregularly shaped particles when packed together. When a minimum void space is desired, graded size fractions of material are utilized. Only a limited amount of work has been carried out to ascertain the packing of subsieve powders.

4) Flow of dry particle systems. - The ease of initiating flow of a particle system or granular mass is indicated by its angle of repose. High angles are found for systems whose distribution has a top size of less than 100 microns; low angles are obtained for closely sized material over 100 microns in size. The angle of repose depends on the way in which the powder heap is formed. The dimensions of openings blocked by a powder increase with increasing particle size; cohesion of the granules will also cause blocking. The dimensions of blocked apertures vary in the same way as the width of the empty annulus which forms adjacent to the edge of an aperture through which the material flows.

The flow of particle systems is usually studied in terms of theoretical work on the mechanics of plastic systems and recent treatments suggest that a flowing powder is analogous to a medium having cohesive properties, frictional resistance, and granular structural resistance which may vary as deformation proceeds.

The flow properties of powders are dependent upon the transmission of forces through the system, particle size, shape, and distribution, resilience, cohesion, and state of the surface.

5) Permeability of packed beds. - The permeability of a packed powder is defined as the volume of a fluid of unit-viscosity passing through a unit cross-section of a packing under a unit-pressure gradient in unit-time. This is really a simplified statement of Darcy's equation and hence the unit of permeability is termed the darcy. The permeability constant is a function of many factors, such as particle size, shape, porosity, type of fluid, particle surface energy, contact angle, and surface area. In fact, permeametry involves the passage of fluid through packed beds to determine

surface area of the bed. The utilization of flow through packings to study particle packing, porosity, and suction potentials is rapidly gaining momentum.

6) Heat flow through packed beds or compacts.- Heat may flow through a packing, through the particles, or through the fluid which contacts the particles. If the particles themselves are porous the heat capacity of the granules varies and must be considered in relation to the bed as a whole. The study of the flow of heat through packings is important to various pressure forming methods such as hot pressing. Numerous mathematical treatments have been formulated, these originating either from classical and statistical mechanical approaches or from dimensional analysis.

PROPERTIES DEPENDENT UPON THE CHEMICAL NATURE OF PARTICLES

Only those chemical properties which are being quite widely investigated, such as the surface activity of powders, will be mentioned in this short summary.

1) Surface energy, solid-fluid interfaces.- When a homogeneous phase becomes discontinuous, such as at a solid-fluid contact line, then that interface which forms becomes the seat of an excess or deficit energy content. At the surface of discontinuity, surface atoms are not in their equilibrium positions because of a difference in coordination. The literature is filled with erroneous definitions of surface energy and surface free energy per unit of area. In many cases it is thought to be analogous to surface tension as measured for liquids. From a thermodynamic point of view, surface tension and surface free energy per unit area are equivalent for a one component system provided the adsorption of the solvent can be taken as zero. For a system of two or more components, the surface tension and the specific surface free energy are not the same. For example, in the relation between pressure drop across a curved surface and the surface tension, one must define the system carefully before the surface tension may be referred to as the specific surface free energy. Similar ideas hold when surface tension is defined in terms of other variables such as energy content. The concepts hold for solids, for liquids, and for gases.

It should be noted that the real surface stress of a solid is related to its surface tension, the difference being due to the position constraints on atoms in a solid. Also surface energy is some positive function of a surface area increase, so it follows that a powder of high surface area has a higher total surface energy. This may relate directly to reactivity and to solid-fluid behavior such as with a rheological suspension.

Calculations of the surface energy of solids have been made by a number of researchers but many uncertainties exist in these calculations. Experimental measurement of surface energies is difficult but many of the investigations now agree reasonably well.

When a solid is immersed in a fluid, a redistribution of species will occur until an electrical double layer is generated. The properties of the double layer, which can be thought of as an equivalent condenser, are still open to question, especially since the models used are based on the assumption that solids have no space charge layer. Considerable refinements of the theory have been made with electrodes which are almost perfectly polarizable. In the case of solids, the parameter that is of interest is the zero point of charge of the solid-liquid interface. The nature of the potential-determining species must be characterized.

Any movement of a fluid past a solid results in an asymmetrical distribution of charge in the fluid relative to the solid. Hence a potential gradient exists and a force acts on the solid in accordance with the sign of the surface charge and the direction of the field. The field acts tangentially to the plane of movement. Various phenomena are related to this principle, namely streaming potential, electrophoresis, sedimentation potentials, and electro-osmosis. Under certain conditions, the dynamic double layer which is present during motion of a fluid past a solid is related to the static double layer developed in theoretical models. In these cases, considerable information may be obtained.

The rheological properties of solids are significantly dependent upon the existence of an electrical condenser at a surface of discontinuity. The double layer is important to cohesion with a compacted powder.

2) Reactivity of solids; stoichiometry; impurities. - A reactive powder is one which has been given some physical or chemical pretreatment to improve its ability to react more favorably in some way. For example, a reactive powder will more readily densify during sintering as compared to the same kind of powder which has not been made reactive. It is a phenomenon connected with surfaces and has been referred to as surface activity or surface reactivity. The reactivity of a surface is altered by a change in surface area and surface roughness, by a change in the content of bulk impurities, kind of lattice defects, and number of defects, by surface distortion and surface composition relative to the lattice type, by the gaseous atmosphere in contact with the powder, by the degree to which the atmosphere dissolves in the solid, and by the composition of the reacting mixture of solids (presence of additives). Particle size and reactivity are closely connected.

Most ceramic powders are insulators or semi-conductors. Therefore, their electrical properties may be severely changed by impurities and by

the relative proportions of lattice components present. Moreover, their solid state behavior will depend on these factors, which also pertain to surface reactivity. The self diffusion of a species or of an impurity will depend on whether the powder is an insulator or semi-conductor.

Generally, a powder is made reactive during its initial preparation, or is purposely treated in some fashion in the batching or forming stage to alter its reactivity.

3) Rheology of suspensions.- Rheology is the science of the time dependent deformation and flow of matter. Suspensions whose properties are dependent on the degree of flocculation or dispersion, i.e., the state of electrical double layers, exhibit different kinds of rheological behavior. This is very dependent on the properties of the solids, especially size, shape, and solid concentration, all of which affect the deformation/stress response.

Theoretical models of non-Newtonian suspensions have been developed for spheres in fluids and for other geometries. Considerable progress in theory of rheological behavior has been made in recent years.

4) Electrical and magnetic properties which characterize powders.- Electrical properties of powders will differ from those of a solid when they depend upon the transfer of charge, because conduction paths are broken up in the powder. The surface will be chemically different from the bulk, for there will be layers of chemisorbed atoms and impurities. Therefore, the surface resistivity will differ from that of the bulk particle. The resistance of the powder compact will be dependent upon such factors as relative humidity, temperature, contact resistance, and the number of contact points which depend in turn upon the surface topography. Moreover, dry powders are extremely susceptible to contact charging wherein a particle charges oppositely to that object with which it is in contact. The charging properties of the powders will depend upon whether they are metallic, non-conducting, or semi-conducting in character. Charging may occur by particle-particle contact or friction, by particle-container contact, or by both. The maximum charge obtainable is limited by the breakdown strength of the fluid phase in contact with the powder, unless a direct short to ground is present. The electric charges which participate in the transfer are electrons and ions. There is no direct proof that ions are actually transferred by contact charging.

The magnetic properties of powders are affected by the degree of packing, particle size, and specific surface area. Magnetic powders are usually considered to have a dipole electrical double layer at the surfaces. Recent techniques based on precession of these dipoles have been used to study adsorption on magnetic particles.

NEED FOR CAREFUL CHARACTERIZATION OF POWDERS

Preceding sections have attempted to define and summarize the state of the knowledge dealing with basic particle and powder properties and behavior. The Bibliography contains many references which are more specific and which deal with subject matter of importance to characterization but which have not been summarized here.

There are two classes of basic properties of importance to characterization, namely those associated with the particle and those which are a characteristic of the assembly of particles. For proper characterization of particulate systems, basic properties of particles and groups of particles must be classified and measured. It must be determined which of these are important to a given forming operation and to the behavior of the formed piece in a subsequent treatment. This kind of information will serve to assist in choosing the forming method which is best suited for the particulate system.

In a highly ideal case, a raw material would undergo a standard testing procedure to obtain data which would place it into a classification scheme. Depending upon how the material is classed, the forming operation would be chosen to produce the best possible product with that material. The classification would include schemes to modify properties and behavior to fit the forming method where desirable.

B. COLD FORMING PROCESSES

by A. W. Allen

Cold forming processes are the traditional mainstay of the ceramic industry in which particulate materials are compacted to the requisite shape under dimensional control by the application of pressure. As has been pointed out in the preceding section, the forming process receives from the batch processing a system of particles organized into a complex agglomerate system. The response of this system to a specific forming deformation is determined by the compaction response of the agglomerate base material.

1. Compaction Response in Cold Forming

The common denominator to the many cold forming systems which have been utilized may be in delineating the deformation response of a particulate system to the application of the forming energy. The final result of this response should be the geometrically characterized shape. The total mechanism of the compaction process which starts with a particulate system and ends with a shaped piece might be termed the "compaction response."

In the process class called slip casting the medium for the transport of particles during the compaction process is liquid, usually aqueous. If the shape to be formed is complex in geometry, the fluidity of the system must be increased to allow maximum conformity to the mold or die cavity which dictates the shape. Such fluidity is produced by a combination of (1) increasing the liquid-solid ratio and (2) fluidizing the particulate system at low liquid contents with special additives. The particulate system responds as a liquid of controlled viscosity (usually non-Newtonian). Compaction in the system occurs when the liquid is removed at very low shear rates and at pressures which are essentially the static pressure of the liquid itself acting against a rigid (or semi-rigid), porous, permeable mold surface. A portion of the liquid is removed by the mold during this process but more remains to be removed in the early stages of heat treatment.

Aids to the slip casting process to remove liquid and control casting rates have taken the form of applying pressure to the slip, pressure casting, or vacuum to the mold, vacuum casting. Centrifugal casting may be placed in this same category where the centrifugal pressure from mold rotation forces the liquid out of the particulate system.

Note that a particular liquid-solid ratio is not specified. As will be seen later the detailed application of rheology has expanded the applicability of this method to a wide range of particle-liquid systems.

If the cross section is constant and it is desired to produce a shape in which the length to cross section ratio is large and variable, the application of pressure to force the particle-liquid system through a die orifice may be employed. This type of plastic forming, referred to as extrusion, requires that the particulate system respond to forming energy by plastic deformation. The application of stress deforms the mass beyond its elastic limit but without fracture and in a manner which allows retention of the formed shape after the forming energy has been removed. The liquid-solid ratio is generally lower than for slip casting but again rheological studies of the systems have produced plasticity by a combination of (1) control of liquid characteristics; (2) employment of special rheological additive aids; and (3) control of rate of application of forming energy (strain rate).

Compaction during extrusion occurs by plastic deformation in both the extrusion chamber and in the die orifice. It occurs rapidly at high shear rates and high forming pressures. Liquid removal must occur after the piece is formed, most likely during the first stage of heat treatment. An innovation here is the incorporation of a liquid removal step as an integral part of the extrusion process but immediately following the extrusion step. Heat-induced diffusion of the liquid to an evaporative surface is motivated by the use of infrared or radio frequency energy.

The plastic deformation response of such systems may also be such that a die cavity of variable cross section but fixed volume may be employed in an injection molding process. The compaction response here is one of plastic deformation but finally in compression as the particle system builds up back pressure on itself. Additives which act as rheological aids are the key to uniform transmission of forming energy to provide fill and dimensional control.

To avoid the subsequent problem of moisture removal and to enhance the transmission of forming pressure, thermoplastic or thermosetting organic resins have been employed in injection molding. The temperature-time dependency of plasticity in an organic liquid-particulate system thus allows control of compaction response. The temperature-time cycle of forming concludes with a stage wherein the liquid viscosity increases to rigidity either by cooling or polymerization (or combination of both). The type of resin selected may allow the entire cycle to occur near room temperature and be primarily time dependent. Resin removal now becomes a part of the heat treatment cycle, although for certain applications the resin may actually remain as the bond, the forming stage being the final step in processing the product. Plastic deformation is still the major mode of compaction response.

Coextrusion of two different particulate materials is possible if their compaction responses are matched carefully by rheological analysis. Correlating the flow rate with extrusion pressure has been used for this approach.

The extrusion process or filter pressing may be used to prepare the particulate system in a plastically deformable condition, the major compaction response occurring when a blank or "bat" is formed. The blank in this condition is subsequently brought to the required shape in an auxiliary forming step. Slight additional compaction occurs in this step, the response here being primarily to deform plastically to the intended shape.

Thus in jigging one surface is formed by plastically deforming the particulate system against a mold or die surface with a profile tool which defines the second surface. Generally cylindrical or elliptical cross sections are made by automating the movement of mold and/or tool. If the mold is permeable a liquid removal stage may be part of the process, but jigging is also done in rigid, non-permeable dies.

Plastic pressing also employs a plastically deformable blank previously prepared by extrusion. In this process the blank is compressed against a permeable die surface with a second permeable die surface. The compaction response is now one of plastic deformation in compression not unlike injection molding. Liquid removal occurs under pressure by enforced diffusion into the die material. Pressurized air blown through the die material releases the piece and expels excess moisture from the die (usually plaster). Jigging and plastic pressing have been widely employed where automation is a requirement of production.

Plastic rolling is a more recent extension of the plastic pressing process. At low liquid contents this may be substantially powder rolling.

Pressure forming is a process class in which the liquid content is essentially eliminated or minimized to avoid the attendant problems associated with liquid removal. Compaction response is a more critical function of (1) packing density; (2) mode of application of forming energy; (3) die design; and (4) particle-particle interaction. Additives are most typically employed which fall in the group of lubricants to affect minimum particle-particle friction and die wall friction, as well as binders to strengthen particle-particle cohesion after compaction. Compaction response is apparently one of particle packing and elastic deformation perhaps to the point of fracture at high pressure but low shear levels.

Where close dimensional tolerances are required and the liquid content is low, "springback" is sometimes observed after the forming pressure is removed. This may be related to recovery of elastic deformation which occurred during compaction.

Some distinction may be made between dry pressing at liquid levels between 0 and 5% and "semidry" pressing where up to 15% liquid may be

employed. The liquid level is a materials dependent factor. Particulate systems in which clay minerals are prominent components would be a typical example of the latter. An inert particulate system like alpha aluminum oxide may not tolerate very large quantities of liquid. Again process additives may fall in a class of surface active agents which influence this solid-liquid interaction in the system and hence markedly influence compaction response.

In the pressure forming process class great concern is expressed for the uniformity of transmission of pressure in a particulate system which is designed to pack to maximum density.

This is the paradox of pressure forming which has led to a multiplicity of inventive techniques for die design and system operation to facilitate compaction response in a basically immobile material. Most of these are based on uniaxial or at best biaxial application of forming pressure directly applied through rigid punches, platens, etc. to the particulate system. The engineering in these operations is highly developed and well adapted to particular product classes.

Realization that the homogeneous transfer of energy to the material in the die was a basic limitation of pressure forming led to the development of the isostatic pressure forming system. Compaction response results from the fact that forming pressures are applied simultaneously to the continuous outside surface of the shape. The die is an elastically deformable material which approximately determines the external configuration. The interior shape is defined by a rigid non-deformable steel mandrel. Compaction response here may involve the entire stress range of elastic deformation through fracture and perhaps plastic deformation in the particles themselves because this process permits operation at higher pressures than other methods of pressure fabrication (10^5 psi. as compared to 10^4 psi.). This also has become a well engineered system used in high volume, high precision production operations. Recent attempts to automate the process have also been successful.

An earlier version which used a particulate system encased in a rubber bag and isostatically pressed in a hydraulic fluid (usually oil) pressurized in a conventional die cavity is often referred to as wet bag isostatic or hydrostatic pressing.

In all of these the superior compaction response results from the unique mode of transfer of energy to the particulate system.

If the liquid level is low enough (2% or less) conventional pressure forming in dies may be used to produce a preform which is subsequently isostatically pressed so the compaction response is accomplished with a low pressure step followed by a second pressure cycle.

Realization that compaction response is so greatly influenced by particle packing led to extensive studies of vibratory compaction. Compaction response is the result of reduction in particle to particle friction by control of (1) size distribution and shape of particles; (2) lubricating particle surfaces in a liquid medium which dampens violent interaction; (3) control of vibration frequency and power to fit the geometry and mass of the compaction die system. Here again vibratory techniques may be employed either as a preliminary step to another process or as the sole method of forming. The technique is particularly successful when the shape is fixed by preformed metallic cladding (e.g. vibratory compaction of fuel elements in zirconium alloy tubing or refractory brick in steel jackets). The compacted clad shape may subsequently be altered in geometry by another method of forming. Pressure forming may be employed for this purpose. Cold swaging refers to an area reduction operation on such clad ceramics in which not only the cross section is changed but additional compaction in the particulate system may result.


Many combination processes are possible in which one degree of compaction produced by, for example, extrusion is followed by a second operation which further compacts the particulate system and brings it to more precise dimensions. Repressing of extruded shapes in a pressure forming operation is typical.

Finally any of the processes may provide a shape which is brought to its formed dimension by any of a number of finishing processes such as grinding, sanding, turning on a lathe, etc. This may occur after the drying stage of heat treatment or in a stage prior to removal of all liquid added for forming, the so-called "leather hard stage." With the improvement of finishing abrasives, particularly diamonds, finishing of the final heat treated ceramic shape has also become routine practice.

2. Progression of Material Characterization in Cold Forming Processes

Figure 1 shows schematically the progression of characterization of materials in finally arriving at the end result: a fully characterized, formed ceramic. "Fully characterized" refers to the fact that ideally not only is the geometry known within specified tolerances but properties are known within specified limits of reliability. This requires, of course, a knowledge of the relation between the forming process steps and the heat treatment, finishing, and inspection steps. It should also be emphasized that in a few instances the forming step is the last stage in characterization when the requisite bonding and microstructure are achieved without heat treatment (e.g. "chemical bonding"), unless an auxiliary heat treatment occurs during the forming operation.

Starting at the top of figure 1 the first step is the characterization of the particulate base materials used, single phase or multiphase. Liquid



PROGRESSION OF MATERIAL CHARACTERIZATION IN
COLD FORMING PROCESSES

Figure 1

media, often water, plus processing additives (see below) introduced in a proper mixing, blending, and/or tempering step produces a characterized stable agglomerate base material. This is the "mix" or "batch" which is handled in the forming system. The particulate material is now in a state of aggregation which gives it the requisite rheological properties, composition, liquid content, and particulate size distribution to optimize its compaction response when the forming energy is applied.

In addition to producing a degree of compaction, the forming energy may be expended to achieve liquid removal which is paramount to optimized compaction response. Here is where a number of inventive innovations have appeared in cold forming like centrifugal, pressure and vacuum casting; infrared and high frequency drying coupled to extrusion; and plastic pressing all of which have been previously mentioned.

Void control or removing the gaseous phase (primarily air) is also paramount to optimized compaction response. It should be emphasized, however, that a shape of characterized pore structure may be the objective of a forming operation. The optimum properties may not be achieved in a fully dense material. In other words "optimized compaction response" does not always mean fully dense. Forming a shape of high but known porosity may be a more difficult assignment than achieving maximum density.

Thus energy aids may include those forming system assistants which develop void control either to completely remove pores or to control them. (1) Chemical additives or (2) mechanical aids are two broad sub-classes in this category.

While chemical additives to produce pores or a stabilized foam can be readily envisioned, the class of additives which reduce entrapped voids may not be so familiar. Gaseous additives or solid additives of high vapor pressure which displace the air in the particulate system with a vapor phase which liquefies at forming pressure is an example. The mineralizers or sintering aids which facilitate reaction and/or grain growth in the heat treatment stages might be included here.

Mechanical aids take the form of either (1) air removal, (2) packing assists, or (3) control instrumentation. Deairing under vacuum is common practice in extrusion and pressure fabrication as well as in slip casting. Vibratory compaction as an assist to pressure forming is also widely practiced. Press equipment for dry pressing can be designed with almost any specified control over rate of application of pressure, dwell time and vibratory stroke during or before compaction.

Special mention should be made of ultrasonic aids because of their recent success on a pilot plant scale in ceramics. At relative easily attainable power level (50-500 watts) and frequency (60,000 cycles/sec.) a pressure insensitive transducer applied to extrusion dies for rods ($\frac{1}{4}$ " to $\frac{1}{2}$ " diameter) markedly reduced the power required and the liquid content needed for forming non-clay ceramics. A bell mode of vibration introduced at the die may act as an antifriction aid or may introduce forming energy at the point in the process where compaction response is occurring most rapidly. Ultrasonic energy applied through the mold to a thixotropic slip of very low liquid content has broadened the applicability of slip casting.

Some effort has been made to employ the feedback control loop approach to forming systems in general. In one instance the success of coextruding materials of quite different compaction responses has been the result of automatically monitoring extrusion rate as a function of extrusion pressure. If the extrusion pressure was controlled using the detection of flow rate as a basis, this control loop could be completed. In another instance detection of elastic strain in a vertical member of a toggle compaction press is used as a basis for automatically adjusting die depth and hence for controlling compaction response in pressing.

A secondary step in forming referred to in Figure 1 as auxiliary forming enhances compaction response and may be used to define the final geometry of the formed shape.

The particulate base materials have now progressed to a geometrically characterized shape. To this point the major problem has been producing geometric configuration with dimensional control. If heat treatment is included in the process the problem changes to one of maintaining dimensional control without geometric distortion. The traditional role of heat treatment is also to affect mineralogical and chemical changes which define phase placement in the microstructure. This may occur in prereacted materials which are discussed later.

The bottom of Figure 1 shows the links between the cold formed shape and the fully characterized ceramic shape to be microstructure and property specifications as modified by finishing treatments, testing and inspection. If the ceramic engineer could form to a characterized microstructure and if he had ultimate knowledge of the correlation of microstructure and properties this linkage would be precise.

3. Characterized Particulate Base Materials

Particulate raw materials with known physical and chemical (including mineralogical) properties are an obvious requisite to successful forming

operation. A dilemma exists here because often the raw material supplier and the user are not sure where the responsibility for the characterization lies. This is true because the value of the product may not allow expensive characterizations of the complex system to the degree which is theoretically necessary. Empirical characterization and interdependence of supplier and user is thus a traditional situation. In the development of some materials (BeO and UO_2 for example) where costs were less critical, much fundamental information on characterizing the raw materials has been developed.

Of the properties of particulate systems considered important the following should be emphasized (see also Chapters II A and V E, the Bibliography):

- (1) size distribution and shape
- (2) surface area per unit weight and density
- (3) crystal modifications, stoichiometry, defect structure
- (4) chemical activity (e.g. hydration behavior, iodine number, anion impurities)
- (5) degree of chemical purity or controlled impurity

Of these factors the size distribution seems to be the most universally important one to all methods of cold forming and to all product categories. In spite of the classical studies of particle packing the characterization of size distribution still appears to be at a semi-empirical stage because of (1) inability to produce stable particulate systems reproducibly in sizes below 10-15 microns; (2) complexity of the influence of shape factor in multiphase particulate systems; (3) poor reliability in measurement of particle size and shape, especially below 10 microns.

The abrasives industry is one of the few that has made an attempt to standardize specification of particle size and shape over the wide range of sizes necessary. This necessary range may extend from greater than $\frac{1}{2}$ " diameter for some refractory products to less than $\frac{1}{2}$ micron for certain pure oxide products. Thus the engineer begins to reach a point of diminishing return in applying packing theory to the size formulation of particulate systems. This is complicated by the fact that in multiphase systems he may require several size distributions depending on the material component involved. The phase placement in the final microstructure may be related to this requirement. For example, in a recently developed process for improving high alumina refractory brick, secondary mullite formed at the grain boundaries of corundum was the result of incorporating "colloidal" silica in the particulate system. The familiar "gap sizing" used in the refractories industry is also an example of this increasing complexity.

So the engineer learns to relate the characterization of the particle distribution to a particular comminution process or mixing operation.

His characterization then becomes a function of the reproducibility of the process. The literature is replete with studies of particle size distribution (or more exactly equivalent spherical diameter distribution) as a function of dry milled versus wet milled versus energy milling or of the effect of calcining temperature on particle size, etc. etc.

Such a simulative, statistical approach may be his only economically feasible recourse. In fact, the most used tests for characterization of particulate systems seem to be of this simulative type. "Sintering behavior": press a pellet and see what happens when it is fired, or "compaction behavior": press a pellet in a standardized die and measure its compacted density. These are all realistic, expedient approaches to characterization. The extent to which characterization is fundamental may be a matter of degree of knowledge, and the criticality of characterization may be a function of the reactivity in the particulate system.

This kind of reasoning extends to the other particle properties listed above more than we like to believe.

One approach to minimize these variables is to prereact the particulate system, then reconstitute and carefully characterize the new material as a particulate system component. This prereaction may take any of a number of forms. The materials may be simply calcined to remove volatiles and dimensionally stabilize the aggregate. The entire formulation may be sintered at varied temperatures up to fusion to promote desired solid state or crystallization reactions and compaction. Or the materials may be completely melted to form a glass aggregate (called a "frit"). In certain instances the deposition or codeposition of phases by vaporization or precipitation from a liquid has produced a special characterization needed to improve beginning materials. In each case the resulting material could then form the sole particulate component of the forming batch or may be one of a multicomponent particulate system.

4. Characterized Stable Agglomerate Base Material

After the dry particulate system has been established it must be put in a stable rheological form acceptable to the forming process. The key to this operation is the addition of liquid and certain process additives which have a variety of functions. This is a highly proprietary area in which not only the kind of additive but the sequence of addition may be important. Criteria for selection become empirical and intuitive. Special granulating, agglomerating, or blending techniques also play a part here.

About all that can be done is to classify the additives as to function:

- (1) binders for strength;
- (2) lubricants for release, antifriction agents, or rheological aids;
- (3) deflocculents and flocculents (soluble salts) for pH control or particle surface charge control;
- (4) plasticizers for water retention, rheological aids, or strength during and after forming;
- (5) wetting agents;
- (6) water retention agents;
- (7) antistatic agents for charge control;
- (8) antifoaming or foam stabilizers;
- (9) chelating or sequestering agents (ion retention);
- (10) fungicides and bactericides for aging stability.

As an example, a good casting slip must (1) have controlled viscosity; (2) have good suspending capacity for solids; (3) have reproducible casting rate; (4) drain and release from mold; (5) have high strength after casting; (6) have known shrinkage when liquid is removed; (7) have complete stability with age. Obviously all these requirements will not be met with simple water-particle mixtures.

The ability to remove such additives in subsequent processing may control the selection of an additive and hence limit the entire forming operation. The thermal degradation of organic additives may be studied in detail as to (1) carbon residue; (2) ash content; (3) volume stability of formed shape during removal.

Reactivity between the liquid medium and the solid particles may present a problem in rheological stability which could carry over as a problem in heat treatment or as a problem in defining the chemical composition of the final material. For example, when the liquid medium is water and the solid material is a chemically active oxide like CaO or MgO , hydration readily occurs to change the chemical and physical constituency of the particulate system. Such an effect is exaggerated in the small particle fraction of the particulate system. The stability of casting slips of these oxides is very definitely affected by hydration. Reducing the temperature during all operations is one method of reducing activity. Employing liquids less reactive than water (e.g. alcohols) or additives which protect particles from hydration are other approaches to minimize the effect. Further complications arise in the removal of the water when hydrated oxides which are stable to temperatures in excess of the normal drying temperature introduce an added dehydration step in the heat treatment cycle. In certain composites where easily oxidizable metal particles are part of the particulate system, complications arise from oxide skins formed. Special mixing sequences or mixing in inert atmosphere may be necessary in these cases.

The complexity of this stage in preparation of the particulate system introduces the problem of characterizing the agglomerate batch material as input to the forming operation as a basis for control of the final product. Again an outline of the pertinent factors seems appropriate:

- (1) Particulate size
 - (a) mill product
 - (b) granulated product
- (2) Homogeneity
 - (a) moisture and ignition loss
 - (b) micro and macrostructure in formed shape
 - (c) tracer technique
- (3) Densification
 - (a) bulk density
 - (b) permeability
- (4) Flowability and Formability
 - (a) casting rate
 - (b) granule flow rate
 - (c) extrusion rate vs. pressure
- (5) Green Strength-Density Correlations
- (6) Sintering Behavior of a Standard Specimen

Any or a combination of these factors may be used to characterize the agglomerate base material in an attempt to predict how it will act during forming. A non-destructive, rapid test for green density and strength would facilitate this type of determination. (The characterization of particulate systems is further discussed in Section II A and references are cited in the Bibliography.)

5. Forming System Design: General Comments.

A thorough discussion of forming system design is beyond the scope of this writing because the recitation of historical developments would not be meaningful and because the significant contributions are either covered well in patent literature or are completely proprietary.

It is significant that factors such as (1) production rates, (2) production quantities, (3) continuity of demand, (4) safety considerations, (5) tooling amortization, and (6) required capitalization costs play a heavy role in the design of forming systems, perhaps an

equal role with the requirements of the finished product or the characteristics of the material to be formed.

The problem of scaling up the production of a shape which is feasible in the laboratory is a particularly difficult one. A requirement for a forming system coupled to a heat treatment which would require a minimum of capital investment is a challenge given to design engineers particularly in producing large ceramic shapes.

The isostatic process development may be in this category because the capital investment per unit of forming energy available is substantially less than the conventional heavy press equipment. This is by virtue of improved efficiency of the process of transferring energy directly from a hydrostatic fluid or deformable die material to the particulate system.

Also the ultrasonic aids previously discussed are in the realm of improved efficiency in forming energy transfer.

One opinion holds that new concepts in forming system design will most always come from the intuitive, inventive person who may have broad experience but little formal scientific training. Support of development efforts in this category may be quite effective.

As the use of automated systems develops and the pressure applied in isostatic systems increases, a need for superior mold and die materials will develop. Automation places more stringent requirements on wear resistance and corrosion. Higher pressures in isostatic forming may be limited by the availability of suitable pressure vessels. Plaster as a material for molds may become inadequate as pressure casting, ultrasonic-assisted casting, and similar processes develop. Already the use of porous ceramic molds other than plaster, and porous metallic molds which are readily rejuvenated, are being explored. Low cost expendable molds may not be out of the question.

Another concept is that all forming system development should be oriented primarily to the end use. The development of radomes and of oxide nuclear fuel elements are two typical examples in which this is being done. This may be a much more realistic way of matching capital expenditures and development costs to the economics and strategies of the end product.

6. Geometric Characterization of Finished Ceramic Shapes.

Early in the survey it was thought that a limitation on size, tolerance or geometry could be developed for each cold forming process. Time did not permit a systematic survey. It became quite apparent, however, that such a survey would not have much value because theoretical limits are not recognized by the industry. Given time and funds most any fabrication job could be attempted with reasonable probability for success.

On the small end of the scale, barium titanate discs as small as 0.010" in diameter and 0.003" thick have been made by cold pressure forming. Hollow alumina porcelain cylinders 8 feet long and 27" in diameter have been made by pressure casting a slip. Graphite rod stock 105" in diameter is now available. 0.002" to 0.005" coatings have been applied to rod by co-extrusion and 0.003" holes have been held in rod only slightly larger than this in outside dimension. Almost any degree of finish or tolerance can be developed by grinding or polishing.

The smallness limitation seems to be somewhat more technically limited in that microstructure control looms as a barrier when the size of the part desired approaches the size of particles used or the grain size in the fired piece. Handling and transport systems need to be worked out for the small sizes. The economics of finishing (grinding) may dictate the degree to which very small parts can be brought to tolerance which is closer than $\frac{1}{4}\%$ of any final dimension. All of these capabilities are well within the scope of the industry if the continuity of demand and/or price of the product allows it.

The largeness limitation is much more materials dependent. Large particulate sizes in certain oxides (e.g. BeO and BaTiO₃) have not been available, and producing an extremely large part from very finely divided material may be a definite limitation. The properties of a green formed piece may limit its size. If the green compressive strength is about 100 pounds per square inch how will it support its own weight if it weighs 2000 pounds? In the heat treatment process the ceramic usually loses strength in the early stages before it develops its coherent microstructure. All of these present handling problems which, while not insurmountable, may be expensive in their solution.

One very realistic largeness limitation is the availability of large heat treating furnaces. In the production of the 8 foot alumina cylinder mentioned a special kiln was engineered for this purpose. The problem of the large kiln is amplified when the temperature required is above 2900°F or the temperature uniformity demands gradients held to less than 10°F. Atmosphere control is an equally difficult problem in larger kilns.

So the largeness limitation is dictated primarily by the economics of translating precise technology to a large shape. It must be related to the total ceramic process rather than the forming process alone.

Better communication with designers who specify sizes, shapes, and tolerances may be a way of realistically modifying the requirements of geometric characterization. Often if the design is adapted to the material to a small degree rather than a complete attempt to adapt the material to the design, procurement is expedited without sacrificing any overall design requirements.

C. HOT FORMING PROCESSES

by R. M. Fulrath

Hot forming includes those processes for densifying ceramic powders or shaping a pre-compacted ceramic by the simultaneous application of pressure and heat. In a few isolated instances hot forming is used as a production method. The majority of the cases where hot forming is used, however, lie in the area of research and development. These methods of forming are unique in that they can be adapted to form many materials into high density specimens without extensive experimental studies. Because hot forming has been essentially a research tool, individual opinions on its utility and potential are often prejudiced by personal experience. This section has attempted to be objective in injecting the individual opinions of numerous workers in the field.

The evaluation of a forming method is primarily made on the basis of the properties of its product. The differences in the importance of a specific property to a technological area dictates the extent of interest in hot forming. For example, in producing oxide or carbide tool bits, high mechanical strength requires high density and a small grain size in the polycrystalline material. Hot forming by hot pressing has been developed to give these characteristics. In the development of nuclear fuels the density of compacted UO_2 grains is of importance. The utilization of this material does not require a high strength ceramic because of the metallic cladding used to form the fuel element. Hot forming by hot swaging or hot isostatic pressing can give a high density ceramic. The optimum optical properties of the alkali or alkaline earth halides require a high density. Hot pressing can again be applied to form such materials with the desired properties. The latter two examples do not require high strength in the compacted material, and, therefore, the hot forming methods applicable to these two technological areas may be broader than those applicable to the first example given.

1. Hot Forming Methods

Hot forming methods may be classified in a manner similar to those methods used in cold forming. In general, these methods are outgrowths of the cold forming methods with the added variable of heat. In a few cases the application of metal working methods has been tried to densify or shape ceramics and are included in this classification more to show awareness rather than give details of the application.

Because of the amount of information and experience available in uniaxial hot pressing, a major portion of this section will be devoted to this method.

TABLE I. Methods of Hot Forming Ceramics

- (1) Hot pressing
 - A. Uniaxial pressure application
 - B. Biaxial pressure application
 - C. Triaxial or isostatic pressure application
 - (1) Pressure mechanically applied
 - (2) Pressure applied through a gas or liquid medium
- (2) Hot coining
- (3) Hot rolling
- (4) Hot extrusion
- (5) Hot forging
- (6) Hot swaging
- (7) Methods involving high rates of pressure application

2. Uniaxial Hot Pressing

This forming technique has been applied to practically all of the oxides, nitrides, carbides, borides, beryllides, and halides. In the case of boron nitride, iron carbide, aluminum nitride, silicon nitride, and titanium diboride uniaxial hot pressing has been the forming method that produced compacted material with acceptable properties. A variation of the usual method of uniaxial hot pressing has been used to semicontinuously produce aluminum oxide rods.

The equipment and methods used in uniaxial hot pressing show considerable variation. Practically every individual working in the field has constructed his own hot pressing system. Each hot pressing system has its own characteristics with regard to its operation depending on the individual design. Recently engineered apparatus for uniaxial hot pressing has appeared on the market indicating the surge of interest in this technique.

A general description of a typical uniaxial hot pressing system is included and variations of this system described. In the simplest uniaxial hot pressing system the material to be hot pressed is placed in the center of a cylindrical graphite die. Cylindrical graphite plungers are inserted and the die assembly placed between platens of a press with suitable refractory insulators between the graphite plungers and the platens. Carbon black, carbon wool, or alternate insulation is packed around the die assembly and retained in place by a nonconducting shell of fused silica or cement bonded asbestos. An induction coil around the outer shell is used to heat the die assembly. Argon or other inert atmosphere is circulated over and through the thermal insulation to prevent oxidation. The pressure is applied to the material by a hydraulic jack acting on the graphite plungers. Normally the die and material to be pressed is heated to the desired temperature and then

pressure applied. Maximum temperature and pressure attainable depend on the particular installation and design.

The major variables encountered in hot pressing equipment are the die material and design, method of heating, atmosphere control, and pressing aids employed.

Graphite is the most common die material used for uniaxial hot pressing systems. However, other die materials are being used on a limited scale. Table II lists the materials being used or considered for use and limits of temperature and pressure at forming temperature considered to be attainable at the present time.

TABLE II. Uniaxial Hot Pressing Die Materials

<u>Material</u>	<u>Maximum Use Temperature (in °C)</u>	<u>Maximum Pressure (in psi)</u>	<u>Remarks</u>
Graphite	2500	10,000	Inert atmosphere required
SiC	1500	2,500	Reactive with many materials difficult to machine
TaC	1700	8,000	Expensive, difficult to machine
WC and TiC	1400	10,000	
W	1500	3,500	Easily oxidized
Mo	1100	3,000	
Al ₂ O ₃	1200	20,000	Difficult to machine,
ZrO ₂	1100	?	needs extreme care in
BeO	?	?	loading, low thermal resistance
TiB ₂	1200	15,000	Expensive, difficult to machine
Inconel X			
Hastelloy	1100	varies	Mainly used for halides
Stainless Steels			

Graphite is the most universally used material for hot pressing dies. It is available in many grades with differing densities, strengths, and thermal and electrical properties. Its increase in strength with temperature, low thermal expansion, ease of machining, and low cost make it a nearly ideal die material. Experience with many grades of graphite has not suggested any criteria for selecting one grade for hot pressing dies. Generally, the 1.6 to 1.8 gm/cc density extruded graphites are used. Molded graphites rather than extruded grades are considered best when the die is heated by electrical resistance. New materials such as the "ZT" grades of graphite and pyrolytic graphite are being appraised as possible hot pressing dies and plungers. Because of the enhanced anisotropic properties of these materials, their applicability to hot pressing

dies appears to pose serious problems in die design. "Glassy Carbon" is another new material that may be investigated, though cost and availability of significantly large sizes presently limits its applicability.

The carbides have been tried as hot pressing die materials on a very limited scale. The expense of machining may be a limiting factor. The refractory metals tungsten and molybdenum have been used, but creep of the metals at high temperature limits their usefulness. Titanium diboride although showing excellent high temperature strength and an increase in strength with temperature (35,000 psi flexural strength at room temperature and 60,000 psi flexural strength at 1600°C) is limited because of the difficulty in machining, and, consequently, few experiments using TiB_2 as a die material have been attempted.

The alloys based on iron-nickel-chromium or nickel-chromium have been used extensively in hot pressing the alkali and alkaline earth halides. Their maximum temperature limitation is due to metallic creep.

Interest in oxide die materials for hot pressing in oxidizing atmospheres has increased significantly. High density alumina has shown promise in this area and can be operated up to 40 hot pressing cycles, provided extreme care is used in the operation of the equipment. Both alumina and stabilized zirconia are limited by low thermal shock resistance and creep at elevated temperatures; however, the lack of chemical reactivity with some materials and oxidation stability compensates for these limitations.

Design of hot press dies is generally based on the standard formulas for thick-walled cylinders with internal pressure. For small diameters these are generally successful in predicting maximum pressures attainable at any temperature, provided the tensile strength-temperature relationships are known for the die material. As the die internal diameter increases, imperfections in the die material make the behavior more erratic. This is especially true for large graphite dies where there has been considerable experience with hot pressing in the metallurgical field.

Die washes, liners, or sleeves have not been investigated sufficiently to predict their potential. Metallic foils of platinum, molybdenum, and tantalum have been used in graphite dies to prevent reaction between the material being pressed and carbon. Success has also been attained in using a mold wash such as boron nitride on graphite. Molybdenum dies have been chromium plated and used to 1100°C successfully with materials that react with molybdenum. Complex designs such as alumina sleeves in stainless steel have been attempted for low temperature hot pressing (under 1100°C).

In the hot pressing of dielectric ceramics of the barium titanate type, a zirconium oxide powder has been used between the graphite die

and the dielectric. The zirconia powder transmits the pressure from the graphite plungers to the dielectric powder and prevents graphite reaction with it. It is not known whether the pressure acting on the barium titanate is uniaxial or hydrostatic. However, useful products have been obtained.

Induction heating of graphite dies is a simple and economical method. This technique, however, is more difficult to adapt to controlled rates of heating and cooling and to assured temperature uniformity in the specimen. Even so, induction heating is used in a majority of hot pressing systems because of the high temperatures attainable. Resistance heating of graphite dies by direct passage of electric current has interesting applications. For oxide dies and in some cases graphite die assemblies heating by radiation from resistance heating elements has allowed closer control of temperatures. Temperatures attainable by this method in general are under 1800°C. The type of heating employed in many instances is coupled to the type of material being hot pressed and specific hot press design.

Atmosphere control in hot pressing is often necessary. Graphite below 2200°C must be operated in an inert atmosphere or vacuum. Above 2200°C an inert atmosphere must be used because of the vapor pressure of the graphite. In many assemblies the graphite is heated and residual oxygen reacts with the carbon black thermal insulation or die material to form carbon monoxide as the gaseous atmosphere. The low rate of oxygen permeation through the carbon black prevents serious oxidation. Other systems flood and continuously flush with an inert gas such as argon. In either case the atmosphere at the sample position is unknown, but probably in the first stages of hot pressing is reducing.

Vacuum hot pressing has been attempted successfully in a number of laboratories. In pressing oxides one would suspect that an applied vacuum would facilitate attaining very high densities. There is no direct experimental evidence to confirm this. When pressing two-phase systems, such as glass-crystal combinations, there is definite experimental evidence that vacuum hot pressing reduces entrapped gas and leads to more uniform microstructures.

To aid the densification process during hot pressing controlled impurities are often added. Fluorides are added to oxide materials such as MgO and BeO. Post-forming heat treatment in oxidizing atmospheres of these materials can be used to eliminate the fluoride. This method has been used to produce translucent MgO.

In all hot forming processes the response of the material to the application of pressure and temperature is the most important parameter. Unfortunately, this response is a major unknown. Because density attained is the most universally accepted measure of hot pressing success, numerous

materials have been investigated as to the density achieved under various pressure-time-temperature conditions. These relationships have been used to formulate the mechanism by which materials densify. Two major mechanisms have been proposed. One regards the mass transfer to occur by volume diffusion and the other by plastic flow. It is not apparent at present that either method alone is the only mechanism. It is possible and quite probable that particle sliding, plastic flow, and volume diffusion each take place during hot pressing and their relative importance in achieving a final density is governed by the character of the initial powder and the exact hot pressing environment. No worker in the field can or will predict the hot pressing conditions necessary for a given crystalline powder unless he has previously tried to hot press it. The general consensus is that a "try and see" attitude must be taken at the present time.

There are numerous examples of the same material chemically behaving quite differently according to the character of the crystalline powder. Fine particle sized (below 0.5 micron) alumina will compact to approximately 30 percent of the theoretical density under a load of 1000 psi, whereas, larger sized particles (above 2 microns) will pack to approximately 50 percent of the theoretical density. On heating these materials to 1000°C under 1000 psi applied load, the large particle size alumina will essentially retain the same volume, whereas, the smaller particle size material will densify to 50 percent of the theoretical density. No evidence of sintering or grain growth can be found in the fine powder. This difficulty in understanding the response of a material to hot forming in general has kept the field active in research and development. The ultimate ability to characterize fine powders and to determine the characterized powder's response to the simultaneous application of pressure and temperature is paramount to the development of a scientific approach to hot forming.

Experience has dictated the primary process control in hot pressing to be the pressure-temperature relationship. Most systems are operated so that the full pressure is applied at the maximum temperature. During the heating cycle a small holding pressure is applied to maintain alignment of the system. Other than this very little work has been attempted in evaluating the temperature-time relationships or effects of atmosphere control. Because uncompact powders have low thermal conductivities, it is possible that severe thermal gradients would exist in the material to be hot pressed just prior to the application of pressure. In vacuum hot pressing time would also play an important role due to the slow permeation of gas through graphite or the powder to be hot pressed. These factors will increase in importance as the size of the hot pressed shape is increased.

Pressure distributions undoubtedly occur in hot pressing similar to those encountered in cold pressing. No information other than density variations in limited samples is available to support this conclusion.

It is realized that this would become increasingly important as sizes of hot pressed shapes are increased.

Hot pressed shapes, sizes, and uniformity are important considerations. Cylindrical, square, and rectangular cross sections have been fabricated. By use of a collapsible graphite tube to form the inner diameter, oxide tubes have been formed by hot pressing. As a "rule of thumb" the length-to-diameter ratio for hot pressed specimens should not be greater than 4 to 1. Although specimens with ratios as high as 9 to 1 have been formed, density variations along the length become increasingly severe above the 4 to 1 ratio. A unique method whereby the hot pressed material itself forms the bottom plunger has allowed alumina rods 4 inches in diameter and up to 6 feet long to be formed on a semicontinuous basis. The density of the product in this case varied between 90 and 95 percent of the theoretical density.

Examples of maximum sizes that have been hot pressed to this time are given in Table III.

TABLE III. Maximum Sizes of Hot Pressed Shapes

<u>Material</u>	<u>Diameter in inches</u>	<u>Length in inches</u>
BN	14	14
BeO	10	10
	12	2
Al ₂ O ₃	9	6
MgO	7	1/2
TiB ₂	6	18
	8	8

It is by no means implied that the sizes in Table III are the maximum possible sizes attainable. The general opinion is that if a larger shape were desired, it could be made by hot pressing if suitable equipment were available.

The smallest size that can be attained by hot pressing an individual shape is thought to be approximately 1/4 inch diameter by 1/4 inch high. No clear-cut limit is apparent, however.

Uniformity of hot pressed pieces either piece to piece or within one piece has not been subjected to thorough study. With beryllia density variations of $\pm 0.2\%$ in one piece and $\pm 0.5\%$ in repeated specimens have been reported. Alumina tool bits are quoted as having better uniformity from hot pressing than from cold pressing and sintering. Grain size variations in one beryllia sample 12 inches in diameter varied from 10 microns at the center to nearly 100 microns at the edge. The number of pieces repetitively produced by hot pressing to date has not been sufficient to adequately evaluate the uniformity of grain size, density,

and other properties that can be achieved.

Various schemes to make hot pressing more economical by a continuous or volume process have been proposed. Die assemblies maintained hot with a heated feed and hot ejection have been suggested, but there is no evidence for such a systems having been tried. The use of many die assemblies which are preheated, passed under a press, and then cooled has been proposed but die costs are a prohibitive factor. Stacked pressing of a number of pieces in one die and gang pressing of a number of die assemblies have both been used successfully on a semicontinuous process.

The pressing of large shapes and cutting of the desired specimens from them is practiced by the producers of boron nitride and ferroelectric ceramics. This method has been limited to those materials for which cutting costs are not prohibitive.

Continual production by hot pressing does not appear to be impossible but superficial examination of the problem indicates unit costs would probably be high.

3. Other Hot Forming Methods

Little experience with biaxial pressure application at temperature is available, although the method has been tried in systems similar to conventional uniaxial pressing systems. No apparent gain was realized.

Interest in isostatic or triaxial hot pressing has significantly increased during the past five years. At least four laboratories are actively pursuing this forming method. The current interest is in using a gas for the transmission of pressure. In high pressure geophysical research the heated tetrahedral mechanical press has been used, but little information concerning its application to ceramics is available.

The equipment used in hot isostatic pressing consists of a pressure vessel containing a furnace. The material to be pressed is sealed into a metallic container, inserted into the furnace, and heated to the desired temperature. The pressure of an inert gas in the vessel is then raised to the desired level. One small isostatic press has a chamber 1-1/2 inches in diameter and 3 inches long. It can reach 2200°C with a pressure of 40,000 psi.

Large installations capable of forming samples 13 inches in diameter and 3 to 4 feet long have been constructed. These operate to 1550°C and 15,000 psi helium gas pressure. Canning materials to contain ceramic samples have been primarily of stainless steel.

Hot isostatic pressing has been applied to ceramics, cermets, and other composite materials containing ceramics. The method offers a unique pressure pattern which may be expected to cause material to respond to temperature

and pressure differently than other hot forming methods.

Hot rolling of crystalline ceramics for the production of plates or sheets has been investigated in a number of laboratories. An extensive research effort is now in progress at one laboratory. The equipment that is being and has been used is essentially metal working rolls with alumina ceramic sleeves. Internally heated rolls have not been used; rather, the material is precompact and heated then passed through rolls which are at a lower temperature than the compact. This results in undesirable heat transfer from the material to the roll. Evidence from barium titanate, forsterite, and synthetic mica indicates that a glass phase must be present to successfully hot roll ceramics. A porcelain body has been successfully rolled by preheating an isostatically preformed body to 1520°C and passing it between alumina ceramic rolls. A 25 percent reduction in thickness per pass was achieved. The glass viscosity and proportion appear to be important parameters in hot rolling. Twenty to 40 percent glass is necessary with approximately 30 percent optimum.

Hot Extrusion of canned and unrestrained ceramic powders has been investigated in many laboratories. Lithium fluoride powder has been hot extruded in vacuum to give translucent rods approximately 1/8 inch in diameter. Fine grain sizes were not attained. The extrusion of a single crystal of lithium fluoride gave a glass clear polycrystalline rod of fairly large grain size. The more refractory materials such as oxides have generally been restrained and coextruded with a metal can. Magnesium oxide has been hot extruded in a heavy molybdenum can. The oxide material exhibited a fine-grained surface and coarse-grained interior.

Marble dust canned in steel has been extruded and hot rolled between 700 and 800°C with no evidence of a liquid phase. Barium titanate has been canned in stainless steel and hot extruded at 1000°C with pressures of about 270,000 psi. A research effort on the hot extrusion of uranium dioxide both clad in stainless steel and unclad was recently initiated. The work to date has shown that at approximately 70% of the melting point in degrees Kelvin sufficient plasticity is achieved for hot extrusion. Density of the final product is the major criterion; however, a wide range of process variables will be studied.

Hot extrusion has posed serious problems on extrusion die materials. The high pressures required have usually necessitated that the material to be extruded be preheated and rapidly placed in a relatively cold extrusion chamber and extruded through relatively cold dies. What effect this has on the material response is unknown and may be a limiting factor.

The major problems with hot extrusion are associated with the lack of high temperature extrusion dies and the inability to characterize the material response.

Hot forging of cermet materials to both densify and shape has been

successfully applied. Uranium dioxide-molybdenum and friction materials in which ceramics are dispersed in metallic matrices are two examples. Hot forging has been used to improve the density of fused silica. No evidence exists of hot forging being successfully applied to pure crystalline oxide ceramics. The response of either precompacted ceramics or powders to the relatively rapid application of pressure in forging appears to make this hot forming method impractical for this class of materials. The ductility imparted by a metallic or glassy matrix is necessary. The lack of availability of impact resistant platens and hammers for high temperature use would certainly make this area difficult to pursue.

Hot coining has been used extensively in the metal working field to impose a change in configuration on a preshaped blank. It has possibilities in ceramics for densification, changing shape, and embossing.

The application of hot swaging to unrestrained ceramics for densification is similar to hot forging and does not appear to have been tried. Metallic clad uranium dioxide has been hot swaged to densities above 95 percent of theoretical in forming nuclear fuel elements. However, less expensive and more reliable methods of achieving a high density have discouraged extensive investigation in this area. One investigation in hot swaging clad barium titanate resulted in a dense but cracked ceramic on stripping the metallic cladding. The compaction of electrical insulation by swaging is of course a well established technique.

Methods of hot forming involving high rates of pressure application have been studied. Cold forming of ceramics and cermets have been attempted by explosive methods. The experience to date has shown some promise when the material contains a ductile matrix. This method has not been tried on preheated ceramics or cermets. Pressure application in the millisecond instead of the microsecond range encountered in explosive forming has been achieved by use of gas accelerated plungers. This method has been tried to both densify and to extrude uranium dioxide and a few selected cermets for nuclear applications. UO_2 compacted by this method at 1100 C is reported to give large grains. No evidence of forming a structural ceramic by this method has been reported.

4. Summary of Hot Forming Methods

Hot forming ceramics by uniaxial or isostatic hot pressing is presently being quite actively pursued. The full potential of either method has not been exploited due to lack of studies in process control and the inability to characterize the response of materials to the simultaneous application of pressure and heat. The materials subjected to hot forming are often judged by one physical property because of specific technological interest. More detailed study of all properties are needed to adequately assess the forming method.

Improved die design is essential in both hot extrusion and uniaxial

hot pressing. Production studies on equipment design by competent design engineers should assist in producing a continuous hot pressing scheme on an economical basis.

The kinetics of densification under simultaneous pressure and heat appears to be the important parameter in limiting the application of hot extrusion, hot rolling, hot swaging, hot forging, and hot coining to structural ceramics that do not contain a metallic or glassy phase.

D. MELT FORMING PROCESSES

by Alfred R. Cooper

Those processes in which at some stage, typically prior to the forming operation, the material is in a totally molten or nearly molten state are classified under melt forming. In Table I is shown an outline of the types of melt forming processes used in ceramics along with an indication of the types of materials and shapes that are produced. Each composition will exhibit its own characteristic behavior during processing. Because of the variety of processes, important material variables, and the rapid advances in the state of the art, it appears an overwhelmingly difficult task to hope to characterize definitively the limitations of all these processes for all materials and for all time. Instead the effort will be made in this section to suggest the types of limitations, the special features, the degree of understanding that seem desirable for fuller understanding of various melt forming processes.

Melt forming processes are divided into four major groups as indicated by the underlined headings in Table I. In general melting ceramic oxides prior to forming provides the opportunity to use a feed that is usually homogeneous and virtually without pores. It provides opportunity to obtain microstructures that are not achievable by any other processes. It typically allows fabrication to sizes and shapes that are only slightly modified by the shrinkage of the piece after forming. It presents an easy opportunity to achieve a wide degree of control of the atmosphere that is in contact with the material at high temperatures. Melting can often be used as a purification process. Finally non-equilibrium or high temperature phases with specially desirable properties can often be obtained only by crystallization from a melt.

Not only are there inherent advantages associated with melt forming, but clearly there exist serious disadvantages, some related to the fact that higher temperatures are required than in any other ceramic processing scheme, and others associated with the phase change from liquid to solid and the accompanying significant reduction in volume and the potential large change in gas solubility. Also, crystallization from a melt can result in segregations that negate the advantages of the original homogeneity.

TABLE I. Melt Forming Processes

1. Glass Forming Processes

A. One Dimensional Objects

- (1) solid fiber
 - a. melt drawn fiber
 - b. melt blown fiber
 - c. made initially as marbles, remelted, and drawn as fiber
- (2) solid rod
 - a. gravity feed (Vello)
 - b. extrusion feed (Danner)
 - c. up draw process
 - d. down draw process
 - e. hand draw
- (3) hollow fiber
- (4) hollow rod (tubing)
same processes as rod

B. Two Dimensional Objects

- (1) sheet (three Process)
- (2) plate
 - a. continuously rolled followed by grinding and polishing
 - b. pot melted and poured
- (3) film

C. Three Dimensional Objects

- (1) press
- (2) blow and blow
- (3) press and blow
- (4) casting (including centrifugal and injection)

D. Coatings

- (1) flame spraying
- (2) room temperature coating with powder and melting (enameling)

2. Crystallization of Articles Originally Formed as Glasses

- A. Nucleated by radiation
- B. Nucleated by catalyst
- C. Self-nucleated

TABLE I. (continued)

3. Forming from Melts of Non-Glassy Ceramics in Bulk (Fusion Casting)

- A. Cooling in Place (in furnace)
 - (1) to produce blocks for cutting to shape
 - (2) to produce grain (refractory or abrasive)
 - (3) to produce single crystals
- B. Pouring and Cooling in Molds
 - (1) graphite compositions
 - (2) refractory grain
 - (3) steel
 - (4) water cooled copper
- C. Continuous Casting
- D. Single Crystal Growing
 - (1) vertical pull (Czochralski)
 - (2) temperature gradient (Bridgman/Stockbarger)
 - (3) floating zone (Pfann)
 - (4) flux-grown

4. Forming from Individually Melted Particles

- A. Melt Sprayed Coatings
- B. Free Standing Shapes Formed by Melt-spraying
- C. Single Crystal Growing
 - (1) flame fusion (Vernueil)
 - (2) F fusion

1. Glass Forming Processes

Glass forming technology takes advantage of viscous deformations, a stable mode of shaping, involving a logarithmic increase in viscosity with decrease in temperature. Practical glass compositions permit transition over many orders of magnitude (10^3 to 10^{15} poise) of viscosity with decrease in temperatures to occur in a relatively short time interval during cooling to rigidity. The merits of the glass forming process lie in its wide flexibility to produce an extreme variety of shapes and sizes efficiently. Glass is virtually the most homogeneous of ceramics which among other advantages permits the polishing of surfaces to extreme smoothness (75 Angstrom units).

The ability to form a glass depends on the relative sluggishness of crystal nucleation and growth in super-cooled viscous liquids. It will depend therefore on the cooling rate achieved during processing. Thus, large articles will be more difficult to obtain as glasses and the compositions that can be utilized for glass forming will depend on the shapes and sizes of objects to be formed, and the method used for cooling. A rough indication of the viscosities of liquids that are suitable for glass forming under usual mass production conditions appears in Table II.

TABLE II. Minimum Viscosity at Liquidus Temperatures

spinning	2,000 poise
pressing	3,000
blowing	2,000
tube drawing	100,000
sheet drawing	100,000
sheet rolling	100,000

Those forming processes which cool the glass rapidly by having it contact metal mold surfaces with high surface heat transfer coefficients can tolerate much lower viscosities at the liquidus temperature than processes which inherently cool the glass more slowly because of the low surface heat transfer coefficients that occur at gas--glass interfaces. Not evident in Table II is the fact that surface area to volume ratio will also govern the cooling rate. Thus glass fibers can be drawn from relatively fluid liquids, while larger objects of the same composition will tend to crystallize.

Inherent Size Limitations. --The fundamental question as to how large a monolithic piece can be made from glass relates to this same heat transfer behavior. To produce a glass it is necessary to be able to cool the piece sufficiently rapidly to prevent the interior from remaining at crystallization temperatures for a period prolonged enough for devitrification to progress inward from its origin on the surface. As the rate of heat transfer of a slab is proportional to its thickness and the quantity of heat contained in the slab is also proportional to thickness, the rate of cooling of the interior is inversely proportional to the square of the thickness. Because of the inherent slowness of homogeneous nucleation, extremely low rates of cooling may be tolerable. In fact in certain glass systems there may be only little overlap of the temperature regions where crystal nucleation and crystal growth occur at finite rates. Depending on its nucleation and growth rates, each glass composition should have some limiting size to which it can be produced without devitrification. Little effort has been made to determine these limits but indications are that a thickness of 6" would be safely below the limit for most commercial glasses.

Limitations on Glass Utility. -- The utility of glasses is limited not by the forming processes but by (1) their behaving as viscously deforming liquids when heated to relatively low temperatures, and their (2) susceptibility to brittle fracture at lower temperatures. Since glasses invariably fail from tensional stresses at the surface, it is logical to attempt to improve their serviceability and strength by introducing internal stresses that will result in compression on the surface. This can be achieved in several ways as indicated in Table III.

The first process in Table III is most favorable for relatively thick cross sections of simple shape while the latter three processes can be applied even to thin sections of more complicated shapes.

Process 1 can be expected to increase the long-term strength of glass by a factor of four or more. Process 2 has reportedly achieved fifteen fold strength enhancements of standard abraded surfaces, but such techniques are mainly in the development stage and presently limited to a few compositions. Process 3 is equivalent to the application of a compressive glaze. Process 4, because its stress development does not depend on cooling, has possibly the widest potential. Unfortunately it is the least developed of the surface strengthening procedures.

Dimensions. --As mentioned earlier and indicated by Table I, there are a wide variety of ways of viscously deforming glasses to desired shapes and sizes at very rapid rates. In fact one of the fundamental advantages of glass as a material is the flexibility and speed of the glass-making process. There are however limitations in the size and shape that are attained by the equipment presently available as indicated by Table IV. While these limitations should not be considered fundamental they do represent what has been achieved and therefore represent an

indication of the present limitations. As long as thirty years ago techniques for casting glass up to 200" were developed. The limitation was not the forming step but the annealing time, which required six months.

TABLE III. Methods for Inducing Compressive Stresses on Glass Surfaces

1. Cooling rapidly through the annealing range so as to have a "no stress" condition with a severe temperature differential between surface and center. When the glass cools completely to a uniform temperature, a continuous pattern of internal stresses develops from the unequal cooling with maximum compression on surface and maximum tension in center. This is called tempering.
2. Changing the structure or compositions of the surface region at elevated temperatures to have a lower coefficient of expansion than the bulk. On cooling compressive stresses will develop on the surface. Since the region treated is typically very thin, the compressive stresses are confined to an equivalently narrow region, and the interior tensions are of much lower absolute magnitude than the surface compression.
3. Cladding the bulk glass at elevated temperature with a glass of lower thermal expansion.
4. It has been proposed that diffusing large ions into the glass at the surface and thereby tending to expand the surface will result in the development of compressive stresses. Since this would be the only process that would not depend on subsequent cooling for stress development it would be the only process that would be of value for a low-expansion material like fused silica.

TABLE IV. Typical Dimensions for Articles Made by Glass Forming

<u>Shape</u>	<u>Size</u>
<u>One dimensional solid</u>	
*fiber	0.00012 $\pm$ 0.00002" min. diameter
*extruded rod	2.0 $\pm$ 0.10" max. diameter
cast rod	4.0" (or greater) diameter, limited length
<u>One dimensional hollow</u>	
*fiber	min. outside diameter unknown
*standard tubing	0.120 $\pm$ 0.016" min. outside diameter
*standard tubing	7.0 $\pm$ 0.150" max. outside diameter
hollow cylinder	14.0" (or greater) max. outside diameter
wall thickness	typical for 4" outside diameter tube 0.093 to 0.500"
<u>**Two dimensional</u>	
continuous ribbon	oil to 1.5" wide, 0.0014" min. thickness
continuous ribbon	up to 14" wide, 0.002 to 0.024" thickness
drawn sheet	up to 120" wide, 0.040" to 0.400" thickness
plate glass	up to 158" wide, 0.106 to 1.25" thickness
rolled glass	thickness up to 3"
<u>Three dimensional</u>	
small three dimensional articles fashioned from tubing	
pressed ware	30" diameter, 18" height approximate maximum; wide variety of single tapered shapes and sizes
blown ware	no shape limitation. 18" outside diameter; 30" length maxima
spun ware	limited to axially symmetrical shapes. 14" outside diameter; 36" length maxima

*continuously drawn products; lengths depend only on convenience of cutting and/or winding

**all two dimensional products except rolled glass are made continuously so thickness depends on convenience of cutting. Thickness variations of 10% are typical.

2. Crystallization of Articles Originally Made as Glasses

Although the idea of utilizing the ease of the glass making process to form shapes and later on transforming them to different structures by heat treatment is relatively old, it is only very recently that this principle has been exploited in modern technology. Probably the first major example is the liquid-liquid separation that can be obtained by heat treatment of certain borosilicate glasses leading to two continuous phases. One of the phases being soluble, it can be eliminated by leaching. The remaining porous structure is readily sintered to form a non-porous glass. This technique has technological importance in that it allows relatively high temperature glass (96% silica) to be formed using ordinary glass making procedures.

Subsequent to this development there have been devised processes in which articles originally formed by glass-making have been crystallized either completely or locally and a new class of polycrystalline ceramic materials that have unique structures and properties have resulted.

An advantage of this process is that it utilizes the flexibility and speed of ordinary glass making to form the shapes. It therefore possesses the inherent merits of forming by viscous deformation. In addition the types of crystal structure and microstructure that can be achieved in crystallized glass go beyond those that are obtained by conventional ceramic processes. This is because the immobility of very viscous liquids allows nucleation and crystal growth to be separate processes. By controlling the temperatures and the sites for nucleation it is possible to nucleate different crystals. By controlling the time of nucleation it is possible to have the desired density of nuclei and thus determine the eventual crystal size. By controlling the time and temperature of crystal growth it is possible to obtain the degree of crystallization desired. This separation of nucleation and growth allows a wide variety of microstructures to be obtained. Particularly important is the opportunity to develop very fine structures with grain size as small as 200 Angstrom units. This results in transparent polycrystalline ceramics.

The homogeneity of the original glass material results in the development of polycrystalline structures that are extremely uniform from one local region to another. The process is controlled well enough to obtain reproducible microstructures. Typically, crystallized glass structures have zero porosity because the uniform crystallization and the remaining glass allow the structure to shrink during crystallization to compensate for any changes in volume that may occur on solidification.

Certain crystals that can be developed by crystallization from glass are difficult if not impossible to obtain by other ceramic processes. Some allow extremely low thermal expansion ceramics to be achieved. The fine microstructure is important for low expansion bodies because it

tolerates the anisotropic thermal expansion typical of low expansion crystals. These low expansion bodies are extremely resistant to thermal shock. Finally, the small uniform grain size allows the development of polycrystalline structures whose strengths are relatively insensitive to surface damage, giving glass-ceramics significantly higher engineering strength than the glasses from which they were formed.

The presently available glass-ceramics are limited by the temperatures to which they can be utilized. The present maximum melting temperature is of the order of 1250°C and the recommended long-term use temperature has a maximum of 730°C . At the present the available compositions have involved the use of nucleating agents to develop the structures, and therefore the resulting composition has certain impurities from these nucleating agents.

In terms of their microstructures glass-ceramics have fairly wide flexibility. Single phase compositions have been produced, and compositions with as many as three or four different phases have been obtained. The amount of glass remaining in the structure can be varied over wide limits. Typically there is only one continuous phase. Because of the homogeneous nature of the original glass and the randomness of nucleation and growth, the crystals are entirely unoriented in the body. Grain sizes can be varied from as low as 200 Angstrom units to 10 - 20 micron, but generally the sizes are of the order of 1 micron. Porosities are usually vanishingly small.

The sizes and shapes that can be obtained in glass-ceramics are very nearly the same as those obtained by ordinary glass making procedures, Table IV. However, it must be recognized that the typical glass-ceramic compositions have greater tendency to crystallize than usual commercial glass and therefore if one wishes to control completely the crystallization process he cannot tolerate crystal nucleation or growth during the original forming process. This restriction undoubtedly limits the maximum size of the smaller dimension of certain glass ceramic compositions.

It is not known whether glass-ceramics have been produced from all shapes that are made as glass. For example, no indication of glass-ceramics in the form of fine fibers is presently available.

It is possible to utilize the principles of glass-ceramics in typical enamel coating procedures. Metals can be coated with glass by traditional methods and subsequently the coating can be converted by heat treatment into a polycrystalline ceramic that may have more desirable properties than the original glass. This procedure has also been used in the development of graded glass to metal seals where the thermal expansion is continuously varied by adjusting the degree of crystallization of a glass ceramic. Protective ceramic coatings on molybdenum metal that are said to be impervious up to temperatures of 1300°C have been achieved in a similar way.

Some of the processes described in Table III for inducing compression on the surface of glass can be utilized in glass-ceramics. Increases in strength from 20,000 psi to 35,000 psi, have been achieved in this way.

Localized crystallization of glass has been used as a process for chemically machining glass. In this procedure glass-ceramics containing traces of silver silicate are irradiated in local regions so as to favor nucleation of colloidal silver in that area. The resulting silver particles serve as nuclei for crystal growth when the material is heat treated at the growth temperature. If proper selection of crystal phase is made, the crystals can be dissolved or leached out by an acid that only slightly affects the surrounding glass. After the holes or other depressions are produced in this way, the remaining glass is totally radiated, nucleating colloidal silver throughout. A final crystal growth heat treatment converts it into a glass-ceramic. By this procedure holes of as low as 3 mils diameter can be obtained with a tolerance of $\pm 1/2$ mil. The geometry of the holes that are produced in this way can be either cylindrical or conical and perhaps even hemispherical.

While it has been reported that thousands of compositions have been demonstrated to produce glass-ceramics, there are only relatively few currently available. Extensive research promises to broaden the range of compositions and unique properties available by this process.

3. Melting and Solidification of Non-Glassy Ceramics in Bulk (Fusion Casting)

Fusion casting of ceramics currently has been confined to three areas, (1) production of relatively large refractory shapes for use in glass melting and steel making furnaces or for surfaces where unusually high abrasion resistance is required, (2) the production of small, high-purity, high-density shapes for nuclear reactor application, and (3) production of refractory, abrasive, and special purpose grain. While the nature of these processes is fundamentally the same, the size and the overall objectives differ drastically.

Fusion casting allows the achievement of localized regions of very high density (of the order less than 2% volume porosity) in extremely refractory materials. It is a process particularly suitable for the most refractory ceramics. The structure that develops on solidification frequently results in interlocking grains. These two characteristics produce a microstructure that is highly resistant to corrosion and erosion. It is possible to obtain extremely high purity in fusion cast materials, although often this possibility is not important. It is possible to utilize various atmospheres above the liquid during melting and in this way the stoichiometry and state of oxidation can be controlled. For extremely refractory, high-cost material it is possible to produce shapes of high strength and low porosity by fusion casting at lower cost than by the traditional ceramic processing. Uranium nitride and

uranium carbide are examples of materials to which this rule applies. Extremely large shapes are routinely produced by fusion casting and the technology has developed so that shapes other than bricks, blocks or slabs can be produced. For example, large bowls and channels of various shapes are made for the furnaces of the glass industry by fusion casting.

An important advantage of fusion casting has been the opportunity to produce special crystalline ceramics such as beta alumina which is a sodium aluminate. This crystal is much more resistant to alkali atmospheres than is pure alumina itself. It would seem therefore that as a general principle it should be possible to produce by fusion casting ceramics that are specifically resistant to certain environments.

In spite of many advantages, fusion casting has inherent disadvantages which must be appraised with candor. Because of the brittle nature of ceramics and their characteristic thermal conductivity, there is minimum control over the grain structure and grain size that are attained from fusion cast bodies. In multiphase fusion cast bodies there is often a tendency for either direct or inverse segregation to occur. Thus both the composition and the microstructure of fusion cast bodies may vary significantly from the surface to the interior. The as cast surfaces produced by fusion casting usually have a waviness typical of the process. Casting void defects are also typical.

Methods of Fusion of Ceramics.--Melting of large quantities of ceramic materials and cooling in a controlled manner without pouring is an important process for the production of ceramic grains. Shapes may be cut from these ingots, but more likely they are carefully crushed to produce ceramic grain of controlled particle size and shape for subsequent processing. Much refractory and abrasive grain is produced in this way, as is the insulation for swaged electrical resistance heating elements.

If instead of cooling in place the melt is poured into molds, usually graphite or bonded refractory grain, the process is termed "fusion casting." While this is characteristically a periodic process, it has been found possible to continuously fusion cast both uranium compounds and ceramic oxides on a small scale.

Heating of ceramic materials on large scale for fusion casting has been done by immersing electrodes in the melt and more recently by the so-called "long arc" process in which the melt is used as one electrode and a relatively long arc is struck between it and graphite electrodes. This long-arc process allows for control of atmosphere that is impossible when the electrodes are immersed. It is also possible to use a disposable electrode that reacts with the atmosphere and in this way a very high purity melt can be obtained. Induction heating and electron beam heating are also potential methods.

The usual way of melting ceramic materials is in a shell of unmelted

grain of the same composition which results in a non-homogeneous temperature distribution throughout the melt with the center being hotter and the edges being cooler. This temperature inhomogeneity to some degree is unavoidable. However in the long-arc process considerable stirring occurs which should minimize temperature variation.

It is reported that thousands of ceramic compositions have been successfully fusion cast. However, at the moment only relatively few are available commercially. This is probably because these compositions have been determined to have optimum properties for specific uses in furnaces for the process industries like steel and glass. Among the compositions presently available are magnesia, magnesia spinel, magnesia-chrome, zirconia-alumina-silica, alumina-silica, beta alumina, a mixture of alpha and beta alumina, chrome-alumina, uranium carbide, uranium nitride. There seems to be no reason why any oxide that melts at a relatively low vapor pressure could not be produced by fusion casting.

Typically the fusion cast refractory oxides have porosities of the order of 15 volume %. Most of this porosity is associated with a casting void or pipe that is ordinarily in the upper interior of the piece. At regions far from the casting void the local porosity is usually less than 2 volume %, and in the case of carbides it can be significantly less than 1%.

The pipe or void in fusion casting can be located with some degree of certainty by the positioning of the pour and by tilting of the mold, and in this way objects can be produced with the void in the least vulnerable area. If it is necessary to have fusion cast pieces without void it is possible to cast in a way that the void is all confined to a "riser". Then by cutting off the "riser" a sound casting is obtained. It is also possible to more or less distribute the shrinkage from solidification throughout the piece and thus avoid the presence of a large void.

The microstructure obtained in fusion cast materials depends on the chemical and physical properties of the material. Characteristically a reasonably fine grain size is obtained right at the surface of a fusion cast block where the melt has been rapidly quenched by contact with the mold. For some single phase compositions, immediately adjacent to the quenched surface there is found a region of columnar grains, some of which appear to extend almost to the center of the block or to the casting void. These grains are invariably oriented with their direction of rapid crystal growth in the direction of the center. In polyphase blocks the crystal size may be noticeably smaller as crystal growth of the primary phase can deplete the liquid of the components necessary for its further growth. Grain size in fusion cast ceramics will depend on the size of the block to be cast (increasing with increasing block dimensions) and the composition of the melt. They can be as large as a centimeter or two and sometimes as small as 30 microns. In certain compositions there is a uniformity of grain size from surface to center that may only vary by

a factor of two. In other compositions and sizes a tenfold increase in grain size may occur from surface to center of the casting.

The more rapidly the block is cooled the greater the possibility of developing small size grains. However the rate of cooling is generally kept very slow in order to prevent thermal fracture during the cooling process. Hence it is usually only the very exterior which can be quenched. It must be concluded that in the present technology grain size is only moderately adjustable by varying the casting technique. In large shapes particularly, the grain size is mostly determined by the composition and the size of the casting.

Fusion cast oxide blocks typically contain from 0.5 to 17 volume % glassy phase. While this may be due to silica impurities or silica introduced to gain the proper compositions, the presence of a viscous liquid allows adjustments during solidification and during the early stages of cooling that diminish thermal stresses which tend to develop.

Data on dimensions, detailed descriptions of specifications, tolerances, squareness, and maximum sizes of various shapes are available from manufacturers. They are too specific and too extensive to list here. In the following only a few possibilities are mentioned.

Fusion cast blocks are currently cast in sizes as large as 18" x 30" x 48" with a weight of 3400 pounds from zirconia-alumina-silica and other compositions. In magnesia-chrome the maximum size presently made is 6" x 18" x 7". It is probably true that the presence of some glassy phase in the zirconia-alumina-silica composition allows it to be produced with a larger minimum dimension in reasonable cooling time. The surfaces of such blocks are typically rather rough and frequently hairline cracks from cooling are present. It is possible however to surface grind these shapes to relatively accurate dimensions and plane parallel surfaces.

The maximum size piece that can be obtained that is virtually free from porosity is about 8 cubic feet or essentially half the maximum size with voids. Plates 2" - 4" thick x 6" wide and 6' long are probably feasible to make in a virtually pore-free condition. Because of handling difficulties the minimum thickness typically made from fusion cast oxides is 1", but much smaller sizes are routinely cast with uranium carbide. Uranium carbide cylindrical bars of 1/2" to 3/4" diameter, 6" - 12" long are cast with a diameter tolerance of ± 0.004 ".

Coating with molten ceramics has been proposed. Drain or slush casting has been achieved with molten ceramics in which steel cylinders have been clad on the inside surface by pouring in and then pouring out the molten ceramics. This suggests that it might be possible to obtain impermeable coatings for cladding of refractory metals by this process, or by dipping, or any other procedure in which molten ceramic was brought in contact with the cool metal surface.

Single crystal growing from liquid melts.--Unfortunately it was only recognized late in the study that such single crystals might be useful structural materials and no information regarding the melt processes for making single crystals has been obtained. Some references cited in the bibliography will convey the present state of the art. Single crystal growing by melt spraying is discussed briefly in the last paragraph of this chapter.

4. Melting Particles Individually

Melt spraying of ceramics has been successfully utilized in two primary areas: (1) the production of high temperature coatings of high abrasion and corrosion resistance, (2) the production of free standing shapes, usually limited to shapes with axial symmetry. In the following there is presented a summary of the present state of the art followed by a discussion of some of the limitations. There is wide research and development interest in melt sprayed ceramics plus a developing industrial and commercial use. In the area of coatings alone one firm has three plants that are involved entirely with the application of coatings by melt spraying to a wide variety of shapes and materials. One list of commercial applications includes twenty-one items utilizing the features of wear resistance, thermal or electrical insulation, corrosion protection, or as a base for impregnation by resins.

In Table V is indicated the tolerances and maximum densities that are possible with flame and detonation spraying both for coatings and free standing bodies. In general it is seen that while coating thickness is limited there is no limitation to the size of objects that can be coated. In fact it is usually possible to coat by flame or plasma spraying in a discontinuous manner. While shapes of almost any configuration can be coated (corners and edges being especially troublesome), at present the free standing forms are limited primarily to such hollow axially symmetrical shapes as radomes, nozzles, crucibles, and tubes, or in general shapes with not more than one reentrant angle. If the substrate can be destroyed, greater flexibility can be achieved. The production of flat slabs is usually difficult because of warping. However zirconia discs for fuel cells of nearly perfect flatness were produced by melt spraying on sodium chloride and sintering the discs under weights to prevent warpage. Also 2" diameter alumina discs have been produced by spraying on an aluminum metal substrate, releasing by differential contraction, and sintering to cone 35 (1785°C). It is reported that discs sprayed to 0.025" thickness, sintered without distortion and were diamond ground to 0.015" thick, flat and parallel both sides to ± 0.0005 ".

It is possible by flame spraying to coat wire of as small as 0.004" diameter and practical and convenient to coat wires of 0.030" diameter.

There is no question that melt sprayed coatings of parts that are especially subject to wear or abrasion can greatly increase the lifetime

of the part. Objects as diverse as golf club irons, carving knives, plungers for glass pressing and wear surfaces on jet engine blades are sprayed for this purpose.

For axially symmetrical free standing shapes melt spraying has important advantages and convenience. Some of the relatively thin walled shapes easily attained with melt spraying cannot be produced by other ceramic processes. Large size free standing shapes are also reportedly easy to produce. Shrinkages on subsequent firing are lower than in traditional ceramics and the control of inside dimensions is most easily attained in melt spraying.

For very short runs or for the preparation of polycrystalline samples for experiments with refractory materials melt spraying seems to have special merit.

A wide variety of oxides have been successfully flame sprayed, including such materials as alumina, zirconia, chromia, zircon, zirconates, spinels, yttria, and ceria. The higher energy input and inert atmosphere capability of plasma permits spraying of an additional group of materials such as borides, carbides, and in fact all ceramics that do not have a high vapor pressure at their melting point. Some refractory materials such as beryllia, still present a serious problem of attaining satisfactory adherence. Empirical tabulations of the ease of flame spraying of various ceramics have been assembled. Such properties as heats of fusion, specific heat, thermal conductivity, and emissivity, are the material properties that influence the ease of flame spraying. Predictions of success with flame sprayed coatings cannot, however, be made by considering these properties alone.

In terms of purity, flame and plasma sprayed coatings are extremely useful, impurities introduced by spraying being assumed to be as low as 3 - 5 parts per million. In most instances it is possible to maintain stoichiometry during spraying but certain carbides require a sensitive control of atmosphere. This has been achieved with at least one coating technique. Also the high temperature oxides show some tendency to break down, but this effect is less serious.

In terms of structure melt sprayed coatings often contain but a single phase in addition to the pore phase. This phase may not be the equilibrium or most dense phase, for example in the case of alumina, the flame sprayed material is gamma or eta, rather than alpha alumina. In some instances, for example in flame spraying of zircon, there is a natural breakdown into two solid phases, zirconia and a zirconia rich silicate glass. Usually there is not an opportunity for reaction between powders in melt spraying. Thus in the melt spraying of mixtures of alumina and chromia powders there is no evidence of solid solution in melt sprayed deposits, although a complete range of solid solubility exists. If necessary one can produce more complicated phase distributions, for

example, mixing of nickel and alumina powders or cladding alumina powders with nickel metal permits the production of flame sprayed nickel-alumina cermets. A similar procedure is the flame spray of mixtures of pyrex glass and zirconia to give a two-phase system.

Flame sprayed materials have grains that are usually flattened in the direction of flame spraying. The degree of flattening depends on the velocity and the superheating of the sprayed droplets, detonation spraying perhaps giving the greatest degree of "squash." The grain size is determined in powder spraying almost entirely by the grain size of the incoming powder. Powders that are less than 5 microns are difficult to feed to flame spray or plasma spray guns. This factor limits the minimum grain size that is easily obtainable. Submicron powders have been fed into the detonation gun by utilization of special powder dispensing techniques. Also 0.1 to 0.01 micron spheres have been produced by decomposing organo-metallic liquids in the oxy-hydrogen flame, but this appears to have been a vapor process.

A serious limitation of the applicability of flame sprayed coatings is the presence of continuous pores in the as-sprayed state. Typical porosities of flame sprayed ceramics run from 3 to 15% with the difference depending on operating variables and upon the particle size of the feed powder. While most of the pores seem to be continuous or open, there is some evidence of a minor amount of closed pores existing in flame sprayed deposits. Attempts to attain impermeable coatings have been successful with lower melting materials like barium titanate, and special compositions that are impermeable are said to have been developed for coating molybdenum.

The factors that favor the development of impermeable coatings seem to be: (1) low melting temperature powder, (2) high substrate temperature, (3) uniform particle size, (4) fine particle size, and (5) uniform heating of every particle. Even when impermeable coatings are obtained their utility is still questionable. The brittle character of ceramics makes them susceptible to fracture from impact or heat shock. Microcracks can spoil the impermeability. Also when complex shapes need to be coated the corners and edges seriously compound the difficulty of attaining truly impermeable coatings by melt spraying. As-sprayed permeability is not as serious a handicap to free standing shapes because they can be sintered to an impermeable condition after spraying.

While it is usually impossible to heat melt sprayed coatings hot enough to sinter the coating to eliminate gas permeability, a nearly equivalent procedure is to subsequently impregnate the coating with glass after spraying. A recent development allows the glass to be sprayed concurrently with the ceramic particles. While this does not result directly in an impervious coating, sintering of the glass when the material is heated to operating temperatures causes the coating to become impervious by the time the surface protection is required.

When the feed material is introduced in the form of a sintered rod rather than as individual powders, the particle size distribution is determined by the turbulence in the plasma or flame. To date a technique of obtaining finer particle size than 10-15 microns from rod spraying has not been achieved. Rod spraying is said to have an advantage of allowing the residence time for each droplet to be greater and perhaps more nearly uniform than can be achieved in powder spraying.

Melt sprayed ceramics have been applied to a variety of materials including metals (with melting points equal to or greater than aluminum), other ceramics, graphite, resins and such soluble materials as alkali chlorides. It has been shown that the primary bond to substrate in melt sprayed ceramics is largely mechanical. Typically it is adherence that limits the utility of the coating, therefore it is desirable to roughen or even undercut the substrate to gain good adherence. Values for adherence of alumina and zirconia coatings to roughened substrates in tensile testing have ranged from 400 to 1300 psi. An interesting technique for achieving adherence is to melt spray a substrate with its own composition at low velocity and low superheat to form well bonded but only slightly "squashed" droplets on the surface. This reportedly provides a surface equivalent to undercutting which gives higher measured values of adherence.

For free standing shapes it is desirable to spray at temperatures as low as possible to minimize the possibility of adherence. Then it is necessary to use a high expansion metal that will shrink away from the coating. When it is necessary to spray free standing shapes at high temperature to achieve greater densities or strengths, there is a problem of finding suitable parting agents.

To date spraying has been done with either flame or plasma or acetylene/oxygen detonation as the source of the energy. Table VI shows some of the advantages and disadvantages of the alternate techniques. (Electron beam and radio frequency heating can also be utilized, but these are in the early stages of development and their specific advantages remain to be proved.) The feed is introduced as either rod or powder and comparisons are indicated in Table VII.

Deposit efficiency for flame spraying (deposit weight/feed weight) varies between 15 and 95 %, depending primarily on the fraction of the spray that is intercepted by the work and also upon the velocity and degree of melting of the droplets.

Flame spraying is a convenient way of making spherical particles. The minimum size is about 1 micron and the maximum size seems relatively unlimited, for example 500 microns. A difficulty with large spheres produced by flame spraying is that cooling from the outside results in an interior pore due to the volume change on solidification.

The manufacture of single crystals by spraying powders is a melt process. While such parts have been used for special optical and electronic purposes, structural uses also exist for single crystals. Compared with their polycrystalline counterparts, single crystals possess the advantage of higher thermal conductivity, freedom from gas diffusion, and less sensitivity to attack because of the absence of grain boundaries. Properly mounted crystals will not develop the thermal stresses that can be present, even at uniform temperature, in usual polycrystalline bodies of anisotropic materials.

Single crystals can be grown from all ceramics that (1) melt congruently, (2) have relatively low vapor pressure at melting point, and (3) have no crystallographic transformations between m.p. and room temperature. Single crystals can be grown under the tolerances and specifications shown in Table VIII. Ability to control crystal orientation at will has been a limitation.

TABLE V. Dimensions and Tolerances of Melt Sprayed Coatings and Shapes

<u>Coatings</u>	<u>Flame Sprayed</u>	<u>Detonation Sprayed</u>
thickness variation as sprayed	$\pm 0.002''$	$\pm 0.0001''$
maximum tapers as sprayed	$\pm 0.002''$	
maximum thickness of coatings	0.050 to 0.375"	0.020"
maximum thickness of continuous coatings	0.002 to 0.004"	0.0005"
open porosity	3--15%	1%
finished thickness variation	std. grinding limits: $\pm 0.0001''$	$\pm 6 \times 10^{-6}''$ (special gauge block)
surface roughness as sprayed	200 microinches	150 microinches
surface roughness, finished	10 microinches	1 microinch

Free Standing Shapes

thickness of axially symmetrical bodies	unlimited	not determined
length or width, normal to spray direction	unlimited	unlimited
linear shrinkage during sintering	3-4%	
inside diameter variation	1" $\pm 0.0015''$ 1-2" $\pm 0.003''$ 2-3" $\pm 0.005''$	
outside diameter variation	2x inside diameter variation	
open porosity after sintering	practically zero	

Notes: 1. Relative values do not indicate superiority of one process over the other

2. Deep cavities where depth is greater than diameter are difficult to spray if inside diameter is less than $3\frac{1}{2}''$
3. Example of a flame sprayed free standing shape is alumina of 12" diameter with $\pm 0.020''$ on both inside and outside dimensions.

TABLE VI. Some Features of Different Types of Melt Spraying

Flame Spraying

Cheapest

Easiest

Portable

Quickly set up

Useful for free standing shapes and coatings

Possible to coat inside diameters

Particle velocity 150-500 ft./sec. depending upon design of apparatus

Arc Spraying

Highest Temperatures

Wider control of atmosphere for protections of grains and/or substrate

Used for coatings and free standing shapes

Any material with low enough vapor pressure can be plasma sprayed

Possible to coat inside diameters

Particle velocity approximately 1200 ft./sec.

Detonation Spraying

Oxy-acetylene explosions about 4-9 per second

High velocities give best adherence and density

Pulsed energy and particle impingement reportedly gives least heating of substrate

Mostly used for eutectic-liquid-carbide combinations, alumina and alumina-chromia mixtures

Only used for coating, extremely noisy, large stationary installations

Particle velocity approximately 2500 ft./sec.

TABLE VII. Some Features of Powder and Rod Spraying

Powder

Doesn't require additional processing steps (but is often prepared to close specifications)

Allows more control of grain size

Gives finer grain sizes

Slower build up usually

Cheaper for certain materials

Can be used with plasma, flame or detonation

More materials available

Rod

Larger particles

Longer resident times in high temperature zone is claimed

Better adherence (in comparison with similarly heated powder) is claimed

Faster build up of thickness

Not practical with detonation

NOTE: Feed rods can be obtained as solid rods, fluted solid rods, and hollow rods.

TABLE VIII. Present Single Crystal Dimensional Limitations (Alumina)

rods:

maximum diameter 1 1/2" or larger

minimum diameter unknown

maximum length 18"*

discs:

maximum diameter 6"

minimum thickness 1/2"

domes:

maximum diameter 6"

sheets:**

maximum width 1 1/2" or wider

maximum thickness uncertain

minimum thickness 1/4"

maximum length 18"*

*This limitation is easily overcome because rods are formed continuously in this direction

**Called by crystal growers "boule sheet"

E. MISCELLANEOUS FORMING METHODS

by Donald J. Bowers

Battelle Memorial Institute

In the following sections several less common, but highly useful and strategic forming techniques are discussed. Each is undergoing intensive research and development because it contributes certain structures or permits flexibility in processing which can be realized by no other approach. The potential for these techniques is wide, but their usefulness has been limited by economic considerations in many cases. One limitation has been the low-volume demand for the products whose characteristics are uniquely set by the forming method--foamed ceramics, for instance.

The processes considered can be further studied through the references cited in the Bibliography under the classifications indicated:

1. Forming from vapors--F25
2. Porous or foamed ceramics--F16
3. Forming from fibers--F26
4. Bulk placement and molding--F2h, F2j, F2k, F3g, and F5b
5. Impregnation and infiltration--H16
6. Reaction sintering--F5g
7. High energy rate forming--F8
8. Electrophoretic forming--F27 and F7
9. Machining and grinding--all of G and specifically G4, G17, G18, G19

1. Forming from Vapors

Unusual ceramics not obtainable by other forming techniques are being formed by chemical vapor deposition. Chemical vapor deposition is a technique which can be termed molecular forming; that is, the building up of coatings and massive deposits by deposition of molecular or atomic particles. A solid product is formed when the reaction of a suitable vapor is made to occur on a heated surface. The reaction used is one in which all of the components of the system except the desired product and the substrate are volatile at the deposition temperature. The product is of theoretical density and, when the reaction takes place properly, is impervious.

Chemical vapor deposition is accomplished in equipment usually termed a reactor. In its essentials, the equipment must include a retort in which to volatilize the feed material, a carrier gas to take a vapor to the working surface, a hot substrate on which to deposit the material of interest, and an exhaust. The equipment can be laboratory size or

large enough to form structures suitable for missiles and rockets.

The source materials from which the vapor deposited ceramics can be formed fall in three categories: inorganic halides, purely organic compounds such as methane (used commonly for the deposition of pyrolytic carbon), and the alkyl and carbonyl families of metal-organics. It is appropriate to point out that some of the carbonyls are toxic and should be used with extreme caution. All of the halides, which are common source materials for vapor deposition of ceramics, are sensitive to moisture and oxidation. The oxyhalides thus formed are stable and are difficult to volatilize. The metal-organic compounds oxidize readily even to the point of being explosive.

A principle use for chemical vapor deposition for forming ceramics is for the production of high density, impervious coatings. Considerable effort has gone into the coating of nuclear fuel particles. Coatings of pyrolytic carbon, niobium carbide, silicon carbide, alumina, beryllia, zirconia, chromia, and mixed oxides have been made.

Mixed feed vapors can be used to form intimate-mixture deposits. In systems which normally form solid solutions, solid solutions will form by vapor deposition also. In two phase systems, microcrystalline products can be formed and crystal sizes kept small if the deposition is carried out at a sufficiently low temperature. Carbides are formed by the deposition of a metal on a carbon substrate with proper control of the temperature and pressure so that only the metal carbide is stable. The rate of carbide formation is controlled in such cases by the rate of diffusion of carbon from the substrate through the carbide coating, providing very uniform coatings.

The rate at which ceramics can be built up by chemical vapor deposition will vary, of course, depending upon the material and the requirements of its structure. Build-up rates of about 20 mils per hour are possible. Since ceramics formed by this process must be formed on a heated substrate, the shape of the ceramic is determined by the substrate shape. Since the reacting gas surrounds the substrate, the surface on which the ceramic is deposited can be of any shape. Thus, the shape of the ceramic itself can vary as desired. In making coatings, the gas flow must reach all surfaces as evenly as possible to provide uniform coatings. The gas flow can be controlled by baffles or jet streams. If the ceramic desired is to be free standing, the material is deposited on molds or mandrels which are subsequently removed.

The making of thick sections of either a coating or a free standing ceramic poses problems. Progress is being made in the production of thicker pieces, but thicknesses ranging from 1/4 inch to 2 inches, depending upon the material, still present considerable deposition difficulties.

2. Foamed Ceramics

An accepted method of producing very light weight ceramics is to foam the structure, and a number of foaming techniques have been used. The techniques include chemical reaction-hydrolytic reaction, reaction of acid or alkali with a metal additive, incorporating air by agitation, and oxide reduction and gas release. Not strictly a foaming process, but a process used to prepare a similar porous product is one which involves burning out organic additives. Other techniques of producing a light weight material involve bloating the material being fired and sintering of the preformed bubbles or spheres.

All of the foaming techniques are characterized by, at some point in the forming process, the formation of a thin-walled porous structure which is self-supporting and which is given its shape because it retains a generated gas. In such processes the rate of gas evolution must be closely controlled and must occur during a period of the process in which the structure can be stiffened to retain the outline of the foam after the gas generation is arrested.

A detailed discussion of one of the common foaming processes will illustrate some of the factors important in foaming. This foaming technique involves the use of resins. Three types of resins are used together--a phenol formaldehyde, an epoxide, and an isocyanate. The isocyanate resin provides the foaming action while the other two provide the necessary stiffness to the porous mass. The foaming action results from water in the phenol resin reacting with the isocyanate resin to produce carbon dioxide and some nitrogen. The reaction increases the temperature of the mass, causing the phenol and epoxide resins to polymerize and set to a firm structure, trapping the gas bubbles. Ceramic particles mixed with the resins prior to the foaming action are dispersed by the foaming and are left on the walls of the pores.

In controlling the characteristics of the foam, temperature is very important, as is the proportion of the resins. By varying the resin proportion, the strength, density, pore size, and bubble content can be varied and controlled. Control of the environmental pressure during the foaming also can be used to control the foam characteristics.

After the foamed article has been formed, the resins are carbonized to eliminate the volatiles and then the porous mass is given a final heat treatment to sinter the structure. If carbides are to be formed the carbon residue of the resins can be reacted with an oxide in the final heat treatment to sinter the structure. If carbides are to be formed the carbon residue of the resins can be reacted with an oxide in the final sintering treatment in an inert atmosphere. If carbon is not wanted in the final structure, it can be burned out during sintering.

In forming of foamed ceramics in which the foaming takes place

at an elevated temperature, the temperature must be controlled closely to generate the desired pore characteristic. For enhanced control of the type of pore generation which takes place during firing, carbon or graphite particles have been added to the ceramic mix. Properly dispersed, they provide a source of gas in dispersed locations throughout the mass, leading to more uniform pore structure.

Foamed ceramics usually are of a simple geometry as fired. The fired mass is readily machinable and can be shaped as desired. The size limitation depends upon the foaming technique used but is less severe than in most ceramic forming techniques. Massive blocks have been made.

3. Forming from Fibers

Structures utilizing fibers are made in such a way as to take advantage of the fiber tensile strength. Typically, fibers having a high-elastic modulus are incorporated into a material of low-elastic modulus so that the fibers will absorb most of the tensile stress to which the structure is subjected. Also, there has been some use of fibers alone, so wound as to be self-supporting. By far the greater use, however, is the fiber-containing composite. The fibers may be either continuous-filament or woven. They might be short randomly-oriented fibers, they might be self-bonded to one another as well as to the matrix, or they might be true whiskers, of extremely small cross section and very high strength. Composite types include those made with ceramic fibers in either a metallic or a resin matrix, and those made with metal fibers in a ceramic matrix. More recently there has been attention to the possibility of using ceramic fibers in a ceramic matrix. Where continuous filaments are used, the fiber is wound on a mandrel of the proper type to give the desired shape to the piece and the matrix material is impregnated into the filament windings. Where the fibers are randomly oriented, the matrix material and fiber mixture may be formed by any of the conventional ceramic techniques.

In making a composite containing a fiber it is necessary first of all, of course, to have a fiber of high-tensile strength. If it is not woven into a free-standing structure, the fiber must be combined with a matrix material which will hold it in place and give the compressive strength necessary for the structure. The fiber and matrix material must not react unduly. There is a best amount of bond between the fiber and matrix so that the load can be transmitted throughout the piece. The fiber and matrix must have the correct relationship of thermal expansivities. In the fabrication of composites made with metal fibers and a ceramic matrix and those made with ceramic fibers and a metallic matrix, the problems of reactivity between matrix and fiber in the firing of the structure and the internal stresses of thermal expansion mismatches during the firing treatment are formidable. The same holds true, of course, for a composite made of a ceramic fiber in a ceramic matrix.

In structures made with filament-wound fibers and an impregnated

matrix which requires no elevated heat treatment, the size and geometry limitation is not a critical one. In such a structure there is considerable latitude to form the flexible fibers onto a mandrel of any desired size and shape and then impregnate the woven fiber with matrix material. If a heat treatment of the matrix material is required, then the shrinkage and firing characteristics of the matrix impose size and geometry limitations. The limitations here are the same as for conventional fired ceramics. Similarly, the composites with randomly oriented fibers formed by conventional ceramic techniques have the same size and geometry limitations as conventional ceramics.

4. Bulk Placement and Molding

Ceramics may be formed to advantage by bulk placement or molding when a large or irregular shape is desired, or when the material is to be placed at the site of the utilization. This technique is also often used when it is desired to make a limited number of special shapes. Forms or molds can be made simply and cheaply since mold strength requirements are not stringent. The material may be cast into a mold, rammed, troweled, gunned, or poured like concrete into forms. The materials so formed may have a rigid structure provided by a hydraulic cement such as a high-alumina cement, or a chemical bond such as provided by sulfates, phosphates, chlorides, sulfites and silicates. Typical of these bonded materials are the refractory concretes, castables, and ramming mixes widely used in the heavy refractories industry. The materials might also merely be mechanically compacted to a rigid shape and develop a bonding phase only after heat treatment.

Typically, a mixture formed by this technique, taken in a broad sense, contains the sized aggregate which is the desired residual material or the end product, additives to enhance the formability, water to provide for rheological properties, and, depending upon the type of product, a cementing material.

The water content is critical, not only to the ease of forming or placement, but also to the density and strength of the product. Vibration is finding increasing use for better flow into complex molds, and for higher and more uniform density. Insulating materials of controlled density are also widely employed.

Because the forces applied in this forming process are comparatively low, any characteristics of the mixture being formed which influence the flowability become very important. Critical factors include besides the water content mentioned previously, size, shape, and surface activity of the aggregate grains, and amount and behavior of additives. The setting rate and strength of a cementitious phase is influenced greatly, of course, by the water content and the nature of the additives used.

Close control must be exercised over the rate at which water is removed from a formed piece. Cracking, or even explosion of massive

pieces, particularly in job-placed products, may result if too-rapid water removal is attempted. The heat of hydration of high alumina cements may be large enough to require special provision for water cooling during placement, or large installations may have to be poured in carefully sized, alternate sections to avoid thermal rupture during curing. With these precautions this type of process lends itself to the forming of many sizes and shapes, particularly large ones, not obtainable by other forming techniques.

5. Impregnation

The technique of forming ceramic products by impregnation involves only chemical forces, not the usual mechanical forces of the more common forming processes. Impregnation may be considered a secondary forming process in that it is applied to a skeleton already shaped and sized by another technique. Commonly, impregnation is used to incorporate into a structure other elements or compounds which could not be so placed in the initial fabrication of the structure.

The infiltrant material function may be to fill pores, or to exert a bonding action, or to confer specific properties. In any case, the driving force for the impregnation is the surface free energy of the system. The impregnation is accomplished at temperatures, atmospheres, and pressures (both vacuum and high pressures) dictated by the chemical and physical properties of the impregnant and the skeleton.

Impregnation often is combined with a heat treatment to provide for a reaction between the skeleton and a liquid phase impregnant.

Impregnation techniques have been applied to a considerable extent to the fabrication of high-density graphites and of high-temperature resistant, special refractory ceramics and metals.

Since the driving forces are chemical and the combinations of skeleton and impregnant almost limitless, controls required and size and shape limitations are not well defined. They will be determined by specific situations. In situations where a reaction occurs between the skeleton and impregnant, the extent of the reaction and, if two or more phases are present, thermal expansivity mismatches will strongly influence the quality of the product.

6. Reaction Sintering

In forming ceramics by reaction sintering, a compound is formed of two elements which react exothermically and the heat of this thermite reaction is used to cause the sintering of the mass. The components to be reacted plus a throttling agent (inert material) and a binder are mixed and compacted into the desired shape. The compact may be surrounded by a shrouding material. Heat is applied to bring the

specimen up to ignition temperature. At the ignition temperature, the thermitic reaction proceeds and the heat generated sinters the compact.

To control the rate of the reaction, the throttling and shrouding material moderate the reaction and the furnace temperature is closely controlled. Controlled atmosphere also may be used.

In addition to the forming of solid articles by reaction sintering, attempts have been made to take advantage of the thermitic reaction to sinter a coating on a substrate which could not normally endure the required firing temperature for the coating. To date there has been limited success with such coatings because of adherence problems, but an area of potential usefulness appears to be indicated.

To make sound compacts by the reaction-sintering process, it is essential that all volatiles and chemical water be removed before ignition takes place. If not, disruptive forces and nonuniform temperatures will cause degradation of the compact.

Dimensional stability and control of reaction rates are problem areas. Specimen shapes must be kept simple. Compacts up to one inch in size have been reported.

7. High-Energy-Rate Forming

High-energy-rate forming processes have been developed in recent years and used primarily for forming of metals. Some exploratory work has been done to determine the usefulness of high-energy-rate forming processes for ceramics. Two types of high-energy-rate techniques have been used for the compaction of ceramic powders. In one, direct explosive charges are used, and in the other the compaction takes place in a pneumatic-mechanical press. In the direct explosive technique, the explosive charge is placed immediately around the material to be compacted and the energy dissipated outward is absorbed in a body of water. In the pneumatic-mechanical technique, a rapidly expanding gas propels a ram at high velocity (up to 60 feet per second) to the material to be compacted. Pressures applied have been calculated to be in the range of about 1-1/2 million to 7 million psi. In both the explosive-forming technique and the pneumatic-mechanical technique, the pressures generated are of sufficient magnitude to cause metals to behave plastically and flow. Some evidence of plastic deformation in ceramics has been obtained in exploratory work, but, to date, brittle behavior is the more common characteristic of ceramics exposed to the high-energy-rate forming.

In the explosive forming of ceramics, the amount of pressure and the rate at which the pressure is applied can be varied by controlling the placement, the amount, and the type of explosive charge used around the specimens. In the pneumatic-mechanical equipment, the pressure applied will depend, of course, upon the velocity and mass of the ram

as it strikes the compact.

The response of a ceramic material to a high-energy-rate forming process will depend, of course, on the characteristics of the material. Some of the factors which affect the response are crystal size, crystal orientation to the shock wave, and the crystal structure. Also, of course, the mechanical characteristics of the material affects its response. An insufficient plastic flow of the material will cause it to be fractured. Elevated temperature operations would be expected to improve the response of many ceramics because of the greater likelihood of plastic flow, but little work has been done in this area.

The exploratory work which has been done with ceramics indicates that it is possible to increase the sinterability of ceramics by forming them under a high-energy-rate condition, allowing subsequent use of much lower sintering temperatures. Powder materials have been densified to as high as 95 percent of theoretical in high-energy-rate forming, but in most cases this appears to be a mechanical densification and no significant bond strength develops. In MgO , a coalescence of grains has been observed even though there was not an appreciable strength development. In quite highly densified compacts, there often are macro-cracks, resulting presumably from the stresses caused by the reflection of shock waves after the initial densification. In a few selected ceramics there has been enough strength developed to indicate some promise that specimens could be formed to useable shapes in a high-energy-rate forming process without the subsequent sintering operation. At the present time, however, it appears that this method will be most useful in compacting materials to densities and structures not otherwise obtainable so that they sinter more readily. Some defect structures which would enhance sinterability have been noted.

The work with high-energy-rate forming of ceramics is still in an exploratory stage to the degree that it is difficult to set the size and geometry limitations. In the pneumatic-mechanical system, specimens with a 12-inch plan diameter are the maximum that can be made currently. The thickness limitation of such specimens has not yet been determined. A problem area exists in that spring-back of ceramic materials after the ram has struck and densified the compact will cause the compact to fracture.

In the forming of ceramic specimens using direct explosives, the cross-section is the limiting dimension at the present time. Quite long pieces can conceivably be made, but the difficulty of transmitting the energy through and to the center of a large cross-section piece has not been overcome to date. The cross-section limitation will depend upon the density of the material and its absorbing characteristics. With a very high specific-gravity material of a cross-section greater than two inches, sound compacts are difficult to produce. A lighter material might be formed in a larger cross-section.

When the ceramic work piece being formed has an appreciable mass there is a difficulty in releasing the load applied at a slow enough rate to prevent the specimens from fracturing. In the forming using explosives, the specimens can be contained within a metal can which will restrain them from cracking as the explosive energy dissipates. To date, the geometry has been limited to very simple shapes such as rods, plates, or hollow cylinders.

The uniformity of ceramics obtained from the explosive-compaction operation has not been good due to the variation in stress-wave strength as it progresses through a part. Often, internal fractures will occur at the center of the compact due to the tensile reflection of the shock waves as they meet at the center. In the pneumatic-mechanical process, the uniformity of compacts will depend on the amount of lateral flow which has occurred during the compaction.

8. Electrophoretic Forming

In forming ceramics by electrophoretic deposition it is necessary that the ceramic particles from which an article is to be made acquire an electrical charge. Usually this is accomplished by absorbing an ionic material onto the surface. The particles then are suspended in a low dielectric fluid such as alcohol in a system which provides for a voltage to be impressed across the suspension. Voltages might range from 100 to 1,000 volts. Under the influence of the impressed voltage, the ceramic particles will move and deposit on one electrode. The characteristics of the deposit will depend upon the particle charge carried, the size (usually about 60 microns and finer) and size distribution of the ceramic particles, the particle shape, and the voltage applied. If the particle size distribution is correct a dense layer can be formed. It is common practice to add to the suspension a material to cause the formed layer to have adequate green strength. Materials such as gelatins and polyvinyl alcohol are suitable binders.

If it is desired to use electrophoretic deposition to form a ceramic coating, the electrode can be the substrate and the product can be made by appropriate heat treatment of the coated substrate. If free-standing ceramics are desired the deposited material can be removed from the electrode and fired in a normal operation. The geometry of ceramics formed by this process thus is set by the geometry of the electrode. Ceramic depositions up to 1/2-inch thick appear feasible.

The electrophoretic techniques are well established and the fundamentals understood, but the potential usefulness of this forming method does not appear to have been established.

9. Machining and Grinding

Machining and grinding processes are used to give a final shape,

dimension or surface finish to ceramics which are already shaped and fired. Two types are commonly used. One is the conventional grinding, using abrasives either in the wheel or powder form. Such grinding is used to provide the final form of the surfaces of the ceramic. Abrasive wheels also are used commonly for cut-off work. The other principal type of process for the machining and grinding of ceramics is termed ultrasonic machining, used primarily for holes, slots, and depressions of the ceramic. In general, machining and grinding operations are used to provide dimensional accuracy, complex designs not obtainable before final heat treatment, and control of the surface texture. Usually, machining and grinding are used only when no other forming process will provide these requirements to the degree needed.

In the abrasive grinding of ceramics, well-developed equipment and wheel designs are used. The abrasive used in most cases is either silicon carbide or diamond. Other abrasive grains rarely are used for the moderately hard ceramics. Silicon carbide is usually the choice for grinding all but the very hard ceramics. For the hardest ceramics, diamond abrasive is required. The abrasive must be harder than the work piece, with material removal depending somewhat on the difference in hardness between the abrasive and the work piece. The greater the difference the more rapid the material is removed. The silicon carbide abrasive is used in the loose form in a lapping operation, in a wheel with a vitreous or resin bond, or attached to a cloth or a paper belt. The diamond abrasive usually is bonded with metal on a metal wheel or lap.

A grinding operation generates heat, resulting sometimes in cracking due to thermal shock. For the protection of both the work piece and the abrasive, coolants are used. A considerable variety of coolants are available and most are satisfactory and are chosen primarily on the basis of shop preference.

The removal of ceramic material in a grinding operation is considered to be slow and expensive. Feeds and speeds are selected on the basis of experience and, of course, on the characteristics of the material being ground. Removal of more than 0.015 inch of material per pass is unusual. For good surface finish, removal rates often are limited to less than half of this amount.

The material removal and surface finish is influenced by the porosity, crystal size, and the structure of the ceramics being ground. Porosity, of course, can prevent the obtainment of a good finish. If there is more than one phase present and the phases differ in hardness, the hardness differences will affect the surface finish detrimentally.

The size limitations on surface grinding are not a particular concern if the surface to be ground is an exterior one. Interior surface grinding poses many problems if the length-to-cross-section ratio is great. In such cases, the usual practice is to machine ultrasonically

rather than to use conventional abrasive grinding.

In abrasive grinding operations there is material fracture, chemical reaction between the abrasives and the ceramic work piece, and thermal shock. A better understanding of the phenomena which occur in grinding in all of these areas is required.

Ultrasonic machining is used to shape ceramics where abrasive grinding is not suitable. Basically, the ultrasonic machining technique uses a shaped tool and an abrasive slurry and impresses the tool image into the work. It is feasible to make a cut of any required shape by giving the tool the desired form. The tool is pressed against the work piece with a light pressure and an alternating motion. An abrasive slurry is fed between the tool and the work piece. The machining is accomplished by the chipping caused by the abrasive being hammered against the work piece by the vibrating tool. In such an operation it is essential that the work piece be brittle and the tool be tough and comparatively soft. The liquid containing the abrasive acts as a coolant, carries the wear debris away from the working face, and provides for an efficient transfer of energy from the tool to the abrasive and the work piece. Cavitation of the coolant liquid also is an essential feature of ultrasonic machining. The bubbles formed at the work face by the cavitation stir the abrasive slurry and aids in removing chips of the ceramic being machined and of the worn abrasive.

The tool is given an oscillatory motion by an electrical transducer. Cutting rates are dependent upon the oscillatory amplitude, on the static load imposed on the tool, and on the size and nature of the abrasive particles. Diamond, silicon carbide and boron carbide abrasives are commonly used.

Cutting speeds will vary considerably, of course, because of the complex shapes that are machined by this method.

Since the abrasive grains must pass around the edges of the tool, the machined shape is always oversize relative to the tool. The oversize is a little greater than the dimensions of the abrasive and becomes less as the penetration goes deeper. The accuracy of the dimensions depends, also, of course, on the alignment and the stiffness of the tool. In operations using relatively coarse abrasive (200 mesh) the dimensions can be held to about 0.002 inch. Where greater precision is required and finer abrasive is used, dimensions as close as 0.0005 inch have been obtained.

For most of today's ceramics, ultrasonic machining can be used to produce almost any desired size and external geometry. Long holes are a problem, however, due to tool drift and to difficulties of maintaining the desired flow of abrasive slurry to the working face.

Ultrasonic machining is a relatively new process, and improvements in machine design are continuing.

III. FUNDAMENTALS OF FORMING

In deriving a critical picture of forming, the actions have been to first catalog the variety of methods which are being utilized or advocated. Then a classification has been presented so that the dozens of techniques could be analyzed in logical fashion. An attempt has been made to seek the similarities as well as the differences among the techniques, and establish common threads which weave through the diverse procedures and determine the physical structures realized.

The prospective common threads applying to forming identified so far are listed

- (1) Characterization of the material feed.
- (2) Characterization of the process as a controlled engineering system.
- (3) Rheological response of materials to forming energy.
- (4) Topological aspects of the packing of matter (space filling).
- (5) Bonding and phase interaction.
- (6) Forming stress interpretation.
- (7) Product realization.

(1) Characterization of the material feed to the forming process has been discussed at length in earlier sections. It includes not only the raw materials themselves but also the prepared agglomerate mixture of materials.

(2) The phrase "Characterization of the process as a controlled engineering system" indicates the need for instrumentation which will measure the significant processing variables for each forming technique so that impersonal controls can be established. These should be developed to be as satisfactory for the forming process as temperature measurement and control have become for heat treatment. The factors which need to be detected and controlled will be learned from the science of deformation and flow of matter: rheology.

(3) Rheology evaluates the response of the material to the forming forces. This response has been discussed at some length in the section on cold forming, but is inherent in consideration of any forming technique. In every case the material which is being formed comprises a complex system, usually a three phase assemblage of solid, liquid, and air.

Inadequate understanding and poor control of the rheology of the material being formed can initiate flaws which persist through to the

finished product. This well illustrates the need for repeated communication between the scientist accumulating fundamental understanding of the phenomena and the engineer exploiting the phenomena to make a useful product. For example, although ceramic engineers have utilized an understanding of rheology of suspensions in slip casting with success, there still remains a large body of knowledge in this regard that could be profitably exploited. Rheological properties of dry powders are a fascinating field for research and process development which have scarcely been touched.

(4) Space filling involves the geometrical considerations which govern the packing of matter whether atoms, individual grains from sub-micron to the coarsest screen sizes, or assemblages of particles.

Accompanying forming is a densification by packing of particles or granules. The scientist investigates how this compaction occurs: whether by sliding of particles past each other; by elastic, plastic, or viscous deformation; by fracture of particles; or by diffusion of atoms across phase and grain boundaries.

(5) Always accompanying the geometrical phenomena of packing are the force phenomena which account for the bonding strength in the impressed shape. Here the scientists argue over whether the strength of a cold-formed piece arises solely from mechanical interlocking, or adhesive phenomena, or actual particle to particle welding by a chemical interaction. Hot forming exemplifies the attempt to simultaneously achieve packing and bonding while controlling grain growth.

(6) Forming processes may impose two types of stresses in ceramic shapes. First the thermal, liquid, or pressure gradients that may exist in shapes during forming may create long range stress distributions or body stresses. These stresses may lead to warpage or cracking of the ceramic shape. The effect of these body stresses on the resultant **properties** of the formed shape are difficult to assess because of the relatively few methods available to detect and measure them.

In addition to body stresses, microstresses on and between individual grains may be developed by the difference in physical properties of different phases or the anisotropic character of a single crystalline phase. The ultimate of microstresses effect on the mechanical properties of a ceramic are still open to question even though the techniques for their determination are more advanced than those available for body stress analysis.

(7) "Production realization" encompasses the whole range of technical, economic, and strategic considerations which arise from the fact that the processing of ceramics must result in quality products for which someone is willing to pay. The products must not only be controlled as to structure and properties, meet dimensional and surface finish

specifications, and be free of flaws, but also must be competitive. Availability may be of prime strategic and economic importance.

Realizing all this will always demand considerable skill on the part of the processor, but again a progression of "characterization" of the material in process and of the final product is proposed as an essential requirement.

During the course of this survey it became evident that semantic clarification required a distinction between the terms "structure" and "microstructure." Microstructure has been taken here to mean the qualitative or quantitative description of the relationships between phases present. This is true whether seen with the unaided eye, with a light or electron microscope, or with other analytical tools for extending resolution. Structure is intended to mean the total description including microstructure, chemical and mineral composition, purity, and submicroscopic features relating to imperfections. The attainment of a controlled, reproducible structure is the initial objective of the forming process.

"Characterization" implies not only knowing the structure and selected physical properties at each stage of processing, but knowing also how all these correlate. As we improve our ability to add this knowledge of characterization to engineering judgment, the accomplishment of the goals of processing occurs faster, cheaper, and more effectively.

IV. SUMMARY AND CONCLUSIONS

The state of the art of the forming of ceramics has been surveyed within the limitations imposed by a tight time schedule of only four months. Information was sought both by a search of the literature and by personal interviews through group conferences and individual contacts. The results are presented in individual reports on the topics: (A) characterization of particulate systems, (B) cold forming, (C) hot forming, (D) melt forming, and (E) miscellaneous forming processes, as well as in two bibliographies based on a specially developed classification scheme.

It is evident from the range of the reports and the references that forming, as one step in the total processing sequence, is undergoing a dynamic expansion of attention and competence in research, development, engineering, and manufacturing. Specialized leadership has been contributed by the nuclear fuel industry because of its particular end use requirements and economics. The pioneering of the aerospace industries is also beginning to become apparent, while the more traditional and established portions of the ceramic industry have certainly not been timid about introducing timely innovations and improvements.

Needs for the future appear to include a unifying of the technology by a recognition of the common elements in the diverse forming methods, and a closer interaction between scientists and engineers for the mutual stimulation of both.

It is not feasible to attempt to select the most promising forming methods for making a particular material in a specific shape. The selection must be based on a complex of considerations of end use and service environment, shape, size, design, tolerances, time available, and money available, so that each case must be individually appraised. It is ~~prob-~~
ably true that of the many forming processes here examined, none will ever be wholly discarded or exclusive. Each has a special contribution to offer to solve a specific problem in forming.

V. BIBLIOGRAPHIES

1. Procedures

Concerning the bibliography on "Methods for Forming Ceramics" the following comments can be made on method and completeness. In the time available the intensive search for references has been pretty much limited to the years 1954 through July 1963. The search has been largely based on Ceramic Abstracts and Nuclear Science Abstracts for the sections on forming, and on Chemical Abstracts (1958 through July 1963) for the section on characterization of particulates. Spot checks were made in the abstracts section of Transactions of the British Ceramic Society and OTS Reports (Office of Technical Services, U. S. Department of Commerce). Certain outstanding papers were pursued after being cited as footnote references.

Though the bibliography is necessarily incomplete, it is extensive and representative. As it happens the years covered have witnessed a high level of activity in the field of forming of ceramics, led and dominated by the nuclear field.

The collected and selected references are presented in the bibliography which follows. This bibliography has been gleaned from a more extensive and detailed set of references, complete with abstracts, which are mounted on ASM-SLA Metallurgical Punched Cards. One complete set of these cards has been submitted with this report to the contracting agency. A second set has been retained at the Department of Mineral Technology, University of California, Berkeley. They can form the nucleus of a continuing and more extensive bibliography on the topics treated, and also as the basis for coverage of other topics in Ceramics.

Any reader who misses certain favorite references in the area of his special knowledge is welcome to call attention to them for future expansion of this bibliography.

It would have been desirable to have included a brief, critical description of each of the references cited, in the context in which it has been classified. This has not been feasible in the time available for this initial survey. It is hoped that it can be done in any continuations.

2. Storage and Retrieval of Technical Literature

As the number of references accumulates in a bibliography or any information storage system, it becomes necessary to settle upon some classification scheme. Information storage and retrieval, also called documentation, is at present in a period of rapid growth and change. A variety of coding techniques is being advanced. It is best to agree that there is no one best way, but the system chosen must be individually

determined for the amount and type of information being handled and the needs and personalities of the people being served.

For the purposes of the present bibliography it was determined to base the presentation on the classification and related edge punched cards adopted by the American Society of Metals, called the ASM-SIA Metallurgical Literature Classification, International (Second) Edition as revised in 1958.

The positive reasons for adopting this system were that it had been worked out in detail for the needs of metallurgists. In view of the trend in the government, industry, and universities to a unification of metals, ceramics, and polymers into materials science and materials engineering, it would be interesting to see how few modifications would adapt the classification and card for Ceramics, starting with the limited and specialized field of "Methods for Forming Ceramics."

Though it was recognized that the most recent documentation practice stresses certain shortcomings in both classifications and edge punched cards, these do not enter during the early stages of documenting a new subject when the number of items is less than two or three thousand. As the number of items increases, it is feasible to shift to the so-called "peek-a-boo" type of cards, building on rather than abandoning the established classification and card file. Above twenty to thirty thousand items it first becomes necessary to think in terms of more advanced systems and computers. And even here the work done on the original classification and cards would still have served a useful function.

The classification coding scheme which has evolved is summarized in the following pages.

In organizing the bibliography an attempt was always made to keep it as simple as possible. Though the classification extends to fourth order breakdowns, references were grouped at the highest order which was feasible for the number of references to be scanned. That is, no groupings have been attempted at higher than third orders, and wherever reasonable the breakdown was stopped at second orders.

Inevitably there will be overlaps and repetitions in the use of classification. Various devices have been used to minimize these. Certain references appear under more than one topic, but attempt was made to classify each reference primarily under the topic which appeared to best describe its major and novel features. To a limited extent cross-references have been indicated by repeating references at two or more places in the bibliography. General review articles and books have been classified under general headings, rather than attempting to repeat them under each process mentioned.

Selected References on Documentation

ASM-SLA Metallurgical Literature Classification, International Second Edition

American Society for Metals, Cleveland 3, Ohio (1958) 74p. \$3.00

Workbook for above in loose-leaf \$5.00

ASM-SLA edge-punched cards and accessories may be purchased from:

E-Z Sort Systems--Vaughn Agency

236 North Clark St.

Chicago 1, Illinois

or

E-Z Sort Systems, Ltd.

45 Second St.

San Francisco 5, California

Information and supplies about "peek-a-boo" cards and related accessories in their "Thermatrex" system can be obtained from:

Jonker Business Machines, Inc.

Gaithersburg, Maryland,

or at four regional sales offices.

Among the many papers appearing on the topic of information systems, the following have been found useful:

Eugene Wall

Information Systems

Chemical Engineering Progress 55 (1) 55-9 (1959)

John W. Murdock and G. B. Simpson, Jr. (Battelle)

Practical Information Handling

Industrial Research, April-May 1961

Ralph Cushing

Improving Personal Filing Systems

Chemical Engineering, January 7, 1963, p. 73-88

Attention is called to:

Chemical Engineering Thesaurus

American Institute of Chemical Engineers

345 East 47th St.

New York 17, New York

\$10.00 to non-members

Thesaurus of all engineering terms

Engineers Joint Council

To be published in 1964

National Bureau of Standards

Technical Note 157

Bibliography on Coding Systems

Bart Holm
Coordinate indexing
Engineers Joint Council \$1.00

Literature and training courses available from Battelle Memorial
Institute on information handling

Acknowledgements for discussions in information handling:

Ralph L. Darby, Battelle Memorial Institute

R. S. Sheldon, American Ceramic Society

E. Dugger, Research and Technology Division, U. S. Air Force.

3. Coding Scheme Adopted for These Bibliographies

The detailed classification scheme which has been followed in preparing the two bibliographies included in this report is presented in the following six pages.

Classification Scheme Adopted for Current Purposes

Based on ASM-SLA Metallurgical Literature Classification
International (Second) Edition (1958)

Processes and Properties Schedule supplemented by
Products and Equipment Schedule

First Order Divisions

- A - General
- B - Ores and Raw Materials
Geology and Mineralogy
- C - Batch Preparation
- D - (Iron and Steelmaking) - (tentatively retained)
- E - Melting. Foundry
- * F - Primary Forming
- * G - Secondary Forming and Surface Finishing
Machining and Grinding
- * H - Particle Technology
Powders, Fibers, Filaments, Whiskers,
Sheets and Films
- J - Heat Treatment
Including Sources of Heat, Fuels and
Combustion
- K - Assembling and Joining
- L - Cleaning, Coating and Finishing
- M - Microscopy, Constitution and Primary Structure
- N - Transformations and Resulting Structures
- P - Physics
Physical Properties and Their Measurement
- Q - Mechanical Properties and Tests
- R - Chemistry
Chemical Properties
Corrosion
- S - Inspection and Control
Measurements - Metrology
- U - Allied Fields
- T - Products and Parts
- * W - Plant Equipment
Production Equipment and Layout
Unit Operations
- X - Laboratory and Control Equipment

*Principle categories used in this bibliography

Second Order Divisions

- F - Primary Forming
 - Molding. Compacting. Shaping.
 - Consolidation
 - 1. Cold forming from "dry" powders
 - 2. Cold forming from pastes (plastic masses)
 - 3. Cold forming from suspensions
 - 4. Polymer-assisted forming
 - 5. Chemically-assisted forming
 - 6. X (Forbidden)
 - 7. Forming by combinations of energy forms
 - 8. High energy rate forming
 - 9. Open
 - 10. Forming glasses
 - 11. Fusion casting
 - 12. Hot deposition
 - 13. Open
 - 14. Open
 - 15. Forming specific shapes
 - 16. Forming porous bodies--foaming
 - 17. Forming composites
 - 18. Open
 - 19. Open
 - 20. Theoretical bases of forming
 - 21. Preparations for forming (linked to C-Batch Preparation)
 - 22. Open
 - 23. Hot forming
 - 24. Open
 - 25. Vapor forming
 - 26. Forming from filaments or films
 - Related to F10g
 - 27. Forming from solutions; electroforming
 - 28. Open
 - 29. Forming - general

Third Order Divisions

- F - Primary Forming
 - 1. Cold forming from "dry" powders
 - a. General
 - b. Rigid die pressing
 - c. Flexible die pressing
 - Isostatic, hydrostatic; polymeric die liners
 - d. Pressing in evacuated dies; vacuum-assisted
 - e. Extruding
 - f. Dieless compacting; powder rolling
 - g. Vibratory compacting; jolting
 - h. Impact forming
 - j. Dry process enameling
 - m. Superpressure forming (above 100,000 psi)
 - n. Zero pressure forming; flow forming
 - p. Supplementary energy to pressure (mechanical)
 - r. Rheological controls and behavior
 - Response of material
 - Absorptive die pressing - see F2d
 - Additives - see F21s
 - Design of parts - see F21k
 - 2. Cold forming from pastes (plastic forming)
 - a. General
 - b. Manual
 - c. Pressing
 - d. Pressing - absorptive mold
 - e. Extruding (clay-water type)
 - f. Dropping, impacting
 - g. Turning (jigging, jollying, "flower pot" forming
 - Linked to G2
 - h. Tamping, ramming
 - j. Cements, trowelling
 - k. Cements, gunning
 - m. Silk screening
 - n. Rolling, coiling
 - p. Supplementary energy to mechanical
 - r. Rheological controls and behavior
 - Response of material
 - s. Steam - assisted; warm working
 - (Also see F23k)
 - Additives - see F21s
 - Mechanization, Automation - see W24
 - 3. Cold forming from suspensions
 - a. General
 - b. Slipcasting, gravity and general
 - c. Slipcasting, superimposed motions
 - (vibratory, centrifugal)
 - e. Slipcasting, vacuum or pressure assisted
 - g. Cement casting
 - h. Surface coating from suspensions:
 - porcelain enameling, glazing, etc.
 - j. Application techniques: brushing, spraying, dipping, slush coating, electrostatic spraying
 - p. Supplementary energy to mechanical
 - r. Rheological controls; additives (see also F21s)
 - Response and behavior of material
 - Molds - see F21g
 - Design of molds - see F21j
 - Additives for specific purposes - see F21s
 - 4. Polymer - assisted forming
 - a. General
 - b. Compression molding
 - c. Transfer molding - thermosetting
 - d. Injection molding - thermoplastic
 - e. Extrusion
 - f. Rolling
 - g. Casting (Hot spray, . . .)
 - h. Vibratory-assisted
 - j. Vacuum-assisted or Blown
 - r. Rheological controls and behavior
 - Response of material
 - s. Binder-plasticizer (polymer) selection and content (see also F21s)
 - Additives for specific purposes - see F21s
 - 5. Chemically - assisted forming
 - a. General
 - b. Cement setting
 - g. Reaction sintering; reaction pressing

8. High energy rate forming
 - a. General
 - b. Explosive forming
 - c. Spark discharge
 - d. Ultrasonic impulse
10. Forming Glass

Linked to E-Melting, Foundry

 - a. General
 - b. Pressing
 - c. Blowing
 - d. Combinations of pressing and blowing
 - e. Extruding
 - f. Drawing
 - g. Fiberizing
 - h. Dropping, bending
 - m. Preparations for forming: gathering, feeding, marvering, forming blank or parison (see also F21)
 - n. Casting: free flow, centrifugal, injection
 - p. Rolling
 - r. Rheological controls
 - Dies and Molds - see F21g
 - Porcelain enamel application - see F1j, F3h, F3j
 - Forming specific shapes (marbles, plates, etc.) -- see F15
11. Forming by Melting and solidification of non-glassy ceramics in bulk (Fusion casting).

Linked to E-Melting, Foundry

Also see F10, F12

 - a. General
 - b. Pouring techniques
 - c. Cooling in place
 - d. Molding techniques (see also F21g, h)
 - e. Continuous casting
 - f. Single crystal growing
 - r. Rheology; Response of material
12. Forming by hot deposition - Melting particles individually
 - g. Flame spraying
 - j. Arc spraying
 - k. Plasma arc spraying
 - m. Detonation (explosive propulsion)
 - r. Response of material
 - s. Source of material
15. Forming specific shapes
 - a. General
 - b. Single crystals (see F11f; . . .)
 - c. Cylinders, rings
 - d. Cones, ogives
 - g. Sheets, plates, films
 - j. Laminates, casing
 - k. Spheres, pellets, marbles
 - m. Hollow-ware incl. crucibles, boats
 - n. Rods and bars
 - p. Tubing
 - q. Complex designs
 - Fibers - see F10g
16. Forming porous bodies - foaming
 - a. General
 - b. By underfiring
 - d. Honeycombing
 - g. Light-weight aggregates; bloating
 - n. From powders by gas evolution
 - p. From melts by gas evolution
 - Gas opacified enamels and glasses
17. Forming composites
 - a. General
 - b. Reinforced structures, forming of
 - Impregnation; infiltration
 - see E16d, e
20. Theoretical bases of forming
 - a. General
 - b. Applied mechanics of (see F21j, k)
 - d. Applied rheology (see F21r, F1r, F2r, F3r, F10r, etc.)
 - f. Theory of space filling - compaction
21. Preparations for forming

Linked to C-Batch Preparation

 - a. General
 - b. De-airing
 - c. Granulation
 - d. Coatings on granules
 - f. Feeding
 - g. Dies and molds
 - j. Design of dies and molds
 - k. Reaction of parts
 - r. Adjustment of rheology (see F1r, F2r, F3r, F4r, F23r)
 - s. Additives for specific purposes
23. Hot forming (pressure sintering)
 - a. General
 - b. Forging
 - c. Rolling
 - d. Drawing; i.e. wire drawing
 - e. Extrusion
 - g. Coining or stamping
 - h. Swaging; impact forming (see also F1h)
 - k. "Warm" pressing (see also F2s)
 - m. Zero pressure applied
 - n. Pressing - atmospheric and general
 - p. Pressing - vacuum
 - q. Pressing - isostatic (pressure bonding)
 - r. Response of material; flow; rheology
 - Dies and molds - see F21g
 - Reaction pressing - see F3g
25. Vapor forming (gas plating, vapor plating, vapor deposition)
 - a. General
 - b. Co-deposition
 - g. Physical - general
 - h. Physical - vacuum evaporation
 - j. Physical - very high temperature heating
 - k. Physical - sputtering
 - m. Chemical - general
 - n. Chemical - thermal decomposition (pyrolysis, surface - catalyzed)
 - p. Chemical - hydrolysis
 - q. Chemical - reduction by hydrogen
 - r. Chemical - reduction by carbon
 - s. Chemical - oxidation

Coating of granules - see F21d
26. Forming from films, filaments, or whiskers

Linked to F10g

 - a. General
 - b. Felting
 - c. Weaving
 - d. Filament winding
 - e. Polymer coated, bonded, or impregnated
 - See for forming of initial films, filaments, or whiskers F10g, F11f, etc.
27. Forming from solution; electroforming
 - a. General
 - b. Electrophoretic (cataphoretic)
 - c. Anodization
 - d. Electroplating
29. Forming - general

Second Order Divisions

- G - Secondary Forming and Surface Finishing
 - 1. Secondary Forming (Machining) Operations in general
 - 2. Forming from "green" (unfired) blanks-- general
Linked to P2g
 - 3. Forming from partially fired blanks-- general
 - 4. Forming from fully matured ceramics-- general
- 8. Manual operations
- 15. Chemical forming, surface finishing, and etching
- 16. Mechanical operations--stamping and punching
- 17. Mechanical operations--machining by cutting action
- 18. Mechanical operations--grinding
- 19. Mechanical operations--surface finishing
- 20. Mechanical operations--impact and abrasive blasting
- 21. Mechanical operations--sawing, cutting
- 22. Thermal operations--forming, cutting, surface finishing, etching
- 23. Final forming
- 24. Forming by combinations of energies-- special material removal methods
- 25. Applied mechanics of forming and machining
 - Stress analysis
 - Measurements, Metrology (see S)

Third Order Divisions

G - Secondary Forming

- 15. Chemical processes
 - b. Material removal - "chemical machining"
 - j. Etching
 - k. Polishing

- 16. Mechanical operations - stamping, punching
 - n. Stamping
 - p. Punching
 - q. Coining
 - r. Embossing and Engraving

- 17. Mechanical operations - machining
 - a. Turning
 - b. Milling and hobbing
 - c. Planing and shaping and facing
 - d. Boring and broaching
 - e. Drilling and reaming
 - f. Tapping and threading
 - g. Gear cutting and screw cutting
 - j. Filing
 - k. Machinability
 - Sawing - see G2l
 - Fettling - see G2

- 18. Mechanical operations - Grinding
 - a. General
 - b. Barrel rolling
 - c. Vibratory - assisted (see G24c)
 - g. Cylindrical
 - h. Centerless
 - j. Internal
 - k. Surface
 - n. Form grinding
 - o. Grinding with loose abrasives
 - p. Grinding holes, core bits
 - r. Diamond tooling

- 19. Mechanical operations - surface finishing
 - a. General
 - b. Barrel burnishing; tumbling
 - c. Buffing
 - e. Vibratory - assisted (see G24c)
 - n. Honing
 - p. Lapping
 - q. Superfinishing
 - r. Other
 - s. Polishing with loose fine abrasives

- 20. Mechanical operations - impact, abrasive blasting

- 21. Mechanical operations - sawing, cutting
 - a. Contour
 - b. cut-off
 - c. Wire cutting

- 22. Thermal operations
 - g. Flame processes - reshaping, "lampworking"
 - h. Processes utilizing very high temperature heat sources
 - j. Material removal
 - k. Surface finishing - fire polishing
 - n. Thermal etching
 - o. Cutting
 - p. Drilling holes

- 24. Forming by combinations of energies
 - a. Spark
 - b. Chemical-mechanical (see also G15)
 - c. Ultrasonic, electromechanical
 - d. Electrochemical
 - e. Arc (see also G22h)
 - f. Magnetic impulse

Second Order Divisions

- H - Particle Technology
 - Powders, Fibers, Filaments, Whiskers, Sheets and Films
 - 10. Particle powder preparation
 - 11. Properties of particles
 - 12. Properties of assemblies of particles
 - 13. Mixing and blending
 - Related to C
 - 14. Granulation, agglomeration
 - Related to C, F21c
 - 15. Sintering
 - Related to J
 - 16. Secondary operations on porous bodies
 - 17. Fiber Metallurgy (see also F17)

Third Order Divisions

- H - Particle Technology
 - 10. Particle-powder preparation
 - a. Wet-chemical
 - b. Electrochemical, electrical
 - c. Comminution
 - d. Decomposition and calcination
 - e. Vapor-solid reactions
 - f. Melting and solid state reactions
 - g. Purification
 - 11. Properties of particles
 - a. Size, shape, density
 - b. Surface area, gas inclusions
 - c. Electrical, magnetic, thermal
 - d. Impurity analysis, distribution of pores, crystal structure, defect
 - e. Solid-liquid interface; Solid gas interface
 - g. Reactivity of particle; relation to defects
 - 12. Properties of assemblies of particles
 - a. Size distribution
 - b. Particle packing, packing density, tap density
 - c. Flow, angle of repose
 - d. Rheology of solid-fluid systems
 - f. Permeability
 - 13. Mixing and blending
 - a. Mixing theory
 - b. Dry mixing
 - c. Wet mixing
 - 14. Granulation, agglomeration
 - a. Pelletizing
 - b. Briquetting
 - c. Green strength and compressibility
 - Slip casting; Extrusion (see F1c; F1e; F3e; F4e)
 - 15. Sintering (see J)
 - c. Properties of sintered material; characterizing particles and assemblies of particles
 - 16. Secondary operations on porous bodies
 - d. Impregnation
 - e. Infiltration

Second Order Divisions

- W - Production Plant Equipment and Layout
 - 1. Mechanical assembling equipment
 - 2. Mechanical cleaning and finishing
 - 3. Chemical and electrochemical cleaning and finishing
 - 4. Other cleaning and finishing equipment
- * 10. Plant installations
- 11. Power generation and distribution
- 12. Materials handling equipment
 - Packaging and shipping
- 13. General service and maintenance equipment
- 14. Open
- 15. Ore and raw material preparation
- 16. Fuels
- 17. Calcining furnaces
- 18. Melting furnaces
- 19. Casting equipment
- * 24. Forming and shaping equipment
- * 25. Machine tools
- * 26. Powder processing equipment
- 27. Heat treating furnaces and kilns
- 28. Other heat treating equipment
- 29. Joining and assembling equipment--
 - welding, metalizing, brazing, soldering

*Most pertinent to present bibliography

Third Order Divisions

- W - Plant Equipment
- 24. Forming and Shaping
 - g. Presses
 - m. Shears and saws
 - n. Dies (see also F2lg)
 - p. Mandrels and punches
- 25. Machine tools (see G)
 - a. Cut-off machines
 - b. Jigs and fixtures
 - c. Grinding belts and wheels
 - d. Accessories
 - n. Lathes
 - p. Drills
 - q. Shapers
 - r. Millers
 - s. Grinders

4. Initial Bibliography on
"CHARACTERIZATION OF PARTICLES
AND ASSEMBLIES OF PARTICLES"

Compiled by A. L. Mular and V. A. Mee
for years 1958 to July, 1963

H-PARTICLE TECHNOLOGY

H10. PARTICLE-POWDER PREPARATION

(See also B, C)

H10a. WET-CHEMICAL PREPARATION

(ARRANGED ALPHABETICALLY BY MATERIAL COMPOSITION)

O. B. Wilcox (E. I. du Pont de Nemours & Co.)

Microfibrous Alumina

U. S. 3,039,849 (6/19/62) Appl. 6/5/57

Chem. Abstr. 57 8195

S. I. Kuznetsov, V. A. Derevyankin, and O. K. Shabalina

Recrystallization Process of Hydrargillite to Boehmite

Nauch. Doklady Vysshei Shkoly, Met. No. 4, 87-93 (1958)

Chem. Abstr. 53 17618

M. Burk and A. Marcowska (Akad. Gorn.-Hutnicza, Krakow, Poland)

Preparation of Activated Alumina From Aluminum Nitrate and Sodium Aluminate

Zeszyty Nauk. Akad. Gorn.-Hutniczej Krakowie Ceram. No. 2, 81-90 (1958)

Chem. Abstr. 58 3928

E. Zoccheddu

Acid Extraction of Alumina From Clay

Ital. 599,258 (10/26/59) Appl. 11/28/58

Chem. Abstr. 57 9461

C. Eyraud and P. Lanaspese

Structure and Evolution of Sodium Aluminate Solutions

Compt. rend. 248, 2592-4 (1959)

Chem. Abstr. 54 12

M. C. Gastuche

Investigation of the Alteration of Kaolinite by Different Chemical Agents

Silicates inds. 24, 237-44, 313-20 (1959)

Chem. Abstr. 53 1842

J. Girod and J. Lacroix (E.N.S. Agron., Toulouse, France)

Influence of Acidity on the Movement of Aluminum in a Mixture of Clays

Compt. rend. 250, 4182-3 (1960)

Chem. Abstr. 54 21689

M. C. Gastuche and A. Herbillon (Univ. Louvain, Heverle-Louvain, Belg.)

Alumina Gels: Crystallization in a Deionized Medium

Bull. Soc. Chim. France 1404-12 (1962)

Chem. Abstr. 56 11163

Chem. Abstr. 57 13202

W. Gilbert and W. L. German

Influence of Chemical Treatment on the Properties of Some British Clays

Ziegelindustrie 9, No. 11, 399-403 (1956)

J. Am. Ceram. Soc. 41, No. 2

Ceram. Abstr. 54 (1958)

Chem. Abstr. 54 21689

A. B. Schwartz (Socony Mobil Oil Co., Inc.)

Silica-Alumina Gels

U. S. 2,966,466 (12/27/60)

Chem. Abstr. 55 7705

E. V. Nikitina

Effect of the Methods for Preparing Aluminosilicates on Their Structure

Tr. Groznensk Neft. Inst. No. 24, 27-37 (1960)

Ref. Zh., Khim., Abstr. No. 23M75 (1961)

Chem. Abstr. 57 2903

W. J. Kirkpatrick, G. R. Anderson, and E. S. Funston
(General Electric)

Basic Materials Studies; Sinterable High Purity BeO

Final Report (6/30/61)

Contracts AF33(600)-38062 and AT(11-1)-171

Nucl. Sci. Abstr. 1962 (5) 1351

I. V. Riskin and T. V. Rogova

Preparation and Properties of Cadmium Sulfide and Sulfoselenides. II. Chemistry of the Reaction of Cadmium Salts with Sodium Thiosulfate

Zh. Prikl. Khim. 34, 2195-2202 (1961)

Chem. Abstr. 56 6874; 56 12520

T. Shiraishi, K. Yamanaka, and H. Kwarada (Matsushita Elec.
Ind. Co., Osaka)

Preparation and Some Physical Properties of Cadmium Sulfide
Single Crystal

Natl. Tech. Rept. 7, 269-79 (1961)

Chem. Abstr. 56 15605

V. Karkoska, B. Pomahac, and Z. Cizinsky

Pure Iron Oxides

Czech. 97,547 (12/15/60) Appl. 11/8/58

Chem. Abstr. 57 8196

L. E. Slaten (Intern. Business Machines Research Lab.)

Precipitation of Dispersed Fine-Particle Magnetite

J. Appl. Phys. 31, 74S-75S (1960)

Chem. Abstr. 55 62

A. A. Alent'ev

Dependence of Recrystallization and Activity of Magnesium
Oxide From Brine on Annealing Temperature

Izvest. Kiev Politekh. Inst. 30, No. 2, 91-8

Referat. Zhur., Khim. Abstr. No. 10K267 (1961)

Chem. Abstr. 56 4387

G. Eyber and W. Konig (Didier-Werke Akt.-Ges.)

Sintered Magnesia

Ger. 1,072,540 (12/31/59)

Chem. Abstr. 55 16932

K. Ito and T. Takahashi (Univ. Nagoya)

Preparation of Well-Crystallized Beta-Manganese Dioxide and
Measurement of its Specific Gravity

Kogyo P.aku Zasshi 64, 1375-8 (1961)

Chem. Abstr. 57 2936

J. L. Straughn and W. B. Tarpley

Particle Size Reduction During Ultrasonic Precipitation of
Thorium Oxalate

U. S. At. Energy Comm. NYO-7935 (1959)

Nucl. Sci. Abstr. 13, Abstr. No. 20895 (1959)

Chem. Abstr. 54 19025

- R. G. Sowden and G. N. Stockdale
 Characterization of Precipitates by Filtration and Settling
 Parameters--A Comparison of Ammonium Diuranate and
 Uranium (IV) Oxalate
 At. Energy Research Estab. (Gt. Brit.) R-3767 (1961)
 Chem. Abstr. 55 25388
- J. C. Clayton and S. Aronson (Westinghouse Elec. Corp.)
 Some Preparation Methods and Physical Characteristics of UO_2
 Powders
 U. S. At. Energy Comm. WAPD-178 (1958)
 Chem. Abstr. 50 7642; 53 17743
- W. G. Carlson, H. D. Root, and R. S. Shane
 Pressure-Temperature-Density Relations in Several Samples
 of UO_2
 Am. Ceram. Soc. Bull. 39 (2) 69-73 (1960)
 Ceram. Abstr. 1960 (4) 88
- Comitato Nazionale per l'Energia Nucleare. Divisione Materiali,
 Rome, Italy
 Wet Preparations of UO_2 Powders
 Second Quarterly Report, April-June 1961
 Contract 028-60-10-RDI
 Nucl. Sci. Abstr. 1962 (7) 2342
- A. J. Caputo and J. E. Perry (Union Carbide Nuclear Co.)
 Production, Precision Forming, and Sintering of Ceramic-Grade UO_2
 Contract W-7405-eng-26 (3/16/61)
 Nucl. Sci. Abstr. 1961 (7) 2384
- J. M. Googin (U. S. Atomic Energy Commission)
 Preparation of UO_2 for Nuclear Reactor Fuel Pellets
 U. S. Patent 3,037,839 (6/5/62)
 Nucl. Sci. Abstr. 1962 (8) 2514
- K. H. Puechl (Nuclear Materials and Equipment Corp.)
 Development of Plutonium-Bearing Fuel Materials
 Monthly Progress Letter for Month of January 1962 (2/5/62)
 Contract AT(30-1)-2389
 Nucl. Sci. Abstr. 1962 (5) 1356

D. E. Ferguson, E. D. Arnold, W. S. Ernst, Jr., and O. C. Dean
(Oak Ridge National Lab.)

Preparation and Fabrication of ThO_2 Fuels

Contract W-7405-eng-26 (6/19/62)

Nucl. Sci. Abstr. 1962 (8) 2729

R. Prasad and A. K. Dey (Univ. Allahabad, India)

Electrometric Studies of the Precipitation of Thorium

Hydroxide. I. Changes in pH of Thorium Chloride Solution
by the Progressive Addition of Sodium Hydroxide

Kolloid-Z. 184, No. 1, 54-6 (1962)

Chem. Abstr. 57 13204

D. E. Ferguson, O. C. Dean, and P. A. Haas (Oak Ridge
National Lab.)

Preparation of Oxide Fuels for Vibratory Compaction by the
Sol-Gel Process

CEND-153, 1, 23-38

Nucl. Sci. Abstr. 1963 (4) 1449

T. Hibino, Y. Wakao, S. Naka, H. Matsumoto, and C. Noguchi
(Govt. Ind. Research Inst., Nagoya)

Oxide Materials for Cermets. I. Effects of Drying Methods on
Particle Size of Zirconium Hydroxide

Nagoya Kogyo Gijutsu Shikensho Hokoku 2, 510-14 (1956)

Chem. Abstr. 54 20743

H10b. ELECTROCHEMICAL, ELECTRICAL PREPARATION

U. S. At. Energy Comm.
Electrostatic Precipitation of Submicron Alumina Particles
IDO-14522, 1-18 (1960)
Chem. Abstr. 55 13962

R. E. Snow (International Minerals & Chemical Corp.)
Electrostatic Separation of Feldspars
U. S. 2,961,092 (11/22/60)
Chem. Abstr. 55 22739

H10c. PREPARATION BY COMMINUTION

A. M. Ginstling

The Effect of Grain Size and Uniformity of a Solid Mixture on
Chemical Reactions

Sbornik Nauch. Rabot Khim. i. Tekhnol. Silikatov, 274-82 (1956)
Chem. Abstr. 55 13944

C. E. Berry and H. J. Kamack (E. I. du Pont de Nemours & Co., Inc.)

Surface Activity in Fine Dry Grinding

Proc. Intern. Congr. Surface Activity, 2nd, London 4, 196-202 (1957)
Chem. Abstr. 55 22946

J. Janowski (Acad. Gorniczo-Hutnicza, Krakow, Poland)

Grinding of Wet Blast Furnace Slag

Cement-Wapno-Gips 14 (23), 162-70 (1958)

Chem. Abstr. 52 15870; 53 4689

R. Kubicki

Grindability of Raw Materials and Products of the Cement Industry

Cement Wapno-Gips 14 (23), 180-7 (1958)

Chem. Abstr. 53 4689

E. D. Shchukin and P. A. Rebinder (Inst. Phys. Chem. Acad. Sci.
U.S.S.R., Moscow)

Formation of New Surfaces During the Deformation and Rupture of a
Solid in a Surface-Active Medium

Kolloid. Zhur. 20, 645-54 (1958)

Chem. Abstr. 53 1883

Z. A. Livson

Optimal Conditions for Preparing Raw Materials During the Firing
of Refractories in Rotary Kilns

Trudy Khar'kov. Politekh. Inst. 17, 225-32 (1958)

Referat. Zhur., Khim. Abstr. No. 32077 (1959)

Chem. Abstr. 54 18921

N. A. Bessonov

The Relation Between Work, Heat, and Energy Absorbed During
Abrasive Wear of Rock Salt Crystals

Belorus. Politekh. Inst. im. V. I. Stalina, Sbornik Nauch. Trudov
No. 60, 116-24 (1958)

Chem. Abstr. 56 9441

R. L. Brown

Calculation of Closed-Circuit Grinding.

Brit. Chem. Eng. 4, 463-6 (1959)

Chem. Abstr. 54 974

E. Rettig
Very Fine Pulverization of Magnetite
Ger. (East) 16,375 (2/9/59)
Chem. Abstr. 54 18834

Y. Oyama and Y. Sawahata (Inst. Phys. Chem. Research, Komagome,
Tokyo)

Powder for Industrial Testing (Trial manufacture and size
distribution)

Rikagaku Kenkyusho Hokoku 36, 104-13 (1960)

Chem. Abstr. 55 15853

M. T. Trambouze and B. Imelik (Sorbonne, Paris)

Influence of the Heterogeneity of Particle Size on the Comminution
of Solids

J. Chim. Phys. 57, 656-65 (1960)

Chem. Abstr. 58 13463

N. I. Gel'perin and L. M. Polotskn

Fine Grinding of Solids in a Vibrating Ball Mill

Khim. Mashinostroenie No. 1, 28-33 (1960)

Chem. Abstr. 54 21873

M. T. Arrambide and P. J. F. Lezy

Grinding Granular Slag From Blast Furnaces Before Use in the
Preparation of Hydraulic Concretes

Fr. 1,257,694 Appl. 2/22/60

Chem. Abstr. 56 9724

L. Dintenfass

Microrheology of Pigment Dispersion by Ball Milling in Non-Aqueous
Media

Kolloid-Z., 170-(1) 1-19 (1960)

Ceram. Abstr. 1960 (9) 215

G. S. Khodakov and P. A. Rebinder

Mechanism of Quartz Comminution in Surfactive Media

Kolloid. Zhur. 23, 482-90 (1961)

Chem. Abstr. 57 2016

N. A. Brunt (Centraal Lab. T.N.O., Delft, Neth.)
The Dispersion of Pigments I.
Verfkroniek 34, 474-9 (1961)
Chem. Abstr. 56 11743

P. P. Budnikov and M. Nekrich
Work of Disintegration in Powder Technology
Silikat Tech. 12, 452-7 (1961)
Chem. Abstr. 51 17262; 56 9733

W. J. Kenny and E. L. Piret (Univ. of Minnesota)
Slow Compression Crushing of Single Particles of Glass
A. I. Ch. E. Journal 7, 199-202 (1961)
Chem. Abstr. 56 4380

Mallinckrodt Chemical Works, Nuclear Div., Hematite, Mo.
Characterization of UO₂ Powders
Sixth Monthly Progress Report for March 1961
Contract AT(40-1)-2699
Nucl. Sci. Abstr. 1961 (10) 3250

D. W. Fuerstenau and D. A. Sullivan, Jr. (Univ. of California)
Comminution of Mixtures in Ball Mills
Trans. AIME 223, 152-7 (1962)
Chem. Abstr. 56 12213

F. J. P. Clarke, R. A. J. Sambell, and H. G. Tattersall
(At. Energy Res. Estab., Harwell, Engl.)
Mechanisms of Microcrack Growth in Magnesium Oxide Crystals
Phil Mag. 7, 393-413 (1962)
Chem. Abstr. 56 15006

G. I. Aleksandrova, V. F. Kiselev, and M. P. Maiorova (State Univ., Moscow)
Change of the Silica Gel Structure on its Comminution
Kolloidn. Zh. 24, No. 1, 3-7 (1962)
Chem. Abstr. 57 87

Y. Nishimura, R. Naito, R. Yamamoto, and S. Kato (Govt. Ind.
Res. Inst., Nagoya, Japan)
Effects of the Particle Size of Raw Materials in Procelain
Manufacturing. VI. Effect of Comminution of Feldspar
and Quartz on the Behaviors of Porcelain Bodies During
Firing.
Nagoya Kogyo Gijutsu Shikensho Hokoku 11, 713-25 (1962)
Chem. Abstr. 58 12273; 58 13578

C. Moss (United Kingdom Atomic Energy Authority)
Improvements in or Relating to Densification and Granulation
of Uranium Dioxide
British Patent 910,700 (11/14/62)
Nucl. Sci. Abstr. 1963 (2) 640

J. F. Carpenter (United Nuclear Corp. Chemicals Div.)
Characterization of UO₂ Powders
Monthly Progress Report, December 1961-January 1962
Contract AT(40-1)-2699 (2/28/62)
Nucl. Sci. Abstr. 1962 (11) 4043

K. H. Puechl (Nuclear Materials and Equipment Corp.)
Development of Plutonium-Bearing Fuel Materials
Monthly Progress Letter for Month of April 1962
Contract AT(30-1)-2389 (5/18/62)
Nucl. Sci. Abstr. 1962 (10) 3606

H10d. PREPARATION BY DECOMPOSITION BY HEAT, CALCINATION
(ARRANGED ALPHABETICALLY BY COMPOSITION)

H. Bremer and G. Henrion (Humboldt-Univ., Berlin)
Stepwise Isothermal Dehydration of Pure and Simultaneously
Precipitated Gels of Chromium and Aluminum Hydroxides
Chem. Tech. (Berlin) 11, 555-6 (1959)
Chem. Abstr. 54 21938

A. J. Hegedues and J. Kuerthy (Forschungsinst. Nachrichtentech.
Ind., Budapest, Hung.)
Some Aluminum Oxides of the Following Kinds. I. An Amorphous,
Globular Aluminum Oxide. II. A Black, Semi-Conducting
Aluminum Oxide. III. A High-Purity Aluminum Oxide
J. Prakt. Chem. 14, 113-18 (1961)
Chem. Abstr. 56 6898

P. Tardieu and R. Perieres (Pechiney-Compagnie de Produits
Chimiques et Electrometallurgiques)
Alumina Manufacture in Low-Stack Blast Furnace
U.S. 3,009,778 (11/21/61) Fr. Appl. 7/31/56
Chem. Abstr. 57 12106

Rutgers Univ., School of Ceramics
Development of Refractory Ceramics That Can be Processed at
Temperatures Considerably Lower Than Their Maximum Use
Temperature
Final Report, December 1, 1960-April 1, 1962
Contract No. 61-0211-C (N62-12088)
Nucl. Sci. Abstr. 1963 (4) 1642

B. S. Lee, J. C. Chu, A. A. Jonke, and S. Lawroski (Polytechnic
Inst. of Brooklyn)
Kinetics of Particle Growth in a Fluidized Calciner
A. I. Ch. E. J. 8, 53-8 (1962)
Chem. Abstr. 56 14009

J. L. Evans and J. White (Univ. Sheffield, Engl.)
The Thermal Decomposition (Dehydroxylation) of Clays
Kinet. High-Temp. Processes, Conf. Dedham, Mass., 301-8 (1958)
(Pub. 1959)
Chem. Abstr. 54 12521

A. L. Ruiz
Effect of Calcination Temperature on Heat of Solution of Clays
ASTM Bull. No. 233, 51 (1958)
Chem. Abstr. 53 5626

A. V. Shlykov

The Kinetics of the Dehydration of Clays at 600-900 Degrees
Sbornik Trudov, Resp. Nauch.-Issledovatel. Inst. Mestnykh
Stroitel. Materialov No. 18, 112-52 (1960)

U.S.S.R. 128,633

Chem. Abstr. 56 11251

T. Jacobs and M. de Fre.

Kinetic Studies of the Dehydroxylation of Montmorillonite by
Thermogravimetric Analysis.

Silicates Inds. 26, 363-5 (1961)

Chem. Abstr. 53 5841; 56 11249

R. Caillat, R. Pointud, E. Pruvot, and P. Baradez

(Commissariat a l'Energie Atomique)

Process for Obtaining Fritted Beryllium Oxide

Swiss Patent 348,397 (8/31/60)

Nucl. Sci. Abstr. 1962 (12) 4221

I. J. Holland (United Kingdom Atomic Energy Authority)

Improvements in or Relating to Suspensions of Beryllia

British Patent 914,895 (1/9/63) Filed 9/9/60

Nucl. Sci. Abstr. 1963 (3) 1136

D. T. Livey, N. Brett, I. Denton, and P. Murray (Atomic Energy
Research Establishment, Harwell, Berks, Eng.)

Factors Affecting the Density of Sintered and Hot Pressed Beryllia

Progr. in Nuclear Energy, Ser. IV, 3: 111-34 (1960)

Nucl. Sci. Abstr. 1962 (5) 1631

P. P. Budnikov and A. A. Zvyagil'skii.

Sintering of Beryllium Oxide

Ogneupory, 26: No. 11, 525-30 (1961)

Nucl. Sci. Abstr. 1962 (5) 1350

R. C. Bau (Gen. Elec. Co.)

X-Ray Diffraction Investigation of BeO Calcination Processes

Advan. X-Ray Anal. 4, 19-39 (1961)

Chem. Abstr. 57 2948

P. Murray and D. T. Livey (United Kingdom Atomic Energy Authority)
Production on Sintered Compacts of Beryllia
U. S. Patent 3,025,137 (3/13/62)
Nucl. Sci. Abstr. 1962 (7) 2344

T. Takada (Kyoto Univ.)
Effect of Calcining Conditions of Iron and Chromium Salts on the
Particle Size of Their Products
Funtai oyobi Funmatsuyakin 4, 139-48 (1958)
Chem. Abstr. 53 2725

W. Lahl
The Burning Behavior of Various Dolomites
Tonind.-Ztg. 83, 461-5 (1959)
Chem. Abstr. 57 3084

A. Braniski
Reactions Between Marine Magnesia and Chromite During the
Process of Heating
Acad. Rep. Populare Romine, Studii Cercetari Met. 7, 233-56 (1962)
Chem. Abstr. 57 12098

H. Hashimoto and T. Nagato (Univ. Chiba)
Particle Size of Magnesia Prepared by the Thermal Decomposition
of Magnesite
Kogyo Kagaku Zasshi 62, 1478-81 (1959)
Chem. Abstr. 57 14706

C. Hyde and W. H. Duckworth (Battelle Memorial Inst.)
Investigation of Sinterable Oxide Powders and Ceramics Made From
Them
Contract AF33(616)-6238
Nucl. Sci. Abstr. 1962 (2) 426

R. Valverde and J. P. Saenz (Facultad Quim Montevideo, Uruguay)
Production of Active Magnesium Oxide by Heating in Vacuum
Nature 192, 653-4 (1961)
Chem. Abstr. 56 4364

R. I. Razouk and R. Sh. Mikhail (Ain Shams Univ., Cairo)

Surface Properties of Magnesium Oxide II.

J. Phys. Chem. 63, 1050-3 (1959)

Chem. Abstr. 51 17307; 54 1049

Al. Braniski, A. Kathrein, C. H. Lonescu, and S. Fruchter

The Changes and Reactions of Magnesium Hydroxide From Sea Water in
the Presence of a Mineral Flux During Calcination and Sintering

Acad. Rep. Populare Romine, Studii Cercetari Met. 6, 315-39 (1961)

Chem. Abstr. 56 9726

A. V. Bondarenko, V. F. Kiselev, and K. G. Krasil'nikov

Thermal Dehydration of Silica and Certain Properties of its Surface

Dokl. Akad. Nauk SSSR 136, 1133-6 (1961)

Chem. Abstr. 56 14957

K. H. McCorkle, A.T. Kleinstaubert, C. E. Schilling, and O. C. Dean

(U.S. Atomic Energy Commission)

High-Density Compactible Thorium Oxide Particles

U. S. 3,035,895 (5/22/62) Appl. 11/25/60

Chem. Abstr. 57 9322

R. C. Asher and S. J. Gregg (Wash. Singer Labs., Exeter, Engl.)

Production of Active Solids by Thermal Decomposition XII. The

Calcination of Hydrous Titania

J. Chem. Soc. 5057-62 (1960)

Chem. Abstr. 54 13809; 55 12787

B. N. Melent'ev

Conditions for the Production of Titanium Dioxide

Izvest. Akad. Nauk SSSR, Otdel. Tekh. Nauk, Met. i Toplivo, No. 4

69-70 (1960)

Chem. Abstr. 55 11163

P. Chenebault (Compagnie Generale de Telegraphie sans Fil, Paris)

Preparation of UO_2 in Powder Room

Appendix 1 of Sintered Uranium Oxide: Sintering Technique and
Behavior Under Irradiation

Quarterly Report No. 2, First Quarter 1961, 6-17

EURAE-57 (App. 1)

Nucl. Sci. Abstr. 1962 (9) 3179

R. Delmas (Centre d'Etudes Nucleaires, Grenoble, France)
New Developments Concerning Uranium Oxides
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee Ag., 63-71 (1962)
Nucl. Sci. Abstr. 1963 (1) 256

R. Caillat, M. Delange, R. Hauser, and J. Sauteron (France.
Commissariat a l'Energie Atomique. Centre d'Etudes Nucleaires,
Saclay)
The Creation of a Uranium Oxide Industry, from the Laboratory
Stage to a Pilot Plant
CEA-1670 (1961)
Nucl. Sci. Abstr. 1961 (9) 2880

Y. S. L'urie
On Methods of Production of Portland Clinker
Cement-Wapno-Gips 14 (23) 197-201 (1958)
Chem. Abstr. 53 4689

A. E. Sheikin
The Composition and Structure of Portland Cement Clinker
Tr. Mosk. Inst. Inzh. Zheleznodor. Transp No. 140, 142-68 (1962)
Chem. Abstr. 57 12107

H. Hashimoto (Chiba Univ., Matsudo)
Rate of Thermal Decomposition of Polycrystalline Solids
Nippon Kagaku Zasshi 82, 1605-11 (1961)
Chem. Abstr. 57 109

H10e. PREPARATION OF PARTICLES BY VAPOR-SOLID REACTIONS

- I. B. Mizetskaya, N. I. Vitrikhovskii, and V. D. Fursenko
Effect of Growing Conditions of CdS and CdSe Single Crystals on
Their Physical Properties
Voprosy Met. i Fiz. Poluprovod., Akad. Nauk SSSR, Trudy 3-go
(Tret'ego) Soveshchaniya, Moscow 107-11 (1957) Pub. 1959
Chem. Abstr. 56 78
- K. Homma, S. Koshi, and H. Sakabe
Preparation of Submicron Particles
Bull. Natl. Inst. Ind. Health (Kawasaki, Japan) 2, 57-62 (1959)
Chem. Abstr. 54 20352
- S. W. Bradstreet and J. S. Griffith (Armour Research Foundation
of Illinois Institute of Technology)
Fine Particle-Size Metal Oxides
U. S. 2,900,244 (8/18/59)
Chem. Abstr. 54 854
- J. A. Hedvall (Tech. Univ., Goteborg, Swed.)
Effect of Nonreacting Gases on Technical Processes and on Formation
of Minerals
Planseeber. Pulvermet. 9 4-10 (1961)
Chem. Abstr. 56 6898
- C. R. Morelock (Gen. Elec. Research Lab.)
Sub-Micron Whiskers by Vapor Deposition
Acta Met. 10, 161-7 (1962)
Chem. Abstr. 56 15003
- S. A. Amirova, V. V. Pechkovskii, and A. N. Ketov
Thermodynamics of the Reduction of Barium, Calcium, Magnesium, Zinc,
Manganese, and Iron Sulfates by Hydrogen
Sb. Nauchn. Tr. Permsk. Politekh. Inst. No. 10, 33-51 (1961)
Chem. Abstr. 58 980
- K. Th. Wilke (Deut. Akad. Wiss., Berlin)
Preparation of Refractory Crystalline Compounds by the Vapor
Deposition Process
Z. Physik. Chem. (Leipzig) 220, 137-43 (1962)
Chem. Abstr. 57 8210

H10f. PREPARATION OF PARTICLES BY MELTING AND SOLID STATE REACTIONS

- J. Stocker and R. Collongues
Preparation of Ultrarefractory Compounds with Zirconium Base by
Different Methods
Congr. intern. chim. pure et appl., 16e Paris (1957)
Mem. sect. chim. minerale, 647-54 (Pub. 1958)
Chem. Abstr. 54 18921
- F. S. Ham (Gen Elec. Research Lab.)
Diffusion-Limited Growth of Precipitate Particles
J. Appl. Phys. 30, 1518-25 (1959)
Chem. Abstr. 53 7707; 54 1026
- H. W. Newkirk (Gen. Elec. Co., Hanford Atomic Products Operation)
Induction Melting of Uranium Dioxide Powder
HW-59740 (3/23/59)
Nucl. Sci. Abstr. 1961 (4) 1199
- H. Matsuo (Nippon Telegraph & Telephone Public Corp., Tokyo)
Crystallinity Studies of Polychlorotrifluoroethylene by the
Infrared Method. II. Kinetics of the Crystallization
Bull. Chem. Soc. Japan 32, 1184-8 (1959)
Chem. Abstr. 52 6881; 54 21914
- G. R. Rigby
Reactions in the Solid State and their Application to Refractory
Materials
Trans. Intern. Ceram. Congr. 7th London, Engl., 153-61 (1960)
(Pub. 1961)
Chem. Abstr. 56 8321
- G. M. Schwab and R. V. Ammon (Univ. Munich, Ger.)
Changes in the Surface During Solid-State Reactions
Z. Metallk. 52, 583-7 (1961)
Chem. Abstr. 56 9677
- V. Prochazka and E. Navara
Preparation of Metal Powders by Atomization in a Granulating
Apparatus
Sbornik Ved. Prac Vysokcj Skoly Tech. v Kosiciach 5, No. 1, 169-84
(1961)
Chem. Abstr. 56 11325
- M. M. Pavlyuchenko and M. P. Gilevich
Chemical Exchange Reactions in Solid Phases and the Contact
Between the Reacting Particles of Solids
Doklady Akad. Nauk SSSR 139, 648-50 (1961)
Chem. Abstr. 56 10963

- G. P. Popov and G. I. Chufarov
Activities, Heats, and Entropies of Mixing in $\text{NiFe}_2\text{O}_4\text{-Fe}_3\text{O}_4$
Solid Solutions
Dokl. Akad. Nauk SSSR 141, 877-9 (1961)
Chem. Abstr. 57 2934
- B. Locsei (Central Research Inst., Budapest)
The Effect of Mineralizers and of Composition on the Crystallization
of Fused Silicates
Acta Chim. Acad. Sci. Hung. 22, 1-25 (1960)
Chem. Abstr. 54 23235
- L. O. Meleshko (Inst. Building Architecture, Minsk)
Determination of the Relation Between Temperature and Crystallization
Parameters of a Substance
Inzhener.-Fiz. Zhur., Akad. Nauk Belorus. SSR 3, No. 9, 114-16 (1960)
Chem. Abstr. 55 25414
- J. Vandemaele
Effect of the Manufacturing Process on Characteristics and Properties
of Zinc Oxide
Rev. Gen. Caoutchouc 37, 1666-70 (1960)
Chem. Abstr. 57 12098
- S. R. Yoganarasimhan (Indian Inst. Sci., Bangalore)
Studies on the Brookite-Rutile Formation
J. Sci. Ind. Res. (India) 21B, No. 2, 88-9 (1962)
Chem. Abstr. 57 2941

H10g. PURIFICATION OF PARTICLES

H11. PROPERTIES OF INDIVIDUAL PARTICLES

H11a. SIZE, SHAPE, DENSITY (See also H12a)

R. J. Bard, O. E. Fry, and R. W. Kewish (Los Alamos Sci. Lab.)
Specific Surface and Bulk Density of U_2O_8 and UO_2 as Factors in UF_4
Production on the 250-Gram Uranium Scale
U. S. At. Energy Comm. LA-1854 (1954)
Chem. Abstr. 57 6874

M. J. Root
Measuring Particle Size
Aerosol Age 2, No. 8, 21, 60 (1957)
Chem. Abstr. 53 3789

V. Vecerikova, F. Bares, and Vl. Charvat
Determination of Particle Sizes of Less than 0.06 mm.
II. Sedimentation Methods
Sbirka Praci Vyzkumn. Ustavu AS, No. 17-26, 87-109 (1957)
Chem. Abstr. 55 9986

G. Kortum (Tubingen)
Light Absorption by Solids
Spectrochim. Acta, Suppl. 534-41 (1957)
Chem. Abstr. 54 8280

E. V. Donat
Determination of Particle Size with Gravimetric Separators
(Elutriators)
Prom. Ventilyatsiya, Vsesoyuz. Nauch.-Issledovatel. Inst. Okhrany
Truda, Sbornik Statei No. 6, 67-77 (1957)
Chem. Abstr. 55 25389

D. Delic, M. Tecilazic-Stevanovic, and N. Petrovic (Tehnot. fak.,
Belgrade, Yugoslavia)
Granulometric Composition of Clays
Glasnik Khim. Drustva, Beograd 22, 245-51 (1957)
Chem. Abstr. 54 3899

J. Jaray
Determination of the Particle Size Distribution of Sedimentary Rocks
with the Hydrometer Method
Banyaszati Kutato Intezet Kozlemenyei 2, 54-65 (1957)
Chem. Abstr. 53 6700

N. Mori
The Method of Measuring Particle Size by the Higher-Order Tyndall
Spectra
Oyo Butsuri 27, 564-9 (1958)
Chem. Abstr. 53 5819

- G. D. Joglekar and B. R. Marathe (Natl. Phys. Lab., New Delhi)
 Nomographs for Particle-Size Analysis by Sedimentation and
 Permeability Methods
 J. Sci. Ind. Research (India) 17B, 232-5 (1958)
 Chem. Abstr. 53 1891
- R. J. Fries (Mellon Inst.)
 The Determination of Particle Size by Adsorption Methods
 Am. Soc. Testing Materials Spec. Tech. Publ. 234, 259-78 (1958)
 Chem. Abstr. 54 36
- W. A. Buck (Marconi Instruments, Ltd.)
 Application of Flying-Spot Microscopy to the Counting and Sizing of
 Small Particles
 U.S. At. Energy Comm. TID-7568 (Pt. 3), 89-97 (1958)
 Chem. Abstr. 53 17632
- N. Kasai, M. Kakudo, and T. Watake (Univ. Osaka)
 Study of the Structure of Finely Divided Solids by X-Ray Small-Angle
 Scattering--Particle-Size Determination of Silica Gel
 Technol. Repts. Osaka Univ. 8, 443-53 (1958)
 Chem. Abstr. 53 17624
- I. A. Vainshenker
 Study of Highly Dispersed Particles by Means of an Electron
 Microscope
 Obogashchenie Rud 3, No. 2, 35-6 (1958)
 Chem. Abstr. 56 943
- T. Takada (Kyoto Univ.)
 Effect of Particle Size and Shape on the Color of Ferric Oxide
 Powders
 Funtai oyobi--Funmatsuyakin 4, 160-8 (1958)
 Chem. Abstr. 53 2725
- U. Muller (Deut. Akad. Wiss., Berlin-Adlershof)
 Improved Adjustable-Height Pipet for the Measurement of Particle
 Size
 Chem. Tech. (Berlin) 10, 663-4 (1958)
 Chem. Abstr. 53 9733

- P. Connor, W. H. Hardwick, and B. J. Laundry
Determination of Particle Size by Beta-Back-Scattering
J. Appl. Chem. (London) 9, 525-31 (1959)
Chem. Abstr. 54 2881
- K. E. Francis and R. G. Sowden (At. Energy Research Estab., Harwell, Engl.)
The Microstructure of Plutonium Dioxide Prepared by Various Methods
At. Energy Research Estab. R2939 (1959)
Chem. Abstr. 54 1974
- L. Feret
Comparative Tests of the Determination of Specific Gravity and Blaine Specific Surface
Rev. Materiaux construct. et trav. publ. C, No. 529, 221-30 (1959)
Chem. Abstr. 54 3907
- G. Simmons (Harvard Univ.)
Photoextinction Method for the Measurement of Silt-Sized Particles
J. Sediment. Petrol. 29, 233-45 (1959)
Chem. Abstr. 54 976
- M. W. Hong (Seoul Natl. Univ., Korea)
Rapid Method for the Determination of Particle Size of the Pharmaceutical Powder
Seoul Univ. J. 8, 325-34 (1959)
Chem. Abstr. 54 2666
- E. Loos (Staub- und Silikosebekampfungsstelle Steinkohlenbergbauvereins, Essen, Ger.)
The Sedimentation Balance
Staub 19, 392-8 (1959)
Chem. Abstr. 55 25381
- A. K. Gupta
Particle Size Analysis by Sedimentation in a Long-Arm Centrifuge
J. Appl. Chem. 9, 487-9 (1959)
Chem. Abstr. 54 1941
- M. Ehrenreich (Israel Inst. Technol., Haifa) and A. R. Steinherz
The Direct Measurement of Particle Shape
Chem. and Ind. (London) 1418 (1959)
Chem. Abstr. 54 6255
- G. V. Vosseller (Nikok Chems., Inc.)
Charts Help You Estimate Particle Properties
Chem. Eng. 66, No. 14, 149-50 (1959)
Chem. Abstr. 53 19470

A. Peterlin and M. Ribaric (J. Stefan Inst., Ljubljana, Yugoslavia)
Dynamic Theory of Electrosedimentation
J. Chem. Phys. 31, 759-67 (1959)
Chem. Abstr. 54 4107

S. Okuda and I. Uei (Kyoto Kogei Seni Daigaku)
Particle-Size Determination of Fine Powders by the Heat-of-
Immersion Method
Yogyo Kyokai Shi 67, 321-5 (1959)
Chem. Abstr. 55 62

M. R. Harris and K. S. W. Sing (Roy. Tech. Coll., Salford, Engl.)
Adsorption of Nitrogen on Nonporous Silicas
Chem. & Ind. (London) 487-8 (1959)
Chem. Abstr. 53 19514

L. L. Lyon, G. R. Crocker, and J. S. Dahler (Univ. of Wichita)
Physical Adsorption and the Surface Areas of Carbon Blacks
Proc. Conf. Carbon, Buffalo 4th, 71-7 (1959) (pub. 1960)
Chem. Abstr. 55 14011

F. Hofmann
Determination of Specific Surface Area, Grain Shape, and Grain
Structure of Foundry Sand
Giesserei 47, 49-56 (1960)
Chem. Abstr. 54 14046

N. Kasai
Study on the Structure of Finely Divided Solids by X-Ray Small-Angle
Scattering. II. Particle-Size Determination of Carbon Black
Technol. Repts. Osaka Univ. 10, 833-7 (1960)
Chem. Abstr. 52 6799; 55 14007

Gj. Dezelic and J. P. Kratochvil (Univ. Zagreb, Yugoslavia)
Determination of Size of Small Particles by Light Scattering.
Experiments on Ludox Colloidal Silica
Kolloid-Z. 173, 38-48 (1960)
Chem. Abstr. 55 6103

B. E. Warren (Massachusetts Inst. of Technol.)
X-Ray Measurement of Grain Size
J. Appl. Phys. 31, 2237-9 (1960)
Chem. Abstr. 55 11992

- P. Connor and W. H. Hardwick (At. Energy Research Estab., Harwell, Engl.)
 Use of Radioactivity in Particle-Size Determination
 Ind. Chemist 36, 427-33 (1960)
 Chem. Abstr. 55 62
- H. H. Hausner and R. King (Sylvania Corning Nuclear Corp.)
 Effect of Powder Particle Size on the Grain Size of the Sintered Material
 Planseeber. Pulvermet. 8, 28-36 (1960)
 Chem. Abstr. 55 18482
- O. Lauer (Technikum der Alpine Akt.-Ges., Augsburg, Ger.)
 The Use of Precision Microsieves in Particle Size Determination
 Staub 20, 69-71 (1960)
 Chem. Abstr. 55 17118
- S. Z. Lewin, J. C. Sheridan, E. J. Hewitt, F. L. Acampora, A. N. Panos, E. M. Knitl, and F. Maliha (Evans Research and Develop. Corp.)
 Development of a Beta-Ray Particle Size Analyzer
 U. S. At. Energy Comm. NYO-2655 (1960)
 Chem. Abstr. 55 7935
- J. Pouchly (Vysoka skola chemicko-technol., Prague)
 The Kinetics of Adsorption from Solutions III. The Effect of Adsorbent Particle Shape
 Collection Czechoslov. Chem. Commun. 25, 1397-1412 (1960)
 Chem. Abstr. 54 1020; 54 20410
- I. I. Strizhevskii and S. P. Kal'manovich
 Determination of Grain Properties and Specific Surface of Calcium Carbide Particles Varying in Size
 Trudy Vsesoyuz. Nauch.-Issledovatel. Inst. Avtogen. Obrabotki Metal. No. 6, 114-33 (1960)
 Chem. Abstr. 55 25388
- V. L. Zolotavin, V. V. Vol'khin, and V. V. Rezvushkhin (S.M. Kerov Ural Polytech. Inst., Sverdlovsk)
 Effect of Freezing on the Properties of Metal Oxide Hydrates. I. Influence of Freezing and Thawing Conditions on Properties of Iron Hydroxide
 Kolloid. Zhur. 22, 395-13 (1960)
 Chem. Abstr. 55 12002

- G. W. Phelps and J. S. Dennis (United Clay Mines Corp.)
Particle Size of Feldspar and Flint as a Factor in Slip Behavior
J. Am. Ceram. Soc. 44, 149-56 (1961)
Chem. Abstr. 12798 (1961)
- W. C. McCrone (McCrone Assocs.)
Microscopic Identification of Single Particles
Microchem. J. Symp. Ser. 1, 181-200 (1961)
Chem. Abstr. 58 10731
- A. D. Genkin and N. V. Korolev (State Optical Inst., Leningrad)
The Determination of Small Mineral Grains in Ores
Geol. Rudn. Mestorozhdenii No. 5, 64-79 (1961)
Chem. Abstr. 56 2173
- V. S. Komarov
New Method of Determining the Apparent Specific Gravity of Powdered Substances
Dokl. Akad. Nauk Belorussk. SSR 5, No. 8, 336-8 (1961)
Chem. Abstr. 57 9224
- W. H. Coulter
Apparatus to Measure the Number and Size of Suspended Particles in a Liquid and to Study their Distribution and Other Properties
Ger. 1,118,503 (11/30/61) U. S. Appl. 1/9/59
Chem. Abstr. 56 9918
- L. A. Papazian (Wayne State Univ.)
Light Scattering of Flowing Colloidal Systems
U. S. Dept. Com., Office Tech. Serv., AD 261,748 (1961)
Chem. Abstr. 58 1932
- W. C. Ormsby, J. M. Shartsis, and K. H. Woodside (Natl. Bur. of Stds., Washington, D.C.)
Exchange Behavior of Kaolins of Varying Degrees of Crystallinity
J. Am. Ceram. Soc. 45, 361-6 (1962)
Chem. Abstr. 57 13843
- B. R. Puri, S. Parkash, and D. D. Singh (Univ. Punjab)
Properties of Charcoal-Silica Mixed Adsorbent Systems
J. Sci. Ind. Res. (India) 21C, 158-61 (1962)
Chem. Abstr. 57 6650

- W. Heller and R. Tabibian (Wayne State Univ.)
Experimental Investigations on the Light Scattering of Colloidal
Spheres. IV. Scattering Ratio
J. Phys. Chem. 66, 2059-65 (1962)
Chem. Abstr. 52 8685; 57 15849
- A. Langier-Kuzniarowa (Geol. Inst., Warsaw)
The Effect of Dispersing Agents Used for Grain Size Analysis
Tonind.-Ztg. Keram. Rundschau 87, 93-8 (1963)
Chem. Abstr. 59 291
- J. Tuul and R. M. DeBaun (Am. Cyanamid Co.)
Measurement of Skeletal Densities of High-Surface-Area Inorganic
Oxides With a Gas Pycnometer
Anal. Chem. 34, 814-17 (1962)
Chem. Abstr. 57 4066
- U. N. Bhargava and J. H. Brown (U. S. Steel Corp.)
Particle Size Measurement and Control
Trans. AIME 223, 248-54 (1962)
Chem. Abstr. 56 12213
- J. Hinnueber and W. Kinna
Hard Metal Technique and Research
Stahl Eisen 82, No. 1, 31-46 (1962)
Chem. Abstr. 57 527
- D. Bialas and R. Hosemann (Max-Planck-Ges., Berlin)
Roentgenographic Determination of Particle Size and Poly-Disperity
on Colloidal Nickel, Nickel Oxide, and Nickel-Montmorillonite
Chem. Erde 22, 41-56 (1962)
Chem. Abstr. 58 1986
- D. L. Deadmore (Natl. Aeron. Space Admin.)
Influence of Surface Area on the Density of Quartz Heated at
1300-1500 Degrees
Nature 196, 1083-4 (1962)
Chem. Abstr. 58 5386
- H. Schluge
Determining Particle Size Distribution from Photomicrographs
Res. Develop. Ind. No. 9, 34-6 (1962)
Chem. Abstr. 58 2158

- Z. M. Topuriya
Determination of the Sizes of Synthetic Manganese Dioxide Particles
Tr. Inst. Prikl. khim. i Elektrokhim., Akad. Nauk Gruz. SSR 3,
181-7 (1962)
Chem. Abstr. 58 2170
- R. I. Mitchell and J. M. Pilcher (Battelle Mem. Inst.)
Cascade Impactor for Measuring Aerosol Particle Sizes
Ind. Eng. Chem. 51, 1039-42 (1959)
Chem. Abstr. 54 2826
- R. Naito, R. Yamamoto, Y. Nishimura, and S. Kato (Govt. Ind.
Research Inst., Nagoya)
Effect of Particle Size of Raw Material in Porcelain Manufacturing
IV. Reaction Between Feldspar of Various Grain Sizes and Kaolin
Nagoya Kogyo Gijutsu Shikensho Hokoku 10, 741-8 (1961)
Chem. Abstr. 54 17828; 56 6922
- P. Kratochvil, P. Munk, and B. Sedlacek (Czechoslovak Acad. Sci.,
Prague)
Continuous Observation of Particle Polymerization by Means of Light-
Scattering Extrapolation Method
J. Polymer Sci. 53, 295-9 (1961)
Chem. Abstr. 57 67
- S. F. Bartram (Gen. Elec. Co.)
Crystallite-Size and Particle-Size Measurements on BeO Powders
by X-Ray Methods
Advan. X-Ray Anal. 4, 40-62 (1961)
Chem. Abstr. 57 2949
- H. Heywood (Woolwich Polytechnic, London)
Techniques for the Evaluation of Powders. I. Fundamental Properties
of Particles and Methods of Sizing Analysis
Powder Met. 7, 1-28 (1961)
Chem. Abstr. 56 4482
- J. Kobak and D. J. Taveridge
Single Tube Sedimentation Apparatus for the Measurement of
Particle Size Distribution
J. Sci. Instr. 37, 266-9 (1960)
Chem. Abstr. 55 26560

- O. Kolar, Z. Pelzbauer, and F. Kaspar (VUSPL, Pardubice, Czech.)
 Estimation of Particle Size, of its Distribution, and the Specific
 Surface of Pigments for the Formulation of Paints
 Chem. prumsyl 10, 274-8 (1960)
 Chem. Abstr. 54 25877
- S. Miura (Univ. Hiroshima)
 Monodispersed Fine Particles
 Koroido To Kaimen-Kasseizai 1, 25-9 (1960)
 Chem. Abstr. 57 4067
- I. Watanabe and S. Kachi (Univ. Kyoto)
 Uranium Dioxide Powders
 Funtai Oyobi Funnatsuyakin 7, 269-74 (1960)
 Chem. Abstr. 57 369
- B. Sedlacek and J. Sponar (Chemicky ustav CSAV, Prague)
 Light Scattering XIV. Determination of the Interaction Constant
 and of the Particle Size by the Method of Known Dilution
 Collection Czechoslov. Chem. Commun 25, 1214-15 (1960)
 Chem. Abstr. 54 6; 54 20417
- G. Schneider (Inst. Appl. Phys. High-Purity Materials,
 Dresden, Ger.)
 Direct Determination of Average Particle Sizes of Microscopic
 Objects with Electric Point Counters with Attached Oculars
 Z. Metallk. 51, 414-20 (1960)
 Chem. Abstr. 54 21875
- G. H. Taylor and R. C. Wilson (Am. Nepheline Co.)
 Particle-Size Control of Nepheline Syenite for Whitewares
 Am. Ceram. Soc. Bull. 41, 12-13 (1962)
 Chem. Abstr. 56 8316
- N. A. Dushkina
 Granulometric and Microscopic Composition of Chalks and Chalklike
 Rocks
 Tr. Lab. Gidrogeol. Probl. Akad. Nauk SSSR 44, 44-50 (1962)
 Chem. Abstr. 57 1896
- P. Connor (At. Energy Res. Estab., Harwell, Engl.)
 Automatic Counting and Sizing of Particles
 Ind. Chemist 39, 69-74 (1963)
 Chem. Abstr. 58 13470

H11b. SURFACE AREA

B. V. Deryagin, N. N. Zakhavaeva, M. V. Talaev, and V. V. Filippovskii
Filtration Method of Determining the Specific Surface of Porous Bodies
Metody Issledovaniya Struktury Vysokediapers. i Poristyykh Tel, Akad.
Nauk SSSR, Inst. Fiz.-Khim., Trudy Vtorogo Soveshchaniya, 203-13
(1956) (Pub. 1958)

Chem. Abstr. 53 21034

A. V. Kiselev and E. V. Khrapova
The Effect of the Pore Dimensions and the Hydration of the Surface
of Silicas on the Adsorption of Nitrogen Vapor
Colloid J. (USSR) 19, (1957)
Chem. Abstr. 52, 3460; 53 64856

I. N. Plaksin, A. M. Okolovich, and L. P. Zaraiskaya
Measurement of the Specific Surface of Mineral Powders in the
Investigation of the Flotation Process
Chin Shu Hsueh Pao 2, 387-95 (1957)
Chem. Abstr. 53 2706

A. S. Joy (Dept. Sci. and Ind. Research, Greenwish, Engl.)
An All-Metal Apparatus for the Determination of Specific Surface by
Gas Adsorption
Vacuum 7 & 8, 30-7 (1957-58) (Pub. 1959)
Chem. Abstr. 54 7242

B. V. Deryagin, N. N. Zakhavaeva, M. V. Talaev, and V. V. Filippovskii
Method and Apparatus for Measuring Specific Surface (or disperseness)
of Porous and Powdered Substances from Rate of Flow of Attenuated
Air
Trudy Inst. Fiz. Khim., Akad. Nauk SSSR No. 6
Novye Metody Fiz.-Khim. Issledovaniy No. 2, 131-9 (1957)
Chem. Abstr. 53 2

B. Arh
Determination of Binding Material in Granulated and Powder
Compositions
Neva Proizvodnja 8, 208-14 (1957)
Chem. Abstr. 53 3760

H. Lehmann and U. Haese (Bergakad. Clausthal, Ger.)
The Importance of Grain-Size Distribution and Specific Surfaces for
the Determination of the Grinding Resistance of Ceramic Materials
Tonind.-Ztg. u. keram. Rundschau 82, 479-86, 546-51 (1958)
Chem. Abstr. 53 6561

M. B. Harris and K. S. W. Sing (Coll. Technol., Liverpool, Engl.)
The Surface Properties of Precipitated Alumina. III. Samples
Prepared from Aluminum Isopropoxide
J. Appl. Chem. (London) 8, 586-9 (1958)
Chem. Abstr. 51 17328; 54 6248

S. Tilenschi
Experimental Measurements of Specific Surface
Rev. chim. (Bucharest) 9, 239-46 (1958)
Chem. Abstr. 54 5207

B. V. Erofeev and V. A. Protashchik
Determination of the Surface Area of Magnesium Oxide in Mixtures with
Magnesium Carbonate by the Chemical Sorption of Radioactive Carbon
Dioxide
Vestsi Akad. Navuk Belarus. SSR, Ser. Fiz.-Tekh. Navuk, No. 2, 61-6
(1958)
Chem. Abstr. 54 8211

G. Kampf and H. W. Kohlschutter (Tech. Hochschule, Darmstadt, Ger.)
The Determination of the Specific Surface Area and the Pore Volume
of Porous Materials
Z. Elektrochem. 62, 958-65 (1958)
Chem. Abstr. 53 2730

S. G. Entelis, M. A. Tsikulin, L. V. Volkov, and N. M. Chirkov
(Inst. Chem. Phys., Acad.Sci. USSR, Moscow)
Measurement of the Specific Surface of Porous Bodies and Powders by
the Method of Outflow of Dilute Gas
Zhur. Fiz. Khim. 32, 2187-91 (1958)
Chem. Abstr. 53 778

M. F. Skalozubov and V. I. Matsokin (Polytech. Inst. Novochoerkassk)
Radiometric Determination of Surfaces of Dispersed and Porous
Materials
Zhur. Priklad. Khim. 31, 1429-31 (1958)
Chem. Abstr. 48 9837; 53 904

S. Ronssin
Measurement of the Specific Surface of Nitrocelluloses and of
Powders, Fibers, and Crystals
Mem. poudres 40, 457-71 (1958)
Chem. Abstr. 51 1602; 54 25825

- R. L. Ferguson and G. W. Leddicotte (Oak Ridge Natl. Lab.)
 Surface-Exchange Method for Determination of Surface Area of UO_2
 Powder
 U. S. At. Energy Comm. CF-59-8-62 (1959)
 Chem. Abstr. 57 10554
- A. Bel, B. Francois, R. Delmas, and R. Caillat
 Sintering Uranium Oxide Powder
 Compt. rend. 249, 1045-7 (1959)
 Chem. Abstr. 54 6343
- A. L. Klyachko-Gurvich
 Measurements of Specific Surface by Krypton Adsorption
 Sbornik Nauch. Trudov Gosudarst. Nauch.-Issledovatel. Inst.
 Tavetnykh Metal. No. 16, 63-70 (1959)
 Chem. Abstr. 56 36
- O. P. Mehra and M. L. Jackson (Univ. of Wisconsin)
 Specific Surface Determination by Duointerlayer and Monointerlayer
 Glycerol Sorption for Vermiculite and Montmorillonite Analysis
 Soil Sci. Soc. Am. Proc. 23, 351-4 (1959)
 Chem. Abstr. 54 13515
- H. P. Dibbs
 Surface-Area Determination of Magnesium Powder with Chromium-51
 Tracer Solutions
 Can. Dept. Mines and Tech. Surveys, Mines Branch Research Rept. R53
 (1959)
 Chem. Abstr. 54 13808
- V. A. Protashchik
 Determination of the Surface Area of Separate Components in Mixtures
 of Solid Substances by Chemisorption of Cl^{40}_2
 Doklady Akad. Nauk Belorussk. SSR 3, 372-4 (1959)
 Chem. Abstr. 54 7281
- A. V. Fernandez
 Determination of Free Silica and Specific Surface of Portland Cement
 Raw Materials
 Inst. Tec. Construc. Cemento, Publ. (Madrid), No. 203 (1959)
 Chem. Abstr. 57 9461

H. P. Schreiber and M. H. Waldman (Can. Inds. Ltd., MacMasterville)
Rapid Determination of Some Surface Properties of Solids
Can. J. Chem. 37, 1782-5 (1959)
Chem. Abstr. 54 7281

J. M. Haynes (English Clays Lovering Pochin & Co., Ltd., St. Austell,
Cornwall, Engl.)
A Gas-Adsorption Method for Rapid Comparison of Specific Surface Areas
Clay Minerals Bull. 4, 69-74 (1959)
Chem. Abstr. 54 9429

O. P. Mehra (Univ. of Wisconsin)
Specific Surface Determination of Layer Silicates in the Presence
of Mica
Univ. Microfilms (Ann Arbor, Mich.), L. C. Card No. Mic 59-3207,
Dissertation Abstr. 20, 817-18 (1959)
Chem. Abstr. 54 2098

G. M. Schwab and W. Kohler (Univ. Munich, Ger.)
Change of Surface Area in Reactions of Powdered Components in the
Solid State
Z. anorg. u. allgem. Chem. 301, 1-6 (1959)
Chem. Abstr. 54 2909

F. M. Nelson and F. T. Eggersten (Bataafsche Petroleum
Maatschappij N.V.)
Determination of Surface Area
Ger. 1,058,282 (5/27/59)
Chem. Abstr. 55 9987

J. F. Roth and R. J. Ellwood (Gen. Aniline & Film Co.)
Determination of Surface Area Using a Gas Chromatograph
Anal. Chem. 31, 1738-9 (1959)
Chem. Abstr. 55 9972

Y. S. Nikitin
The Porous Structure and the Catalytic Activity of Spherical,
Aluminosilicate Catalysts
Zhur. Fiz. Khim. 33, 2513-16 (1959)
Chem. Abstr. 54 21964

- V. Danes and J. Novakova (Czechoslov. akad. ved, Prague)
 Determination of the Surface Area and Surface Structure of Porous
 Materials by Physical Adsorption Measurements. II. The Ad-
 sorption of Argon Above and Below its Melting Point and the
 State of the Adsorbed Film
 Collection Czechoslov. Chem. Commun. 24, 874-84 (1959)
 Chem. Abstr. 52 19405; 53 11937
- T. Suzuki (Univ. Tokyo)
 Measurement of Surface Area of Finely Ground Particles of Minerals
 Tohoku Kozan 5, No. 4, 12-16 (1959)
 Chem. Abstr. 53 15705
- K. Wheatley
 Measurement of the Surface Area of Tridymite
 J. Appl. Chem. (London) 9, Pt. 3, 159-62 (1959)
 Chem. Abstr. 53 14638
- L. Tomlinson
 Measurement of Powder Surface Areas by Krypton Adsorption
 U. K. At. Energy Authority, Ind. Group Hdg. IGR-TN/S 1032 (1959)
 Chem. Abstr. 53 14633
- O. N. Repkova, D. A. Vasil'kov, and R. L. Grechnyuk
 Determination of the Specific Surface of Powders with an Electron
 Microscope
 Nekotorye Voprosy Ekspitl. Fiz. No. 2 106-16 (1959)
 Chem. Abstr. 54 21934
- V. Danes and J. Novakova (Ustav fysikalni chemie CSAV, Prague)
 The Determination of the Surface and Structure of Porous Materials and
 Catalysts by Measurement of Physical Adsorption. III. The Deter-
 mination of the Pore-Distribution of Solids from the Adsorption
 Isotherms of Argon
 Collection Czechoslov. Chem. Commun. 24, 1914-23 (1959)
 Chem. Abstr. 53 11937; 54 1017
- M. Fukuda, T. Hirai, and H. Manabe (Matsushita Elec. Ind. Co. Osaka)
 Determination of Surface Area of Manganese Dioxide by the B.E.T.
 Method
 Natl. Tech. Rept. 5, 127-34 (1959)
 Chem. Abstr. 53 21001

P. Fejes, J. Kiraly, and G. Schay (Ungar. Akad. Wiss., Budapest, Hung.)

Simplified Method for Determination of the Specific Surfaces of Porous Adsorbents. III. Isotherms of Furan at 23 Degrees; Surface Requirements of Furan, Butane, and Isobutane

Z. anorg. u. allgem. Chem 300, 72-80 (1959)

Chem. Abstr. 51 7102; 53 17628

L. Bini (Am. Cyanamid Co.)

Modification of the Innes Equation for Determining Areas of Low-Area Solids

Anal. Chem. 31, 1404-5 (1959)

Chem. Abstr. 53 21035

F. Kindervater

Critical Investigations of the Permeability Method for the Determination of the Specific Surface of Pigments

Deut. Farben-Z. 8, 312-17 (1959)

Chem. Abstr. 53 20832

J. Siedlewski and K. Karpinski (Univ., Torun, Poland)

Adsorption Methods of Determining the Surface Area of Adsorbents and Catalysts

Wiadomosci Chemi. 14, 279-94 (1960)

Chem. Abstr. 54 16987

R. A. W. Haul and G. Dumbgen (Univ. Bonn, Ger.)

A Simple Method for Measuring Surface Areas by Means of Gas Adsorption

Chem.-Ing.-Tech. 32, 349-54 (1960)

Chem. Abstr. 54 16099

G. A. Gaziev, M. I. Yanovskii, and V. V. Brazhnikov

A Simplified Chromatographic Method of Determining the Surface Area of Solid Absorbents and Catalysts

Kinetika i Kataliz 1, 548-52 (1960)

Chem. Abstr. 56 36

C. Moreau

Thermal Exchanges in the B.E.T. Method

Comm. energie at. (France), Rappt. No. 1678 (1960)

Chem. Abstr. 55 11024

F. Hofmann (George Fischer Akt.-Ges.)
Apparatus for Determining the Specific Surface of Granular Material,
Especially Foundry Sand
Swiss 347,027 (7/30/60)
Chem. Abstr. 55 12960

K. H. Woodside and W. C. Ormsby (Natl. Bur. of Standards)
Surface-Area Determination of Kaolinite Using Glycerol Adsorption
J. Am. Ceram. Soc. 43, 671-2 (1960)
Chem. Abstr. 55 5895

G. Dumoulin
Control of Grinding by Measurement of the Permeability of the
Ground Products
Ind. ceram. No. 515, 18-22 (1960)
Chem. Abstr. 54 16043

F. D. Leipziger and L. A. Altamari (Knolls At. Power Lab.)
An Apparatus for Measurement of the Surface Area of Irradiated
Coarse Powders
Nuclear Sci. and Eng. 8, 312-14 (1960)
Chem. Abstr. 55 17272

G. Shumway and K. Igelman (U.S. Electronics Lab.)
Computed Sediment Grain-Surface Areas
J. Sediment. Petrol. 30, 486-9 (1960)
Chem. Abstr. 55 26898

C. M. Lapointe (Can. Dept. Mines and Tech. Surveys, Ottawa)
Surface-Area Determination of Magnesium Powders by Sorption of C¹⁴-
Labeled Oleic Acid
Mines Branch Research Rept. R60 (1960)
Chem. Abstr. 54 19082

K. Kodera and Y. Onishi (Univ. Kyoto)
The Molecular Cross-Sectional Areas for the Determination of Specific
Surface Areas of Solids. II. Titania and Silica
Bull. Chem. Soc. Japan 33, 338-43 (1960)
Chem. Abstr. 54 14865; 54 19082

M. P. Freeman (Univ. of California)

The Quantum-Mechanical Correction for the High-Temperature van der Waals Interaction of Light Gases and Surfaces. A New Method of Determining Surface Area

J. Phys. Chem. 64, 32-7 (1960)

Chem. Abstr. 54 9430

A. Ilantzis

Specific Surface of Powdered Materials. The Blaine Apparatus

Rev. matériaux construct. et trav. publ. C, No. 534, 59-66 (1960)

Chem. Abstr. 54 16933

G. Schay, L. Gy. Nagy, and T. Szekrenyesy (Polytech. Univ., Budapest, Hung.)

Comparative Studies on the Determination of Specific Surface Areas by Liquid Adsorption

Periodica Polytech. 4, 95-117 (1960)

Chem. Abstr. 55 4099

K. Chujo, S. Okajima, and M. Yamasaki (Nihon Cement Co., Tokyo)

Study on the Blaine Method and Comparison Between the Specific Surface of Blaine and Nitrogen Adsorption Methods and the Fineness by the Air Elutriation Method

Semento Gijutsu Nenpo 14, 106-12 (1960)

Chem. Abstr. 55 19181

G. Taschen

Measurement of Specific Heat of Wetting

Plaste u. Kautschuk 7, 471-4 (1960)

Chem. Abstr. 55 16033

G. Sandstede and E. Robens (Battelle Inst. c.V., Frankfurt a.M., Ger)
Gravimetric Determination of Gas Adsorption with an Electronic Microbalance

Chem.-Ing.-Tech. 32, 413-17 (1960)

Chem. Abstr. 54 19081

A. P. Medvedeva

The Determination of the Specific Surface of Finely Dispersed Alumina by Adsorption from the Liquid Phase

Ogneupory 25, 184-6 (1960)

Chem. Abstr. 54 14867

- R. I. Razouk and R. Sh. Mikhail (Ain-Shams Univ., Cairo)
The Dependence of the Surface Properties of Catalysts on the
Presence of Air During their Production by Thermal De-
composition
Actes intern. Congr. catalyse, 2 Paris, 2, 2023-32 (1960)
(Pub. 1961)
Chem. Abstr. 55 23008
- G. Schay, L. G. Nagy, and T. Szekrenyesy (Muszaki egyetem,
Budapest, Hung.)
Surface-Area Determination by Measurement of the Heat of
Immersion
Magyar Kem. Folyoirat 66, 271-5 (1960)
Chem. Abstr. 55 7983
- I. I. Strizhevskii and S. P. Kal'manovich
Determination of Grain Properties and Specific Surface of Calcium
Carbide Particles Varying in Size
Trudy Vsesoyuz. Nauch.-Issledovatel. Inst. Avtogen. Obrabotki Metal.
No. 6, 114-33 (1960)
Chem. Abstr. 55 25388
- A. L. Klyachko-Gurvich
Simplified Method for Determining the Surface from the Adsorption
of Air
Izv. Akad. Nauk SSSR, Otd. Khim. Nauk 1884-6 (1961)
Chem. Abstr. 58 6217
- W. D. Machin, B. I. Parsons, and D. S. Montgomery (Dept. Mines
Tech. Surveys, Ottawa)
Calculation of the Pore-Size Distribution from the Nitrogen
Desorption Isotherm
Can. Dept. Mines Tech. Surv., Mines Branch, Tech. Bull. TB 26 (1961)
Chem. Abstr. 57 4066
- O. Grubner and V. Benesova (Ustav fysikalni chemie CSAV, Prague)
Apparatus for the Determination of Surface Areas of Powders by
Adsorption of Gases
Chem. prumysl 11, 71-3 (1961)
Chem. Abstr. 55 22941

M. C. Kordecki and M. B. Gandy (Georgia Inst. of Technol.)
An Investigation of the Use of Radioactive Isotopes for Determining
the Surface Area of Powdered Materials by Sorption Methods
U. S. At. Energy Comm. SRO-55 (1961)
Chem. Abstr. 56 2019

D. W. Aylmore and W. B. Jepson (Univ. Exeter, Engl.)
Technique Using Kr⁸⁵-Labeled Krypton for Surface Area Measurements
J. Sci. Instr. 38, 156-9 (1961)
Chem. Abstr. 56 12691

P. Connor
Surface Area Measurement
Ind. Chemist 37, 178-82, 224-8 (1961)
Chem. Abstr. 55 16039

J. Amiel, M. Figlarz, and J. Songeon
Specific Area of Solids Measured by the Brunauer, Emmett, and
Teller (B.E.T.) Method
Compt. rend. 252, 1783-5 (1961)
Chem. Abstr. 55 20535

C. P. Hedlin and S. H. Collins (Natl. Research Council, Saskatoon)
Method of Measuring the Surface Area of Granular Material
Can. J. Chem. Engr. 39, 49-51 (1961)
Chem. Abstr. 55 8964

S. B. Skladzien
Emanation Method for the Determination of the Surface Area of Thorium
Oxide
U. S. At. Energy Comm. ANL-6335 (1961)
Chem. Abstr. 55 20680

J. M. Haynes
The Specific Surface of Clays
Trans. Brit. Ceram. Soc. 60, 691-707 (1961)
Chem. Abstr. 57 9471

M. Hollnagel
Measurement of Specific Surface by the Method of Deryagin
Abhandl. Deut. Akad. Wiss. Berlin, Kl. Chem., Geol. Biol., No. 3
85-8 (1961)
Chem. Abstr. 57 15839

P. Cannon and G. L. Gaines, Jr. (Gen. Elec. Research Lab.)
Use of Krypton for Surface-Area Measurements
Nature 190, 340 (1961)
Chem. Abstr. 55 18242

R. Stock (Coll. Technol., Liverpool, Engl.)
Determination of Surface Area by Gas Chromatography
Anal. Chem. 33, 966-7 (1961)
Chem. Abstr. 53 15701; 55 17156

L. Grzelewski, N. Krawczyk, and A. Teichert (Univ. Warsaw)
Determination of the Specific Surface of Catalysts and Carriers
by Adsorption from Solutions
Przemysl Chem. 40, 684-7 (1961)
Chem. Abstr. 56 14974

G. Bliznakov, D. Mekhandzhiev, and Iv. Bak'rdzhiev
Determination of Adsorbent and Catalyst Surfaces by the B.E.T.
Method
Khim. Ind. (Sofia) 33, 186-90 (1961)
Chem. Abstr. 57 4065

M. G. Kaganer
The Adsorption of Nitrogen, Argon, and Krypton on Various Surfaces
and the Determination of Surface Area
Doklady Akad. Nauk SSSR 138, 405-8 (1961)
Chem. Abstr. 56 7449

N. C. Ganguli, P. N. Mukherjee, and A. Lahiri (Central Fuel
Research Inst., Jealgora, India)
Surface Area of Coal
Fuel 40, 525-6 (1961)
Chem. Abstr. 56 5029

B. C. Lippins (Koninklijke Zwavelzuurfabrieken v/h Ketjen N.V.,
Amsterdam) and M. E.A. Hermans
Measurement of the Surface Area of Powders by the BET (Brunauer,
Emmett, Teller) Method
Powder Met. 7, 66-81 (1961)
Chem. Abstr. 56 4544

M. C. Kordecki and M. B. Gandy (Georgia Inst. of Technol.)
Surface-Area Measurement by the Sorption of Stearic-1- C^{14} Acid
Intern. J. Appl. Radiation and Isotopes 12, 27-31 (1961)
Chem. Abstr. 56 9450

H. P. Dibbs, P. R. Gorla, and C. M. Lapointe (Dept. Mines Tech.
Surveys, Ottawa, Can.)
Measurement of Surface Area Using Radio-Isotopes
Vortraege Originalfassung Intern. Kongr. Grenzflaechen-aktive
Stoffe, 3., Cologne, 3, 242-50 (1960) (Pub. 1961)
Chem. Abstr. 57 9224

T. Hirai, H. Manabe, and M. Fukuda
Surface-Area Determination of Manganese Dioxide by Liquid-Phase
Adsorption Method
Natl. Tech. Rept. (Matsushita Elec. Ind. Co., Osaka) 7, 16-20 (1961)
Chem. Abstr. 55 16076

J. F. Carpenter (United Nuclear Corp. Chemicals Div.)
Characterization of UO_2 Powders
Monthly Progress Report, February 1962
Contract AT(40-1)-2699
Nucl. Sci. Abstr. 1962 (11) 4043

G. Parravano (Univ. of Michigan)
Surface Heterogeneity: A Modern Version
Gazz. Chim. Ital. 91, 467-78 (1961)
Chem. Abstr. 57 14453

K. V. Wise and E. H. Lee (Monsanto Chem. Co.)
Versatility of Dynamic Sorption Method for Routine Measurements on
Solids
Anal. Chem. 34, 301-2 (1962)
Chem. Abstr. 56 9449

Cl. Sfintescu
Determination and Correlation of the Activity of Catalysts with
the Specific Surface and the Porosity
Rev. Chim. (Bucharest) 13, 224-31 (1962)
Chem. Abstr. 58 7409

V. T. Bykov and O. E. Presnyakova
Dynamic Method for Determining the Specific Surface of Adsorbents by
Adsorption from Flowing Solution
Kinetika i Kataliz 3, 784-7 (1962)
Chem. Abstr. 58 5063

J. F. Carpenter (United Nuclear Corp. Chemicals Div.)
Characterization of UO₂ Powders
Monthly Progress Report, March 1962
Contract AT(40-1)-2699
Nucl. Sci. Abstr. 1962 (11) 4043

J. Kiraly (MYA, Kozp. Kem. Kut. Int., Budapest, Hung.)
Surface-Area Determination of Adsorbents by Krypton Adsorption
Magyar Kem. Folyoirat 68, No. 2, 77-80 (1962)
Chem. Abstr. 57 89

H. J. Bultemann
Apparatus for Measuring Surface Area According to B.E.T. (Brunauer,
Emmett, Teller) Method
Vide 17, No. 99, 201-7 (1962)
Chem. Abstr. 57 14453

S. Maneschi
The Specific Surface and the Form of Grains of Fine Materials
Bull. Soc. Franc. Ceram. No. 55, 31-6 (1962)
Chem. Abstr. 58 1217

V. A. Nelidov
An Improvement in the Method of Determining the Specific Surface
of Dusts
Tsement 28, No. 2, 15-17 (1962)
Chem. Abstr. 57 4067

F. Scholl (Robert Bosch G.m.b.H., Stuttgart, Ger.)
Determination of Surface Area and Surface Quality of Solids by Gas
Chromatographic Methods
Trans. Intern. Ceram. Congr., 8th, Copenhagen, 75-83 (1962)
Chem. Abstr. 58 948

- V. Ponec and Z. Knor (Ustav Fysikalni Chem. CSAV, Prague)
Measurement of Small Surface Areas by Means of Physical Adsorption
Collection Czech. Chem. Commun. 27, 1091-8 (1962)
Chem. Abstr. 57 9224
- G. Kortuem and D. Oelkrug (Univ. Tuebingen, Ger.)
Reflection Measurements on Adsorbed Substances for Determining the
Surface of Powders; Comparison with the B.E.T. Method
Z. Physik. Chem. (Frankfurt) 34, 58-66 (1962)
Chem. Abstr. 58 2869
- J. M. Haynes (English Clays Loving Pochin & Co., Ltd., Cornwall,
Engl.)
Use of Krypton for Surface-Area Measurements
J. Phys. Chem. 66, 182-5 (1962)
Chem. Abstr. 56 12337
- J. Fuul and W. B. Innes (Am. Cyanamid Co.)
Inorganic Oxide Air Adsorption at Room Temperature and Correlation
with Surface Area
Anal. Chem. 34, 818-20 (1962)
Chem. Abstr. 57 4066
- J. A. Barker and D. H. Everett (Commonwealth Sci. Ind. Research
Organization, Melbourne)
High-Temperature Adsorption and the Determination of the Surface
Area of Solids
Trans. Faraday Soc. 58, 1608-23 (1962)
Chem. Abstr. 58 2866
- L. Imre and J. Nagy (Univ. Debrecen, Hung.)
The Adaptation of Radioactive-Indicator Methods to the Determination
of the Surfaces of Solids. III.
Kolloid Z. 183, 134-41 (1962)
Chem. Abstr. 58 3893
- H. W. Daeschner and F. H. Stross (Shell Develop. Co.)
Efficient Dynamic Method for Surface-Area Determinations
Anal. Chem. 34, 1150-5 (1962)
Chem. Abstr. 57 10538

V. Bosacek, R. Polak, E. Kucera, and V. Danes (Ceskoslov. Akad. Ved, Prague)
Surface and Structure Properties of Aluminum Oxide Pretreated by Halogens and Aluminum Tetrafluoroborate
Collection Czech. Commun 27, 2575-85 (1962)
Chem. Abstr. 58 11981

R. B. Fischer (Indiana Univ.)
The Surfaces of Precipitated Particles
Record Chem. Progr. (Kresge-Hooker Sci. Lib.) 23, 93-103 (1962)
Chem. Abstr. 58 6223

H. L. Gruber (Atlantic Refining Co.)
Adsorption Flow Method for Specific Metal Surface Area Determination
Anal. Chem. 34, 1828-31 (1962)
Chem. Abstr. 58 3941

M. M. Egorov and V. F. Kiselev
The Surfaces of Silica Gel and Quartz and their Adsorption Properties
VII. The Heats of Wetting and the Surface Energy of Silica
Zh. Fiz. Khim. 36, 318-24 (1962)
Chem. Abstr. 56 5421; 57 5322

J. B. Ainscough (U.K. At. Energy Authority, Springfield, Engl.)
Effect of Adsorbent Temperature on the Brunauer-Emmett-Teller Surface Area Determined by Krypton Adsorption at 77 Degrees K
Nature 195, 1089-90 (1962)
Chem. Abstr. 57 15841

D. Caulfield and R. Ullman (Polytech. Inst. of Brooklyn)
High-Angle Limit in Low-Angle Scattering and its Effect on the Determination of Surface Area
J. Appl. Phys. 33, 1737-40 (1962)
Chem. Abstr. 57 15850

R. M. Cahen and J. Marechal (Labofina, S. A., Brussels, Belg.)
Surface-Area Determination by the Continuous-Flow Method
Anal. Chem. 35, 259-60 (1963)
Chem. Abstr. 58 8427

- K. R. Lange (Phila. Quartz Co.)
Adsorption Isotherms by a Rapid Flow Method
J. Colloid Sci. 18, 65-72 (1963)
Chem. Abstr. 58 8429
- H. K. Dettmar, W. Lode, and E. Marre (Farbenfabriken Bayer A.-G.,
Leverkusen, Ger.)
Light Scattering and Particle-Size Distribution of Spherical
Particles I. Theoretical Part
Kolloid-Z. 188, 28-40 (1963)
Chem. Abstr. 58 13175
- G. S. Khodakov
Specific Surface Area of Highly Dispersed Powders as Determined
by the Flow of Rarefied Gas
Dokl. Akad. Nauk SSSR 148, 581-4 (1963)
Chem. Abstr. 58 11979
- E. A. Arroyo and F. C. Gimeno (Spain. Junta de Energia Nuclear,
Madrid)
Determination of Superficial Activities of Powders with BET
Apparatus
JEN-81-DMe/I6 (1960)
Nucl. Sci. Abstr. 1963 (5) 2164
- S. Okuda, K. Inoue, and I. Uei (Kyoto Univ. Ind. Arts and Textile
Fibers)
Determination of Surface Area of Several Oxide and Clay Minerals by
the Heat-of-Immersion Method
Funtai Oyobi Funnatsuyakin 7, 275-9 (1960)
Chem. Abstr. 56 8040
- M. Arakawa (Univ. Kyoto)
Measurement of Specific Surface Area of Fine Powder by Adsorption
from Solution
Koroido To Kaimen-Kasseizai 1, 223-30 (1960)
Chem. Abstr. 57 4064
- M. A. Kerdivarenko and G. A. Krenis
Measurement of Specific Surface of Crystalline Substances by the
Oil-Film Method
Uch. Zap., Kishinev. Gos. Univ. 56, 197-201 (1960)
Chem. Abstr. 57 68

- J. Weber et al
Surface Area/P.V.C. (Pigment Volume Concentration) Relation for
Various Extender Pigments
Offic. Dig., Federation Socs. Paint Technol. 33, 1461-88 (1961)
Chem. Abstr. 56 6117
- D. M. Shakhtin and E. V. Levintovich (Ukrain. Sci. Research Inst.
Refractories, Kharkov)
Determination of the Specific Surface of Clays and Kaolins by Means
of Radioactive Tungsten
Kolloid. Zhur. 23, 495-8 (1961)
Chem. Abstr. 56 5424
- C. Legrand, M. Navez, and H. Merx (C.N.R.S., Bellevue, France)
Use of X-Ray Fluorescence to Study the Surface Composition of Glasses
Compt. Rend. 253, 1439-41 (1961)
Chem. Abstr. 56 2162
- M. H. Milford and M. L. Jackson (Univ. of Wisconsin)
Specific Surface Determination of Expansible Layer Silicates
Science 135, 929-30 (1962)
Chem. Abstr. 56 15178

H11c. ELECTRICAL, MAGNETIC, AND THERMAL PROPERTIES OF PARTICLES

- I. A. Uskov and O. T. Uskova
Colloidal-Chemical Qualities of Aluminum Oxide Suspensions
I. Electrokinetic Potential of the Suspension with Additions
of Hydrochloric Acid
Nauk. Zapiski, Kii. Derzhav. Univ. im. T. G. Shevchenka 16, No. 15
Zbirnik Khim. Fax. No. 8, 49-53 (1957)
Chem. Abstr. 53 7720
- B. V. Deryagin, N. A. Krotova, V. V. Karasev, Yu. M. Kirillova, and
I. N. Aleinikova
Electrical Phenomena Accompanying the Formation of New Surfaces, and
Their Role in Adhesion and Cohesion
Proc. Intern. Congr. Surface Activity, 2nd, London, 3, 417-26 (1957)
Chem. Abstr. 55 13005
- B. V. Deryagin and S. P. Bakanov
Theory of the Motion of Small Aerosol Particles in a Diffusion Field
Soviet Phys. "Doklady" 2, 563-7 (1957)
Chem. Abstr. 53 19518
- H. Laudelout (Catholic Univ., Louvain, Belg.)
Distribution of Surface Charges on Clay Particles
Bull. group franc. argiles 9, No. 4, 61-5 (1957)
Chem. Abstr. 55 20362
- P. G. Meerman (Dutch States Mines, Hoensbroek-Treebeek, Neth.)
Geomagnetic Flocculation: An Explanation of the Rheological
Behavior of Suspended Magnetite
Rheol. Acta 1, 106-10 (1958)
Chem. Abstr. 53 19522
- R. E. DeLaRue and C. W. Tobias (Univ. of California)
The Conductivity of Dispersions
J. Electrochem. Soc. 106, 827-33 (1959)
Chem. Abstr. 53 21051
- W. H. Lien and N. E. Phillips (Univ. of California)
Heat Capacity of Small Particles of MgO Between 1.5 and 4.0 K
J. Chem. Phys. 29, 1415-16 (1958)
Chem. Abstr. 53 7749
- I. Epelboin and D. Quivy (Fac. Sci., Paris)
Permittivity and Magnetic Permeability of Mixtures. I.
Arch. sci. (Geneva) 11, Spec. No., 104-7 (1958)
Chem. Abstr. 53 20971

C. E. Johnson, Jr. and W. F. Brown Jr. (Minnesota Mining and Manufacturing Co.)

Shape Distribution of Magnetic Powders

J. Appl. Phys. 29, 1699-1701 (1958)

Chem. Abstr. 53 21003

H. P. Nieboj (Univ. Saarland, Physik. Inst., Saarbrücken, Ger.)

Aerosol Spectrometer for Measuring Size, Electrical Charge, and

Density of Dust Particles

Kolloid-Z. 160, 58 (1958)

Chem. Abstr. 53 778

K. Barron and L.E. Lawley (Polytechnic, London)

Absorption of Sound in Sediments or Small Particles in Liquids

Proc. Phys. Soc. (London) 72, 933-9 (1958)

Chem. Abstr. 54 20417

C. E. Johnson Jr. and W. F. Brown Jr. (Minnesota Mining & Mfg. Co.)

Shape Distribution of Magnetic Powders

J. Appl. Phys. 30, 136S-137S (1959)

Chem. Abstr. 53 20972

B. R. Eichbaum (Intern. Business Machines Corp.)

The Dielectric Behavior of Solids Embedded in a Homogeneous Medium

J. Electrochem. Soc. 106, 804-9 (1959)

Chem. Abstr. 53 20967

I. I. Strelkov and A. N. Dzizin

Dielectric Permeability of Suspensions of Moistened Clays in
Nonpolar Media

Trudy Khar'kov Politekh. Inst. im. V. I. Lenina 31, No. 1, 11-16
(1959)

Chem. Abstr. 55 16082

H. W. Douglas and J. Burden (Univ. Liverpool, Engl.)

Surface Charge and Sedimentation of Thoria Suspensions. I. Electro-
phoretic Behavior of Thoria Particles in Aqueous Solutions of Acids,
Alkalies, and Various Salts

Trans. Faraday Soc. 55, 350-5 (1959)

Chem. Abstr. 54 1026

- A. Vardukadze
The Influence of Exchangeable Cations on the Value of the Potential
of Clay Suspensions
Tr. Tbilissk. Gos. Univ. 74, 203-9 (1959)
Chem. Abstr. 57 7950
- K. B. Deshpande and C. E. Marshall (Univ. of Missouri)
An Interpretation of Electrochemical Measurements on a
Montmorillonite Clay
J. Phys. Chem. 63, 1659-62 (1959)
Chem. Abstr. 54 8213
- G. I. Berezin, A. V. Kiselev, and V. A. Sinitstn
The Specific Heat of the Silica Gel-Water Adsorption System
Doklady Akad. Nauk SSSR 135, 638-41 (1960)
Chem. Abstr. 55 22992
- A. A. Slinkin, V. I. Yakerson, and A. M. Rubinshtein
Catalytic and Magnetic Properties of the Nickel Oxide-Magnesium
Oxide Catalysts
Izvest. Akad. Nauk. SSSR, Otdel. Khim. Nauk 435-41 (1960)
Chem. Abstr. 56 10971
- L. V. Gregor
Heat Capacity of Ag₂O at Low Temperatures
UCRL 9723, 99 pp. (1961)
Chem. Abstr. 56 12378
- M. B. Serebryakova
Electrokinetic Potential of Suspensions of Certain Minerals and
Rocks
Mineral'n. Syr'e. Moscow, Sb. No. 3, 122-8 (1961)
Chem. Abstr. 57 16169
- B. Prasad and A. K. Dey (Univ. Allahabad, India)
Conductometric Studies of the Precipitation of Thorium Hydroxide
II. Effect of Age on the Conductance of the Systems Containing
the Precipitated Hydroxide
Kolloid-Z. 175, 53-5 (1961)
Chem. Abstr. 55 14035; 55 17162

- V. V. Tarasov and Kh. B. Khokonov
Effect of Particle Size on Heat Capacity of Magnesium Oxide in the
Region from 1 to 5 Degrees K
Uch. Zap. Kabardino-Balkarsk. Univ. No. 13 97-9 (1961)
Chem. Abstr. 58 12016
- E. V. Smith
Balance for Measurement of Magnet Susceptibilities
J. Sci. Instr. 38, 466-8 (1961)
Chem. Abstr. 56 13987
- Yu. K. Popyalkovskii
Separation of Disperse Mineral Products in a Non-Uniform Electrical
Field
Sb. Nauchn. Tr., Irkutskii Nauchn.-Issled. Inst. Redkikh Metal.
No. 9 70-5 (1961)
Chem. Abstr. 58 6473
- I. N. Kutseva
Influence of Superstoichiometric Oxygen on the Catalytic Adsorptive,
and Electrical Properties of Nickelous Oxide
Doklady Akad. Nauk SSSR 138, 409-11 (1961)
Chem. Abstr. 56 10973
- W. Batel (Inst. Landtech. Grundlagenforschung, Braunschweig, Ger.)
Amount and Behavior of Interstitial Liquid in a Granular Solid
Chem.-Ingr.-Tech. 33, 541-7 (1961)
Chem. Abstr. 55 25389
- V. O. Shevchenko
Dilatometric Study of Calcium Bentonites
Dopovidi Akad. Nauk Ukr. RSR 1215-18 (1962)
Chem. Abstr. 58 1927
- A. V. Kiselev and V. I. Lygin (State Univ., Moscow)
Application of Infrared Spectroscopy to the Study of Structure of
Surface Chemical Compounds and Adsorption
Uspekhi Khim. 31, 351-84 (1962)
Chem. Abstr. 57 2877
- W. T. Clark and R. W. Powell (Natl. Phys. Lab., Teddington, Engl.)
Measurement of Thermal Conduction by the Thermal Comparator
J. Sci. Instr. 39, 545-51 (1962)
Chem. Abstr. 58 1922

R. A. Mischke and J. M. Smith (Northwestern Univ.)
Thermal Conductivity of Alumina Catalyst Pellets
Ind. Eng. Chem., Fundamentals 1, 288-92 (1962)
Chem. Abstr. 58 3919

M. J. Shah and C. M. Hart (Kaiser Electronics)
The Electro-Optical Birefringence of Polydisperse Bentonite
Suspensions
IBM J. Res. Develop. 7, No. 1, 44-57 (1963)
Chem. Abstr. 58 7401

H11d. IMPURITY ANALYSIS, STOICHIOMETRY

S. I. Beneslavskii

Composition and Technological Properties of Bauxites

Byull. Tsvetnoi Met. No. 8, 20-30 (1957)

Chem. Abstr. 54 11402

P. S. Mamykin

Impurities in Kaolins and Clays. and their Effect on the Heat-Resistance, Caking, and Slag-Resistance

Materialy Soveshchan po Ispol'zovan. Polukislykh Glin Urala Sbornik 27-36 (1958)

Chem. Abstr. 55 5896

A. J. Ahearn (Bell Telephone Labs., Inc.)

Mass Spectrographic Studies of Impurities on Surfaces

Natl. Symposium on Vacuum Technol. 1-5 (1959)

Chem. Abstr. 55 11953

S. J. Gregg and M. I. Pope (Univ. Exeter, Engl.)

The Effect of the Ionic Environment During Precipitation on the Structure of Hydrous Titanium Dioxide

Kolloid-Z. 174, 27-32 (1961)

Chem. Abstr. 55 11031

J. Godon-Benou, J. Francois-Rossetti, and B. Imelik (Sorbonne, Paris)

Influence of Adsorbed Cations on the Texture of Porous Silica

Bull. Soc. Chim. France 816-22 (1962)

Chem. Abstr. 53 21053; 57 5321

H11e. SOLID-LIQUID INTERFACE
(ALPHABETICALLY BY ADSORBING SOLID)

F. M. Kutsakov

Determination of Activity of Alumina by Use of Methylene Blue
Trudy Khar'kov. Politekh. Inst. im. V. I. Lenina 26, Ser. Khim.-
Tekhnol. No. 6, 77-80 (1959)
Chem. Abstr. 55 21750

E. Calvet and H. Thibon (Fac. scis., Marseille)

Contribution to the Study of the Mechanism of Decomposition of
Solutions of Sodium Aluminate
Bull. soc. chim. France, 1577-85 (1959)
Chem. Abstr. 46 328; 54 9439

H. Winkler (Univ. Leipzig, Ger.)

Nuclear Magnetic Resonance of Water Sorbed in Al_2O_3
Arch. sci. (Geneva) 12, Fasc. spec. 161-3 (1959)
Chem. Abstr. 53 5813; 54 6252

T. Cummings, H. C. Garven, C. H. Giles, S. M. K. Rahman, J. G. Sneddon,
and C. E. Stewart (Roy. Coll. Sci. Technol., Glasgow, Scot.)

Adsorption of Inorganic Surfaces IV. Mechanism of Adsorption of
Organic Solutes by Chromatographic Alumina
J. Chem. Soc. 535-44 (1959)
Chem. Abstr. 53 21038

I. M. Konyushko

Adsorption of Nonelectrolytes from Aqueous Solutions by Aluminum
Hydroxide

Uchenye Zapiski Belorus. Gosudarst. Univ. im. V. I. Lenina, Ser. Khim.
No. 42, 259-70 (1958)
Chem. Abstr. 54 37

L. P. Shirinskaya and N. F. Ermolenko

Effect of the Preparation Conditions of Aluminum Oxide on its
Adsorption Activity

Sb. Nauchn. Rabot, Akad. Nauk Belorussk. SSR, Inst. Obshch. i
Neorgan. Khim. No. 1, 171-80 (1960)
Chem. Abstr. 57 91

A. C. Chatterji and G. S. Singhal (Univ. Lucknow)

Adsorption from Different Solvents I. Adsorption of Aliphatic
Monocarboxylic Acids on Alumina
J. Sci. Ind. Research (India) 19B, 298-301 (1960)
Chem. Abstr. 55 17159

- R. Pilleri (Univ. Turin, Italy)
 Adsorption Isotherms of Salicylic Acid and Atophan on Alumina
 Rass. chim. 12, No. 1, 25-6 (1960)
 Chem. Abstr. 54 18021; 54 20410
- T. N. Skoulikidis and M. Vasilopoulos (Tech. Hochschule, Athens, Greece)
 The Mechanism of the Sorption of Molecular Colloids on Solids
 II. The Sorption of Methylene Blue on Alumina
 Kolloid-Z. 168, 150-3 (1960)
 Chem. Abstr. 54 10451; 54 20410
- A. E. Lewis (Curtiss-Wright Corp.)
 Polar-Screen Theory for the Deflocculation of Suspensions
 J. Am. Ceram. Soc. 44, 233-9 (1961)
 Chem. Abstr. 55 18248
- T. Skoulikidis and P. Bekiaroglou (Tech. Hochschule, Athens, Greece)
 Kinetics of the Aging of Anodic Layers on Aluminum Caused by the
 Absorption of Dye II. Higher Temperatures
 Kolloid-Z. 178, 45-50 (1961)
 Chem. Abstr. 53 903; 56 2245
- M. Gery, M. A. Michou-Saucet, J. Lenoir, P. Pierron, and C. Eyraud
 (Institut Natl. Sciences Appliques Villeurbanne, France)
 Properties of Certain Chemical Compounds of Alumina
 Compt. Rend. 254, 688-90 (1962)
 Chem. Abstr. 56 14957
- F. Umland and C. R. Engel (Tech. Hochschule, Hannover, Ger.)
 Interaction of Electrolyte Solutions and Gamma-Al₂O₃. VI. Determina-
 tion of Water Adsorption from Aqueous Solution
 Z. Anorg. Allgem. Chem. 317, 129-41 (1962)
 Chem. Abstr. 53 14785; 57 14457
- R. G. Greenler (Allis-Chalmers Manufg. Co.)
 Infrared Study of the Adsorption of Methanol and Ethanol on
 Aluminum Oxide
 J. Chem. Phys. 37, 2094-100 (1962)
 Chem. Abstr. 57 15841

- J. H. de Boer, G. M. M. Houben, B. C. Lippens, W. H. Meijs, and
W. K. A. Walrave (Technol. Univ., Delft, Neth.)
Nature of Surfaces with Polar Molecules. I. Adsorption of Lauric
Acid on Aluminum Oxides and Hydroxides
J. Catalysis 1, No. 1, 1-7 (1962)
Chem. Abstr. 57 2891
- I. V. Smirnova, A. A. Kubasov, K. V. Topchieva (M. V. Lomonosov
State Univ., Moscow)
Heats of Wetting Aluminum Oxide by n-Heptane Solutions of Benzene,
Cyclohexane, and Cyclohexene
Doklady Akad. Nauk SSSR 139, 150-3 (1961)
Chem. Abstr. 56 9506
- A. M. Rubinshtein, Yu. A. El'tekov, and T. R. Brueva
Adsorption Studies of Monohydrated Aluminum Oxide and of Gamma-
Aluminum Oxide
Izv. Akad. Nauk SSSR, Otd. Khim. Nauk, 2107-17 (1960)
Chem. Abstr. 57 88
- H. Grasshof (Firma M. Woelm, Eschwege, Ger.)
Chromatographic Behavior of Hydroxyl-Containing Carboxylic Acids
and Phosphoric Acid Esters on Alumina
J. Chromatog. 3, 285-9 (1960)
Angew. Chem. 63, 219 (1951)
Chem. Abstr. 54 2041
- B. N. Ghosh and S. Bandyopadhyay (Univ. Colls. Sci. Technol.,
Calcutta)
Stability and Electrokinetic Potential of Aluminum Arsenate Sol.
J. Indian Chem. Soc. 39, 373-6 (1962)
Chem. Abstr. 57 13204
- M. V. Eirish
Investigation of the Adsorption Process of Cations and Water on
Bentonite Clays. I. Application of Methods of Electrometric
Titration to the Study of Cation Adsorption
Izvest. Vysshikh Ucheb. Zavedenii, Khim. i Khim. Tekhnol. 2, 876-80
(1959)
Chem. Abstr. 54 10452

S. Okuda, K. Inoue, and I. Uei (Kyoto Kogei Seni Daigaku)
Cation Fixation in Kaolinitic Clay Minerals
Yogyo Kyokai Shi 67, 421-6 (1959)
Chem. Abstr. 54 21688

J. P. Eeckman, Y. Massart, and H. Laudelout (Univ. Catholique,
Louvain, Belg.)
Catalytic Properties and Chemical Stability of Suspension of
Montmorillonite Acid
Bull. groupe franc. argiles 11, No. 6, 3-8 (1959)
Chem. Abstr. 54 20446

P.I. Bel'kevich and I. M. Konyushko
Composition of the Adsorption Phase of Montmorillonite-Type Clay
Uchenye Zapiski Belorus. Gosudarst. Univ. im. V.I. Lenina, Ser.
Khim. No. 29, 233-50 (1956)
Chem. Abstr. 54 1974

S. Nakamura and C. Noguchi (Govt. Ind. Research Inst., Nagoya)
Strength of Dry Clayey Materials. II. The Relation Between Main
Mineral Components and Physical Properties of Some Unfired Clay
Materials
Nagoya Kogyo Gijutsu Shikensho Hokoku 2, 389-97 (1956)
Chem. Abstr. 54 21031

O. B. Krayanskii (Inst. Food Ind., Krasnodar)
Influence of Different Factors on the Adsorption Properties of
Bentonite
Izvest. Vysshikh Ucheb. Zavedenii, Pishchevaya Tekhnol. No. 1, 77-82
(1957)
Chem. Abstr. 53 19516

Z. A. Kruchinina and S. N. Aleshin
Changes in Some Clay Minerals by Proton Sorption
Izvest. Timiryazev. Sel'skokhoz Akad. No. 1, 212-22 (1959)
Chem. Abstr. 54 7283

C. M. Cho (Seoul Natl. Univ., Korea)
Effects of pH on Cation-Exchange Capacity of Illite and Bentonite
Seoul Univ. J. 2, 108 (1959)
Chem. Abstr. 54 7285

W. F. Bradley (Illinois Geol. Survey)
Density of Water Sorbed on Montmorillonite
Nature 183, 1614-15 (1959)
Chem. Abstr. 54 177

Y. Shiraki (Tokyo Inst. Technol.)
Buffer Action, Exchangeable Bases, and Exchange Acidity of Clay and
Other Ceramic Raw Materials
Yogyo Kyokai Shi 67, 283-93 (1959)
Chem. Abstr. 54 20131

M. Koizumi and R. Roy (Pennsylvania State Univ.)
Synthetic Montmorillonoids with Variable Exchange Capacity
Am. Mineralogist 44, 788-805 (1959)
Chem. Abstr. 53 19517

F. H. Gillery (Pennsylvania State Univ.)
Adsorption-Desorption Characteristics of Synthetic Montmorillonoids
in Humid Atmospheres
Am. Mineralogist 44, 806-18 (1959)
Chem. Abstr. 53 19517

K. Inagaki and Y. Inakuma (Aichi Prefecture Ceramic Research Inst.,
Seto)
The pH Value of Kaolins and Variation of pH with Base Exchange
Nendokagaku no Shimpo 1, 369-77 (1959)
Chem. Abstr. 53 19516

T. Egawa, Y. Watanabe, and A. Sato (Agr. Technol. Research Inst.,
Tokyo)
The Cation-Exchange Capacity of Allophane
Nendokagaku no Shimpo 1, 260-72 (1959)
Chem. Abstr. 53 19516

R. V. Mikhalyuk and O.D. Kurilenko (Technol. Inst. Food Ind., Kiev)
Lyophilic Properties of Aminated Bentonites
Izvest. Vysshikh Ucheb Zavedenii, Khim. i Khim. Tekhnol. 2, 196-9
(1959)
Chem. Abstr. 53 19221

- M. S. Ostrikov and E. P. Danilova
Influence of Electrolytes on the Capillary Contraction Force Acting
When Montmorillonite Dries
Uch. Zap. Rostovsk.-na-Donu Gos. Univ. 60, No. 10, 37-49 (1959)
Chem. Abstr. 57 13200
- N. M. Tatarchenko, V. I. Tsimbalist, V. G. Tsimbalist, and
V. V. Balandina
The Effect of Adsorbed Cations on Certain Technical Properties of
Clay
Nauch. Raboty Stud. Khim.-Tekhnolog. Fak., Novocherkasskii Politekh.
Inst. im. S. Ordzhonikidze No. 7, 39-42 (1959)
Chem. Abstr. 55 4909
- S. R. Sergienko, L. N. Kvitkovskii, Yu. T. Gordash, and Al. A Petrov
Adsorption Properties of High-Molecular Hydrocarbons Having a Mixed
Structure
Doklady Akad. Nauk SSSR 128, 769-72 (1959)
Chem. Abstr. 55 6984
- P. E. Watkins and T. White (Forestral Central Labs., Harpenden, Engl.)
Use of Tannin Extracts to Modify the Physical Properties of Clay
Suspensions
Proc. Intern. Congr. Surface Activity, 2nd, London, 4, 183-95 (1957)
Chem. Abstr. 54 3927
- V. Aleixandre-Ferrandis, J. G. Vicente, and M. C. Rodriguez-Pascual
(Inst. Edafol. Fisiol. Vegetal, Madrid)
Modification of the Adsorptive Properties of Clay Minerals Produced
by Thermal Treatment and Base-Exchange Cations
Anales Edafol. y. Fisiol. Vegetal 17, 133-61 (1958)
Chem. Abstr. 52 7810; 56 5424
- Y. Hendrickx (Univ. Ghent, Belg.)
Adsorption of Anions on Bentonites
Proc. U.N. Intern. Conf. Peaceful Uses At. Energy, 2nd, Geneva, 27,
178-81 (1958) (Pub. 1959)
Chem. Abstr. 55 17159
- R. Bittel, C. Boursat, and R. Platzer
Fixation of Zirconium by Acid Montmorillonite
Bull. groupe franc. argiles 11, No. 6, 9-19 (1959)
Chem. Abstr. 54 20410

O. D. Kurilenko and R.V. Mikhalyuk

Adsorption of Aliphatic Amines on Bentonite from Aqueous Solutions

Kolloid. Zhur. 21, 195-9 (1959)

Chem. Abstr. 54 2878

V. M. Yakovleva

The Question of a Method for Determining the Swelling of Clays

Trudy Vsesoyuz. Nauch.-Issledovatel. Inst. Stroitel. Keram. No. 13,
180-7 (1958)

Chem. Abstr. 53 18423

J. de D. Lopez Gonzales and C. del P. Vazquez

The Structure of, and Forces Between, Layers of Montmorillonites
and their Aqueous Suspensions

Anales real soc. espan. fis. y quim (Madrid) 55B, 711-16 (1959)

Chem. Abstr. 54 6251

O. I. Dmitrenko and G. A. Pavlova

Water Binding by Finely Dispersed Sediments. II. Dependence of the
Amount of Bound Water on the Composition and Concentration of
Equilibrium Solutions

Kolloid. Zhur. 21, 419-26 (1959)

Chem. Abstr. 52 17912; 54 7283

M. V. Eirish

Adsorption of Cations and Water in Bentonite Clays. II. Two
Fractions of Adsorbed Cations

Izvest. Vysshikh Ucheb. Zavedenii, Khim. i Khim. Tekhnol. 3,
No. 4, 657-62 (1960)

Chem. Abstr. 54 10452; 55 1140

M. A. Tamers and H. C. Thomas (Yale Univ.)

Ion-Exchange Properties of Kaolinite Slurries

J. Phys. Chem. 64, 29-32 (1960)

Chem. Abstr. 54 9433

R. W. Hoffmann and G. W. Brindley (Pennsylvania State Univ.)

Clay-Organic Studies. II. Adsorption of Nonionic Aliphatic Molecules
from Aqueous Solutions on Montmorillonite

Geochim. et Cosmochim. Acta 20, 15-29 (1960)

Chem. Abstr. 52 18105; 55 6100

- C. S. Brooks (Shell Develop. Co.)
Free Energies of Immersion for Clay Minerals in Water, Ethanol,
and n-Heptane
J. Phys. Chem. 64, 532-7 (1960)
Chem. Abstr. 54 20131
- O. Sieskind
The Adsorption Complexes Formed in Acid Media Between
Montmorillonite-H and Certain Amino Acids
Compt. rend. 250, 2392-3 (1960)
Chem. Abstr. 55 21752
- H. Leanpere (State Univ., Tartu)
Exchange Adsorption of Li and K ions on Tosu Clay
Uchenye Zapiski Tartusk. Gosudarst. Univ. No. 95, 148-54 (1960)
Chem. Abstr. 56 5424
- B. V. Deryagin, N. N. Zakhavaeva, and A. M. Lopatina (Inst. Phys.
Chem., Moscow)
New Method for Determining the Permeability of a Liquid and the Rate
of Capillary Absorption in Powders
Inzhener.-Fiz. Zhur., Akad. Nauk Belorus. SSR 3, No. 10, 66-8 (1960)
Chem. Abstr. 55 26560
- M. V. Eirish
Sorption of Cations and Water by Bentonite Clays. IV. Sorption
Properties and Microstructure of Montmorillonite
Izvest. Vysshikh Ucheb. Zavedenii, Khim. i Khim. Tekhnol. 4,
64-9 (1961)
Chem. Abstr. 55 13000; 55 17160
- V. S. Komarov and N. F. Ermolenko (Inst. Chem., Minsk)
Dependence of Adsorption Selectivity on the Nature of Binary
Mixtures
Zhur. Fiz. Khim. 35, 9-14 (1961)
Chem. Abstr. 55 11027
- J. J. Jurinak (Univ. of California)
The Effect of Pretreatment on the Adsorption and Desorption of
Water Vapor by Lithium and Calcium Kaolinite
J. Phys. Chem. 65, 62-4 (1961)
Chem. Abstr. 55 21748

- N. P. Zatenatskaya
Heat of Wetting and Tightly Bound Water in Clay Deposits
Pochvovedenie No. 4, 47-55 (1961)
Chem. Abstr. 55 20276
- J. J. Jurinak and D. H. Volman (Univ. of California)
Cation Hydration Effects on the Thermodynamics of Water Adsorption
by Kaolinite
J. Phys. Chem. 65, 1853-6 (1961)
Chem. Abstr. 56 71
- K. Darab and T. Schoenfeld (Vizgazdalkodasi Tudomanyos Kutato
Intezet, Budapest, Hung.)
The Adsorption of Cesium Ion on Clay Minerals
Agrokem. Talajtan 10, 539-46 (1961)
Chem. Abstr. 57 1883
- H. L. Jessberger (Tech. Hochschule, Munich, Ger.)
Water Absorption of Clays and Plasticity and Dispersibility of Clay-
Water Mixtures
Bautechnik 38, No. 9, 1-7 (1961)
Chem. Abstr. 56 15167
- I. A. Uskov and E. T. Uskova (T. G. Shevchenko-Univ., Kiev)
Electrochemical Study of Bentonite Suspensions. VI. Potentiometric
Titration of Aminobentonite Complexes
Kolloid Zhur. 23, 469-73 (1961)
Chem. Abstr. 56 44; 56 10974
- S. K. De (Univ. Allahabad, India)
Adsorption of Phosphate Ion by Calcium- and Aluminum- Derivatives of
Indian Montmorillonite
Neues Jahrb Mineral., Monatsh., 102-6 (1961)
Chem. Abstr. 55 20571
- F. D. Ovcharenko, S. P. Nichiporenko, and V. M. Valitskaya (Inst.
Gen. and Inorg. Chem., Acad. Sci. Ukr. SSR, Kiev)
The Determination of the Magnitude of Clay Swelling
Kolloidn. Zh. 24, No. 1, 55-7 (1962)
Chem. Abstr. 57 95

- R. T. Martin (Massachusetts Inst. of Technol.)
 Adsorbed Water on Clay: A Review
 Clays Clay Minerals, Proc. Natl. Conf. Clays Clay Minerals 9,
 28-70 (1962)
 Chem. Abstr. 57 14739
- F. Szanto (Eotvos Univ., Budapest)
 The Electrochemical Properties and Disaggregation of Bentonites
 Acta Geol. Acad. Sci. Hung. 7, 305-14 (1962)
 Chem. Abstr. 54 15863, 18023; 58 931
- M. Nishidoi (Japan At. Energy Res. Inst., Ibaraki)
 Ion Exchange by Kaolinite Treated with Sodium Hydroxide Solution
 Kogyo Kagaku Zasshi 65, 866-9 (1962)
 Chem. Abstr. 58 1930
- L. E. Vrublevskii
 Reasons for the Swelling of Clays
 Steklo i Keram. 19, No. 1, 20-2 (1962)
 Chem. Abstr. 57 1870
- W. Holtzman (Inst. Paper Chem.)
 The Application of the Verwey and Overbeek Theory to the Stability of
 Kaolinite-Water Systems
 J. Colloid Sci. 17, 363-82 (1962)
 Chem. Abstr. 57 1590
- V. S. Ramachandran, K. P. Kacker, and N. K. Patwardhan (Central
 Building Res. Inst., Roorkee, India)
 Adsorption of Dyes by Clay Minerals
 Am. Mineralogist 47, 165-9 (1962)
 Chem. Abstr. 57 92
- J. Beeckmans (Ontario Res. Found., Toronto)
 Adsorption of Lignosulfonates on Solids
 Can. J. Chem. 40, 265-74 (1962)
 Chem. Abstr. 56 14959

S. Ozaki and R. Tatematsu (Govt. Ind. Research Inst., Nagoya)
Action of Surfactants on the Pulverized Materials for Ceramics
Nagoya Kogyo Gijutsu Shikensho Hokoku 11, 41-7 (1962)
Chem. Abstr. 56 13826

S. Y. Elovich and O. G. Larionov (Inst. Phys. Chem., Moscow)
Adsorption from Nonelectrolyte Solutions on Solid Adsorbents
Izv. Akad. Nauk SSSR, Otd. Khim. Nauk 529-31 (1962)
Chem. Abstr. 57 4067

J. J. Chessick and A. C. Zettlemoyer (Lehigh Univ.)
A Comparison of Integral Enthalpies, Free Energies, and Entropies
of Adsorption
J. Phys. Chem. 65, 1672-5 (1961)
Chem. Abstr. 56 75

G. Kandilarov
Internal Friction and Sedimentation Volumes of Polydisperse Kaolin
Suspensions in Solutions of Electrolytes
Bulgar. Akad. Nauk Izvest. Khim. Inst. 4, 287-310 (1956)
Chem. Abstr. 53 8767

F. S. Stone, B. Rudham, and R. L. Gale (Univ. Bristol, Engl.)
Adsorption and Catalysis on Cobaltous Oxide
J. Elektrochem. 63, 129-35 (1959)
Chem. Abstr. 53 7759

R. B. Hajela and S. Ghosh (Univ. Allahabad, India)
Adsorption of Crystal Violet on Hydrrous Cr Oxide. I. Nature of
Adsorption Isotherm
Proc. Natl. Acad. Sci. India 28A, 59-63 (1959)
Chem. Abstr. 46 2873; 54 18019

N. E. Brezhneva, S. N. Oziraner, and V. N. Rozanova
Adsorption of Cations by Precipitates of Iron Hydroxyacetate
Zhur. Fiz. Khim. 34, 1866-71 (1960)
Chem. Abstr. 55 11999

V. L. Zolotavin and V. V. Vol'khin (S. M. Kirov Polytech. Inst.
Sverdlovsk)
Effect of Freezing on the Properties of Metal Hydroxide Hydrates.
III. Influence of Electrolytes on the Particle Size and Filtration
Speed Change of Iron Oxide Hydrate
Kolloid. Zhur. 23, 276-80 (1961)
Chem. Abstr. 56 45; 56 2021

J. Shimoizaka, M. Yusa, and I. Matsuoka (Tohoku Univ., Sendai)
The Effect of Phosphate Ion on the Dispersion of Ferric Oxide
Nippon Kogyo Kaishi 77, 253-7 (1961)
Chem. Abstr. 56 10974

A. A. Isirikyan and A. V. Kiselev (M. V. Lomonosov State Univ.,
Moscow)
Heats of Adsorption of Hydrocarbons on Magnesium Oxide
Zhur. Fiz. Khim. 34, 2817-24 (1960)
Chem. Abstr. 55 11997

G. I. Fuks and A. S. Mikhail'yuk (Sci.-Research Inst. Watch Ind.,
Moscow)
Investigation of the Boundary Friction and Adhesion to Study the
Interaction of Highly Dispersed Particles. III. Effect of Neutral
Electrolytes on Friction of Quartz, Ruby, and Agate at High
Contact Pressures
Kolloid. Zhur. 22, 720-9 (1960)
Chem. Abstr. 55 6106; 55 17160

M. Cignitti and A. Uva (Univ. Rome)
Determination by Infrared Spectroscopy of the Presence of the High-
Solubility Stratum on the Surface of Quartz
Ricerca sci. 28, 1915-16 (1958)
Chem. Abstr. 53 7725

W. Stober
Surface Structure and Adsorption Properties of SiO₂
Beitr. Silikose-Forsch. Sonderband 1, 15-29 (1955)
Chem. Abstr. 54 19092

H. Baumann
The Dissolving Process of Solid SiO₂ Modifications
Beitr. Silikose-Forsch. Sonderband 1, 31-41 (1955)
Chem. Abstr. 54 19092

W. Stober
Theoretical Aspects of the Dissolving Process of SiO₂ Preparations
and of SiO₂ Minerals
Beitr. Silikose-Forsch. Sonderband 1, 43-8 (1955)
Chem. Abstr. 54 19092

H. Seifert

Crystallographic Experiments about the Behavior of the Surfaces of
Quartz and of other Substances

Beitr. Silikose-Forsch. Sonderband 1, 85-104 (1955)

Chem. Abstr. 54 19092

I. Y. Babkin, V. S. Vasil'eva, I. V. Drogaleva, A. V. Kiselev,
A. Y. Korolev, and K. D. Shcherbakova (M. V. Lomonosov State Univ.,
Moscow)

Effects of Degree of Modification of the Surface of Silica by $(\text{CH}_3)_3\text{SiCl}$
on the Adsorption Properties

Doklady Akad. Nauk SSSR 122, 131-4 (1959)

Chem. Abstr. 54 7283

M. M. Egorov, V. F. Kiselev, K. G. Krasil'nikov, and V. V. Murina
(M. V. Lomonosov State Univ., Moscow)

Effect of the Surfaces of Silica Gel and Quartz on their Adsorption
Properties. III. Heat of Wetting of Silica with Various Liquids

Zhur. Fiz. Khim. 33, 65-73 (1959)

Chem. Abstr. 50 14310; 53 13724; 53 21036

L. G. Ganichenko, V. F. Kiselev, and K. G. Krasil'nikov (M. V.
Lomonosov State Univ., Moscow)

Effect of the Hydration of the Surface of Silica on the Adsorption
of Aliphatic Alcohols from Solutions

Doklady Akad. Nauk SSSR 125, 1277-80 (1959)

Chem. Abstr. 53 19515

W. M. Heaton Jr., R. K. Iler, and G. W. Sears Jr. (E. I. du Pont de
Nemours & Co.)

The Adsorption of Hydroxyl Ions from Aqueous Solution on the Surface
of Amorphous Silica

J. Phys. Chem. 64, 147-50 (1960)

Chem. Abstr. 54 10451

A. N. Sidorov

Spectroscopic Investigation of Water Adsorption on Porous Glass as a
Function of its Degree of Surface Hydration

Optika i Spektroskopiya 8, 806-10 (1960)

Chem. Abstr. 55 11998

- V. F. Kiselev (M. V. Lomonosov State Univ., Moscow)
 Relation of the Surface Energy of Silica to its Dispersion
 Zhur. Fiz. Khim. 34, 698-9 (1960)
 Chem. Abstr. 55 16075
- J. A. Hockey and B. A. Pethica (Univ. Manchester, Engl.)
 Thermodynamic Studies of Adsorption on Characterized Silicas
 I. Benzene
 Trans. Faraday Soc. 58, 2017-26 (1962)
 Chem. Abstr. 58 8429
- C. C. Ballard, E. C. Broge, R. K. Iler, D. S. St. John, and J. R. McWhorter (E. I. du Pont de Nemours and Co.)
 Esterification of the Surface of Amorphous Silica
 J. Phys. Chem. 65, 20-5 (1961)
 Chem. Abstr. 55 24160
- Z. Z. Vysotskii, L. F. Divnich, and M. V. Polyakov
 The Effect of Dehydrating Agents on the Porosity, Structure, and Sorption Properties of Silica Gel Surface
 Kolloid. Zhur. 23, 248-54 (1961)
 Chem. Abstr. 56 40
- T. S. Egorova, Y. A. Zarif'yants, V. F. Kiselev, K. G. Krasil'nikov, and V. V. Murina (M. V. Lomonosov State Univ., Moscow)
 Effect of the Surfaces of Silica Gel and Quartz on their Adsorptive Properties. VIII. Differential Heats of Adsorption of Water Vapor on Silica
 Zh. Fiz. m. 36, 1458-65 (1962)
 Chem. Abstr. 55 6099; 56 2016; 57 5322; 57 11883
- O. M. Dzhigit, A. V. Kiselev, and G. G. Muttik (M. V. Lomonosov State Univ., Moscow)
 Differential Heats of Adsorption of Water Vapor on Fine-Porous Silica Gel
 Kolloidn. Zh. 24, No. 1, 15-21 (1962)
 Chem. Abstr. 57 87
- Y. A. El'tekov and S. V. Markevich
 The Effect of Potassium Ions on the Properties of Silica Gels
 Issled. v Obl. Prom. Primenen. Sorbentov, Akad. Nauk SSSR, Otd. Khim. Nauk 31-5 (1961)
 Chem. Abstr. 56 14962

- J. Fraissard (Univ. Paris)
 Structure and Properties of Silica Gels
 Comm. Energ. At. (France) Rappt. No. 2129 (1962)
 Chem. Abstr. 58 5061
- R. L. Every, W. H. Wade, and N. Hackerman (Univ. of Texas)
 Free Energy of Adsorption. I. The Influence of Substrate Structure
 in the $\text{SiO}_2\text{-H}_2\text{O}$, $\text{SiO}_2\text{-n-hexane}$, and $\text{SiO}_2\text{-CH}_3\text{OH}$ Systems
 J. Phys. Chem. 64, 25-9 (1961)
 Chem. Abstr. 54 17028; 55 21749
- P. E. Eberly, Jr. (Humble Oil & Refining Co.,)
 Measurement of Adsorption Isotherms and Surface Areas by Continuous-
 Flow Method
 J. Phys. Chem. 65, 1261-5 (1961)
 Chem. Abstr. 55 22991
- R. E. Mould (Am. Glass Research)
 Strength and Static Fatigue of Abraded Glass under Controlled Ambient
 Conditions. IV. Effect of Surrounding Medium
 J. Am. Ceram. Soc. 44, 481-91 (1961)
 Chem. Abstr. 54 10254; 56 2161
- J. W. Whalen
 Thermodynamic Properties of Water Adsorbed on Quartz
 J. Phys. Chem. 65, 1676-81 (1961)
 Chem. Abstr. 56 71
- G. J. Young and T. P. Bursh (Alfred Univ., Alfred, N. Y.)
 Immersion Calorimetry Studies of the Interaction of Water with
 Silica Surfaces
 J. Colloid Sci. 15, 361-9 (1960)
 Chem. Abstr. 52 8674; 54 21977
- Vlad. Satava (Vysoka skola chem.-technol., Prague)
 Reactions of Solids with Liquids
 Silikaty 5, 171-81 (1961)
 Chem. Abstr. 55 24160
- L. A. Romo (E. I. du Pont de Nemours & Co.)
 Adsorption Selectivity and Electrostatic Fields of Rutile Powders
 J. Colloid Sci. 16, 139-49 (1961)
 Chem. Abstr. 55 11999

- C. M. Hollabaugh and J. J. Chessick (Lehigh Univ.)
 Adsorption of Water and Polar Paraffinic Compounds onto Rutile
 J. Phys. Chem. 65, 109-14 (1961)
 Chem. Abstr. 55 21749
- R. L. Every, W. H. Wade, and N. Hackerman (Univ. of Texas)
 Free Energy of Adsorption. II. The Influence of Substrate Structure
 in the Systems Al_2O_3 and TiO_2 with n-hexane, CH_3OH and H_2O
 J. Phys. Chem. 65, 937-41 (1961)
 Chem. Abstr. 55 21749; 55 26635
- W. Susse (Tech. Univ., Berlin)
 The Coagulation and Dispersion of Fine Grained Dry Minerals
 Staub 20, 429-38 (1960)
 Chem. Abstr. 55 20534
- A. V. Kiselev.
 The Theory of Adsorption
 Vestnik Akad. Nauk SSSR 27, 43-53 (1957)
 Chem. Abstr. 56 958
- P. M. Lapin
 Effect of Various Factors on the Swelling of Lyophilic Colloids
 Trudy Moskov. Tekh. Inst. Rybnoi Prom. i Khoz. No. 8, 170-84 (1957)
 Chem. Abstr. 55 17161
- H. Kuno and R. Abe (Keio Univ., Tokyo)
 Relation Between Liquid Absorption and Void Volume of Powdery Pigments
 Kogyo Kagaku Zasshi 61, 1445-8 (1958)
 Chem. Abstr. 56 13575
- G. I. Fuks (Sci. Research Inst., Horological Ind., Moscow)
 Boundary Friction and Adhesion in the Study of the Interaction of
 Finely Dispersed Particles. I. Certain Boundary Properties of
 Solutions in Narrow Clearances between Solid Planes
 Kolloid. Zhur. 20, 748-58 (1958)
 Chem. Abstr. 54 9437
- J. O. Kopplin, J. R. Eaton, and J. E. Christian (Purdue Univ.)
 Adsorption of Odorous Materials. I. Surface Potential Changes of
 Solid and Liquid Adsorbing Surfaces
 J. Am. Pharm. Assoc. 48, 427-30 (1959)
 Chem. Abstr. 53 19514

E. Biscnoff (Lab. Physik Chem. Grenzflächen, Kirchheim-Boland, Ger.)
Interfacial Behavior of Powdered Solids in Liquids
Kolloid-Z. 168, 8-23 (1960)
Chem. Abstr. 53 18594; 54 3875; 54 19091

Y. Kubokawa
The Elovich Equation for the Rate of Chemisorption
Bull. Univ. Osaka Prefecture, Ser. A9, No. 1, 63-8 (1960)
Chem. Abstr. 55 25423

V. S. Komarov and N. F. Ermolenko
The Selective Character of Adsorption, as Dependent upon the Structure
of the Sorbent
Doklady Akad. Nauk SSSR 135, 129-32 (1960)
Chem. Abstr. 55 25432

S. M. Kogan (State Univ., Moscow)
Effect of Dispersion on the Adsorptive Capacity of a Semi-conductor
Problemy Kinetiki i Katiliza, Akad. Nauk SSSR No. 10, 52-7 (1960)
Chem. Abstr. 55 25494

A. Watanabe (Univ. Kyoto)
Physicochemical Studies on Surface-Active Agents. I. Theory of
Coagulation of Hydrophobic Sols
Bull. Inst. Chem. Research, Kyoto Univ. 38, 158-78 (1960)
Chem. Abstr. 55 26607

J. J. Kipling (Univ. Hull, Engl.)
Adsorption at Interfaces: Some Comparisons
Vortraege Originalfassung Intern. Kongr. Grenzflaechenaktive Stoffe
3., Cologne 2, 77-84 (1960) (Pub. 1961)
Chem. Abstr. 57 15843

H. Lange (Henkel Cie. G.m.b.H., Duesseldorf, Ger.)
New Developments in the Field of Wetting, Spreading, and Rewetting
Vortraege Originalfassung Intern. Kongr. Grenzflaechenaktive Stoffe
3., Cologne, Ger. 2, 415-25 (1960) (Pub. 1961)

A. J. Teller (Univ. of Florida)
Adsorption with Chemical Reaction
Chem. Eng. 67, No. 14, 111-24 (1960)
Chem. Abstr. 54 17988

C. H. Giles, T. H. MacEwan, S. N. Nakhwa, and D. Smith (Roy. Coll. Sci. Technol., Glasgow, Scot.)
Adsorption. XI. A System of Classification of Solution Adsorption Isotherms, and its Use in Diagnosis of Adsorption Mechanisms and in Measurement of Specific Surface Areas of Solids
J. Chem. Soc. 3973-93 (1960)
Chem. Abstr. 53 5681; 55 5083

B. Tamamushi
Reviews of Studies on Surface-Active Agents in Japan. Introduction
Yukagaku 9, 219 (1960)
Chem. Abstr. 54 20257

K. Tamaki (Univ. Tokyo)
Absorption of Ionic Surface-Active Agents at the Interface of Solid and Liquid Phases
Yukagaku 9, 283-8 (1960)
Chem. Abstr. 54 20250

E. G. Shafrin and W. A. Zisman (Naval Research Lab.,)
Constitutive Relations in the Wetting of Low-Energy Surfaces and the Theory of the Retraction Method of Preparing Monolayers
J. Phys. Chem. 64, 519-24 (1960)
Chem. Abstr. 54 20407

R. J. Ruch and L. S. Bartell (Iowa State Univ.)
Wetting of Solids by Solutions as a Function of Solute Adsorption
J. Phys. Chem. 64, 513-19 (1960)
Chem. Abstr. 54 20408

Y. Kubokawa (Univ. Osaka)
Rate of Adsorption from a Heterogeneous Surface
Bull. Chem. Soc. Japan 33, 1226-7 (1960)
Chem. Abstr. 55 7984; 56 10964

V. I. Osherov
Theory of Chemical Adsorption
Doklady Akad. Nauk SSSR 130, 117-19 (1960)
Chem. Abstr. 56 39

H. M. Myers (Univ. of California)
Factors Governing Water Binding by Hydroxyapatite
Arch. Oral Biol. 5, 45-8 (1961)
Chem. Abstr. 56 37

J. P. Olivier (Rensselaer Polytech. Inst.)
Adsorption Isotherm and the Adsorptive Energy Distribution of Solids
Univ. Microfilms (Ann Arbor, Mich.) L. C. Card No. Mic 60-2691
Dissertation Abstr. 21, 3648 (1961)
Chem. Abstr. 55 22992

R. Prasad and A. K. Dey (Univ. Allahabad)
Adsorption of Inorganic Ions by Hydrous Thorium Oxide. Association
of Different Cations and Anions with Precipitated Hydrous Thorium
Oxide
J. Sci. Ind. Research (India) 20B, 230-1 (1961)
Chem. Abstr. 55 25425

S. M. Ellerstein (Polytech. Inst. of Brooklyn)
Adsorption of Poly(methyl methacrylate) from Solution on to Solid
Surfaces
Univ. Microfilms (Ann Arbor, Mich.), L.C. Card No. Mic 61-1266
Dissertation Abstr. 21, 3645 (1961)
Chem. Abstr. 55 22994

R. R. Weiler, J. Beeckmans, and R. McIntosh (Univ. Toronto)
Adsorption of Benzene and Ethanol up to High Relative Pressures on
Finely Divided Sodium Chloride. I. Particle- Size Effects and
the Adsorption of Benzene. II. Lowering of Surface Free
Energy by Ethanol
Can. J. Chem. 39, 1360-71 (1961)
Chem. Abstr. 55 22991

R. Kohn (Slovenska akad. vied, Bratislava, Czech.)
Determination of the Volume of Hydrated Particles in Suspensions by
the Modified Indicator Method
Chem. Zvesti 15, 81-94 (1961)
Chem. Abstr. 55 17161

S. Ross and J. P. Olivier (Rensselaer Polytechnic Inst.)
Physical Adsorption. XII. The Adsorption Isotherm and the Adsorp-
tive Energy Distribution of Solids
J. Phys. Chem. 65, 608-15 (1961)
Chem. Abstr. 52 17888; 55 17159

Y. Kubokawa and O. Toyama (Univ. Osaka Prefect., Sakai)
Adsorption and Catalytic Reaction
Koroido To Kaimen-Kasseizai 2, 342-8 (1961)
Chem. Abstr. 57 11885

J. W. McGrath and A. A. Silvidi (Kent State Univ., Ohio)
Structure of the Water Molecule in Solid Hydrated Compounds
J. Chem. Phys. 34, 322-5 (1961)
Chem. Abstr. 55 20552

I. E. Neimark
Alteration of Adsorption Properties of Mineral Sorbents by Geometric
and Chemical Modification
Issledovan. v Oblasti Prom. Primeneniya Sorbentov, Akad. Nauk SSSR,
Otd. Khim. Nauk 5-12 (1961)
Chem. Abstr. 56 12338

J. A. Dillon, Jr. (Brown Univ.)
Clean-Surface Approach to Adsorption Studies
Trans. Natl. Vacuum Symp. 8, 113-18 (1961) (Pub. 1962)
Chem. Abstr. 57 15834

P. Chiche (Centre Etude Rechs. Charbonnages France, Verneuil-en-
Halatte, Oise, France)
Thermodynamics of Adsorption. I.
J. Chim. Phys. 59, 375-93 (1962)
Chem. Abstr. 57 5320

A. V. Kiselev (Moscow Univ.)
New Problems of Adsorption Investigation. Influence of the Nature
of the Adsorbent, of the Surface Nonuniformity, and of the Inter-
action of Adsorbed Molecules on the Adsorption Properties of
Solids
Kolloidn. Zh. 24, 185-94 (1962)
Chem. Abstr. 57 2877

A. Silberberg (Mellon Inst.)
The Adsorption of Flexible Macromolecules. I. The Isolated
Macromolecule at a Plane Interface
J. Phys. Chem. 66, 1872-83 (1962)
Chem. Abstr. 57 15892

H. J. Neumann (Tech. Hochschule, Braunschweig, Ger.)
Explanation of Boundary-Layer Eruptions
Z. Elektrochem. 66, 555-9 (1962)
Chem. Abstr. 54 1976; 57 14453

M. M. Dubinin, E. G. Zhukovskaya, and K. O. Murdmaa
Adsorption Properties and the Secondary Pore Structure of Adsorbents
Having a Molecular-Sieve Effect. VI. Adsorption of Nitrogen and
Water Vapors on the Zeolites, Type X, and the Potential Theory
of Adsorption
Izv. Akad. Nauk SSSR, Otd. Khim. Nauk 960-8 (1962)
Chem. Abstr. 57 11884; 58 42

V. V. Panasyuk and S. E. Kovchik
Influence of a Surface-Active Medium on the Surface Energy of a
Brittle Body
Dokl. Akad. Nauk SSSR 146, 82-5 (1962)
Chem. Abstr. 57 16155

S. Y. Elovich and O. G. Larionov
The Theory of Adsorption from Solutions of Nonelectrolytes on Solid
Adsorbents. I. The Equation of Adsorption Isotherm from Solutions
and the Analysis of its Simplest Form
Izv. Akad. Nauk SSSR, Otd. Khim. Nauk No. 2, 209-16 (1962)
Chem. Abstr. 57 13201

O. D. Kurilenko, F. D. Ovcharenko, and E. A. Yakovkina (Technol. Inst.
Food Ind., Kiev)
Wetting Thermodynamics
Izv. Vysshikh Uchebn. Zavedenii, Khim. i Khim. Tekhnol. 5, No. 1,
87-90 (1962)
Chem. Abstr. 57 5330

C. A. Guderjahn (Univ. of Cincinnati)
Surface Energy and Heat of Immersion of Solids
Univ. Microfilms (Ann Arbor, Mich.) Order No. 61-6693
Dissertation Abstr. 22, 3005 (1962)
Chem. Abstr. 57 2932

R. M. Barrer and B. E. F. Fender (Imp. Coll., London)
The Diffusion and Sorption of Water in Zeolites. I. Sorption
Phys. and Chem. Solids 21, 1-11 (1961)
Chem. Abstr. 56 5423

A. R. Burkin and G. Halsey (Imp. Coll. Sci. and Technol., London)
Chemisorption at Solid-Liquid Interfaces
Nature 191, 348-9 (1961)
Chem. Abstr. 56 5424

M. M. Dubinin (Inst. Phys. Chem., Acad. Sci. USSR, Moscow)
Theory of Physical Adsorption and Practical Use of Sorbents
Izv. Akad. Nauk Arm. SSR, Khim. Nauki 13, 377-85 (1960)
Chem. Abstr. 57 86

S. Kachanak (Slovenska vysoka skola tech., Bratislava, Czech.)
Kinetics of Adsorption on Porous Adsorbents
Chem. Zvesti 14, 247-57 (1960)
Chem. Abstr. 54 21923

H11f. SOLID-GAS INTERFACE
(ALPHABETICALLY BY ADSORBING SOLID)

M. Gery, J. Lenoir, and C. Eyraud
Chemisorption of Water on Alumina
Compt. Rend. 254, 128-9 (1962)
Chem. Abstr. 56 12337

A. Bielanski and M. Burk (Akad. Gorniczo-Hutnicza, Krakow, Poland)
Kinetics of Sorption of Water Vapor on Active Aluminum Oxide
Zeszyty Nauk. Akad. Gorniczo-Hutniczej, Ceram. No. 1, 97-106 (1956)
Chem. Abstr. 53 21031

R. T. Johansen and H. N. Dunning (U.S. Bur. of Mines)
Water-Vapor Adsorption on Clays
Clays, Clay Minerals, Proc. Natl. Conf. Clays, Clay Minerals, 6th,
Berkeley, 249-58 (1957) (Pub. 1959)
Chem. Abstr. 53 18590

R. T. Martin (Massachusetts Inst. of Technol.)
Water-Vapor Sorption on Kaolinite: Hysteresis
Clays, Clay Minerals, Proc. Natl. Conf. Clays, Clay Minerals, 6th,
Berkeley, 259-78 (1957) (Pub. 1959)
Chem. Abstr. 53 3633; 53 18590

M. Takizawa (Radiation Chem. Lab. Tokyo)
Mechanism of Water-Vapor Adsorption on Bentonite
J. Sci. Research Inst. (Tokyo) 54, 313-22 (1960)
Chem. Abstr. 55 10013

L. Juhasz
Water-Vapor Adsorption Isotherms of Clays
Acta Geol. Acad. Sci. Hung. 6, 345-64 (1962)
Chem. Abstr. 58 1927

Y. A. Zarif'yants, V. F. Kiselev, and G. G. Fedorov (State Univ.,
Moscow)
Chemical Adsorption of Oxygen on a Freshly Formed Graphite Surface
Zhur. Fiz. Khim. 35, 1885-6 (1961)
Chem. Abstr. 56 39

M. C. Cannon, W. R. Grimes, W. T. Ward, and G. M. Watson (Oak Ridge
Natl. Lab.)
Adsorption of Xenon and Argon on Graphite
Nucl. Sci. Eng. 12, 4-9 (1962)
Chem. Abstr. 57 13290

F. J. Salzano and A. M. Eshaya (Brookhaven Natl. Lab.)
Sorption of Xenon in High-Density Graphite at High Temperatures
Nucl. Sci. Eng. 12, 1-3 (1962)
Chem. Abstr. 57 13199

V. R. Linde
Adsorbing Properties of the Spinel CoMn_2O_4 and MnCo_2O_4 , and of the
Oxides Mn_3O_4 and Co_3O_4
Doklady Akad. Nauk SSSR 127, 1249-52 (1959)
Chem. Abstr. 54 21927

D. S. MacIver and H. H. Tobin Jr. (Gulf Research & Develop. Co.)
The Chemisorption of Gases on Cobalt Oxide Surfaces at Low Temperatures
J. Phys. Chem. 65, 1665-71 (1961)
Chem. Abstr. 56 959

D. S. MacIver and H. H. Tobin (Gulf Research and Develop. Co.)
Physical Adsorption on Chemisorbed Films
J. Phys. Chem. 64, 683-6 (1960)
Chem. Abstr. 54 20407

K. Tarama, S. Teranishi, and K. Hattori (Univ. Kyoto)
Adsorption and Desorption of Oxygen, Carbon Monoxide, and Carbon
Dioxide on Chromic Oxide
Nippon Kagaku Zasshi 81, 1665-9 (1960)
Chem. Abstr. 55 6985

G. R. Pulliam (Douglas Aircraft Co., Inc.)
Influence of Surface on Ceramic Mechanical Properties
U. S. Dept. Com., Office Tech. Serv., P B Rept. 161,309 (1959)
Chem. Abstr. 55 22750

K. S. Shatenirov and S. F. Lozitskaya
Chemisorption of SO_2 on Oxides on Heating. I.
Izvest. Akad. Nauk Kirgiz. SSR, Ser. Estestven. i Tekh. Nauk 2, No. 11
79-89 (1960)
Chem. Abstr. 55 21750

D. M. Speros and L. J. Schupp (Gen. Elec. Co., Nela Park)
Surface Phenomena During the Interaction between MgO (s) and Various
Gases at Elevated Temperatures
Phys. and Chem. Solids 15, 157-66 (1960)
Chem. Abstr. 55 11026

L. H. Germer and C. D. Hartman (Bell Telephone Labs.)
Structures of Monolayers of Adsorbed Gases
Phys. and Chem. Solids 14, 75-6 (1960)
Chem. Abstr. 55 11026

K. Hauße (Kalle Akt.-Ges. Wiesbaden-Biebrich, Ger.)
The Mechanism of Chemisorption of Gases on Oxides
Z. Elektrochem. 65, 321-7 (1961)
Chem. Abstr. 56 960

J. Horiuchi (Hokkaido Univ., Sapporo)
The Heterogeneous Model of the Surface of Adsorbents
J. Research Inst. Catalysis, Hokkaido Univ. 9, 108-29 (1961)
Chem. Abstr. 56 9450

Y. Kubokawa, I. Matsuura, and O. Toyama
The Chemisorption of Oxygen on Promoted Oxides of Nickel and Zinc
Bull. Univ. Osaka Prefect. Ser. A9, No. 2, 45-50 (1961)
Chem. Abstr. 55 25423

G. Sandstede (Johann-Wolfgang-Goethe Univ., Frankfurt/Main, Ger.)
Energy Evaluation of Adsorption Isotherms, Applied to the Adsorption
of Nitrogen and Argon on Galena
Z. physik. Chem (Frankfurt) 29, 99-119 (1961)
Chem. Abstr. 56 38

I. E. Neimark, R. Y. Sheinfain, and A. I. Kazantseva
Role of the Chemical Nature of the Surface of the Synthetic and
Natural Sorbents in Adsorption
Prirodnye Mineral. Sorbenty, Akad. Nauk Ukr. SSR, Otdel. Khim. i
Geol. Nauk, Trudy Soveshchaniya, Kiev, 52-62 (1958) (Pub. 1960)
Chem. Abstr. 55 9699

L. Bewilogua, M. Knorn, and H. Zimmer
Adsorption Measurements at Low Temperature
Monatsber. deut. Akad. Wiss. Berlin 1, No. 11, 660-7 (1959)
Chem. Abstr. 54 19082

S. V. Starodubtsev, S. A. Ablyayev, S. E. Ermatov, and U. U. Pulatov
Changes of Adsorption Capability of Silica Gel Under the Influence of
High-Frequency Discharges
Izv. Akad. Nauk Uz. SSR, Ser. Fiz.-Mat. Nauk, No. 6, 77-8 (1961)
Chem. Abstr. 57 2879

M. Folman (Israel Inst. Technol., Haifa)
Infrared Studies of NH_3 Adsorption on Chlorinated Porous Vycor Glass
Trans. Faraday Soc. 57, 2000-6 (1961)
Chem. Abstr. 57 88

I. P. Lychkin, Z. M. Rizov, and O. M. Todes
Measuring the Dynamics of Sorption and Desorption of Moisture by
Activated Silica by the Thermal Method
Zhur. Priklad. Khim. 34, 1225-31 (1961)
Chem. Abstr. 50 10478; 56 37

S. Anderson and D. D. Kimpton (Anderson Phys. Lab.)
Some Phenomena Related to the Hydrophobicity of Silicate Glasses
J. Am. Ceram. Soc. 43, 484-8 (1960)
Chem. Abstr. 54 23235

A. V. Bondarenko, V. F. Kiselev, and K. G. Krasil'nikov (M. V. Lomonosov State Univ., Moscow)
Composition of Products of Thermal Dehydration of Silica and the
Properties of its Dehydrated Surface
Kinetika i Kataliz 2, 590-8 (1961)
Chem. Abstr. 56 9466

M. M. Tagieva and V. F. Kiselev (M. V. Lomonosov State Univ., Moscow)
Effect of Gamma-Radiation on the Properties of the Surface of Silica
Zhur. Fiz. Khim. 35, 1381-2 (1961)
Chem. Abstr. 52 6889; 56 9449

W. Stoeber and M. Arnold (Max. Planck Ges., Goettingen, Ger.)
The Beilby Layer on the Surfaces of Quartz Powder
Beitr. Silikose-Forsch., Sonderband 4, 73-82 (1960) (Pub. 1961)
Chem. Abstr. 57 3087

L. T. Zhuravlev and A. V. Kiselev (Inst. Phys. Chem. Acad Sci. USSR, Moscow)
Investigation of the Hydroxyl Coating of Silica Gel by the Method of
Deuterium Exchange, and the Adsorption of Light and Heavy Water
Vapors
Kolloidn. Zh. 24, No. 1, 22-9 (1962)
Chem. Abstr. 57 87

K. Miyata and T. Kuwahara (Ind. Research Inst., Osaka)
Adsorption of Water Vapor on Finely Powdered Silica
Nippon Kagaku Zasshi 81, 353-6 (1960)
Chem. Abstr. 55 7983

M. J. Rand (Bell Telephone Labs., Inc.)
The Adsorption of Water Vapor by Porous Glass
J. Electrochem. Soc. 109, 402-8 (1962)
Chem. Abstr. 57 87

D. J. C. Yates (Columbia Univ.)
Infrared Studies of the Surface Hydroxyl Groups on Titanium Dioxide,
and of the Chemisorption of Carbon Monoxide and Carbon Dioxide
J. Phys. Chem. 65, 746-53 (1961)
Chem. Abstr. 56 2905

L. Spenadel (Univ. of Cincinnati)
Adsorption of Water on Titanium Dioxide
Univ. Microfilms (Ann Arbor, Mich.), Order No. 61-6696
Dissertation Abstr. 22, 3011 (1962)
Chem. Abstr. 57 2878

R. D. Murley (Brit. Titan Prod., Ltd., Billingham, Engl.)
Some Aspects of the Physical Chemistry of Titanium Pigment Surfaces
J. Oil & Colour Chemist's Assoc. 45, 16-27 (1962)
Chem. Abstr. 56 11743

F. Schytil and H. Schwalb (Metallgesellschaft Akt.-Ges., Frankfurt/
Main, Ger.)
Dependence of the Catalytic Oxidation of Sulfur Dioxide on the Particle
Size of the Catalyst in Fixed and Agitated Beds
Chem. Eng. Sci. 14, 367-74 (1961)
Chem. Abstr. 55 19373

A. G. Nasini, G. Saini, and F. Ricca (Univ. Turin, Italy)
Adsorption of Gases on Clean Metal Surfaces. Kinetics of Absorption,
(Fine structure) Heterogeneity of Surfaces, and Active Centers
Actes intern. congr. catalyse, 2 Paris, 1, 241-58 (1960) (Pub. 1961)
Chem. Abstr. 55 22993

Z. K. Enikeev, L. Y. Margolis, and S. Z. Roginskii
Effect of the Surface Charge of Zinc Oxide on the Rate of Chemisorp-
tion of Oxygen
Doklady Akad. Nauk SSSR 129, 372-5 (1959)
Chem. Abstr. 55 25424

Y. Kubokawa (Univ. Osaka Prefecture, Osaka)
Chemisorption of Hydrogen on Zinc Oxide. I. Rate of Desorption
and Adsorption Isotherm
Bull. Chem. Soc. Japan 33, 546-50 (1960)
Chem. Abstr. 54 20410

V. Kesavulu and H. A. Taylor (New York Univ.)
Sites for Hydrogen Chemisorption on Zinc Oxide
J. Phys. Chem. 64, 1124-31 (1960)
Chem. Abstr. 55 6986

R. Glemza and R. J. Kokes (Johns Hopkins Univ.)
Transient Species in Oxygen Take-Up by Zinc Oxide
J. Phys. Chem. 66, 566-8 (1962)
Chem. Abstr. 56 14957

Y. Kubokawa (Univ. Osaka Prefecture, Osaka)
Monoxide Chemisorption on Zinc Oxide
Bull. Chem. Soc. Japan 33, 555-9 (1960)
Chem. Abstr. 54 20411

K. Laws and V. R. Honnold (Naval Ordnance Test Sta., China Lake, Calif.)
A Kinetic Study of Oxygen Chemisorption on PbS Layers
U. S. Dept. Com., Office Tech. Serv., PB Rept. 144876 (1958)
Chem. Abstr. 56 958

C. H. Pitt and M. E. Wadsworth (Univ. of Utah)
A Kinetic Study of CO₂ Desorption from Thoria
U. S. At. Energy Comm. AECU-3759 (1958)
Chem. Abstr. 55 21751

M. S. Ostrikov (State Univ., Rostov)
Nonreproducibility of Hysteresis During Vapor Sorption
Prirodnye Mineral. Sorbenty, Akad. Nauk Ukr. SSR, Otdel. Khim. i Geol.
Nauk, Trudy Soveshchaniya, Kiev, 172-6 (1958) (Pub. 1960)
Chem. Abstr. 55 6985

- L. G. Tensineyer and M. E. Wadsworth
Quantitative Determination of Adsorbed Sulfates on Thorium Oxide by
Means of Infrared Spectroscopy
U.S. At. Energy Comm. AECU-4076 (1959)
Chem. Abstr. 54 21927
- R. S. Hansen (Iowa State Univ.)
The Virial Treatment of the Interaction of Gas Molecules with
Solid Surfaces
J. Phys. Chem. 63, 743-5 (1959)
Chem. Abstr. 53 19514
- B. J. Wood and H. Wise (Stanford Res. Inst.)
The Interaction of Atoms with Solid Surfaces
U.S. Dept. Com., Office Tech. Serv., P B Rept. 156,822 (1960)
Chem. Abstr. 58 5046
- J. M. Honig (Massachusetts Inst. of Technol.)
Physical Adsorption Processes and their Relation to Order-Disorder
Theory
Trans. N. Y. Acad. Sci. 22, 313-22 (1960)
Chem. Abstr. 55 6983
- D. P. Timofeev and I. T. Erashko
Kinetics for the Sorption of Water Vapor on Type-A Zeolites
Izv. Akad. Nauk SSSR, Otd. Khim. Nauk, 1192-7 (1961)
Chem. Abstr. 58 1927
- S. S. Minn, S. Offret, and B. Vodar (Lab. Hautes Pressions, C.N.R.S.,
Bellevue, France)
Disturbances Caused by Hg in Studying the Adsorption of Gases on
Very Thin Layers of Pt.
Compt. rend. 252, 3445-7 (1961)
Chem. Abstr. 55 22994
- J. Toth (Oil Sci. Lab., Nagykanizsa, Hung.)
Gas Adsorption on Solid Surfaces of Inhomogeneous Activity. IX.
Magy. Kem. Folyoirat 68, 377-81 (1962)
Chem. Abstr. 58 41; 58 8427

V. A. Zabelin (State Univ., Saratov)
Sorption-Structural Properties of Opaque Rocks
Zh. Prikl. Khim. 35, 962-9 (1962)
Chem. Abstr. 57 6650

J. G. Parker (Johns Hopkins Univ.)
Effect of Adsorption on Acoustic Boundary-Layer Losses
J. Chem. Phys. 36, 1547-54 (1962)
Chem. Abstr. 57 5320

S. Tsuchihashi (Univ. Kobe)
The Glass Surface
Koroido To Kaimen-Kasseizai 3, 24-31 (1962)
Chem. Abstr. 57 11885

O. Sinanoglu and K. S. Pitzer (Univ. of California)
Interactions between Molecules Adsorbed on a Surface
J. Chem. Phys. 32, 1279-88 (1960)
Chem. Abstr. 54 21925

K. Ishida, J. Shimokawa, and Y. Yamamoto
Effect of the Surface Diffusion on the Separation Efficiency
Trans. Faraday Soc. 57, 2018-26 (1961)
Chem. Abstr. 57 89

U. A. Asanov and N. A. Shishakov
Surface Structure of True Solids
Vestn. Akad. Nauk Kirg. SSR No. 1, 39-43 (1961)
Chem. Abstr. 56 15009

Hilg. REACTIVITY OF PARTICLES, HEAT OF WETTING
(See also Hile)

A. Krause and S. Zioliński (Univ. Poznań, Poland)
The Number of Active Centers on the $\text{Al}(\text{OH})_3$ Surface
Roczniki Chem. 33, 845-7 (1959)
Chem. Abstr. 54 2878

E. V. Ballou, R. T. Barth, and R. A. Flinn (Gulf Research & Development Co.)
Effect of Fluorination on the Surface Acidity of Catalytic Alumina
and the Loss in Acidity Due to Water-Vapor Adsorption
J. Phys. Chem. 65, 1639-41 (1961)
Chem. Abstr. 56 2917

M. M. Egorov, V. F. Kiselev, K. G. Krasil'nikov, and Y. P. Simanov
(M.V. Lomonosov State Univ., Moscow)
Influence of Phase Composition of the Adsorbents in the System
 $\text{Al}_2\text{O}_3\text{-H}_2\text{O}$ on their Surface Properties
Izvest. Vysshikh Ucheb. Zavedenii, Khim. i Khim. Tekhnol. 2, No. 3,
360-5 (1959)
Chem. Abstr. 54 4105

D. Stefanescu and N. Tuchel
Color Reactions of Colloidal Clays
Farmacia (Bucharest) 8, 19-25 (1960)
Chem. Abstr. 22141

M. A. Kaliko
Formation and Nature of the Active Centers in Alumino-Silicate
Catalysts
Zhur. Fiz. Khim. 33, 2517-20 (1959)
Chem. Abstr. 54 21964

W. H. Wade and N. Hackerman (Univ. of Texas)
Heats of Immersion. II. Calcite and Kaolinite, Effect of Pretreatment
J. Phys. Chem. 63, 1639-41 (1959)
Chem. Abstr. 53 16677; 54 9480

V. S. Komarov, N. F. Ermolenko, and V. I. Varlamov
Production of a Highly Active, Mechanically Stable Clay-Hydroxide
Adsorbent by Acid-Treatment Activation of Clays
Doklady Akad. Nauk SSSR 139, 665-8 (1961)
Chem. Abstr. 56 2163

M. J. Ridge, H. Surkevicius, and A. A. Milne (Commonwealth Sci. and
Ind. Research Organization, Highett, Australia)
Reactivity of Calcium Sulfate Hemihydrate
Nature 191, 704-5 (1961)
Chem. Abstr. 56 5634

A. Swinarski and J. Siedlewski
Influence of Pore Dimensions on Catalytic Activity of Carbon
Activated by Oxygen for Oxidation of Hydrogen Sulfide
Actes Congr. intern. catalyse, 2 Paris 2, 2345-56 (1960) (Pub. 1961)
Chem. Abstr. 55 26622

A. E. Agronomov and A. P. Mishchenko
Dependence of the Catalytic Activity on the Porosity of the Co-SiO_2
Catalyst. IV.
Vestnik Moskov. Univ., Khim. Ser. II, 15, No. 1, 35-9 (1960)
Chem. Abstr. 52 63; 54 20446

I. Y. Babkin and A. V. Kiselev (Univ., Moscow)
Increase in the Energy of Adsorption on Compressing Nonporous
Silica Particles with Chemically Modified Surface
Kolloidn. Zh. 24, 648-50 (1962)
Chem. Abstr. 58 9649

O. Szabadka and F. Schmidt (Univ. Chem. Ind., Veszprem, Hung.)
Chemical Activity of Silicate-Skeleton Catalysts
Veszpremi Vegyipari Egyet. Közleményei, 5, 303-10 (1961)
Chem. Abstr. 57 14466

V. Gottardi and G. Bonetti
Study of Differently Activated Surfaces of Glasses by Means of a
Micrographic Process
Vetro Silicati 5, No. 29, 13-20 (1961)
Chem. Abstr. 56 13824

E. Leignitz, W. Hager, and I. Prufer (Inst. f. Verfahrenstechnik,
Leipzig, Ger.)
Adsorption Capacity of Silica Gels from Heat Measurements
J. prakt. Chem. 9, 201-9 (1959)
Chem. Abstr. 54 16987

E. F. Nekryach and Z. A. Samchenko (Inst. Gen. and Inorg. Chem, Kiev)
Water Vapor Sorption and Heat of Wetting of Silica Gels
Kolloid. Zhur. 22, 293-6 (1960)
Chem. Abstr. 55 8999

W. H. Wade and N. Hackerman (Univ. of Texas)
Heats of Immersion. V. The $\text{TiO}_2\text{-H}_2\text{O}$ System--Variations with
Particle Sizes and Outgassing Temperature
J. Phys. Chem. 65, 1681-3 (1961)
Chem. Abstr. 56 75

A. A. Balandin, A. A. Tolstopyatova, and W. Strzyzewski (State
Univ., Moscow)
The Catalytic Activity of Tungsten Pentoxide
Doklady Akad. Nauk SSSR 134, 625-8 (1960)
Chem. Abstr. 56 2917

B. M. Fabuss (Dominion Tar & Chem Co. Ltd., Montreal, Can.)
The Effect of TiO_2 and SnO_2 Promoters on V_2O_5 Catalysts
Actes intern. Congr. catalyse, 2 Paris, 2, 2561-6 (1960) (Pub. 1961)
Chem. Abstr. 55 23008

G. M. Zhabrova, V. I. Vladimirova, and E. V. Egorov (Inst. Phys.
Chem., Acad. Sci. USSR, Moscow)
Effect of Sorbed Impurities on the Catalytic Properties of Zinc Oxide
Zhur. Fiz. Khim. 33, 2442-50 (1959)

V. D. Kuznetsov
The Surface Energy of Solids
Trudy Sibir. Fiz-Tekh. Inst., Tomsk. Univ. No. 34, 55-79 (1955)
Referat. Zhur., Khim., Abstr. No. 53758 (1956)
Chem. Abstr. 53 3820

J. Koutecky
Quantum Chemistry of the Crystal Surface
Kinetika i Kataliz 2, 319-39 (1961)
Chem. Abstr. 56 83

Y. Yoneda and S. Makishima (Univ. Tokyo)
The Role of Surface Layers of an Oxide Catalyst
Actes intern. congr. catalyse, 2 Paris, 2, 2103-10 (1960) (Pub. 1961)
Chem. Abstr. 55 23009

- V. D. Frechette (Alfred Univ.)
Solid State Reactivity in Relation to Progress in Refractory
Technology
Trabajos reunion intern. reactividad solidos, 3, Madrid, 2, 189-209
(1956) (Pub. 1958)
Chem. Abstr. 53 18426
- B. R. Puri, J. Singh, D. D. Singh, and L. R. Sharma (Univ. Panjab,
India)
Surface Chemical Reactivity and Surface Area of Suspensoids. I.
Methods of Estimation
Research Bull. Panjab Univ. No. 135, 1-7 (1958)
Chem. Abstr. 50 16267; 53 16653
- P. P. Ryazantsev and L. M. Shcherbakov (Mech. Inst., Tula)
The Effect of Comminution on the Solubility and the Heat of Solution
Kolloid Zhur. 21, 464-69 (1959)
Chem. Abstr. 54 7293
- G. Ehrlich (Gen. Elec Co.)
Molecular Dissociation and Reconstitution on Solids
J. Chem. Phys. 31, 1111-26 (1959)
Chem. Abstr. 54 8253
- O. M. Potorak (State Univ., Moscow)
Thermodynamics of Crystalline Catalysts
Zhur. Fiz. Khim. 33, 2524-38 (1959)
Chem. Abstr. 54 21964
- K. Kawakita (Kink Univ., Fuse)
Chemistry of Fine Powders
Koroido To Kaimen-Kasseizai 2, 433-40, 629-33 (1961)
Chem. Abstr. 57 13189
- J. A. Hedvall (Goteborg Univ., Sweden)
Factors Affecting the Surface Activity of Solids
Kinetika i Kataliz 3, 3-12 (1962)
Chem. Abstr. 57 11905
- F. A. P. Maggs and P. H. Schwabe
Recording Calorimeter for the Measurement of Heats of Wetting, Mixing,
or Solution
J. Sci. Instr. 37, No. 2, 60-4 (1960)
Chem. Abstr. 54 20365

H11r. INTERNAL STRAINS IN PARTICLES

H. Arnold (Max-Planck-Inst. Silikatforschung, Wurzburg, Ger.)
Vanishing of Internal Strains on the Formation of Acicular In-
homogeneities in Synthetic Spinel
Z. Krist. 114, 23-7 (1960)
Chem. Abstr. 54 21914

H12. PROPERTIES OF ASSEMBLIES OF PARTICLES

H12a. SIZE DISTRIBUTION

W. Fritz

Problems in the Determination of Particle Sizes and in the Graphic
Treatment of Particle Size Distribution according to Rosin, Rammler,
and Sperling

Chemiker Ztg. 83, 819-23 (1959)

Chem. Abstr. 54 9374

R. R. Irani (Monsanto Chem. Co.)

The Interpretation of Abnormalities in the Log-Normal Distribution
of Particle Size

J. Phys. Chem. 63, 1603-7 (1959)

Chem. Abstr. 54 8222

A. Masson (Univ. Liege, Belg.)

Search for a Precise Definition of the Characteristic Dimension
of a Group of Heterogeneous Particles or Grains. Present State
of the Question

Rev. matériaux construct. et trav. publ., C, No. 524, 123-31 (1959)

Chem. Abstr. 53 17632

H. E. Rose (Univ. London)

The Problem of Particle-Size Measurement

Chem. Ing. Tech. 31, 183-91 (1959)

Chem. Abstr. 53 10858

D. P. Ames and R. R. Irani (Monsanto Chem. Co.)

The Agreement Between Independent Methods for Particle-Size-Distribu-
tion Measurements on Finely Divided Powders Including Phosphates

J. Phys. Chem. 63, 531-4 (1959)

Chem. Abstr. 53 15705

H. F. Fischmeister, C. A. Blande (Metallografiska Inst., Stockholm),
and S. Palmqvist

A Comparative Study of Methods for Particle-Size Analysis in the
Sub-Sieve Range

Powder Met. 7, 82-119 (1961)

Chem. Abstr. 56 14930

A. Winkel (Staubforschungsinstit., Bonn, Ger.)

Practical Problems in Dust Measurement

Staub 22, No. 3, 77-9 (1962)

Chem. Abstr. 57 4488

E. Mikailiene

Suspension Preparation for Determination of Granulometric Composition
of Clay

Mokslas ir Technika, No. 4, 39-40 (1960)

Chem. Abstr. 55 13798

E. V. Donat

Determination of Particle Size with Gravimetric Separators (Elutriators)

Prom. Ventilyatsiya, Vsesoyuz. Nauch.-Issledovatel. Inst. Okhrany

Truda, Sbornik Statei, No. 6, 67-77 (1957)

Chem. Abstr. 52 25389

G. A. H. Elton and J. B. Peace (Battersea Polytechnic, London)

The Determination of Particle-Size Distributions in Suspensions
from Measurements of Sedimentation Potentials

Proc. Intern. Congr. Surface Activity, 2nd, London, 4, 177-82 (1957)

Chem. Abstr. 50 5366; 54 5211

Y. Nishimura, R. Yamamoto, and R. Naito (Govt. Ind. Res. Inst, Nagoya)

Determination of Particle Size Distribution

Nagoya Kogyo Gijutsu Shikensho Hokoku 7, 281-4 (1958)

Chem. Abstr. 57 16163

N. A. Figurovskii and T. B. Gavrilova (M.V. Lomonosov State Univ.,
Moscow)

Influence of the Concentration of a Dispersed Phase on the Complete
Characterizing of the Dispersed Suspension

Izvest. Vysshikh Ucheb. Zavedenii, Khim. i Khim. Tekhnol. 3, 295-300
(1960)

Chem. Abstr. 54 21934

J. M. Dalla Valle, J. P. McBride, V. D. Allred, and E. V. Jones
(Oak Ridge Natl Lab.)

Application of Hindered Settling to Particle-Size Measurement

U.S. At. Energy Comm. ORNL-2565 (1958)

Chem. Abstr. 53 7720

J. J. Hermans and A. M. Ryke (Univ. of Syracuse)

Distribution of Particle Size in Colloidal Silica by Ultra-Centrifu-
gation

J. Colloid Sci. 13, 508-9 (1958)

Chem. Abstr. 53 1891

- K. T. Whitby and A. B. Algren (Univ. of Minnesota)
Particle-Size Analysis of Subsieve Particulates by Centrifugal
Sedimentation
U.S. At. Energy Comm. TID-7568, Pt. 3, 67-82 (1958)
Chem. Abstr. 53 16610
- N. A. Figurovskii and T. B. Gavrilova (M.V. Lomonosov Univ.,
Moscow)
Sedimentometric Analysis of Highly Dispersed Suspensions by Means
of the Centrifuge Balance
Kolloid. Zhur. 21, 354-8 (1959)
Chem. Abstr. 54 42
- W. Heller (Wayne State Univ.)
The Determination of Particle Sizes and Size Distributions by Means
of Light Scattering
U.S. At. Energy Comm. TID-7568, Pt. 3, 3-10 (1958)
Chem. Abstr. 53 17632
- A. Spiliadis, D. Bretcann, and V. Cornea
Method for Determining Particle-Size-Distribution Curves for Dyes
Rev. Chim. (Bucharest) 12, 220-3 (1961)
Chem. Abstr. 57 5309
- R. F. Pilgrim (Dept Mines and Tech. Surveys, Ottawa)
Review and Evaluation of Methods of Particle Size Analysis. I. The
Definition of Terms and Classification of Sizing Methods. II. Sieve
Analysis
Can. Dept. Mine and Tech. Surveys, Mines Branch No. IC 106 (1958)
Chem. Abstr. 53 11904
- M. Yamamoto, H. Imamura, and A. Okutani (Fukuda Metal Powder Co.,
Kyoto)
Sieving Tests of Metal Powders
Funtai Oyobi Funmatsuyakin 2, 170-6 (1958)
Chem. Abstr. 54 7
- J. W. Mullin
Analysis of Sieve Test Data
Ind. Chemist 36, 272-8 (1960)
Chem. Abstr. 54 17988

I. Y. Slonim

Particle-Size Determination by the Light-Scattering Method.

I. Formulas and Nomograms for the Calculation of Particle Size
by Optical Density and Scattered Light Intensity

Optika i Spektroskopiya 8, No. 1, 98-108 (1960)

Chem. Abstr. 55 19419

H. H. Weber (Farbenfabriken Bayer A.-G., Leverkusen, Ger.)

Light Scattering and Particle-Size Distribution of Particles.

II. Experimental Part

Kolloid-Z. 188, 40-4 (1963)

Chem. Abstr. 58 13175

E. J. Meehan (Univ. of Minnesota)

Determination of Particle Size by Higher-Order Tyndall Spectra

J. Polymer Sci. 27, 590-1 (1958)

Chem. Abstr. 53 9779

A. I. Michaels (Sylvania Elec. Prods., Inc.)

Turbidimetric Particle Size Distribution Theory--Application to
Refractory Metal and Oxide Powders

Am. Soc. Testing Materials, Spec. Tech. Publ. 234, 207-43 (1958)

Chem. Abstr. 54 41

I. Y. Slonim

A Nomogram for the Calculation of the Diameter of Particles from
Turbidity Using the Mie Equation

Optika i Spektroskopiya 8, No. 2, 255-7 (1960)

Chem. Abstr. 55 19419

R. J. Gledhill (Eastman Kodak Co.)

Particle-Size Distribution Determination by Turbidimetry

J. Phys. Chem. 66, 458-63 (1962)

Chem. Abstr. 56 14930

S. Sekido and T. Goto (Matsushita Elec. Ind. Co.)

Measurement of Particle Size Distribution of Lead Oxide Powder by
Photoelectric Colorimetry

Natl. Tech. Rept. 5, 135-9 (1959)

Chem. Abstr. 53 21002

A. F. Stevenson (Wayne State Univ.), W. Heller, and M. L. Wallach
Theoretical Investigations on the Light Scattering of Colloidal
Spheres. XI. Determination of Size Distribution Curves from
Spectra of the Scattering Ratio or from Depolarization Spectra
J. Chem. Phys. 34, 1789-95 (1961); *ibid.* 971-9
Chem. Abstr. 54 16111; 56 10948

A. M. Gurvich (N.A. Semashko Chem.-Pharm. Plant, Moscow)
Determination of the Granulometric Composition of Poly-Dispersed
Crystalline Powders
Zavodskaya Lab. 23, 827 (1957)
Chem. Abstr. 54 8169

M. Arnold, P. E. Morrow, and W. Stoeber (Max-Planck-Ges., Goettingen,
Ger.)
Comparison of Particle-Size Distributions of Solid Dusts Determined
by a High-Voltage Separator and the Electron Microscope
Kolloid-Z. 181, No. 1, 59-65 (1962)
Chem. Abstr. 57 1585

A. M. Gutkin, N. G. Sushkin, V. S. Fadeeva, and E. A. Shcherbakova
A Study of the Distribution of Fine Particles by the Use of the
Electron Microscope
Sbornik Trudov, Vsesoyuz. Nauch.-Issledovatel. Inst. Novykh Stroitel.
Materialov, 130-61 (1960)
Chem. Abstr. 56 8044

I. Westerboer (Univ. Munster, Ger.)
Improvements in the Routine Measurement of Particle-Size Distribu-
tions for Fine Dusts Sampled with a Thermal Precipitator and
Using an Electron Microscope
Staub 20, 361-4 (1960)
Chem. Abstr. 55 22942

K. Iwamoto (Japan At. Energy Research Inst., Tokai)
UO₂ Particle Size Distribution as Determined by Radioactivation
Funtai Oyobi Funmatsu Yakin 7, 197-200 (1960)
Chem. Abstr. 56 9656

M. Cowan, Jr. (Sandia Corp.)
Technique for Obtaining Particle Activity and Size Distribution
U.S. At. Energy Comm. SCR-296 (1961)
Chem. Abstr. 55 17288

C. P. Ross (E. I. du Pont de Nemours, Inc.)
Particle Size Analysis by Gamma-Ray Absorption
Anal. Chem. 31, 337-9 (1959)
Chem. Abstr. 53 9885

A. Knappwost (Univ. Tübingen, Ger.)
A New Magnetic Method for Particle-Size Determination in the
Angstrom Region
Z. Elektrochem. 63, 278-83 (1959)
Chem. Abstr. 52 6873; 53 8748

V. G. Drozin and V. K. LaMer (Columbia Univ.)
The Determination of the Particle Size Distribution of Aerosols by
Precipitation of the Charged Particles
J. Colloid Sci. 14, 74-90 (1959)
Chem. Abstr. 53 8766

A. Goetz (California Inst. of Technol.)
The Aerosol Spectrometer--A New Instrument for the Analysis of
Airborne Particles in the Submicron Range
Public Works 90, No. 2, 91-3 (1959)
Chem. Abstr. 53 8729

S. Hayakawa, T. Tomotsu, R. Takagi, and S. Makishima (Univ. Tokyo)
Servo-Controlled Recording Sedimentation Analyzer
Kogyo Kagaku Zasshi 60, 1249-52 (1957)
Chem. Abstr. 53 13681

W. Friedrich (Tech. Hochschule, Braunschweig, Ger.)
Particle Size Analyses with the Sedimentation Balance
Staub 19, 281-7 (1959)
Chem. Abstr. 55 25318

E. Loos (Staub- und Silikosebekämpfungsstelle Steinkohlenbergbauver-
eins, Essen, Ger.)
The Sedimentation Balance
Staub 19, 392-8 (1959)
Chem. Abstr. 55 25381

R. E. Vogel
New Sedimentation Balance. An Automatic Apparatus for Determining
Grain Size
Euro-Ceram. 10, No. 1, 11-14 (1960)
Chem. Abstr. 54 14811

- H. Gerstenberg
Determination of Particle-Size Distribution of Solid Material with
a Sedimentation Balance
Dechema Monograph. 31, 52-60 (1959)
Chem. Abstr. 54 16110
- E. S. Palik (Gen Elec. Co.)
Particle Size Measurements with an Improved Continuously Recording
Sedimentation Apparatus
Anal. Chem. 33, 956-9 (1961)
Chem. Abstr. 55 16025
- C. G. M. Slesser and R. Deens
Estimation of Particle Size: An Improved Werner Sedimentation
Apparatus
J. Appl. Chem. (London) 10, 62-5 (1960)
Chem. Abstr. 54 14813
- R. Dallendorfer and L. Langhammer
Fast Determination of Particle Distribution in Ceramic Raw Materials
Epitoanyag 12, 251-3 (1960)
Chem. Abstr. 56 9726
- G. Bergshoeff (Inst. Gezondheidstech. T.N.O., The Hague)
Determination of Particle-Size Distributions. II. The Pipet
Method of Andreasen-Esenwein
Chem. Weekblad 56, 709-16 (1960); ibid. 434-40
Chem. Abstr. 55 13002
- R. R. Irani and C. F. Callis (Monsanto Chem.Co.)
Accurate Particle-Size Distribution with Electroformed Sieves
Anal. Chem. 31, 2026-8 (1959)
Chem. Abstr. 54 6309
- N. Kleine
A Photoelectric Turbidimeter for Small Volumes of Liquid
Dechema Monograph. 31, 200-6 (1959)
Chem. Abstr. 53 20941
- E. Y. Zemlitskii (V. A. Malyshev Machinery Plant, Kharkov)
New Method of Dispersion Analysis by Centrifuging Highly Dispersed
Systems Suspended in a High-Viscosity Medium
Kolloidn. Zh. 23, 679-705 (1961)
Chem. Abstr. 56 14963

W. H. Coulter

Device for the Determination of Particles in Liquid Suspensions

Ger. 964,810 (5/29/57)

Chem. Abstr. 53 10861

W. S. Treffner and D. W. Robertson

Electronic Size Analysis in the Subsieve Size Range

Radex Rundschau, 55-69 (1962)

Chem. Abstr. 57 3244

L. V. Radushkevich, E. A. Leont'ev, and V. A. Kolganov

Semiautomatic Device for the Determination of the Particle Size

Distribution of Dispersed Systems

Zhur. Fiz. Khim. 35, 1153-5 (1961)

Chem. Abstr. 55 25588

M. A. Qaiyum and A. Ali (Osmania Univ., Hyderabad)

Particle-Size Distribution in the Clays of Andhra Pradesh. I. Pachegaon,

Chintryal, Srirangapur, and Shekhapur Clays

Trans Indian Ceram. Soc. 16, 111-25 (1957)

Chem. Abstr. 53 2561

L. Lecrivain

Effect of the Particle-Size Distribution of Grog on the Properties

of Sanitary Fireclay Bodies

Bull. Soc. Franc. Ceram. No. 52, 13-19 (1961)

Chem. Abstr. 56 5649

O. A. Orio and A. C. D'Onofrio

Distribution of Particle Size in Fluid Cracking Catalysts

Bol. inform. petrol. (Buenos Aires) No. 313, 269-75 (1959)

Chem. Abstr. 54 1835

M. Nakagaki, M. Yagyu, and H. Okamoto (Univ. Kyoto)

Particle-Size Distribution of Monodispersed Barium Sulfate Prepared

by the EDTA (ethylenediaminetetraacetic acid) Method

Yakugaku Zasshi 82, 1181-5 (1962)

Chem. Abstr. 57 15847

T. Nishida (Matsushita Elec. Ind. Co., Osaka)

Distribution of Particle Size in Manganese Dioxide Powder

Natl. Tech. Rept. 2, 1-4 (1956)

Chem. Abstr. 53 21002

J. F. Carpenter, C. W. Kuhlman, and R. A. Nelson (United Nuclear
Corp. Chemical Div.)
Characterization of UO_2 Powders
Quarterly Report No. 5, 10/10/61 to 1/10/62
Contract AT(40-1)-2699 (3/21/62)

H12b. PARTICLE PACKING, PACKING DENSITY, TAP DENSITY

B. V. Deryagin, N. N. Zakhavaeva, M. V. Talaev, and A. M. Lopatina
Equipment for Determining the Filtration Coefficient and Capillary
Flow in Porous and Disperse Solids
Trudy Inst. Fiz. Khim., Akad. Nauk SSSR No. 6 i Novye Metody Fiz.-
Khim. Issledovaniy No. 2, 123-30 (1957)
Chem. Abstr. 53 1

H. Haupt (VEB Jenapharm, Jena, Ger.)
Influence of the Structure of Real Porous Media on Flow and Fil-
tration
Chem. Tech. (Berlin) 10, 299-302 (1958)
Chem. Abstr. 53 3

R. Meldau (Gutersloh/Westf., Langer Veg, Ger.)
A Cell of the Closest Spherical Packing and Some of its Properties
Tonind.-Ztg. u. Keram. Rundschau 82, 466-8 (1958)
Chem. Abstr. 53 2697

T. F. Berry, W. C. Allen, and W. A. Hassett
Role of Powder Density in Dry-Pressed Ceramic Parts
Am. Ceram. Soc. Bull., 38, 393-400 (1959)
Ceram. Abstr. 1959 (10) 271
Chem. Abstr. 53 20728

R. W. Hagemeyer (Wyandotte Chem. Co.)
The Effect of Pigment Combination and Solids Concentration on Particle
Packing and Coated Paper Characteristics. I. Relation of Particle
Shape to Particle Packing
Tappi 43, 277-88 (1960)
Chem. Abstr. 54 18956

R. Aoki and Y. Mori (Yokohama Natl. Univ.)
The Bottom Pressure of Powder Packed in a Cylindrical Vessel
Kagaku Kogaku 24, 926-35 (1960)
Chem. Abstr. 55 8963

R. K. McGeary (Nuclear Materials and Equipment Corp.)
Mechanical Packing of Spherical Particles
J. Am. Ceram. Soc. 44, 513-22 (1961)
Chem. Abstr. 56 2168

R. W. Heckel (E. I. du Pont de Nemours & Co.)
Density-Pressure Relations in Powder Compaction
Trans. AIME 221, 671-5 (1961)
Chem. Abstr. 55 23241

T. Plaul
Ceramic Batch Properties in the Winkler Diagram
Silikat Tech. 13, 361-5 (1962)
Chem. Abstr. 58 12272

H12c. FLOW OF DRY PARTICLE ASSEMBLIES

D. Train

Some Aspects of the Property of Angle of Repose of Powders

J. Pharm. and Pharmacol. 10, Suppl. 127T-135T (1958)

Chem. Abstr. 53 6700

D. J. Craik and B. F. Miller

Flow Properties of Powders under Humid Conditions

J. Pharm. and Pharmacol. 10, Suppl. 136T-144T (1958)

Chem. Abstr. 53 6700

R. T. Fowler and F. A. Wyatt (Univ. of New South Wales, Australia)

Effect of Moisture Content on the Angle of Repose of Granular Solids

Australian J. Chem. Engrs. 1, No. 2, 5-8 (1960)

Chem. Abstr. 55 6061

F. A. Zenz (Polytech. Inst. of Brooklyn)

Effects of Particle Size Distribution on Saltation Velocity and Bin Flow

Univ. Microfilms (Ann Arbor, Mich.) L.C. Card No. Mic 61-1271

Dissertation Abstr. 22, 204-5 (1961)

Chem. Abstr. 55 20534

M. M. Benarie (Israel Inst. Biol. Research, Ness-Ziona)

Rheology of Granular Material. II. Method for the Determination of the Intergranular Cohesion.

Brit. J. Appl. Phys. 12, 514-18 (1961)

Bull. Research Council Israel Sec. F 8, 229 (1960)

Chem. Abstr. 57 1575

E. Awada, E. Nakajima, T. Morioka, Y. Ikegami, and M. Yoshizumi
(Sankyo Co., Tokyo)

Fluidity of Powders. IV. Method of Fluidity Measurement of Sticky Powders

Yakugaku Zasshi 80, 1657-60 (1960)

Yakuzaigaku 19, 119 (1959)

Chem. Abstr. 55 10803

E. Nakajima, T. Morioka, Y. Ikegami, and I. Tanaka (Sankyo Co, Tokyo)

Fluidity of Powders. VI. Effect of Particle Size and Surface Rugosity on Fluidity of Powders

Yakugaku Zasshi 81, 712-16 (1961)

Chem. Abstr. 55 10803; 55 22941

E. Nakajima (Sankyo Co., Tokyo)

Fluidity of Powders. VIII. Relation between Fluidity and Agglomeration

Yakugaku Zasshi 81, 1068-75 (1961)

Chem. Abstr. 55 22941; 56 11393

H12d. RHEOLOGY OF SOLID-FLUID SYSTEMS

J. G. Oldroyd
Complicated Rheological Properties
Rheol. Disperse Systems, Proc. Conf. Univ. Coll. Swansea, 1-15 (1957)
(Pub. 1959)
Chem. Abstr. 54 4110

S. G. Mason and W. Bartok (McGill Univ., Montreal, Can.)
The Behavior of Suspended Particles in Laminar Shear
Rheol. Disperse Systems, Proc. Conf. Univ. Coll. Swansea, 16-48
(1957) (Pub. 1959)
Chem. Abstr. 54 4110

O. L. Forgac and S. G. Mason (Pulp and Paper Research Inst. Can.
Montreal)
Particle Motions in Sheared Suspensions. IX. Deformation of Thread-
like Particles
J. Colloid. Sci. 14, 457-72 (1959)
Chem. Abstr. 53 7722; 54 4109

F. H. Garner, V. G. Jenson, and R. B. Keey
Flow Pattern Around Spheres
Trans. Inst. Chem. Engrs. (London) 37, 191 (1959)
Chem. Abstr. 54 9373

A. Jobling (Univ. Cambridge, Engl.) and J. E. Roberts
Dilatancy and Thixotropy
Rheol. Disperse Systems, Proc. Conf. Univ. Coll. Swansea, 127-38 (1957)
(Pub. 1959)
Chem. Abstr. 54 4110

C. van der Poel (Koninklijke-Shell-Lab., Amsterdam)
Rheology of Concentrated Dispersions
Rheol. Acta 1, 198-205 (1958)
Chem. Abstr. 53 19581

E. W. J. Mardles
Wetting and Dispersion Action of Liquids on Powders
Paint Technol. 22, 353-6 (1958)
Chem. Abstr. 53 3730

R. R. Myers (Lehigh Univ.)
Physical Stability of Dispersions; Basic Considerations
Advances in Chem. Ser. No. 25, 92-103 (1960)
Chem. Abstr. 54 19092

S. J. Gregg (Univ. Exeter, Engl.)
Preparation of Highly Disperse Solids
Kolloid-Z. 169, No. 1-2, 5-11 (1960)
Chem. Abstr. 54 14870

T. F. Ford (Dept. of Agr., Washington, D. C.)
Viscosity-Concentration and Fluidity-Concentration Relations for
Suspensions of Spherical Particles in Newtonian Liquids
J. Phys. Chem. 64, 1168-74 (1960)
Chem. Abstr. 55 6964

J. J. Chessick (Lehigh Univ.)
Colloidal Dispersions
Am. Ink Maker 39, No. 8, 33-5, 37, 62-4 (1961)
Chem. Abstr. 56 2022

F. Schultz-Grunow (Tech. Hochschule, Aachen, Ger.)
Contribution to Thixotropy
Progr. Intern. Res. Thermodyn. Transport Properties Papers Symp.
Thermophys. Properties, 2nd, Princeton, N.J., 718-27 (1962)
Chem. Abstr. 57 1575

D. G. Thomas (Univ. Cambridge, Engl.)
Transport Characteristics of Suspensions: Applications of Different
Rheological Models to Flocculated Suspension Data
Progr. Intern. Res. Thermodyn. Transport Properties Papers Symp.
Thermophys. Properties, 2nd, Princeton, N.J., 704-17 (1962)
Chem. Abstr. 57 4510

M. Joly (Inst. Pasteur, Paris)
Application of Rheoturbidity to the Measurement of Interaction
Energies Between Particles in Solution
J. Chim. Phys. 59, 249-58 (1962)
Chem. Abstr. 57 1576

A. Havranek (Karlova Univ., Prague)
Rheology
Cesk. Casopis Fys. 12, 292-301 (1962)
Chem. Abstr. 57 9253

G. R. Purdy and G. G. Eichholz
Viscometer for Mineral Suspensions
Can., Dept. Mines and Tech. Surveys, Mines Branch, Tech. Bull.
TB 11 (1959)
Chem. Abstr. 54 14813

- K. Hottinger
New Methods for Measuring Mechanical Parameters in Rheology
Rheol. Acta 1, 525-30 (1961)
Chem. Abstr. 57 624
- K. A. Lammiman and J. E. Roberts (Esso Research Ltd., Abingdon, Engl.)
Notes on the Measurements of Viscoelasticity in Materials of High
Viscosity
Lab. Practice 10, 816-24 (1961)
Chem. Abstr. 56 14008
- R. Roscoe (King's Coll., Newcastle-upon-Tyne, Engl.)
The Oscillating-Disk Viscometer
Lab. Practice 10, 813-15 (1961)
Chem. Abstr. 56 10932
- I. P. Levsh and O. B. Erofeeva
Restricted Sedimentation of Solid Particles in Viscous Liquids
Trudy Sredneaziat. Politekh. Inst. No. 4, 291-8 (1957)
Chem. Abstr. 54 7294
- H. Kuno (Keio Univ., Tokyo)
Effect of Density and Viscosity of Liquids on Sedimentation Volume
of Powder
Kolloid-Z. 166, 54-5 (1959)
Chem. Abstr. 54 41
- M. J. Vold (Univ. of S. California)
Sediment Volume and Structure in Dispersions of Anisometric Particles
J. Phys. Chem. 63, 1608-12 (1959)
Chem. Abstr. 53 10901; 54 8222
- D. R. Oliver (Univ. Birmingham, Engl.)
Sedimentation of Suspensions of Closely-Sized Spherical Particles
Chem. Eng. Sci. 15, 230-42 (1961)
Chem. Abstr. 56 4578
- H. W. Douglas and J. Burden
Sedimentation of Dilute and Concentrated Suspensions in Relation to
Particle Size and the Verwey-Overbeek Theory of Sol Stability
Trans. Faraday Soc. 55, 350-5 (1959)
Chem. Abstr. 54 1027

- S. F. Kuz'kin and V. P. Nebera
Aggregation of Suspensions by Polyelectrolytes
Byull. Tsvetnoi Met. No. 13, 10-14 (1958)
Referat. Zhur., Met. Abstr. No. 2231 (1958)
Chem. Abstr. 53 19470
- T. A. Malinovskaya
The Thickening of Dispersed Pigment Suspensions by Temporary
Aggregating with Polyacrylamide
Khim. Prom. 113-15 (1961)
Chem. Abstr. 55 20452
- A. V. Senakhov and F. I. Sadov (Textile Inst. Moscow)
Investigation of Structure-Mechanical and Rheological Properties
of Aqueous Solutions of Unchanged Thickening Agents
Kolloid. Zhur. 21, 476-84 (1959)
Chem. Abstr. 54 7290
- T. Matsumura (Lion Dentifrice Co., Ltd., Tokyo)
Effects of Inorganic Salts on the Rheological Properties of Calcium
Carbonate Suspensions in Polyelectrolyte Solutions
Kogyo Kagaku Zasshi 64, 2009-13 (1961)
Chem. Abstr. 57 4075
- J. Okada
Plasticity of Carbon Mixes. I. Dependence of the Plasticity on
Binder Content and Temperature of Carbon Mixes
Kogyo Kagaku Zasshi 63, 2071-6 (1960)
Chem. Abstr. 57 3244
- H. Ukihashi (Research Lab., Asahi Glass Co., Yokohama)
Physico-Chemical Properties of Sodium Silicate Aqueous Solutions
IX. Rheological Properties. 1. Non-Newtonian Viscosity
Asahi Garasu Kenkyu Hokoku 10, 29-51 (1960)
Chem. Abstr. 57 1577
- I. Teraoka and S. Ito (Tokyo Shibaura Elec. Co., Ltd., Kanagawa-ken)
Dehydration of Slurry
Sekko to Sekkai No. 46, 93-8 (1960)
Chem. Abstr. 54 17828

- M. Gotoda and M. Ajichi
Rheological Properties of Paints Measured by a Green Type Rotational
Viscometer
Shikizai Kyokaishi 30, 14-18 (1957)
Chem. Abstr. 53 3729
- A. F. Gabrysh, H. Eyring, M. Shimizu, and J. Asay (Univ. of Utah)
Flow Properties of Attapulgitic Suspension in Water. A Method for
Determining the Relaxation-Time Parameter Beta
J. Appl. Phys. 34, 261-5 (1963)
Chem. Abstr. 58 5063
- A. M. Gutkin and N. V. Zhukov (Energetic Inst., Moscow)
Plastic and Viscous Properties of Clay Paste under the Normal Load
Kolloidn. Zh. 25, 27-33 (1963)
Chem. Abstr. 59 56
- U. Hofmann (Univ. Heidelberg, Ger.)
Clay Minerals and the Plasticity of Clays
Keram. Z. 14, 14-19 (1962)
Chem. Abstr. 56 15168
- A. H. Nissan
Rheological Behavior of Hydrogen-Bonded Solids. III. A Theory of
Tensile Strength
Trans. Faraday Soc. 57, 1646 (1961)
Chem. Abstr. 54 16084; 56 12390
- V. Ophen
The Rheological Behavior of Clay-Water Systems
Am. Perfumer 77, No. 4, 42-6 (1962)
Chem. Abstr. 57 96
- J. Graham (Commonwealth Sci. Ind. Res. Organ., Melbourne)
Density of Clay-Water Systems
Nature 196, 1124 (1962)
Chem. Abstr. 58 6209
- N. Mungan (Univ. of Texas)
Gel-Strength Studies in Fractionated Clay Suspensions
Univ. Microfilms (Ann Arbor, Mich.), Order No. 62-2566
Dissertation Abstr. 23, 175 (1962)
Chem. Abstr. 58 6223

M. P. Volarovich and L. L. Koshlyak
The Dispersion Change of Clay on Disruption of its Natural Structure
in the Plastic State
Kolloidn. Zh. 24, 128-32 (1962)
Chem. Abstr. 57 3088

B. C. Sen (Presidency Coll., Calcutta)
Viscometric Study of Clay-Humus Complexes
J. Indian Chem. Soc. 38, 963-6 (1961)
Chem. Abstr. 56 10932

G. V. Kukolev and N. V. Pitak
Change in the Properties of Bentonite Suspensions Under the Action
of Peptizers
Dopovidi Akad. Nauk Ukr. RSR, 772-5 (1961)
Chem. Abstr. 56 2020

T. Watanabe (Univ. Osaka Prefecture)
Thixotropy. II. Thixotropic Gel Structure of Bentonite
Bull. Chem. Soc. Japan 33, 523-7 (1960)
Chem. Abstr. 53 3839; 54 19091

N. Tuchel, V. Gheorghe, and F. Stefanescu
Colloidal-Clay Suspensions. The Influence of Electrolytes
Farmacia (Bucharest) 8, 565-7 (1960)
Chem. Abstr. 55 12002

Societe Francaise des Glycerines
Viscosity of Clay
Fr. 1,256,585 Appl. 2/9/60
Chem. Abstr. 56 8321

J. Stawitz (Kalle A.-G., Wiesbaden, Ger.)
Dispersive Effect of Carboxymethylcellulose on Kaolin Suspensions
Vortraege Originalfassung Intern. Kongr. Grenzflaechenaktive Stoffe,
3., Cologne, 2, 649-52 (1960) (Pub. 1961)
Chem. Abstr. 57 9253

H. Dettaille
Problems of Lamination and Rheological Characteristics of Clays
Silicates inds. 24, 370-5 (1959)
Chem. Abstr. 54 20130

W. Flaig and H. Sochtig (Inst. Biochem. Boden., Forschungsanst.
Landwirtsch. Braunschweig-Volkenrode, Ger.)
Mutual Exchange Between Kaolinite and Anionic Polymers
Z. Pflanzenernahr. Dungung u. Bodenk. 87, 44-57 (1959)
Chem. Abstr. 55 20362

H. Van Olphen
Forces Between Suspended Bentonite Particles. II. Calcium Bentonite
Clays, Clay Minerals, Proc. Natl. Conf. Clays, Clay Minerals, 6th,
Berkeley, 196-206 (1957) (Pub. 1959)
Chem. Abstr. 51 17333; 53 19522

L. A. Abduragimova
Effect of Sodium Oleate on the Viscosity of the Critically Collapsed
Structure of Clay Suspensions
Azerbaij. Khim. Zhur. No. 1, 19-22 (1959)
Chem. Abstr. 55 11031

G. V. Kukolev and N. V. Pitak
Effect of Peptizers on the Water-Retaining Capacity of Kaolin
Suspensions and Glazed Earthenware Masses, with and without the
Addition of Bentonite
Trudy Khar'kov. Politekh. Inst. im. V. I. Lenina, Ser. Khim.-Tekhnol.
18, No. 5, 177-87 (1958)
Chem. Abstr. 52 19056; 53 20729

A. Baudran and C. Deplus
Rheological Behavior of Clay Bodies
Trans. Brit. Ceram Soc. 58, 454-69 (1959)
Chem. Abstr. 54 10255

G. V. Kukolev and N. V. Pitak (V.I. Lenin Polytech. Inst., Kharkov)
Variation of the Structural-Mechanical Properties of Bentonite
Suspensions in Relation to the Nature and the Quantity of Peptizers
Izvest. Vysshikh Ucheb. Zavedenii, Khim. i Khim. Tekhnol. 2, 244-6
(1959)
Chem. Abstr. 53 19221

S. Okuda (Kyoto Kogei Seni Daigaku)
Effects of the Fixation Phenomena on the Rheological Properties of
Clay Slips and Plastic Masses
Yogyo Kyokai Shi 67, 357-64 (1959)
Chem. Abstr. 54 21689

- H. Lehmann and G. Marx (Bergakad. Clausthal, Clausthal-Zellerfeld, Ger.)
Investigation of the Thixotropy of Clay Suspensions of Clay Minerals
Tonind.-Ztg. u. Keram. Rundschau 82, 354-64 (1958)
Chem. Abstr. 53 667
- S. Sen and S. K. Guha (Central Glass & Ceram. Research Inst, Calcutta)
Sedimentation Volume of Clays
Trans. Indian Ceram. Soc. 17, 57-66 (1958)
Chem. Abstr. 53 18423
- J. Barta (Israel Inst. Technol., Haifa)
The Effect of Deflocculants on the Viscosity of Local Clay Suspensions
Bull. Research Council Israel 6C, 207-14 (1958)
Chem. Abstr. 53 10689
- L. A. Abduragimova
Newtonian Viscosity of Bentonite Clay Suspensions
Trudy Inst. Khim., Akad. Nauk Azerbaidzhan. SSR 15, 77-83 (1956)
Referat. Zhur., Khim. Abstr. No. 30229 (1957)
Chem. Abstr. 53 10903
- E. C. Bloor
Plasticity in Theory and Practice
Trans. Brit. Ceram. Soc. 58, 429-53 (1959)
Chem. Abstr. 54 10255
- A. Leon-Maroto, C. Villalobos, and M. Herreros
Plasticity of Clays, Kaolins, and Ceramic Materials. IV. Experimental Results Obtained with Various Substances Used to Modify the Plasticity
Ion 16, 340-9 (1956)
Chem. Abstr. 50 8986; 54 8016

H12f. PERMEABILITY, POROSITY, DENSITY OF AGGREGATES OF PARTICLES

D. Yarnnton (Flintshire Tech. Coll., Connah's Quay, Wales) and G.R. Simpson
A Method for Determining the Size Distribution of Micropores in
Powder Particles

Powder Met. 8, 42-7 (1961)

Chem. Abstr. 56 5734

J. A. Currie (Rothamsted Exptl. Sta., Harpenden, Engl.)
Gaseous Diffusion in Porous Media. I. A Nonsteady State Method
Brit. J. Appl. Phys. 11, 314-17 (1960)

Chem. Abstr. 55 4061

J. H. deBoer and J. J. Steggerda (Tech. Univ., Delft, Neth.)
The Helium Density of Microporous Substances
Koninkl. Ned. Akad. Wetenschap., Proc., Ser. B, 61, 317-23 (1958)

Chem. Abstr. 53 10900

G. M. Plavnik and B. M. Rovinskii
Study of Submicroporosity of Weakly Absorbing Materials by the
Method of Multiple Low-Angle X-Ray Scattering

Fiz. Tverd. Tela 2, 1099--1106 (1960)

Chem. Abstr. 57 89

J. M. Hutcheon, B. Longstaff (At. Energy Research Estab., Harwell,
Engl.) and R. K. Warner
The Flow of Gases Through a Fine-Pore Graphite
Ind. Carbon and Graphite, Papers Conf., London, 259-71 (1957) (Pub.
1958)

Chem. Abstr. 53 10900

B. F. Steepochkin (S.M. Kirov Chem.-Technol. Inst., Kazan)
Hydraulics of a Granular Layer
Izvest. Vysshykh Scheb. Zavedenii, khim. i khim. Tekhnol. 2, No. 3,
460-6 (1959)

Chem. Abstr. 53 20942

A. A. Komarovskii and V. V. Strel'tsov (S. Ordzhonikidze Polytech.
Inst., Novocherkassk)

Hydrodynamic Resistance of a Layer of Granular Materials

Zhur. Priklad. Khim. 32, 1755-63 (1959)

Chem. Abstr. 53 20922

D. H. Everett (Univ. Bristol, Engl.)

Problems in the Investigation of Porosity by Adsorption Methods

Proc. Symposium Colston Research Soc. 10, 95-120 (1958)

Chem. Abstr. 51 7799; 53 10924; 53 21032

S. Cerny and M. Smisek (Ceskoslov. Akad. Ved, Prague)
Mercury Porosimetry
Chem. Listy 56, 1296-301 (1962)
Chem. Abstr. 58 2866

A. Watson, J. O. May, and B. Butterworth
Studies of Pore-Size Distribution. II. Apparatus for the Measurement of Coarse Pores
Sci. Ceram. 1, 187-99 (1962)
Chem. Abstr. 51 9113; 58 12272

R. Pampuch
Determination of Pore-Size Distribution in Refractories
Prace Inst. Hutniczych 11, No. 1, 11-17 (1959)
Chem. Abstr. 56 3155

W. Lohre
Studies to Determine the Size of Pores in Refractory Products
Tonind.-Ztg. u. Keram. Rundschau 83, 334-41 (1959)
Chem. Abstr. 53 20730

D. Hayes, D. W. Budworth, and J. P. Roberts
Selective Permeation of Gases Through Dense Sintered Alumina
Trans. Brit. Ceram. Soc. 60, 494-504 (1961)
Chem. Abstr. 56 2167

D. Kudelka
Capillary-Active Materials in the Ceramics Industry
Epitoanyag 12, 63-5 (1960)
Chem. Abstr. 56 9734

Y. A. El'tekov
Nature of the Pores in Chromia Gel
Izv. Akad. Nauk SSSR, Otd. Khim. Nauk, 2236-7 (1960)
Chem. Abstr. 57 89

A. V. Kiselev and V. I. Lygin (M.V. Lomonosov State Univ, Moscow)
Electron Microscopic Study of the Porous Structure of Magnesium Hydroxide and its Changes After Thermal Treatment
Izvest. Akad. Nauk SSSR, Otdel Khim. Nauk, 412-16 (1959)
Chem. Abstr. 53 18587

B. R. Puri, S. N. Khanna, and Y. P. Myer (Panjab Univ., Hoshiarpur)
Properties of Capillary-Held Liquids. VI. Hysteresis Effect in
Adsorption by Porous Bodies
J. Sci. Ind. Research (India) 18B, 67-70 (1959)
Chem. Abstr. 53 21036

K. Miyata and T. Kuwahara
Determination of Pore Size of Finely Pulverized Silicic Acid
Kogyo Kagaku Zasshi 61, 1104-7 (1958)
Chem. Abstr. 56 957

K. Oestergaard (Danmarks Tek. Højskole, Copenhagen)
Influence of Intraparticle Diffusion on the Kinetics of Consecutive
Heterogeneous Reactions
Acta Chem. Scand. 15, 2037-42 (1961)
Chem. Abstr. 56 14973

J. O. Mingle and J. M. Smith (Northwestern Univ., Evanston, Ill.)
Pore-Size Distribution Functions for Porous Catalysts
Chem. Eng. Sci. 16, 31-8 (1961)
Chem. Abstr. 57 5337

B. V. Zaleskii and E. A. Sanina
Determination of the Permeability of Solid Rocks
Tr. Inst. Geol. Rudn. Mestorozhd., Petrogr., Mineralog. i Geokhim.
No. 43, 111-19 (1961)
Chem. Abstr. 56 15196

C. L. Hiltrop and J. Lemish
Relation of Pore-Size Distribution and Other Rock Properties to
Serviceability of Some Carbonate Aggregates
Highway Res. Board, Bull. No. 239 (1960)
Chem. Abstr. 57 3084

T. G. Plachenov, G. M. Belotserkovskii, and V. F. Karel'skaya
(Technol. Inst., Leningrad)
The Study of Porous Structure of Some Natural Sorbents by a Mercury
Porosimetric Method
Prirodnye Mineral. Sorbenty, Akad. Nauk Ukr. SSR, Otdel. Khim. i Geol.
Nauk, Trudy Soveshchaniya, Kiev, 43-51 (1958) (Pub. 1960)
Chem. Abstr. 55 8699

N. I. Zalevskii and V. T. Bykov
Types of Pore Structure of Natural Sorbents
Trudy Dal'nevostoch. Filiala im. V. L. Komarova, Akad. Nauk SSSR,
Ser. Khim. No. 4, 24-33 (1960)
Chem. Abstr. 55 17156

M. J. Laubitz (Natl. Research Council, Ottawa)
Thermal Conductivity of Powders
Can. J. Phys. 37, 798-808 (1959)
Chem. Abstr. 53 16677

D. H. Charlesworth
The Internal Insulation of Reactor Pressure Tubes. III. Heat-Transfer
Studies of Layers of Compressed Powders
At. Energy Can. Ltd., Chalk River, Ont. AECL-828 (1959)
Chem. Abstr. 53 18654; 54 12682

H13. MIXING AND BLENDING UTILIZED FOR CHARACTERIZATION OF PARTICLE SYSTEMS

(For mixing as part of processing see C)

H13a. MIXING THEORY

J. Löffler

Definition of Batch Uniformity

Symposium sur fusion verre, Brussels, 185-7 (1958)

Chem. Abstr. 54 20121

R. Chudzikiewicz (Szczecin Polytech., Poland)

Methods of Expressing Quality of Powder Mixtures

Przemysl Chem. 38, 419-22 (1959)

Chem. Abstr. 54 10415

T. Yano, I. Kanise, Y. Sano, Y. Okamoto, and M. Tsutsumi (Univ. Osaka)
Prefecture

Influence of Particle Size of Powder on Degree of Mixing and Mixing
Speed in Several Types of Mixers

Kagaku Kogaku 23, 589-94 (1959)

Chem. Abstr. 54 3

T. Yano, I. Kanise, K. Tanaka, and S. Kurahashi (Univ. Osaka Prefect.)
Effect of the Physical Properties of Powders on the Degree of Mixing
and Mixing Speed of Several Types of Mixers

Kagaku Kogaku 22, 758-63 (1958)

Chem. Abstr. 53 2705

V. Kolar (Vysoka skola chem.-technol., Prague)

Studies on Mixing. V. Effect of Mechanical Mixing on the Rate of
Mass Transfer from Granular Solids in a Liquid

Collection Czechoslov. Chem. Commun. 24, 3309-25 (1959)

Chem. Abstr. 53 4; 54 12; 54 10415

H. Steidl (Vysoka skola chem.-technol., Prague)

Mixing. IV. Rate of Solution of a Suspended Poly Disperse Solid in
a Liquid. The Rate Relation for an Isothermal Batch Process With-
out Disintegration of the Crystals

Chem. listy 52, 1411-21 (1958); 52 852 (1958)

Chem. Abstr. 52 4

H. Steidl and J. Vlcek (Vysoka skola chemicko-technol., Prague)

Mixing. VII. The Solution Velocity of a Polydisperse, Solid, Whirled-
Up Phase in a Liquid. An Experimental Test of the Rate Relation
for the Case of the Isothermic, Discontinuous Course Without
Crystal Disintegration

Collection Czechoslov. Chem. Commun. 25, 1632-41 (1960)

Chem. Abstr. 54 10415, 14819; 54 19091

W. Weydanz (Penicillin-Ges. Dauelsberg & Co., Gottingen, Ger.)
Time Function of a Mixing Process
Chem.-Ing.-Tech. 32, 343-9 (1960)
Chem. Abstr. 54 14812

H. A. Becker (Natl. Research Council, Saskatoon, Can.)
Investigation of Laws Governing the Spouting of Coarse Particles
Chem. Eng. Sci. 13, 245-62 (1961)
Chem. Abstr. 18210 1961

H13b,c. MIXING PRACTICE: DRY OR WET
EQUIPMENT

J. E. Lloyd (United Kingdom Atomic Energy Authority)
Mixing Uranium Tetrafluoride and Ground Magnesium
Ger. 1,087,354 (8/18/60)
Chem. Abstr. 55 22739

K. G. Timm (Struthers Wells Corp., Warren, Pa.)
Clay Slip Preparation
Ceram. Ind. 74, No. 6, 78-82, 98 (1960)
Chem. Abstr. 54 21688

L. B. Heesen, T. J. Heesen, and L. B. Heesen, Jr.
Mixer for Powders or Granules
Dutch 96,130 (11/15/60)
Chem. Abstr. 55 17130

A. Kaufman (Merck, Sharp & Dohme Res. Labs.,)
Mixing of Solids. Experiments with Tumbling Blenders
Ind. Eng. Chem. Fundamentals 1, 104-6 (1962)
Chem. Abstr. 57 2021

J. Weisman and L. E. Efferding (Westinghouse Elec. Corp.)
Suspension of Slurries by Mechanical Mixers
A.I.Ch.E. Journal 6, 419-26 (1960)
Chem. Abstr. 56 4577

S. Yagi, D. Kunii, K. Nagahara, and H. Naito (Univ. Tokyo)
Axial Mixing of Particles in Moving Beds
Kagaku Kogaku 25, 469-76 (1961)
Chem. Abstr. 55 18209

H14. GRANULATION, AGGREGATION UTILIZED FOR CHARACTERIZATION
OF PARTICLES
H14a,b. GRANULATING, PELLETIZING, BRIQUETTING, COMPRESSIONING

K. Wencke (German Acad. Sci., Berlin)
Experiments on Structure Determination of Alumina Pills
J. prakt. Chem. 3, 183-95 (1956)
Chem. Abstr. 54 2881

A. Wustefeld
Agglomeration of Minerals
Ger. 1,012,243 (7/11/57)
Chem. Abstr. 54 10186

H. Matsumaru (Takeda Pharm. Inds., Ltd., Tokyo)
Mechanism of Tablet Compression and Disintegration. I. Influence
of Degree of Compression on the Adsorption Isotherm
Yagugaku Zasshi 78, 1198-1200 (1958)
Chem. Abstr. 53 3602

K. Meyer (Metallgesellschaft Akt.-Ges.)
Pelletizing of Granular and Powdered Materials
Ger. 1,039,235 (9/18/58)
Chem. Abstr. 54 19052

N. K. Yagovdik and I. K. Kisel
Effect of Addition of Dehydrated Clay to the Ceramic Pulp of the
Physicomechanical Characteristic of the Ceramic Body
Belorus. Politekh. Inst., Sbornik Nauch. Rabot, No. 63, 142-52 (1958)
Chem. Abstr. 54 20130

J. Wehn, R. Schlee, and H. Rumpf (Farbenfabriken Bayer Akt.-G.)
Granulation of Powders
Ger. 1,041,472 (10/23/58)
Chem. Abstr. 54 20371

J. Wehn, R. Schlee, H. Rumpf, W. Stroh, and R. Erdmenger (Farben-
fabriken Bayer Akt.-Ges.)
Granulation of Powders
Ger. 1,051,815 (3/5/59)
Chem. Abstr. 55 1109

B. K. Kiselev
The Production of High-Grade Building Material by an Agglomeration
Process
Obogashchenie Bud 3, No. 1, 41-9 (1959)
Chem. Abstr. 54 17836

- A. L. Papadopoulos (Univ. London)
Mechanism of Granule Formation
Fertiliser Soc. (Engl.) Proc. No. 55 (1959)
Chem. Abstr. 54 9
- O. Knacke and H. Pohl (Stolberger Zink Akt.-Ges., Aachen, Ger.)
Contribution to the Principles of Pelletizing
Chem. Ing. Tech. 31, 50-4 (1959)
Chem. Abstr. 53 6700
- E. Bischoff (Lab. Physik and Chemie Grenzflächen, Kirchheim-Boland, Ger.)
The Agglomeration Ability of Powdery Substances
Deut. Farben-Z. 13, 275-80 (1959)
Chem. Abstr. 53 18594
- R. V. Malo and H. M. Brennan (Standard Oil Co.)
High-Strength Alumina Pellets
U.S. 2,939,848 (6/7/60)
Chem. Abstr. 54 20016
- Y. A. Landa
Granulation of Refractory Raw Material
Trudy, Vsesoyuz. Gosudarst. Inst. Nauch.-Issledovatel. i Proekt. Rabot Ogneupor. Prom. No. 29, 107-52 (1960)
Chem. Abstr. 55 25188
- M. J. Powell and T. A. Cecil (Minerals & Chemicals Corp of America)
Apparatus for Pelletizing Acid-Treated Kaolin
U.S. 2,944,986 (7/12/60)
Chem. Abstr. 54 20016
- V. V. Pechkovskii, S. A. Amirova, G. F. Kameko, and M. I. Polotnyan-shchikova
The Effect of Granulation on the Oxidizing Roasting of a Vanadium-Bearing Slag
Izvest. Vysshikh Ucheb. Zavedenii, Tsvetnaya Met. 4, No. 3, 88-93 (1961)
Chem. Abstr. 56 2203
- J. R. Farnand, H. M. Smith, and I.E. Puddington (Natl. Research Council, Ottawa)
Spherical Agglomeration of Solids in Liquid Suspension
Can. J. Chem. Engr. 39, 94-7 (1961)
Chem. Abstr. 55 14018

J. P. Sutherland
Spherical Agglomeration
Chem. Can., 14 (1) 36, 40 (1962)
Ceram. Abstr. 1963 (1) 23

M. F. Gur'yanova and Y. A. Frolov
Granulation of a Glass Batch with Coarse Sand
Steklo i Keram. 18, No. 10, 26-7 (1961)
Chem. Abstr. 56 9723

A. J. Martin and G. C. Ellis (At. Weapons Research Estab., Aldermaston, Engl.)
The Relation Between Powder Properties and the Pressing and Sintering Behavior of Beryllium
Powder Met. 7, 120-38 (1961)
Chem. Abstr. 56 3136

I. M. Arkhipov
Production of Open-Hearth Agglomerate from the Krivoi Rog Iron Ores
Obogashchenie Rud 4, No. 3, 24-9 (1959)
Chem. Abstr. 55 25650

"Shell" Research Ltd.
Agglomeration of Pulverized Ores
Brit. 874,785 Appl. 2/4/60 Fr. 2/6/59
Chem. Abstr. 56 2203

H. D. G. Zapf (Sintermetallwerk Krebsoge G.m.b.H., Krebsoge/Rhld., Ger)
The Pressing and Sintering Properties of Iron Powders
Powder Met. 7, 218-48 (1961)
Chem. Abstr. 56 3193

M. Cap and J. Cibulka
Pelletizing and Sintering of Fine Siderite Concentrates
Freiberger Forschungsh. A195, 20-5 (1961)
Chem. Abstr. 56 3173

M. J. Greaves and A. English
Engineering Contributions to New Techniques of Iron-Ore Agglomeration
Agglomeration Intern. Symp., Philadelphia, 419-53 (1961) (Pub. 1962)
Chem. Abstr. 57 1912

H. U. Ross and A. Ohno
Shrinkage of Iron-Ore Pellets During Agglomeration
Agglomeration Intern. Symp., Philadelphia, 721-41 (1961) (Pub. 1962)
Chem. Abstr. 57 1911

H14c. GREEN STRENGTH AND COMPRESSIBILITY

R. P. Jewett, C. E. Wood, and J. P. Hansen (Michigan Coll. of Mining & Technol., Houghton)
Effect of Particle Size Upon the Green Strength of Iron Oxide Pellets
U.S. Bur. Mines, Rept. Invest. No. 5762 (1961)
Chem. Abstr. 55 14226

H. Flemming
Consideration of the Form of Particles in the Production of Slabs of Lignite Material
Freiberger Forschungsh. A148, 96-105 (1959)
Chem. Abstr. 54 17836

Y. Nishimura, R. Naito, R. Yamamoto, and S. Kato (Govt. Ind. Research Inst., Nagoya)
Effect of the Particle Size of Raw Material on Porcelain Body
III. Compression Test for Workability
Nagoya Kogyo Gijutsu Shikensho Hokoku 2, 347-51 (1960)
Chem. Abstr. 54 15878; 54 17828

A. R. Cooper, Jr. and L. E. Eaton (Massachusetts Inst. of Technol.)
Compaction Behavior of Several Ceramic Powders
J. Am. Ceram. Soc. 45, 97-101 (1962)
Chem. Abstr. 56 13833

N. I. Maksimova, N. N. Serb-Serbina, N. I. Titkov, and A.S. Korzhuev (Inst. Geol. and Fuel Mineral Treatment, Moscow)
Change in (plastic) Strength of Argillaceous Rocks by Electrochemical Treatment
Kolloid. Zhur. 23, 605-14 (1961)
Chem. Abstr. 56 10947

I. M. Gor'kova and N. A. Dushkina
Structural-Mechanical Properties and Deformation of Chalk and Chalk-like Rocks
Tr. Lab. Hidrogeol. Probl., Akad. Nauk SSSR 44, 100-14 (1962)
Chem. Abstr. 57 1896

B. P. Warkentin and R. N. Yong (McGill Univ., Montreal, Can.)
Shear Strength of Montmorillonite and Kaolinite Related to Inter-Particle Forces
Clays Clay Minerals, Proc. Natl. Conf. Clays Clay Minerals 2, 210-18 (1962)
Chem. Abstr. 57 14739

I. M. Gor'kova

Plastic Strength, Sensitivity, Thixotropy, Deliquescence, and
Rheologic Properties of Chalk and Chalklike Rocks

Tr. Lab. Hidrogeol. Probl., Akad. Nauk SSSR 44, 64-75 (1962)

Chem. Abstr. 57 1896

H. S. Eisner, G. Fogg, and T. W. Taylor (Min. Power, Buxton, Engl.)
Cohesion of Powders and the Effect of Atmospheric Moisture

Vortraege Originalfassung Intern. Kongr. Grenzflaechenaktive Stoffe,
3., Cologne, 2, 378-82 (1960) (Pub. 1961)

Chem. Abstr. 57 10554

W. Patterson, D. Boenisch, and S. S. Khanna

The Effect of Cation and Anion on the Green Strength of Clay-Bonded
Foundry Sands

Giesserei, Tech.-Wiss. Beih. Giessereiw. Metallk. 14, No. 2, 117-25
(1962)

Chem. Abstr. 57 6892

H15. SINTERING BEHAVIOR UTILIZED FOR CHARACTERIZATION OF PARTICLES

J. F. Quirk, N. B. Mosley, and W. H. Duckworth (Battelle Memorial Inst)
Characterization of Sinterable Oxide Powders. I. BeO
J. Am. Ceram. Soc. 40, 416-19 (1957)
Nucl. Sci. Abstr. 1958 (2) 329

C. Hyde, A. Rudnick, M. J. Snyder, and W. H. Duckworth (Battelle
Memorial Inst.)
Investigation of Sinterable Powders and Ceramics Made From Them
Third Quarterly Report
Contract AF33(616)-7733 10/20/61
Nucl. Sci. Abstr. 1962 (1) 257

R. B. Wrinkle (Mallinckrodt Chem. Works, St. Charles, Mo.)
Sinterability of Uranium Dioxide Powders for Fuel Elements
Nuclear Eng. Sci. Conf., 5th, Cleveland (1959)
Chem. Abstr. 53 18653

J. E. Clayton and L. Berrin (Westinghouse Elec. Corp.)
The Sintering Behavior of Some Uranium Dioxide Powders
U.S. At. Energy Comm. WAPD-BT-20, 23-38 (1960)
Chem. Abstr. 55 9804

T. Kubo, K. Shinriki, and K. Kutaka (Tokyo Inst., Technol.)
Shrinkage of Powder Compacts During Sintering
Kogyo Kagaku Zasshi 61, 918-22 (1958)
Chem. Abstr. 55 21515

T. Watanabe (Govt. Ind. Research Inst., Nagoya)
Self-Lubricating Fe-Cu Bearing. I. Mechanism of Pore Formation
Nagoya Kogyo Gijutsu Shikensho Hokoku 7, 743-51 (1958)
Chem. Abstr. 56 3193

M. Y. Bal'shin
Kinetics of Change of Isolated Pores
Issledovaniya po Zharoproch. Splavam, Akad. Nauk SSSR, Inst. Met. im.
A. A. Baikova 6, 174-9 (1960)
Chem. Abstr. 56 2252

G. Economos and T. R. Clevenger, Jr. (Massachusetts Inst. of Technol.)
Magnetic Ceramics. VII. Effect of Iron Oxide Particle Size on Nickel
Ferrite Formation
J. Am. Ceram. Soc. 43, 48-52 (1960)
Chem. Abstr. 54 5033; 54 6073

- J. Williams, J. W. S. Jones, and K. H. Westmacott (At. Energy
Research Estab., Harwell, Engl.)
The Effect of Surface Characteristics on the Sintering of Uranium
and Beryllium Powders
Powder Met. 7, 167-88 (1961)
Chem. Abstr. 56 3229
- P. Murray (U.K. At. Energy Authority Res. Group, Harwell, Engl.)
Properties of Active Ceramic Powders in Relation to Sintering
Behavior
Agglomeration Intern. Symp., Philadelphia, Pa., 93-116 (1961)
(Pub. 1962)
Chem. Abstr. 57 1873
- J. Goodison and J. White (Univ. Sheffield, Engl.)
Sintering of Mixed Powders
Agglomeration Intern. Symp., Philadelphia, Pa., 251-70 (1961)
(Pub. 1962)
Chem. Abstr. 57 3117
- H. J. Oel (Max-Planck-Inst. Silikatforschung, Wuerzburg, Ger.)
Characterization and Sintering of Powders
Agglomeration Intern. Symp., Philadelphia, Pa., 271-302 (1961)
(Pub. 1962)
Chem. Abstr. 57 1873
- H. J. Oel (Max-Planck-Inst. Silikatforschung, Wuerzburg, Ger.)
Powder Properties and Sintering Behavior of Pure MgO and MgO-Ni
Ber. Deut. Keram. Ges. 39, No. 2, 78-95 (1962)
Chem. Abstr. 57 9474

H29. CHARACTERIZATION OF PARTICLES--GENERAL

- I. Bertetti (Univ. Genoa)
Characteristics of Synthetic Kaolinite
Atti accad. ligure sci. lettere 14, 169-77 (1957) (Pub. 1958)
Chem. Abstr. 53 17779
- A. L. Draper and W. O. Milligan (Rice Inst., Houston, Tex.)
Structure and Surface Chemistry of Thorium Oxide
U.S. At. Energy Comm. AECU-4395 (1959)
Chem. Abstr. 55 18248
- S. J. Gregg
Preparation of Highly Dispersed Solids
Kolloid-Z., 169 (1-2) 5-11 (1960)
Ceram. Abstr. 1960 (9) 215
- P. J. Anderson and D. T. Livey (At. Energy Research Estab., Harwell, Engl.)
Physical Methods for Investigating the Properties of Oxide Powders in Relation to Sintering
Powder Met. 7, 189-203 (1961)
Chem. Abstr. 56 4483
- H. S. Taylor (Woodrow Wilson Natl. Fellowship Foundation)
Honoring the B in B.E.T.
Advances in Chem. Ser. (American Chem. Soc.), 2-4 (1961)
Chem. Abstr. 56 2335
- L. Halle and S. Brandberg (ASEA, Vasteras, Sweden)
Uranium Dioxide as a Reactor Fuel. Industrial Production and Economic Aspects
Atompraxis, 8, 74-9 (1962)
Nucl. Sci. Abstr. 1962 (6) 1955
- Nuclear Materials and Equipment Corp., Apollo, Penna.
Development of Plutonium-Bearing Fuel Materials
Progress Report for Period January 1 through March 31, 1962
Contract AT(30-1)-2389
Nucl. Sci. Abstr. 1962 (10) 3369

ADDENDUM

H. R. Kruyt
Colloid Science
Elsevier Publishing Co., Inc. (1952)

E. J. W. Verwey and J. T. G. Overbeek
Theory of the Stability of Lyophobic Colloids
Elsevier Publishing Co., Inc. (1948)

A. W. Adamson
Physical Chemistry of Surfaces
Interscience (1960)

C. Kittel
Introduction to Solid State Physics
John Wiley & Sons (1961)

G. F. Huttig
Intermediate States Involved in Reactions in the Solid State
Jour. Chim. Phys. 36, 84 (1939)
Kolloid Z. 97 281 (1941); 98 6 (1942), 263 (1942)

5. Initial Bibliography on
"FORMING OF CERAMICS"

Compiled by A. G. Pincus, R. E. Rose, and V. A. Mee
for years 1955 to July 1963

Flb. RIGID DIE COLD PRESSING

Flbl. Processing studies

W. C. Lucking and R. S. Bradley (A. P. Green Fire Brick Co.)
Effect of Forming Pressure on Properties of a Fire-Clay Mix
Private communication (undated)

S. Levine

Manufacture of Vitrified-bond Grinding Wheels by Dry-press Process: I-III
Ceram. Age 64 (5) 13-16, 56; (6) 19-23 (1954); 65 (1) 18, 53-56 (1955)
Ceram. Abstr. 1955 (6) 99

L. R. McCreight

Processing Studies of Pure Oxide Bodies
J. Am. Ceram. Soc. 37 (8) 378-85 (1954)
Ceram. Abstr. 1954 (8) 163

J. R. Fisher and J. F. Potter

Factors Affecting the Physical Structure of Dry Pressed Steatite
Am. Ceram. Soc. Bull. 34 (6) 177-81 (1955)
Ceram. Abstr. 1955 (9) 161

G. Economos

Magnetic Ceramics: IV, Development of a Complex Ferrite with a Rectan-
gular Hysteresis-loop Characteristic
J. Am. Ceram. Soc. 38 (10) 353-57 (1955)
Ceram. Abstr. 1956 (11) 206

H. C. Dunegan (American Lava Corp.)

A Study and Evaluation of Methods of Producing a Ceramic-to-Metal Seal
by Pressed Powder Techniques for Automatic Mass Production
Contract AF33(600)-27329 (11/56)
Nucl. Sci. Abstr. 1957 () 468

A. F. Ogarkov and P. S. Mamykin

Effect of Moisture content of Bodies and Forming Pressure on Density
of Unfired and Grog Refractories Made by Semidry Pressing
Ogneupory 22 (4) 178-83 (1957)
Ceram. Abstr. 1960 (9) 210

J. J. Rosenthal and S. D. Stoddard (Los Alamos Scientific Lab)

A Study of Process Variables in Barium Titanate Ceramics
Contract (W-7405-eng-36) (1957)
Nucl. Sci. Abstr. 1958 (2) 329

- H. Thurnauer
Controls Required and Problems Encountered in Production Dry Pressing
Ceramic Fabrication Processes: The Technology Press of Mass. Institute
of Technology and John Wiley & Sons, Inc. 62-70 (1958)
- V. R. Starun, M. I. Kolesnik, I. N. Sokolov, M. G. Trofimov, and I. W.
Dudavskii
Pressing Magnesite-chromite Refractories on Hydraulic Presses at High
Specific Pressures
Ogneupory 23 (6) 244-50 (1958)
Ceram. Abstr. 1959 (9) 237
- M. W. Gormly
Technical Aspects of Vitrified Grinding Wheel Manufacture: III, Mixing
and Molding
Am. Ceram. Soc. Bull. 37 (4) 189-92 (1958)
Ceram. Abstr. 1958 (6) 137
- T. F. Berry, W. C. Allen, and W. A. Hassett
Role of Powder Density in Dry-pressed Ceramic Parts
Am. Ceram. Soc. Bull. 38 (8) 393-400 (1959)
Ceram. Abstr. 1959 (10) 271
- A. K. Smalley, J. F. Quirk, and W. H. Duckworth (Battelle Memorial
Inst.)
Investigation of Sinterable Powders and Beryllium Oxide Properties
Quarterly Report No. 1 2/15/59--4/30/59 (5/15/59)
Contract AF33(616)-6238
Nucl. Sci. Abstr. 1959 (8) 1951
- C. Hyde, A. Rudnick, M. J. Snyder, and W. H. Duckworth (Battelle
Memorial Inst.)
Investigation of Sinterable Powders and Ceramics Made from Them
Third Quarterly Report (10/20/61)
Contract AF33(616)-7733
Nucl. Sci. Abstr. 1962 (1) 257
- R. Truesdale, B. B. Lympny, E. M. Grala, R. M. Paine, and W. W. Beaver
(Brush Beryllium Co.)
Investigation of the Effects of Processing Variables and Fabrication
Techniques Upon the Properties of Intermetallic Compounds
Progress Report No. 3 10/1/60--12/31/60 (1/15/61)
Technical Report No. 197-229
Contract AF33(616)-7108
Nucl. Sci. Abstr. 1961 (6) 1898

W. B. Tarpley and H. Kartluke (Aeroprojects, Inc.)
Application of Ultrasonic Vibration to Cold Pressing of Ceramic Pellets
Contract AT(30-1)-1836 (11/61)
Nucl. Sci. Abstr. 1962 (4) 1009

T. Yoshioka and K. Okazaki
Forming of Powder Mixtures with Special Reference to the Manufacturing
Process of Cylindrical Piezoelectric Ceramic Vibrators
Yogyo Kyokai Shi 69 (789) 307-12 (1961)
Ceram. Abstr. 1963 (1) 19
Brit. Ceram. Abstr. 1962 (8) 228A

T. Yoshioka and K. Okazaki
Manufacturing Conditions of $(\text{Pb}, \text{Sr})(\text{Ti}, \text{Zr})\text{O}_3$ Ceramics and Their Electrical Properties
Yogyo Kyokai Shi 69 (790) 361-65 (1961)
Ceram. Abstr. 1963 (3) 76

J. Williams and D. T. Livey (United Kingdom Atomic Energy Authority)
Methods of Manufacturing Graphite Bodies and Nuclear Fuel Materials
Comprising Them
Patent U.S. 3,011,960 (12/5/61)
Ceram. Abstr. 1962 (5) 118f.

W. C. Allen
Dimensional Control of Ceramic Materials
Am. Ceram. Soc. Bull. 40 (6) 383-89 (1961)
Ceram. Abstr. 1961 (9) 216

S. W. Ratcliffe
Some Principles of Dust Pressing and the Casting Process
Claycraft 35 260 (1962)
Brit. Ceram. Abstr. 1962 (11) 311A

F. J. Cach
Comments on "A New Method for the Mechanical (Pressing) Shaping of
Plates."
Zeram. A. 14 (6) 349-50 (1962)
Ceram. Abstr. 1963 (3) 79

C. A. Bruch
Sintering Kinetics for the High Density Alumina Process
Am. Ceram. Soc. Bull. 41 (12) 799-806 (1962)
Ceram. Abstr. 1963 (1) 29

A. M. Illing (Cambridge Tile Mfg. Co.)
Pressing Defects in Ceramic Tile
Am. Ceram. Soc. Bull. 42 (8) 8 (1963)

Flb2. Cold pressing of uranium dioxide

J. Glatte, H. R. Hoge, and B. E. Schaner (Westinghouse Electric Corp.
Atomic Power Div.)

The Fabrication of Dense Uranium Dioxide Cylindrical Compacts by Cold
Pressing and Sintering

Contract At-11-1-GEN-14 10/14/55 Decl. 3/12/57

Nucl. Sci. Abstr. 1957 (12) 1529

J. Glatte and B. E. Schaner

Process of Forming Powdered Material

U. S. Patent 2,991,601 (5/14/61)

Nucl. Sci. Abstr. 1961 (9) 2922

Anon.

Composite Element and Method of Manufacture

Australian Patent 222,604 (5/8/57)

Nucl. Sci. Abstr. 1962 (3) 773

W. G. Carlson, H. D. Root, and R. S. Shane

Pressure-temperature-density Relations in Several Samples of UO_2

Am. Ceram. Soc. Bull. 39 (2) 69-73 (1960)

Ceram. Abstr. 1960 (4) 88

L. D. Huckstepp and G. V. Day

Processing of Enriched Uranium Oxide-paraffin Wax Mixtures

Powder Met. No. 6 150-59 (1960)

Ceram. Abstr. 1963 (1) 29

Compagnie Industrielle des Combustibles Atomiques Frites, Corbeville,
par Orsay (Seine-et-Oise), France

Molding of Uranium Dioxide. Appendix 2 of Sintered Uranium Oxide Sintering
Methods Behavior Under Irradiation

Quarterly Report No. 4, 3rd Quarter 7/1/61--9/30/61 (10/61)

Nucl. Sci. Abstr. 1962 (7) 2164

Anon.

Composite Nuclear Fuel Element and Method of Manufacture

British Patent 858,061 (1/4/61)

Nucl. Sci. Abstr. 1961 (4) 1072

A. J. Caputo and J. E. Perry (Union Carbide Nuclear Co.)

Production, Precision Forming, and Sintering of Ceramic-grade UO_2

Contract W-7405-eng-26 (3/16/61)

Nucl. Sci. Abstr. 1961 (7) 2384

D. L. Schwartz (to General Electric Co.)
Process for Producing High Density Refractory Bodies
U. S. Patent 3,051,566 (8/28/62)
Nucl. Sci. Abstr. 1962 (11) 4045

Flb3. Response of material
(See also Flr, F20d)

P. Visseriat

Pressure measurements in Ceramics

Bull. soc. franc. ceram. No. 16 25-32 (1952)

Ceram. Abstr. 1954 (3) 55

E. A. Ab and A. S. Ostryakov

Controlling the Quality of Clay Powder in Dry Pressing Brick

Steklo i Keram 11 (5) 18-21 (1954)

Ceram. Abstr. 1954 (11) 200

C. Kawashima and Y. Murata

Spray Drying and Semidry Pressing of Ceramics: I

J. Ceram. Assoc. Japan 61 (690) 605-10 (1953)

Ceram. Abstr. 1954 (5) 94

C. Kawashima and Y. Murata

Spray Drying and Semidry Pressing of Ceramics: II

J. Ceram. Assoc. Japan 62 (691) 4-9 (1954)

Ceram. Abstr. 1954 (9) 162

C. Kawashima and Y. Murata

Spray Drying and Semidry Pressing of Ceramics: III

J. Ceram. Assoc. Japan 62 (694) 237-42 (1954)

Ceram. Abstr. 1954 (9) 185

C. Kawashima and Y. Murata

Fundamental Studies on the Spray Drying and Semidry Pressing of
Ceramics: VI

J. Ceram. Assoc. Japan 63 (707) 133-37 (1955)

Ceram. Abstr. 1956 (11) 206

H. W. H. West

Some Observations on the Properties of Dust-pressed Earthenware

Tile: I, Green Strength

Trans. Brit. Ceram. Soc. 54 (9) 543-69 (1955)

Ceram. Abstr. 1960 (3) 63

E. V. Ivanov, F. I. Chuprinin, and Y. M. Minskii

Measurements of Elastic Aftereffects During Pressing of Magnesite
Bodies

Ogneupory 23 (3) 120-22 (1957)

Ceram. Abstr. 1960 (9) 211

I. S. Kainarskii and I. Y. Piven
Influence of Lowering the Microhardness of Mineral Powders Under
the Action of Surface-active Agents on Their Capacity to Densify
During Pressing
Ogneupory 22 (1) 27-29 (1957)
Ceram. Abstr. 1959 (1) 19

A. F. Ogarkov and P. S. Mamykin
Effect of Moisture Content of Bodies and Forming Pressure on Density
of Unfired and Grog Refractories Made by Semidry Pressing
Ogneupory 22 (4) 178-83 (1957)
Ceram. Abstr. 1960 (9) 210

A. F. Ogarkov and P. S. Mamykin
Elastic Expansion of Clay and Grog Bodies During Semidry Pressing
Ogneupory 22 (9) 398-406 (1957)
Ceram. Abstr. 1958 (9) 244

K. K. Strellov
Compression of (Ceramic) Ware
Ogneupory 22 (1) 38-42 (1957)
Ceram. Abstr. 1959 (1) 19

K. K. Strellov
Elastic Expansion and Crushing of Mixtures During Pressing
Ogneupory 23 (3) 131-35 (1958)
Ceram. Abstr. 1951 (8) 201

W. Noble, A. N. Williams, and F. H. Clews
Influence of Moisture Content and Forming Pressure on the Properties
of Heavy Clay Products
Trans. Brit. Ceram. Soc. 57 (7) 414-61 (1958)
Ceram. Abstr. 1960 (9) 210

W. D. Kingery
Pressure Forming of Ceramics
Ceramic Fabrication Processes: The Technology Press of Mass. In-
stitute of Technology and John Wiley & Sons, Inc. 62-70 (1958)

T. Haase

Mechanism of Dry Pressing

Ber. deut. keram. Ges. 37 97-101 (1960)

Ceram. Abstr. 1960 (9) 215

F. V. Kondrashev and P. Y. Popil'skii

Method of Measuring the Elastic Expansion of Green Ceramic Products
and the Pressure of the Trapped Air

Steklo i Keramika 17 No. 3 29 (1960)

Brit. Ceram. Abstr. 1961 (2) 50A

W. M. Long

Radial Pressures in Powder Compaction

Powder Met. No. 6 73-86 (1960)

Ceram. Abstr. 1963 (1) 23

W. M. Long and J. R. Alderton

Displacement of Gas from Powders During Compaction

Powder Met. No. 6 52-72 (1960)

Ceram. Abstr. 1963 (1) 22

A. P. Larin, S. A. Losev, and V. G. Sloushch

Determining the Pressing Force of Toggle Presses

Ogneupory 25 (1) 14-16 (1960)

Ceram. Abstr. 1960 (8) 195

G. M. Zhdanovich

Problems on the Theory of the Process of Pressing Metal Powders
and Their Mixtures

Minsk 1960

Nucl. Sci. Abstr. 1963 (3) 860

C. A. Bruch

Sintering Kinetics for the High Density Alumina Process

Am. Cer. Soc. Bull. 41 (12) 799-806 (1962)

A. R. Eaton and R. L. Cooper

Compaction Behavior of Several Ceramic Powders

J. Am. Ceram. Soc. 45 (3) 97-101 (1962)

Ceram. Abstr. 1962 (4) 110

A. R. Cooper, Jr. and W. H. Goodnow
Density Distributions in Dry-pressed Compacts of Ceramic Powders
Examined by Radiography of Lead Grids
Am. Ceram. Soc. Bull. 41 (11) 760-61 (1962)
Ceram. Abstr. 1963 (1) 22

W. D. Kingery, R. L. Coble, A. R. Cooper, Jr., and T. R. Clevenger, Jr.
(Mass. Inst. of Tech. Dept of Metallurgy)
Basic Research in Ceramics and Non-Crystalline Systems
Annual Report (3/30/62)
Contracts AT(30-1)-1852 and AT(30-1)-2574
Nucl. Sci. Abstr. 1962 (6) 1964

P. Daignaud and M. Aveline
Study of the Uniformity of Pressing Stoneware Tiles--Influence of
the Method of Filling the Moulds
Trans. 8th Int. Ceram. Congr. 1962 p. 255
Brit. Ceram. Abstr. 1962 (10) 289A

U. Hoffman, E. Scharrer, W. Czerkh, K. Fruhauf, and W. Burk
Fundamentals of Dry Pressing and the Causes of Compacting of the
Dry Body
Ber. deut. keram. Ges. 39 (2) 125-30 (1962)
Ceram. Abstr. 1962 (8) 195

F. H. McRitchie (Refractories Fellowship, Mellon Institute)
Pressure Distribution in Dry Pressing of Refractories
Presented at 65th ACS
Am. Ceram. Soc. Bull. 42 (4) 1963 237

Flb4. Descriptions of equipment

C. E. Adams (Denison Engineering Co.)

Hydraulic Press

U. S. 2,618,833 (11/25/52)

Ceram. Abstr. 1953 (5) 88

S. Stanislaw

Model Shop for Dry-pressing Precision Ceramics

Ceram. Age 64 (1) 15-19 (1954)

Ceram. Abstr. 1955 (5) 89

L. Kupchinsky

Achieving Quality Control with Hydraulic Presses

Ceram. Age 67 (3) 14 (1956)

Ceram. Abstr. 1962 (1) 16

K. Geppert (Kugelfischer Georg Schafer & Co.)

Method of and Device for Pressing Grinding Wheel Blanks

U. S. 2,830,320 (4/15/58)

Ceram. Abstr. 1958 (7) 163

R. G. Frank (F. J. Stokes Corp.)

Proportional Pressing

U. S. 2,888,715 (6/2/59)

Ceram. Abstr. 1959 (9) 248

J. W. Ludowici

Dry-pressing and the Dry Press

Bull. Soc. Franc. Ceram. No. 53 49 (1961)

Brit. Ceram. Abstr. 1962 (7) 195A

R. Rusev

Semidry Pressing in Floating Mold

Stroitel. Materiali i Silikat. Prom. 2 (4) 17-19 (1961)

Ceram. Abstr. 1962 (2) 39

H. Apfelbeck

A New Method of Mechanized Production of Plates

Keram. Z. 14 72 (1962)

Brit. Ceram. Abstr. 1962 (9) 254A

Flc. FLEXIBLE MOLD PRESSING

(Isostatic; polymeric die liners)

B. A. Jeffery (to Champion Porcelain Co.)
Method of and Apparatus for Shaping Articles
U. S. Patent 1,863,854 (6/21/32)

H. W. Daubenmeyer (to Champion Spark Plug Co.)
Elastic Mold and Method of Molding Material
U. S. Patent 1,983,602

B. A. Jeffery (Champion Spark Plug Co.)
Method of and Apparatus for Molding Materials
U. S. 2,152,748 4/4/39 (4/17/36)
Ceram. Abstr. 1939 (6) 162

B. A. Jeffery (to Champion Spark Plug Co.)
Preparing and Molding Material
U. S. Patent 2,251,454 (8/5/41)

L. R. McCreight
Laboratory Hydrostatic Pressing Chamber
Am. Ceram. Soc. Bull. 30 (4) 127-29 (1951)
Ceram. Abstr. 1951 (6) 109

L. R. McCreight
Processing Studies of Pure Oxide Bodies
J. Am. Ceram. Soc. 37 (8) 378-85 (1954)
Ceram. Abstr. 1954 (8) 163

Anon.
Unique "Isostatic Process" Marks Manufacture of Coors High Density
Grinding Media
Ceram. News 6 (4) 20-22 (1957)
Ceram. Abstr. 1957 (9) 208

W. D. Kingery
Hydrostatic Molding
Ceramic Fabrication Processes: The Technology Press of Mass. In-
stitute of Technology and John Wiley & Sons, Inc. 70-73 (1958)

H. W. Newkirk, Jr. and R. J. Anicetti (General Electric Co.)
Fabrication of Uranium Dioxide Fuel Element Shapes by Hydrostatic
Pressing
Contract W-31-109-Eng-52 (8/1/57)
Nucl. Sci. Abstr. 1958 () 1178

H. W. Newkirk, Jr. and R. J. Anicetti
Fabrication of Uranium Dioxide Fuel Element Shapes by Hydrostatic Pressing
Am. Ceram. Soc. Bull. 37 (11) 471-75 (1958)
Ceram. Abstr. 1959 (1) 12

C. Kawashima, S. Saito, and M. Kato
Fundamental Studies on Pressing of Powder by Hydrostatic Pressing
Method: I, Studies on Pressing of TiC-Co System Cermet
Funtai oyobi Fumatsuyakin 5 (1) 18-25 (1958)
Ceram. Abstr. 1960 (4) 95

W. D. Anderson
Hydrostatic Pressing of Alumina Radomes
PB Rept. 131565
U. S. Govt. Research Repts. 29 (3) 125 (1958)
Ceram. Abstr. 1961 (1) 17

Anon. A New Division for the West's Oldest and Largest Ceramic Firm
Ceramic News 10 No. 2 12 (1961)
Brit. Ceram. Abstr. 1961 (8) 287A

W. D. Anderson (Gladding, McBean & Co.)
Method of Making Dense Refractory Objects
U. S. Patent 3,016,598 (16/1/62)
Brit. Ceram. Abstr. 1962 (7) 216A

L. E. Mong and D. M. Adelman
Control of Factors Affecting Reproducibility of Mechanical Properties of Refractory Semidry Press Specimens
J. Am. Ceram. Soc. 41 (7) 267-72 (1958)
Ceram. Abstr. 1958 (8) 201

W. D. Johnston
Isostatic Pressing Gains Favor
Ceram. Age 76 (5) 14-18 (1960)
Ceram. Abstr. 1961 (9) 219

A. K. Smalley, W. C. Riley, and W. H. Duckworth
Al₂O₃-clad UO₂ Ceramics for Nuclear-fuel Applications
Am. Ceram. Soc. Bull. 39 (7) 359-61 (1960)
Ceram. Abstr. 1960 (9) 210

C. Hyde, A. Rudnick, M. J. Snyder, and W. H. Duckworth (Battelle
Memorial Inst.)
Investigation of Sinterable Powders and Ceramics Made From Them
Fourth Quarterly Report 10/1/61--12/29/61 (2/12/62)
Contract AF 33(616)-7733
Nucl. Sci. Abstr. 1962 (5) 1356

M. J. Snyder, A. A. Rudnick, W. H. Duckworth, and C. Hyde
(Battelle Memorial Inst.)
Investigation of Sinterable MgO Powders and Ceramics Made From
Them
Contract AF 33(616)-7733 (6/62)
Nucl. Sci. Abstr. 1963 (3) 858

G. S. Blockh, L. G. Brodskii, R. M. Zaients, E. L. Rokhvarger, and
N. P. Sheverdyayev
Semidry Pressing of Ceramic Sewer Pipe by the Hydrostatic Method
Steklo i Keram. 18 (4) 24-27 (1961)
Ceram. Abstr. 1962 (2) 37

P. B. Archibald (Univ. Of California, Livermore)
Isostatic Solvent Pressing
Ind. Eng. Chem 53 737-8 (9/61)
Nucl. Sci. Abstr. 1962 (2) 565

P. B. Archibald (to U. S. Atomic Energy Commission)
Method for Solvent-isostatic Pressing
U. S. Patent 3,054,147 (9/18/62)
Nucl. Sci. Abstr. 1962 (11) 4045

C. F. Schaefer and J. Z. Stola (General Motors)
Isostatic Molding Apparatus
Patent U. S. 3,034,101 (5/15/62)
Ceram. Abstr. 1962 (9) 220

D. G. Loomis (Loomis Engineering & Mfg. Co.)
Isostatic Pressing as a High Production Process
Am. Ceram. Soc. Bull. 42 (4) 233 (1963)

V. Ferrero and S. F. Riunite
Process and Device for Molding Brick, etc.
Fr. 1,047,303 (7/22/53)
Ceram. Abstr. 1954 (11) 200

V. D. Yashin, N. A. Golushko, and V. G. Ipatov
Pressing Articles from Powdered Bodies in a Rubber Mold
Ogneupory 21 (3) 135-38 (1956)
Ceram. Abstr. 1959 (1) 19

B. E. Vassiliou
Simple Laboratory Method for Making Crucibles and Other Shapes
Trans. Brit. Ceram. Soc. 56 (10) 516-18 (1957)
Ceram. Abstr. 1959 (9) 260

T. W. Penrice
Compaction of Powders Using Molds Made from Reversible Gels
Powder Metallurgy 1958 No. 1-2 79-84 (1958)
Ceram. Abstr. 1962 (7) 176

P. Popper, ed.
Special Ceramics. Proceedings of a Symposium Held at the British
Ceramic Research Association
Academic Press, Inc. 1960
Nucl. Sci. Abstr. 1962 (8) 2506

Compagnie Industrielle des Combustibles Atomiques Frittes, Corbe-
ville, par Orsay (Seine-et-Oise), France
Uranium Oxide Extrusion
4th Quarterly Report 6/61--9/61 (11/61)
Nucl. Sci. Abstr. 1962 (7) 2169

R. Hauser (Compagnie Industrielle des Combustibles Atomiques
Frittes)
New Developments Concerning the Technology of Uranium Oxide
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG., 1962 519-28

General Electric Co. Ltd.
Compacted Powdered Article Manufacture
Brit. Pat. 895,492,2/5/62
Brit. Ceram. Abstr.

Fla. VACUUM-ASSISTED PRESSING

Philips Electrical Industries, Ltd.
Manufacture of Ceramic Moldings
Brit. 719,498 (12/1/54)
Ceram. Abstr. 1958 (6) 146

G. Funke
One Hundred Years of the Pug Mill
Ziegelind 9 (1) 9-11 (1956)
Ceram. Abstr. 1956 (6) 120

F. V. Kondrashev
Vacuum Treatment of Ceramic Powders During Pressing
Steklo i Keram. 19 (5) 19-21 (1962): Glass Ceram (USSR) (English
Transl.) 251-54
Ceram. Abstr. 1963 (4) 106

Fle. EXTRUDING COLD, DRY POWDERS

W. J. Kramers (Gt. Brit. Ministry of Supply. Materials Research
Div.)
Review of the Refractory Sulphides. The Preparation of Cerium Ses-
quisulphide Ceramics
June 1952
Nucl. Sci. Abstr. 1957 (7) 774

M. R. Horne
Elastic-plastic Theory of Containers and Liners for Extrusion
Presses
Proc. Inst. Mech. Engrs. (London) 169 107-22 (1955)
Ceram. Abstr. 1956 (2) 59

D. G. Loomis
Hydraulic Extrusion Press
U. S. 2,702,409 (2/22/1955)
Ceram. Abstr. 1955 (5) 90

A. N. Novikov
Plastic Shaping of Ware of Monomineral Composition by the Use of
Paste
Ogneupory 22 (1) 12-21 (1957)
Ceram. Abstr. 1960 (1) 7

H. Z. Schofield, W. H. Duckworth, and R. E. Long (Battelle
Memorial Inst.)
Fabrication of Beryllia Shapes by Ceramic Extrusion
5/1/49 Decl. 2/13/57
Contract W-7405-eng-92
Nuc. Sci. Abstr. 1958 (1) 218

C. Hyde
Vertical Extrusion of Nonclay Compositions
Ceramic Fabrication Processes: The Technology Press of Mass. In-
stitute of Technology and John Wiley & Sons, Inc. 107-111 (1958)

Compagnie Industrielle des Ceramiques Electroniques, Paris
Uranium Oxide Extrusion
Quarterly Report No. 1 (12/15/59)
EURATOM Contract EUR/C/1323/3/59 EURATOM/U.S.A. Agreement Proposal
No. 37
Nucl. Sci. Abstr. 1961 (7) 2237

Compagnie Industrielle des Combustibles Atomiques Frittes, Corbeville, par Orsay (Seine-et-Oise), France
Uranium Oxide Extrusion
Quarterly Report No. 3 (6/15/60)
Contract 001-59-9-RDF
Nucl. Sci. Abstr. 1962 (5) 1348

Compagnie Industrielle des Combustibles Atomiques Frittes, Corbeville, par Orsay (Seine-et-Oise), France
Uranium Oxide Extrusion
Quarterly Report No. 2 (3/15/60)
Contract 030-60-9RDF
Nucl. Sci. Abstr. (7) 1962 2342
Nucl. Sci. Abstr. (7) 1961 2387

Compagnie Industrielle des Combustibles Atomiques Frittes, par Orsay Seine-et-Oise, France
Uranium Oxide Extrusion
Draft of Final Report
EURATOM Contract EUR/C/1323/3/59 (1960?)
Nucl. Sci. Abstr. 1961 (7) 2384

Compagnie Industrielle des Combustibles Atomiques Frittes, Corbeville, par Orsay (Seine-et-Oise), France
Production of Mixed UO_2 - ThO_2 Oxide Pellets by Sintering in Air
Quarterly Report No. 2 (nd.)
Contract 014-60-9RDF
Nucl. Sci. Abstr. 1962 (6) 1953

Compagnie Industrielle des Combustibles Atomiques Frittes, Corbeville, par Orsay (Seine-et-Oise), France
Extrusion of Uranium Oxide Rods
Quarterly Report No. 3 (4/61--6/61)
Contract 030-60-9RDF
Nucl. Sci. Abstr. 1962 (7) 2342

Compagnie Industrielle des Combustibles Atomiques Frittes, Corbeville, par Orsay (Seine-et-Oise), France
Uranium Oxide Extrusion
Quarterly Report No. 4 (9/15/60)
Contract 001-59-9-RDF
Nucl. Sci. Abstr. 1962 (5) 1348

Compagnie Industrielle des Combustibles Atomiques Frittes, Corbe-
ville, par Orsay (Seine-et-Oise), France
Uranium Oxide Extrusion
Quarterly Report No. 6 (1/61--3/61)
Contract 030-60-9RDF
Nucl. Sci. Abstr. 1962 (7) 2169

Compagnie Industrielle des Combustibles Atomiques Frittes, Corbe-
ville, par Orsay (Seine-et-Oise), France
Uranium Oxide Extrusion
Final Report (1/61)
Contract 001-59-9-RDF
Nucl. Sci. Abstr. 1962 (5) 1348

Compagnie Industrielle des Combustibles Atomiques Frittes, par
Orsay (Seine-et-Oise), France
Uranium Oxide Extrusion
Quarterly Report No. 1 (second year) (12/15/60)
EURATOM Contract EUR/3081/60r
Nucl. Sci. Abstr. 1961 (7) 2387
Nucl. Sci. Abstr. 1963 (3) 1138

Compagnie Industrielle des Combustibles Atomiques Frittes, Corbe-
ville, par Orsay (Seine-et-Oise), France
The Extrusion of Uranium Dioxide; Technique of Extrusion
CEND-153 Vol. II 115-29
Nucl. Sci. Abstr. 1963 (4) 1451

A. Porneuf (Compagnie Industrielle des Combustibles Atomiques
Frittes)
The Extrusion of Uranium Dioxide. Physico-Chemical Properties of
Extruded Uranium Dioxide
CEND-153 Vol. II 131-4
Nucl. Sci. Abstr. 1963 (4) 1451

C. L. Brown and T. A. Mroz (General Electric Co. Aircraft Nuclear
Propulsion Dept.)
Camber Study of Extruded Tubes
Contract AT(11-1)-171 (2/22/1960)
Nucl. Sci. Abstr. 1962 (5) 1348

W. E. Baily (Westinghouse Electric Corp. Atomic Power Dept.)
UO₂ Fuel Fabrication by Extrusion
For Carolinas Virginia Nuclear Power Associates, Inc.
Contract AT(30-1)-2289 (2/1/60)
Nucl. Sci. Abstr. 1963 (3) 1138

E. A. Hawk Sr., E. A. Hawk Jr., and P. P. Marchiano
Apparatus for Forming Composite Extruded Articles
U. S. Patent 2,962,786 (12/6/60)
Ceram. Abstr. 1961 (4) 96

Aeroprojects, Inc.
Applications of Ultrasonic Energy. Task 1. Ultrasonic Chemical
Processing. Task 2. Ultrasonic Metal and Ceramic Powder Proces-
sing. Task 3. Ultrasonic Instrumentation
Progress Report No. 22 (6/1/60--7/31/60)
Changed from OFFICIAL USE ONLY 6/23/61
Contract AT(30-1)-1836
Nucl. Sci. Abstr. 1962 (1) 249

Aeroprojects Inc.
Applications of Ultrasonic Energy. Task 1. Chemical Processing
Task 2. Metal and Ceramic Powder Processing. Task 3. Ultrasonic
Instrumentation
Progress Report No. 19 (12/1/59--1/31/60)
Contract AT(30-1)-1836
Nucl. Sci. Abstr. 1961 (11) 3513

Aeroprojects, Inc.
Applications of Ultrasonic Energy. Task 1. Ultrasonic Chemical
Processing. Task 2. Ultrasonic Metal and Ceramic Powder Proces-
sing. Task 3. Ultrasonic Instrumentation
Progress Report No. 24 (10/1/60--11/31/60)
Contract AT(30-1)-1836
Nucl. Sci. Abstr. 1961 (9) 3040

W. B. Tarpley, K. H. Yocom, R. Pheasant (Aeroprojects, Inc.)
Ultrasonic Extrusion; Reducation in Vehicle and Plasticizer Require-
ments for Non-clay Ceramics
Contract AT(30-1)-1836 (11/61)
Nucl. Sci. Abstr. 1962 (5) 1555

V. I. Likhtman, N. S. Gorbunov, I. G. Shatalova, and P. A. Rebinder
(Inst. of Physical Chemistry, Academy of Sciences, USSR)
On the Vibrational Increase of Density in Powder Metallurgy
Doklady Akad. Nauk S.S.S.R. 134 (10) 1150-2 (1960)
Nucl. Sci. Abstr. 1961 (4) 993

L. Meny, J. Buffet, and C. Sauve
Powder Sintering and Extrusion for the Fabrication of U-Al and
UO₂--Stainless Steel Dispersion Fuel Elements
Plansee Proc. 4th Seminar Reutte/Tyrol (1961)
Translated by J. V. L. Hopkins (U.K.A.E.A.)
Nucl. Sci. Abstr. 1962 (10) 3612

Compagnie Industrielle des Combustibles Atomiques Frittes, Corbe-
ville, par Orsay (Seine-et-Oise), France
Uranium Oxide Extrusion
4th Quarterly Report (2nd year) (6/61--9/61)
EURAEC-195
Nucl. Sci. Abstr. 1962 (7) 2169

R. Hauser (Compagnie Industrielle des Combustibles Atomiques
Frittes, Domaine de Corbeville, Orsay, France
New Developments Concerning the Technology of Uranium Oxide
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG. 1962 519-28
Nucl. Sci. Abstr. 1963 (1) 259

Allis-Chalmers Mfg. Co. Nuclear Power Dept.
Extruded Ceramic Nuclear Fuel Development Program
Final Report (1/23/61)
Contract AT(11-1)-767
Nucl. Sci. Abstr. 1961 (5) 1479

Allis-Chalmers Mfg. Co. Nuclear Power Dept
Extruded Ceramic Nuclear Fuel Development Program
Final Report, Phase II (6/15/62)
Contract AT(11-1)-767
Nucl. Sci. Abstr. 1963 (2) 457

W. J. O'Leary & R. S. Miller (Allis-Chalmers Mfg. Co. Atomic
Energy Div.)
Extrusion of UO_2 and ThO_2-UO_2 Nuclear Fuels
CENDO153 Vol. II 135-54
Nucl. Sci. Abstr. 1963 (4) 1451

L. Navias
Extrusion of Refractory Oxide Insulators for Vacuum Tubes
J. Amer. Ceram. Soc. 15 (4) 234 (1932)

Flr. DIELESS COMPACTING; POWDER ROLLING

S. Shapiro (Martin Co.)

A New Fabrication Technique for the Production of Stainless Steel
Oxide Dispersion Fuel Elements

A/CONF-15/P/784

Nucl. Sci. Abstr. 1958 () 1816

Anon.

Continuous Process for Fabricating Thin Sheet Ceramic Parts

Ceram. News 8 (6) 17 (1959)

Ceram. Abstr. 1959 (11) 288

H. H. Hausner

Powder Metallurgy in Nuclear Engineering

Funtai oyobi Fumatsuyakin 6 (1) 1-18 (1959)

Ceram. Abstr. 1960 (7) 160

K. H. Moyer and I. Sheinhart (Sylvania-Corning Nuclear Corp.)

Feasibility Study for Direct Rolling of Beryllium Powders

Final Report 4/15/59--11/30/59 (1/60)

Contract NORD-17017

Nucl. Sci. Abstr. 1962 (10) 3612

Anon.

Continuous Compaction

Materials in Design Eng. 51 (1) 14, 159 (1960)

Ceram. Abstr. 1960 (6) 143

F. Emley (Westinghouse Electric Corp.)

Large Sintered Bodies and Parts

Powder Metallurgy: Academic Press, 389-401 (1961)

Nucl. Sci. Abstr. 1961 (9) 3083

W. H. Lenz and C. E. Peterson (Los Alamos Scientific Lab.)

The Powder Rolling of Molybdenum and Tungsten

Contract W-7405-ENG-36 (6/61)

Nucl. Sci. Abstr. 1962 (2) 418

J. W. Lingafelter (General Electric Co.)

Fabrication of Stainless Steel Clad Uranium Dioxide Fuel Elements
by Tandem Rolling

Trans. Am. Nuclear Soc. 4 No. 1 (6) 151 (1961)

Nucl. Sci. Abstr. 1961 (8) 2736

J. W. Lingafelter (General Electric Co.)
Fabrication of Fuel Rods by Tandem Rolling
Contract AT(04-3)-361 (7/61)
Nucl. Sci. Abstr. 1962 (5) 1349

Anon.

A New Division for the West's Oldest and Largest Ceramic Firm
Ceramic News 10 No. 2 12 (1961)
Brit. Ceram. Abstr. 1961 (8) 287A

R. C. Ragan (Gladding, McBean and Co.)
Method for Continuous Manufacture of Ceramic Sheets
U. S. Patent 3,007,222 (11/7/61)
Ceram. Abstr. 1962 (4) 93

J. J. Fargo (Gladding, McBean and Co.)
Summary Report on Development of Flat Plate Ceramic Fuel Elements
Technical Progress Report 26
Contract AT(04-3)-249
Nucl. Sci. Abstr. 1962 (8) 2831

J. J. Fargo (International Pipe and Ceramics Corp.)
Fabrication of Thin Uranium Dioxide Plates by a Powder Rolling
Process
Presented at 65th ACS
Am. Ceram. Soc. Bull. 42 (4) 269 (1963)

J. Dasher (Crucible Steel Co. of America)
Rolling Mill (for Metal Powder)
U. S. Patent 3,010,148 (11/28/61)
Ceram. Abstr. 1962 (5) 122

B. J. Triffleman (Curtiss-Wright Corp.)
Method of Manufacturing Homogeneous Carbides
U. S. Patent 3,013,875 (12/19/62)
Ceram. Abstr. 1962 (6) 142

J. H. Westbrook
High-temperature Materials in the Soviet Union
Metal Progress 81 (2) 97-101 (1962)
Ceram. Abstr. 1962 (7) 168

National Research Council. Materials Advisory Board
State of the Art on Powder Metallurgy
Fourth Progress Report by the Panel on Casting and Powder Metal-
lurgy (5/28/62)
Nucl. Sci. Abstr. 1962 (9) 3180

Fig. VIBRATORY COMPACTING; JOLTING

(see also Flh)

W. E. Hawth and H. A. Wilhelm (Ames Lab.)

Fabrication of Large Beryllia Crucibles

Nuclear Science and Technology 451-4

Extracts from Journal of Metallurgy and Ceramics. Issue Nos. 1
to 6, 7/48--1/51

Nucl. Sci. Abstr. 1958 () 2153

W. C. Bell (North Carolina State Coll.)

Research on Vibratory Compacting of Metal and Ceramic Powders
Quarterly Report No. 3 (10/20/52--1/20/53)

Project No. 52-670A-83

Contract AF33(616)-73

Nucl. Sci. Abstr. 1957 (12) 1480

W. C. Bell, R. D. Dillender, H. R. Lominac, L. W. Long, and E. G.
Manning

Vibratory Compacting of Metal and Ceramic Powders

U. S. Air Force, Air Research and Development Command, WADC Tech.
Rept. No. 53-193 (4/53)

Ceram. Abstr. 1954 (1) 13

W. C. Bell, R. D. Dillender, H. R. Lominac, L. W. Long, E. G.
Manning (North Carolina State Coll.)

Vibratory Compacting of Metal and Ceramic Powders

Period Covered: 4/20/53--4/20/54

Task title: Ceramic and Cermet Research

Contract AF-33(616)-73

Ceram. Abstr. 1957 (10) 1237

W. C. Bell and J. R. Hart (North Carolina State Coll.)

Vibratory Compacting of Metal and Ceramic Powders

Quarterly Report No. 10 (10/1/54--1/1/55)

Project No. 7350

Contract AF33(616)-73

Nucl. Sci. Abstr. 1958 (1) 25

W. C. Bell and J. R. Hart (North Carolina State Coll.)

Vibratory Compacting of Metal and Ceramic Powders

Quarterly Report No. 11 (1/2/55--4/2/55)

Project No. 7350

Contract AF33(616)-73

Nucl. Sci. Abstr. 1958 (1) 25

W. C. Bell

An Introduction to the Vibratory Compaction of Powders
Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc. 74-77 (1958)

G. Helm

Use of Shaking Procedures in Ceramics
Sprechsaal 88 (10) 221-3; (11) 243-5; (12) 266-9 (1955)
Ceram. Abstr. 1956 (6) 120

H. R. Hoge (Westinghouse Electric Corp. Atomic Power Div.)
An Interim Report on Vibratory Packing for the Period of October 1954 to April 1955

Decl. 3/19/57
Nucl. Sci. Abstr. 1958 (1) 223

P. N. Kulryavtsev

Mechanical Molding of Silicon Carbide Electric Heating Elements
Ogneupory 23 (4) 156-9 (1958)
Ceram. Abstr. 1958 (9) 238

To Societe Belge pour l'Industrie Nucleaire
Manufacture of Fuel Elements for Nuclear Reactors
Belgain Patent 584,990 (11/25/59)
Nucl. Sci. Abstr. 1961 (6) 2070

J. J. Hauth (General Electric Co.)
Vibration-compacted Ceramic Fuel Elements (Invention Report)
6/9/59
Nucl. Sci. Abstr. 1961 (5) 1484

J. E. Brown (General Electric Co.)
Swage Compaction of Ceramics. Unique Fabrication Technique Utilized to Advantage in Production of UO_2 Fuel Elements
Ceram. Age 75 No. 1 (1) 20-4 (1960)
Nucl. Sci. Abstr. 1962 (1) 253

J. J. Hauth (General Electric Co.)
Vibrationally Compacted Ceramic Fuels
Contract AT(45-1)-1350 (1/10/61)
Nucl. Sci. Abstr. 1961 (8) 2624

J. J. Hauth (General Electric Co. Hanford Atomic Products Operation)
Vibration-compacted Ceramic Fuels
Nucleonics 20 (9) 50-4 (1962)
Nucl. Sci. Abstr. 1962 (11) 4044

J. J. Hauth and R. J. Anicetti (USA-AEC)
Method of Preparing a Fuel Element for a Nuclear Reactor
U. S. Patent 3,067,117 (12/4/62)
Nucl. Sci. Abstr. 1963 (3) 1141

J. J. Hauth (USA-AEC)
Vibration Compaction
U. S. Patent 3,042,594 (7/3/62)
Ceram. Abstr. 1962 (10) 248

J. J. Hauth (General Electric Co. Hanford Atomic Products Operation)
Fabrication Techniques for Packed-powder Fuel Elements
CEND-153 Vol. I 11-12
Nucl. Sci. Abstr. 1963 (4) 1449

General Electric Co. Hanford Atomic Products Operation
IV. Ceramic Uranium Fuel
HW-74761 41-47
Nucl. Sci. Abstr. 1963 (3) 976

R. K. Koler and R. E. Sharp (General Electric Co. Hanford Atomic
Products Operation)
Fabrication of Plutonium-bearing Ceramic Fuel Elements by Vibrational
Compaction
Contract AT(45-1)-1350 (11/9/62)
Nucl. Sci. Abstr. 1963 (5) 1918

R. K. Koler and R. E. Sharp (General Electric Co.)
Fabrication of Plutonium-bearing Ceramic Fuel Elements by Vibra-
tional Compaction
Trans. Am. Nucl. Soc., 5 (11) 543-4 (1962)
Nucl. Sci. Abstr. 1963 (2) 500

C. H. Bloomster, R. E. Bardsley, and W. T. Ross (General Electric
Co. Hanford Atomic Products Operation)
An Incremental Loading Process to Control Plutonium Enrichment
in Mechanically-mixed Oxide Fuel Systems
Contract AT(45-1)-1350 (11/1/62)
Nucl. Sci. Abstr. 1963 (5) 1917

Combustion Engineering, Inc. Nuclear Div.
The Development and Testing of the UO_2 Fuel Element System
Quarterly Report (9/1/60--11/30/60) (12/60)
Contract AT(30-1)-2379
Nucl. Sci. Abstr. 1961 (6) 1887

Combustion Engineering, Inc. Nuclear Div.
The Development of the UO_2 Fuel System
Quarterly Report (12/1/60--2/28/61) (3/61)
Contract AT(30-1)-2379
Nucl. Sci. Abstr. 1962 (11) 4046

Combustion Engineering, Inc. Nuclear Div.
Vibratory Compaction of Double Annular Fuel Elements for NUSU
Critical Experiment
Contract AT(11-1)-795 (2/61)
Nucl. Sci. Abstr. 1962 (11) 4042

B. E. Murtha and W. P. Chernock (Combustion Engineering, Inc.
Nuclear Div.)
The Development and Testing of the UO_2 Fuel Element System
Summary Report (6/61)
Contract AT(30-1)-2379
Nucl. Sci. Abstr. 1962 (5) 1432

B. E. Murtha and W. P. Chernock (Combustion Engineering, Inc.
Nuclear Div.)
The Development and Testing of UO_2 Fuel Systems for Water Reactor
Applications
Quarterly Report (7/61--9/61) (10/27/61)
Contract AT(30-1)-2863
Nucl. Sci. Abstr. 1962 (8) 2728

B. E. Murtha and W. P. Chernock (Combustion Engineering, Inc.
Nuclear Div.)
The Development and Testing of UO_2 Fuel Systems for Water Reactor
Applications
Quarterly Report No. 2 10/61--12/61 (1/62)
Contract AT(30-1)-2863
Nucl. Sci. Abstr. 1962 (12) 4215

Combustion Engineering, Inc. Nuclear Div.
Symposium on Powder Packed Uranium Dioxide Fuel Elements
Vol. I 11/30/61--12/1/61
Contract AT(30-1)-2379
Nucl. Sci. Abstr. 1963 (4) 1448

Combustion Engineering, Inc. Nuclear Div.
Symposium on Powder Packed Uranium Dioxide Fuel Elements
Vol. II 11/30/61--12/1/61
Contract AT(30-1)-2379
Nucl. Sci. Abstr. 1963 (4) 1450

R. C. Brayer and B. E. Murtha (Combustion Engineering, Inc.
Nuclear Div.)
Pneumatic Vibratory Compaction of UO_2
CEND-153 Vol. I 45-59
Nucl. Sci. Abstr. 1963 (4) 1449

E. I. Veil and R. H. Gale (Combustion Engineering, Inc. Nuclear
Div.)
Fabrication of UO_2 Fuel Elements by the 'Vibswage' Process
CEND-153 Vol. I 137-47
Nucl. Sci. Abstr. 1963 (4) 1449

B. E. Murtha and W. P. Chernock (Combustion Engineering, Inc.
Nuclear Div.)
The Development and Testing of UO_2 Fuel Systems for Water Reactor
Applications
Third Quarterly Report 1/62--3/62
Contract AT(30-1)-2863
Nucl. Sci. Abstr. 1963 (5) 1917

Babcock and Wilcox Co. Atomic Energy Div.
Development and Testing of Low Cost Fuel Elements for Power Reactor
Service

6/2/61

Nucl. Sci. Abstr. 1962 (1) 323

J. D. L. Harrison, E. Foster, and L. E. Russel (Atomic Energy
Research Establishment)

The Sintering Behavior of Mixed UO_2 and PuO_2 Powders
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG. 1962 140-65
Nucl. Sci. Abstr. 1963 (1) 256

J. Servais and C. Descamps (Centre d'Etude de l'Energie Nucleaire
and Societe Belge pour l'Industrie Nucleaire)

Sonic and Ultrasonic Compaction of UO_2
Contract O27-60-7RDB (11/30/61)
Nucl. Sci. Abstr. 1962 (11) 4042

Aeroprojects Inc.

Applications of Ultrasonic Energy. Task 1. Chemical Processing.
Task 2. Metal and Ceramic Powder Processing. Task 3. Ultrasonic
Instrumentation

Progress Report No. 19 Covering 12/1/59--1/31/60 (3/60)
Contract AT(30-1)-1836
Nucl. Sci. Abstr. 1961 (11) 3513

Aeroprojects Inc.

Applications of Ultrasonic Energy. Task 1. Chemical Processing.
Task 2. Ultrasonic Metal and Ceramic Powder Processing. Task 3.
Ultrasonic Instrumentation

Progress Report No 24. 10/1/60--11/31/60 (12/60)
Contract AT(30-1)-1836
Nucl. Sci. Abstr. 1961 (9) 3040

W. B. Tarpley and R. Pheasant (Aeroprojects Inc.)

Ultrasonic Filling of Tubular Cladding with Ceramic Fuel Powders
Presented at 64th ACS
Am. Ceram. Soc. Bull. 41 (4) 1962

- B. E. Murtha and W. P. Chernock (Combustion Engineering, Inc.
Nuclear Div.)
The Development and Testing of UO_2 Fuel Systems for Water Reactor
Applications
Progress Report, Period Ending 12/31/62 (1/63)
Contract AT(30-1)-2863
Nucl. Sci. Abstr. 1963 (5) 1922
- C. E. Burdg, D. E. Nulk, B. E. Murtha, and W. P. Chernock
(Combustion Engineering, Inc.)
Vibratory Compaction of UO_2 Fuel Elements for Use In Critical Ex-
periments
Trans. Am. Nuclear Soc. 5 No. 1 (6) 237-8 (1962)
Nucl. Sci. Abstr. 1962 (9) 3222
- W. Uhlmann (Aktiebolaget Atomenergi)
The Vibratory Compacting of Powders, in Particular as Applied to
Uranium Dioxide
11/61
Nucl. Sci. Abstr. 1962 (2) 419
- H. H. Hausner
Pressureless Compacting and Sintering Metal Powders
J. Metals 13 (10) 752-8 (1961)
Nucl. Sci. Abstr. 1961 (12) 4193
- W. C. Pritchard, K. A. Johnson, J. A. Leary, and W. J. Maraman
(Los Alamos Scientific Lab.)
Compaction and Sintering of PuO_2 -Mo Powder Mixtures
Contract W-7405-ENG-36 (8/23/61)
Nucl. Sci. Abstr. 1962 (2) 418
- N. Quinn
Zirconia Refractories--a New Approach
Refractories Journal 37 (8) 236-7 (1961)
Ceram. Abstr. 1962 (2) 39
- F. W. Calderwood, D. R. Wilder, and H. A. Wilhelm (Ames Lab.)
The Jolt-pack Fabrication of Special Ceramic Ware
Proc. Iowa Acad. Sci. 68 202-21 (1961)
Nucl. Sci. Abstr. 1962 (10) 3612

H. G. Marsh (Du Pont de Nemours (E.I.) & Co.)
Fabrication of UO_2 Fuel Elements by Vibrational Compaction
Contract AT(07-2)-1 (2/62)
Nucl. Sci. Abstr. 1962 (11) 4042

W. R. DeHollander (General Electric)
Vibrational Compaction of Uranium Dioxide
AEC Research and Development Report GEAP-4032 (3/1/62)
Contract AT(04-3)-361

W. R. DeHollander (General Electric)
Particle Size Relationships in the Packing of UO_2
CEND-153 Vol. 1 75-83
Nucl. Sci. Abstr. 1963 (4) 1449

C. M. Ryer (General Electric)
Powder Fuel Processing by Two-pass Swaging. The Effect of Particle
Size and Distribution
Contract AT(04-3)-361 (4/10/62)
Nucl. Sci. Abstr. 1963 (2) 631

General Scientific Corp.
Development of Unique Methods for Radioactive Source Fabrication--
Vibratory Compaction
Quarterly Progress Report I. (7/62)
Contract AT(30-1)-2981
Nucl. Sci. Abstr. 1963 (5) 2164

General Scientific Corp.
Development of Unique Methods for Radioactive Source Fabrication--
Vibratory Compaction
Quarterly Progress Report II. (10/62)
Contract AT(30-1)-2981
Nucl. Sci. Abstr. 1963 (4) 1643

M. A. Feraday (Atomic Energy of Canada Ltd.)
Cold Swaging UO_2 in Zircaloy; the Effect of Some Process Variables
on Fuel Density and Sheath Integrity
An Interim Report
Nucl. Sci. Abstr. 1963 (4) 1449

Anon.

Fuel Elements: Fabrication by Powder Compaction
Power Reactor Technology 6 No. 1 26-37
Nucl. Sci. Abstr. 1963 (4) 1558

W. B. Tarpley and R. Pheasant (Aeroprojects, Inc.)
Ultrasonic Filling of Tubular Cladding with Ceramic Fuel Powders
CEND-153 Vol. II 163-94
Nucl. Sci. Abstr. 1963 (4) 1451

J. D. Luoma, W. G. Lussie, and K. R. Trosien (Argonne National
Lab.)
Fabricating Particulate Fuel Rods
Unpublished to date: compiled 7/26/63

S. D. Clinton, O. C. Dean, W. S. Ernst, D. E. Ferguson, P. A. Haas,
and K. H. McCorkle (Oak Ridge National Lab.)
Preparation of High-density Oxides and Vibratory Compaction in
Fuel Tubes.
Contract W-7405-eng-26 (2/13/61)
Nucl. Sci. Abstr. 1961 (4) 1205

P. Patriarca (Oak Ridge National Lab.)
Part I. Reactor Project Activities
ORNL-3313 1-18
Nucl. Sci. Abstr. 1962 (11) 4045

D. E. Ferguson, O. C. Dean, and P. A. Haas (Oak Ridge National
Lab.)
Preparation of Oxide Fuels for Vibratory Compaction by the Sol-
gel Process
CEND-153 Vol. I 23-38
Nucl. Sci. Abstr. 1963 (4) 1449

W. S. Ernst, Jr. and R. L. Beatty (Oak Ridge National Lab.)
Vibratory-compaction Studies at the Oak Ridge National Laboratory
CEND-153 Vol. I 61-74
Nucl. Sci. Abstr. 1963 (4) 1449

R. L. Eichinger (Allis-Chalmers Mfg. Co.)
Vibratory and Swage Compaction of Small Diameter Stainless Steel
Clad Fuel Rods
CEND-153 Vol. 1 149-62
Nucl. Sci. Abstr. 1963 (4) 1449

S. Takahashi and N. Asami (Mitsubishi Atomic Power Industries,
Inc.)
An Approach to Vibration Compaction of Uranium Dioxide
Nippon Genshiryoku Gakkaishi 5 (2) 133-40 (1963)
Nucl. Sci. Abstr. 1963 (6) 2444

Flh. IMPACT FORMING; SWAGING
(see also Flg, F23h)

A. S. Bain, G. M. Allison, W. Evans, M. B. Watson, and E. Barnes
(Atomic Energy of Canada Ltd.)

The Failure of a Stainless Steel Clad Swaged Uranium Oxide Specimen in the X-2 Loop

12/12/58

Nucl. Sci. Abstr. 1959 (7) 1590

Societe Belge pour l'Industrie Nucleaire, Brussels and Brussels.
Centre d'Etude de l'Energie Nucleaire

The Use of Plutonium as Fuel in Nuclear Reactors

Quarterly Report No. 1 7/15/60--10/15/60

Contract 027-60-7RDB

Nucl. Sci. Abstr. 1962 (7) 2417

C. Sari and E. Jonckheere (Centre d'Etudes l'Energie Nucleaire)

Depositing of Particles by Metalization in Vacuum

Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961

Reutte/Tyrol, Metallwerk Plansee AG. 600-14 (1962)

Nucl. Sci. Abstr. 1963 (1) 260

A. S. Ferrara (Du Pont de Neumours (E.I.) & Co.)

Swaging of Uranium Dioxide Tubes. Part I

Contract AT(07-2)-1 (8/60)

Nucl. Sci. Abstr. 1963 (6) 2442

FIAT. Sezione Energia Nucleare

Swaging of Uranium Oxide

Quarterly Report No. 1 5/60--7/31/60

Contract 013-60-5RDI

Nucl. Sci. Abstr. 1962 (8) 2734

Nucl. Sci. Abstr. 1961 (7) 2237

FIAT. Sezione Energia Nucleare

Swaging of Uranium Dioxide

Quarterly Report No. 2 8/1/60--10/31/60 (11/30/60)

Contract EUR/C/434/60 I

Nucl. Sci. Abstr. 1961 (7) 2237

Nucl. Sci. Abstr. 1962 (8) 2511

FIAT. Sezione Energia Nucleare

Swaging of Uranium Dioxide

Quarterly Report No. 5 7/1/61--9/30/61 (10/31/61)

Contract 059-61-7RDI

Nucl. Sci. Abstr. 1962 (7) 2343

FIAT. Sezione Energia Nucleare
Swaging of Uranium Dioxide
Quarterly Report No. 6 10/1/61--12/31/61 (1/31/62)
Contract 059-61-7RDI
Nucl. Sci. Abstr. 1962 (8) 2512

FIAT. Sezione Energia Nucleare
Swaging of Uranium Dioxide
Annual Report No. 2 7/1/61--6/30/62 (7/31/62)
Contract 059-61-7RDI
Nucl. Sci. Abstr. 1963 (4) 1451

FIAT. Sezione Energia Nucleare
Swaging of Uranium Dioxide
Quarterly Report No. 7 1/1/62--3/31/62 (4/30/62)
Contract 059-61-7-RDI
Nucl. Sci. Abstr. 1962 (12) 4224

FIAT. Sezione Energia Nucleare
Cold Swaging of Uranium Dioxide
CEND-153 Vol. I 163-9
Nucl. Sci. Abstr. 1963 (4) 1449

E. A. Lees (General Electric Co.)
Fabrication of Fuel Elements by Swaging
Trans. Am. Nuclear Soc. 4 No. 1 (6) 151-2 (1961)
Nucl. Sci. Abstr. 1961 (8) 2736

R. L. Brown (General Electric Co.)
Swaging Over Unground Pellets
Contract AT(04-3)-361 (1/25/61)
Nucl. Sci. Abstr. 1961 (11) 3613

R. E. Bardsley and R. E. Sharp (General Electric Co.)
Fabrication of UO_2 - PuO_2 Swage-Compacted Fuel Elements
Trans. Am. Nucl. Soc. 5 (11) 452-3 (1962)
Nucl. Sci. Abstr. 1963 (2) 500

R. E. Bardsley and R. E. Sharp (General Electric Co.)
Fabrication of UO_2 - PuO_2 Swage Compacted Fuel Elements
Contract AT(45-1)-1350 (11/62)
Nucl. Sci. Abstr. 1963 (5) 1918

M. Yokosuka, S. Takahashi, Y. Honda, and Y. Seki (Mitsubishi Atomic Power Industries, Inc.)
On the Sheath Defects of Swaged UO_2 Fuel Elements of Rod and Hollow Types
Fuel Element Fabrication with Special Emphasis on Cladding Materials: Academic Press 55-72 (1961)
Nucl. Sci. Abstr. 1961 (10) 3252

F. Hofmann and B. Liebmann (Nuklear-Chemie und-Metallurgie G.m.b.H.)
First Quarterly Report on the Production of Swaged Oxide Fuel Elements
5/1/60--7/30/60
AEC149/EURATOM 132
Nucl. Sci. Abstr. 1961 (8) 2561
Nucl. Sci. Abstr. 1962 (8) 2511

P. Himmelstein, F. Hofmann, B. Liebmann, O. Neumann, and L. Schaefer (Nuklear-Chemie und-Metallurgie G.m.b.H.)
Fabrication of Uranium and Mixed Carbides and UC-Based Cermets, Corrosion Processing and Property Tests
Quarterly Report No. 4 4/61--6/61
Appendix 1 to NUKEM letter dated 7/31/61
Contract (012-60-5RDA)
Nucl. Sci. Abstr. 1962 (7) 2343

F. Hofmann, H. Kroll, and B. Liebmann (Nuklear-Chemie und-Metallurgie G.m.b.H.)
Fabrication of Oxide Fuel Elements Using The Swaging Process
Fourth Quarterly Report 4/61--6/30/61
Appendix 2 to NUKEM Letter to Euratom 7/31/61
Nucl. Sci. Abstr. 1962 (4) 1180

F. Hofmann and B. Liebmann (Nuklear-Chemie und-Metallurgie G.m.b.H.)
Second Quarterly Report on the Formation of Oxidic Fuel Elements by Means of the Swaging Method
8/1/60--10/31/60
AEC149/EURATOM 132
Nucl. Sci. Abstr. 1961 (8) 2561

Nuklear-Chemie und-Metallurgie G.m.b.H.
Production of Swaged Fuel Elements
Quarterly Report No. 9 7/1/62--9/30/62
Contract 062-61-7RDD
Nucl. Sci. Abstr. 1963 (4) 1643

Flm. FORMING AT SUPERPRESSURES (ABOVE 100,000 psi)

G. V. Chilingar and L. Knight

Relationship between Pressure and Moisture Content of Kaolinite,
Illite, and Montmorillonite Clays

Bull. Am. Assoc. Petrol. Geologists 44 (1) 101-106 (1960)

Ceram. Abstr. 1961 (4) 103

P. W. Montgomery, H. Stromberg, and G. Jura (Univ. of California)
Sintering of Refractory Materials at Room Temperature by High Pres-
sures

Advan. Chem. Ser. 33 18-25 (1961)

Nucl. Sci. Abstr. 1963 (2) 474

Flr. ZERO PRESSURE COLD FORMING

H. H. Hausner, D. P. Ferriss, and F. W. Heck (Penn-Texas Corp.
and Stevens Inst. of Tech.)
Compacting and Sintering of Metal Powders without the Application
of Pressure
Contract AT(30-1)-1991 (5/25/57)
Nucl. Sci. Abstr. 1958 () 1251

H. H. Hausner (Polytechnic Inst.)
Sintering Behavior of Loose Metal Powders
Planseeber. Pulvermet. 9 (4) 26-32 (1961)
Nucl. Sci. Abstr. 1961 (8) 2562

F. V. Lenel (Rensselaer Polytechnic Inst.)
The Comparison of Sintering Loose Metal Powders and Pressed Metal
Powder Compacts
Progress Report 3/1/62--2/28/63 (3/63)
Contract AT(30-1)-2408
Nucl. Sci. Abstr. 1963 (6) 2443

H. H. Hausner
Pressureless Compacting and Sintering Metal Powders
J. Metals 13 (10) 752-8 (1961)
Nucl. Sci. Abstr. 1961 (12) 4193

Flr. RHEOLOGICAL CONTROLS. RESPONSE OF MATERIAL
(see Flb3, F20d)

F2a. GENERAL

F2-COLD FORMING FROM PASTES (PLASTIC FORMING)

H. Salmang

Texture of Ceramic Materials

Ber. Deut. keram. Ges. 30 (11) 247-51 (1953)

Ceram. Abstr. 1954 (7) 128

F. H. Norton

Warping and Its Control

Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc. 115-120 (1958)

J. R. Castillo Villaamil

Modern Methods of Forming Refractory Brick

Bol. Soc. Espan. Ceram. 1 (4) 199-205 (1962)

Ceram. Abstr. 1963 (6) 160

F2c,d. PRESSING PLASTIC BODIES

C. R. Amberg

Slurry Process for Making Soft-mud Brick

Am. Ceram. Soc. Bull. 32 (5) 183-5 (1953)

Ceram. Abstr. 1953 (6) 121

W. Mason

Shaping or Finishing of Articles of Clay

Brit. 715,815 (9/22/54)

Ceram. Abstr. 1956 (1) 18

E. M. Gibbs and J. Stout

Story of Electrical Porcelain IV, Pugging and Pressing

Ceram. Ind. 66 (5) 84-6 (1956)

Ceram. Abstr. 1957 (1) 15

P. P. Budnikov

Physicochemical Fundamentals of Ceramics--a Collection of Papers
Scientific-Technical Society of the Construction Material Industry
1956

Ceram. Abstr. 1958 (6) 105

A. A. Korsakov

Economic Advantages of the Semidry Method of Production

Ogneupory 22 (7) 296-300 (1957)

Ceram. Abstr. 1958 (7) 173

R. E. Steele and A. R. Blackburn

Method and Apparatus for Forming Holes in Ceramic Ware

U. S. 2,818,628 (1/7/58)

Ceram. Abstr. 1958 (4) 95

A. R. Blackburn and R. E. Steele (Ram., Inc.)

Method of Molding Ceramic Ware

U. S. Patent 3,010,176 (11/28/61)

Ceram. Abstr. 1962 (5) 120

F2e. EXTRUDING CLAY-WATER PASTES

E. Vogt

Manufacture of Porcelain Tubes on Extrusion Presses

Silikattech 4 (2) 82 (1953)

Ceram. Abstr. 1953 (9) 163

W. Avenhaus (Verlag Wilhelm Knapp)

Mechanical Tile Production

1953

Ceram. Abstr. 1953 (9) 160

J. H. Weymouth and W. D. Williamson

Effects of Extrusion and Some Other Processes on the Microstructure
of Clay

Am. J. Sci. 251 (2) 89-108 (1953)

Ceram. Abstr. 1954 (1) 20

J. O. Everhart, K. E. Krill, R. E. Dine, and R. R. VanDer Beck

(National Clay Pipe Research Corp.)

Method and Apparatus for Forming Tubular Ceramic Bodies

U. S. 2,671,939 (3/16/54)

Ceram. Abstr. 1954 (9) 162

D. M. Baker

Extrusion as a Method of Forming

Ceram. Age. 64 (5) 41-42 (1954)

Ceram. Abstr. 1955 (6) 109

A. Puigdemont

Extruding Thin Ceramic Plates.

Ceramica (Sao Paulo) 1 (4) 184-87 (1955)

Ceram. Abstr. 1956 (8) 169

J. G. Seanor

Extraneous Factors that Affect the Operation of Clay Extrusion
Dies

Am. Ceram. Soc. Bull. 35 (9) 361-62 (1956)

Ceram. Abstr. 1956 (11) 243

P. P. Rost and V. S. Fadeeva

Shaping Components of a Band Press

Steklo i Keram 13 (7) 16-23 (1956)

Ceram. Abstr. 1959 (7) 188

L. R. Alt

Extrusion Die Problems

Am. Ceram. Soc. Bull. 36 (4) 137-38 (1957)

Ceram. Abstr. 1957 (6) 140

G. C. Robinson and J. J. Keilen

Role of Water in Extrusion and Its Modification by a Surface-active Chemical

Am. Ceram. Soc. Bull. 36 (11) 422-30 (1957)

Ceram. Abstr. 1958 (1) 27

V. S. Fadeeva

Shaping Ceramic Ware from Plastic Clay Bodies

Steklo i Keram 14 (3) 12-20 (1957)

Ceram. Abstr. 1959 (6) 165

F. J. Goodson

Experiments in Extrusion

Trans. Brit. Ceram. Soc. 58 (3) 158-87 (1959)

Ceram Abstr. 1960 (6) 143

W. Gilbert

Some Problems of Manufacture by the Wire-cut Process

Trans. Brit. Ceram. Soc. 58 (11) 629-44 (1959)

Ceram. Abstr. 1960 (9) 215

E. B. Cornelius (Houdry Process Corp.)

Method for Clay Extrusion

U. S. 2,952,888 (9/20/60)

Ceram. Abstr. 1961 (1) 17

J. O. Everhard

Thoughts on Die Design

Ceram. Age 76 (3) 29-31 (1960)

Ceram. Abstr. 1961 (4) 96

J. G. Seanor

Brick Dies

Journal of Canadian Ceram. Soc. 29 72-78 (1960)

Ceram. Abstr. 1962 (1) 7

- E. Stutzky
Defects in Mechanical Shaping and Their Remedies
Ziegelind 13 (14) 504-509 (1960)
Ceram. Abstr. 1961 (1) 17
- F. S. Entelis
Determining Anisotropy and the Artificial Structural Properties
in Plastic Ceramic Bodies
Glass & Ceramics, Moscow 18 No. 2. 83 (1961)
Brit. Ceram. Abstr. 1962 (5) 128A
- British Ceramic Research Association
Plugging and Extrusion Research, 1958-1959
Claycraft 35 88 (1961)
Brit. Ceram. Abstr. 1962 (6) 162A
- E. Bruckner (Gebrüder Netzsch Maschinenfabrik)
Apparatus on Extrusion Worm Presses for Eliminating the Texture
in Ceramic Masses
U. S. 3,031,731 (5/1/62)
Ceram. Abstr. 1962 (9) 211
- H. H. Lund, S. A. Borman, A. J. Reed
Auger Design for Clay Extrusion
Am. Ceram. Soc. Bull. 41 (9) 554-59 (1962)
Ceram. Abstr. 1962 (10) 238
- M. E. Stedham
Improved Method of Moisture Control for Ceramic Products
Trans. Brit. Ceram. Soc. 61 (9) 550-70 (1962)
Ceram. Abstr. 1963 (3) 71
- A. J. Reed
Auger Design
Am. Ceram. Soc. Bull. 41 (9) 549-50 (1962)
Ceram. Abstr. 1962 (10) 238
- J. G. Seanor and W. P. Schweitzer
Basic Theoretical Factors in Extrusion Augers
Am. Ceram. Soc. Bull. 41 (9) 560-63 (1962)
Ceram. Abstr. 1962 (10) 238

Z. Szwiecki (Polytech. Wroclaw)

Effect of Internal Separation During the Extrusion of Plastic
Clays on Their Properties in the Dry Condition

Chem. Stosowana 6 79-97 (1962)

Chem. Abstr. 1962 (8) 4341

T. H. Milliken, Jr. (to Houdry Process Corp.)

Plastic Kaolin for Extrusion into Catalyst Pellets

U. S. 2,988,518 (6/13/61)

Chem. Abstr. 55 25093

Engelhard Industries, Inc.

Extrusion of Alumina Hydrate Catalyst Bases

Brit. 834,210 (5/4/60)

Chem. Abstr. 54 20016

F2g. TURNING COLD PLASTIC BODIES
(see also F2s, G2)

H. J. Smith, J. A. Johnson, and E. A. Hawk (T. G. Green & Co.)
Shaping of Clayware Articles
Brit. 676,428 (6/5/52)
Ceram. Abstr. 1953 (5) 88

A. J. Wahl and G. J. Croninger
Development of a Machine for Turning Green Ware
Am. Ceram. Soc. Bull. 32 (12) 415-16 (1953)
Ceram. Abstr. 1954 (2) 36

H. Salmano
Macrostructure of Fragments of Earthenware Fabricated by Jiggering
Bull. soc. franc. ceram. No. 18 15-29 (1953)
Ceram. Abstr. 1954 (3) 52

E. Kleinpaul
Process of Changing a casting slip into a Body for Turning
Fr. 1,120,381 (4/16/56)
Ceram. Abstr. 1957 (9) 208

R. W. Watkin (Edwin M. Knowles China Co.)
Ware-forming Apparatus
U. S. 2,813,324 (11/19/57)
Ceram. Abstr. 1958 (2) 49

R. E. Gould and J. Lux
Some Experiences with the Control of Plastic Bodies for Automatic
Jiggering
Ceramic Fabrication Processes: The Technology Press of Mass. In-
stitute of Technology and John Wiley & Sons, Inc. 98-107 (1958)

J. A. Johnson
Apparatus for Shaping Clayware
U. S. 2,876,522 (3/10/59)
Ceram. Abstr. 1959 (6) 165

G. Helm
Shaping and Auxiliary Equipment for the Jollying (Jiggering) of
Ceramic (Flat and Hollow) Ware
Glas-Email-Keramo-Tech. 11 (6) 185-92 (1960)
Ceram. Abstr. 1960 (11) 265

F2h. TAMPING, RAMMING

Materiel Ceramique Moderne
Automatic Ramming Press
Fr. 1,076,092
Ceram. Abstr. 1955 (10) 185

Soc. Anon. Etablissements A. Valuy and Materiel Ceramique Moderne
Apparatus for Tamping Ceramic Powders
Brit. 732,560 (6/29/55)
Ceram. Abstr. 1958 (3) 77

T. T. Magel, J. L. Ohlson, and A. Zais (Mass. Inst. of Tech.)
The Preparation of Large Magnesia Crucibles
9/45 Decl. with deletions 2/18/57
Nucl. Sci. Abstr. 1957 (10) supplement

P. N. Kudryavtsev
Mechanical Molding of Silicon Carbide Electric Heating Elements
Ogneupory 23 (4) 156-59 (1958)
Ceram. Abstr. 1958 (9) 238

F2j,k. CEMENT-AIDED PLASTIC FORMING

T. E. Barlow and P. D. Humont
Gun-placed Silica Cupola Linings
Am. Ceram. Soc. Bull. 33 (10) 301-306 (1954)
Ceram. Abstr. 1955 (1) 11

L. A. Tseitlin and V. P. Rakina
Plasticizing Treatment of Grog and High Alumina Mortars
Ogneupory 22 (11) 513-19 (1957)
Ceram. Abstr. 1958 (9) 238

E. Stephen
Plastics and Castables
Tonind.-Ztg. u. Keram. Rundschau 78 (1/2) 11-13 (1954)
Ceram. Abstr. 1954 (7) 126

J. F. Wygant
Pneumatic Gun Operating Variables Affecting Castable Refractories
Am. Ceram. Soc. Bull. 42 (5) 317-20 (1963)
Ceram. Abstr. 1963 (6) 160

F2r. RHEOLOGY OF CLAY PASTES

E. C. W. A. Geuze
Rheology as a Basis for the Study of the Plastic Properties of
Ceramic Materials
Trans. Intern. Ceram. Congr., 3rd Congr., Paris, 1952 91-97
Ceram. Abstr. 1957 (6) 96

V. C. Mitsuki and M. Kobayashi
Fundamental Studies on Plasticity
Bull. Govt. Research Inst. Ceramics (Kyoto) 6 (1) 29-30 (1952)
Ceram. Abstr. 1953 (1) 9

P. Visseriat
Pressure Measurements in Ceramics
Bull. soc. franc. ceram. No. 16 25-32 (1952)
Ceram. Abstr. 1954 (3) 55

J. H. Weymouth and W. O. Williamson
Some Effects of Processing Operations on the Porosity of Earthen-
ware and Related Bodies
Trans. Brit. Ceram. Soc. 51 (10) 489-510 (1952)
Ceram. Abstr. 1954 (3) 52

J. H. Weymouth and W. O. Williamson
Some Observations on the Microstructure of Fired Earthenware
Trans. Brit. Ceram. Soc. 52 (6) 311-28 (1953)
Ceram. Abstr. 1954 (3) 53

E. Deeg
Investigation of the Elastic-plastic Behavior of a Hard Porcelain
Body from the Wet Plastic to the Fully Fired State
Ber. deut. keram. Ges. 33 (1) 1-7 (1956)
Ceram. Abstr. 1956 (6) 147

T. Haase
Workability of Plastic Ceramic Bodies
Ber. deut. keram. Ges. 34 (2) 27-33 (1957)
Ceram. Abstr. 1957 (10) 260

W. O. Williamson
Particle Orientation in Clays and Whitewares and Its Relation to
Forming Processes
Ceramic Fabrication Processes: The Technology Press of Mass. In-
stitute of Technology and John Wiley & Sons, Inc. 89-98 (1958)

T. Haase

Investigations of the Plasticity of Ceramic Bodies

Silikattech. 5 (10) 429-31 (1954)

Ceram. Abstr. 1955 (5) 89

A. S. Michaels

Rheological Properties of Aqueous Clay Systems

Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc 23-31 (1958)

F. H. Norton

Clay-water Pastes

Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc. 81-89 (1958)

S. P. Nichiporenko

Significance of Rheological Curves of Ceramic Bodies in Ceramic Technology

Dokl. Akad. Nauk SSSR 118 (4) 785-87 (1958)

Ceram. Abstr. 1963 (1) 29

J. A. Nelson and A. I. Andrews

Rheological Properties of the Clay-water System Under Pressure

Am. Ceram. Soc. Bull. 38 (9) 447-55 (1959)

Ceram. Abstr. 1959 (11) 292

E. Hallmann

Calculation of Extrusion Press for Solid Particles

Ziegelind. 13 (-10) 321-30 (1960)

Ceram. Abstr. 1960 (10) 239

K. Zimmermann and W. Cremer

Plasticizing of Slips and the Possible Industrial Applications of This Method

Ber. deut. keram. Ges. 37 (7) 316-23 (1960)

Ceram. Abstr. 1961 (5) 121

Brit. Ceram. Abstr. 1961 (2) 49A

C. Ekedahl

Influence of Water and Pressure on the Forming of Clay Bodies

Ceram. Age 77 (5) 28-30, 32-33 (1961)

Ceram. Abstr. 1962 (3) 69

A. Kubovy and Z. Popisil
Some Physical Relations of the Wet Pressing of Ceramic Bodies
Silikaty 5 40 (1961)
Brit. Ceram. Abstr. 1961 (10) 323A

G. Capriz (Nelson Research Laboratories, English Electric Co.)
A Theoretical Analysis of Extrusion Processes
Trans. Brit. Ceram. Soc. (4) 339 (1963)

V. S. Fadeeva
The Optimum Moisture (content) for Shaping Building Ceramics Ware
from Plastic Dispersed Masses
Steklo i Keram. 16 No. 8 33-9 (1959)
Chem. Abstr. 53 20729

F2s. STEAM-ASSISTED FORMING OF CLAY BODIES

W. Ziegler

Hot Preparation of Ceramic Bodies to Obtain Better Disintegration,
Faster Drying, and Less Fracture
Silikattech. 2 (11) 337-40 (1951)
Ceram. Abstr. 1953 (1) 10

D. N. Poluboyarinov and R. M. Zalonts

Basic Factors in the Hot Pressing of Ceramic Shapes
Steklo i Keram. 9 (9) 16-21 (1952)
Ceram. Abstr. 1955 (10) 179

F. W. Hisschemoller

Practical Tests on the Warming of Clay by Steam and on the Deairing
of Clay for the Soft-mud Process
Klei 3 (6-7) 245-60 (1953)
Ceram. Abstr. 1954 (5) 90

Soest-Ferrum Apparatebau G.m.b.H.

Process and Apparatus for the Preparation of Plastic Ceramic
Bodies
Fr. 1,040,478 (5/20/53)

C. J. Lenz

Hot Preparation of Refractory and Coarse Ceramic (Plastic) Bodies
Ber. deut. keram. Ges. 32 (3) 72-75 (1955)
Ceram. Abstr. 1955 (8) 144

E. M. Gibbs and J. Stout

Story of Electrical Porcelain: IV, Pugging and Pressing
Ceram. Ind. 66 (5) 84-86 (1956)
Ceram. Abstr. 1957 (1) 15

K. H. Kohne

Hot Preparation of Plastic Ceramic Bodies
Glas-Email-Keramo-Tech. 7 (2) 44-48 (1956)
Ceram. Abstr. 1956 (6) 149

F. Hubner

Application of Steam in the Processing of Heavy Clay Bodies of
the Brick and Stoneware Industry
Euro. Ceram. 7 (12) 298-301 (1957)
Ceram. Abstr. 1958 (6) 146

H. B. Ries
Possibilities in the Hot Plastic Preparation of Ceramic Bodies
Ber. deut. keram. Ges. 35 (12) 398-403 (1958)
Ceram. Abstr. 1959 (6) 165

Anon.

The Use of Steam in Clay Preparation
Austral. Nat. Clay 2 No. 4 14 (1961)
Brit. Ceram. Abstr. 1961 (10) 322A

F. J. Cach

I. Increasing the Efficiency of Machines for (Hot-plastic) Pressing with Rotating Tools

II. Elimination of the Batting Machine

Translated in Interceram. No. I 40-2 (1961)

Ceram. Abstr. 1961 (6) 147

Ceram. Abstr. 1962 (6) 147

L. Paolasso

Extrusion of Hot Clay Mixes: Application and Prospects

Ziegelindustrie 14 669 (1961)

Brit. Ceram. Abstr. 1962 (4) 93A

P. Gilson

Hot Plastic Body Preparation with Steam Injection in the Univap Machine

Keram. Z. 14 (1) 20-1 (1962)

Ceram. Abstr. 1962 (11) 267

A. Schuster

Hot Plastic Preparation and Shaping of Clayware

Keram. Z. 14 (3) 128-30 (1962)

Ceram. Abstr. 1962 (11) 267

H. Schuster

Hot Body Preparation and Hot Forming: II. Heating and Moistening by the Perio-Kontinu Process

Keram. Z. 14 (6) 348-9 (1962)

Ceram. Abstr. 1963 (3) 79

Brit. Ceram. Abstr. 1963 (3) 73A

W. W. Coates, Jr.
Hot Extrusion
Presented at 65th ACS
Am. Ceram. Soc. Bull. 42 (4) 249 (1963)

F3-COLD FORMING FROM SUSPENSIONS

F3b. SLIP CASTING, GRAVITY, AND GENERAL
(also see F3r)

W. E. Hauth, Jr.

Slip Casting of Aluminum Oxide

J. Am. Ceram. Soc. 32 (12) 394-8 (1949)

Ceram. Abstr. 1950 (1) 10

A. G. Allison and M. R. Nadler (Los Alamos Scientific Lab.)

Slip Casting Process for Magnesia Crucibles

Contract W-7405-Eng-36 (6/15/50)

Decl. with deletions 2/28/57

Nucl. Sci. Abstr. 1957 (12) 1528

G. H. Chalder (Gt. Brit. Springfields Works)

Preparation of Pure Oxide Refractories by Slip Casting

2/1/52

Nucl. Sci. Abstr. 1959 (9) 2179

H. Salmang

Macrostructure of a Fragment of Cast Ceramic

Bull. soc. franc. ceram. No. 16 2-8 (1952)

Ceram. Abstr. 1954 (3) 52

J. G. Woodward

Vibrating-plate Viscometer--an Aid in Slip-casting Control

Am. Ceram. Soc. Bull. 31 (10) 389-91 (1952)

Ceram. Abstr. 1953 (1) 14

G. W. Phelps, J. G. Woodward, and S. G. Maguire

Clay-slip Testing with the Vibrating-plate Viscometer

J. Am. Ceram. Soc. 36 (2) 60-5 (1953)

Ceram. Abstr. 1953 (3) 45

E. Deeg

Slip Casting, a Diffusion Problem

Ber. deut. keram. Ges. 30 129-38 (1953)

Ceram. Abstr. 1953 (11) 194

G. V. Kukolev and L. A. Shchukareva

Improving the Properties of Sanitary-ware Slips by Means of a

Combination Peptizer

Steklo i Keram. 10 (7) 15-6 (1953)

Ceram. Abstr. 1954 (8) 143

National Research Development Corp.
Manufacture of Refractory Articles
Brit. 688,624 (1/14/53)
Ceram. Abstr. 1954 (4) 71

Al. E. Williams
Manufacture of Refractory Articles from Pure Magnesia
U. S. 2,636,244 (4/28/53)
Ceram. Abstr. 1954 (8) 142

S. K. Chatterjee
Slip Casting of Refractory Oxides by Acid Treatment
Indian Ceramics 1 (4) 132-36 (1954)
Ceram. Abstr. 1955 (2) 32

S. K. Chatterjee and S. N. Chakravarty
Slip Casting of Refractory Oxides in Aqueous or Acid Media
Indian Ceramics 2 (1) 33-57 (1955)
Ceram. Abstr. 1956 (11) 241

P. Howard and A. L. Roberts
Study of Alumina Suspensions: III. Effect of Aging on Rheological
and Casting Behavior
Trans. Brit. Ceram. Soc. 53 (4) 271-91 (1954)
Ceram. Abstr. 1960 (2) 48

J. H. Partridge
Slip-casting Mullite and Zircon Tank Blocks
Silicates ind. 19 (4) 161-65 (1954)
Ceram. Abstr. 1955 (8) 145

P. Murray, R. W. Thackray, P. Rado, and D. George
Preparation and Properties of Slip-cast Calcium Fluoride Crucibles
Trans. Brit. Ceram. Soc. 54 (11) 693-97 (1955)
Ceram. Abstr. 1960 (3) 61

P. Murray, I. Denton, and D. Wilkinson (to USA-AEC)
Production of Thoria Ware
U. S. Patent 2,807,857 (10/1/57)
Nucl. Sci. Abstr. 1958 () 1727

P. D. S. St. Pierre
Slip Casting Thorium Dioxide
Am. Ceram. Soc. Bull. 34 (7) 231-32 (1955)
Ceram. Abstr. 1955 (9) 162

H. Rolke
Casting Ceramic Products with Heated Slip
Silikattech. 6 (9) 405 (1955)
Ceram. Abstr. 1956 (3) 79

Y. Shiraki and D. Katase
Studies on Slip Casting: VII. Slip Casting of Grog Body
J. Ceram. Assoc. Japan 63 (717) 728-37 (1955)
Ceram. Abstr. 1957 (7) 163

I. P. Gvozdev and G. L. Efremov
Manufacture of Glazed Tile by Casting
Steklo i Keram 13 (4) 29-32 (1956)
Ceram. Abstr. 1959 (10) 270

E. Kieffer
Casting Slips and Casting Molds
Ber. deut. keram. Ges. 33 (8) 258 (1956)
Ceram. Abstr. 1957 (2) 41

W. O. Williamson
Casting from Alkaline Slips
Clay Prods. J. Australia 23 (4) 9-11, 13; (6) 5, 7; (8) 18-19, 21
(1956)
Brit. Clayworker 65 (772) 132-35; (774) 190-92 (1956)
Ceram. Abstr. 1958 (9) 241

H. Salmang
Texture of Ceramic Materials
Ber. deut. keram. Ges. 30 (11) 247-51 (1953)
Ceram. Abstr. 1954 (7) 128

P. Murray, L. Denton, and D. Wilkinson
Slip Casting, Sintering, and Hot Pressing of Beryllia
Silicates ind. 19 (12) 412-17 (1954)
Ceram. Abstr. 1955 (9) 162

H. Salmang
Importance of Surface Tension in the Slip-casting Process
Ber. deut. keram. Ges. 33 (3) 65-72 (1956)
Ceram. Abstr. 1956 (9) 192

H. Salmang
Surface Tension of Ceramic Slips
Bull. soc. franc. ceram. No. 34 3-10 (1957)
Ceram. Abstr. 1957 (11) 272

H. Salmang, W. Deen, and A. Vroemen
Configuration of the Slip Cast Ceramic Surface as Affected by the
Surface Tension of the Clay
Ber. deut. keram. Ges. 34 (2) 33-38 (1957)
Ceram. Abstr. 1957 (10) 252

H. C. Friedemann (Penn-Texas Corp.)
Development of Cermets, 1950-1956
Project Slip Casting (6/7/57)
Contract AT(30-1)-1991
Nucl. Sci. Abstr. 1957 (9) 1107

H. H. Hausner, D. P. Ferriss, E. B. Wilson, and F. W. Heck (Penn-
Texas Corp.)
Preliminary Report on the Metal Powder Slip Casting Process. Part I
Contract AT(30-1)-1991 (9/9/57)
Nucl. Sci. Abstr. 1958 () 749

H. H. Hausner (Penn-Texas Corp.)
Slip Casting of Cermets
Contract AT(30-1)-1991 (3/31/58)
Nucl. Sci. Abstr. 1958 () 1057

H. Hausner
Preliminary Report on the Metal Powder Slip Casting Process Part II
Contract AT(30-1)-2131 (5/8/58)
Nucl. Sci. Abstr. 1958 () 1356

H. H. Hausner
The Forming of Complicated Shapes by Powder Metallurgy Slip Casting
Contract AT(30-1)-2131 (8/15/58)
Nucl. Sci. Abstr. 1958 () 1932

H. H. Hausner
Powder Metallurgy in Nuclear Engineering
Funtai oyobi Fumatsuyakin 6 (1) 1-18 (1959)
Ceram. Abstr. 1960 (7) 160

H. H. Hausner (Polytechnic Inst. of Brooklyn) and A. R. Poster
Slip Casting of Metal Powders and Metal-ceramic Combinations
Powder Metallurgy: Academic Press 461-506 (1961)
Nucl. Sci. Abstr. 1961 (9) 3084

S. D. Stoddard, D. T. Doll, J. M. Taub, D. E. Nuckolls, B. L.
Shroyer, J. J. Rosenthal, and T. I. Jones (Los Alamos Scientific Lab.)

Casting of Magnesium Oxide in Aqueous Slips
Contract W-7405-eng-36 (3/57)
Nucl. Sci. Abstr. 1958 (1) 155

A. G. Allison (USA-AEC)
Slip Casting Method
U. S. 2,902,380 (9/1/59)
Ceram. Abstr. 1960 (2) 37

W. G. Garrett and L. S. Williams
Progress in Aqueous Slip Casting of Magnesia
J. Am. Ceram. Soc. 43 (2) 114 (1960)
Ceram. Abstr. 1960 (3) 61

Anon.
How to Cast Aqueous MgO Slips
Ceram. Ind. 76 No. 2 54 (1961)
Brit. Ceram. Abstr. 1961 (10) 341

S. G. Whiteway, M. Coll-Palagos, and C. R. Massor.
Slip Casting Magnesia
Am. Ceram. Soc. Bull. 40 (7) 432-38 (1961)
Ceram. Abstr. 1961 (9) 214

L. S. Williams
Slip Casting of Calcium Oxide
Am. Ceram. Soc. Bull. 42 (6) 340-43 (1963)
Ceram. Abstr. 1963 (7) 188

Ceramic Research Station, New Brunswick
Technical Report No. 4: 6/15/55--10/15/56
Project NR-032-348
Contract N-our-404(03)
Nucl. Sci. Abstr. 1957 (10) 1236

E. J. Smoke
Fabrication of Dense Ceramic Radomes by Casting
Ceram. Age 69 (4) 32 (1957)
Ceram. Abstr. 1962 (2) 40

P. Murray, I. E. Denton, and D. Wilkinson (National Research
Development Corp.)
Production of Thoria Ware
U. S. 2,807,857 (10/1/57)
Ceram. Abstr. 1958 (1) 18

D. R. Stenquist and R. J. Anicetti (General Electric Co.)
Slip Casting of UO_2
Contract W-31-109-Eng-52
Nucl. Sci. Abstr. 1958 () 1932

L. E. Theiss (General Electric Co.)
Method for Casting Ceramic Shapes
U. S. 2,835,019 (5/20/58)
Ceram. Abstr. 1958 (9) 242

L. M. Schifferli, Jr.
Slip Casting
Metal Progr. 76 (4) 99-102 (1959)
Ceram. Abstr. 1960 (4) 88

L. M. Schifferli, Jr.
Slip Casting Offers Greater Design Flexibility for Cermets
Ceram. Age 73 (1) 28-30 (1959)
Ceram. Abstr. 1961 (9) 214

J. J. Finley, M. Korchynsky, and G. Reinhardt (Union Carbide
Metals Co.)
Columbium Alloy Clad Uranium Carbide Fuel Element
Monthly Letter Report for Period Ending /12/31/60
Contract AT-(40-1)-2559
Nucl. Sci. Abstr. 1961 (5) 1467

G. J. Comstock and E. H. Baron (Stevens Inst. of Tech.)
Slip Casting of Nuclear Fuel Elements
Terminal Report (11/1/60)
Contract AT(30-1)-2258
Nucl. Sci. Abstr. 1961 (10) 3425

P. Rado
Preparation and Properties of Calcium Fluoride Ware
Special Ceramics 237 (1960)

J. D. Fleming and J. W. Johnson (Georgia Inst. of Tech.)
Progress Report No. 2 Materials for High Temperature Nuclear Engineering Applications
8/15/59--8/15/60
Contract AT(40-1)-2483
Nucl. Sci. Abstr. 1961 (6) 1888

J. D. Fleming and J. W. Johnson (Georgia Inst. of Tech.)
Materials for High Temperature Nuclear Engineering Applications
Progress Report No. 3 8/15/60--8/15/61
Contract AT(40-1)-2483
Nucl. Sci. Abstr. 1962 (11) 3845

J. D. Fleming, J. W. Johnson, P. Boland, S. H. Bomar, and A. R. Colcord (Georgia Inst. of Tech.)
Materials for High Temperature Nuclear Engineering Applications
Summary Report No. 1 6/1/61--6/1/62
Contract AT(40-1)-2483
Nucl. Sci. Abstr. 1963 (2) 460

N. E. Poulos, S. R. Elkins, C. A. Murphy, and J. D. Walton (Georgia Inst. of Tech.)
High Temperature Ceramic Structures
Final Summary Report, 11/1/61--10/31/62
Contract NOrd-15701
Nucl. Sci. Abstr. 1963 (2) 633

N. E. Poulos, S. R. Elkins, and J. D. Walton (Georgia Inst. of Tech.)
High Temperature Ceramic Structures
Quarterly Report No. 22 11/1/61--1/31/62
Contract NOrd-150701
Nucl. Sci. Abstr. 1963 (2) 469

J. D. Fleming
Slip Casting of Fused Silica
Am. Ceram. Soc. Bull. 40 (12) 748-50 (1961)
Ceram. Abstr. 1962 (1) 17

J. D. Walton and N. E. Poulos
Fused silica Refractories
Trans. 8th Int. Ceram. Congr. 213 (1962)
Brit. Ceram. Abstr. 1962 (10) 298A

J. D. Walton and N. E. Poulos
Slip-cast Metal Fiber Reinforced Ceramics
Am. Ceram. Soc. Bull. 41 (11) 778-80 (1962)
Ceram. Abstr. 1963 (1) 4

J. Walton
Technical Notes on Slip Casting
Private Communication 7/63

W. Schulle (Bergakad)
Manufacturing Silica Ware by Slip-casting and Sintering
Silikat Tech. 13 282-4 (1962)
Chem. Abstr. 58 4279 (1962)

Anon.
New Kiln, Modern Ideas Help Georgia Sanitary Get Mass Market
Ceram. Age 77 (5) 44-47 (1961)
Ceram. Abstr. 1962 (3) 64

G. Dumoulin
Casting in Thin Sheets: Its Use in the Manufacture of Dielectrics
for Ceramic Condensers
Bull. Soc. Franc. Ceram. No. 52 21-26 (1961)
Brit. Ceram. Abstr. 1962 (4) 93A

G. V. Kukolev and A. G. Karaulov (Ukrainian State Inst. of High
Refractory Materials, Academy of Sciences)
Colloidal and Chemical Properties of Aqueous Suspensions of Stabil-
ized ZrO_2 and Their Relation to the Technological Properties
of These Suspensions
Dopovidi Akad. Nauk Ukr. R.S.R. No. 2 215-18 (1961)
Nucl. Sci. Abstr. 1961 (8) 2562

National Beryllia Corp.

Development of Fabrication Techniques for Beryllium Oxide Radome
Materials

Final Report (6/61)

Contract NOW-60-0057c

Nucl. Sci. Abstr. 1962 (6) 1958

J. L. Park (American Lava Corp)

Manufacture of Ceramics

U. S. Patent 2,966,719 (3/1/61)

Brit. Ceram. Abstr. 1961 (6) 233A

G. W. Phelps and J. S. Dennis (United Clay Mines Corp.)

Particle Size of Feldspar and Flint as a Factor in Slip Behavior

J. Am. Ceram. Soc. 44 149-56 (1961)

G. W. Phelps

Soluble Salts--Their Effect on Casting Properties in Ball Clays

Ceram. Ind. 76 (3) 68-69 (1961)

Ceram. Abstr. 1962 (3) 69

J. W. Szymaszek (Union Carbide Corp.)

Slip Casting

U. S. 2,979,401 (4/11/61)

Ceram. Abstr. 1961 (9) 220

Chem. Abstr. 1961 () 16381

G. P. Kalliga, V. A. Kolbasova, and D. N. Poluboyarinov

Mendeleev Inst. of Chemistry and Tech.)

Technology of Molding Zirconium Objects

Ogneupory No. 1 28-34 (1962)

Nucl. Sci. Abstr. 1962 (9) 3184

G. P. Kalliga, V. A. Kolbasova, and D. N. Poluboyarinov

Peculiarities of the Technology of Casting zircon Products

Ogneupory 27 (1) 28-34 (1962)

Ceram. Abstr. 1963 (1) 14

Anon.

How to Make Sanitaryware Casting Slip

Ceram. Ind. 78 (6) 70 (1962)

Brit. Ceram. Abstr. 1963 (3) 73A

E. R. Herrmann and I. B. Cutler

Kinetics of Slip Casting

Trans. Brit. Ceram. Soc. 61 (4) 207-11 (1962)

Ceram. Abstr. 1963 (5) 144

Philips Electrical Industries Ltd.

Moulding Press

Brit. Patent 899,257 (6/20/62)

Brit. Ceram. Abstr. 1963 (2) 43A

W. Schulle and J. Ulbricht (Bergakad)

New Method for Production of Silica Ware

Silikat Tech. 13 229-32 (1962)

Chem. Abstr. 1962 (12) 16163

S. D. Stoddard, D. E. Nuckolls, and R. E. Cowan (USA-AEC)

Casting Slips for Fabrication of Refractory Metal Ware

U. S. Patent 3,052,532 (9/4/62)

Nucl. Sci. Abstr. 1962 (11) 4045

E. R. Herrmann (Corning Glass Works) and I. B. Cutler (Dept.
of Ceramic Engineering, Univ. of Utah)

Kinetics of Slip Casting

Presented at 65th ACS

Am. Ceram. Soc. Bull. 42 (4) 275 (1963)

W. A. Daniel (Bendix Corp.)

Apparatus for Slip Casting Ceramic Materials

U. S. Patent 3,041,699 (7/3/62)

Ceram. Abstr. 1962 (10) 247

P. S. Mamykin and S. G. Zlatkin

Calcium Oxide Crucibles

Ogneupory 27 (8) 376-80 (1962)

translated in Ceramics 14 (167) 18-20 (1963)

Ceram. Abstr. 1963 (5) 132

P. S. Mamykin and S. G. Zlatkin
Calcium Oxide Crucibles
Ogneupory 27 (8) 376-80 (1962)
translated in Ceramics 14 (167) 18-20 (1963)
Ceram. Abstr. 1963 (5) 132

S. W. Ratcliffe
Some Principles of Dust Pressing and the Casting Process
Claycraft 35 260 (1962)
Brit. Ceram. Abstr. 1962 (11) 311A

P. Renault
Diagram for Establishing the Optimum Formula for Casting: I,II
Ind. Ceram. No. 542 245-53 (1962)
Silikat J. No. 3 114-22 (1962)
Ceram. Abstr. 1963 (4) 103

B. C. Weber
The Use of the Slip-casting Method in the Manufacture of Cermets
Keram. Z. 14 (8) 454 (1962)
Brit. Ceram. Abstr. 1963 (2) 41A

I. J. Holland (United Kingdom Atomic Energy Authority)
Improvements in or Relating to Suspensions of Beryllia
Brit. Patent 914,895 (1/9/63)
Nucl. Sci. Abstr. 1963 (3) 1136

P. D. S. St. Pierre (General Electric Research Laboratory)
Advances in Slip Casting
Presented at 64th ACS
Am. Ceram. Soc. Bull. 41 (4) 1962

F3e. SLIP CASTING ASSISTED BY SUPERIMPOSED MOTIONS

D. E. Parker

How Centrifugal Casting Produces Precision Shapes

Ceram. Ind. 69 (5) 97-98 (1957)

Ceram. Abstr. 1958 (6) 149

L. E. Theiss (General Electric Co.)

Method for Casting Ceramic Shapes

U. S. 2,835,019 (5/20/58)

Ceram. Abstr. 1958 (9) 242

R. Z. Elkinson and S. G. Tumanov

Use of Vibration in Casting Ceramic Ware

Steklo i Keram 16 (6) 7-12 (1959)

Ceram. Abstr. 1960 (2) 41

W. A. Daniel (Bendix Corp.)

Method of Centrifugally Slip-casting Ceramic Materials

U. S. 2,962,700 (12/6/60)

Ceram. Abstr. 1961 (4) 97

R. Y. Popilskii and I. P. Galkina

Tests on the Casting of High Grog Bodies

Ogneupory 25 (3) 137-42 (1960)

Ceram. Abstr. 1962 (5) 117

A. Jourdain

Moulding by Simultaneous Vibration and Pressure

Bull. Soc. Franc. Ceram. No. 53 55 (1961)

Brit. Ceram. Abstr. 1962 (7) 195A

Aeroprojects, Inc.

Applications of Ultrasonic Energy. Task 1. Ultrasonic Chemical

Processing. Task 2. Ultrasonic Metal and Ceramic Powder Proces-

sing. Task 3. Ultrasonic Instrumentation

Progress Report No. 22 6/1/60--7/31/60 (8/60)

Changed from Official Use Only 6/23/61

Nucl. Sci. Abstr. 1962 (1) 249

Aeroprojects, Inc.

Applications of Ultrasonic Energy. Task 2. Ultrasonic Metal and

Ceramic Powder Processing. Task 3. Ultrasonic Instrumentation

Progress Report No. 26 2/1/61--3/31/61 (4/61)

Contract AT(30-1)-1836

Nucl. Sci. Abstr. 1961 (10) 3319

C. Dana McKinney, Jr., W. B. Tarpley, and F. H. Gaskins (Aero-projects, Inc.)
Applications of Ultrasonic Energy. Ultrasonic Casting of Ceramic and Cermet Slips
Contract AT(30-1)-1836 (11/61)
Nucl. Sci. Abstr. 1962 (5) 1349

C. Dana McKinney, Jr. W. B. Tarpley, and F. H. Gaskins (Aero-projects, Inc.)
Ultrasonic Casting of Ceramic and Cermet Slips
Presented at 64th ACS
Am. Ceram. Soc. Bull. 41 (4) 1962

N. E. Poulos, S. R. Elkins, and J. D. Walton (Georgia Inst. of Tech.)
High Temperature Ceramic Structures
Quarterly Report No. 23 2/1/62--4/30/62
Contract NOrd-15701
Nucl. Sci. Abstr. 1962 (9) 3183

F3e. SLIP CASTING, VACUUM OR PRESSURE ASSISTED

B. N. Ol'shevskii

Vacuum Casting of Sanitary Earthenware Products

Steklo i Keram. 16 (7) 15-17 (1959)

Ceram. Abstr. 1960 (5) 115

D. E. Tomkins (Shenango China, Inc.)

Process for the Manufacture of Ceramic Objects

U. S. Patent 2,964,822 (12/20/60)

Ceram. Abstr. 1961 (4) 93

G. V. Kukolev and A. G. Karaulov

The Production of Refractories by Pressure Casting

Ogneupory 26 531 (1961)

Brit. Ceram. Abstr. 1963 (2) 41A

A. Adami and L. S. Williams (Commonwealth Scientific and Industrial Research Organization)

Vacuum-assisted Slip Casting

Am. Ceram. Soc. Bull. 42 (7) 391-393 (1963)

F3g. CASTING CEMENTS

E. C. Petrie

Techniques in the Installation of Castable Refractories

Ind. Heating 20 (10) 2049-56 (1953)

Ceram. Abstr. 1954 (2) 34

E. Stephan

Plastics and Castables

Tonind.-Ztg. u. Keram. Rundschau 78 (1/2) 11-13 (1954)

Ceram. Abstr. 1954 (7) 126

G. R. Eusner and D. H. Hubble

Castable Technology

Am. Ceram. Soc. Bull. 39 (8) 395-401 (1960)

Ceram. Abstr. 1960 (10) 232

H. M. Kraner, R. C. Padfield, and R. E. Hauser

Casting Large Sections of Basic Refractories

Am. Ceram. Soc. Bull. 39 (9) 456-59 (1960)

Ceram. Abstr. 1960 (11) 258

F3r. RHEOLOGY OF SUSPENSIONS (CASTING SLIPS)
(see also F3b)

I. Y. Piven

Effect of Temperature on Structural Viscosity of Ceramic Suspensions and Rate of Accumulation of the Body

Steklo i Keram. 11 (9) 8-9 (1954)

Ceram. Abstr. 1955 (6) 109

A. Dietzel and H. Mostetzky

Mechanism of the Dewatering of a Ceramic Slip by the Plaster Mold

I, Experimental Investigation of the Diffusion Theory of the Slip-casting Process; III, Penetration of the Slip Water into the Plaster Mold as a Wetting Problem; IV, X-ray Definition of the Texture of the Cast

Ber. deut. keram. Ges. 33 (1) 7-18; (3) 73-85; (4) 115-18 (1956)

Ceram. Abstr. 1956 (9) 193

D. S. Adcock and I. C. McDowall

Mechanism of Filter Pressing and Slip Casting

J. Am. Ceram. Soc. 40 (10) 355-62 (1957)

Ceram. Abstr. 1957 (11) 272

K. Dietz, R. Gauglitz, and H. E. Schwiete

Deflocculation of Silicate Clay Mineral Slips

Ziegelind. 10 (11) 353-59 (1957)

Ceram. Abstr. 1958 (4) 94

A. S. Michaels

Rheological Properties of Aqueous Clay Systems

Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc. 23-31 (1958)

C. A. Jouenne

The Setting of Argillaceous Slips

Bull. Soc. Franc. Ceram. No. 46 55-68 (1960)

Chem. Abstr. 54 17830

W. Ryan and W. E. Worral

Casting Experiments with Fireclays

Trans. Brit. Ceram. Soc. 60 (3) 60 (1961)

P. Renault

Diagram for the Establishment of an Optimum Casting Formula

Industr. Ceram. 542 245 (1962)

Brit. Ceram. Abstr. 1963 (3) 73A

H. A. Kearsey and A. G. Cheney (At. Energy Res. Establ. Engl.)
Effect of Temperature on the Rheology of Thoria Slurries
Trans. Inst. Chem. Engrs.
Chem. Abstr. 58 11396

E. G. Richardson (King's College)
The Rheology of Clay Slips
Geol. Foren. i Stockholm Forh. 81 609-19 (1959)
Chem. Abstr. 55 20362

F4c. TRANSFER MOLDING WITH THERMOSETTING POLYMERS

H. D. MacMaster, H. E. Bauer, and S. A. Guthrie (General Grinding
Wheel Corp.)

Method of Making Abrasive Articles

U. S. 2,943,357 (7/5/60)

Ceram. Abstr. 1960 (10) 225

Anon.

Transfer and Compression Molding of Glass-bonded Mica

Ceram. Age. 77 (3) 28-31 (1961)

Ceram. Abstr. 1962 (2) 41

F4d. INJECTION MOLDING

K. Schwartzwalder (General Motors Corp.)
Refractory Body and Method of Making Same
U. S. Patent 2,122,960 (7/5/38)

K. Schwartzwalder
Injection Molding of Ceramic Materials
Am. Ceram. Soc. Bull. 28 (11) 459-61 (1949)

Bendix Aviation Corp.
Molding Ceramics
Australian 146,790 (2/18/49)
Ceram. Abstr. 1953 (4) 68

J. S. Kilpatrick (Mycalex Co., Ltd.)
Manufacture of Micaceous Insulating Materials
U. S. 2,669,764 (2/23/54)
Ceram. Abstr. 1954 (8) 144

E. J. Rogers and E. L. Mooney (Bendix Aviation Corp.)
Molding of Ceramics
U. S. 2,694,245 (11/16/54)
Ceram. Abstr. 1955 (3) 54

M. Skunda (General Motors Corp.)
Method for Shaping Ceramic Articles
U. S. 2,726,433 (/12/13/55)
Ceram. Abstr. 1956 (2) 59

R. Bahn and H. Blechschmidt
Shaping of Nonplastic Ceramic Materials by Injection Molding
Silikattech. 10 (9) 44204⁵ (1959)
Ceram. Abstr. 1960 (3) 67

A. Moteki
Studies on the Injection Molding of Ceramics: I, Factors affecting
the Workability of Resins Used for Injection Molding, II, Var-
ious Factors in the Heat-treatment of the Injection Molded
Products
Yogyo Kyokai Shi 67 (768) 387-99 (1959); 68 (769) 11-21 (1960)
Ceram. Abstr. 1960 (11) 268

A. Moteki
Studies on the Injection Molding of Ceramics: III, Properties of
High-alumina Porcelain Produced by Injection Molding
Yogyo Kyokai Shi 68 (770) 23-32 (1960)
Ceram. Abstr. 1961 (2) 38

R. L. Randolph
Injection Molded Ceramics
Materials in Design Engineering 54 (2) 10-12 (1961)
Ceram. Abstr. 1962 (6) 147

Anon.
Processing Breakthrough--Injection Molding High Alumina Components
Ceram. Age 78 (2) 30-32 (1962)
Ceram. Abstr. 1962 (10) 247

Anon.
Injection Molding Process for Intricate Technical Ceramic Shapes
Ceram. News 11 (6) 20 (1962)
Ceram. Abstr. 1962 (11) 267

M. A. Strivens
Injection Molding of Ceramic Insulating Materials
Am. Ceram. Soc. Bull. 42 (1) 13-19 (1963)
Ceram. Abstr. 1961 (2) 47

F4e. EXTRUSION

C. C. Treischel and E. W. Ehrich
Study of Several Groups of Organic Binders Under Low Pressure
Extrusion
J. Am. Ceram. Soc. 29 (5) 129-32 (1946)

R. Lecuir
Method of Manufacturing Plastic Ceramic Masses from Lamellar
Organic Substances
U. S. 2,603,837 (7/22/52)
Ceram. Abstr. 1953 (3) 44

F4f. ROLLING

Compagnie Generale de Telegraphie sans Fil
Manufacture of Ceramic articles
Fr. 1,050,129 (8/26/53)
Ceram. Abstr. 1954 (11) 205

J. J. Fargo (Gladding, McBean and Co.)
Summary Report on Development of Flat Plate Ceramic Fuel Elements
Technical Progress Report 26 (8/28/61)
Contract AT(04-3)-249
Nucl. Sci. Abstr. 1962 (8) 2831

R. C. Ragan (Gladding, McBean and Co.)
Method for Continuous Manufacture of Ceramic Sheets
U. S. Patent 3,007,222 (11/7/61)
Ceram. Abstr. 1962 (4) 93

Fig. CASTING (HOT SPRAY)

O. Balcar

Hot Spray Casting of Ceramic Products

Sklar Keram. 10 (1) 15-16 (1960)

Ceram. Abstr. 1963 (4) 104

I. N. Zubatova

Once-firing of Porcelain Ware Made by Hot Casting under Pressure

Steklo i Keram. 19 (6) 26-27 (1962)

Glass Ceram (USSR) (English Transl.) 318-20

Ceram. Abstr. 1963 (7) 190

F4h. SPINNING

K. H. McGhee and N. J. Johnson (Union Carbide Corp.)
Spin Molding of Carbonaceous Mix
U. S. 2,892,218 (6/30/59)
Ceram. Abstr. 1959 (9) 240

F4j. VACUUM-ASSISTED FORMING

R. F. Tatnall, ed.

Vacuum Casting and Car Bell Kilns Mark Progress for Sterling Grinding Wheels

Ceramic Age (6) 38 (1963)

F5-CHEMICALLY-ASSISTED FORMING

F5b. FORMING BY CEMENTITIOUS BONDING
(see also F2j, k; F3g)

J. F. Wygant

Cementitious Bonding in Ceramic Fabrication

Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc. 171 (1958)

V. V. Vasil'eva

Viscoplastic Properties of Masonry Mortars

Kolloid. Zhur. 21 151-6 (1959)

Chem. Abstr. 53 20747

F5g. REACTION SINTERING

S. Tacvorian (Office National d'Etudes et de Recherches Aeronautiques)

Metalloceramic Compositions and Process of Producing

U. S. 2,767,463 (19/23/56)

Ceram. Abstr. 1956 (2) 40

J. D. Walton and C. R. Mason (Georgia Institute of Tech.)

Investigation of High Temperature Resistant Materials

Quarterly Report No. 11 2/1/58--4/30/58

Project No. A-212

Contract NOrd-15701

Nucl. Sci. Abstr. 1958 () 1146

J. D. Fleming, J. D. Walton, and C. R. Mason (Georgia Inst. of Tech.)

Investigation of High Temperature Resistant Materials

Quarterly Report No. 10 11/1/57--1/31/58

Project No. A-212

Contract NOrd-15701

Nucl. Sci. Abstr. 1958 (6) 825

C. R. Mason, J. D. Walton, M. D. Bowen, and W. T. Teague (Georgia Inst. of Tech.)

Investigation of High Temperature Resistant Materials

Quarterly Report No. 14 2/1/59--4/30/59

Project No. A-212

Contract NOrd-15071

Nucl. Sci. Abstr. 1959 (8) 1951

J. D. Fleming and J. W. Johnson (Georgia Inst. of Tech.)

Materials for High Temperature Nuclear Engineering Applications

Progress Report No. 2, Part 2 8/15/59--8/15/60

Contract AT-(40-1)-2483

Nucl. Sci. Abstr. 1962 (12) 4181

J. D. Fleming and J. W. Johnson (Georgia Inst. of Tech.)

Materials for High Temperature Nuclear Engineering Applications

Progress Report No. 3 8/15/60--8/15/61

Contract AT(40-1)-2483

Nucl. Sci. Abstr. 1962 (11) 3845

J. D. Fleming, J. W. Johnson, P. Boland, S. H. Bomar, and A. R. Colcord (Georgia Inst. of Tech.)
Materials for High Temperature Nuclear Engineering Applications
Quarterly Report No. 1 8/15/61--4/1/62
Contract AT(40-1)-2483
Nucl. Sci. Abstr. 1962 (11) 3984

J. D. Fleming, J. W. Johnson, P. Boland, S. H. Bomar, and A. R. Colcord (Georgia Inst. of Tech.)
Materials for High Temperature Nuclear Engineering Applications
Summary Report No. 1 6/1/61--6/1/62
Contract AT(40-1)-2483
Nucl. Sci. Abstr. 1963 (2) 460

A. Accary and J. Dubuisson (Commissariat a l'Energie Atomique)
Methods for Making Uranium Carbide Articles
Canadian Patent 653,803 (12/11/62)
Nucl. Sci. Abstr. 1963 (5) 2165

P. Popper
The Preparation of Dense Self-Bonded Silicon Carbide
Special Ceramics: Heywood 209 (1960)

T. A. Ingles and P. Popper
The Preparation and Properties of Boron Nitride
Special Ceramics: Heywood 144 (1960)

P. Popper and S. N. Ruddlesden
Preparation, Properties, and Structure of Silicon Nitride
Trans. Brit. Ceram. Soc. 60 (9) 603-26 (1961)
Ceram. Abstr. 1962 (3) 62

N. L. Parr, G. F. Martin, and E. R. W. May
Preparation, Microstructure, and Mechanical Properties of Silicon Nitride
Special Ceramics: Heywood 102 (1960)

Commissariat a l'Energie Atomique
Method for Manufacturing Molded Objects Consisting of Uranium Silicides
French Patent 1.235,561 (6/30/60)
Nucl. Sci. Abstr. 1961 (12) 4194

A. Accary and R. Caillat (Centre d'Etudes Nucleaires)
Industrial Methods of Fabrication of Dense Uranium Monocarbide
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG. 231-48 (1962)
Nucl. Sci. Abstr. 1963 (1) 257

D. J. Brown and J. J. Stobo (C. A. Parsons and Co., Ltd.)
Preparation and Properties of Uranium Monocarbide
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG. 279-93 (1962)
Nucl. Sci. Abstr. 1963 (1) 258

M. C. Regan and H. J. Hedger (Atomic Energy Establishment)
The Properties of Uranium Monocarbide Fabricated by Direct Reaction of the Elemental Powders
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG. 420-32 (1962)
Nucl. Sci. Abstr. 1963 (1) 259

P. Stephas and E. W. Hoyt (General Electric Co.)
Reactive Hot Pressing of ZrC-UC Solid Solution
Am. Ceram. Soc. Bull. 40 (5) 320-3 (1961)
Nucl. Sci. Abstr. 1961 (7) 2388

Commissariat a l'Energie Atomique
Improvements in Methods for Making Uranium Monocarbide Articles
Brit. Patent 911,957 (12/5/62)
Nucl. Sci. Abstr. 1963 (3) 1140

A. Accary and R. Caillat
Study of Mechanism of Reaction Hot Pressing
J. Am. Ceram. Soc. 45 (7) 347-51 (1962)
Ceram. Abstr. 1962 (8) 191
Chem. Abstr. 57 12115

W. V. Goeddel and M. T. Simnad (USA-AEC)
Method of Making Metal Bonded Carbon Bodies
U. S. 3,001,238 (9/26/61)
Ceram. Abstr. 1962 (3) 63

R. Colton
Two Boron Silicides
Materials in Design Engineering 53 (6) 9-10 (1961)
Ceram. Abstr. 1962 (1) 10

R. R. Van Der Beck and K. M. Taylor (Carborundum Co.)
Refractory Boride and Silicide Shapes and Method of Making
U. S. Patent 3,041,142 (6/26/62)
Ceram. Abstr. 1962 (11) 261

National Research Development Corporation
Silicon Nitride Body Production
Brit. Patent 895,769 (9/5/62)
Brit. Ceram. Abstr. 1963 (1) 22A

W. V. Goeddel and M. T. Simnad (USA-AEC)
Method of Making Fuel Bodies
U. S. Patent 3,087,877 (4/30/63)
Nucl. Sci. Abstr. 1963 (6) 2445

G. L. Hanna and D. N. Turner (Australian Atomic Energy Commission
Research Establishment)
Preparation of the Beryllides of Uranium and Thorium
Nucl. Sci. Abstr. 1963 (6) 2437

J. R. Johnson (Minnesota Mining and Mfg. Co.)
Thermally Resistant Articles and Method for Their Fabrication
U. S. Patent 3,079,316 (2/26/63)
Nucl. Sci. Abstr. 1963 (5) 2166

F7-FORMING BY COMBINATIONS OF ENERGY FORMS

G. Helm

Use of Shaking Procedures in Ceramics

Sprechsaal 88 (10) 221-3; (11) 243-5; (12) 266-9 (1955)

Ceram. Abstr. 1956 (6) 120

A. G. Bodine, Jr.

Sonic Method for Powdered Metal Molding

U. S. 2,815,535 (12/10/57)

Ceram. Abstr. 1958 (3) 78

V. I. Likhtman, N. S. Gorbunov, I. G. Shatalova, and P. A. Rebinder
(Inst. of Physical Chemistry, Academy of Sciences, USSR)

On the Vibrational Increase of Density in Powder Metallurgy

Doklady Akad. Nauk SSSR 134 10/11 1150-2 (1960)

Nucl. Sci. Abstr. 1961 (4) 993

Aeroprojects, Inc.

Applications of Ultrasonic Energy. Task 1. Ultrasonic Chemical

Processing. Task 2. Ultrasonic Metal and Ceramic Powder Proces-

sing. Task 3. Ultrasonic Instrumentation

Progress Report No. 22 6/1/60--7/31/60

Changed from Official Use Only 6/23/61

Contract AT(30-1)-1836

Nucl. Sci. Abstr. 1962 (1) 249

E. Barbara

Method of Applying High Pressure to a Body

U. S. Patent 2,990,583 (7/4/61)

Ceram. Abstr. 1962 (1) 17

Aeroprojects, Inc.

Applications of Ultrasonic Energy. Task 2. Ultrasonic Metal and

Ceramic Powder Processing. Task 3. Ultrasonic Instrumentation

Progress Report No. 28 6/1/61--7/31/61

Nucl. Sci. Abstr. 1962 (3) 721

J. J. Hawth and R. J. Anicetti (USA-AEC)

Method of Preparing a Fuel Element for A Nuclear Reactor

U. S. Patent 3,067,117 (12/4/62)

Nucl. Sci. Abstr. 1963 (3) 1141

F8-HIGH ENERGY RATE FORMING
(see also F12m)

D. Beck (United Kingdom Atomic Energy Authority)
Explosive Forming. References to Unclassified Reports and Articles
Published from 1/57 to 9/60 with a Supplement up to 12/60
5/61

Nucl. Sci. Abstr. 1961 (8) 2733

Office of Technical Services
Explosive Metal Forming. OTS Selective Bibliography
SB-441 (Rev.) (12/61)
Nucl. Sci. Abstr. 1962 (5) 1351

K. M. Gibbs, comp. (Armed Services Technical Information Agency)
Explosive Forming. An ASTIA Report Bibliography
2/62
Nucl. Sci. Abstr. 1963 (3) 1138

H. P. Tardif (Canadian Armament Research and Development Establishment)
The Explosive Forming of Conical Shapes by Metal Gathering
2/58
Nucl. Sci. Abstr. 1962 (11) 3844

A. Cross (Storchheim Research & Develop. Corp.)
Explosive Compacting of Powder Products
Iron Age 184 No. 26 48-50 (1959)
Chem. Abstr. 54 3113 (1960)

S. W. Porembka and C. C. Simons (Battelle Memorial Inst.)
Compacting Metal Powders with Explosives
Creative Manufacturing Seminars, 1960-61 Paper AP60-102
Nucl. Sci. Abstr. 1961 (5) 1481

Chromalloy Corp.
Explosive Forming of Refractory Metals
Bi-Monthly Report No. 6 6/1/60--7/31/60 (12/60)
Nucl. Sci. Abstr. 1961 (7) 2387

Chromalloy Corp.
Explosive Forming of Refractory Metals
Final Technical Report 6/30/59--9/30/60 (12/31/60)
Contract NOas 59-6265
Nucl. Sci. Abstr. 1961 (7) 2387

G. A. Refmann (Westinghouse Electric Corp.)
High Energy Rate Extrusion
Interim Technical Progress Report No. 1 9/23/60--1/61 (2/61)
Contract AF33(600)-41948
Nucl. Sci. Abstr. 1961 (5) 1707

Y. Kimura
Properties of Metallic Oxides formed by Explosives
Funtai Oyobi Furumatsuyakin 8 (2) 58-62 (1961)
Ceram. Abstr. 1963 (6) 174

F. C. Polhemus (Union Carbide Nuclear Co.)
Explosive Forming of Metals
Contract W-7405-eng-26 (3/24/61)
Nucl. Sci. Abstr. 1961 (6) 2071

Chromalloy Corp. Propellex Chemical Div.
A Study of Explosive Forming Selected Refractory Metals
Progress Report No. 1: through 6/30/61 (7/15/61)
Contract NOW 61-0832-C
Nucl. Sci. Abstr. 1961 (10) 3425

Commonwealth Engng. Co. of Ohio
Brit. Patent 872,024 (5/7/61)
Brit. Ceram. Abstr. 1962 (2) 36A

D. W. Brite (General Electric Co.)
High Energy Impact Forming of Ceramic Fuels
Contract AT(45-1)-1350 (10/4/62)
Nucl. Sci. Abstr. 1963 (1) 265

Q. C. Carloni and L. Lewis (Bridgeport Brass Co.)
Dynapak Extrusion of I & E Fuel Elements. Phase II Technical Ac-
tivity Alpha Phase
Contract AT(30-1)-1405 (9/14/62)
Nucl. Sci. Abstr. 1963 (5) 2163

Anon.
Special Fabrication Techniques
Reactor Materials 2 No. 4 79-90
Nucl. Sci. Abstr. 1963 (4) 1447

Anon.

Special Fabrication Techniques

Reactor Materials 6 No. 1 96-110

Nucl. Sci. Abstr. 1963 (5) 2273

R. A. Cooley (Cromalloy Corp.)

The Explosive Forming of Metals

Chem. Rundschau (Solothurn) 13 295-6 (1960)

Chem. Abstr. 54 20744

F10a. GENERAL

S. D. Stookey and F. W. Schuler
 Ultraviolet and X-ray Irradiation Effects in Photosensitive Glasses
 Proc. IV Intl. Cong. on Glass 390-95 (1956)

S. D. Stookey
 Nucleation
 Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc. 189 (1958)

S. D. Stookey
 Catalyzed Crystallization of Glass in Theory and Practice
 Glastechn. Ber. 32K, V Inter. Cong. on Glass (1959)

S. D. Stookey
 Glass Ceramics
 Chemical and Engineering News 39 116 (1961)

S. D. Stookey
 Ceramics Made by Nucleation of Glass-comparison of Microstructure and Properties with Sintered Ceramics
 Am. Ceram. Soc. Symposium on Nucleation and Crystallization in Glasses and Melts 1 (1962)

S. D. Stookey
 Modern Glass
 Science and Technology 7/62

S. N. Lungu and D. Popescuhas
 Fine Ceramic Masses Obtained by the Crystallization of Glass (porcelain from glass)
 Ind. usoara (Bucharest) 5 63-5 (1958)
 Chem. Abstr. 53 668

R. C. Anderson and A. L. Friedberg
 Crystallization of Lead Metaniobate from a Glass
 Am. Ceram. Soc. Symposium on Nucleation and Crystallization in Glasses and Melts 29 (1962)

W. B. Hillig
 A Theoretical and Experimental Investigation of Nucleation Leading to Uniform Crystallization of Glass
 Am. Ceram. Soc. Symposium on Nucleation and Crystallization in Glasses and Melts 77 (1962)

R. D. Maurer

Crystallization of a Titania-Nucleated Glass

Am. Ceram. Soc. Symposium on Nucleation and Crystallization in
Glasses and Melts 5 (1962)

W. Vogel and K. Gerth

Catalyzed Crystallization in Glass

Am. Ceram. Soc. Symposium on Nucleation and Crystallization in
Glasses and Melts 11 (1962)

F10g. FORMING GLASS INTO FIBERS
 (see also F26)

C. J. Stalego (Owens-Corning Fiberglas Corp.)
Method and Apparatus for Forming Glass Fibers
U. S. 2,687,551 (8/31/54)
Ceram. Abstr. 1955 (1) 8

M. M. Bourgeaux (Soc. Anon. des Manufactures des Glaces et Pro-
 duits Chimiques de St. Gobain)
Method of and Apparatus for Producing Glass Fibers
U. S. 2,708,813 (5/24/55)
Ceram. Abstr. 1955 (10) 179

Office of Technical Services
Fiber Glass and Glass Laminates. OTS Selective Bibliography
Supplement to CTR-292 (9/61)
Nucl. Sci. Abstr. 1962 (2) 430

P. A. Lockwood (Owens-Corning Fiberglas Corp.)
Investigations of Radioactive Fuel-bearing Glasses
5/1/60--3/31/61 (7/31/61)
Contract AT(30-1)-2489
Nucl. Sci. Abstr. 1963 (4) 1444

P. A. Lockwood (Owens-Corning Fiberglas Corp.)
Investigations of Nuclear Fuel-bearing Glasses
Nucl. Sci. Abstr. 1962 (10) 3457

F10h. DROPPING, BENDING OF GLASS

A. F. Donovan, H. T. Jacquot, R. E. Richardson (Pittsburgh Plate
Glass Co.)

Glass Bending Mold

U. S. Patent 2,961,801 (11/29/60)

Ceram. Abstr. 1961 (4) 86

F. J. Carson (Libby Owens Ford)

Glass Bending Mold

U. S. Patent 2,963,822 (12/13/60)

Ceram. Abstr. 1961 (4) 86

Fl1-FORMING BY MELTING AND CASTING OF NON-GLASSY
CERAMICS IN BULK (FUSION CASTING)

R. Reinhart

Fused Mineral Bodies

Sprechsaal 83 (18) 357-61 (1950)

Ceram. Abstr. 1954 (2) 34

T. Hand and H. W. Baque

Electrically Melted and Cast Magnesite-chrome Refractory

Am. Ceram. Soc. Bull. 33 (6) 176-9 (1954)

Ceram. Abstr. 1954 (8) 142

F. R. Duerr (Corhart Refractories Co.)

Mold for Fusion-casting of Refractory Oxide Compositions

U. S. 2,705,851 (4/12/55)

Ceram. Abstr. 1955 (7) 120

K. H. Sandmeyer (Carborundum Co.)

Fused Cast Refractory Articles and Method of Making Them

U. S. 2,911,313 (11/3/59)

Ceram. Abstr. 1960 (5) 114

A. A. Litvakovskii

Fused Cast Refractories: Moscow, 1959; English transl. 1961

OTS 60-51137

Ceram. Abstr. 1963 (4) 123

P. Bortaud

Electrocast Refractories

Silicates Industr 27 171 (1962)

Brit. Ceram. Abstr. 1962 (11) 323A

W. M. Phillips, W. Chubb, and E. L. Foster (Battelle Memorial
Inst.)

Direct Casting of Uranium Monocarbide Reactor Fuel Elements

J. Less-Common Metals 2 (12) 451-7 (1960)

Nucl. Sci. Abstr. 1961 (5) 1480

D. J. Brown and J. J. Stobo (C. A. Parsons and Co., Ltd.)

Preparation and Properties of Uranium Monocarbide

Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961

Reutte/Tyrol, Metallwerk Plansee AG. 279-93 (1962)

Nucl. Sci. Abstr. 1963 (1) 258

- J. Crane, F. B. Litton, and H. S. Kalish (United Nuclear Corp.)
Arc Skull Melting and Casting of Uranium Carbide
Am. Soc. Metals, Trans. Quart. 56 (3) 176-93 (1963)
Nucl. Sci. Abstr. 1963 (6) 2439
- C. A. Smith and F. Rough (Atomics International Div., North American Aviation, Inc.)
Properties of Uranium Monocarbide
Contract AT-11-1-GEN-8 (6/1/59)
Nucl. Sci. Abstr. 1959 (9) 2060
- A. Accary and R. Caillat (Centre d'Etudes Nucleaires)
Industrial Methods of Fabrication of Dense Uranium Monocarbide
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG. 231-48 (1962)
Nucl. Sci. Abstr. 1963 (1) 257
- G. L. Hanna and D. N. Turner (Australia Atomic Energy Commission Research Establishment)
Preparation of the Beryllides of Uranium and Thorium
1/63
Nucl. Sci. Abstr. 1963 (6) 2437
- A. Stone
Quality Control for Cast Refractories
Ceram. Age 70 (4) 20-1, 36 (1957)
Ceram. Abstr. 1962 (1) 10
- K. H. Sandmeyer
Quality in Fusion-cast Refractories for the Glass Industry
J. Can. Ceram. Soc. 28 38-40 (1959)
Ceram. Abstr. 1960 (7) 160
- T. E. Field and H. T. Smyth (Corhart Refractories Co.)
Producing Fusion-cast Refractories
U. S. 2,603,914 (7/22/52)
Ceram. Abstr. 1953 (2) 27

D. H. Turner (Atomics International, Div. of North American
Aviation, Inc.)
Fabrication of Uranium Monocarbide Fuel Elements for Hallam Nu-
clear Power Facility Exponential Experiments
Contract AT(11-1)-Gen-8 (2/15/62)
Nucl. Sci. Abstr. 1962 (6) 1958

H. S. Kalish, F. B. Liton, and J. Crane (Olin Mathieson Chem-
ical Corp.)
Skull Melting and Casting of Uranium Monocarbide
Contract AT(30-1)-2374 (2/28/61)
Nucl. Sci. Abstr. 1962 (9) 3183

Flif. GROWING SINGLE CRYSTALS FROM MELTS

L. A. Dauncey (General Electric Co., Ltd.)
Apparatus for Manufacturing Synthetic Jewels
U. S. 2,692,456 (10/26/54)
Ceram. Abstr. 1955 (3) 54

Anon.
Synthetic Sapphires Competitive with Sintered Aluminas, Quartz
Materials in Design Eng. 46 (3) 161 (57)
Ceram. Abstr. 1958 (4) 86

D. A. Jenny and R. V. Jensen (Radio Corp. of America)
Method for Single Crystal Growth
U. S. 2,902,350 (9/1/59)
Ceram. Abstr. 1960 (1) 21

J. Eckstein and Z. Wachtl
Growing Single Crystals from a Molten Mass with a Linear Isotherm
Czech. 94,996 (4/15/60)
Chem. Abstr. 55 (3) 2217 (1961)
Ceram. Abstr. 1963 (2) 60

F. G. Froemel, E. C. Worden, et al.
Synthetic Mica Crystal Growth Program
PB Rept. 155154
U. S. Govt. Research Repts. 35 (6) 798 (1961)
Ceram. Abstr. 1963 (1) 19

R. T. Dolloff (Union Carbide Corp.)
Method and Apparatus for Growing Crystals
U. S. 3,053,639 (9/11/62)
Ceram. Abstr. 1963 (1) 16

E. A. Giess
Growth of Single-crystal $MgGa_2O_4$ Spinel from Molten $PbOPbF_2$
Solutions
J. Appl. Phys. 33 (6) 2143 (1962)

R. A. Laudise
Growing Oxide Crystals
Bell Lab. Record 40 (7) 244-50 (1962)
Ceram. Abstr. 1963 (3) 86

R. C. Linares
Growth of Refractory Oxide Single Crystals
J. Appl. Phys. 33 (5) 1747-49 (1962)
Ceram. Abstr. 1963 (5) 144

J. W. Nielsen (Bell Telephone Lab.)
Single Crystal Garnets
U. S. 3,050,407 (8/21/62)
Ceram. Abstr. 1963 (1) 21

W. Shockley (Clevite Corp.)
Method of Growing Silicon Carbide Crystals
U. S. 3,053,635 (9/11/62)
Ceram. Abstr. 1963 (1) 16

S. B. Austerman
Growth of Beryllia Single Crystals
J. Am. Ceram. Soc. 46 (1) 6-10 (1963)
Ceram. Abstr. 1963 (3) 87

F12-FORMING BY HOT DEPOSITION

Oak Ridge National Lab.

Ceramic Information Meeting Held at Oak Ridge National Lab. on
10/1,2,3/56 (4/57)

Nucl. Sci. Abstr. 1957 (7) 723

N. N. Ault and L. H. Milligan

Alumina Radomes by Flame-spray process

Am. Ceram. Soc. Bull. 38 (11) 661-64 (1959)

Ceram. Abstr. 1960 (1) 7

Norton Co.

Ceramic Shells

Brit. Patent 847,449 (7/9/60)

Brit. Ceram. Abstr. 1961 (3) 111A

C. R. Mason, J. D. Walton, M. D. Bowen, and W. T. Teague

Investigation of High Temperature Resistant Materials

Quarterly Report No. 14 2/1/59--4/30/59

Project No. A-212

Contract NOrd-15701

Nucl. Sci. Abstr. 1959 (8) 1951

H. W. Newkirk (General Electric Co.)

Continuous Arc Fusion of Uranium Dioxide Powder

2/17/59

Nucl. Sci. Abstr. 1961 (4) 1199

C. R. Mason, J. D. Walton, C. A. Murphy, and A. T. Sales (Georgia Inst. of Tech.)

Investigation of High Temperature Resistant Materials

Quarterly Report No. 18 5/1/60--7/31/60

Nucl. Sci. Abstr. 1961 (10) 3256

N. E. Poulos, S. R. Elkins, and J. D. Walton (Georgia Inst. of Tech.)

Investigation of High Temperature Resistant Materials

Quarterly Report No. 20 2/1/61--4/30/61

Contract NOrd-15701

Nucl. Sci. Abstr. 1961 (8) 2566

D. R. Mash, N. E. Weare, and D. L. Walker (Advanced Tech. Labs.)

Process Variables in Plasma-jet Spraying

J. Metals 13 473-8 (7) 1961

Nucl. Sci. Abstr. 1961 (9) 3080

R. Truesdale, B. B. Lympny, E. M. Grala, R. M. Paine, and W. W. Beaver (Brush Beryllium Co.)
Investigation of the Effects of Processing Variables and Fabrication Techniques upon the Properties of Intermetallic Compounds
Progress Report No. 3 10/1/60--12/31/60 (1/15/61)
Technical Report No. 197-229
Contract AF33(616)-7108
Nucl. Sci. Abstr. 1961 (6) 1898

B. E. Kramer and M. A. Levinstein (General Electric Co.)
The Effect of Arc Plasma Deposition on the Stability of Non-metallic Materials
Bi-monthly Report No. 6 1-2/61
Contract NOas 60-6076-C
Nucl. Sci. Abstr. 1961 (7) 2240

B. E. Kramer, M. A. Levinstein, and J. W. Grenier (General Electric Co.)
The Effect of Arc Plasma Deposition on the Stability of Non-metallic Materials
Final Report Covering 4/60--5/61
Contract No NOas-60-6076-C
Nucl. Sci. Abstr. 1961 (9) 3078

D. G. Moore, A. G. Eubanks, H. R. Thornton, W. D. Hayes, Jr., and A. W. Crigler (National Bureau of Standards)
Studies of the Particle Impact Process for Applying Ceramic and Cermet Coatings
Final Summary Report (4/61)
Contract AF33(616)-58-10
Nucl. Sci. Abstr. 1962 (7) 2164

H. J. Hedger and A. R. Hall (Atomic Energy Research Establishment)
Preliminary Observations on the Use of the Induction-Coupled Plasma Torch for the Preparation of Spherical Powder
Powder Met. No. 8 65-72 (1961)
Nucl. Sci. Abstr. 1962 (3) 723

- T. S. Laszlo (Avco Corp.)
 Mechanical Adherence of Flame-sprayed coatings
 Am. Ceram. Soc. Bull. 40 (12) 751-5 (1961)
 Nucl. Sci. Abstr. 1962 (2) 556
- A. R. Stetson and C. A. Hauck (Solar Aircraft Co.)
 Plasma Spraying Techniques for Toxic and Oxidizable Materials
 J. Metals 13 (7) 479-82 (1961)
 Nucl. Sci. Abstr. 1961 (9) 3080
- H. K. Orbach
 Ceramic Uses of Plasma Jet
 Ceram. Ind. 72 (5) 72-5 (1962)
 Ceram. Abstr. 1963 (3) 81
- W. D. Klopp (Battelle Memorial Inst. Defense Metals Information Center)
 Summary of the Fifth Meeting of the Refractory Composites Working Group
 Contract AF33(616)-7747 (3/12/62)
 Nucl. Sci. Abstr. 1962 (7) 2345
- W. A. Gibeaut and D. J. Maykuth (Battelle Memorial Inst. Defense Metals Information Center)
 Summary of the Sixth Meeting of the Refractory Composites Working Group
 9/24/62
 Nucl. Sci. Abstr. 1963 (1) 59
- T. Vasilos and G. Harris
 Impervious Flame-sprayed Ceramic Coatings
 Bull. Amer. Ceram. Soc. 41 14 (1962)
 Brit. Ceram. Abstr. 1962 (7) 214A
- M. Levy
 Refractory Coating Research and Development at U. S. Army Materials Research Agency (AMRA)
 Prepared for ASD-NASA-Sponsored Refractory Composites Working Group Meeting (3/63)

J. L. Bliton, H. L. Rechter, and Y. Harada (Illinois Inst. of
Tech.)

Flame Sprayed Zirconia Films for Fuel Cell Components

Am. Ceram. Soc. Bull. 42 (1) 6-9 (1963)

Nucl. Sci. Abstr. 1963 (3) 1139

F15-FORMING SPECIFIC SHAPES

F15g. FORMING SHEETS, PLATES, FILMS

Compagnie Generale de Telegraphie sans Fil

Manufacture of Ceramic Articles

Fr. 1,050,129 (8/26/53)

Ceram. Abstr. 1954 (11) 205

M. D. Heyman

Means and Method for Producing Continuous Sheet of Integrated

Mica

U. S. 2,659,412 (11/17/53)

Ceram. Abstr. 1954 (5) 93

W. R. Weinberger and H. S. Kalish (Sylvania-Corning Nuclear Corp.)

The Fabrication of Stainless Steel-UO₂ Fuel Plates

Presented at Nuclear Engineering and Science Conference, Chicago

3/17-21/58

Nucl. Sci. Abstr. 1958 () 1256

S. I. Megeff and J. L. Zambrow (Sylvania-Corning Nuclear Corp.)

Fabrication of Aluminum Plate-Type Elements Containing Uranium

Dioxide as the Fuel

Am. Inst. Mining. Met. Petrol. Engrs., Inst. Metals Div., Spec.

Rept. Ser. 2 No. 7 25-8 (1958)

Nucl. Sci. Abstr. 1959 (8) 1821

B. E. Schaner (Westinghouse Electric Corp.)

Fabrication of High-Density UO₂ Fuel Platelets

Am. Ceram. Soc. Bull. 38 494-8 (1959)

Nucl. Sci. Abstr. 1961 (10) 3426

G. Dumoulin

Casting in Thin Sheets: Its Use in the Manufacture of Dielectrics

for Ceramic Condensers

Bull. Soc. Franc. Ceram. No. 52 21-26 (1961)

Brit. Ceram. Abstr. 1962 (4) 93A

G. B. Andreev, A. S. Deineko, I. Y. Malakhov, P. V. Sorokin, A. Y.

Taranov (Inst. of Physics and Tech. Academy of Sciences)

Pribery i Tekh. Ekspt. 6 No. 6 (11-12) 149-50 (1961)

Nucl. Sci. Abstr. 1962 (5) 1555

K. Ennerst, K. G. Hackstein, and H. J. Hein (NUKEM Nuklear-Chemie
und-Metallurgie G.m.b.H.)

Manufacture of Fuel Plates for Research Reactors by the Coextrusion
Technique

Atomwirtschaft, 6 (6) 325-32 (1961)

Nucl. Sci. Abstr. 1961 (9) 3080

A. H. F. Muggleton and F. A. Howe (Atomic Weapons Research Establishment)

The Preparation of Thin Self Supporting Boron Films
Nuclear Instr. & Methods 13 (9) 211-14 (1961)
Nucl. Sci. Abstr. 1962 (3) 723

J. J. Fargo (Gladding, McBean and Co.)
Summary Report on Development of Flat Plate Ceramic Fuel Elements
Technical Progress Report 26 (8/28/61)
Contract AT(04-3)-249
Nucl. Sci. Abstr. 1962 (8) 2831

R. C. Ragan (Gladding, McBean and Co.)
Method for Continuous Manufacture of Ceramic Sheets
U. S. Patent 3,007,222 (11/7/61)
Ceram. Abstr. 1962 (4) 93

J. L. Park (American Lava Corp.)
Manufacture of Ceramics
U. S. Patent 2,966,719 (3/1/61)
Brit. Ceram. Abstr. 1961 (6) 233

N. A. Frigerio (Argonne National Lab.)
Fabricating Thin Neutron Foils
Nucleonics 20 No. 3 78 (1962)
Nucl. Sci. Abstr. 1962 (5) 1350

R. Moreh (Israel Atomic Energy Commission) and D. Samuel
Preparation of Thin Targets of Isotopic Oxygen
Rev. Sci. Instr. 33 (11) 1292-3 (1962)
Nucl. Sci. Abstr. 1963 (3) 771

J. T. Thompson (Steatite Div. American Lava Corp.)
Methods of Forming Thin Ceramics
Presented at 64th ACS
Am. Ceram. Soc. Bull. 41 (4) 1962

R. L. Lambert
Formation and Application of Porous Metal or Ceramic Sheet
Technical Publication of Sylvania Electronic Tubes (5/63)

E. K. Muller, B. J. Nicholson, and M. H. Francombe
The Vapor Deposition of BaTiO_3 by a Grain-by-Grain Evaporation
Method
Electrochemical Technology 1 (5-6) 158 (1963)

J. C. Williams, W. R. Sinclair, and S. E. Koonce
Preparation of Thin Mullite Films
J. Am. Ceram. Soc. 46 (4) 161-67 (1963)
Ceram. Abstr. 1963 (6) 165

F15j. FORMING LAMINATES
(also see F15g)

R. K. Francis, R. Brown, E. P. McNamara, and J. R. Tinklepaugh
(State Univ. Coll. of Ceramics, Alfred)

Metal-Ceramic Laminates

8/1/56--7/31/57 and 11/1/57--10/31/58

Project and Task Title: High Temperature and High Stress Characteristics of Ceramics and Cermets

Contract AF33(616)-3798

Nucl. Sci. Abstr. 1959 (9) 2180

Office of Technical Services

Fiber Glass and Glass Laminates OTS Selective Bibliography

Supplement to CTR-292 (9/61)

Nucl. Sci. Abstr. 1962 (2) 430

F15k. FORMING SPHERES, PELLETS

E. W. Drakengren (AB Malardalens Tegelbruk)
Forming of Hollow Ceramic Spheres
Swed. 147,383 (7/31/50)
Ceram. Abstr. 1955 (9) 161

B. K. Frederiksen
Process and Apparatus for the Preparation of Balls, etc., of Uniform
Size and Shape
Fr. 1,032,462 (3/25/53)
Ceram. Abstr. 1954 (7) 130

W. Mason
Shaping or Finishing of Articles of Clay
Brit. 715,815 (9/22/54)
Ceram. Abstr. 1956 (1) 18

H. C. Brassfield (General Electric Co.)
Production of Pebble-type Fuel Elements
Contracts AF33(038)-21102 and AT(11-1)-171 (6/55) Decl. 6/16/61
Nucl. Sci. Abstr. 1962 (3) 767

H. C. Brassfield and C. T. Durham (USA-AEC)
Method of Fabricating Small Spherical Pellets
U. S. Patent 2,872,719 (2/10/59)
Nucl. Sci. Abstr. 1959 (8) 1833

J. R. Fisher and M. D. Rigterink (Bell Telephone Labs., Inc.)
Formation of Expanded Silica Spheres
U. S. 2,883,347 (4/21/59)
Ceram. Abstr. 1959 (8) 218

Doulton & Co. Ltd.
Forming Articles of Plastic Material by Rolling
Brit. Patent 855,739 (7/12/60)
Brit. Ceram. Abstr. 1961 (6) 232A

N. H. Brett, J. D. L. Harrison, and L. E. Russell (Atomic Energy
Research Establishment)
The Production of PuO₂-UO₂ Irradiation Pellets
Plutonium 1960: Cleaver-Hume Press Ltd. 430-48 (1961)
Nucl. Sci. Abstr. 1962 (2) 559

G. Patton, Jr. and S. Zirinsky (USA-AEC)
Eccentric Rolling of Powder and Bonding Agent into Spherical Pellets
U. S. 2,986,772 (6/6/61)
Ceram. Abstr. 1961 () 269

W. B. Tarpley and H. Kartluke (Aeroprojects, Inc.)
Application of Ultrasonic Vibration to Cold Pressing of Ceramic
Pellets

Contract AT(30-1)-1836 (11/61)
Nucl. Sci. Abstr. 1962 (4) 1009

Anon.

Plutonium Oxide Microspheres Could Be Used in Fuel Elements
Chem. Eng. News 40 (43) 72 (1962)
Ceram. Abstr. 1963 (3) 82

O. Brendel, K. Grantz, K. E. Hofstadt, and W. Franz
Method and Apparatus for Mass-producing Small Balls of Plastic
Materials

U. S. 3,049,760 (8/21/62)
Ceram. Abstr. 1963 (1) 23

P. F. Stablein

Apparatus for Forming Small Ceramic Spheres
J. Am. Ceram. Soc. 45 (10) 505-6 (1962)
Ceram. Abstr. 1962 (11) 270

J. F. Ward and C. W. Funk (Aerojet-General Nucleonics)
Fabrication Development of Beryllium Oxide-Uranium Dioxide Ceramic
Fuel at Aerojet-General Nucleonics

TID-7602 Pt. 1 (rev.) 1-11
Nucl. Sci. Abstr. 1962 (2) 424

R. P. Levey, Jr. and A. E. Smith (USA-AEC)
Preparation of Spherical Uranium Dioxide Particles
U. S. Patent 3,087,781 (4/30/63)
Nucl. Sci. Abstr. 1963 (6) 2439

Minnesota Mining and Mfg. Co.
Improvements in Radioactive Refractory Particles
Br. Patent 917,649 (2/6/63)
Nucl. Sci. Abstr. 1963 (2) 461

E. Blaha (Selas Corp. of America)
U. S. 3,071,357 (1/1/63)
Ceram. Abstr. 1963 (4) 106

H. J. Hedger and A. R. Hall (Atomic Energy Research Establishment)

Preliminary Observations on the Use of the Induction-coupled Plasma Torch for the Preparation of Spherical Powder

Powder Met. No. 8 65-72 (1961)

Nucl. Sci. Abstr. 1962 (3) 723

J. B. Francis

Fabricating a 3.5-inch Ferrite Sphere

Am. Ceram. Soc. Bull. 42 (5) 321 (1963)

Ceram. Abstr. 1963 (6) 164

F15m. FORMING HOLLOW WARE

Gt. Brit. Ministry of Supply. Materials Research Div.
Review of the Refractory Sulphides. The Preparation of Cerium
Sesquisulphide Ceramics

6/52

Nucl. Sci. Abstr. 1957 (7) 774

P. Murray, R. W. Thackray, P. Rado, and D. George
Preparation and Properties of Slip-cast Calcium Fluoride Crucibles
Trans. Brit. Ceram. Soc. 54 (11) 693-97 (1955)
Ceram. Abstr. 1960 (3) 61

R. Pointud and J. Roger (Centre d'Etudes nucleaires)
Elaboration of Several Refractory Pieces Used in Metallurgical
Laboratories

Rev. met. 54 No. 4 283-7 (1957)

Nucl. Sci. Abstr. 1958 () 1352

B. E. Vassiliou
Simple Laboratory Method for Making Crucibles and Other Shapes
Trans. Brit. Ceram. Soc. 56 (10) 516-18 (1957)
Ceram. Abstr. 1959 (9) 260

M. J. Kofoed
Ceramic Radome Wall Thickness Tolerance Requirements and Their
Interpretation
Am. Ceram. Soc. Bull. 37 (1) 4-8 (1958)
Ceram. Abstr. 1958 (3) 74

F15n,p. FORMING RODS AND TUBES

J. O. Everhart, K. E. Krill, R. E. Dine, and R. R. Van Der Beck
(National Clay Pipe Research Corp.)

Method and Apparatus for Forming Tubular Ceramic Bodies

U. S. 2,671,939 (3/16/54)

Ceram. Abstr. 1954 (9) 162

P. C. Rossin, Jr. (General Electric Co.)

Continuous Rod or Tube Forming Press

U. S. 2,799,046 (7/16/57)

Ceram. Abstr. 1957 (10) 243

G. V. Samsonov and P. S. Kislyi (Inst. of Metal Ceramics and
Special Alloys)

A New Method for Preparation of Tubes and Rods from Refractory
Metals and Compound Powders

Dopovidi Akad. Nauk Ukr. RSR No. 1 46-8 (1959)

Nucl. Sci. Abstr. 1959 (8) 1826

J. W. Lingafelter (General Electric Co.)

Fabrication of Fuel Rods by Tandem Rolling

Contract AT(04-3)-361 (7/61)

Nucl. Sci. Abstr. 1962 (5) 1349

F16-FORMING POROUS BODIES

H. Z. Schofield, W. H. Duckworth, and R. E. Long (Battelle Memorial Inst.)

Fabrication of Beryllia Shapes by Ceramic Extrusion
Contract W-7405-eng-92 (5/1/49) Decl. 2/13/57
Nucl. Sci. Abstr. 1958 (1) 218

Morgan Crucible Co., Ltd. (Babcock & Wilcox Co.)
Insulating Firebrick and Process of Manufacture
Brit. 661,607 (9/26/51)
Ceram. Abstr. 1953 (1) 9

K. A. Smirnova
Porous Ceramic Shapes with Grog Base and Alkaline-silicate Bond
Steklo i Keram. 8 (10) 16-18 (1951)
Ceram. Abstr. 1953 (5) 88

F. Muckl and P. Gluck
Porous Ceramic Body and Its Manufacture
Fr. 1,054,045 (10/7/53)
Ceram. Abstr. 1954 (11) 200

A. J. Bruno and S. Speil (Johns-Manville Corp.)
Thermal Insulating Bodies and Method of Manufacture
U. S. 2,808,338 (10/1/57)
Ceram. Abstr. 1958 (1) 18

S. Speil and I. Barnett (Johns-Manville Corp.)
Inorganic Bonded Thermal Insulating Bodies and Method of Manufacture
U. S. 2,811,457 (10/29/57)
Ceram. Abstr. 1958 (2) 47

T. M. Giles, N. Tallan, P. S. Hessinger, and J. O. Everhart
Development of Sandwich Construction Inorganic Radomes: I, II
PB Repts. 131408 and 131406
U. S. Govt. Research Repts. 29 (3) 124 (1958)
Ceram. Abstr. 1961 (1) 12

J. R. Fisher and M. D. Rigterink (Bell Telephone Labs., Inc.)
Formation of Expanded Silica Spheres
U. S. 2,883,347 (4/21/59)
Ceram. Abstr. 1959 (8) 218

B. B. Lympny, J. G. Theodore, and W. W. Beaver (Brush Beryllium Co.)

Investigation and Development of Methods for Producing High-porosity Beryllium Bodies

Final Report. Technical Report No. 146 (1/60)

Nucl. Sci. Abstr. 1961 (8) 2735

G. H. Bischoff and A. H. Rosetti (Emerson and Cuming, Inc.)

Development of a Porous Metallic Composite Material

Final Technical Report (6/24/60)

Contract DA-19-020-505-ORD-4971

Nucl. Sci. Abstr. 1962 (2) 426

I. M. Logan, D. C. Wise, J. J. McGahan, and C. von Doenhoff

Development of Non-oxidic Refractory Foams

WADD Technical Report 60-124 (5/60)

Commissariat a l'Energie Atomique

Improvements in Methods of Manufacturing Porous Barriers

Brit. Patent 883,760 (12/6/61)

Nucl. Sci. Abstr. 1962 (2) 420

S. M. Astrakhsantsev, S. P. Gromova, V. L. Kalikhman, and Y. S. Umanski

Effect of Diffusion-porosity Formation in Nichrome on Sintering of Nickel and Chromium Powders

Metalloved. i Termichesk. Obrabotka Metal. No. 7 52-4 (1961)

S. Fernhof

Method of Manufacturing Porous Ceramic Products

U. S. Patent 2,996,389 (8/15/61)

Ceram. Abstr. 1962 (2) 41

National Beryllia Corp.

Development of Fabrication Techniques for Beryllium Oxide Radome Materials

Final Report (6/61)

Contract NOW-60-0057c

Nucl. Sci. Abstr. 1962 (6) 1958

M. E. Tyrrell (Bureau of Mines, Norris Metallurgy Research Lab.)
Experimental Production of Lightweight Basic Refractories
9/61
Nucl. Sci. Abstr. 1962 (10) 3610

M. E. Tyrrell
Experimental Production of Lightweight Basic Refractories
U. S. Bur. Mines Rept. Invest. No. 6025 (1962)
Ceram. Abstr. 1963 (1) 13

E. Blaha (Selas Corp. of America)
Manufacture of Uniform Cellular Ceramic Articles
U. S. 3,056,184 (10/2/62)
Ceram. Abstr. 1963 (2) 46

J. L. Felder
Method of Producing Vitreous Clay Products
U. S. 3,050,812 (8/28/62)
Ceram. Abstr. 1963 (1) 13

I. Y. Guzman and D. N. Poluboyarinov
BeO-porous Ceramics
Ogneupory No. 10 457-62 (1962)
Nucl. Sci. Abstr. 1963 (4) 1459

N. E. Poulos, J. D. Walton, Jr., and S. R. Elkins
Fused Silica-hydrated Cements for Thermal Protection Systems
Am. Ceram. Soc. Bull. 41 (12) 812-15 (1962)
Ceram. Abstr. 1963 (1) 4

A. L. W. Williams and C. K. Gravley (Clevite Corp.)
Method of Producing Cellular Ceramic Electromechanical Transducers,
Transducer Materials, and Elements
U. S. 3,052,949 (9/11/62)
Ceram. Abstr. 1963 (1) 21

Anon.
New Uses for Cellular Ceramics
Industrial World (3) (1963)

J. H. Fishwick
Manufacture of Foamed Ceramics Based on Petalite and beta
spodumene
Am. Ceram. Soc. Bull. 42 (3) 110-13 (1963)
Ceram. Abstr. 1963 (4) 101

R. L. Lambert
Formation and Application of Porous Metal or Ceramic Sheet
Technical Publication of Sylvania Electronic Tubes (5/63)

I. Y. Guzman (D. I. Mendeleev Chem. Technol. Inst., Moscow)
Structural Peculiarities and Properties of Foam Ceramics Based on
Pure Oxides (Al_2O_3 and BeO)
Nauch. Doklady Vysshego Shkoly, Khim. i Khim. Tekhnol. 1959 No. 1
181-5
Chem. Abstr. 53 14443

F17-FORMING COMPOSITES

W. D. Kingery

Metal-ceramic Interactions: I, Factors Affecting Fabrication and Properties of Cermet Bodies

J. Am. Ceram. Soc. 36 (11) 362-65 (1953)

Ceram. Abstr. 1954 (1) 9

L. R. Whitaker

Prestressed Tile Beams

Brick & Clay Record 122 (5) 50-51 (1953)

Ceram. Abstr. 1955 (1) 10

S. Tacvorian (Office National d'Etudes et de Recherches Aeronautiques)

Metalloceramic Compositions and Process Producing

U. S. 2,767,463 (10/23/56)

Ceram. Abstr. 1956 (2) 40

H. C. Dunegan (American Lava Corp.)

A Study and Evaluation of Methods of Producing a Ceramic-to-Metal Seal by Pressed Powder Techniques for Automatic Mass Production

Final Report 8/16/56--11/30/56

Contract AF33(600)-27329

Nucl. Sci. Abstr. 1957 () 468

M. T. Curran, R. P. Riegert, R. K. Francis, R. S. Truesdale, and J. R. Tinklepaugh

Ceramic Reinforced Alloys and Plated Cermets

PB Rept. 131188

U. S. Govt. Research Repts. 29 (5) 274 (1958)

Ceram. Abstr. 1961 (9) 212

S. Shapiro (Martin Co.)

A New Fabrication Technique for the Production of Stainless Steel Oxide Dispersion Fuel Elements

A/CONF.15/P/784

Nucl. Sci. Abstr. 1958 () 1816

C. G. Goetzel and L. P. Skolnick (Sintercast Corp. of America)
Method of Interstitially Casting Metal in High Melting Skeleton Bodies

U. S. 2,828,226 (3/25/58)

Ceram. Abstr. 1958 (7) 176

H. H. Hausner (Penn-Texas Corp.)
Slip Casting of Cermets
Contract AT(30-1)-1991 (3/31/58)
Nucl. Sci. Abstr. 1958 () 1057

S. I. Megeff, and J. L. Zambrow (Sylvania-Corning Nuclear Corp.)
Fabrication of Aluminum Plate-type elements Containing Uranium Dioxide as the Fuel
Am. Inst. Mining Met. Petrol. Engr., Inst. Metals Div., Spec. Rept.
Ser. 5, No. 7 25-8 (1958)
Nucl. Sci. Abstr. 1959 (8) 1821

Y. Baskin and C. A. Arenberg (Armour Research Foundation) and
J. H. Handwerk (Argonne National Lab.)
Thoria Reinforced by Metal Fibers
Am. Ceram. Soc. Bull. 38 (7) 345-8 (1959)
Nucl. Sci. Abstr. 1959 (10) 2436

J. F. C. Morden
Metallic Fibers
Metal Ind. (London) 96 (25) 495-99 (1960)
Ceram. Abstr. 1961 (1) 10

E. S. Machlin (Materials Research Corp.)
Non-metallic Fibrous Reinforced Metal Composites
Status Report (9/61)
Contract NOw 61-0209-c
Nucl. Sci. Abstr. 1962 (1) 257

W. V. Goeddel and M. T. Simnad (USA-AEC)
Method of Making Metal Bonded Carbon Bodies
U. S. 3,001,238 (9/26/61)
Ceram. Abstr. 1962 (3) 63

Anon.
Transfer and Compression Molding of Glass-bonded Mica
Ceram. Age II (3) 28-31 (1961)
Ceram. Abstr. 1962 (2) 41

L. Meny, J. Buffet, and C. Sauve
Powder Sintering and Extrusion for the Fabrication of U-Al and UO₂
Stainless Steel Dispersion Fuel Elements
Translated by J. V. L. Hopkins (U.K.A.E.A. Atomic Research
Establishment)
Plansee Proc., 4th Seminar Reutte/Tyrol (1961)
Nucl. Sci. Abstr. 1962 (10) 3612

N. E. Poulos, J. D. Walton, Jr., and S. R. Elkins
Fused Silica-hydrated Cements for Thermal Protection Systems
Am. Ceram. Soc. Bull. 41 (12) 812-15 (1962)
Ceram. Abstr. 1963 (1) ⁴

Y. Baskin and J. H. Handwerk (Argonne National Lab.)
Thoria and Thoria-Urania Reinforced by Metal Fibers
Contract W-31-109-Eng-38
Nucl. Sci. Abstr. 1962 (11) 4046

G. Klanke
Prestressed Ceramics
Keram. Z. 14 (6) 340-47 (1962)
Ceram. Abstr. 1963 (3) 71
Brit. Ceram. Abstr. 1963 (3) 76A

W. D. Klopp (Battelle Memorial Inst. Defense Metals Information
Center)
Summary of the Fifth Meeting of the Refractory Composites Working
Group
Contract AF33(616)-7747 (3/12/62)
Nucl. Sci. Abstr. 1962 (7) 2345

W. A. Gibeaut and D. J. Maykuth (Battelle Memorial Inst. Defense
Metals Information Center)
Summary of the Sixth Meeting of the Refractory Composites Working
Group
9/24/62
Nucl. Sci. Abstr. 1963 (1) 59

J. D. Walton, Jr. and N. E. Poulos
Slip-cast Metal Fiber Reinforced Ceramics
Am. Ceram. Soc. Bull. 41 (11) 778-80 (1962)
Ceram. Abstr. 1963 (1) ⁴

B. J. Triffleman (Curtiss-Wright Corp.)
Method of Manufacturing Homogeneous Carbides
U. S. Patent 3,013,875 (12/19/62)
Ceram. Abstr. 1962 (6) 142

National Research Council. Materials Advisory Board
State of the Art on Powder Metallurgy
Fourth Progress Report by the Panel on Casting and Powder Metal-
lurgy (5/28/62)

H. M. Abbott, comp. (Lockheed Missiles and Space Co.)
Composite Materials: an Annotated Bibliography
Nucl. Sci. Abstr. 1963 (6) 2437

O. J. Whittemore, Jr. (Norton Co.)
Process of Making a Nuclear Fuel Element
U. S. Patent 3,081,249 (3/12/63)
Nucl. Sci. Abstr. 1963 (5) 2166

F20b. APPLIED MECHANICS OF FORMING
(see F21p,q)

K. K. Strelov
Compression of (Ceramic) Ware
Ogneupory 22 (1) 38-42 (1957)
Ceram. Abstr. 1959 (1) 19

K. K. Strelov
Elastic Expansion and Crushing of Mixtures During Pressing
Ogneupory 23 (3) 131-35 (1958)
Ceram. Abstr. 1951 (8) 201

E. Hallmann
Calculation of Extrusion Press for Solid Particles
Ziegelind 13 (9-10) 321-30 (1960)
Ceram. Abstr. 1960 (10) 239

A. P. Larin, S. A. Losev, and V. G. Slousheh
Determining the Pressing Force of Toggle Presses
Ogneupory 25 (1) 14-16 (1960)
Ceram. Abstr. 1960 (8) 195

W. C. Allen
Dimensional Control of Ceramic Materials
Am. Ceram. Soc. Bull. 40 (6) 383-89 (1961)
Ceram. Abstr. 1961 (9) 216

V. Chikara Mitsuki and M. Kobayshi
Fundamental Studies on Plasticity: V
Bull. Govt. Research Inst. Ceramics (Koyoto) 6 29-30 (1952)
Ceram. Abstr. 1953 (1) 9

E. Deeg
Slip Casting, a Diffusion Problem
Ber. deut. keram. Ges. 30 (6) 129-38 (1953)
Ceram. Abstr. 1953 (11) 19

T. Haase
Investigations of the Plasticity of Ceramic Bodies
Silikattech. 5 (10) 429-31 (1954)
Ceram. Abstr. 1955 (5) 89

I. S. Kainarskii and I. Y. Piven
Influence of Lowering the Microhardness of Mineral Powders under
the Action of Surface-active Agents on Their Capacity to Densify
During Pressing
Ogneupory 22 (1) 27-29 (1957)
Ceram. Abstr. 1959 (1) 19

S. P. Nichiporenko
Significance of Rheological Curves of Ceramic Bodies in Ceramic
Technology
Dokl. Akad. Nauk SSSR 118 (4) 785-87 (1958)
Ceram. Abstr. 1963 (1) 29

V. V. Eremenko
Rheological Characteristics of Plastic Ceramic Materials in Con-
nection with Their Technical Properties
Trudy Akad. Stroitel'stva i Arkhitektury SSSR, Zapad.-Sibir. Filial
No. 2 32-8 (1959)
Chem. Abstr. 55 27830 (1961)

F. J. Goodson
Experiments in Extrusion
Trans. Brit. Ceram. Soc. 58 (3) 158-87 (1959)
Ceram. Abstr. 1960 (6) 143

W. D. Mohr and R. S. Mallouk (E. I. du Pont de Nemours & Co., Inc.)
Flow, Power Requirements, and Pressure Distribution of Fluid in
a Screw Extruder
Chem. Abstr. 53 16610

J. A. Nelson and A. I. Andrews
Rheological Properties of the Clay-water System Under Pressure
Am. Ceram. Soc. Bull. 38 (9) 447-55 (1959)
Ceram. Abstr. 1959 (11) 292

T. Haase
Mechanism of Dry Pressing
Ber. deut. keram. Ges. 37 (3) 97-101 (1960)
Ceram. Abstr. 1960 (9) 215

G. M. Zhdanovich
Problems on the Theory of the Process of Pressing Metal Powders
and Their Mixtures
Nucl. Sci. Abstr. 1963 (3) 860

A. R. Eaton and R. L. Cooper
Compaction Behavior of Several Ceramic Powders
J. Am. Ceram. Soc. 45 (3) 97-101 (1962)
Ceram. Abstr. 1962 (4) 100

F. V. Kondrashev
Vacuum Treatment of Ceramic Powders During Pressing
Steklo i Keram. 19 (5) 19-21 (1962)
Glass Ceram (USSR) (English Transl.) 251-54
Ceram. Abstr. 1963 (4) 106

W. R. DeHollander (General Electric Co.)
Particle Size Relationships in the Packing of UO_2
CEND-153 Vol. 1 75-83
Nucl. Sci. Abstr. 1963 (4) 1449

I. Shapiro
Compressibility of Powders, Fundamental Studies of Aeronautical
Systems
Report No. ASD-TDR-63-147 (3/63)

S. Takahashi and N. Asami (Mitsubishi Atomic Power Industries, Inc.)
An Approach to Vibration Compaction of Uranium Dioxide
Nippon Genshiryoku Gakkaishi 5 (2) 133-40 (1963)
Nucl. Sci. Abstr. 1963 (6) 2444

F21-PREPARATIONS FOR FORMING

F21c. GRANULATION

(see also H14)

R. Weber (Metallgesellschaft Akt.-Ges.)

Powder Metallurgy

Ger. 1,031,615 (6/4/58)

Chem Abstr. 1960 (12) 24310

F21d. COATINGS ON GRANULES

Nuclear Materials and Equipment Corp.
Coating of UO_2 and U Metal Spheres with Metals
Quarterly Progress Report 5/16/60--8/15/60
Contract AT(30-1)-2264
Nucl. Sci. Abstr. 1961 (10) 3250

United Kingdom Atomic Energy Authority
Method of Manufacturing a Nuclear Fuel
Fr. Patent 1,252,507 (12/19/60)
Nucl. Sci. Abstr. 1961 (12) 4195

J. M. Blocher, Jr., M. F. Browning, A. C. Secrest, V. M. Secrest,
and J. H. Oxley (Battelle Memorial Inst.)
Preparation of Ceramic-coated Nuclear-fuel Particles
TID-7622 57-73
Nucl. Sci. Abstr. 1962 (10) 3457

Associated Electrical Industries Ltd.
Preparation of High Density Sintered Uranium Dioxide for Nuclear
Reactors
Fr. Patent 1,264,209 (5/8/61)
Nucl. Sci. Abstr. 1963 (3) 1141

C. Sari and E. Jonckheere (Centre d'Etudes l'Energie Nucleaire)
Depositing of Particles by Metalization in Vacuum
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG. 600-14 (1962)
Nucl. Sci. Abstr. 1963 (1) 260

J. W. Szymaszek (Union Carbide Corp.)
Slip Casting
U. S. 2,979,401 (4/11/61)
Ceram. Abstr. 1961 (9) 220
Chem. Abstr. 1961 16381

F21f. FEEDING BATCH TO DIE

E. Schwabe, R. Kempkes, and H. Voller (Deutsche Edelstahlwerke
Akt.-Ges.)

Method of Producing Compressed Parts for Permanent Magnets

U. S. 2,959,823 (11/15/60)

Ceram. Abstr. 1961 (3) 66

F21g,j. DIES AND MOLDS, MATERIALS FOR AND DESIGN OF

E. Mosthaf

Long Extrusion Dies Cut Costs
Ceram. Ind. 53 (2) 70-71 (1949)
Ceram. Abstr. 1950 (6) 127

A. R. Blackburn and R. E. Steele (Ram, Inc.)
Mold and Method of Making Molds
U. S. 2,615,229 (10/28/52)
Ceram. Abstr. 1953 (2) 29

J. W. Knowlton (Norton Co.)
Mold and Method for Molding Refractory Materials
Can. 481,848 (3/18/52)
Ceram. Abstr. 1953 (2) 27

J. F. Bryer and R. E. Steele
Treatment of Plaster Molds (to Increase Permeability)
U. S. 2,632,209 (3/24/53)
Ceram. Abstr. 1953 (8) 144

A. R. Blackburn and R. E. Steele
Method for Making Ware by Casting
U. S. 2,632,762 (2/23/54)
Ceram. Abstr. 1954 (8) 144

M. R. Horne
Elastic-plastic Theory of Containers and Liners for Extrusion
Presses
Proc. Inst. Mech. Engr. (London) 169 107-22 (1955)
J. Appl. Chem. 5 (11) 11-554 (1955)
Ceram. Abstr. 1956 (2) 59

L. V. Gewiss
Process of Molding Ceramic or Similar Objects, the Apparatus, and
the Objects Obtained
Fr. 1,118,912 (3/26/56)
Ceram. Abstr. 1957 (9) 210

J. Mollers (Hartford National Bank & Trust Co.)
Device for the Manufacture of Ceramic Moldings
U. S. 2,770,025 (11/13/56)
Ceram. Abstr. 1957 (2) 42

R. A. Nesbit
Formation of Ceramic, etc., Articles
U. S. 2,765,512 (10/9/56)
Ceram. Abstr. 1957 (1) 17

B. W. Nies and C. M. Lambe
Movement of Water in Plaster Molds
Am. Ceram. Soc. Bull. 35 (8) 319-24 (1956)
Ceram. Abstr. 1956 (10) 216

L. R. Alt
Extrusion Die Problems
Am. Ceram. Soc. Bull. 36 (4) 137-38 (1957)
Ceram. Abstr. 1957 (6) 140

H. Bollman
Unique New Forming Technique
Ceram. Age 70 (1) 36-38 (1957)
Ceram. Abstr. 1962 (1) 17

F. I. Chuprinin
Mold for Vacuum Pressing
Ogneupory 22 (7) 329-32 (1957)
Ceram. Abstr. 1958 (7) 179

R. V. Ganz
Method of Making Ceramic Forms
U. S. 2,816,347 (12/17/57)
Ceram. Abstr. 1958 (3) 77

C. Rauh
Durable Master Molds for the Ceramic Industry
Euro-Ceram. 7 (2) 27-29 (1957)
Ceram. Abstr. 1957 (7) 156

G. W. Sherratt and C. E. Hahn (General Electric Co.)
Electrostatic Method and Apparatus for Lining Molds
U. S. 2,795,512 (6/11/57)
Ceram. Abstr. 1957 (10) 244

C. M. Lambe
Preparation and Use of Plastic Molds
Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc. 31-40 (1958)

H. S. Magid
Controls Required and Problems Encountered in Production Slip Casting
Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc. 40-5 (1958)

P. D. S. St. Pierre
Slip Casting Nonclay Ceramics
Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc. 45-51 (1958)

S. G. Whiteway, M. Coll-Palagos, and C. R. Masson
Slip-casting Magnesia
Am. Ceram. Soc. Bull. 40 (7) 432-38 (1961)
Ceram. Abstr. 1961 (9) 214

S. D. Stoddard (USA-AEC)
Refractory Coating for Graphite Molds
U. S. Patent 2,840,480 (6/24/58)
Nucl. Sci. Abstr. 1958 () 1728

F. P. Foraboschi
Plastic Molds for Casting Ceramic Ware
Ceramica (Milan) 14 (4) 71-3 (1959)
Ceram. Abstr. 1959 (9) 240

L. A. Hampel and W. J. Wick (Kolmar Labs., Inc.)
Apparatus for Compressing Finely Divided Solids
U. S. 2,900,664 (8/25/59)
Ceram. Abstr. 1960 (2) 41

Philips Electrical Industries Ltd.
Moulding Press
Brit. Patent 899,257 (6/20/62)
Brit. Ceram. Abstr. 1963 (2) 43A

G. R. Hansen (Carborundum Co.)
Refractory Bodies and Method of Making
U. S. 2,897,572 (8/4/59)
Ceram. Abstr. 1959 (11) 286

W. R. Harry (McGraw-Edison Co.)
Method and Apparatus for the Manufacture of Ceramic Ware
U. S. 2,898,658 (8/11/59)
Ceram. Abstr. 1960 (1) 14

J. P. Livingston (USA-AEC)
Spherical Die
U. S. Patent 2,870,484 (1/27/59)
Nucl. Sci. Abstr. 1959 (8) 1832

W. B. Wilson (USA-AEC)
High Pressure Dies
U. S. 2,938,998 (5/31/60)
Ceram. Abstr. 1960 (10) 239

J. R. Parks and M. J. Hill
Design of Extrusion Augers and the Characteristic Equation of Ceramic Extrusion Machines
Am. Ceram. Soc. 42 (1) 1-6 (1959)
Ceram. Abstr. 1959 (2) 55

J. O. Everhard
Thoughts on Die Design
Ceram. Age 76 (3) 29-31 (1962)
Ceram. Abstr. 1962 (4) 96

J. G. Seanor
Brick Dies
Journal of Canadian Ceram. Soc. 29 72-78 (1960)
Ceram. Abstr. 1962 (1) 7

J. G. Seanor and W. P. Schweitzer
Basic Theoretical Factors in Extrusion Augers
Am. Ceram. Soc. Bull. 41 (9) 560-63 (1962)
Ceram. Abstr. 1962 (10) 238

C. O. P. Leusden
Plastic Properties of Clays and Their Influence on the Design of
Extrusion Nozzles
Ber. Deut. Keram. Ges. 39 (8) 427-31 (1962)
Ceram. Abstr. 1963 (3) 71

H. H. Lund, S. A. Borman, A. J. Reed
Auger Design for Clay Extrusion
Am. Ceram. Soc. Bull. 41 (9) 554-59 (1962)
Ceram. Abstr. 1962 (10) 238

A. J. Reed
Auger Design
Am. Ceram. Soc. Bull. 41 (9) 549-50 (1962)
Ceram. Abstr. 1962 (10) 238

T. W. Penrice
Compacting of Powders Using Moulds Made from Reversible Gels
Special Ceramics: Heywood 329 (1960)
Brit. Ceram. Abstr. 1961 (3) 109A

P. Denes
Moulded Ceramic Bodies
Brit. Patent 872,097 (5/7/61)
Brit. Ceram. Abstr. 1962 (2) 40A

General Electric Co. Ltd.
Compacted Powder Articles
Brit. Patent 893,377 (4/11/62)
Brit. Ceram. Abstr. 1962 (11) 311A

L. E. Thiess (General Electric Co.)
Apparatus for Manufacturing Ceramics
U. S. 2,984,887 (5/23/61)
Ceram. Abstr. 1961 (10) 245

H. Seltmann
Mold for Shaping Ceramic Material
U. S. 3,075,846 (1/29/63)
Ceram. Abstr. 1963 (5) 133

9138 UCRL-5066
California Univ., Livermore Radiation Lab.
Die Design for Hot Presses. (A Bibliography).
4 p. Contract W-7405-eng-48. (M-6300).
April 19, 1957
Nuc. Sci. Abstr. 1958 1058

J. P. Livingston
Spherical Die (To U. S. Atomic Energy Commission)
U.S. 2,870,484 (1/27/59)
Nuc. Sci. Abstr. 1959 (8) 1832

Toshiyuki Sata and Ritsaku Kiyoura
Fabrication of cermets of the system alumina-chromium
by hot pressing.
Yogyo Kyokai Shi 67 (760) 116-23 (1959)
Ceram. Abstr. 1960 (6) 138

Wendell B. Wilson (United States of America as represented by
the U. S. Atomic Energy Commission).
High Pressure Dies
U.S. 2,938,998 (5/31/60)
Ceram. Abstr. 1960 (10) 239

John Sidney O'Neill and David Thomas Livey (to United Kingdom
Atomic Energy Authority)
Improvements in or relating to moulds for hot pressing powdered materials
British Patent 878,088 (9/27/61)
Nuc. Sci. Abstr. 1961 (12) 4013

British Aluminum Co., Ltd.
Hot Pressing Process
British Pat. 877,409 (13/9/61)
Brit. Ceram. Abstr. 1962 (4) 112a

Deutsche Edelstahlwerke
A New Type of Hot Pressing Die.
Brit. Pat. 899,915 (27/6/62)
Brit. Ceramic Abstr. 1963 (2) 43a

W. L. Kennicott

Use of Hard Metal Carbides in Ceramic Fabrication

Am. Ceram. Soc. Bull. 42 (3) 106-109 (1963)

Ceram. Abstr. 1963 (4) 106

W. M. Wheildon

Wear Resistant Ceramic Tooling in the Fabrication of Ceramic Shapes

Am. Ceram. Soc. Bull. 42 (5) 308-11 (1963)

Ceram. Abstr. 1963 (6) 167

F21k. DESIGN OF PARTS

F. Strasser

Design Your Parts for Economical Production: I

Ceram. Ind. 73 (1) 68-71, 81 (1959)

Ceram. Abstr. 1962 (2) 42

F. Strasser

Proper Parts Design Saves Time, Money

Ceram. Ind. 77 (2) 54-57 (1961)

Ceram. Abstr. 1962 (3) 69

F21s. ADDITIVES FOR SPECIFIC PURPOSES

C. C. Treischel and E. W. Emrich
Study of Several Groups of Organic Binders Under Low Pressure
Extrusion
J. Am. Ceram. Soc. 29 (5) 129-32 (1946)

C. Kajisaki and K. Hori
Organic Deflocculant: II, Effects of Polyvinylamine and a New Use
of Potassium Polyacrylate
Bull. Govt. Research Inst. Ceramics (Kyoto) 6 (1) 25-8 (1952)
Ceram. Abstr. 1953 (1) 10

C. F. Ludvigsen and H. L. Andsager
Influence of Grain Size, Concentration, Time, and pH Value in
(Nonagitated) Suspensions of Plastic and Nonplastic Materials
on the Unmixing Tendency of the Particles
Trans. Intern. Ceram. Congr., 3rd Congr., Paris 243-50 (1952)
Ceram. Abstr. 1957 (6) 96

R. E. Corwin and G. B. Eyerly
Preparation of Refractories from Uranium Dioxide
J. Am. Ceram. Soc. 36 (4) 137-9 (1953)
Ceram. Abstr. 1953 (5) 84

C. V. Kukolev and L. A. Shchukareva
Improving the Properties of Sanitary-ware Slips by Means of a
Combination Peptizer
Steklo i Keram 10-(7) 15-16 (1953)
Ceram. Abstr. 1954 (8) 143

Spengler-Maschinenbau G.m.b.H.
Process of Increasing the Structural Compactness of Pressure Molded
Ceramic Pieces
Fr. 1,044,337 (6/17/53)
Ceram. Abstr. 1954 (11) 205

G. W. Phelps and S. G. Maguire, Jr.
Water as a Ceramic Raw Material
Am. Ceram. Soc. Bull. 35 (11) 422-26 (1956)
Ceram. Abstr. 1957 (2) 21

E. A. Brandes (Fulmer Research Inst., Ltd.)
Ceramic Molding Process
U. S. 2,810,182 (10/22/57)
Ceram. Abstr. 1958 (2) 47

G. V. Kukolev and A. N. Korel
Use of Surface Active Materials in the Plastic Method of Producing
Ceramics

Steklo i Keram. 14 14-17 (1957)
Ceram. Abstr. 1958 (9) 244

Societe Francaise de Ceramique, Service des Recherches Techniques
Effectiveness of Wetting Agents in Ceramic Materials
Ind. Ceram. No. 483 31-37 (1957)
Ceram. Abstr. 1958 (4) 93

C. Hyde
Vertical Extrusion of Nonclay Compositions
Ceramic Fabrication Processes: The Technology Press of Mass. In-
stitute of Technology and John Wiley & Sons, Inc. 107-11 (1958)

E. Mizzan and G. H. Chalder (Atomic Energy of Canada Ltd.)
Comparison of Binder/Lubricant Additives in Dry Pressing Uranium
Dioxide Powder
6/58
Nucl. Sci. Abstr. 1958

B. C. Weber, P. E. Rempes, and M. A. Schwartz
Slip Casting of Metals, Ceramics, and Cermets
Am. Ceram. Soc. Bull. 37 (7) 334-39 (1958)
Ceram. Abstr. 1958 (9) 239

P. E. Rempes, Jr.
Film Technique Fabrication Improvement for Slip Casting Powdered
Materials
U. S. Patent 2,990,292 (6/27/61)
Ceram. Abstr. 1962 (1) 17

T. M. Benziger (USA-AEC)
Graphite Extrusions
U. S. Patent 3,870,031 (1/20/59)
Nucl. Sci. Abstr. 1959 (8) 1832

P. Flachsenberg
Recent Developments in the Field of Sintered Dolomite
Sprechsaal 93 123-6 (1960)
Chem. Abstr. 54 13589

- G. V. Kukolev and N. V. Pitak
Effect of Peptizers on the Output of a Pug Mill for Preparing
Earthenware Bodies and Kaolin-bentonite Suspensions
Steklo i Keram. 16 (7) 7-11 (1959)
Ceram. Abstr. 1960 (5) 115
- G. V. Kukolev and K. A. Mikhailova (Inst. Refractor. Research,
Kharkov)
Surface-active Agents in the Technology of Semidry Pressing of
Refractories
Silikat Tech. 10 597-8 (1959)
Chem. Abstr. 54 8017
- G. K. Kukelov and K. A. Mikhailova
Effect of Surface-active Agents on the Pressability and Elastic
Aftereffects of Certain Refractory Bodies
Ogneupory 25 (5) 222-26 (1960)
Ceram. Abstr. 1962 (7) 168
- N. G. Mitin, I. N. Zubatova, Z. Z. Romanovskaya, T. I. Kudrina,
and B. I. Vishnevskii
Steklo i Keramika 17 No. 9, 38 (1960)
Brit. Ceram. Abstr. 1961 (7) 265A
- E. Ryshkewitch
Plastic Workability of Oxide Masses
Oxide Ceramics. Physical Chemistry and Technology: Academic Press
31-43 (1960)
- E. Smith (Monsanto Chemicals, Ltd)
Slip-casting Process
U. S. 2,942,991 (6/28/60)
Ceram. Abstr. 1960 (10) 235
- H. Lloyd, N. R. Williams, and C. C. H. Wheatley (United Kingdom
Atomic Energy Authority)
Improvements in or Relating to Production of Uranium Oxide Bodies
Br. Patent 881,883 (11/8/61)
Nucl. Sci. Abstr. 1962 (1) 254

G. W. Phelps

Soluble Salts--Their Effect on Casting Properties in Ball Clays

Ceram. Ind. 76 (3) 68-9 (1961)

Ceram. Abstr. 1962 (3) 69

W. B. Tarpley, K. H. Yocum, R. Pheasant (Aeroprojects, Inc.)

Ultrasonic Extrusion; Reduction in Vehicle and Plasticizer Requirements for Non-clay Ceramics

Contract AT(30-1)-1836 (11/61)

Nucl. Sci. Abstr. 1962 (5) 1555

J. D. Fleming, J. W. Johnwon, P. Boland, S. H. Bomar, and A. R. Colcord (Georgia Inst. of Tech.)

Materials for High Temperature Nuclear Engineering Applications

Quarterly Report No. 1 8/15/61--4/1/62

Contract AT(40-1)-2483

Nucl. Sci. Abstr. 1962 (11) 3934

R. E. Cowan, S. D. Stoddard, D. E. Nuckolls

Slip Casting Calcium Oxide

Am. Ceram. Soc. Bull. 41 (2) 102-104 (1962)

Ceram. Abstr. 1962 (3) 62

S. D. Stoddard, D. E. Nuckolls, and R. E. Cowan (USA-AEC)

Casting Slips for Fabrication of Refractory Metal Ware

U. S. Patent 3,052,532 (9/4/62)

Nucl. Sci. Abstr. 1962 (11) 4045

P. A. Denes

Ceramic Dipping Process

U. S. Patent 3,016,597 (1/16/62)

Brit. Ceram. Abstr. 1962 (7) 216

R. R. Hughan

Lubricant Aids in the Manufacture of Silica and Magnesia Refractories

Refractories J. 38 (3) 85 (1962)

Ceram. Abstr. 1963 (1) 13

F23b. HOT FORGING

S. J. Paprocki, D. L. Keller, G. W. Cunningham, and D. E. Kizer
(Battelle Memorial Inst.)

Development of Cermet Fuel Elements

Contract W-7405-eng-92 (8/11/58) decl. 9/26/58

S. J. Paprocki, D. L. Keller, G. W. Cunningham, and D. E. Kizer
(Battelle Memorial Inst.)

Preparation and Properties of UO_2 Cermet Fuels

Contract W-7405-eng-92 (12/19/60)

Nucl. Sci. Abstr. 1961 (4) 997

W. R. Weinberger and H. S. Kalish (Sylvania-Corning Nuclear
Corp.)

The Fabrication of Stainless Steel- UO_2 Fuel Plates

Presented at Nuclear Engineering and Science Conference, Chicago,

3/17-21/58 Preprint 38, Session 28

Nucl. Sci. Abstr. 1958 () 1256

F23e. HOT EXTRUSION

W. E. Ray (Knolls Atomic Power Lab.)
Extrusion of a Complex Shape Through a Round Die
Metal Progr. 72 No. 3 65-9 (1957)
Nucl. Sci. Abstr. 1958 (1) 36

E. M. Grala (Illinois Inst. of Tech.)
Fabrication of Tubular Fuel Elements
Final Report (9/9/58)
For General Electric Co. Aircraft Nuclear Propulsion Dept.
Contracts AF33(600)-38062 and AT(11-1)-171 Subcontract AF-36
Nucl. Sci. Abstr. 1963 (6) 1746

P. Loewenstein
Some Possible Applications of Metal-Working
Processes to Ceramics and Cermets
Ceramic Fabrication Processes: The Technology Press of Mass. In-
stitute of Technology and John Wiley & Sons, Inc. 195 (1958)

C. E. Pearson and R. N. Parkins
The Extrusion of Metals
John Wiley & Sons Inc., Second Edition (1960)
Nucl. Sci. Abstr. 1961 (10) 3251

P. Loewenstein, L. R. Aronin, and A. L. Geary (Nuclear Metals, Inc.)
Hot Extrusion of Metal Powders
Powder Metallurgy: Academic Press 563-83 (1961)
Nucl. Sci. Abstr. 1961 (9) 3084

A. Kaufmann, P. Lowenstein, and J. Hunt (Nuclear Metal, Inc.)
The Fabrication of Clad Massive UO_2 Fuel Elements by Hot Coextrusion
Fuel Element Fabrication with Special Emphasis on Cladding Materials:
Academic Press, Vol. I 325-41 (1961)
Nucl. Sci. Abstr. 1961 (9) 3082

J. G. Hunt, D. F. Kaufman, and P. Loewenstein (Nuclear Metals, Inc.)
Hot Extrusion of UO_2 Fuel Elements. Fundamental and Applied Research
and Development in Metallurgy
Final Report 7/1/60--6/30/61
Nucl. Sci. Abstr. 1962 (4) 1009

R. N. Randall, D. M. Davies, J. M. Siergiej, and P. Loewenstein
(Nuclear Metals, Inc.)
Fundamental and Applied Research and Development in Metallurgy;
Extrusion by Hydrostatic Pressure
Final Report 7/1/60--6/30/61 (7/13/61)
Changed from Official Use Only 8/2/61
Contract AT(30-1)-1565
Nucl. Sci. Abstr. 1961 (12) 4192

Nuclear Metals, Inc.
Fundamental and Applied Research and Development in Metallurgy
Progress Report 12/60 (2/7/61)
Contract AF(30-1)-1565
Nucl. Sci. Abstr. 1961 (5) 1466

Nuclear Metals, Inc.
Fundamental and Applied Research and Development in Metallurgy
Progress Report 1/61 (3/20/61)
Contract AT(30-1)-1565
Nucl. Sci. Abstr. 1961 (6) 1887

Nuclear Metals, Inc.
Fundamental and Applied Research and Development in Metallurgy
Progress Report to USA-AEC 2/61 (4/14/61)
Contract AT(30-1)-1565
Nucl. Sci. Abstr. 1961 (6) 2064

P. Loewenstein (Nuclear Metals, Inc.)
Hot Extrusion of Powder for Use in Nuclear Reactors
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee Ag. 543-65 (1962)
Nucl. Sci. Abstr. 1963 (1) 260

W. Arbiter (Nuclear Development Corp. of America)
The Preparation and Properties of Dispersion-hardened Uranium
Powder Products
Contract AT(30-1)-2303 (2/21/61)
Nucl. Sci. Abstr. 1962 (2) 567

W. Arbiter and G. Stern (Nuclear Development Corp. of America)
Preparation and Properties of Dispersion Hardened Uranium-Uranium
Oxide

Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG. 467-82 (1962)
Nucl. Sci. Abstr. 1963 (1) 259

N. J. Grant, C. G. Goetzel, and E. J. Kalil (134 Woodworth Corp.)
Solid State Fabrication of Hard, High Melting Point, Heat Resistant
Materials

U. S. Patent 3,000,734 (9/19/61)
Ceram. Abstr. 1962 (3) 63

L. Meny, J. Buffet, and C. Sauve (Centre d'Etudes Nucleaires)
Application of Extrusion and Sintering of Powders for the Fabrication
of Disperse Fuel Elements of U-Al and UO₂ -SS

Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG 566-99 (1962)
Nucl. Sci. Abstr. 1963 (1) 260

B. C. Raynes (Horizons, Inc.)
Studies of the Reinforcement of Metals with Ultra High Strength
Fibers (Whiskers)

Final Report 10/28/60--8/27/61 (11/27/61)
Contract NOW-61-0207-c
Nucl. Sci. Abstr. 1962 (5) 1351

J. G. Hunt and R. B. Russell (Nuclear Metals, Inc.)
Texture in Hot-extruded BeO
J. Nuclear Materials 6 (5-6) 142-3 (1962)
Nucl. Sci. Abstr. 1962 (10) 3377
Ceram. Abstr. 1963 (1) 30

Metallgesellschaft Aktiengesellschaft
A Method of Producing Completely Encased Bodies on an Extrusion
Press

Brit. Patent 892,471 (3/28/62)
Nucl. Sci. Abstr. 1962 (8) 2591

Commissariat a l'Energie Atomique
Study of Shaping and Irradiation of Uranium Monocarbide
Quarterly Progress Report No. 4 10/1--12/31/61 (1/8/62)
Contract 012-60-5RDF
A translation of CEA-3748
Nucl. Sci. Abstr. 1962 (8) 2734

W. B. Tarpley and H. Kartluke (Aeroprojects, Inc.)
Ultrasonic Tube Drawing: Niobium, Zircaloy-2, and Copper
Contract No. AT(30-1)-1836 Task 2 (12/61)

Commissariat a l'Energie Atomique
Extrusion Process and Apparatus Therefor
British Patent 899,453 (6/20/62)
Nucl. Sci. Abstr. 1962 (8) 2735

Commissariat a l'Energie Atomique
Study of the Shaping and the Irradiation of Uranium Monocarbide
Quarterly Progress Report No. 3 6/15--9/15/61 (10/10/61)
Contract 012-60-5RDF
Nucl. Sci. Abstr. 1962 (8) 2734

L. Meny, J. Buffet, and C. Sauve
Application of Extrusion Sintering of Powders to the Fabrication
of Dispersion-type Elements of U-Al and UO₂ Stainless Steel
Plansee Proceedings. 4th Seminar, Reutte/Tyrol, 1961 566-99 (1962)
Ceram. Abstr. 1962 (10) 239

T. H. Hazlett (Inst. Eng. Res., Univ. of Calif.)
Investigation of Ductile Ceramics
Final Report (3/62)

E. R. Parker, J. A. Pask, and J. Washburn (Univ. of Calif.
Materials Research Lab.)
Contract AF49(638)-601 (8/62)
Nucl. Sci. Abstr. 1963 (6) 2445

W. C. Belvel (Univ. of Calif.)
Flexural Behavior of Polycrystalline Lithium Fluoride from Room
Temperature to 300°C
M. S. Thesis (1962)

National Research Council. Materials Advisory Board
State of the Art on Forging and Extrusion
Progress Report No. 4 (5/14/62)
Nucl. Sci. Abstr. 1962 (10) 3369

F23h. HOT SWAGING

E. A. Evans (General Electric Co.)
Fabrication and Enclosure of Uranium Dioxide
Fuel Elements Conference, Paris 11/18-23/57 414-31
Nucl. Sci. Abstr. 1958 () 1096

D. R. Stenquist and R. J. Anicetti (General Electric Co.)
Fabrication of Ceramic Fuel Elements by Swaging
Am. Inst. Mining Met. Petrol. Engrs., Inst. Metals Div., Spec.
Rept. Ser. 5, No. 7, 1-12 (1958)
Nucl. Sci. Abstr. 1959 (8) 1821

J. E. Brown
Swage Compaction of Ceramics
Ceram. Age 75 (1) 20-23 (1960)
Ceram. Abstr. 1962 (3) 69

J. J. Finley, M. Korchynsky, and S. Sarian (Union Carbide Co.)
Columbium Alloy Clad Uranium Carbide Fuel Element
Final Report 5/1/59--4/30/60 (9/1/60)
Metals Research Labs. Technical Report 60-46
Contract AT(40-1)-2559
Nucl. Sci. Abstr. 1961 (10) 3430

Societe Belge pour l'Industrie Nucleaire
Plutonium Used as a Fuel in Nuclear Reactors
Quarterly Report No. 3 1-3/61
Contract 027-60-7RDB
Nucl. Sci. Abstr. 1962 (5) 1636

Centre d'Etude de l'Energie Nucleaire and Societe Belge pour l'Industrie Nucleaire
UO₂ Compaction by Swaging
Contract 027-60-7RDB (11/30/61)
Nucl. Sci. Abstr. 1962 (11) 4043

FIAT. Sezione Energia Nucleare, Turin
Swaging of Uranium Dioxide
Quarterly Report No. 3 11/1/60--3/31/61 (4/30/61)
Contract 013-60-5RDI
Nucl. Sci. Abstr. 1962 (6) 1958

E. A. Lees (General Electric Co.)
Fabrication of Fuel Elements by Swaging
Contract AT(04-3)-361 (5/21/62)
Nucl. Sci. Abstr. 1963 (6) 2442

F. Hofmann and B. Liebmann (Nuklear-Chemie und-Metallurgie G.m.b.H.)
Hot Swaging of Uranium Oxide Fuel Elements
Quarterly Report No. 2 8/1/60--10/31/60
Contract 011-60-5RDA
Nucl. Sci. Abstr. 1962 (8) 2511

F. Hofmann and B. Liebmann (Nuklear-Chemie und-Metallurgie G.
m.b.H.)
Fabrication of Oxide-based Fuel Elements by Swaging
Quarterly Progress Report No. 3 1/1/61--3/31/61 (on) Hot Swaging
of Uranium Oxide Fuel Elements
Appendix 2 to Letter of 5/17/61 to Euratom
Contract 011-60-5RDA
Nucl. Sci. Abstr. 1962 (8) 2512

Nuklear-Chemie und-Metallurgie G.m.b.H.
Fabrication of Swaged UO_2 Fuel Elements
Quarterly Progress Report No. 6 10/61--12/61
EURAEK-238
Nucl. Sci. Abstr. 1962 (11) 3932

Nuklear-Chemie und-Metallurgie G.m.b.H.
Formation of Swaged UO_2 Fuel Elements
Final Report 4/1/60--6/30/61
Contract 011-60-5RDA
Nucl. Sci. Abstr. 1963 (5) 2164

P. Himmelstein, F. Hofmann, H. Kroll, B. Liebmann, and O. Neumann
(Nuklear-Chemie und-Metallurgie G.m.b.H.)
Fabrication of Swaged Fuel Elements
Quarterly Report No. 8 4/1/62--6/30/62
Contract 062-61-7RDD
Nucl. Sci. Abstr. 1963 (3) 860

F. Hofman, H. Kroll, and B. Liebmann (Nuklear-Chemie und-Metallurgie G.m.b.H.)

Fuel Element Fabrication by Cold and Hot Swaging of Specially Prepared UO_2 -Powders

CEND-153 Vol. 1 125-35

Nucl. Sci. Abstr. 1963 (4) 1449

Mitsubishi Atomic Power Industries, Inc.

Method of Preparing Hollow Type High Density Ceramic Nuclear Fuel Elements

Brit. Patent 915,438 (1/9/63)

Nucl. Sci. Abstr. 1963 (3) 1141

F23k. "WARM" PRESSING

R. Scott and J. Williams
Warm Pressing (8000C.) of UO_2 and UO_2 -Metal Mixtures
Trans. Brit. Ceram. Soc. 57 (4) 199-209 (1958)
Ceram. Abstr. 1960 (4) 89

J. Williams (United Kingdom Atomic Energy Authority of Patents
Branch)
Method of Making Uranium-Uranium Monocarbide Cermet
U. S. Patent 2,965,480 (12/20/60)
Ceram. Abstr. 1961 (4) 91

E. J. Felten
Hot-pressing of Alumina Powders at Low Temperatures
J. Am. Ceram. Soc. 44 (8) 381-85 (1961)
Ceram. Abstr. 1961 (10) 253

D. I. Sinizer (Atomics International. Div. of North American
Aviation, Inc.)
Progress in Uranium Carbide Technology at Atomics International
TID-7603 4-11
Nucl. Sci. Abstr. 1961 (8) 2568

W. V. Doeddel and M. T. Simnad (USA-AEC)
Method of Making Fuel Bodies
U. S. Patent 3,301,389 (4/24/62)
Nucl. Sci. Abstr. 1963 (6) 1749

F23n. HOT PRESSING. ATMOSPHERIC AND GENERAL (PRESSURE SINTERING)

A. U. Seybolt, R. M. Linsmayer, and J. P. Frandsen (Knolls Atomic Power Lab.)

The Kapl Beryllium Hot Pressing Process I. The Method

Contract W-31-109-Eng-52 (12/13/48)

Changed from Official Use Only 8/30/56

Nucl. Sci. Abstr. 1957 (2) 271

H. H. Hirsch (Knolls Atomic Power Lab.)

A Powder Metallurgy Technique for Combining Insoluble Materials as Applied to Al-UO₂ Fuel Elements

Proceedings of the Metallurgy and Materials Information Meeting

4/16/51, Oak Ridge Vol. 1 527-37

Nucl. Sci. Abstr. 1958 () 2139

J. W. Knowlton (Norton Co.)

Mold and Method for Molding Refractory Materials

Can. 481,848 (3/18/52)

Ceram. Abstr. 1953 (2) 27

G. E. Comstock III (Norton Co.)

Molded Alumina

U. S. 2,618,567 (11/18/52)

Ceram. Abstr. 1953 (2) 27

E. C. Railton, A. R. Hall and W. Watt

Ceramics and Glass: 9, Experiments on the Hot Pressing of Zirconium

Carbide Powder at 20000°C

Selected Govt. Research Repts. (Gt. Brit.) 10 57-69 (1952)

Ceram. Abstr. 1953 (4) 66

H. M. McCullough and J. L. Zambrow (Sylvania Electric Products, Inc.)

Equipment and Procedures for Hot-pressing Uranium and Uranium Hydride Powders

Contract AT-30-1-Gen-366 (4/1953)

Nucl. Sci. Abstr. 1957 (11) 1380

J. E. Comeforo, R. A. Hatch, R. A. Humphrey, and W. Eitel

Synthetic Mica Investigations: I, Hot-pressed Machinable Ceramic Dielectric

J. Am. Ceram. Soc. 36 (9) 286-94 (1953)

Ceram. Abstr. 1953 (10) 178

P. Murray, E. P. Rodgers, and A. E. Williams
Practical and Theoretical Aspects of the Hot Pressing of Refractory
Oxides
Trans. Brit. Ceram. Soc. 53 (8) 474-510 (1954)
Ceram. Abstr. 1960 (1) 8

P. Murray, L. Denton, and D. Wilkinson
Slip Casting, Sintering, and Hot Pressing of Beryllia
Silicates Ind. 19 (12) 412-17 (1954)
Ceram. Abstr. 1955 (9) 162

D. H. Schell, J. M. Taub, and D. T. Doll (Los Alamos Scientific
Lab.)
Fabrication of Lithium Hydride by Hot-pressing
Contract W-7405-eng-36 (6/1/44)
Nucl. Sci. Abstr. 1958 () 1243

R. A. Alliegro, L. B. Coffin, and J. R. Tinklepaugh
Pressure-sintered Silicon Carbide
J. Am. Ceram. Soc. 39 (11) 386-89 (1956)
Ceram. Abstr. 1957 (1) 11

B. Bovarnick
Preparing Ceramic Tool Material
Ceramic Abstr. 1957 (2) 39

C. A. Bielawski, T. M. Harkulich, and R. E. Long (Brush Beryllium
Co.)
A Study of Hot Pressing of Beryllia Rocket Nozzles
6/56--11/56
Contract AF33(616)-56223
Nucl. Sci. Abstr. 1957 (8) 981

J. E. Comeforo and T. S. Stanislaw
How Ceramics Can Be Shaped to Precision Tolerances: I
Ceram. Abstr. 1957 (7) 139

University of California, Livermore. Radiation Lab.
Die Design for Hot Presses
Contract W-7405-eng-48 (4/19/57)
Nucl. Sci. Abstr. 1958 () 1058

R. R. Van Der Beck, A. W. von Mickwotz, and L. G. Scheinman
How Oxide Cutting Tools Are Made and What They Do
Ceram. Ind. 69 (6) 113-15, 128-31 (1957)
Ceram. Abstr. 1958 (6) 137

P. Murray
Hot Pressing of Ceramics with Particular Reference to Beryllia
Ceram. Abstr. 1957 (9) 223

E. Barnes and P. Murray
Sintering and Hot Pressing of Uranium Tetrafluoride
J. Am. Ceram. Soc. 41 (7) 246-48 (1958)
Ceram. Abstr. 1958 (8) 217

J. K. Evans and G. D. Kriebel (Beryllium Corp.)
Hot Pressing of Beryllia Rocket Nozzles
7/56--1/57
Contract AF33(616)-3699
Nucl. Sci. Abstr. 1957 (10) 1158

Pratt and Whitney Aircraft Div., United Aircraft Corp.
Summary Progress Report on an Investigation of the Manufacture
of High-Density Beryllium Oxide Parts by the Brush Beryllium
Company

4/5/57
Contracts AF33(038)-27340 and AT(11-1)-229
Nucl. Sci. Abstr. 1957 (7) 774

K. M. Taylor (Carborundum Co.)
Method of Making Molded Boron Nitride Bodies
U. S. 2,808,314 (10/1/57)
Ceram. Abstr. 1958 (2) 48

K. M. Taylor (Carborundum Co.)
Methods for Making Boron Nitride Materials
U. S. 3,058,809 (10/16/62)
Ceram. Abstr. 1963 (2) 46

G. H. Fetterley and G. R. Watson (Norton Co.)
Process of Molding Boron Carbide and Boron
U. S. 2,806,799 (9/17/57)
Ceram. Abstr. 1958 (1) 2

R. Caillat and R. Pointud (Centre d'Etudes nucleaires)
Sintering Under Pressure of Alumina and Beryllia
Rev. met. 54 No. 4 277-82 (1957)
Nucl. Sci. Abstr. 1958 () 1352

V. Y. Riskin and V. V. Goncharov
Research on the Pressing of Refractories at High Temperatures
Ogneupory 22 (4) 186-88 (1957)
Ceram. Abstr. 1960 (9) 211

D. T. Livey, P. Murray, and J. Williams
The Hot Pressing of Ceramics
Ceramic Fabrication Processes: The Technology Press of Mass. Institute of Technology and John Wiley & Sons, Inc. 147-71 (1958)

H. H. Hausner (USA-AEC)
Hot Pressing with a Temperature Gradient
U. S. 2,835,573 (5/20/58)
Ceram. Abstr. 1958 (9) 245
Nucl. Sci. Abstr. 1958 () 1728

S. A. Tsukerman
Powder Metallurgy
Translated from Poroshkovaya Metallurgiya: Publishing House of the Academy of Science, Moscow. 89-96, 125-36, 154-7 (1958)
Nucl. Sci. Abstr. 1961 (6) 2066

P. S. Hessinger (Mycalex Cor. of America)
Ceramoplastic and Method of Manufacture
U. S. 2,897,573 (8/4/59)
Ceram. Abstr. 1960 (1) 13

J. P. Livingston (USA-AEC)
Spherical Die
U. S. Patent 2,870,484 (1/27/59)
Nucl. Sci. Abstr. 1959 (8) 1832

I. S. Kainarskii, I. G. Orlova, and E. V. Merkulova
Pressing Graphite and Silicon Carbide Refractories in the Thermo-plastic State
Ogneupory 24 (4) 173-80 (1959)
Ceram. Abstr. 1961 (3) 61

- I. Denton and P. Murray
 Note on Grain Growth in Fabricated Beryllia
 Trans. Brit. Ceram. Soc. 58 (1) 35-39 (1959)
 Ceram. Abstr. 1960 (11) 258
- V. S. Neshpor and P. S. Kislyi
 Hot Pressing of Powdered Chromium Boride and Some Properties of
 the Sintered Material
 Ogneupory 24 (5) 231-36 (1959)
 Ceram. Abstr. 1961 (3) 61
- R. Pointud, C. Rispal, and M. Le Garec
 Manufacture of Sintered Bricks of High Density from Beryllium
 Oxide
 Silicates Inds. No. 2 (1959)
 Nucl. Sci. Abstr. 1961 (5) 1480
- M. Sakata
 Hot-press Sintering of Precious Metals and Glass Beads
 Proc. Fujihara Mem. Fac. Eng. Keio Univ. 12 (45) 14-44 (1959)
 Ceram. Abstr. 1961 (5) 130
- T. Sata and R. Kiyoura
 Fabrication of Cermets of the System Alumina-chromium by Hot Pressing
 Yogyo Kyokai Shi 67 (760) 116-23 (1959)
 Ceram. Abstr. 1960 (6) 138
- R. K. Francis, J. J. Swica, et al.
 Hot Pressing of Fine Grained Ceramic Oxides for Use in Thermal
 Conductivity Studies
 P. B. Rept. 161851
 U. S. Govt. Research Repts. 34 (4) 447 (1960)
 Ceram. Abstr. 1962 (5) 116
- W. B. Wilson (USA-AEC)
 High Pressure Dies
 U. S. 2,938,998 (5/31/60)
 Ceram. Abstr. 1960 (10) 239

J. B. Huffadine
The Fabrication and Properties of Molybdenum Disilicide and Molybdenum Disilicide-Alumina
Special Ceramics: Heywood 220 (1960)

G. E. Mangsen, W. A. Lambertson, and B. Best
Hot Pressing of Aluminum Oxide
J. Am. Ceram. Soc. 43 (2) 55-59 (1960)
Ceram. Abstr. 1960 (3) 75

N. J. Kreidl, H. C. Hafner, et. al
Fabrication of Infrared Transmitting Materials by Hot-pressing Techniques
P. B. Rept. 150149
U. S. Govt. Research Repts. 34 (5) 598 (1960)
Ceram. Abstr. 1962 (3) 57

K. D. Reeve and E. J. Ramm (Australia Atomic Energy Commission Research Establishment)
The Preparation of a Set of BeO-based Fuel Element Specimens for the H.T.G.C. Irradiation Programme
10/60
Nucl. Sci. Abstr. 1961 (7) 2383

A. Blainey
Hot Pressing Powders in England
Metal Progr. 77 (1) 104-8, 178, 180, 190, 192 (1960)
Ceram. Abstr. 1960 (7) 160

L. B. Alden and F. P. Holloway (Union Carbide Corp.)
Improved Method for Pressure Baking of Carbon Articles
U. S. 2,965,931 (12/27/60)
Ceram. Abstr. 1961 (5) 120

W. A. Sanders and S. J. Grisaffe
Hot-pressing of Hafnium Carbide (Melting Point, 7030°F.)
NASA Tech. Note, D-303 (1960)
Ceram. Abstr. 1961 (9) 213

T. S. Kainarskii, E. V. Degtyareva, and V. A. Kukhtenke
Hot-pressed Super-dense Silicon Carbide Products
Ogneupory 25 362 (1960)
Brit. Ceram. Abstr. 1961 (7) 279A

T. Vasilos
Hot Pressing of Fused Silica
J. Am. Ceram. Soc. 43 (10) 517-19 (1960)
Ceram. Abstr. 1960 (11) 270

J. S. Jackson and P. F. Palmer
Hot Pressing Refractory Hard Materials
Special Ceramics: Academic Press Inc. 305-28 (1960)
Nucl. Sci. Abstr. 1962 (8) 2507
Chem. Abstr. 56 4385

G. V. Sansonov, G. A. Yasinskaya, T. Shou-Vei
Crucibles Made from Refractory Carbides, Borides, and Nitrides
Ogneupory 25 (1) 35-38 (1960)
Ceram. Abstr. 1962 (4) 88

M. Nacken, S. Scholz, and B. Letsmacher
The Kinetics of Pressure Sintering of Tantalum Carbide
Arch. Eisenhuettenw. 33 635-41 (1962)
Chem. Abstr. 58 4280

M. Nacken, S. Scholz, and B. Letsmacher
A Note on the Hot-pressing of Tantalum Carbides
Ber. Dtsch. Keram. Ges. 39 137 (1962)
Brit. Ceram. Abstr. 1962 (9) 272A

British Aluminum Co. Ltd.
Hot-pressing Process
Brit. Patent 877,409 (9/13/61)
Brit. Ceram. Abstr. 1962 (4) 112A

W. B. Crandall, D. H. Chung, and T. J. Gray
The Mechanical Properties of Ultra-fine Hot-pressed Alumina
Mechanical Props. of Engng. Ceramics: Intersci. Publ. 349 (1961)
Brit. Ceram. Abstr. 1962 (6) 179A

W. B. Tarpley and H. Kartluke (Aeroprojects, Inc.)
Ultrasonic Hot Pressing of Metals and Ceramics
Contract AT(30-1)-1836 (12/61)
Nucl. Sci. Abstr. 1962 (5) 1349

J. D. McClelland, J. H. Richardson, and L. R. Franklin (Atomics International Div. of North American Aviation, Inc.)
Fabrication and Properties of Translucent Beryllium Oxide
Contract AT(11-1)-GEN-8 (10/30/61)
Nucl. Sci. Abstr. 1962 (2) 564

J. D. McClelland and W. M. Smith (Atomics International Div. of North American Aviation, Inc.)
Research Hot Pressing
Contract AT(11-1)-GEN-8 (10/30/61)
Nucl. Sci. Abstr. 1963 (1) 63
Ceram. Abstr. 1962 (9) 220

E. H. Zehms and J. D. McClelland (Atomics International)
Semi-continuous Hot Pressing
Am. Ceram. Soc. Bull. 42 (1) 10-12 (1963)
Nucl. Sci. Abstr. 1963 (3) 1139

S. C. Carniglia and J. E. Hove (Atomics International)
Fabrication and Properties of Dense Beryllium Oxide
J. Nuclear Materials 4 (7) 165-76 (1961)
Nucl. Sci. Abstr. 1961 (12) 4023

A. Bisson and H. Frisby (Centre d'Etudes Nucleaires)
Electron Microscope Observations of Porosity Inclusions of Carbon,
and Dislocations in Beryllium Oxide Sintered Under Pressure
J. Nuclear Materials 4 (7) 133-42 (1961)
Nucl. Sci. Abstr. 1962 (12) 4023

D. Weiss and W. J. Knapp
Hot-pressing a Simple Petalite-clay Body
Am. Ceram. Soc. Bull. 40 (2) 66-7 (1961)
Ceram. Abstr. 1961 (4) 96

J. S. Jackson (Associated Electrical Industries, Ltd.)
Hot Pressing High-temperature Compounds
Powder Met. No. 8 73-100 (1961)
Nucl. Sci. Abstr. 1962 (3) 724

Compagnie Industrielle des Combustibles Atomiques Frittes
Uranium Dioxide Shaping
Appendix 2 of Sintered Uranium Oxide: Sintering Technique and
Behavior under Irradiation
Quarterly Report No. 2 (1961)
Nucl. Sci. Abstr. 1962 (9) 3179

C. G. Rhodes (Atomics International)
Microstructural Investigation of Hot Pressed Uranium Carbides
Using Extremely High Pressures
1/16/61
Nucl. Sci. Abstr. 1961 (8) 2734

W. Chubb and F. A. Rough (Battelle Memorial Inst.)
Research on Uranium Carbide and Uranium Carbide-base Fuel Materials
at Battelle Memorial Institute
Nucl. Sci. Abstr. 1961 (8) 2568

R. H. Baskey (Clevite Corp. Mechanical Research Div.)
Fuel-bearing Fiberglass in Aluminum Base Fuel Elements
Monthly Progress Letter No. 24 8/1/61--8/31/61 (9/14/61)
Nucl. Sci. Abstr. 1961 (12) 4193

A. Accary (France Commissariat a l'Energie Atomique)
Advances in Uranium Carbide Technology in France
Nucl. Sci. Abstr. 1961 (8) 2570

P. Popper and T. A. Ingles (British Ceramic Research Ass.)
Hot-pressed Boron Nitride
Brit. Patent 887,658 (1/24/62)
Brit. Ceram. Abstr. 1962 (7) 215A

C. Eyraud, C. Daneyrolle, M. Chevreton, G. Thomas, P. Plurien,
and D. Massignon (Commissariat a l'Energie Atomique)
Process for Manufacturing Compact or Fine-pored Metallic Compo-
sitions from Particulate Metals
Brit. Patent 889,427 (2/14/62)
Nucl. Sci. Abstr. 1962 (5) 1344

R. H. Dungan (Minneapolis-Honeywell Regulator Co.)
Molding Method for Ceramics
U. S. 2,960,747 (11/22/60)
Ceram. Abstr. 1961 (3) 63

Brandmayr, Brown, Di Vita, and Fischer (USA Secretary of the Army)
Method of Hot Pressing Ceramic Ferroelectric Materials
U. S. Patent 2,990,602 (7/4/61)
Ceram. Abstr. 1962 (1) 16

Massachusetts Inst. of Tech.
Progress Report No. 30 On Insulation
Contracts Nonr-1841(10); AF33(616)-8353; AF19(604)-8493; AF19(604)-
6155 (1/62)
Nucl. Sci. Abstr. 1962 (6) 1954

R. E. Jaeger and L. Egerton
Hot Pressing of Potassium-sodium Niobates
J. Am. Ceram. Soc. 45 (5) 209-13 (1962)
Ceram. Abstr. 1962 (6) 144

G. L. Vincent
Gulton Pioneers Size Ceramic Capacitors
Ceramic Industry 78 (4) 1962

G. N. Howatt (Hulton Industries Inc.)
Ceramic Components and Method of Making Same
U. S. Patent 3,054,035 (9/11/62)
Brit. Ceram. Abstr. 1963 (3) 80A

A. J. Mountvala
Hot-pressing Piezoelectric and Ferroelectric Materials
Am. Ceram. Soc. Bull. 42 (3) 120-1 (1963)
Ceram. Abstr. 1963 (4) 105

I. S. Kainarskii, I. G. Orlova, and E. V. Merkulova
Properties of Thermopressed Refractories Based on Clays and Kaolins
Sb. Nauchn. Tr. Ukr. Nauchn. Issled. Inst. Ogneuporov No. 5 79-91
(1961)
Chem. Abstr. 57 14728

J. S. O'Neill and D. T. Livey (United Kingdom Atomic Energy Authority)
Improvements In or Relation To Moulds for Hot Pressing Powdered Materials

Brit. Patent 878,088 (9/27/61)
Nucl. Sci. Abstr. 1961 (12) 4013

K. D. Reeve and E. J. Ramm
A Comparative Study of Two Grades of BeO
Australia Atomic Energy Commission Research Establishment (11/61)
Nucl. Sci. Abstr. 1962 (4) 118

Deutsche Edelstahlwerke A. G.
A New Type of Hot-pressing Die
Brit. Patent 899,915 (6/27/62)
Brit. Ceram. Abstr. 1963 (2) 43A

J. D. McClelland (Aerospace Corp.)
Advanced Techniques in Hot Pressing
Presented at 64th ACS
Am. Ceram. Soc. Bull. 41 (4) 1962

R. M. Spriggs, L. A. Brissette, M. Rossetti, and T. Vasilos
Hot Pressing of Ceramics in Alumina Dies
Presented at 64th ACS
Am. Ceram. Soc. Bull. 41 (4) 1962

W. B. Tarpley and H. Kartluke (Aeroprojects Inc.)
Ultrasonic Hot Pressing of Metals and Ceramics
Presented at 64th ACS
Am. Ceram. Soc. Bull. 41 (4) 1962

K. Langrod (Atomics International)
Fabrication of Ceramic Internal Reflector for the Snap's Experimental Reactor
Contract AT(11-1)-GEN-8 (7/15/62)
Nucl. Sci. Abstr. 1962 (10) 3369

R. J. Schafer, M. Quatinete, and J. W. Weeton (NASA)
Some Effects of Variation of Hot-pressing Temperature upon the Agglomeration of MgO in a Dispersion Strengthened Nickel-MgO Alloy
NASA Tech. Note D-1167 (1962)
Ceram. Abstr. 1962 (9) 213

F23p. HOT PRESSING IN VACUUM

R. Takagi and K. Tamura
Vacuum Hot Pressing of MoSi_2
Nippon Knizoku Gakkasishi 21 169-72 (1957)
Chem. Abstr. 1962 (4) 7009

R. M. Fulrath
Internal Stresses in Model Ceramic Systems
J. Am. Ceram. Soc. 42 (9) 423-9 (1959)
Ceram. Abstr. 1959 (10) 276

Systems Research Labs., Inc.
The Electrical Behavior of Refractory Oxides
Bi-monthly Progress Report 3/21/61
Contract AF33(616)-7748
Nucl. Sci. Abstr. 1961 (12) 4195

K. Kida, S. Nishigaki, and R. Ueda
Study on the Fabrication of the BeO-UO_2 Sintered Body by Means
of Vacuum Hot Pressing
J. Atomic Energy Soc. Japan 3 (3) 200-7 (1961)
Nucl. Sci. Abstr. 1961 () 2388

K. Kida, S. Nishigaki, and R. Ueda
A Study of the Fabrication of BeO-UO_2 by Means of Vacuum Hot Pressing
Translated by M. Luyang (United Kingdom Atomic Energy Research
Establishment)
Nippon Genshiryoku Gakkaishi 3 200-7 (1961)
Nucl. Sci. Abstr. 1963 (1) 64

K. G. Wikle and V. C. Potter (Brush Beryllium Co.)
Beryllium Processing by Powder Metallurgy
J. Metals 13 (8) 537-44 (1961)
Nucl. Sci. Abstr. 1961 (10) 3432

D. A. Mannas and J. P. Smith (General Electric Co.)
Beryllium Intermetallic Compounds--Their Preparation and Fabrication
J. Metals 14 (8) 575-8 (1962)
Nucl. Sci. Abstr. 1962 (10) 3612

E. W. Hoyt (General Electric Co.)
Vacuum Hot Pressing of Refractory Materials
Transactions of the Eighth National Vacuum Symposium Combined with
the Second International Congress on Vacuum Science and Technology: Pergamon Press Vol. 2 788-90 (1962)
Nucl. Sci. Abstr. 1962 (12) 4181

J. Molinari (Nucl. Studies Lab., Saclay, France)
Solid-state Preparation of Massive Uranium Mononitride from Mixed
Powders of Uranium and Its Higher Nitrides
Comm. Energie At. Rappt. No. 2103 (1962)
Chem. Abstr. 1962 (7)

E. G. Wolff
Laboratory Vacuum Hot Press to 2500°C.
Powder Metallurgy Spring 93 (1963)

F23q. HOT ISOSTATIC PRESSING (PRESSURE BONDING)

- M. J. Whitman (USA-AEC)
Exploratory Fuel Element Research
Fuel Element Fabrication with Special Emphasis on Cladding Materials:
Academic Press Vol. 2 287-300 (1961)
Nucl. Sci. Abstr. 1961 (10) 3252
- S. J. Paprocki, E. S. Hodge, and C. B. Boyer (Battelle Memorial
Inst.)
Preparation of Reactor Components by a Gas-pressure Bonding
Technique
Nucl. Sci. Abstr. 1958 () 1816
- S. J. Paprocki, E. S. Hodge, and D. C. Carmichael (Battelle
Memorial Inst.)
Pressure Bonding of Zircaloy-clad Flatplate Uranium-dioxide Fuel
Elements
Am. Inst. Mining Met. Petrol. Engrs., Insts. Metals Div., Spec.
Rept. Ser. 5 No. 7 13-24 (1958)
Nucl. Sci. Abstr. 1959 (8) 1821
- W. Cunningham, D. E. Kizer, and S. J. Paprocki (Battelle Memorial
Inst.)
Cermet Fuel Elements
Powder Metallurgy in the Nuclear Age. Fourth Plansee Seminar
6/20-24/61
Reutte/Tyrol, Metallwerk Plansee A. G. 483-506 (1962)
Nucl. Sci. Abstr. 1962 (11) 3841
- E. S. Hodge, C. B. Boyer, and F. D. Orcutt (Battelle Memorial
Inst.)
Gas Pressure Bonding
Ind. Eng. Chem. 54 No. 1 (1) 31-5 (1962)
Nucl. Sci. Abstr. 1962 (7) 2169
- S. J. Paprocki, E. S. Hodge, P. J. Gripshover, and D. C. Carmichael
(Battelle Memorial Inst.)
Fabrication of a Compartmented Flat-plate Ceramic Fuel Element
Fuel Element Fabrication with Special Emphasis on Cladding Materials:
Academic Press Vol. 1 283-300 (1961)
Nucl. Sci. Abstr. 1961 (9) 3081

D. L. Keller, J. M. Fackelmann, E. O. Speidel, and S. J. Paprocki
(Battelle Memorial Inst.)
Powder Metallurgy of Uranium Carbide and Uranium Nitride
Powder Metallurgy in the Nuclear Age. Plansee Proceedings 1961
Reutte/Tyrol, Metallwerk Plansee AG. 304-28 (1962)
Nucl. Sci. Abstr. 1963 (1) 258

S. J. Paprocki, E. S. Hodge, and P. J. Gripshover (Battelle
Memorial Inst.)
Gas-pressure Bonding
Contract AF33(616)-7747 (9/25/61)
Nucl. Sci. Abstr. 1961 (12) 4192

S. J. Paprocki (Battelle Memorial Inst.)
Progress on the Use of Gas-pressure Bonding for Fabricating Low-
cost Ceramic, Cermet, and Dispersion Fuels
Final Report on AEC Fuel-cycle Program (11/24/61)
Contract W-7405-eng-92
Nucl. Sci. Abstr. 1962 (2) 563

S. J. Paprocki, D. L. Keller, and W. M. Pardue (Battelle Memorial
Inst.)
Study of Experimental Fuel Bodies Made From Alumina-coated UO₂
Particles
Contract W-7405-eng-92 (7/16/62)
Nucl. Sci. Abstr. 1962 (10) 3371

G. W. Cunningham (Battelle Memorial Inst.)
Recent Developments in Reactor Materials from Powders
Reactor Materials 6 No. 1 1-18
Nucl. Sci. Abstr. 1963 (5) 2273

I. Sheinhart and J. Fugardi (Sylvania-Corning Nuclear Corp.)
Isostatic Pressing of UO₂ in High Temperature Metals
Contract AT-30-1-GEN-366 (9/60)
Nucl. Sci. Abstr. 1961 (4) 993

I. Sheinhart and J. Fugardi (Sylvania-Corning Nuclear Corp.)
Ceramic Fuel Elements Made by Hot Isostatic Pressing
Contract AT-30-1-GEN-366 (9/60)
Nucl. Sci. Abstr. 1961 (7) 2387

I. Sheinhart (Sylvania Electric Products Inc.)
The Fabrication of Beryllium by Hot Isostatic Pressing and by
Impact Extrusion
For General Nuclear Engineering Corp. (9/61)
Contract AT(38-1)-200 Subcontract 40-9-11
Nucl. Sci. Abstr. 1961 (12) 4193

Westinghouse Electric Corp.
Pressurized Water Reactor (PWR) Project Technical Progress Report
2/24/59--4/23/59
Contract AT-11-1-GEN-14
Nucl. Sci. Abstr. 1959 (8) 1889

F23r. RHEOLOGY OF HOT FORMING.
RESPONSE OF MATERIALS

M. S. Kovaltchenko and G. V. Samsonov
Certain Rules in Fritting Refractory Compounds with Compression
at High Temperature
Izvest. Akad. Nauk SSSR Ser. Tekh. Met. 4 143-7 (1959)
Nucl. Sci. Abstr. 1961 (11) 3614

J. D. McClelland (Atomics International)
Kinetics of Hot Pressing
Powder Metallurgy: Academic Press 157-71 (1961)
Nucl. Sci. Abstr. 1961 (9) 3083

J. D. McClelland and E. H. Zehms
End-point Density of Hot-pressed Alumina
J. Am. Ceram. Soc. 46 (2) 77-80 (1963)
Ceram. Abstr. 1963 (4) 13

M. S. Koval'chenko and G. V. Samsonov
Viscous Flow in Sintering of Zirconium Boride by Hot Pressing
Poroshkovaya Met. No. 5 (9) 3-9 (1961)
Nucl. Sci. Abstr. 1962 (5) 1555

M. S. Koval'chenko and G. V. Samsonov
Application of the Viscous Flow Theory to the Sintering of Powders
by Hot Pressing
Poroshkovaya Met., Akad. Nauk Ukr. SSR 1 No. 2 3-13 (1961)
Chem. Abstr. 55 26923 (1962)

G. V. Samsonov and M. S. Koval'chenko
Some Features of Sintering of Powders Consisting of Refractory
Compounds
Poroshkovaya Met., Akad. Nauk Kr. SSR 1 No. 1 20-9 (1961)
Chem. Abstr. 1961 25661

M. Y. Balshin and A. Trofimova
Sintering Under Pressure
Poroshkovaya Met., Akad. Nauk Ukr. SSR. 1 82-91 (1961)
Chem. Abstr. 55 25652

R. G. Carlson (Univ. of Cincinnati)
Hot-press Sintering Kinetics of Metal Powders
Thesis (1962)
Nucl. Sci. Abstr. 1963 (3) 1140

F25. VAPOR FORMING

H. W. Schultz

Chemicals in Metallurgy: Vapor-phase Deposition
Ind. Eng. Chem. 53 48A (1961)

G. B. Andreev, A. S. Deineko, I. Y. Makakhov, P. V. Sorokin, and
A. Y. Taranov (Inst. of Physics and Tech., Academy of Sciences)
Preparation of Thin Al_2O_3 Foils
Pribery i Tekh. Ekspt. 6 No. 6 (11-12) 149-50 (1961)
Nucl. Sci. Abstr. 1962 (5) 1555

A. H. F. Muggleton and F. A. Howe (Atomic Weapons Research Estab-
lishment)
The Preparation of Thin Self Supporting Boron Films
Nuclear Instr. & Methods 13 (9) 211-14 (1961)
Nucl. Sci. Abstr. 1962 (3) 723

R. Bakish, C. A. Gellar, and I. Marinow (Alloyd)
Vapor Phase Metallurgy and Ceramics
J. Metals 14 (10) 770-4 (1962)

J. M. Blocher, Jr. and J. H. Oxley (Battelle Memorial Inst.)
Chemical Vapor Deposition Opens New Horizons in Ceramic Technology
Am. Ceram. Soc. Bull. 41 (2) 81-4 (1962)
Nucl. Sci. Abstr. 1962 (4) 1177

J. M. Blocher, Jr., M. F. Browning, A. C. Secrest, V. M. Secrest,
and J. H. Oxley (Battelle Memorial Inst.)
Nuclear-fuel Particles, Preparation of Ceramic-coated
Nuclear. Sci. Abstr. 1962 (10) 3457

R. G. Bourdeau (High Temperature Materials, Inc.)
New Pyrolytic Materials
Materials in Design Eng. 56 (8) 106-9 (1962)
Nucl. Sci. Abstr. 1962 (10) 3618

W. van Lierde, R. Strumane, E. Smets, and S. Amelinckx
Preparation of Uranium Oxide Single Crystals by Sublimation
J. Nucl. Mater. 5 (2) 250-3 (1962)
Ceram. Abstr. 1963 (1) 29

E. K. Muller, B. J. Nicholson, and M. H. Francombe
The Vapor Deposition of $BaTiO_3$ by a Grain-by-Grain Evaporation
Method
Electrochemical Technology 1 (5-6) 158 (1963)

F26. FORMING FROM FILMS, FILAMENTS, OR WHISKERS

E. H. B. Nystrom and B. W. Collin (AB Statens Skogsindustrier)
Mineral Wool
Swed. 145,612 (8/7/50)
Ceram. Abstr. 1955 (5) 89

G. Slayter (Owens-Corning Fiberglas Corp.)
Apparatus for Forming Glass Fiber Mats
U. S. 2,653,416 (9/29/53)
Ceram. Abstr. 1955 (1) 8

A. M. Shibley (Picatinny Arsenal)
State of the Art--Flake-glass Laminates
Plastec Report-1 (10/60)
Nucl. Sci. Abstr. 1961 (8) 2739

R. H. Baskey and R. D. Johnson (Clevite Corp.)
Fuel-bearing Fiberglas in Aluminum-base Fuel Elements
Summary Report 5/4/60--10/31/60 (12/2/60)
Contract AT(40-1)-2557
Nucl. Sci. Abstr. 1961 (6) 2152

R. H. Baskey (Clevite Corp.)
Fuel-bearing Fiberglas in Aluminum-base Fuel Elements
Monthly Progress Letter No. 19 3/1/61--3/31/63
Contract AT(40-1)-2557
Nucl. Sci. Abstr. 1961 (7) 2387

W. G. Cox and H. L. Crispin
Filament Winding Radomes and Missile Nose Cones
Glass Ind 42 (1) 33, 49-50 (1961)
Ceram. Abstr. 1961 (10) 236

R. H. Baskey (Clevite Corp.)
Fuel-bearing Fiberglas in Aluminum-base Fuel Elements
Monthly Progress Letter No. 24 8/1/61--8/31/61
Contract AT(40-1)-2557
Nucl. Sci. Abstr. 1961 (12) 4193

C. Z. Carroll-Porczynski
Advanced Materials: Chemical Publishing Co., Inc (1962)

W. L. Lachman and J. P. Sterry (H. I. Thompson Fiber Glass Co.)
Ceramic Fibers
Chem. Eng. Progr. 58 (10) 37-41 (1962)
Nucl. Sci. Abstr. 1963 (4) 1644

E. Wainer and A. Cunningham (Horizons, Inc.)
Preparation of Sapphire Fibers
U. S. 3,077,380 (2/12/63)
Ceram. Abstr. 1963 (6) 162

F27. ELECTROFORMING

F. Fahnoe and J. J. Shyne (Vitre Corp. of America)
Method of Forming a High Friction Element
U. S. 2,828,254 (3/25/58)
Ceram. Abstr. 1958 (7) 176

I. S. Kainarskii and K. B. Malinovskii
Electrophoresis as a Method of Forming Fine Ceramics
Steklo i Keram. 15 (4) 26-30 (1958)
Ceram. Abstr. 1958 (9) 244

N. K. Antonevich and E. S. Butyleva
Materials for the Anodes (Formers) in the Electrophoretic Method
of Casting Ceramic Ware
Steklo i Keram. 16 (1) 20-3 (1959)
Ceram. Abstr. 1959 (8) 213

F. Fahnoe and J. J. Shyne (Vitre Corp. of America)
Uranium Dioxide Impregnated Compacts and Method for Making
U. S. 2,938,839 (5/31/60)
Ceram. Abstr. 1960 (10) 235

V. A. Lamb and H. I. Salmon
Electrophoretic Deposits of Barium Titanate
Am. Ceram. Soc. Bull. 41 (11) 781-82 (1962)
Ceram. Abstr. 1963 (1) 19

F. A. Scott (General Electric Co.)
The Electrolytic Growth of Dense Self Supported Uranium Dioxide
Shapes
Final Status Report (10/5/62)
Contract AT(45-1)-1350
Nucl. Sci. Abstr. 1963 (3) 846

F29. GENERAL TREATMENTS OF FORMING METHODS

E. Umblia

Metal-ceramic Materials

Industritidning. Norden 81 (17) 240-5, 252; (18) 260-2, 262;
(19) 272-4, 284 (1953)

Ceram. Abstr. 1954 (7) 126

G. A. Kirkendale (State University of New York)

Textbook for Ceramic Engineers (1954)

Ceram. Abstr. 1957 (6) 154

V. Bodin

Technology of Products of Fired Earth: Gauthier-Villars, Paris
(1956)

Ceram. Abstr. 1960 (1) 25

D. W. Luks

Aluminum Oxide Ceramics

Ceram. Ind. 66 (6) 109-12 (1956)

Ceram. Abstr. 1957 (1) 13

H. J. Karmaus and G. Helm

Developments in Shaping Machines for Clayware

Glas-Email-Keramo-Tech. 6 (10) 345-8; (11) 390-3 (1955)

Ceram. Abstr. 1955 (3) 76

F. Reinhart

Developments in Ceramics During 1956

Glas-Email-Keramo-Tech. 8 (1) 4-11; (2) 42-8 (1957)

Ceram. Abstr. 1957 (10) 261

U. S. Dept. of Commerce, Office of Technical Services

Minutes of Symposium on Ceramic Cutting Tools

PB 111757

Ceram. Abstr. 1957 (2) 39

J. W. Deaderick

High Dielectric Constant Ceramics: I Definition

Ceram. Ind. 68 (2) 81, 83 (1957)

Ceram. Abstr. 1958 (1) 20

W. D. Kingery

Ceramic Fabrication Processes

Mass. Institute of Technology and John Wiley & Sons, Inc. (1958)

Nucl. Sci. Abstr. 1958 () 2129

Ceram. Abstr. 1958 (6) 123

W. D. Jones
 Fundamental Principles of Powder Metallurgy
 Edward Arnold Ltd. (publishers) (1960)
 Nucl. Sci. Abstr. 1961 (12) 4013
 Ceram. Abstr. 1962 (9) 229

E. Ryshkewitch
 Plastic Workability of Oxide Masses
 Oxide Ceramics. Physical Chemistry and Technology: Academic Press
 31-43 (1960)
 Nucl. Sci. Abstr. 1961 (9) 3101

P. Popper
 Special Ceramics
 Heywood (1960)
 Brit. Ceram. Abstr. 1961 (6) 260A

Institut National des Sciences et Techniques Nucleaires, Paris
 and France
 Powder Metallurgy. Principles, Recent Progress of Technology,
 Materials and Applications
 1961
 Nucl. Sci. Abstr. 1963 (4) 1642

W. Leszynski
 Powder Metallurgy--Proceedings of an International Conference, New
 York (1960)
 Interscience Publishers (1961)
 Ceram. Abstr. 1962 (8) 203

Proceedings of the Seventeenth Annual Technical Meeting of the
 Metal Powder Industries Federation, Cleveland, 4/24-26/61
 Progress in Powder Metallurgy. Vol. 17: Metal Powder Industries
 Federation (1961)
 Nucl. Sci. Abstr. 1962 (1) 254

G. W. Cunningham
 Powder Metallurgy--the State of the Art
 Battelle Tech. Rev. 11 No. 8 (8) 3-9 (1962)
 Nucl. Sci. Abstr. 1962 (11) 3846

R. S. Truesdale, B. B. Lympany, E. M. Grala, C. A. Bielawski,
R. M. Paine, and W. W. Beaver (Brush Beryllium Co.)
Investigation of the Effects of Processing Variables and Fabrication Techniques upon the Properties of Intermetallic Compounds
Progress Report No. 4 1/1/61--3/31/61
Technical Report No. 210-229
Contract AF33(616)-7108
Nucl. Sci. Abstr. 1961 (8) 2735

A. J. Stonehouse (Brush Beryllium Co.)
Beryllides for Lightweight, High Temperature Structures
Materials in Design Eng. 55 No. 2 (2) 84-6 (1962)
Nucl. Sci. Abstr. 1962 (4) 1014

F. J. P. Clarke and J. Williams (Atomic Energy Research Establishment)
Reactivity Problems Concerning the Formation of Ceramic Materials
Reactivity of Solids: Elsevier Publishing Co. 593-601 (1961)
Nucl. Sci. Abstr. 1962 (12) 4127

Anon.
Forming
Ceram. Age 78 (10) 67-77 (1962)

J. D. Latva (Wright-Patterson Air Force Base)
Selection and Fabrication of Nonmetallics--Oxides, Beryllides and Silicides
Metal. Progr. 82 No. 5 97-102 (1962)
Chem. Abstr. 58 267 (1962)

J. D. Latva (Wright-Patterson Air Force Base)
Selection and Fabrication of Ceramics and Intermetallics
Metal Progr. 82 No. 4 139-44 (1962)
Chem. Abstr. 1962 (12) 14727

The Carborundum Co.
Advanced Materials Technology
Spring Issue (1963)

H. D. Taylor (Diamonite Products Manufacturing Co.)
Forming Alumina Ceramics
Ceram. Age 12 (7) 76-81 (1963)

B. E. Waye
Technical Ceramics: 4. Further Consideration of Shaping Methods
Ceramics 14 (169) 19 (1963)

F. Clark
Consolidation of Metal Powders
Advanced Techniques in Powder Metallurgy: Rowman and Littlefield,
Inc. 48-79 (1963)

F29. FORMING GENERAL, NUCLEAR FUELS

P. Murray

Ceramics and Atomic Energy

Claycraft 26 (1) 2-7 (1952); (5) 210-16 (1953)

Ceram. Abstr. 1953 (6) 121

Z. M. Shapiro (Westinghouse Electric Corp.)

Resume of Uranium Oxide--II

6/30/55 Decl. 4/9/57

Nucl. Sci. Abstr. 1958 (1) 215

Anon.

Nuclear Metallurgy. Vol. IV. A Symposium on Uranium and Uranium Dioxide

IMD Special Report Series No. 4: The Metallurgical Society of American Institute of Mining, Metallurgical, and Petroleum Engineers (1957)

Nucl. Sci. Abstr. 1958 () 679

J. H. Handwerk and R. A. Noland (Argonne National Lab.)

Oxide Fuel Elements for High Temperatures

Chem. Eng. Progr. 53 (2) 60F-2F (1957)

Nucl. Sci. Abstr. 1957 (5) 612

C. Corsetti (CISE, Milan)

Fabrication Technology of Ceramic Fuel Elements

Energia Nucleare 5 (8) 509-21 (1958)

Nucl. Sci. Abstr. 1958 () 2216

C. Corsetti

Technology Fabrication of Ceramic Fuel Elements

Energia Nucleare 5 579-90 (1958)

Translated into French

Nucl. Sci. Abstr. 1963 (1) 64

H. H. Hausner (Gladding, McBean and Co., Inc.)

Bibliography on Uranium Dioxide

Contract AT(04-3)-249 (3/59)

Nucl. Sci. Abstr. 1959 (8) 1948

D. W. Brite and R. J. Anicetti (General Electric Co.)

Uranium Dioxide Fabrication

Contract AT(45-1)-1350 (12/5/60)

Nucl. Sci. Abstr. 1963 (1) 73

E. A. Evans (General Electric Co.)
Novel Ceramic Fuel Fabrication Processes
Fuel Element Fabrication with Special Emphasis on Cladding Materials
Vol. 2: Academic Press 335-70 (1961)
Nucl. Sci. Abstr. 1961 (10) 3253

G. M. Butler, Jr. and H. H. Hausner (Gladding, McBean and Co.)
Data Book on Uranium Dioxide
1960
Nucl. Sci. Abstr. 1961 (10) 3260

H. H. Hausner (International Atomic Energy Agency)
Powder Metallurgy in Nuclear Reactor Construction
1961
Nucl. Sci. Abstr. 1961 (9) 2922

G. E. Christie and F. S. Martin (Reactor Fuel Element Lab.,
U.K.A.E.A.)
Pilot Plant for Ceramic Nuclear Fuel Processes
Chem. & Process Eng. 42 (7) 308-9; 311-12 (1961)
Nucl. Sci. Abstr. 1961 (10) 3251

Oak Ridge National Lab.
Gas-cooled Reactor Project Quarterly Progress Report
3/31/61
Contract W-7405-eng-26
Nucl. Sci. Abstr. 1961 (9) 2979

R. W. Dayton, E. M. Simmons, and R. W. Endebrock (Battelle Me-
morial Inst.)
Reactor Materials
Vol. 5 No. 4 (11/62)
Nucl. Sci. Abstr. 1963 (4) 1447

A. R. Kaufmann
Nuclear Reactor Fuel Elements: Metallurgy and Fabrication
Interscience Publishers (1962)
Ceram. Abstr. 1962 (11) 273

P. Loewenstein, P. D. Corzine, and J. Wong
Fabrication of Core Materials
Nuclear Reactor Fuel Elements. Metallurgy and Fabrication: Inter-
science Publishers 383-426 (1962)
Nucl. Sci. Abstr. 1962 (7) 2166

G. Matz (Nuclear-Chemie und Metallurgie G.m.b.H.)
Fabrication of Fuel Elements
Review Series No. 25: Developments in the Peaceful Applications
of Nuclear Energy (International Atomic Energy Agency)
(9/62)
Nucl. Sci. Abstr. 1963 (1) 268

J. Doumerc (Compagnie pour l'Etude et la Realisation de Combus-
tibles Atomiques)
Fuel Elements--Manufacturing Procedure
Energie Nucl. 5 (1-2) 4-15 (1963)
Nucl. Sci. Abstr. 1963 (6) 2444

F29. FORMING GENERAL, BERYLLIUM OXIDE

T. Cheron (Aerospace Corp.)
Beryllium Oxide. A Literature Survey
Contract AFO4(647)-930 (9/1/61)
Nucl. Sci. Abstr. 1962 (9) 3184

Oak Ridge National Lab.
Proceedings of the Beryllium Oxide Meeting Held at Oak Ridge Na-
tional Lab, 12/1-2/60
Nucl. Sci. Abstr. 1961 (8) 2568

Anon.
BeO at National
Ceram. Age 76 No. 6 25 (1960)
Brit. Ceram. Abstr. 1961 (6) 249A

C. A. Bielawski, E. A. Douglas, and J. G. Theodore (Brush
Beryllium Co.)
Maritime Gas-cooled Reactor Program. Technical Feasibility Studies
of Fabrication Techniques Applicable to the Manufacture of High-
density Beryllia Tubes for Potential Utilization in the
Maritime Gas-cooled Reactor
Final Report 5/9/60--6/30/60
Contract AT(04-3)-187
Nucl. Sci. Abstr. 1962 (1) 323

P. S. Hessinger (National Beryllia Corp.)
Beryllia. Engineered Space Age Material
Ind. Eng. Chem. 54 No. 3 16-21 (1962)
Nucl. Sci. Abstr. 1962 (5) 1358

G-SECONDARY FORMING

G2. FORMING FROM "GREEN" UNFIRED BLANKS
Linked to F2g

G. Bostlund

Forming of Spiral Grooves in (Soft) Ceramic Rods

Swed. 137,663 (11/30/50)

Ceram. Abstr. 1953 (8) 145

Anon.

High Speed Cutting-off Machine for Small Components

Brit. Clayworker 64 (761) 170-71 (1955)

Ceram. Abstr. 1956 (8) 171

M. Skunda (General Motors Corp.)

Method for Shaping Ceramic Articles

U. S. 2,726,433 (12/13/55)

Ceram. Abstr. 1956 (2) 59

E. G. Arelt (Onondaga Pottery Co.)

Apparatus for Fettling Articles of Green Pottery Ware

U. S. 2,755,531 (7/24/56)

Ceram. Abstr. 1956 (10) 216

E. M. Gibbs and J. Stout

Story of Electrical Porcelain: IV, Pugging and Pressing

Ceram. Abstr. 1957 (1) 15

G. Helm

Shaping of Ceramic Ware by Turning

Glas-Email-Keramo-Tech. 7 (9) 321-24; (10) 367-9 (1956)

R. E. Steele and A. R. Blackburn

Method and Apparatus for Forming Holes in Ceramic Ware

U. S. 2,818,628 (1/7/58)

Ceram. Abstr. 1958 (4) 95

Lawrence Radiation Lab.

Investigations of Titanate Ceramics for Voltage Generation under
High Impact Loading

Final Report 9/58--12/59

Contract W-7405-eng-48

Nucl. Sci. Abstr. 1963 (3) 1146

F. P. Hall (Pass & Seymour, Inc.)
Removal of Flash from Ceramic Parts Formed by Pressing
U. S. 2,883,312 (4/21/59)
Ceram. Abstr. 1959 (9) 248

S. M. Tsenter
Semi-automatic Machines for Grinding and Polishing Porcelain
Glass and Ceramics, Moscow 18 (12) 621 (1961)
Brit. Ceram. Abstr. 1963 (1) 4A

G4. FORMING FROM FULLY MATURED CERAMICS--GENERAL

K. F. Romanov and I. G. Grinchenko
Grinding of Steatite Ceramics
Translated in Machines and Tooling 31 (5) 31-4 (1960)
Ceram. Abstr. 1961 (7) 157

Anon.
Finishing
Ceram. Age 78 (10) 97-101 (1962)

G15. FORMING AND SURFACE FINISHING BY CHEMICAL PROCESSES

A. Engelbrecht and G. Jaeger
Preparation of Smooth Surfaces on Objects of Sintered Alumina
Ger. 828,974 (1/21/52)
Ceram. Abstr. 1953 (4) 66

J. G. Gualtieri, M. J. Katz, G. A. Wolff
Gas Etching and Its Effect on Semiconductor Surfaces
Z. Krist. 114 (1-2) 9-22 (1960)
Ceram. Abstr. 1962 (4) 101

R. R. Stead (Texas Instruments)
Etching of Semiconductor Materials
U. S. Patent 2,973,253 (2/28/61)
Ceram. Abstr. 1961 (7) 170

R. R. Stead (Texas Instruments)
Process and Composition for Etching Semiconductor Materials
U. S. 2,983,591 (5/9/61)
Ceram. Abstr. 1961 (10) 248

R. T. Vaughan (Philco Corp.)
Controlled Jet Etching of Semiconductor Units
U. S. Patent 3,012,921 (12/12/61)
Ceram. Abstr. 1962 (5/62) 121

G16. FORMING BY STAMPING, PUNCHING

Anon.

Continuous Process for Fabricating Thin Sheet Ceramic Parts

Ceram. News 8 (6) 17 (1959)

Ceram. Abstr. 1959 (11) 288

Anon.

A New Division for the West's Oldest and Largest Ceramic Firm

Ceramic News 10 No. 2 12 (1961)

Brit. Ceram. Abstr. 1961 (8) 287A

J. J. Fargo (International Pipe and Ceramics Corp.)

Fabrication of Thin Uranium Dioxide Plates by a Powder Rolling
Process

Presented at 65th ACS

Am. Ceram. Soc. Bull. 42 (4) 1963 269

G17. MACHINING BY CUTTING ACTION

W. Peter

Drilling Hard Materials

Ind. Diamond Rev. 12 (139) 120-21 (1952)

Ceram. Abstr. 1953 (1) 1

W. Richter and G. Kammerich

Some Investigations on Ceramics and Cermet Materials for the Production of Blades for Cutting Tools

Silikattechnik 6 No. 12 528-34 (1955)

Nucl. Sci. Abstr. 1958 () 1058

J. E. Comeforo and T. S. Stanislaw

How Ceramics Can Be Shaped to Precision Tolerances: I

Ceram. Ind. 67 (4) 121-3 (1956)

Ceram. Abstr. 1957 (7) 139

American Society of Tool Engineers

Ceramic Tool Symposium

Detroit (1957)

Ceram. Abstr. 1957 (9) 195

V. Bertazzoni

Cutting and Machining of Refractory Materials

Ceramica 12 (1) 45-6 (1957)

Ceram. Abstr. 1957 (9) 195

R. C. Brewer (Dept. of Mechanical Engineering, Royal Tech. College)

Bibliography of Ceramic Tools

Ceram. Abstr. 1958 (6) 137

R. M. Gill

Ceramic Oxide Cutting Tools

Machinery (London) 91 (2351) 1341-46 (1957)

Ceram. Abstr. 1958 (5) 107

R. F. Rea and J. W. Ripple

Cutting and Grinding Ceramics

Am. Ceram. Soc. Bull. 36 (5) 163-7 (1957)

Ceram. Abstr. 1957 (7) 155

E. C. Graesser

How to Machine Glass Base Laminated Plastics

Tooling and Production 24 (7) 56-8 (1958)

Ceram. Abstr. 1959 (5) 121

E. C. Graesser

How to Machine Glass Base Laminated Plastics

Tooling and Production 24 (7) 56-8 (1958)

Ind. Diamond Abstr. (12) A195

Ceram. Abstr. 1959 (5) 121

H. J. Randhahn

Glass Machining with Hard Metals

Silikattech. 11 (3) 126-30 (1960)

Ceram. Abstr. 1961 (10) 237

National Research Council. Materials Advisory Board

A Survey by Task Force on Alternative Methods for Machining

Progress Report No. 3 (3/10/61)

Nucl. Sci. Abstr. 1961 (8) 2561

Office of Technical Services

Metalworking. Part I. Machining. Selective Bibliography

4/61

Nucl. Sci. Abstr. 1961 (8) 2562

Office of Technical Services

Metalworking. Part II. Machine and Cutting Tools

4/61

Nucl. Sci. Abstr. 1961 (8) 2562

W. H. Hampton and W. R. Shaw

Economical Accurate Hole Making in Exotic Metals

Grinding and Finishing 7 (1) 38-9 (1961)

Ceram. Abstr. 1961 (6) 135

G18. FORMING BY GRINDING

L. Coes, Jr.
Chemistry of Abrasive Action
Ind. Eng. Chem 47 (12) 2493-4 (1955)
Ceram. Abstr. 1957 (9) 195

Anon.
New Grinder for Ceramics
Ceram. Age 68 (2) 19 (1956)
Ceram. Abstr. 1957 (1) 253

Ceramic Research Station, New Brunswick
Technical Report No. 4 6/15/55--10/15/56
Project NR-032-348
Contract N-onr-404(03)
Nucl. Sci. Abstr. 1957 (10) 1236

E. L. Sinclair
How to Select Abrasives for Grinding Ceramics
Ceram. Ind. 67 (5) 92-3, 95 (1956)
Ceram. Abstr. 1957 (6) 123

F. K. Aleinikov
Determination of the Basic Factors in Polishing by the Mutual Grinding Method
Steklo i Keram. 14 (8) 7-11 (1957)
Ceram. Abstr. 1958 (7) 178

E. V. Flanders (Jones & Lamson Machine Co.)
Method of Grinding, including Grinding Wheel Forming
U. S. 24,448 (4/1/58)
Ceram. Abstr. 1958 (7) 163

M. W. Gormly
Technical Aspects of Vitrified Grinding Wheel Manufacture: V,
Finishing and Inspection
Am. Ceram. Soc. Bull. 37 (6) 283-6 (1958)
Ceram. Abstr. 1958 (8) 191

A. A. Giardini
Double Arc Goniometer Head for Crystal Orientation, Sawing, and Grinding
Am. Mineralogist 43 (3-4) 370-5 (1958)
Ceram. Abstr. 1959 (8) 190

R. B. McPherson

Grinding Ceramics by Dual Method is Faster

Electronics 31 (23) 112 (1958)

Ind. Diamond Abstr. (12) A178 (1958)

Ceram. Abstr. 1959 (5) 121

R. Burch

Grinding UO₂ Fuel Elements

Ceram. Age 73 (5) 30-1 (1959)

Ceram. Abstr. 1961 (9) 212

G. K. Demishev

Intensifying the Grinding Process by Vibrating the Polisher

Steklo i Keram. 16 (10) 27-31 (1959)

Ceram. Abstr. 1961 (7) 161

S. Eide

Cutting, Grinding, and Lapping of Piezoelectric Crystals

Ceram. Age 74 (2) 34-40 (1959)

Ceram. Abstr. 1961 (10) 245

N. Grechny, Jr.

Microwave Controlled Grinding of Ceramic Radomes

Am. Ceram. Soc. Bull. 38 (12) 699-702 (1959)

Ceram. Abstr. 1960 (2) 40

Compagnie Industrielle des Combustibles Atomiques Frittes

Uranium Oxide Extrusion

Quarterly Report No. 3 (6/15/60)

Contract OOI-59-9-RDF

Nucl. Sci. Abstr. 1962 (5) 1348

R. N. Samppala (General Electric Co.)

Machinability Data Sheet No. 17, External Grinding of Ceramic
Tubes

Contract AT(11-1)-171 (3/15/60)

Nucl. Sci. Abstr. 1963 (6) 1746

D. Ward and M. E. Passmore

Nose Cones--Study in Grinding Technique

Machine & Tool Blue Book 55 (6) 131-7 (1960)

Ind. Diamond Rev. 20 (237) 146-9 (1960)

Ceram. Abstr. 1963 (3) 63

F. G. Wihsmann and A. Petzold
Microhardness and Grindability
Silikattech. 11 (4) 151-3 (1960)
Ceram. Abstr. 1961 (10) 237

G. Botte
Machine for Shaping the Rectilinear Edge Faces of Glass Sheets
by Means of a Cylindrical Grinding Drum
U. S. Patent 2,994,991 (8/8/61)
Ceram. Abstr. 1962 (2) 36

J. W. Giffen (Corning Glass Works)
Precision Grinding
U. S. Patent 2,997,827 (8/29/61)
Ceram. Abstr. 1962 (3) 69

Lamesch, Jansen, and Knospe (Compagnie de Saint-Gobain)
Grinding Machines Simultaneously Working both Surfaces of a Continuous Ribbon of Glass
U. S. Patent 2,989,826 (6/27/61)
Ceram. Abstr. 1962 (1) 6

I. Peyches (Compagnie de Saint-Gobain)
Process for Grinding or Polishing Simultaneously the Two Faces of a Glass Sheet
U. S. Patent 2,990,663 (7/4/61)
Ceram. Abstr. () 7

Anon.
Grinding Ceramics to Close Tolerances
Am. Ceram. Soc. Bull. 41 (10) 606-7 (1962)
Ceram. Abstr. 1962 (11) 253

R. O. Heisel
Apparatus for Shaping Crystals
U. S. Patent 3,041,800 (7/3/62)
Ceram. Abstr. 1962 (10) 247

W. A. Merkl and H. P. Wasshausen (USA-Sec. Army)
Device for Treating (Grinding and Polishing) Piezoelectric Crystals
U. S. Patent 3,027,689 (4/3/62)
Ceram. Abstr. 1962 (8) 194

N. Stuckey

Hard Ceramics Need Diamond

Ind. Diamond Rev. 22 (259) 168-71 (1962)

Ceram. Abstr. 1962 (10) 247

N. Zlatin, M. Field, and J. Gould (Metcut Research Associates)

Machining of Refractory Materials

Phase II Technical Engineering Report 5/1/62--7/31/62

Contract AT33(600)-42349

Nucl. Sci. Abstr. 1962 (11) 4042

G19. SURFACE FINISHING

F. L. White (Crane Packing Co.)
Method of Lapping Quartz Crystals
U. S. 2,687,603 (8/31/54)
Ceram. Abstr. 1955 (1) 15

S. Boetcher
Lapping for Precision Ceramics
Ceram. Age 68 (5) 26-9 (1956)
Ceram. Abstr. 1962 (1) 16

E. L. Long, Jr. and R. J. Gray (Oak Ridge National Lab.)
Preparation of Metallographic Specimens Through Vibratory Polishing
Contract W-7405-eng-26 (6/26/58)
Nucl. Sci. Abstr. 1958 () 1356

T. P. Kapustina
Polishing Ceramic Materials by Free Abrasion
Steklo i Keram. 16 (6) 18-21 (1959)
Ceram. Abstr. 1960 (2) 41

I. Ida and Y. Arai
VHF Crystal Polishing and the Nature of Polished Quartz Surfaces
Rev. Elec. Commun. Lab. 8 (3-4) 119-74 (1960)
Ceram. Abstr. 1961 (5) 123

C. A. Hawkins
Precision Lapping Device
U. S. Patent 2,998,676 (9/5/61)
Ceram. Abstr. 1962 (3) 69

A. Porneuf (Centre d'Etudes Nucleaires)
Optical and Electronic Microscopy of Sintered Uranium Dioxide
J. Nuclear Materials 4 (7) 200-17 (1961)
Nucl. Sci. Abstr. 1961 (12) 4023

R. E. Gardner and G. W. Robinson, Jr.
Improved Method for Polishing Ultra-high-density MgO
J. Am. Ceram. Soc. 45 (1) 46 (1962)
Ceram. Abstr. 1962 (2) 46

H. D. Taylor
Microscopy Technique for Alumina Ceramics
Am. Ceram. Soc. Bull. 42 (3) 104-5 (1963)
Ceram. Abstr. 1963 (4) 103

G20. ABRASIVE IMPACT FORMING

B. G. Schwacha (North American Aviation, Inc.)
Liquid Cutting of Hard Materials
U. S. 2,985,050 (5/23/61)
Ceram. Abstr. 1961 (10) 249

Anon.
Cutting Hard Brittle Ceramics by Air Abrasion
Ceram. Age 78 (2) 48-9 (1962)
Ceram. Abstr. 1962 (10) 231

G21. SAWING, CUTTING-OFF

W. Avenhaus (Mechanische Ziegelherstellung)
Mechanical Tile Production
Verlag Wilhelm Knapp (1953)
Ceram. Abstr. 1953 (9) 160

H. Jebsen-Marwedel
Art and Science of Glass Cutting
Ind. Diamond Rev. 17 (204) 209-13 (1957)
Ceram. Abstr. 1958 (3) 66

K. Funabashi, S. Sakai, and K. Yamada
Machining of Porcelain Insulators: I, Efficiency in Cutting-off
with Grinding Wheels
Nagoya Kogyo Gijutsu Shikensho Hokoku 7 (3) 70-3 (1958)
Ceram. Abstr. 1959 (10) 263

K. Funabashi, S. Sakai, and K. Yamada
Machining of Porcelain Insulators: II, Cutting-off with Grinding
Wheels in the Wet State
Nagoya Kogyo Gijutsu Shikensho Hokoku 7 (5) 81-4 (1958)
Ceram. Abstr. 1959 (11) 279

W. Gilbert
Some Problems of Manufacture by the Wire-cut Process
Trans. Brit. Ceram. Soc. 58 (11) 629-44 (1959)
Ceram. Abstr. 1960 (9) 215

P. D. Jewett (Transitron Electronic Corp.)
Machine for Cutting Germanium, Silicon, Quartz, and Other Hard
Materials
U. S. 2,917,873 (12/22/59)
Ceram. Abstr. 1960 (5) 118

R. F. Stewart (Texas Instruments, Inc.)
Method of and Apparatus for Cutting a Semiconductor Crystal
U. S. 2,886,026 (5/12/59)
Ceram. Abstr. 1959 (9) 243

G22. THERMAL OPERATIONS FOR SURFACE REMOVAL OR FINISHING

M. H. Barnes and E. L. McCandless (Union Carbide & Carbon Corp.)
Flame Glossing Rod-shaped Single Crystals of Corundum
U. S. 2,608,031 (8/26/52)
Ceram. Abstr. 1953 (2) 26

T. K. Bierlein, H. W. Newkirk, Jr., and B. Mastel
Etching of Refractories and Cermets by Ion Bombardment
J. Am. Ceram. Soc. 41 (6) 196-200 (1958)
Ceram. Abstr. 1958 (7) 173

J. F. H. Custers, H. B. Dyer, and P. T. Wedepohl (DeBeers Consolidated Mines, Ltd.)
Polishing Hard Crystalline Carbon
U. S. 2,931,351 (4/5/60)
Ceram. Abstr. 1960 (8) 185

R. F. Bunshah (Lawrence Radiation Lab.)
The History of Electronbeam Technology
Contract W-7405-eng-48 (7/24/61)
Nucl. Sci. Abstr. 1961 (11) 3514

B. M. Gibbs and H. Rawson
Thermal Etching of Sintered UO_2
Trans. Brit. Ceram. Soc. 60 (11) 854-7 (1961)
Ceram. Abstr. 1962 (6) 155

N. E. Poulos, S. R. Elkins, C. A. Murphy, and J. D. Walton (Georgia Inst. of Tech.)
High Temperature Ceramic Structures
Final Summary Report 11/1/61--10/31/62
Contract NOrd-15701
Nucl. Sci. Abstr. 1963 (2) 633

C. K. Crawford (M.I.T.)
Electron Beam Machining
Introduction to Electron Beam Technology: Wiley 315-53 (1962)

O. C. Wells (Westinghouse)
Electron Beams in Microelectronics
Introduction to Electron Beam Technology: Wiley 354-79 (1962)

324. FORMING BY COMBINATIONS OF ENERGIES

T. A. Dickinson

Ultrasonic Machining of Ceramics
Ceram. Age 64 (4) 15-7, 33 (1954)
Ceramics 6 (70) 450-3 (1955)
Ceram. Abstr. 1955 (6) 110

N. Taniguchi

Mechanical Piercing Method of Precious Stones and Glasses: III,
Automatic Repeated Impact Piercing Machine
Soc. Prec. Mech. Jap. J. 20 (1) 8-13 (1954)
Ceram. Abstr. 1960 (5) 118

N. E. Gibbs

Ultrasonic Cutting of Quartz Wafers
J. Acoust. Soc. Amer. 27 (5) 1017 (1955)
Ind. Diamond Rev. 16 (182) B30 (1956)
Ceram. Abstr. 1956 (6) 120

L. B. Pirozhnikov and I. S. Vainshtok

Boring of Glass and Ceramics by Means of Ultrasonics
Steklo i Keram. 12 (6) 7-10 (1955)
Ceram. Abstr. 1957 (6) 140

R. C. Hall

Machining Hard and Brittle Materials
Metal Progr. 70 (2) 78-80 (1956)
Ceram. Abstr. 1957 (2) 42

E. A. Neppiras and R. D. Foskett

Ultrasonic Machining: I, Technique and Equipment
Philips Tech. Rev. 18 (11) 325-34 (1956-57)
Ceram. Abstr. 1958 (8) 208

C. J. Thatcher

Machining by High-frequency Vibratory Abrasion
U. S. 2,736,144 (2/28/56)
Ceram. Abstr. 1956 (6) 120

C. J. Thatcher

High Speed Machining by Ultrasonic Impact Abrasion
U. S. 2,804,724 (9/3/57)
Ceram. Abstr. 1958 (1) 23

N. W. Thibault and G. E. Comstock (Norton Co.)
Methods of Electrolytic Grinding and Eroding
U. S. 2,805,197 (9/3/57)
Ceram. Abstr. 1958 (1) 2

G. F. Keeleric
Method and Apparatus for Electrolytic Cutting, Shaping, and Grinding
U. S. 2,826,540 (3/11/58)
Ceram. Abstr. 1958 (6) 153

L. J. Palush (Gulton Industries, Inc.)
Ultrasonic Drill
U. S. 2,825,186 (3/4/58)
Ceram. Abstr. 1958 (6) 153

M. E. Weiss (Gulton Industries, Inc.)
Rotating Ultrasonic Drill
U. S. 2,818,686 (1/7/58)
Ceram. Abstr. 1958 (4) 98

M. Heerschap and C. M. Levitt (Crown Mines)
Eroding of Hard Crystalline Carbon
U. S. 2,939,941 (6/7/60)
Ceram. Abstr. 1960 (10) 239

A. L. Livsits
Electro-erosion Machining of Metals
Butterworths (London) (1960)
Nucl. Sci. Abstr. 1961 (11) 3614

W. Ullmann and W. Ehrlich (Agie, A.G. für industrielle Elektronek)
Electroerosive Grinding Method and Device for Its Performance
Ceram. Abstr. 1960 (5) 118

G. G. Brown (Bendix Corp.)
Means for Cutting
U. S. 2,967,381 (1/10/61)
Ceram. Abstr. 1961 (5) 125

G. E. Wright
How to Make a Larger Ultrasonic Grinding Tool.
Ceram. Ind. II (4) 75, 89-90 (1961)
Ceram. Abstr. 1962 (3) 68

J. B. Pond
Newest Developments Boost Electrolytic Grinding
Grinding and Finishing 8 (3) 68 (1962)

W. D. Raburn (Sandia Corp.)
Electronic Shaping
Contract AT(29-1)-789 (8/62)
Nucl. Sci. Abstr. 1963 (3) 859

A. Sato (Nippon Electric Co., Ltd.)
Method of Machining Semiconductors
U. S. 3,061,422 (10/30/62)
Ceram. Abstr. 1963 (3) 78

L. Balamuth
Ultrasonic Rotary Drive May Open Up Many New Applications for
Micro Devices
Electronics 36 (2) 56-7 (1963)
Ceram. Abstr. 1963 (6) 165

C. Kleesattel, L. Balamuth, and A. K. Kuris (Cavitron Corp.)
Acoustically Vibrated Material Cutting and Removing Devices
U. S. 3,076,904 (2/5/63)
Ceram. Abstr. 1963 (5) 138

H16d,e. IMPREGNATION AND INFILTRATION

- N. S. Hoyer (Gibson Electric Co.)
Method of Making Powdered Compacts
U. S. 2,768,099 (10/23/56)
Ceram. Abstr. 1957 (1) 11
- K. C. Nicholson (Carborundum Co.)
Zirconium Boride Body Impregnated with Molybdenum Silicide and
Method of Making
U. S. 2,766,141 (10/9/56)
Ceram. Abstr. 1957 (2) 41
- P. Schwarzkopf
Mechanism of Infiltration
Ceram. Abstr. 1957 (9) 222
- J. H. Veale (Illinois Clay Products Co.)
Method of Impregnation of Refractory Bodies with Phosphoric Acid
U. S. 2,805,174 (9/3/57)
Ceram. Abstr. 1958 (1) 18
- C. G. Goetzel and L. P. Skolnick (Sintercast Corp. of America)
Methods of Infiltrating High Melting Skeleton Bodies
U. S. 2,828,225 (3/25/58)
Ceram. Abstr. 1958 (7) 176
- N. E. Poulos, S. R. Elkins, C. A. Murphy, and J. D. Walton (Georgia Inst. of Tech.)
High Temperature Ceramic Structures
Contract NOrd-15701
Summary Report No. 5 11/1/60--10/31/61
Nucl. Sci. Abstr. 1962 (6) 1953
- M. H. Ortner, S. J. Klach, and J. O. Gibson (Vitro Labs.)
Protection of Graphite by Impregnation
Quarterly Progress Report No. 1 2/7/60--5/31/60
Contract NOW 60-0167
Nucl. Sci. Abstr. 1961 (4) 1205
- W. B. Tarpley and H. Kartluke (Aeroprojects Inc.)
Ultrasonic Impregnation: Preparation of Low Permeability Graphite

K. ASSEMBLING AND JOINING

Compagnie Generale d'Electro-Ceramique
Process of Obtaining Ceramic Pieces of Great Thickness
Fr. 1,037,879 (5/6/53)
Ceram. Abstr. 1954 (7) 129

C. W. Fox (Oak Ridge National Lab.)
Brazing of Ceramics
Progress Report 11/8/62
Contract W-7405-eng-26
Nucl. Sci. Abstr. 1963 (2) 631

T. PRODUCTS AND PARTS
CERAMICS FOR AEROSPACE, RADOMES

P. S. Hessinger
Ceramic Radomes for Aircraft
Am. Ceram. Soc. Bull. 34 (5) 145-50 (1955)
Ceram. Abstr. 1955 (7) 126

G. D. Robertson
Some Missile Design Requirements for Ceramic Radomes
Am. Ceram. Soc. Bull. 37 (1) 1-3 (1958)
Ceram. Abstr. 1958 (3) 75

L. D. Richardson
Ceramics for Aircraft Propulsion Systems
Am. Ceram. Soc. Bull. 33 (5) 135-7 (1954)
Ceram. Abstr. 1954 (7) 125

W. M. Sterry
Ceramics Holds Key to Aircraft Development
Ceram. Ind. 68 (5) 92-4, 113 (1957)
Ceram. Abstr. 1958 (6) 162

W. R. Sheridan
Use of Refractory Ceramics in Rocket Engines
Am. Ceram. Soc. Bull. 37 (2) 91-4 (1958)
Ceram. Abstr. 1958 (4) 93

E. J. Smoke
Fabrication of Dense Ceramic Radomes by Casting
Ceram. Age 69 (4) 32 (1957)
Ceram. Abstr. 1962 (2) 40

N. N. Ault and L. H. Milligan
Alumina Radomes by Flame-spray Process
Am. Ceram. Soc. Bull. 38 (11) 661-4 (1959)
Ceram. Abstr. 1960 (1) 7

Norton Co.
Ceramic Shells
Brit. Patent 847,449 (9/7/60)
Brit. Ceram. Abstr. 1961 (3) 111A

M. J. Kofoed
Ceramic Radome Wall Thickness Tolerance Requirements and Their
Interpretation
Am. Ceram. Soc. Bull. 37 (1) 4-8 (1958)
Ceram. Abstr. 1958 (3) 74

T. M. Giles, N. Tallan, P. S. Hessinger, and J. O. Everhart
Development of Sandwich Construction Inorganic Radomes: I, II
PB Repts. 131408 and 131406
U. S. Govt. Research Repts. 29 (3) 124 (1958)
Ceram. Abstr. 1961 (1) 12

National Beryllia Corp.
Development of Fabrication Techniques for Beryllium Oxide Radome
Materials
Final Report 6/61
Contract NOw-60-0057
Nucl. Sci. Abstr. 1962 (6) 1958

R. R. Van Der Beck, A. W. von Mickwitz, and L. G. Scheinman
How Oxide Cutting Tools are Made and What They Do
Ceram. Ind. 69 (6) 113-5, 128-31 (1957)
Ceram. Abstr. 1958 (6) 137

U. S. Dept. of Commerce, Office of Technical Services
Minutes of Symposium on Ceramic Cutting Tools
PB 111757
Ceram. Abstr. 1957 (2) 39

ADDENDUM

V. I. Likhtman, N. S. Gorbunov, I. G. Shatalova, and P. A. Rebinder
Vibrational Densification in Powder Metallurgy
Doklady Akad. Nauk SSSR 134 1150-2 (1960)
Chem. Abstr. 55 19658

I. M. Fedorchenko and N. A. Filatova
The Influence of Technological Factors on Compressibility of Iron
Powders
Voprosy Poroshkovoi Met. i Prochnosti Materialov, Akad. Nauk Ukr.
SSR 1959 No. 7 105-19
Chem. Abstr. 55 19658

G. Yui (Sci. Research Inst. Heavy Met., Peking)
The Relation Between the Density of Magnesite Brick, the Grain
Size, and the Intensity of the Pressing Operation
Ogneupory 25 No. 2 87-92 (1960)
Chem. Abstr. 54 11421

T. R. Barrett, G. C. Ellis, and R. A. Knight
The Pressureless Sintering of Loose Beryllium Powder
Powder Met. No. 1-2 122 (1958)

P. Rado
Preparation and Properties of Calcium Fluoride Ware
Spec. Ceram. Proc. Symposium Brit. Ceram. Research Assoc. 1959
237-51
Chem. Abstr. 56 1166

G. W. Phelps (United Clay Mines Corp.)
Casting Properties of English China Clay
Am. Ceram. Soc. Bull. 38 411-4 (1959)
Chem. Abstr. 53 20718

N. L. Parr, G. F. Martin, and E. R. W. May
Preparation, Microstructure, and Mechanical Properties of Silicon
Nitride
Spec. Ceram., Proc. Symposium Brit. Ceram. Research Assoc. 1959
102-35
Chem. Abstr. 55 25816

S. Kato, R. Naito, R. Yamamoto, and Y. Nishimura
Effect of the Particle Size of Raw Materials in Porcelain Manufac-
turing. V. Effect of the Commminution of Feldspar and Quartz on
the Packing in Porcelain Bodies
Nagoya Kogyo Gijutsu Shikensho Hokoku 11 596-602 (1962)
Chem. Abstr. 58 12273

APPENDIX

Recommended Study Areas to Further Ceramic Forming Processes

All authors have indicated need for development or research in their respective sections as part of their review because the critical surveys revealed lack or even complete deficiency of knowledge in many areas. Most of these ideas relate to bridging the gap between ceramic science and the engineering technology of processing. Many of them relate to intuitive, empirical or even proprietary thoughts as well as to the deductive thoughts that result from any attempt to correlate fundamentals with a highly technological subject. These recommended areas of study have been included as an appendix to this report and are paraphrased below.

- (1) Critically delineate properties of particulate systems which are specifically related to forming theory. The importance of these properties to forming methods cannot be overemphasized.
- (2) Determine relationships of both the bulk and surface reactivity of powders to such factors as particle size, shape, defect structure, stoichiometric composition, and atmosphere.
- (3) Relate the flow properties of particulate systems to their shape and size distributions, reactivity, and particle-particle interaction. Study fluid-solid interfacial reactions.
- (4) Develop methods and conditions for reproducing size and distributions of powders in the range of 15 microns and below, including methods other than mechanical comminution. For the different production methods, study the factors that determine the size, shape, and size distribution of resulting particles.
- (5) Show the application of surface and organic chemistry fundamentals to the understanding of the function of organic additives in model particulate systems.
- (6) Study the fundamentals of compaction response in particulate systems under high pressures at room temperature.
- (7) Define the mechanism of compaction in particulate systems under programmed heat-pressure-atmosphere conditions.
- (8) Study the interaction of ultrasonic energy and particulate systems during compaction processes.
- (9) Support empirical development of ultrasonic energy aids to forming.
- (10) Develop relations between forming energy, compaction response and extrusion rates in extrusion forming systems, hot and cold.
- (11) Apply control theory to develop a sound basis for transmission of forming energy in forming operations treated as true engineering systems, hot and cold.
- (12) Bring hot pressing processes from the laboratory to the production stage by engineering development.
- (13) Develop novel techniques for heat treatment requiring low capital investment.
- (14) Analyze simultaneous viscous flow and heat transfer in glass forming processes.

- (15) Develop processes for utilizing glasses which either (a) are highly refractory, or (b) have viscosities substantially lower than conventional glasses.
- (16) Continue the development of the theory of crystal growth and nucleation of glasses as related to forming ceramics.
- (17) Develop glass forming processes which preserve the inherent strength of glass.
- (18) Study the theory of crystal growth and nucleation of melts as a means of improving process operation and characterization of products produced by fusion casting.
- (19) Develop application of thermodynamic data on ceramic oxide melts to fusion casting.
- (20) Systematically study the material and operational variables as related to the characterization of shapes produced by spraying of matter or semi-matter particulate systems.
- (21) Design transport devices for feeding submicron particle systems or agglomerates in hot spraying and other forming systems.
- (22) Study the effect of impingement and configuration on mass and heat transfer during vapor deposition.
- (23) Initiate a fundamental study of nucleation and crystal growth from the vapor state.
- (24) Systematically review work on fiber ceramics and continue support of work to optimize the process to utilize fiber strengths in composite systems particularly for high temperature use.
- (25) Study the mechanism of material removal in finishing, drilling, or shaping ceramics.

UNCLASSIFIED

UNCLASSIFIED