

AS

AMRL-TR-66-137
AD06 52491



EVALUATION OF WATER RECLAMATION SYSTEMS AND
ANALYSIS OF RECOVERED WATER FOR HUMAN CONSUMPTION

COURTNEY A. METZGER
ALBERT B. HEARLD
BOBBY G. McMULLEN, MASTER SERGEANT, USAF

FEBRUARY 1967

Distribution of this document
is unlimited

AEROSPACE MEDICAL RESEARCH LABORATORIES
AEROSPACE MEDICAL DIVISION
AIR FORCE SYSTEMS COMMAND
WRIGHT-PATTERSON AIR FORCE BASE, OHIO

20100224 443

NOTICES

When US Government drawings, specifications, or other data are used for any purpose other than a definitely related Government procurement operation, the Government thereby incurs no responsibility nor any obligation whatsoever, and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise, as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Requests for copies of this report should be directed to either of the addressees listed below, as applicable:

Federal Government agencies and their contractors registered
with Defense Documentation Center (DDC):

DDC
Cameron Station
Alexandria, Virginia 22314

Non-DDC users (stock quantities are available for sale from):

Chief, Storage and Dissemination Section
Clearinghouse for Federal Scientific & Technical Information (CFSTI)
Sills Building
5285 Fort Royal Road
Springfield, Virginia 22151

Organizations and individuals receiving reports via the Aerospace Medical Research Laboratories' automatic mailing lists should submit the addressograph plate stamp on the report envelope or refer to the code number when corresponding about change of address or cancellation.

Do not return this copy. Retain or destroy.

The voluntary informed consent of the subjects used in this research was obtained as required by Air Force Regulation 169-8.

EVALUATION OF WATER RECLAMATION SYSTEMS AND
ANALYSIS OF RECOVERED WATER FOR HUMAN CONSUMPTION

COURTNEY A. METZGER
ALBERT B. HEARLD
BOBBY G. McMULLEN, MASTER SERGEANT, USAF

**Distribution of this document
is unlimited**

Foreword

This research study was initiated by the Biotechnology Branch, Life Support Division, Biomedical Laboratory, Aerospace Medical Research Laboratories, Aerospace Medical Division, Wright-Patterson Air Force Base, Ohio. The study was conducted in support of project 6373, "Equipment for Life Support in Aerospace," and task 637304, "Waste Recovery and Utilization." The program was under the supervision of C. A. Metzger. Principal investigator was Albert B. Hearld with technical support provided by Master Sergeant Bobby G. McMullen. Additional support was provided by Staff Sergeant Carl Gailey and Master Sergeant Walter Bigelow.

The analytical data referenced was furnished under Contract DO (33-657)-63-377 by the Robert A. Taft Sanitary Engineering Center (U. S. Public Health Service), Cincinnati, Ohio. Robert C. Kroner was in charge of the General Laboratory Services, Water Quality Section, which performed the analyses.

All of the water recovery systems discussed in this report were developed either by the Aerospace Medical Research Laboratories or on Government contracts.

This technical report has been reviewed and is approved.

WAYNE H. McCANDLESS
Technical Director
Biomedical Laboratory
Aerospace Medical Research Laboratories

Abstract

Analyses were made of water recovered from human urine and from atmospheric condensate collected during manned tests inside a sealed chamber. Data on more than 200 samples were prepared for comparison with that of distilled water and tap water and with U. S. Public Health Standards for drinking water. Most of the samples were suitable for human consumption. Candidate systems for recovering potable water from urine were evaluated. Thermoelectric, electrodialysis, and vapor compression water reclamation devices were determined to be suitable for use during extended aerospace missions.

Table of Contents

<i>Section</i>	<i>Page</i>
I. INTRODUCTION.....	1
II. SYSTEM EVALUATION.....	2
Techniques.....	2
System Operation.....	2
III. SAMPLING AND RESULTS.....	9
IV. CONCLUSIONS.....	26
APPENDIX – SURVEY OF WATER RECLAMATION SYSTEMS.....	28
REFERENCES.....	29

List of Illustrations

<i>Figure</i>	<i>Page</i>
1 Vapor Compression System.....	3
2 Evaporator/Condenser.....	3
3 Electrolysis Unit.....	4
4 Ultrafiltration System.....	4
5 Membrane Permeation System.....	5
6 Electrodialysis System.....	6
7 Dehumidification System.....	7
8 Main Assembly – Thermoelectric Unit.....	8
9 Thermoelectric Still.....	8

List of Tables

<i>Table</i>	<i>Page</i>
Ia-Ij. Analytical Results – Reclaimed Waters.....	16 through 25
II. Water Reclamation Systems.....	28

SECTION I.

Introduction

Since 1958, the Aerospace Medical Research Laboratories has been engaged in the study of techniques that have been proposed for recovering potable water from human urine, wash waters, and dehumidification water during earth-orbiting aerospace missions. The study has resulted in an evaluation of the techniques and in the testing of hardware which incorporate some of the techniques. The study is far from complete and will be continued with a more comprehensive evaluation and testing of those systems that are potentially most suitable for aerospace application.

Objectives of this program were: (1) to determine the quality of water recovered from human urine and dehumidification water with off-the-shelf equipment and with devices designed specifically for demonstrating water recovery techniques; (2) to ascertain the changes that occur in the recovered water when the pretreatment, method of processing, and/or posttreatment are altered; (3) to evaluate existing recovery systems for aerospace application and to select for further study the systems having the greatest potential; and (4) to provide industry and other agencies with data that would be of value in future development efforts and in studies of water quality, i.e., the relation between pH and COD or the chloride content of water recovered from urine by vapor distillation and by compression distillation.

SECTION II.

System Evaluation

TECHNIQUES

The techniques used for reclaiming the water are listed below and are identified by the abbreviations shown in the process column of the analytical data sheets, tables Ia-Ij.

VD – Vacuum Distillation

VC – Vapor Compression

E – Electrolysis

UF – Ultrafiltration

MP – Membrane Permeation

ED – Electrodialysis

UFC – Unfiltered Condensate

FC – Filtered Condensate

TE – Thermoelectric Distillation

F Cell – Fuel Cell

Data on distilled water (DW) and tap water (TW) are included for comparison with the data on the recovered water, especially that recovered from urine. The distilled water was purchased locally. The tap water was drawn from the Wright-Patterson Air Force Base water system.

SYSTEM OPERATION

Descriptions of the systems used to illustrate the techniques follow.

Vapor Compression – Two vapor compression water recovery systems were evaluated. One Model MR 08-082, was procured from Mechanics Research Division, General American Transportation Corporation, Niles, Illinois (ref 1). The vapor compression system (ref 2) was procured from General Dynamics/Electric Boat, Groton, Connecticut. An artist's concept of the MR 08-082 system is shown in figure 1. A schema of the evaporator/condenser (Electric Boat system) is shown in figure 2.

In both systems the water in the urine is evaporated under reduced pressures. The vapor is fed through a compressor into a condenser where the reclaimed product is collected. That latent heat rejected during the condensation is transferred back to the evaporator for reuse in vaporizing more water. Heat from an electric motor and/or from a heating coil is used to speed the evaporation and to replace heat lost to the surrounding atmosphere.

Vacuum Distillation – This system consists of a boiler in which urine is evaporated under reduced pressure. The vapors are drawn into a condenser and the product water collected is drained to a reservoir. The vapors are caused to pass through activated charcoal and/or a microporous glass fiber cloth. An excellent description of a typical vacuum distillation apparatus is contained in reference 3.




Figure 1. Vapor Compression System




Figure 2. Evaporator/Condenser




Figure 3. Electrolysis System





Figure 4. Ultrafiltration System

Electrolysis — the system used is shown in figure 3. A d-c current is passed through the urine from one platinum electrode to another. The chlorine produced at the anode reacts with the sodium hydroxide formed at the cathode and the hypochlorite formed decomposes the urea and other organics in the urine. The process lowers the pH of the recovered water and bacterial growth is eliminated.

Ultrafiltration — Urine that has been pretreated to remove urea and calcium is circulated over a membrane under a pressure greater than the osmotic pressure of the urine. Water passing

Figure 5. Membrane Permeation System






Figure 6. Electrodialysis System

out of the urine through the membrane is collected. The process is described in references 4, 5, 6, and 7. The ultrafiltration unit was procured from Radiations Applications, Incorporated, and is shown in figure 4.

Membrane Permeation — Hot urine is circulated through a permeator where the urine flows across two selectively permeable membranes. Water from the urine permeates the membranes and evaporates into a vacuum chamber. The vapor flows from the chamber through an ion exchange resin into a condenser where the product water is collected. The product is then pumped through a charcoal filter and a 0.45-micron (pore size) filter to a storage tank. The permeation system (ref 8) was procured from Ionics, Incorporated. Figure 5 shows the system.

Electrodialysis — This system (refs. 9 and 10) is shown in figure 6 and was procured from Ionics, Incorporated. Urine pretreated to precipitate a portion of the calcium and urea is pumped through a series of carbon filters into a reservoir from which it is circulated through a stack. The stack consists of compartments separated by alternating anion permeable and cation permeable ion exchange membranes and is located between a pair of electrodes. A d-c current passed through the stack results in the formation of two streams — a waste brine stream and a dilute or potable water stream. The pretreatment used consisted of silver nitrate plus oxalic acid in distilled water.

Filtered Condensate — Unless otherwise stated, the condensate was collected inside the AMRL Life Support Systems Evaluator during confinement studies involving four men for periods

of up to 28 days. All condensate was condensed from the atmosphere on a finned aluminum heat exchanger and drained to a sample bottle or pumped through one or more filters to a sample bottle. The samples were then submitted for analysis. Figure 7 is a schematic of one system used.

Unfiltered Condensate — All unfiltered condensate was collected inside the AMRL Evaluator and was submitted for analysis without being processed in any manner.

Thermoelectric Distillation — Urine is evaporated under reduced pressure and at a temperature of approximately 104 F (40 C). The resultant water vapor migrates to a series of condensers where it is condensed. The latent heat of condensation is thermoelectrically pumped back to the boiler for reuse. The product water flows from the condensers through a charcoal filter into a potable water storage tank. A schematic of the main assembly of the thermoelectric unit is shown in figure 8. An external view of the still is shown in figure 9. The thermoelectric distillation device is described in reference 17.




Figure 7. Dehumidification System




Figure 8. Main Assembly — Thermoelectric Unit




Figure 9. Thermoelectric Still

SECTION III.

Sampling and Results

More than 200 samples of water were recovered and submitted to Taft Sanitary Engineering Center (TC) for analyses. The processing varied — often from sample to sample. These differences are noted in the discussion of the samples which is contained herein. The analytical data were grouped, where convenient, in tables so as to illustrate one recovery technique. This grouping permits the data to be readily compared with the U. S. Public Health Standards for drinking water and with data on water reclamation by several techniques.

Following are the techniques used:

VAPOR COMPRESSION — See table Ia.

All samples were recovered by means of the Model 08-082 vapor compression distillation unit procured from MRD Division, General American Transportation Corporation. Unless otherwise specified, the recovered water was pumped through the filters at approximately 2 gallons per hour. Three to 4 liters of urine were processed for each sample.

Data on methods of processing follow:

Sample 1 — The urine was pretreated with one HTH (Hypochlorite 70% Cl tablet) and 10 drops of Antifoam B (Dow Corning). The water recovered was pumped through a 3½-inch inside diameter column containing 1130 grams of Hydrotarco activated carbon, 260 grams of Dowex 50W-X10 cation exchange resin, and a 1-inch thick glass wool filter.

Samples 2 and 3 — Processed same as sample 1 except that the urine was pretreated with 10 grams merthiolate per liter of urine in lieu of the HTH tablet.

Samples 4-7 — The urine was pretreated with merthiolate as in samples 2 and 3. The recovered water, however, was pumped up through a 4-inch diameter carbon (Nuchar C-190) column consisting of 3 inches of coarse carbon plus 12 inches of fine carbon plus 3 inches of coarse carbon at approximately ¼-gal. per minute.

Samples 10, 11, 12, and 14 — Untreated urine, with 10 drops of Antifoam B added to prevent foaming, was processed. The residue from samples 10, 11, and 12 was left inside the evaporator. All water recovered was pumped through a 0.15-micron* filter that was later found to be defective.

Samples 15-17 — The evaporator and condenser were cleaned and flushed with distilled water. A new evaporator liner was installed and two operations to flush the machine were made with a mixture of distilled water and benzalkonium chloride (BAC). The residue from the flush was left in the evaporator. The urine processed was pretreated with 10 grams of trimethylol nitro-methane and ten drops of Antifoam B were added to prevent foaming. The product was pumped through a 0.15-micron filter.

Samples 18 and 19 — The machine was thoroughly scrubbed and flushed. A new evaporator liner was installed and the machine sterilized with cryoxide gas at ½ psig for 5½ hours then flushed for 16 hours with air passed through a sterilized filter. Four liters of sterile injection water were processed. For sample 18, the product was drawn directly from the machine. For sample 19, the water was pumped through the 0.15-micron filter used for samples 15-17.

*Nominal pore opening.

Sample 20 — Urine pretreated with 10 grams of trimethylol nitromethane and 10 drops of Antifoam B was processed on the residue left in the evaporator from samples 18 and 19. The recovered water was pumped through the filter used for samples 15-19.

Sample 25 — Urine with 10 drops of Antifoam B, was processed. The recovered water was drawn directly from the machine. Approximately 1 liter of water was recovered. This was not enough for the spectrographic tests.

Sample 32 — Urine with no additives was processed with the plastic evaporator liner removed from the machine. The sample was drawn directly from the machine.

MISCELLANEOUS TECHNIQUES — See table Ib.

Vapor compression, electrolysis, ultrafiltration, membrane permeation, and electrodialysis were employed in the recovery of the samples listed on table Ib. Data on the individual processings follow:

Sample 13 (Vapor Compression) — Approximately 2500 ml of urine with one HTH-hypochlorite tablet 70% Cl added was processed in a unit procured from General Dynamics/Electric Boat (EB). The distillate was filtered through S&S #595 analytical paper to remove debris from the machine then through a sterilized 0.15-micron filter.

Sample 22 (Electrolysis) — The sample was recovered by passing a d-c current (2 amperes) through a 1-liter beaker filled with untreated urine. A platinum plate (+) and a platinum gauze (−) were used as the electrodes. The urine was cooled by means of a water bath into which the beaker was placed. Six volts were applied to the electrodes. The electrolyzed product was filtered through S&S #595 paper.

Sample 23 (Ultrafiltration) — Three liters of urine were pretreated with 4.3 grams of urease and mixed for 61 hours at room temperature. The digested urine was filtered through coarse filter paper to remove sediment and excess urease. Citric acid (143 gm) was added for ammonia neutralization.

Sample 24 (Ultrafiltration) — Three liters of urine were processed after being pretreated with 4.3 grams of urease, mixed for 66 hours at room temperature, filtered and 98 grams of citric acid added.

Samples 26 and 27 (Membrane Permeation) — The urine was processed without pretreatment.

Sample 33 (Ultrafiltration) — The urine (2.6 liters) was processed after being pretreated with 7 grams of urease, mixed for 64 hours at room temperature, filtered and 237 grams of citric acid added.

Sample 136 (Ultrafiltration) — This sample was processed in the same manner as sample 33 except that an unused membrane was installed in the recovery device.

Samples 138 and 139 (Electrolysis) — For each sample, 2 liters of urine were processed for 24 hours at 9 volts and 10 amperes. All values are approximate.

Sample 174 — This is distilled water (DW). It is included for comparison purposes.

Sample 175 — Urine was processed by electrolysis for 24 hours at 9 volts and 10 amperes then by ultrafiltration. The first process was intended to remove the organics; the second to remove the salts.

Sample 191 — This sample (TW) was taken from the fresh water tap of the Wright-Patterson water distribution system. It is included for comparison purposes.

Samples 194-196 (Electrolysis) — These were recovered from urine in the manner shown for samples 138 and 139. They were pooled then treated as follows:

Sample 194 — No treatment.

Sample 195 — Filtered up through a 6-inch long by 1-inch diameter column of 12 x 30 mesh pecan shell activated charcoal at approximately 3 liters per hour.

Sample 196 — Filtered through the pecan shell filter then through an ion exchange resin (Filter-Ion).

Samples 78 and 266-269 — These were recovered by electrodialysis.

Samples 249 and 250 — Urine was electrolyzed at approximately 9 amperes and 5-6 volts d-c for 24 hours and then forced (ultrafiltration) through a cellulose acetate membrane having a thickness of approximately 5 mils and a pore size of less than 1 μ .

ELECTRODIALYSIS — See table Ia.

All samples reclaimed by electrodialysis were recovered by a system purchased from Ionics, Incorporated (I). Effort was made to follow the operating instructions outlined by the manufacturer even though the early recovery attempts were frequently attended with mechanical and electrical difficulties. Following the recovery of sample 134, a fire in the base of the unit destroyed almost all of the electrical components making it necessary to return the device to the manufacturer for repair. Samples 266-269, table Ib were recovered after the reworked unit was delivered to AMRL.

The variations noted in the samples recovered were probably the result of differences in the composition of the urine processed and because of the residue which accumulated inside the stack. Samples 85 and 102 through 113 were recovered inside the AMRL Evaluator during one of several nutrition experiments conducted by AMRL for NASA (Houston). One liter of urine was processed during each run.

THERMOELECTRIC — See tables Id and Ie.

Urine processed by means of the thermoelectric distillation unit supplied by Whirlpool Corporation (W) was pretreated with 2 grams of trimethylol nitromethane (TN), with one iodine tablet (I) per liter of urine, or with 3.6 ml of a mixture of chromium trioxide, sulfuric acid, and distilled water. Each iodine tablet contained tetraglycene hydroperiodide and liberated 8 milligrams of iodine. Unless otherwise specified, the pretreatment used is indicated by (TN) or (I) at the end of the sample description.

In most cases, the product recovered by the thermoelectric device was forced through an internal charcoal filter to a water storage tank that was lined by a plastic bag. The water sample was drained from the storage tank. One liter of material was processed on each run.

Following is a discussion of the processing of the individual samples:

Table Id

Samples 38-41 — The water recovered on each run was not further altered. (TN)

Samples 42, 43, and 49-51 — These were recovered inside the AMRL Evaluator during a

nutrition experiment conducted for NASA, Houston. The urine was a mixture of that voided by the subjects and was 24-36 hours old when processed. Samples 42, 43, and 49 were pumped through a 0.15-micron filter. Samples 50 and 51 were from a 3-day pool of recovered water. Sample 51 was passed through a "Piodene" filter*. (TN)

Samples 97-99 — These represent the product produced on the dates indicated. For example, the product obtained on 1/20, 1/21, and 1/22 was pooled to provide sample 97. (TN)

Sample 100 — This sample was the residue from the vacuum trap of the distillation unit. It was, reportedly, of the same composition as samples 97-99 except that it has not been passed through the filter of the distillation unit.

Samples 101 and 117 — These were drawn from the storage tank of the distillation unit and are comparable in method of collection to samples 97-99. (I)

Samples 114-116 — These samples were, after being drawn from the storage tank of the distillation unit, filtered through a Millipore AP2004200 prefilter and a HAWP 0 47 00 filter (HA 0.45 μ). For sample 115, an S&S #595 filter was used ahead of the Millipore prefilter. (I)

Sample 118 — This sample was recovered from the residue in the vacuum trap of the distillation unit. It was filtered through the following: 2-inch long by 1-inch diameter column of activated carbon (Columbia Type C-64 Mesh 48-150), S&S #595 filter paper, Millipore AP2004200 prefilter, and Millipore HAWP 0 47 00 filter (HA 0.45 μ) in the order listed.

Samples 242-246 — These were processed without pretreatment and with the plastic bag of the storage tank and carbon of the filter removed from the distillation unit.

Table 1e

Sample 174 — Distilled water. Not processed in any manner.

Sample 135 — Obtained by processing distilled water drawn from the same bottle as was sample 174. The sample shows the elements that were added to the recovered water by the machine.

Sample 137 — This sample was obtained from urine following the processing of distilled water; i.e., sample 135. (I)

Samples 149-161 and 183-185 — The urine was pretreated, refrigerated overnight, and processed the next morning. Except as noted below, all samples were circulated for 15 minutes at 165 F (73.9 C) through a heat exchanger. (I)

Samples 183 and 184 — These were drawn from a 3-day pool of unheated recovered product. Sample 183 was then circulated for 15 minutes at 165 F. (I)

Samples 186 and 187 — These were obtained by processing atmospheric condensate collected inside the AMRL Evaluator during a 36-hour, 3-man heat test. The inside of the Evaluator was maintained at approximately 95 F (35 C).

Samples 189, 190, and 197 — The urine processed to obtain these samples was pretreated with 3.6 ml of a mixture of $\text{CrO}_3 + \text{H}_2\text{SO}_4 + \text{H}_2\text{O}$ per liter of urine.

NOTE: Samples 186, 187, 189, 190, and 197 were processed with the plastic bag of the storage tank and the carbon of the filter removed from the distillation unit.

*A 6-inch long by 1/4-inch diameter column of tetramethylammonium triiodide.

DEHUMIDIFICATION — See tables If, Ig, Ih, and Ii.

Condensate for the dehumidification samples except one sample, was collected inside the AMRL Life Support Systems Evaluator during a series of nutritional experiments conducted for MSC/NASA, Houston, Texas. Excess water in the atmosphere of the Evaluator was condensed by means of a heat exchanger and drained to a collector (aspirator bottle) from whence it is drawn directly or pumped through one or more filters.

All samples were stored in glass bottles and refrigerated at approximately 36 F until submitted to Taft Sanitary Engineering Center for analyses.

Details of the processing follow:

Table If

Sample 21 — This sample was recovered by means of a commercial home type dehumidifier located inside a room occupied by 4 subjects that were confined to the room for nutrition and pressure suit studies. Three days were required to collect the sample which was then filtered through a 0.15-micron filter. All components except the dehumidifier were sterilized prior to use.

Samples 28, 30, and 34 — These were not filtered or altered otherwise.

Samples 29, 31, 35, and 36 — These were filtered through a 0.15-micron filter.

Sample 37 — This sample consisted of ½ of sample 36 which was refiltered by means of a second 0.15-micron filter.

Samples 44-47 — The condensate was pumped from the aspirator bottle through a 0.15-micron filter and a 0.9-micron plus carbon filter in tandem.

Sample 48 — Not filtered. The sample was drawn directly from the collector.

Samples 52 and 53 — Filtered, pumped through a 0.15-micron and a 0.9-micron plus carbon filters in tandem, condensate collected over a 2-day period was pooled. Samples 52 and 53 were drawn from the pool. Sample 52 was filtered through a Piodene filter.

Table Ig

All samples were pumped through a 0.15-micron filter and a 0.9-micron plus carbon filter in tandem, unless otherwise noted.

Sample 54 — The sample was taken directly from the aspirator bottle and was not filtered.

Sample 61 — The sample was refiltered through Piodene filter.

Sample 64 — This sample is one-half of a mixture of two of the three lots of condensate collected during a 24-hour period.

Sample 65 — This sample is the remaining portion of the mixture from which sample 64 was taken. The sample was refiltered through Piodene filter.

Sample 66 — This sample represents the third or unmixed lot referenced under sample 64.

Samples 70, 73, and 75 — Each is a filtered sample to which one iodine tablet (tetraglyciene hydroperiodide) was added. The iodine interfered with the analytical testing and very little data were obtained.

Sample 71 — The sample was taken directly from the collector and was not filtered.

Sample 77 — Water taken from condensate that had collected under the floor of the aft compartment of the AMRL Evaluator. It was not filtered nor treated in any manner.

Table Ih

Prior to the taking of samples, the heat exchanger upon which the water was condensed was washed and rinsed in tap water. The condensate filter system was sterilized with cryoxide gas (5 psig) prior to drawing samples 86-96 and was moved to the outside of the Evaluator after sample 96 was drawn. The air filter before the heat exchanger was changed after sample 92 was drawn. The condensate was taken directly from the collector or pumped through a 0.9-micron plus carbon filter and two 0.15-micron filters in tandem.

Samples 86-95 — These samples were filtered.

Sample 96 — This sample was not filtered.

Samples 119, 120, and 122 — These were pumped through the filters used for samples 86-95. The filters had been rinsed thoroughly in tap and distilled water then sterilized at 20 psig for more than 24 hours with cryoxide gas.

Sample 121 — Same as sample 122 except that it was unfiltered.

Samples 123-128 — These were pumped through new 0.9-micron plus carbon and two 0.15-micron filters that had been sterilized by autoclaving.

Sample 129 — This sample was drawn directly from the collector.

Table Ii

The condensate was drained into a collector from which it was pumped up through a 9-inch long by 4-inch diameter column of 48 x 150 mesh acid-washed carbon then through two 0.15-micron filters all in tandem.

Samples 142, 146, and 147 — These were not otherwise altered after being filtered.

Samples 179 and 180 — These were drawn from a pooled lot. Sample 180 was then circulated at 165 F (73.9 C) for 15 minutes. Sample 179 was not altered.

Other Samples — All samples other than those listed above were altered as follows. One liter of each was circulated at 165 F (73.9 C) for 15 minutes then poured back into the sample after approximately 25 ml were removed for testing.

OTHER TECHNIQUES

Samples recovered from dehumidification water collected inside the AMRL Evaluator are included with water recovered by means of fuel cells and by vacuum distillation. Details follow:

Table Ij

Samples 140-141 and 143-145 — These are unfiltered samples drawn directly from the aspirator bottle.

Sample 188 — This is an unfiltered sample of condensate collected during a 36-hour, 3-man heating capability evaluation (27 May 1965) of the AMRL Evaluator.

Sample 192 — This is unfiltered condensate from a 23 June 1965, 36-hour, 3-man heating capability evaluation of the AMRL Evaluator.

Sample 193 — This sample from the 23 June evaluation was filtered up through a 6-inch long by 1-inch diameter column of 12 x 30 mesh acid-washed pecan shell activated charcoal at the rate of 3 liters per hour.

Samples 200 and 248 — These samples were obtained from fuel cells of the type that were used during "Gemini" flights. Further data were not made available.

Sample 201 — This sample was reportedly obtained by vacuum distilling urine and passing the vapors through a low-temperature catalytic agent. The equipment and technique used were of a proprietary nature.

Samples 206-209 and 247 — All were recovered by vapor distillation. Except for sample 206, the vapors were passed through a 2-micron average pore size glass fiber cloth impregnated with porous "Teflon." For sample 206, nothing was inserted between the evaporator and the condensers. Temperatures at which the urine was evaporated were: Nos. 206 and 207 — 128 F (53.3 C), No. 208 — 100 F (37.8 C), No. 209 — 70 F (21.1 C), and No. 247 — 125 F (51.7 C). Pressures at which the evaporation occurred varied from 60 mm to 140 mm.

TABLE Ia
ANALYTICAL RESULTS — RECLAIMED WATERS

type sheet #1

2

PROCESS, SEE SECTION II		VC	VC	VC	VC	VC	VC	VC	VC	VC	VC	VC	VC	VC	VC	VC	VC	VC	VC	U. S. PUBLIC HEALTH DRINKING WATER STANDARDS (1962)
MANUFACTURER		MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	MRD	
SAMPLE No. (TC)		1	2	3	4	5	6	7	10	11	12	14	15	16	17	18	19	20	25	32
DATE SAMPLE RECOVERED*		12-20-62	2-27-63	2-27-63	4-8-63	4-17-63	6-5-63	9-11-63	2-19-64	2-20-64	2-24-64	2-25-64	3-2-64	3-3-64	3-4-64	3-10-64A	3-10-64B	3-11-64	6-30-64	7-30-64
VOLUME OF SAMPLE (ml)		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SPECTROGRAPHIC DATA (ppb)																				
1	ZINC	<3	14.2	<.7	5	2	<5	15	<20	<20	<20	<10	<20	<20	<20	<20	<20	<20	<20	5000
2	CADMIUM	<3	<3	<.4	<1	<1	<1	<2	<5	<5	<5	<3	<10	<10	<10	<10	<10	<10	<3	10R
3	BORON	-	880	150	250	35	125	200	78	28	36	19	45	36	18	70	40	45	-	6
4	PHOSPHORUS	-	-	-	147	250	<5	>1000	<20	30	25	104	55	250	200	42	<20	<20	-	<5
5	IRON	<3	32.3	15	>500	150	85	22	15	10	18	158	<5	10	<5	<5	<5	25	-	31
6	MOLYBDENUM	18	<3.3	<3.5	<1	1	<10	<5	10	<10	<10	<5	<5	<5	<5	10	<5	<5	-	<5
7	MANGANESE	0.1	<1	<1	11	0.5	<5	5	2.5	2	1.5	2.6	<2	<2	<2	5	<2	<2	-	<5
8	ALUMINUM	Pos.	Pos.	Pos.	-	>1000	>2500	700	4000	1620	2250	2525	3500	2500	3500	50	150	150	-	175
9	BERYLLIUM	<.06	<.02	<.02	<.03	<.03	<.03	<.05	<.03	<.03	<.03	<.01	<.03	<.03	<.03	<.03	<.03	<.03	-	<.03
10	COPPER	0.8	7.3	3.3	7	1.5	2	23	5	7	6.5	9.9	9	24	24	10	7	10	-	<2
11	SILVER	0.01	<.1	<.1	<.2	<.2	<.2	<.5	<.3	<.3	<.3	<.3	<.3	<.3	<.3	<.3	<.3	<.3	-	<.3
12	NICKEL	<.3	<.7	<.7	<.5	<.5	8	20	<.5	<.5	<.5	21.5	<.5	10	8	20	<.5	<.5	-	<.3
13	COBALT	<.3	<.7	<.7	<.2	<.2	<.2	<.5	<.5	<.5	<.5	<.3	<.5	<.5	<.5	<.5	<.5	<.5	-	<.3
14	LEAD	<.6	<.7	<.7	<.5	<.5	<.5	<.5	<.5	<.5	<.5	<.3	<.5	<.5	<.5	<.5	<.5	<.5	-	<.5
15	CHROMIUM	0.1	<.7	<.7	<.5	<.5	<.1	8	<.5	<.5	4.5	23	<.5	<.5	<.5	<.5	<.5	<.5	-	<.1
16	VANADIUM	6	<.7	<.7	<.1	1	<.1	<10	<.5	<.5	<.5	<.3	<.5	<.5	<.5	<.5	<.5	<.5	-	<.5
17	BARIUM	0.6	0.7	0.1	47	29	10	2.7	<.3	<.3	10	4	<.3	<.3	<.3	<.3	<.3	2	-	1.4
18	STRONTIUM	-	0.3	<.4	9	10	8	20	<.5	<.5	<.5	4	<.5	<.5	<.5	<.5	<.5	12	-	1.5
19	MERCURY	-	Neg.	Neg.	115	25	<25	<50	<20	<20	<20	<20	<20	40	<20	<20	<20	<20	-	<20
CATIONS (mg/l)																				
1	CALCIUM (Ca)	0.6	0.3	0.08	2.4	3.2	4.8	3.2	<2	<2	<2	<2	-	-	-	-	-	-	-	2.4
2	MAGNESIUM (Mg)	0.12	1.8	1.8	1	0.5	1.5	1.9	<2	<2	<2	<2	-	-	-	-	-	-	-	1
3	SODIUM (Na)	35	28	0.5	47	25	6.5	17	52	13	2.5	2.5	18	15	9	3.5	78	<1	31	120
4	POTASSIUM (K)	0.2	<.1	0.1	0.3	19	9.4	12	2.8	1.2	0.2	1.7	1.2	52	5.1	1.6	4.1	<1	1.8	6.5
5	ARSENIC (As)	<.1	<.01	<.01	<.01	<.01	<.01	<.01	0.03	<.01	<.01	<.01	<.01	<.01	0.016	-	0.046	-	-	0.05
6	AMMONIA (NH ₃ /N)	0.025	1.3	13.8	1.8	4.5	47	26	7.5	5	5	10	6.5	16	14	2.2	2.2	0	14	10
ANIONS (mg/l)																				
1	SULFATE (SO ₄)	4	2	3	62	5	8	13	57	14	2	4	23	5	5	6	88	<1	-	176
2	CHLORIDE (Cl)	4	3	2	21	7	8	20	Pos.	Pos.	Pos.	2	1	10	10	2.5	2.5	<1	2.5	3.5
3	NITRATE (NO ₃ /N)	<.01	<.1	<.1	<.01	<.01	<.1	-	0.4	<.1	<.1	<.1	0.1	0.1	0.1	-	0.1	<.1	0.8	<.1
4	TOTAL PHOSPHATE (PO ₄)	0	0.02	0.08	0.065	0.3	0.01	1.2	0.18	0.25	0	0.25	<.01	<.01	<.01	-	-	-	0.05	<.01
5	ABS	-	0.04	0.24	<.01	<.01	0.04	-	0.15	0.05	0.06	0.07	<.05	<.02	<.02	-	-	-	-	0.5
6																				
OTHER TESTS																				
1	pH	8.1	7.7	8.3	6.8	10.1	8.6	7.2	8.7	8.4	8.2	8	9	9	9	8	10.3	6.9	-	7.9
2	CONDUCTIVITY (µmhos/cm)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3	TURBIDITY-JACKSON UNITS	<25	<25	<25	-	-	<25	<25	<25	<25	<25	<25	<25	<25	<25	<25	<25	<25	-	-
4	COLOR	<5	0	0	<5	<5	<5	5	-	-	-	-	-	-	-	-	-	-	-	15
5	ODOR	111	19	54	-	1.7	8	-	8	28	28	1.6	Neg.	Neg.	Neg.	Neg.	Neg.	Neg.	24.3	3
6	TOTAL HARDNESS (CaCO ₃)	2	8	8	10	10	18	16	<4	<4	<4	<4	<4	6	6	4	4	8	12	10
7	TOTAL ALKALINITY (CaCO ₃)	70	56	44	16	72	23	48	74	56	42	36	66	60	60	-	-	54	-	120
8	TOTAL SOLIDS	86	75	10	150	128	90	-	230	69	87	43	70	57	59	-	-	77	118	374
9	CHEM O ₂ DEMAND	18	24	62	23	23	170	200	40	33	37	37	47	60	50	90	66	40	450	730
10	UREA	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	Neg.	-
11	TOTAL PLATE COUNT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
12	TOTAL CARBON	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

*Pooled samples may be 2 or 3 days older
Neg.=Not detected
R = Rejection level

TABLE Ib
ANALYTICAL RESULTS - RECLAIMED WATERS

PROCESS, SEE SECTION II		VC	E	UF	UF	MP	MP	MP	UF	E	E	AMRL	AMRL	DW	E&UF	TW	E	E	E	AMRL	AMRL	E	ED	ED	ED	E&UF	E&UF	U. S. PUBLIC HEALTH DRINKING WATER STANDARDS (1962)
MANUFACTURER		EB	AMRL	RAI	RAI	I	I	I	RAI	AMRL	AMRL	AMRL	AMRL	AMRL	AMRL	AMRL	AMRL	AMRL	AMRL	AMRL	AMRL	I	I	I	I	AMRL	AMRL	
SAMPLE No. (TC)		13	22	23	24	26	27	33	136	138	139	174	175	191	194	195	196	78	266	267	268	269	269	249	250			
DATE SAMPLE RECOVERED**		2-25-64	7-1-64	6-26-64	6-30-64	7-7-64	7-8-64	7-11-64	3-19-65	4-15-65	4-20-65	3-17-65	5-4-65	6-15-65	6-25-65	6-25-65	6-25-65	12-21-64	1-17-66	1-19-66	1-26-66	1-27-66	1-28-66	9-8-65	9-16-65			
VOLUME OF SAMPLE (ml)		1600	1200	1200	—	—	—	2000	1500	1900	2000	4000	1500	3500	3000	3000	3000	850	3250	3475	3640	1750	4000	4000				
SPECTROGRAPHIC DATA (ppb)																												
1	ZINC	<44	—	—	—	—	—	<3	12	107	102	29	22	15	<33	<33	<20	40	<20	<20	<20	<20	<20	20	40	5000		
2	CADMIUM	<11	—	—	—	—	—	<3	<10	<26	102	<10	<10	<10	<33	<33	<20	<10	<10	<10	<10	<10	<10	<10	<20	10 R		
3	BORON	28	—	—	—	—	—	3	21	255	238	5	325	36	500	583	>500	175	38	48	50	48	425	225				
4	PHOSPHORUS	<44	—	—	—	—	—	<5	<15	*	*	70	*	*	*	*	*	>500	>500	>500	<50	50	*	*				
5	IRON	<11	—	—	—	—	—	21	<2	<17	<17	138	78	295	<17	<17	<10	18	35	35	20	80	30	300				
6	MOLYBDENUM	<22	—	—	—	—	—	<5	<10	<34	<34	<10	<10	110	<33	<33	<20	<5	<20	<20	<20	<10	<10	<20				
7	MANGANESE	3.6	—	—	—	—	—	0.8	<3	<3.4	<3.4	1.5	<5	23	<5	<5	<3	21	<2	11	<2	<2	<3	<5	50			
8	ALUMINUM	5185	—	—	—	—	—	75	<13	<42	<42	<13	115	13	<42	<42	<25	88	<20	<20	80	53	<13	<25				
9	BERYLLIUM	<.05	—	—	—	—	—	<.03	<.03	<.09	<.09	<.03	<.03	<.05	<.08	<.08	<.05	<.03	<.05	<.05	<.05	<.05	<.03	<.05				
10	COPPER	81	—	—	—	—	—	<2	<2	128	95	7	41	2	<5	<5	<3	29	<2	14	<2	<2	35	460	1000			
11	SILVER	<.5	—	—	—	—	—	<.3	<.5	<1.7	<1.7	<1	2.5	<.5	<1.7	<1.7	<1	8	<1	<1	3.5	<.5	<.5	<1	50 R			
12	NICKEL	<11	—	—	—	—	—	<3	<5	<17	<17	<5	50	<5	<17	<17	<10	8.5	24	115	40	26	60	>1000				
13	COBALT	<11	—	—	—	—	—	<3	<5	<17	<17	<5	<5	<5	<17	<17	<10	<3	<10	<10	<10	<10	<5	<10				
14	LEAD	<11	—	—	—	—	—	<5	<10	<34	<34	<10	<10	<10	<33	<33	<20	<5	<20	<20	<20	<10	<10	<20	50 R			
15	CHROMIUM	<11	—	—	—	—	—	<1	<3	<9	<9	27	<3	<3	<8	<8	<5	6	<5	<5	<5	<5	<3	<5	50 R			
16	VANADIUM	<11	—	—	—	—	—	<5	<10	<34	<34	<10	<10	<10	<33	<33	<20	<20	<20	<20	<20	<20	<10	<10				
17	BARIUM	<6	—	—	—	—	—	5	6	<2	<2	<1	5	45	<2	23	<1	4	3	4	<2	3	<1	<1	1000 R			
18	STRONTIUM	<17	—	—	—	—	—	27	<1	<4	<4	<2	20	400	<5	<5	<3	15	18	12	2	5	<1	<2				
19	MERCURY	<44	—	—	—	—	—	<20	<25	<170	<170	—	<50	—	<50	<50	<50	<30	—	—	—	—	<50	<50				
20																												
CATIONS (mg/l)																												
1	CALCIUM (Ca)	<2	—	—	—	—	—	8.8	—	112	88	—	9.2	20	52	115	48	—	6.4	4.8	2.4	1.6	48	120				
2	MAGNESIUM (Mg)	<2	—	—	—	—	—	4.3	—	41	24	—	11	9.7	36	66	<1	—	6.8	4.9	1.2	1.9	14	12				
3	SODIUM (Na)	126	370	56	212	85	7	106	210	3550	3500	<1	225	26	2600	2600	2100	28	92	44	7	5.5	170	1250				
4	POTASSIUM (K)	11	—	269	100	860	6.6	17	140	3600	2700	<1	194	3.5	2300	2400	1500	15	75	44	4	3	310	1400				
5	ARSENIC (As)	0.068	—	0.23	—	—	—	0.02	0.02	—	—	<.05	<.01	<.01	<.01	<.01	<.01	0.08	0.01	0.016	0.016	0.025	<.01	<.01	.05 R			
6	AMMONIA (NH ₃ /N)	67	—	62	95	3.5	0.1	25	35	ppt	ppt	0	ppt	0.1	ppt	ppt	ppt	ppt	13	11	2.5	3	50	50				
7																												
ANIONS (mg/l)																												
1	SULFATE (SO ₄)	—	—	—	—	—	—	150	60	1700	1600	2	16	137	1300	142	1130	10	30	20	4.0	3.5	19	620	250			
2	CHLORIDE (Cl)	—	—	—	—	—	46	144	290	4650	2200	<1	190	48	1200	1100	1200	19	160	76	6.0	4.5	160	1200	250			
3	NITRATE (NO ₃ /N)	0.2	—	167	350	0.1	<.1	<.1	32	710	>10	<.1	125	0.22	3.2	>50	>50	—	24	12	0.1	0.2	150	200	45			
4	TOTAL PHOSPHATE (PO ₄)	0.65	—	44	5	78	5	<.01	6	300	340	<.05	20	<.05	122	122	122	—	30	28	0.9	0.5	50	1100				
5	ABS	—	—	—	—	—	—	0.03	—	—	—	—	—	<.02	—	—	—	—	—	—	—	—	—	—	0.5			
6																												
OTHER TESTS																												
1	pH	—	—	—	—	—	—	7	8.4	2.7	4.7	6.9	2.6	7.6	3.8	5.5	3.3	—	7.3	7.8	8.4	7.8	2.5	2.4				
2	CONDUCTIVITY (μmhos/cm)	—	—	—	—	—	—	—	1800	14,000	1400	5.7	3100	960	9000	8000	7000	235	1000	540	110	75	3800	10,000				
3	TURBIDITY—JACKSON UNITS	<25	—	—	>25	—	—	—	<25	—	—	—	—	—	—	—	—	—	<25	<25	<25	<25	Clear	Clear				
4	COLOR	—	—	—	—	—	—	—	—	<5	<5	<5	5	15	10	10	10	—	<5	<5	<5	<5	25	10	15			
5	ODOR	84	Toluene Strong	Neg.	Neg.	Neg.	Neg.	Neg.	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	3			
6	TOTAL HARDNESS (CaCO ₃)	<4	—	48	14	—	—	40	10	450	300	4	70	90	280	560	120	—	44	32	12	12	180	350				
7	TOTAL ALKALINITY (CaCO ₃)	—	—	—	—	—	—	174	100	0	—	6	0	250	0	168	0	—	64	32	36	8	0	0				
8	TOTAL SOLIDS	380	>1000	700	—	—	—	373	1700	—	—	<10	1250	—	—	—	—	—	—	—	—	—	—	—	500			
9	CHEM O ₂ DEMAND	59	—	16	1300	50 without Cl correct'n	0	1800	2100	3600	1300	4	1000	15	2240	2600	2100	—	175	200	44	56	2340	6400				
10	UREA	—	—	Neg.	Neg.	Pos.	Pos.	—	214	<.1	<.1	<.1	<.1	<.1	<.1	<.1	<.1	17	75	75	50	50	0.3	0.2				
11	TOTAL PLATE COUNT	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—				
12	TOTAL CARBON	—	—	—	—	—	—	—	790	170	820	0	490	<.5	1400	975	1300	10	312	325	75	50	1130	2600				

*Major constituent
 **Pooled samples may be 2 to 3 days older
 Neg. = Not detected

TABLE 1c
ANALYTICAL RESULTS – RECLAIMED WATERS

PROCESS, SEE SECTION II		ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	ED	U. S.		
MANUFACTURER		I	I	I	I	I	I	I	I	I	I	I	I	I	I	I	I	I	I	I	I	I	I	I	I	PUBLIC HEALTH		
SAMPLE No. (TC)		79	80	81	82	83	84	85	102	103	104	105	106	107	108	109	110	111	112	113	130	131	132	133	134	DRINKING WATER		
DATE SAMPLE RECOVERED**		12-22-64	12-23-64	12-24-64	1-5-65	1-13-65	1-14-65	1-20-65	1-21-65	1-22-65	1-26-65	1-27-65	1-29-65	2-2-65	2-4-65	2-5-65	2-9-65	2-10-65	2-11-65	2-11-65	2-17-65	2-18-65	2-24-65	2-26-65	3-1-65	STAND-ARDS		
VOLUME OF SAMPLE (ml)		850	1800	850	800	900	900	850	620	930	900	870	850	810	675	650	675	525	725	560	850	870	840	850	850	(1962)		
SPECTROGRAPHIC DATA (ppb)																												
1	ZINC	17	95	14	104	3	10	60	47	57	44	32	5	32	35	<10	72	55	<10	<10	410	40	16	25	15	5000		
2	CADMIUM	<10	<10	<20	<16	<10	<10	<20	<10	<10	<20	<10	<10	<10	<10	<10	<12	<10	<10	<10	<20	<20	<20	<15	<13	10 R		
3	BORON	175	130	40	46	54	19	30	38	64	31	84	26	87	45	85	84	90	26	250	235	76	56	32				
4	PHOSPHORUS	250	>500	>1000	>800	>500	400	290	76	>600	>500	450	>1000	220	60	>1000	24	60	>1000	300	*	*	*	*	*			
5	IRON	56	275	10	>800	34	105	58	4	10	45	43	9	73	110	<5	108	75	5	30	117	29	10	5	28	300		
6	MOLYBDENUM	<5	<5	<10	60	55	<5	<10	<4	21	<5	<5	<10	<5	<10	<10	<12	<10	<10	<10	<20	<20	<20	<15	<13			
7	MANGANESE	4.5	14	2.5	16	1	2	3	2.4	6.9	3	2	2.3	4	<1	<1	<1.2	<1	<1	17	<5	<5	<4	<3	50			
8	ALUMINUM	17	4	7	760	9	105	20	<2	<3	4	<3	<5	<3	<3	<3	<3	70	<3	5	<25	<25	<25	<19	<16			
9	BERYLLIUM	<.03	<.03	<.05	<.04	<.03	<.03	<.05	<.02	<.03	<.03	<.03	<.05	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.05	<.05	<.05	<.04	<.03			
10	COPPER	14	9	19	29	6	13	35	47	26	38	25	12	23	10	<2	5	2	3	<2	<3	10	39	8	2	1000		
11	SILVER	5.4	6	6	6	<.5	2	4	1.4	5	1	0.8	<1	1.3	1	<.5	<.6	<.5	<.5	<1	<1	<1	<.8	<.6	50 R			
12	NICKEL	7	23	<5	10	<3	<3	<5	<2	<3	<3	<3	<5	<3	<3	<3	<3	<3	<3	<10	<10	<10	<.8	<.6	<6			
13	COBALT	<3	<3	<5	<4	<3	<3	<5	<7	<21	<3	<3	<5	<3	<3	<3	<3	<3	<3	<10	<10	<10	<.8	<.6	<6			
14	LEAD	<5	<5	<10	<8	<5	<5	<10	6	6	<5	<5	<10	<5	<5	<5	<6	<5	<5	<20	<20	<20	<15	<13	50 R			
15	CHROMIUM	14	31	6	105	12	22	10	2.4	7	6	9	5	6	5	<1	6	5	<1	1	22	<5	<5	<4	<3	50 R		
16	VANADIUM	<20	<20	<40	<32	<20	<20	<40	<20	<20	<20	<20	<20	<20	<20	<20	<24	<20	<20	<20	<20	<20	<15	<13				
17	BARIUM	3	2	2	3	<1	6	11	7	4	3	2.3	<1	3	50	8	48	45	75	45	4	5	3	75	20	1000 R		
18	STRONTIUM	11	<3	<2	<2	<3	5	<2	<.8	2	<1	<1	<2	<1	<.5	8	<6	<5	<5	10	7	6	4	5	<1			
19	MERCURY	<30	125	80	560	<30	70	<30	<30	<30	<30	<30	<30	<30	100	<40	60	<40	<40	180	<50	<50	300	188				
20																												
CATIONS (mg/l)																												
1	CALCIUM (Ca)	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—		
2	MAGNESIUM (Mg)	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—		
3	SODIUM (Na)	20	56	68	12	80	25	33	28	45	41	42	160	30	190	30	26	28	71	37	135	40	35	158	495			
4	POTASSIUM (K)	10	38	9.5	6.2	54	14	24	18	35	27	27	120	17	15	157	9	14	38	24	78	21	14	82	250			
5	ARSENIC (As)	0.05	0.04	0.04	0.07	0.09	0.06	0.04	—	0.04	0.04	0.04	0.01	0.05	0.05	0.02	0.1	0.11	0.11	0.11	0.03	0.07	0.07	0.13	0.16	.05 R		
6	AMMONIA (NH ₃ /N)	—	5.2	6	ppt	6	2.5	3.1	2.6	4.2	3.5	3.8	16	2.8	3.8	25	1.9	3.1	5.6	3.5	29	15	16	39	59			
7																												
ANIONS (mg/l)																												
1	SULFATE (SO ₄)	25	—	26	—	28	15	17	—	—	—	—	—	—	18	80	—	21	22	23	82	35	31	50	100	250		
2	CHLORIDE (Cl)	13	79	93	18	117	25	44	27	63	50	60	275	26	22	220	14	20	83	38	147	53	160	44	530	250		
3	NITRATE (NO ₃ /N)	—	—	—	—	—	—	—	<.1	<.1	<.1	0.12	1	<.1	0.12	19	<.1	<.1	0.1	<.1	4	1.6	<.1	0.45	24	45		
4	TOTAL PHOSPHATE (PO ₄)	—	—	—	—	—	—	—	<.01	0.15	0.07	0.07	0.65	0.02	—	0.76	<.05	<.05	0.4	0.93	77	7	120	7	240			
5	ABS	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	0.5		
6																												
OTHER TESTS																												
1	pH	—	—	—	—	—	—	—	7.5	7	6.5	6.3	6.3	7	7.4	7.7	7.3	7.5	7.1	7.2	7.7	7.6	7.2	7.2	7.6			
2	CONDUCTIVITY (μmhos/cm)	182	750	830	—	750	260	560	390	540	480	480	1460	360	260	1840	200	280	610	340	1200	490	430	1360	3500			
3	TURBIDITY—JACKSON UNITS	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	<25	>25	>25	>25	>25			
4	COLOR	—	—	—	—	—	—	—	—	—	—	—	—	—	<5	—	—	—	—	—	<5	—	—	—	—	15		
5	ODOR	—	—	—	—	—	—	—	—	—	—	—	—	—	—	Pos.	—	—	—	—	—	—	—	—	—	3		
6	TOTAL HARDNESS (CaCO ₃)	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	10	—	—	30	16	12	18	18			
7	TOTAL ALKALINITY (CoCO ₃)	—	—	—	—	—	—	—	—	—	—	—	—	—	8	—	—	—	—	—	174	110	80	180	410			
8	TOTAL SOLIDS	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	942	1462	1158	1400	2700	500		
9	CHEM O ₂ DEMAND	—	—	—	—	—	—	—	260	174	205	360	36	40	75	138	29	59	53	67	1400	2300	2000	2000	2300			
10	UREA	5	120	85	120	38	80	17	300	180	105	115	105	125	17	70	5	46	5	2	105	125	148	120	148			
11	TOTAL PLATE COUNT	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—		
12	TOTAL CARBON	7.8	32	31	49	7.6	12	155	—	—	—	—	—	16	—	—	—	—	—	—	475	985	805	830	740			

*Major constituent
**Pooled samples may be 2 to 3 days older
Pos. = Present in trace quantities
ppt = Precipitate formed. No readout obtained.
— = No data available
R = Rejection level

TABLE 1e
ANALYTICAL RESULTS – RECLAIMED WATERS

PROCESS, SEE SECTION II MANUFACTURER SAMPLE No. (TC)	DW AMRL 174	TEDw W 135	TE W 137	TE W 149	TE W 150	TE W 151	TE W 152	TE W 153	TE W 154	TE W 155	TE W 156	TE W 157	TE W 158	TE W 159	TE W 160	TE W 161	TE W 183	TE W 184	TE W 185	TEc W 186	TEc W 187	TE W 189	TE W 190	TE W 197	U. S. PUBLIC HEALTH DRINKING WATER STAND- ARDS (1962)	
DATE SAMPLE RECOVERED**	3-17	3-17	3-25	4-15	4-16	4-17	4-18	4-20	4-21	4-22	4-23	4-27	4-28	4-29	4-30	5-4	5-10	5-10	5-11	6-6	6-10	6-11	6-14	8-23		
VOLUME OF SAMPLE (ml)	4000	2400	1825	710	1200	1285	1320	769	1250	1000	1000	1150	1300	1180	1560	1750	2000	2000	1450	2230	2390	2140	1980	2170		
SPECTROGRAPHIC DATA (ppb)																										
1 ZINC	29	13	5	13	110	75	37	45	53	24	55	29	26	26	20	12	<10	<10	16	10	<10	<10	<10	165	5000	
2 CADMIUM	<10	<10	<6	<8	<10	<8	<7	<8	<7	<8	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	30	10 R		
3 BORON	5	6	7	14	10	37	13	7	5	7	19	25	14	14	22	9	10	15	28	13	7	<5	5	200		
4 PHOSPHORUS	70	23	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	*	65	35	>1000	250	400		
5 IRON	138	8	2	49	120	145	185	135	90	85	129	390	91	68	129	95	72	60	173	7	5	<3	4	68	300	
6 MOLYBDENUM	<10	<10	<6	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	—			
7 MANGANESE	15	3	<1	1	2	2.5	2.5	1.5	1	1	1.5	3.5	8	0.5	1	1	<5	<5	1.2	6	2.5	<1	3.5	9	50	
8 ALUMINUM	<13	400	>290	245	375	315	320	340	325	305	280	>500	>500	>500	>500	>500	>500	>500	700	400	750	190	>500			
9 BERYLLIUM	<.03	<.03	<.01	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.05	<.05	<.05	<.05	<.03		
10 COPPER	7	3	<.9	5	31	29	23	23	18	12	15	14	14	13	15	3	29	<2	31	2	<2	<2	<2	100	1000	
11 SILVER	<1	<.5	<.3	1.5	7	8	6	6	5.3	5	6	4.3	4	3.5	3.5	<.5	1	<.5	3.5	<.5	<.5	<.5	<.5	4	50 R	
12 NICKEL	<5	<5	<3	<5	7	9	11	5	<5	<5	<5	13	<5	<5	<5	<5	<5	8	<5	<5	<5	<5	12			
13 COBALT	<5	<5	<3	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5		
14 LEAD	<10	<10	<6	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	50 R	50 R	
15 CHROMIUM	27	<3	<1	11	24	29	35	25	15	16	13	65	11	7	20	16	13	7	37	<3	<3	<3	<3	13	50 R	
16 VANADIUM	<10	<10	<6	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10		
17 BARIUM	<1	9	12	7	40	22	20	19	25	12	20	8	17	10	6	4	10	1	14	35	17	5	11	8	1000 R	
18 STRONTIUM	<2	18	11	12	7	5	4	3	2	<1	<2	<2	<2	<2	10	<2	<2	<2	80	22	9	19	3			
19 MERCURY	—	<25	15	<50	60	90	140	115	90	<50	180	250	80	75	100	135	90	75	175	—	—	<50	<50	—		
CATIONS (mg/l)																										
1 CALCIUM (Ca)	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	26	14	6.4	14	4		
2 MAGNESIUM (Mg)	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	3.9	2.4	2.4	5.3	2		
3 SODIUM (Na)	<1	2.5	330	10	3.5	3.5	4.0	5.5	5	5	6	7.5	9	4	5.5	5.5	3.8	3.4	10	13	1	120	8.5	2		
4 POTASSIUM (K)	<1	<1	59	8.2	4	3.4	3.7	4.5	4.2	4	3	4.5	5.8	3	3	5	6.3	6.3	16	0.5	<.5	100	8.2	1.4		
5 ARSENIC (As)	<.05	0.01	0.32	0.016	<.01	0.01	<.01	0.012	0.016	0.012	<.01	<.01	<.01	<.01	<.01	<.01	<.01	<.01	<.01	<.01	<.01	0.06	<.01	<.01	.05 R	
6 AMMONIA (NH ₃ /N)	0	6.3	14	44	38	25	25	29	26	23	24	34	44	50	26	93	64	68	100	35	36	16	22	29		
7																										
ANIONS (mg/l)																										
1 SULFATE (SO ₄)	2	3	4	6	5	4	2	8	14	13	11	16	7	5	1	3	4	4	7	16	8	205	17	6	250	
2 CHLORIDE (Cl)	<1	6	70	50	36	21	17	18	14	13	10	20	17	8	8	9	4	8	7.5	32	9	85	64	1.5	250	
3 NITRATE (NO ₃ /N)	<.1	<.1	<.1	<.1	<.1	<.1	<.1	<.1	<.1	<.1	0.1	0.1	<.1	<.1	<.1	<.1	<.1	<.1	<.1	0.16	0.12	0.64	0.18	—	45	
4 TOTAL PHOSPHATE (PO ₄)	<.05	20	21	1.7	1.7	1.6	1.2	2.8	4	3.2	12	10	10	3	2.5	3.5	2.1	2.2	2.5	0.2	0.15	8	2	0.14		
5 ABS	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	0.04	0.04	0.08	0.02	—	0.5	
6																										
OTHER TESTS																										
1 pH	6.9	7.9	8.3	7.8	7.6	7.6	7.5	7.5	7.5	7.5	8.1	8.2	8.5	8.6	8.4	9	8.9	9	9	8.4	8.3	8.1	8.7	7.6		
2 CONDUCTIVITY (µmhos/cm)	5.7	96	700	—	400	300	280	310	270	260	250	390	430	420	290	600	430	405	620	390	265	1080	670	260		
3 TURBIDITY—JACKSON UNITS	—	<25	<25	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—		
4 COLOR	<5	—	—	5	5	5	5	5	5	<5	5	5	5	5	10	5	5	5	5	<5	<5	20	<5	5	15	
5 ODOR	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	3	
6 TOTAL HARDNESS (CaCO ₃)	4	22	18	14	12	10	10	8	10	4	10	8	10	16	12	—	5	4	4	82	46	26	58	18		
7 TOTAL ALKALINITY (CaCO ₃)	6	40	110	—	120	100	104	108	96	84	86	126	192	210	128	400	250	260	414	104	88	128	208	80		
8 TOTAL SOLIDS	<10	26	340	—	—	—	—	—	—	—	42	52	59	46	44	48	—	—	—	—	—	—	—	—	500	
9 CHEM O ₂ DEMAND	4	34	100	225	140	91	48	61	52	42	<1	<1	<1	3.3	<1	64	28	64	22	15	30	300	54			
10 UREA	<.1	<.1	59	60	85	200	Brown ppt	Pos.	Pos.	Pos.	9	6	14	20	16	8	13	10	7	<.1	<.1	30	50	—		
11 TOTAL PLATE COUNT	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—		
12 TOTAL CARBON	0	<.5	8	59	17	9	3.5	3.5	1	3.5	6.5	4	7	8	6.5	4	14	3.5	11	2.8	2.8	12	102	6		

*Major constituent
ppt = Precipitate formed. No readout obtained.

**Pooled samples may be 2 to 3 days older/All dates are 1965
— = No. data available

Pos. = Present in trace quantities
R = Rejection level

TABLE 14
ANALYTICAL RESULTS - RECLAIMED WATERS

PROCESS, SEE SECTION II													U. S. PUBLIC HEALTH DRINKING WATER STANDARDS (1962)						
MANUFACTURER		AMRL		UFC		FC		UFC		FC		AMRL		FC		AMRL		FC	
SAMPLE No. (TC)		21		28		29		30		31		34		35		36		37	
DATE SAMPLE RECOVERED*		3-13-64		8-64		8-64		8-64		8-64		8-20-64		8-28-64		8-28-64		8-28-64	
VOLUME OF SAMPLE (ml)		~1800		3800		3800		3800		3800		3800		3800		3800		3800	
SPECTROGRAPHIC DATA (ppb)																			
1	ZINC	25	210	<3	315	7	1020	83	75	21	325	330	295	385	700	525	1000	5000	
2	CADMIUM	<10	105	<3	91	<2	122	16	10	<2	<10	<10	40	80	66	110	10 R		
3	BORON	5	5	22	7	30	>340	32	90	192	>250	>250	1+0	>200	>250	95	>250		
4	PHOSPHORUS	<20	45	<5	65	5	388	144	100	<16	7	17	<5	<5	35	35	80		
5	IRON	<5	105	16	48	12	228	153	51	13	11	27	16	33	78	61	160	300	
6	MOLYBDENUM	<5	<5	<5	<5	<5	27	<5	<5	<16	<5	<5	<5	<5	<5	<5	<5	50	
7	MANGANESE	<2	13	<5	10.5	8	197	72	48	1.6	29	20	18	20	13	14	56		
8	ALUMINUM	<20	76	21	4	4	193	24	24	8	475	365	15	8	<3	<3	<3		
9	BERYLLIUM	<.03	<.03	<.03	<.03	<.03	<.02	<.02	<.03	<.08	<.03	<.03	<.03	<.03	<.03	<.03	<.03	1000	
10	COPPER	3	33	<2	25	2	45	7	3	<5	10	5	2	2	7	4	4		
11	SILVER	<3	<3	<3	<3	<3	0.7	0.5	<3	<8	<5	<5	<5	<5	<5	<5	0.5	50 R	
12	NICKEL	<5	20	<3	<3	<3	15	4	<3	<8	<3	<3	<3	<3	4	3	7		
13	COBALT	<5	<3	<3	<3	<3	<3	<3	<3	<8	<3	<3	<3	<3	<3	<3	<3		
14	LEAD	<5	<5	<5	<10	<5	14	7	<5	<16	<5	<5	6	<5	20	28	24	50 R	
15	CHROMIUM	<5	4	2	2	2	8	4	4	<3	<1	2	<1	2	4	5	6	50 R	
16	VANADIUM	<5	<5	<5	<5	<5	<7	<5	<5	<16	<5	<5	<5	<5	<5	<5	<8		
17	BARIUM	<3	>500	27	>500	125	>340	>225	>250	77	150	108	115	135	187	108	150	1000 R	
18	STRONTIUM	<5	<1	13	2	14	8	17	19	35	31	31	8	27	<1	6	8		
19	MERCURY	<20	40	<20	<20	<20	<50	<36	<40	<48	<25	<25	<25	<25	<25	<25	<25		
20																			
CATIONS (mg/l)																			
1	CALCIUM (Ca)	-	3.2	5.8	4	4.8	7.2	6.4	7.2	8	16	8	6.4	7.2	3.2	5.6	4.9		
2	MAGNESIUM (Mg)	-	<.1	<.1	0.9	3	5.3	1.5	1.0	1.9	3.4	1.9	<.2	<.2	<.2	2.4	2.9		
3	SODIUM (Na)	<.1	<.5	68	<.1	1.5	7	11	11	71	18	9	2	3	1	2	1.5		
4	POTASSIUM (K)	<.1	0.6	3.2	0.4	1.7	5.5	7.7	4.4	8.3	6.2	4.7	1.7	1.7	0.8	1.4	1.4		
5	ARSENIC (As)	-	<.01	<.01	<.01	<.01	<.01	0.01	0.01	0.05	<.01	<.01	<.01	<.01	<.01	<.01	<.01	.05 R	
6	AMMONIA (NH ₃ /N)	0	20	20	24	24	39	32	24	15	18	16	15	18	16	ppt	15		
7																			
ANIONS (mg/l)																			
1	SULFATE SO ₄	<.1	114	<.1	11	11	7	6	14	107	14	5	1	1	<.1	2	<.1	250	
2	CHLORIDE (Cl)	<.1	<.1	<.1	10	<.1	11	7	6	15	6	1	1	1	44	<.1	<.1	250	
3	NITRATE (NO ₃ /N)	<.1	<.1	<.1	<.1	<.1	<.1	<.1	<.1	<.1	0.7	0.5	0.1	0.2	0.3	<.1	<.1	45	
4	TOTAL PHOSPHATE (PO ₄)	-	<.01	<.01	<.01	<.01	0.43	0.12	0.13	0.15	<.02	<.02	<.02	<.02	<.02	<.02	<.02	0.5	
5	ABS	-	0.05	<.02	0.04	<.02	<.02	<.02	<.02	<.02	0.12	0.06	<.02	0.02	0.04	1.6	0.02		
6																			
OTHER TESTS																			
1	pH	6.9	6.8	7.3	6.9	7	5.9	6.3	5.8	6.7	8	7.4	7.3	7.1	6.9	7.6	6.9		
2	CONDUCTIVITY (µmhos/cm)	-	-	-	-	-	260	300/270	245/240	500	260	210	163	183	160	270	160		
3	TURBIDITY-JACKSON UNITS	<25	-	-	-	-	-	-	-	-	<25	20	<25	<25	-	<25	<25		
4	COLOR	-	-	-	-	-	22	25	20	22	30	<25	5	5	10	20	5	15	
5	ODOR	Sweet Not Urtine	Neg.	Neg.	Neg.	Neg.	38	2	2.6	16	Neg.	Neg.	Neg.	Neg.	Musty	Neg.	Neg.	3	
6	TOTAL HARDNESS (CaCO ₃)	<4	8	16	14	24	40	22	22	28	54	28	16	22	8	24	24		
7	TOTAL ALKALINITY (CaCO ₃)	4	94	122	108	82	66	114	88	130	108	92	80	78	60	72	74		
8	TOTAL SOLIDS	-	<.1	215	<.1	5	136	88	99	315	248	94	28	35	12	406	94	500	
9	CHEM O ₂ DEMAND	15	330	1100	550	515	1300	670	770	1600	5300	2500	1400	1800	1400	1700	1600		
10	UREA	-	-	-	-	-	5	15	7	11	<.1	<.1	<.1	<.1	<.1	<.1	<.1		
11	TOTAL PLATE COUNT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
12	TOTAL CARBON	-	-	-	-	-	470/370	200/165	250/250	700/600	1675	762	438	550	388	-	-		

*Pooled samples may be 2 to 3 days older
Neg. = Not detected
ppt = Precipitate formed. No readout obtained.

– = No data available
R = Rejection level

*Pooled samples may be 2 to 3 days older

Neg. = Not detected

ppt = Precipitate formed. No readout obtained.

TABLE 19
ANALYTICAL RESULTS - RECLAIMED WATERS

[illegible]

*Pooled samples may be 2 to 3 days older
Neg. = Not detected
ppt. = Precipitate formed. No readout obtained.

– =No data available
R =Rejection level

*Pooled samples may be 2 to 3 days older
Neg. = Not detected
ppt. = Precipitate formed. No readout obtained.

– =No data available
R =Rejection level

TABLE 1b
ANALYTICAL RESULTS - RECLAIMED WATERS

PROCESS, SEE SECTION II MANUFACTURER		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC		FC	
---	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--	----	--

*Pooled samples may be 2 to 3 days older
Pos. = Present in trace quantities
ppt = Precipitate formed. No readout obtained.

– = No data available
R = Rejection level

TABLE I:
ANALYTICAL RESULTS - RECLAIMED WATERS

[illegible]

*Pooled samples may be 2 to 3 days older/All dates are 1965
 – = No data available
 R = Rejection level

TABLE Ij
ANALYTICAL RESULTS – RECLAIMED WATERS

PROCESS, SEE SECTION II															U. S. PUBLIC HEALTH DRINKING WATER STANDARDS (1962)				
MANUFACTURER		UFC		UFC		UFC		UFC		FCell		VD		VD		VD		VD	
SAMPLE No. (TC)		AMRL		AMRL		AMRL		AMRL		GE		Ardé		AMRL		AMRL		AMRL	
		140		141		143		144		145		188		192		193		200	
DATE SAMPLE RECOVERED*		4-16-65		4-17-65		4-18-65		4-19-65		4-20-65		6-10-65		6-23-65		6-23-65		8-5-65	
VOLUME OF SAMPLE (ml)		4000		4000		4000		4000		4000		3000		4000		3500		7-20-65	
SPECTROGRAPHIC DATA (ppb)																			
1	ZINC	5	300	170	140	135	65	200	23	190	85	<10	<10	16	37	55	53	<10	5000
2	CADMIUM	35	24	16	12	12	50	<10		<11	<10	<10	<10	<10	<10	<10	14	<10	10 R
3	BORON	54	130	33	75	51	225	>250	70	50	85	15		19	13	11	53	68	
4	PHOSPHORUS	135	160	65	60	40	40	150	375	450	200	>500		<25	<25	<25	<25	>450	
5	IRON	57	104	50	19	21	11	33	9	95	59	<5	<5	<5	20	5	20	<5	300
6	MOLYBDENUM	<10	<10	<10	<10	<10	<10	<10	<16	<6	<5	<10	<10	<10	<10	<10	<10	<5	
7	MANGANESE	6	3	1.5	1	1	<1	2.2	29	<3	<3	10		<2.5	<2.5	<2.5	<2.5	<3	50
8	ALUMINUM	25	<13	<13	<13	<13	33	.75	41	170	105	<10	<10	<10	15	<10	30	59	
9	BERYLLIUM	<.03	<.03	<.03	<.03	<.03	<.05	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	<.03	1000
10	COPPER	20	10	6	4	3	9	17	3	135	95	2.5		6	11	4	10	2	50 R
11	SILVER	<.5	<.5	<.5	<.5	<.5	<.5	<.5	<.5	4.5	<.5	0.5		<.5	<.5	<.5	<.5	<.5	
12	NICKEL	<.5	<.5	<.5	<.5	<.5	<.5	<.5	<.5	12	<.5	<.5		<.5	<.5	<.5	<.5	<.5	
13	COBALT	<.5	<.5	<.5	<.5	<.5	<.5	<.5	<.5	<6	<.5	<.5		<.5	<.5	<.5	<.5	<.5	
14	LEAD	<10	<10	<10	<10	<10	<10	<10	15	<11	<10	<10	<10	<10	<10	<10	<10	<10	50 R
15	CHROMIUM	10	16	8	<3	<3	<3	<3	<3	6.1	<3	<2.5		<2.5	<2.5	<2.5	<2.5	<3	50 R
16	VANADIUM	<10	<10	<10	<10	<10	<10	<10	<10	<11	<10	<10		<10	<10	<10	<10	<10	
17	BARIIUM	>50	>50	>50	>50	>50	>100	>50	>75	18.5	3	7.5		3.5	5.5	<1	15	8	1000 R
18	STRONTIUM	<1	<1	<1	<1	<1	<1	2	57	<2	<1	<2		<2	<2	<2	4	50	
19	MERCURY	<50	80	<50	<25	<25	—	—	—	100	—	—		<50	<50	<50	<50	<50	
CATIONS (mg/l)																			
1	CALCIUM (Ca)	—	—	—	—	—	2.4	2.4	18	—	—	—	—	—	—	—	—	—	29
2	MAGNESIUM (Mg)	—	—	—	—	—	1.4	1	5.2	—	—	—	—	—	—	—	—	<.5	
3	SODIUM (Na)	1.5	0.5	1.5	0.5	0.5	1.0	1.5	1.5	—	—	<1		<1	<1	1.5	2.5	170	
4	POTASSIUM (K)	1	0.6	1	<.5	<.5	<.5	1	3	—	—	6		<1	<1	<1	2	39	
5	ARSENIC (As)	<.01	<.01	<.01	<.01	<.01	<.01	<.01	<.01	—	—	<.01		<.01	<.01	<.01	<.01	0.01	.05 R
6	AMMONIA (NH ₃ /N)	18	18	19	24	21	72	16	15	1.2	—	0.05		0.22	0.38	0.16	0.1	48	
F=2 F=2																			
ANIONS (mg/l)																			
1	SULFATE (SO ₄)	3	2	1	<1	<1	6	10	11	5	—	—	—	—	—	—	—	100	250
2	CHLORIDE (Cl)	2	<1	<1	<1	<1	1	1	12	6	—	—	—	1	1	3	3	240	250
3	NITRATE (NO ₃ /N)	1.6	<.1	0.4	0.3	0.1	<.1	<.1	3	—	—	<.1		<.1	1	0.6	1.1	<.1	45
4	TOTAL PHOSPHATE (PO ₄)	<.05	<.05	<.05	<.05	<.05	0.13	<.05	<.05	—	—	2.1		0.21	<.05	0.09	<.05	23	
5	ABS	—	—	—	—	—	0.17	—	—	—	—	—	—	—	—	—	—	—	0.5
OTHER TESTS																			
1	pH	6.9	6.8	6.6	6.7	7.4	7.3	6.4	7.2	3.1	3.2	7.3		9.3	9.7	8.6	7.3	4.9	
2	CONDUCTIVITY (µmhos/cm)	300	270	290	300	300	380	142	225	4000	—	120		44	54	62	50	1750	
3	TURBIDITY-JACKSON UNITS	—	—	—	—	—	—	—	—	—	—	—		—	—	—	—	—	
4	COLOR	10	5	5	5	5	5	5	<5	15	—	0		5	5	5	5	<5	15
5	ODOR	—	—	—	—	—	—	—	—	—	—	—		—	—	—	—	—	3
6	TOTAL HARDNESS (CaCO ₃)	14	8	8	8	8	12	10	70	12	8	10		4	8	8	8	72	
7	TOTAL ALKALINITY (CaCO ₃)	116	116	120	140	140	146	44	84	0	—	192		36	44	24	18	192	
8	TOTAL SOLIDS	—	—	—	—	—	—	—	—	—	—	—		—	—	—	—	—	500
9	CHEM O ₂ DEMAND	510	160	220	160	130	132	205	74	200	270	69		31	17	110	52	2045	
10	UREA	<.1	—	<.1	<.1	<.1	<.1	Pos.	Pos.	Pos.	<.1	0.01		0.06	0.02	0.02	0.02	120	
11	TOTAL PLATE COUNT	—	—	—	—	—	—	—	—	—	—	—		—	—	—	—	—	
12	TOTAL CARBON	75	40	36	26	26	53	55	19	40	89	2		4.8	4.8	16	14	790	

*Pooled samples may be 2 to 3 days older
Pos. = Present in trace quantities
— = No data available

SECTION IV.

Conclusions

Considerable variations existed in the composition of water recovered from the same system from day to day. These were, usually, the result of variations in the raw material rather than in the water reclamation system or in the operation thereof. In most cases the recovered water met the requirements of the U. S. Public Health Service for drinking water. Where the standards were exceeded, the constituent level of the recovered water was within allowable limits for aerospace use. Often, the constituent level of water recovered from urine was less than that of the tap and distilled water tested. Trace metals were not a problem.

Condensate recovered from the atmosphere of the Life Support Systems Evaluator (LSSE) showed much higher chemical oxygen demand ratings than did water recovered from urine by a change of phase process. The high COD values were indicative of large quantities of oxidizable compounds. When organic materials were present, the problem of bacterial contamination was magnified. Passing the condensate through activated charcoal did not remove a substantial amount of the organics. Further study of charcoal types and contact time is needed.

Standards in addition to those listed by the U. S. Public Health Service for drinking water should be used in evaluating reclaimed waters. Weights for pH, conductivity, total carbon, ammonia, and bacteria should be included. Extensive testing of recovered water during aerospace missions is not feasible. Minimum standards, based on the capability of the recovery device should be established.

The data in tables Ia-Ij provide opportunity to study correlations between constituents or characteristics of the recovered water, i.e., trace elements vs conductivity or chemical oxygen demand vs total carbon. Sufficient data are available in many cases to permit the inference of a meaningful pattern.

Operation and evaluation tests revealed that thermoelectric, electrodialysis, and vapor compression water reclamation devices are suitable systems for use during an extended aerospace mission. The vacuum distillation water reclamation device, when used in conjunction with isotopes for supplying energy for vaporizing the waste liquid and for pyrolyzing the contaminants in the vapor, is considered the best system for aerospace application.

Appendix

SURVEY OF WATER RECLAMATION SYSTEMS

The reclaiming of potable water for aerospace use has been described in references 12, 13, 14, and 15. These describe in detail the sources from which the water can be recovered as well as the quantities needed for drinking, reconstituting foods, and for personal hygiene and sanitation. Also described are various processes for reclaiming water, with expected yields, power requirements, basic designs, and other pertinent information.

Data on reclamation systems that have been surveyed by the Aerospace Medical Research Laboratories and others are included in table II. Also included is the status of the systems studied and an AMRL rating of the systems for aerospace application. Systems that have been procured and operated by AMRL may be noted by the operating hours assigned.

The data in table II do not include penalties associated with power requirement nor are the systems reported on space optimized. Each system, except where vapors are pyrolyzed, requires both pre- and post-treatment.

Another and a more detailed analysis and comparison of the various candidate systems for recovering water during extended space travel was prepared by J. A. Steele, General Dynamics/Electric Boat (ref 31) for NASA, Langley Research Center.

TABLE II
WATER RECLAMATION SYSTEMS

System	Responsible Agent	Contractor	Reference	Volume (cu. ft.)	Weight (lbs.)	Watt-hrs/ lb. of H ₂ O	Output lb./hr.	Recovery (%)	AMRL Operations (hrs.)	AMRL Rating	Status
1 Thermoelectric	AMRL	Garrett	16	1.2	65	>200	<0.2	<85	>85	NS	Complete
"	"	Whirlpool	17	3.5	49	146	1.0	<85	>270	A	"
"	"	"	*	—	—	—	—	—	—	—	Sep. 67
"	NASA	MRD	18	2	36	121	0.5	92	—	—	—
2 Electrodialysis	AMRL	Ionics	9, 10	1.4	50	100	0.9	85	73	A	Complete
"	—	Douglas	11	—	—	—	—	—	—	—	—
3 Ultrafiltration	AMRL	RAI	4, 5	—	—	—	—	—	338	B	Complete
"	NASA	"	6	—	—	—	—	—	—	—	"
4 Ultrafiltration— Electrolysis	"	"	7	—	—	—	—	—	—	C	—
"	AMRL	In-House	—	—	—	—	—	—	—	C	Dec. 67
5 Membrane Permeation	"	Ionics	8	2	128	400	0.05	85	>50	D	Complete
6 Freeze Drying	"	s. Un. of Iowa	19	—	>85	400	0.75	75	—	D	"
7 Electrolysis Cell— Fuel Cell	"	GE	20	1.6	67	65	0.4	98	—	C	"
8 Air Evaporation	NASA	Ham. Std.	21	12	100	375	1.44	98	—	B	—
"	AMRL	—	**	—	—	—	—	—	—	B	Sep. 67
9 Vacuum Distillation	"	MRD	22, 23	2.1	>35	0	0.6	98	—	D	Complete
10 Vapor Compression	"	"	1	3.4	60	108	1.2	91	>205	A	"
"	"	Elec. Boat	2	—	—	—	—	—	>94	NS	"
"	"	Gard	24	—	—	—	—	—	—	—	Jan. 67
"	NASA	MRD	25	—	59	39	3	97	—	A	Complete
"	"	Marquardt	***	—	—	—	—	—	—	—	—
11 Vacuum Pyrolysis											
a. Electric	"	GE	26	—	—	—	—	—	—	A	Complete
b. Isotope	AMRL	"	27, 28	—	—	—	—	—	—	A	—
12 Spray Condenser	"	Garrett	29	4.5	40	—	—	—	—	NS	Complete
13 Reiterative Freezing	"	Minneapolis Honeywell	30	—	—	—	—	—	—	NS	"

NS = Not suitable

A = Leading

B = Promising

C = Extensive development required

D = Discarded

*AMRL Exhibit MRL-66-30, Thermoelectric Water Recovery System.

**AMRL Exhibit MRL-66-112, Water Recovery by Air Evaporation.

***NASA Contract NAS 9-5119, Waste Collection and Processing System.

References

1. Rest, J., and R. A. Bambenek, *Operating and Maintenance Instructions for AMF Model MR 08-082 Water Reclamation System*, AMF Report MR 1186-50, Mechanics Research Division, American Machine & Foundry Co., Niles, Illinois, July 1962.
2. Presti, J. B., H. C. Miner, R. Nickerson, and H. Wallman, *A Laboratory Model of an Integrated Water Recovery System*, AMRL-TDR-63-88 (AD 424 590), Aerospace Medical Research Laboratories, Wright-Patterson Air Force Base, Ohio, October 1963.
3. Hargreaves, J., T. E. Morgan, Jr., and B. E. Welch, *A Water Recycling System for Use in Sealed Environments*, SAM-TDR-63-60, USAF School of Aerospace Medicine, Brooks Air Force Base, Texas.
4. Meir, E. A., and R. Everett, Jr., *The Feasibility of Using Membranes for Urine Purification*, AMRL-TDR-63-113 (AD 427 413), Aerospace Medical Research Laboratories, Wright-Patterson Air Force Base, Ohio, November 1963.
5. *Operations Manual for Mark II Experimental Laboratory Ultrafiltration System*, Radiation Applications, Inc., Long Island City, New York, Report RIA, 10 May 1964.
6. *Water Recovery Study*, Quarterly Reports prepared under Contract No. NASW-520 for NASA-Ames Research Center by Radiation Applications, Inc., Long Island City, New York.
7. *Research, Design and Development of an Improved Water Reclamation System for Manned Space Vehicles*, Progress Reports 1-13, Prepared under Contract NASI-4373 for NASA-Langley Research Center, by Radiation Application, Inc., Long Island City, New York, September 1964 to October 1965.
8. Warner, A. W., D. L. Brown, and W. Glass, *Recovery of Potable Water from Urine by Membrane Permeation*, AMRL-TDR-64-73 (AD 607 759), Aerospace Medical Research Laboratories, Wright-Patterson Air Force Base, Ohio, September 1964.
9. Brown, D. L., R. W. Lindstrom, and J. D. Smith, *The Recovery of Water from Urine by Membrane Electrodialysis*, AMRL-TDR-63-30 (AD 407 137), Aerospace Medical Research Laboratories, Wright-Patterson Air Force Base, Ohio, April 1963.
10. *Operating and Maintenance Manual for Urine Reclamation Unit Under Contract AF 33(615)-429*, Ionics, Inc., Watertown, Mass., 13 January 1965.
11. Hansen, C. E., and C. Berger, "Urine and Waste-Water Recovery by Electrodialysis," *American Society of Mechanical Engineers*, Publication 65-AV-16, 1965.
12. Wallman, H., and S. M. Barnett, *Water Recovery Systems (Multi-Variable)*, WADD-TR-60-243 (AD 243 574), Wright Air Development Division, Wright-Patterson Air Force Base, Ohio, March 1960.
13. Zeff, J. D., and R. A. Bambenek, *Development of a Unit for Recovery of Water and Disposal or Storage of Solids from Human Wastes. Part I — The Study Phase*, WADC-TR-58-562 (I) (AD 234 007), Wright Air Development Center, Wright-Patterson Air Force Base, Ohio, November 1959.

14. Slonim, A. R., A. P. Hallam, and D. H. Jensen, *Water Recovery from Physiological Sources for Space Applications*, MRL-TDR-62-75, (AD 285 220), Aerospace Medical Research Laboratories, Wright-Patterson Air Force Base, Ohio, July 1962.
15. Popma, D. C., and V. G. Collins, *Space Vehicle Water Reclamation Systems*, Preprint 54a, American Institute of Chemical Engineers, New York, N. Y., February 1965.
16. Hubert, J. A., and E. F. Timpke, *Final Report Recovery of Potable Water from Human Urine by Thermoelectric Distillation*, The Garrett Corporation, AiResearch Mfg. Div., Los Angeles, California, Report No. L-9310, August 30, 1963.
17. Nichols, D. C., *Water Reclamation From Urine Thermoelectric System*, AMRL-TR-65-29 (AD 615 979), Aerospace Medical Research Laboratories, Wright-Patterson Air Force Base, Ohio, March 1965.
18. Rest, J., T. L. Hurley, and J. D. Zeff, *Final Technical Report for a Waste Management Subsystem*, GATC Report MR 1210-8090, MRD Division, General American Transportation Corp., Niles, Illinois, December 1963.
19. Vetter, A. F., and K. Kammermeyer, *Water Recovery by Freeze Drying Using Microwave Energy*, AMRL-TDR-63-130 (AD 434 801), Aerospace Medical Research Laboratories, Wright-Patterson Air Force Base, Ohio, December 1963.
20. Rudek, F. P., and N. Belasco, *Research of Electrolysis Cell – Fuel Cell Method of Recovering Potable Water from Urine*, AMRL-TDR-63-32 (AD 407 000), Aerospace Medical Research Laboratories, Wright-Patterson Air Force Base, Ohio, April 1963.
21. *Improved Water Reclamation System Contract NAS 1-5312*, Progress Report Submitted to NASA-Langley, by Hamilton Standard, Windsor Locks, Conn.
22. Zeff, J. D., and R. A. Bambenek, *System for Recovery of Water from Urine. Part II – Design, Fabrication, and Testing of the Prototype System*, WADC-TR-58-562 (II) (AD 246 336), Wright Air Development Division, Wright-Patterson Air Force Base, Ohio, August 1960.
23. Zeff, J. D., and R. A. Bambenek, *Recovery of Potable Water in Manned Aerospace Vehicles*, presented at the 32nd Annual Meeting of the Aerospace Medical Association, Palmer House, Chicago, Illinois, 27 April 1961.
24. Berninger, J. F., and R. A. Landes, *Vacuum Distillation Water Recovery Unit (Per AF 33 (615)-2124)*, GATC Monthly Progress Reports GARD 1271-1-1271-13.
25. Berninger, J. F., T. R. Charanian, and R. A. Bambenek, *Water Reclamation Via Compression Distillation*, presented at the American Society of Mechanical Engineers Aviation and Space Division Conference, Statler-Hilton Hotel, Los Angeles, California, 16-18 March 1965.
26. Okamoto, A. H., and J. J. Konikoff, *Study of the Purification of Water from Biological Waste*, Second Annual Report (Revised), General Electric Company, Box 8555, Philadelphia, Penn., June 1962.
27. Littman, J., G. D. Davis, and L. E. Hummel, *Application of Radioisotopes to Manned Spacecraft Life Support Systems (Integrated Water Recovery System)*, Monthly Progress Report of Period Ending 31 July 1965, Garrett Corp., AiResearch Mfg. Div., Los Angeles, California, Report SS-3892.

28. MSD Proposal No. N-40161, *Vacuum Distillation Water Recovery Unit*, Missile and Space Division, General Electric Co., P. O. Box 8555, Philadelphia, Penn.
29. Engineering Proposal Water Reclamation System 177970-1, Report No. L-3816-R, The Garrett Corp., AiResearch Mfg. Co., Los Angeles, California, July 1961.
30. Beutel, J., *Water Recovery by Reiterative Freezing*, MRL-TDR-62-14 (AD 278 883), Aerospace Medical Research Laboratories, Wright-Patterson Air Force Base, Ohio, March 1962.
31. Steele, J. A., *Water Management System Evaluation for Space Flights of One Year Duration*, NASA Contract NAS 1-2934, NASA Langley Research Center, Hampton, Virginia (Revised 1965).

Security Classification

DOCUMENT CONTROL DATA - R&D		
(Security classification of title, body of abstract and indexing annotation must be entered when the overall report is classified)		
1. ORIGINATING ACTIVITY (Corporate author) Aerospace Medical Research Laboratories, Aerospace Medical Division, Air Force Systems Command, Wright-Patterson Air Force Base, Ohio 45433		2a. REPORT SECURITY CLASSIFICATION UNCLASSIFIED
		2b. GROUP N/A
3. REPORT TITLE EVALUATION OF WATER RECLAMATION SYSTEMS AND ANALYSIS OF RECOVERED WATER FOR HUMAN CONSUMPTION		
4. DESCRIPTIVE NOTES (Type of report and inclusive dates) Final Report		
5. AUTHOR(S) (Last name, first name, initial) Metzger, Courtney A. McMullen, Bobby G., Master Sergeant, Hearld, Albert B. USAF		
6. REPORT DATE February 1967	7a. TOTAL NO. OF PAGES 31	7b. NO. OF REFS 31
8a. CONTRACT OR GRANT NO. b. PROJECT NO. 6373 c. Task No. 637304 d.	9a. ORIGINATOR'S REPORT NUMBER(S) AMRL-TR-66-137 9b. OTHER REPORT NO(S) (Any other numbers that may be assigned this report)	
10. AVAILABILITY/LIMITATION NOTICES Distribution of this document is unlimited.		
11. SUPPLEMENTARY NOTES	12. SPONSORING MILITARY ACTIVITY Aerospace Medical Research Laboratories, Aerospace Medical Div., Air Force Systems Command, Wright-Patterson AFB, Ohio	
13. ABSTRACT Analyses were made of water recovered from human urine and from atmospheric condensate collected during manned tests inside a sealed chamber. Data on more than 200 samples were prepared for comparison with that of distilled water and tap water and with U.S. Public Health Standards for drinking water. Most of the samples were suitable for human consumption. Candidate systems for recovering potable water from urine were evaluated. Thermoelectric, electrodialysis, and vapor compression water reclamation devices were determined to be suitable for use during extended aerospace missions.		

DD FORM 1473
1 JAN 64

Security Classification

14. KEY WORDS	LINK A		LINK B		LINK C	
	ROLE	WT	ROLE	WT	ROLE	WT
Water (reclamation)						
Urine						
Life Support						
Potable Water						

INSTRUCTIONS

1. **ORIGINATING ACTIVITY:** Enter the name and address of the contractor, subcontractor, grantee, Department of Defense activity or other organization (*corporate author*) issuing the report.

2a. **REPORT SECURITY CLASSIFICATION:** Enter the overall security classification of the report. Indicate whether "Restricted Data" is included. Marking is to be in accordance with appropriate security regulations.

2b. **GROUP:** Automatic downgrading is specified in DoD Directive 5200.10 and Armed Forces Industrial Manual. Enter the group number. Also, when applicable, show that optional markings have been used for Group 3 and Group 4 as authorized.

3. **REPORT TITLE:** Enter the complete report title in all capital letters. Titles in all cases should be unclassified. If a meaningful title cannot be selected without classification, show title classification in all capitals in parenthesis immediately following the title.

4. **DESCRIPTIVE NOTES:** If appropriate, enter the type of report, e.g., interim, progress, summary, annual, or final. Give the inclusive dates when a specific reporting period is covered.

5. **AUTHOR(S):** Enter the name(s) of author(s) as shown on or in the report. Enter last name, first name, middle initial. If military, show rank and branch of service. The name of the principal author is an absolute minimum requirement.

6. **REPORT DATE:** Enter the date of the report as day, month, year; or month, year. If more than one date appears on the report, use date of publication.

7a. **TOTAL NUMBER OF PAGES:** The total page count should follow normal pagination procedures, i.e., enter the number of pages containing information.

7b. **NUMBER OF REFERENCES:** Enter the total number of references cited in the report.

8a. **CONTRACT OR GRANT NUMBER:** If appropriate, enter the applicable number of the contract or grant under which the report was written.

8b, 8c, & 8d. **PROJECT NUMBER:** Enter the appropriate military department identification, such as project number, subproject number, system numbers, task number, etc.

9a. **ORIGINATOR'S REPORT NUMBER(S):** Enter the official report number by which the document will be identified and controlled by the originating activity. This number must be unique to this report.

9b. **OTHER REPORT NUMBER(S):** If the report has been assigned any other report numbers (*either by the originator or by the sponsor*), also enter this number(s).

10. **AVAILABILITY/LIMITATION NOTICES:** Enter any limitations on further dissemination of the report, other than those

imposed by security classification, using standard statements such as:

- (1) "Qualified requesters may obtain copies of this report from DDC."
- (2) "Foreign announcement and dissemination of this report by DDC is not authorized."
- (3) "U. S. Government agencies may obtain copies of this report directly from DDC. Other qualified DDC users shall request through _____."
- (4) "U. S. military agencies may obtain copies of this report directly from DDC. Other qualified users shall request through _____."
- (5) "All distribution of this report is controlled. Qualified DDC users shall request through _____."

If the report has been furnished to the Office of Technical Services, Department of Commerce, for sale to the public, indicate this fact and enter the price, if known.

11. **SUPPLEMENTARY NOTES:** Use for additional explanatory notes.

12. **SPONSORING MILITARY ACTIVITY:** Enter the name of the departmental project office or laboratory sponsoring (*paying for*) the research and development. Include address.

13. **ABSTRACT:** Enter an abstract giving a brief and factual summary of the document indicative of the report, even though it may also appear elsewhere in the body of the technical report. If additional space is required, a continuation sheet shall be attached.

It is highly desirable that the abstract of classified reports be unclassified. Each paragraph of the abstract shall end with an indication of the military security classification of the information in the paragraph, represented as (TS), (S), (C), or (U).

There is no limitation on the length of the abstract. However, the suggested length is from 150 to 225 words.

14. **KEY WORDS:** Key words are technically meaningful terms or short phrases that characterize a report and may be used as index entries for cataloging the report. Key words must be selected so that no security classification is required. Identifiers, such as equipment model designation, trade name, military project code name, geographic location, may be used as key words but will be followed by an indication of technical context. The assignment of links, rules, and weights is optional.