

AD-775 607

OVERSTRESS QUALIFICATION TEST OF THE
MULTIPLE SATELLITE DISPENSER 0.2 LBF
ROCKET ENGINE ASSEMBLY REA 10-16

William W. Arkilander

Hamilton Standard

Prepared for:

Office of Naval Research

7 November 1973

DISTRIBUTED BY:

NTIS

National Technical Information Service
U. S. DEPARTMENT OF COMMERCE
5285 Port Royal Road, Springfield Va. 22151

AD-775607

Hamilton Standard DIVISION OF UNITED AIRCRAFT CORPORATION
U
A.

SVHSER 6305

HAMILTON STANDARD ENGINEERING REPORT

SVHSER 6305

OVERSTRESS

QUALIFICATION TEST

OF THE

MULTIPLE SATELLITE DISPENSER

0.2 LB_F ROCKET ENGINE ASSEMBLY

REA 10-16

Prepared By: *William H. Arkilander*
W. Arkilander, Analytical Engineer

11-7-73
Date

Approved By: *E. K. Moore*
E. K. Moore, Project Manager

11/20/73
Date

R. D. Fisher
R. D. Fisher, Chief Development Engineer

12/9/73
Date

N00014-73-C-0322

DISTRIBUTION STATEMENT A
Approved for public release
Distribution Unlimited

Reproduced by
NATIONAL TECHNICAL
INFORMATION SERVICE
U S Department of Commerce
Springfield VA 22151

TABLE OF CONTENTS

<u>Section</u>	<u>Title</u>	<u>Page</u>
I	Summary	1
II	Introduction	1
III	Objective	1
IV	Conclusion	1
V	Discussion	2
	A. Engine Description	2
	B. Qualification Test Program	2
Appendix A	Acceptance Test Procedures	A-1 - A-17
B	Qualification Test Procedures	B-1 - B-39
C	Qualification Data Curves	C-1 - C-62
D	Vibration Test Reports	D-1 - D-23

I. SUMMARY

This report presents the results of a portion of a Qualification Overstress Test on Hamilton Standard Rocket Engine Assembly, Model 16-10, a nominal 0.2 pound thrust monopropellant engine. The purpose of the tests performed was to establish engine characteristics over extended life and to establish performance parameters over a range of operating conditions.

During the Overstress Life Test the engine accumulated the following operating history:

Accumulated Pulses	375,000
Steady State Time	24 hours
Cumulative Operating Time	30.3 hours

II. INTRODUCTION

This Qualification Overstress Test program was conducted per Department of the Navy, Office of Naval Research, Contract Number N00014-73-C-0322, for the Director of the Naval Research Laboratory (NRL).

The Rocket Engine Assembly (REA) used in this program is Hamilton Standard Model REA 10-16. This engine is a component of the propulsion subsystem of the NRL Multiple Satellite Dispenser (MSD). The engine provides thrust for attitude control and station acquisition on an earth orbiting satellite.

The engine was qualified as reported in Hamilton Standard Report SVHSER 6300. Overstress testing was performed on two engines in two test groups. The qualification test engine was used for $C_d C_f$ verification tests and critical soakback demonstration and the results were reported in SVHSER 6304. A second engine was used for extended life and performance mapping and the results are discussed herein.

III. OBJECTIVE

The objectives of this portion of the Qualification Overstress Tests were to characterize the engine over extended life and at various operating conditions.

IV. CONCLUSIONS

Engine pulsing and steady state characteristics were established at the normal duty cycle for a cumulative operating time of 30.3 hours including 24 hours of steady state operation and 370,000 pulses. Characteristics at four other duty cycles were also determined.

V. DISCUSSION

A. Engine Description

The engine qualified for the Naval Research Laboratories Multiple Satellite Dispenser (NRL/MSD) and used in this test program is Hamilton Standard Model REA 10-16. It is a nominal 0.2 pound thrust rocket engine assembly (REA), employing catalytic decomposition of hydrazine to produce thrust. The Hamilton Standard drawing number is SV755437, with the flight configuration being part number SV755437-1.

The engine consists of a flow control valve and a thrust chamber assembly. The flow control valve is an axial solenoid design using AFE 102 material as the valve seat. The valve is manufactured by Wright Components, Inc., Clifton Springs, New York to their part number 15626-2. The Hamilton Standard part number is SV755439-1. The requirements for the valve are defined by Hamilton Standard Procurement Specification SVHS 6006.

The thrust chamber assembly, manufactured by Hamilton Standard, consists of an injector system, thermal standoff, pressure and reaction chamber, catalyst bed, and a conical nozzle having an area ratio of 55:1. The catalyst used is Shell 405, procured under Hamilton Standard drawing SV725250. The injector consists of a single .010 diameter tube. The thrust chamber assembly is gold plated for passive thermal control.

The specific engine used in this test program was Hamilton Standard part number SV755437-1, Serial Number 00003. The engine is identical to the flight configuration in function, but differs physically from the flight configuration as listed below:

TABLE I

Qualification/Flight Configuration

<u>Feature</u>	<u>Flight Configuration (SV755437-2)</u>	<u>Qual Configuration (SV755437-2)</u>
Valve	HS P/N SV755439-1	G.F.E.

B. Test Results

Performance

Engine performance was monitored using manual, analog and digital techniques. Digital data was reduced using a Hamilton Standard Reduction Program defined by specification SVHS 5430. The

V. B. Test Results - continued

techniques used to determine thrust and impulse characteristics were compliant with NRL specification. This program specification is available for review by the NRL Scientific Officer at Hamilton Standard.

Combined Life

The performance index of the engine was monitored during combined life testing by periodic basepoints. The data from these basepoints is presented in Appendix C of this report. Where applicable specification limits are shown over the required cumulative operating time of 19.2 hours.

Steady State Thrust

The NRL specification requires that the delivered thrust level lie between the limits of 0.20 and 0.24 lb_f at a nominal supply pressure and fuel temperature of 250 psia and 70°F respectively. Figure 1C shows satisfaction of this requirement over 15 ½ hours of engine cumulative operating time. Delivered thrust after 15½ hours of cumulative operating time falls below the specification minimum of 0.20 lb_f. The specification also requires that the engine perform satisfactorily over a thrust range of 0.10 to 0.22 lb_f. Figure 2C shows calculated thrust as a function of cumulative operating time at a supply pressure of 125 psia. Start of life calculated thrust is 0.11 lb_f and end of life calculated thrust is 0.103 lb_f. This represents a degradation in thrust level of 6.4% over a cumulative operating time of 30.3 hours. Thrust degradation at a supply pressure of 250 psia is 13.8% over the same cumulative operating time. Increased catalyst bed pressure drop as a result of catalyst bed packing during life is the cause of this phenomenon.

Pressure Oscillations

The NRL specification requires that the steady state chamber pressure oscillations not exceed +10% of nominal chamber pressure. Figures 3C and 4C show steady state oscillations as a function of cumulative operating time at supply pressures of 250 and 125 psia respectively. Inspection of these figures shows erratic behavior of this parameter over life. Steady state oscillations range from 2½ to 40% at a supply pressure of 250 psia and from 2½ to 13½% at a supply pressure of 125 psia. The wide run-to-run variations in steady state oscillations are characteristic of this unit.

V. B. Test Results - continued

Thrust Overshoot

The NRL specification requires that steady state and pulsing first pulse thrust overshoot not exceed 0.57 lb_f at a nominal supply pressure and fuel temperature of 250 psia and 70°F respectively. In addition, pulsing thrust overshoot for pulses 2-N shall not exceed 0.44 lb_f for the same set point conditions. Table 1C presents thrust overshoot data for both steady state and pulsing operation as a function of cumulative operating time. Also tabulated are the fuel temperature ranges for each baseline run. Specification requirements were satisfied throughout the life test.

Steady State Specific Impulse

The NRL specification requires a steady state specific impulse of 215 $lb_f\text{-sec}/lbm$ minimum, over a supply pressure range of 125 to 250 psia. Figures 5C and 6C show steady state specific impulse for supply pressures of 250 and 125 psia respectively. Specification requirements were met through 19.2 hours of cumulative operating time at a supply pressure of 250 psia. At a supply pressure of 125 psia several baseline runs did not achieve a specific impulse value of 215 $lb_f\text{-sec}/lbm$. A tabulation of specific impulse for the runs shown graphically on Figure 6C are listed below.

23 Baseline Runs $P_I = 125$ psia

<u>Run</u>	<u>Cumulative Operating Time (hrs)</u>	<u>Steady State Isp ($lb_f/lbm\text{-sec}$)</u>
2485	0.97000E-01	214.95
2489	0.42700	214.90
2493	0.75700	215.12
2497	1.0870	216.37
2501	1.4170	214.12
2505	1.6470	214.89
2509	7.6470	213.90
2513	7.9770	216.09
2522	8.6370	218.67
2526	8.9760	217.53
2530	9.1970	218.21
2534	15.197	216.42
2539	15.527	218.62
2542	15.857	220.08
2551	16.517	220.45

V. B. Test Results - continued

<u>Run</u>	<u>Cumulative Operating Time (hrs)</u>	<u>Steady State I_{sp} ($lb_f/lbm\text{-sec}$)</u>
2555	16.747	219.85
2559	22.747	210.77
2563	23.077	216.96
2567	23.407	212.34
2571	23.737	212.65
2575	24.067	215.01
2579	24.297	217.40
2584	30.297	214.55

The average value of specific impulse for the 23 baseline runs is 216.1 $lb_f\text{-sec}/lbm$ and the standard deviation (one sigma) is 2.5 $lb_f\text{-sec}/lbm$ (1.16%).

Pulsing Specific Impulse

The NRL specification requires a pulsing specific impulse of 170 $lb_f\text{-sec}/lbm$ minimum, at a nominal supply pressure and fuel temperature of 250 psia and 700F respectively. This requirement applies to pulse train lengths of 100 at a duty cycle of .060 sec on and .940 sec off. Figure 7C shows compliance with this requirement over 19.2 hours of cumulative operating time. Figures 8C and 9C show pulsing specific impulse at supply pressures of 170 and 125 psia respectively. These figures are shown for information only. Specific impulse values are not presented at a supply pressure of 60 psia due to anomalous flow measurements.

Impulse Repeatability

The NRL specification requires that pulse-to-pulse impulse bits vary by no more than $\pm 10\%$ from the mean impulse bit for pulses 20 through 100 for pulse train lengths of 100. Figures 10C, 11C, 12C and 13C show impulse bit variation as a function of cumulative operating time at supply pressures of 250, 170, 125 and 60 psia respectively. Specification requirements over 19.2 hours of cumulative operating time are satisfied at all supply pressures except 125 and 60 psia. The maximum value of impulse bit variation over 19.2 hours of cumulative operating time at this supply pressure is $\pm 11.6\%$. Figures 14C, 15C, 16C and 17C show average impulse bit as a function of cumulative operating time at supply pressures of 250, 170, 125 and 60 psia respectively. Impulse bit values degrade over life due to catalyst bed packing. These figures are shown for information only.

V. B. Test Results - continued

Centroid Repeatability

The NRL specification requires that pulse-to-pulse time to centroid vary by no more than ± 15 ms. from the mean centroid time for pulses 11 through 100 for pulse train lengths of 100. Figures 18C, 19C, 20C and 21C show time to centroid variation as a function of cumulative operating time at supply pressures of 250, 170, 125 and 60 psia respectively. Specification requirements over 19.2 hours of cumulative operating time are satisfied at all supply pressures except 125 and 60 psia. The maximum value of centroid time variation over 19.2 hours of cumulative operating time at this supply pressure is ± 21 ms. Figures 22C, 23C, 24C and 25C show average centroid time as a function of cumulative operating time at supply pressures of 250, 170, 125 and 60 psia respectively. These figures are shown for information only.

Startup Response

The NRL specification requires that the maximum time to 90% of pulse average chamber pressure not exceed 50 ms for pulses 11 - 100 for pulse train lengths of 100. Figures 26C, 27C, 28C and 29C show time to 90% of pulse average chamber pressure as a function of cumulative operating time at supply pressures of 250, 170, 125 and 60 psia respectively. Specification requirements over 19.2 hours of cumulative operating time are satisfied at all supply pressures.

Shutdown Response

The NRL specification requires that the maximum time to 10% of pulse average chamber pressure not exceed 130 ms for pulses 11 - 100 for pulse train lengths of 100. Figures 30C, 31C, 32C and 33C show time to 10% of average chamber pressure as a function of cumulative operating time at supply pressures of 250, 170, 125, and 60 psia respectively. Specification requirements over 19.2 hours of cumulative operating time are satisfied except at a supply pressure of 60 psia. At this supply pressure the maximum time to 10% of average chamber pressure over 19.2 hours of cumulative operating time is 203 ms.

Steady State Operating Life

The steady state operating life of REA 10-12 is required by NRL specification to be up to 15 hours total. The combined life test series accumulated 24 hours of steady state firing and pressure levels of 250, 210, 170 and 125 psia.

V. B. Test Results - Continued

Pulsing Operating Life

The pulsing life requirement for REA 10-12 is 250,000 pulses at a duty cycle of .060 sec on and .940 sec off. The combined life test series demonstrated a capability of 375,000 pulses.

Performance Map Data

The performance map data presented in this report consists of pulsing runs of pulse train lengths of 100, performed at supply pressures of 250, 170, 125 and 60 psia. Average impulse bit, impulse bit variation, average specific impulse, start response, average centroid time, centroid time variation and shutdown response are presented as a function of supply pressure in Figures 34C through 61C for the following duty cycles:

<u>On Time</u>	<u>Off Time</u>
.045	.955
.060	1.19
.060	.690
.075	.925

This data is presented to show engine performance at duty cycles other than the nominal .060 sec on and .940 sec off.

Propellant

All testing was conducted using particulate clean propellant, per the NRL specification. In addition, a non-flight tophat type 12 micron absolute screen mesh filter was installed throughout the test program. No problems were encountered as a result of this filter.

Supply Pressure

As noted, the engine was tested at supply pressures ranging from 250 to 60 psia. The engine performance at high pressures was better than at low pressures, typical of the relative performance of the Solrad X engines.

Weight, Envelope and Alignment

These dimensional parameters were measured at the start of Acceptance Testing, Appendix A. The weight, well within the specification limit of 0.80 lb including the inlet adapter and test filter, was 0.396 lb. The nozzle alignment was verified within the 1° allowable. The envelope was inspected against Hamilton

V. B. Test Results - continued

Standard Installation Drawing SVHS755437, which reflects the NRL specification envelope requirements.

Vacuum

The engine is required to operate in pressures from sea level to 10^{-11} torr; all performance testing was conducted at vacuum levels or 3.3×10^{-2} torr (.063 psia) maximum. All other non-performance testing, except external leakage was performed at atmospheric pressure.

Vibration

The engine was exposed to Acceptance and Qualification levels of vibration. Vibration test data are given in Appendix D. There were no performance or leakage anomalies attributable to vibration environments in either phase of testing. There was no apparent structural damage.

Leakage

The engine was leak tested during both Acceptance and Qualification phases of the test program. The maximum seat leakage measured was 3.7×10^{-7} scc He/sec against a specification limit of 1.0×10^{-6} . External leakage was 3.2×10^{-5} scc He/sec maximum against a specification limit of 1.0×10^{-4} .

Proof Pressure

The engine was tested for Proof Pressure, 600 psig, during acceptance testing. There was no visible damage and the engine passed its subsequent leakage and performance tests.

Hamilton
Standard

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A_e

SVHSER 6305

APPENDIX A

ACCEPTANCE TEST PROCEDURES

REVISIONS

SYM.	DESCRIPTION	DATE	APPROVED
A	1. Updated to Amendment # 3. Made corrections 4.4(4) and 4.5.5	4-24-73	<i>to 0004</i>
	2. Added forced cooling to beds.	4-24-73	<i>SC 2001</i>
	3. Corrected digital channel allocations	4-24-73	<i>SC 0001</i>
	4. Page 43 - Corrected paragraph number	4-24-73	<i>SC 0001</i>
	5. Added inspection requirements	4-25-73	<i>SC 0001</i>
	6. Added pages for interim leakage tests	4-25-73	<i>SC 0001</i>
	7. Updated to SVHS6007, Rev. A	5-1-73	<i>SC 0001</i>
B	1. Corrected fuel temperature	<i>6/1/73</i>	<i>SC</i>
	2. Corrected Figure 9		
	3. Updated to Amendment 3		
N/A	UPDATED TO AMENDMENT 4	9/29/73	<i>SC 0001</i>

ACCEPTANCE TEST PROCEDURE
 FOR ROCKET ENGINE ASSEMBLY
 REA-NRL-0.2 PER HIS SPEC SVHS 6007 REV. A AMEND. 4
 HIS PART NUMBER SV 755437

Hamilton Standard

WINDSOR LOCKS, CONNECTICUT • U.S.A.

U
A

ACCEPTANCE TEST FOR ROCKET ENGINE ASSEMBLY REA-NRL-0.2

PER HIS SPEC SVHS 6007

SN 00003

PREP. BY	<i>16/200</i>	QUALITY	<i>26/2/73</i>	SIZE	CODE IDENT NO.	REA-NRL-0.2
TEST ENG.	<i>3-20-73</i>			A	73030	ACCEPTANCE
ENGR.						SHEET 1 of 59

1.0 SCOPE

1.1 Objective of this procedure is to define Acceptance Testing of NRL-0.2 lb. thrust - rocket engine. Controlling specification is SVIS 6007.

1.2 Purpose is to define in clear detail tests, test methods, equipment to be used, data to be recorded, data to be reduced and parameter limits to meet SVIS 6007.

2.0 GENERAL NOTES (Unless otherwise specified)

2.1 Handling

NRL engine shall be handled only by personnel wearing lint-free gloves.

2.2 Cleanliness

2.2.1 REA

Precautions shall be taken to insure maintenance of cleanliness of REA. It shall be protected at all times when out of test rigs by taping clean nylon film securely in place over all openings and bagging using polyethylene film.

2.2.2 Test Rig

2.2.2.1 All test rigs used for testing NRL REA's shall be sampled for cleanliness and certified clean per SVP 114, 129, 130, and 133 as applicable. Inspection to verify current status of rig cleanliness prior to performing tests.

2.2.2.2 An 18 micron or less absolute filter shall be installed directly upstream of the NRL engine for all tests during which fluids are introduced to this unit. Removal of filter shall be accomplished in a (Class 10,000) clean work station only. This filter is an integral part of Thrust Control Valve Assembly.

2.3 Failures

2.3.1 In event of a failure, malfunction, or out-of-tolerance condition, test shall be discontinued.

2.3.2 All deficiencies shall be recorded on the Unit History Form (HSF-454) as well as recorded per Hamilton Standard Reliability Data Report (RDR).

2.3.3 Deficiency shall be investigated, analyzed and corrected and REA retested in accordance with Acceptance Test Procedures or authorized deviation.

Hamilton Standard
WILSON LOCAL, CONNECTICUT - U.S.A.

U
A_c

SIZE
A

CODE IDENT NO.
73030

AT-NRL-0.2

SHEET 2054

2.4 Equipment

2.4.1 Substitution of equipment listed herein may be accomplished if range, accuracy, etc. are equal to or better than the item to be replaced.

2.5 Valve Cycles

2.5.1 Valve cycles shall be recorded in each applicable test and summarized in appropriate table. (Table 9)

3.0 Test Sequence

3.1 Tests must be conducted in the sequence specified below:

	<u>Paragraph</u>
A. Examination of Product	4.1
B. Proof Pressure	4.2
C. Leakage	4.3 & 4.4
D. Vibration	4.5
(A) E. Leakage (internal)	4.4
F. Performance	4.6
G. Leakage	4.3 & 4.4
H. Post Test Inspection	4.7

3.2 Test Fixtures

A. Proof Pressure

Holding/Firing Fixture SVSK 77657-T-001

B. Leakage

Holding/Firing Fixture SVSK 77657-T-001

C. Random Vibration

Vibration Fixture SVSK 77886

D. Performance Test

1. Holding/Firing Fixture SVSK 77657-T-001

4.0 TEST METHODS

- A. The following tests shall be conducted in the sequence listed above. Additional copies of the data sheets may be made for repetitive leakage tests.
- B. Points at which acceptance by Inspection is required are indicated on the test sheets by an asterisk at the detailed step and in the "inspection" block at the lower right hand corner. Other portions of the test are subject to surveillance by Inspection on a non-mandatory basis.

Hamilton Standard
HAMILTON LOCKER, CONNECTICUT, U.S.A.

U
A_c

SIZE
A

CODE IDENT NO.
73030

AT-NRI-U.2

SHEET 3 54

AT - NRL-0.2		SER. NO. <u>00003</u>	
Hamilton Standard <small>Div. of United Aircraft Corp.</small>		TEST DATE <u>7-6-73</u>	
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET		4 OF 5	
REF. SPEC. PARA.	ROOM TEMP (°F)		
	CORR BAR. PRES. (IN. HG)		
4.1	TEST RIG		
4.1	<u>Examination of Product</u>		
4.1.1	Transcribe the weight of the REA as listed in the Assembly Operations Sheets below.		
4.1.2	Transcribe information from the Nozzle Alignment check, to space below.		
4.1.3	Inspect REA for compliance with SVHS 755437 as defined by sales order. Record discrepancies below.		
* 4.1.4	<u>Examination of Product</u>		
	(Transcribed data, discrepancies, comments)		
A.	REA Wt. <u>47146</u> lbs. 0.8 lbs. maximum		
B.	Nozzle Alignment - 1° maximum geometric nozzle centerline from REA mounting surface.		
C.	NC deviations from required dimensions.	<u>U/N 5, 6</u>	
D.	Unit must show evidence of good workmanship.	<u>U/N 3, 4</u>	
E.	Record throat diameter <u>0.302-0.304</u>		
	→ $\angle A \angle B \parallel C = 0^{\circ} 11'$		
	$\angle A \angle B \parallel D = 0^{\circ} 18'$		
		OPERATOR <u>[Signature]</u>	INSPECTOR <u>[Signature]</u>
		U/N 7	SVHS 755437

REF. SPEC. PARA. 4.2	ROOM TEMP (°F) 72	CORR BAR. PRES. (IN. HG) 29.98	TEST RIG 57	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00003	TEST DATE 7-9-73	AT-NHL-0.2 5 OF 54
-----------------------------	----------------------	-----------------------------------	----------------	--	-------------------	---------------------	---------------------------

4.2 PROOF PRESSURE

4.2.1 Set up R/A as shown schematically in Figure 1 and as described below:

A. Connect R/A to the GN₂ source.

B. Connect the Thrust Control Valve (TCV) power electrical connector to a D.C. power supply Valve Connector Pins A positive, B negative, C case ground.

C. Connect a portable voltmeter to the binding posts on the power supply.

D. Install nozzle plug into engine nozzle.

E. Connect a bleed valve to the Pc tap. Verify the valve is closed.

* 4.2.2 Pressurize the engine inlet to 15 ± 5 psig.

* 4.2.3 Energize the TCV by applying 28 ± .5 vdc to the valve using power supply and indicated on voltmeter.

* 4.2.4 Increase the inlet pressure to 600 ± 5 psig.
(Pressurization rate 100 psi/min. max.)

* 4.2.5 Maintain this pressure for two (2) minutes minimum.

4.2.6 At the end of the 2 minute period, close the supply shutoff valve.

OPERATOR
 M. J. SLATE NOV 1-1-73
 INSPECTOR
 # HASTINGS 7-9
 (HU) (SR)

AT - NRL-0.2		SER. NO. <u>06663</u>			
		TEST DATE <u>7-9-77</u>			
Hamilton Standard		U A.			
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET					
REF. SPEC. PARA.	ROOM TEMP (°F)	CORR BAR. PRES. (IN. HG)	TEST RIG		
4.2	72	29.98	57		

4.2.7 Slowly open bleed valve to relieve the pressure within REA to 0 psig (depressurization rate 100 psi/min. max.).

4.2.8 De-energize TCV by turning off D.C. power supply.

4.2.9 Back off N₂ regulator to ambient.

4.2.10 Record data as required in Table 1.

* 4.2.11 There shall be no visible evidence of permanent deformation as a result of proof pressure.

NOTE: In the event of leakage at above interface, REA shall be returned to assembly area. Separate thrust chamber assembly from thrust control valve in accordance with appropriate operation sheet procedure.

Examine the interface seal.

A. If seal appears acceptable notify Quality Assurance and Test Engineer for further disposition.

B. If seal is missing, rolled, cut, or gouged, replace seal, reassemble and repeat above Proof Pressure Test.

OPERATOR
M. J. Slatery 7-9-77
INSPECTOR
* C. HASTINGS 7-9


(HJ)
38

AT - NRL-0.2		SER. NO. <i>00043</i>	
REF. SPEC. PARA. 4.2		ROOM TEMP (°F) <i>73</i>	TEST DATE <i>7-9-73</i>
Hamilton Standard <small>DIVISION OF UNITED TECHNOLOGY CORPORATION</small>		CORR BAR. PRES. (IN. HG) <i>2958</i>	7 OF 51
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET		TEST RIG <i>57</i>	
<p>4.2.12 Remove REA from test setup and transmit to next test area. Record number of valve cycles in appropriate table.</p>			
		OPERATOR <i>M. J. SLATOSKY 7-9-73</i> INSPECTOR <i>C. HASTINGS 7-9</i> (38)	

AT - NRL-0.2

REF. SPEC. PARA.	ROOM TEMP (°F)	SER. NO.
4.2	72	00003
	CORR BAR. PRES. (IN. HG)	TEST DATE
	2996	7-9-73
	TEST RIG	
	57	8 OF 54

Hamilton Standard
U
A₀
 SLS ACCEPTANCE TEST
 OPERATIONS/LOG SHEET



(PART OF T.C.V. ASSEMBLY)

OPERATOR
 M. J. Slattery 7-9-73
 INSPECTOR
 C. Hastings 7-9

FIGURE 1 - PROOF PRESSURE

REF. SPEC. PARA. 4.2	ROOM TEMP (°F) <i>72.0</i>	SER. NO. <i>0000J</i>	AT - NRI-0.2	
	CORR BAR. PRES. (IN. HG) <i>29.40</i>			TEST DATE <i>7-9-73</i>
	TEST RIG <i>57</i>			<i>9 OF 54</i>

Hamilton Standard
DIVISION OF UNITED STATES STEEL CORPORATION
U A
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

TABLE I PROOF PRESSURE DATA

PARAMETER	UNIT	ACTUAL	SPEC
Preliminary Supply Pressure (prior to energizing valve)	psig	<i>15.0</i>	10 - 20
Valve Voltage	vdc	<i>28.0</i>	27.5 - 28.5
Test Pressure	psig	<i>600</i>	595 - 605
Time at Pressure	minutes	<i>2 MIN</i>	2 Minimum
Evidence of Damage or Permanent Deformation	X	<i>NONE</i>	None Allowed
Evidence of Leakage at Interface	X	<i>NONE</i>	None Allowed

 	OPERATOR <i>M. J. SLATON</i> 7-9-73 INSPECTOR <i>C. HASTINGS</i> 7-9
--	---

REF. SPEC. PARA.		ROOM TEMP (°F)	73	Hamilton Standard SERIALIZED TO MIL-STD-883C U A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO.	00003
4.3.2.1		CORR BAR. PRES. (IN. HG)	29.98		TEST DATE	7.10.73
		TEST RIG	NRC 98		10 OF 54	

AT - NRL-0.2

- 4.3 Leakage
- 4.3.1 External Leakage
- 4.3.1.1 Set up and calibrate a mass spectrometer using a maximum helium calibrated leak rate standard of 10^{-4} sec/sec. If direct reading (NRC) mass spectrometer is used, adjust gain control to make meter read value of calibrated leak and record. If indirect reading (VEECO) mass spectrometer is used, record scale reading.
- * 4.3.1.2 Install engine in setup as shown schematically in Figure 2 and as described below:
- A. Connect supply line to REA inlet (18 micron filter already installed).
- B. Connect the Thrust Control Valve (TCV) power electrical connector to a D.C. power supply polarity Pin A Pos. Pin B Neg. Pin C Case GND.
- C. Connect a portable voltmeter to the binding posts on the power supply.
- D. Install a nozzle plug into nozzle.
- E. Connect bleed valve and line as shown in schematic.
- * 4.3.1.3 Energize the TCV by applying $28 \pm .5$ vdc to the valve using power supply and indicated on voltmeter. Then reduce voltage to $20 \pm .5$ vdc.

OPERATOR *R. PATAIK*
INSPECTOR *F. HOCKENHAY*
PS
SB

REF. SPEC. PARA. 4.3.2.1	ROOM TEMP (°F) <u>73</u> CORR BAR. PRES. (IN.HG) <u>29.98</u> TEST RIG <u>NRC 98</u>	Hamilton Standard DIVISION OF UNITED TECHNOLOGIES CORPORATION A SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. <u>00003</u> TEST DATE <u>7-16-73</u> <u>11 OF 5</u>	AT - NRI-0.2
<p>4.3.1.4 Verify that Rig Valves S01, S03 and S05 are closed. Valves S02 and S04 are to be open.</p> <p>4.3.1.5 Using the vacuum source evacuate the engine pressure to less than 0.5 psia.</p> <p>4.3.1.6 Close Rig Valves S02 and S04. Open Valves S01 and S03.</p> <p>4.3.1.7 Slowly pressurize the engine to 300 psia (pressurization rate 100 psi/min. max.). "SNIFF" all external leakage areas for gross leakage. Correct any test setup leakage found. If any gross engine leakage noted, record location and report failure.</p> <p>4.3.1.8 Depressurize the system by closing Rig Valve S01 and slowly opening Bleed Valve S05 (depressurization rate 100 psi/min. max.).</p> <p>4.3.1.9 Place bell jar over engine and evacuate the bell jar to proper operating pressure of mass spectrometer (approximately 0.5 psia). Record background reading. If direct reading (NRC) mass spectrometer is used, adjust zero control to make meter read zero and record. If indirect reading (VEECO) mass spectrometer is used, record scale deflection of meter.</p> <p>* 4.3.1.10 Open Rig Valve S01 and close Bleed Valve S05. Then slowly pressurize the engine to 300 psia. Record leakage reading at the start and end of a 15 minute test period. If a direct reading (NRC) mass spectrometer is used read and record leakage rate. If an indirect reading (VEECO) mass spectrometer is used, record meter deflection and compute leakage rate as follows and record.</p>				
			OPERATOR <u>R. PATRICK</u> INSPECTOR <u>F. HOCKENSHAW</u> (S8)	

REF. SPEC. PARA.		ROOM TEMP (°F)	73	Hamilton Standard SERIES OF UNITED STATES COMPANY A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO.	00003
4.3.2.1		CORR BAR. PRES. (IN.HG)	29.98		TEST DATE	7-16-73
		TEST RIG	NCC 98			13 OF 54

AT - NNL-0.2

4.3.1.10 (Continued)

Standard Leak Rate (scc/sec) = X Scale Deflection due to Unknown Leak - due to Background Scale Deflection due to Standard Leak Rate

NOTE: If leakage exceeds specification:

- A. Return bell jar to ambient pressure.
- B. "SNIFF" all external leakage areas (engine and test setup) for leaks. If leakage was found in setup, depressurize item as described in Paragraph 4.3.1.8, repair leak, reinstall bell jar, evacuate bell jar and repeat Paragraph 4.3.1.10. If leakage was found in engine, terminate test and report failure.

4.3.1.11 Record data as required in Table 2.


4.3.1.12 When testing is completed

- A. Close Rig Valve S01 and slowly open Bleed Valve S05 to relieve the pressure within the engine (depressurization rate 100 psi/min. max.).
- B. De-energize the TCV by turning off D.C. power supply.
- C. Back off regulator to ambient. Shut off vacuum supply.
- D. Remove engine from test setup.

OPERATOR *R. PATRICK*
INSPECTOR *F. HOCKENBURY*



REF. SPEC. PARA. 4.3.2.1	ROOM TEMP (°F) 73	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET		AT- 001-001
CURR BAR. PRES. (IN. HG) 29.58	SER. NO. 0003	TEST DATE 7 10 73		
TEST RIG NRC 98	13 OF 54			



OPERATOR K PATRICK	PR 58
INSPECTOR F McLENNERY	

FIGURE 2 - EXTERNAL LEAKAGE

REF. SPEC. PARA. 4.3.2.1	ROOM TEMP (°F) 73	Hamilton Standard U A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. C0003	AT - NRL-0.2
CORR BAR. PRES. (IN.HG) 29.98	TEST DATE 7-10-73			
TEST RIG NAC 98				14 OF 54

EXTERNAL LEAKAGE (Continued)

TABLE 2

Complete the following table:

PARAMETER	MINIMUM ALLOWABLE	ACTUAL	MAXIMUM ALLOWABLE
Standard Leakage Rate		$.62 \times 10^{-4}$	
Scale Reading of Standard Leakage Rate		$.62 \times 10^{-4}$	
Scale Reading of Background		0	
Inlet Pressure	300 psia	306	310 psia
Item Helium Rate (Initial)		0	1×10^{-4} scc/sec
Item Helium Rate (Final)		6×10^{-5}	1×10^{-4} scc/sec
Test Duration	15 minutes	15 MINUTES	15.25 minutes
REA Valve Actuation Voltage	27.7 vdc	28.0	28.3 vdc
REA Valve Running Voltage	19.7 vdc	20.0	20.3 vdc
REA Valve Cycles		4	

OPERATOR
R. Farnick

INSPECTOR
J. HOLCOMB

REF. SPEC. PARA. 4.3.2.2		ROOM TEMP (°F) 73	Hamilton Standard SER. NO. 00003		AT - NRL-0.2
		CORR BAR. PRES. (IN. HG) 29.90	TEST DATE 7.10.73		
		TEST GAS NRC 48	15 OFF 5 1/2		

U
A.
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

LEAKAGE (Continued)

4.4 Internal Leakage

1. Set up and calibrate a helium mass spectrometer using a maximum helium calibrated leak rate standard of 10^{-4} scc/sec. If direct reading (NRC) mass spectrometer is used, adjust gain control to make meter read value of calibrated leak and record. If indirect reading (Veeco) mass spectrometer is used record scale reading.
2. Install REA in a test setup as shown in Figure 3. REA valve is to be closed for this test.
3. Evacuate the mass spectrometer to its operating pressure.
4. Close helium supply shutoff (S01) valve, open the vacuum pump shutoff (S02) and evacuate the pressurization line to less than 0.5 psia. Record background reading.
5. Close vacuum pump shutoff (S02), open helium supply shutoff valve (S01) and pressurize the REA inlet to 100 psia by applying GHe pressure to the inlet (pressurization rate 100 psi/minute maximum).
6. Record the helium leakage rate at the start and end of a 15 minute minimum period. If direct reading (NRC) mass spectrometer is used, read and record leakage rate. If indirect reading (Veeco) mass spectrometer is used, record scale deflection of meter. If an indirect reading (Veeco) mass spectrometer is used, record scale deflection of meter. If an indirect reading (Veeco) mass spectrometer is used, record scale deflection of meter. If an indirect reading (Veeco) mass spectrometer is used, record scale deflection of meter.

OPERATOR <i>R. Parake</i>
INSPECTOR <i>J. Heikens</i>

58

REF. SPEC. PARA. 4.3.2.2		ROOM TEMP (°F) 73	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00013	AT - NRL-0.2
CORR BAR. PRES. (IN. HG) 2998		TEST DATE 7-10-73			
TEST RIG NRC 98		16 CT-54			

LEAKAGE (Continued)

4.4 Continued

6. spectrometer is used compute leakage rate from meter deflection as follows:

Standard Leak	Scale Deflection	Scale Deflection
Leak Rate scc/sec = $\frac{\text{Rate (scc/sec)}}{\text{Scale Deflection}}$.X due to Unknown Leak	- due to Background
	<u>Scale Deflection due to Standard Leak</u>	

7. Back off regulator to depressurize REA.

OPERATOR R. Patrick
INSPECTOR F. Hockensberry

PR 58

REF. SPEC. PARA. 4.3.2.2	ROOM TEMP (°F) 73	CORR BAR. PRES. (IN.HG) 998	TEST RIG NRC 98	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	AT - NRL-0.2
				SER. NO. 00003 TEST DATE 2-10-73 17 OF 54	

HELIUM SUPPLY → VALVE → PRESSURE GAUGE → RELIEF VALVE SET AT 4.0 PSIA MAX. → 18 MICRON ABSOLUTE FILTER (PART OF TC V ASSEMBLY) → TEST ITEM, NOZZLE PLUGGED → VACUUM PUMP

BELL JAR

OPERATOR *R. PATRICK*
 INSPECTOR *F. HOCKENBURY*
58

FIGURE 3 - INTERNAL LEAKAGE

REF. SPEC. PARA. 4.3.2.2	ROOM TEMP (°F) 73	Hamilton Standard U A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00043	AT - NRL-0.2
	CORR BAR. PRES. (IN.HG) 29.98		TEST DATE 7-10-73	
	TEST RIG NRC 98		18 OF 54	

INTERNAL LEAKAGE (Continued)

TABLE 3

4.4 (Continued)

PARAMETER	MINIMUM ALLOWABLE	ACTUAL	MAXIMUM ALLOWABLE
Standard Leakage Rate		$.62 \times 10^{-4}$	
Scale Reading of Standard Leakage Rate		$.62 \times 10^{-4}$	
Scale Reading of Background		0	
Inlet Pressure	100 psia	100	105 psia
Item Helium Leakage Rate (Initial)		0	1×10^{-6} scc/sec
Item Helium Leakage Rate (Final)		$.6 \times 10^{-7}$	1×10^{-6} scc/sec
Duration	15 minutes	15 MINUTES	15.25 minutes

OPERATOR **R. Parick**
INSPECTOR **F. Hockmeyer**

SR SB

REF. SPEC. PARA.	ROOM TEMP (°F)	CORR BAR. PRES. (IN-HG)	TEST RIG	SER. NO.	TEST DATE	AT - NRL-0.2												
4.4	91	91	91	00003	7/11/73													
Hamilton Standard DIVISION OF UNITED TECHNOLOGIES CORPORATION				U A.														
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET																		
4.5 <u>Random Vibration</u>																		
4.5.1 Prepare REA for vibration test in a clean (Class 10,000) work station.																		
4.5.2 Tape Pc tube nut to bottom of Pc tube. Cover Pc tube opening with Polyethylene bag and tape on.																		
4.5.3 Cover nozzle with polyethylene bag																		
* 4.5.4 Move REA to Vibration Lab area. Bolt REA to Vibration Fixture SVSK77886 and vibration fixture to vibration table.																		
4.5.5 REA axes orientation are shown in Figure 4.																		
4.5.6 A triaxial accelerometer shall be used for control and shall be located to provide the following input:																		
* 4.5.7 Vibrate the REA in each axis per the schedule below. Rms shall be conducted at ambient temperature and pressure and may be conducted in any sequence.																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Frequency-Hz</th> <th style="text-align: left;">Level</th> <th style="text-align: left;">Rate or Time</th> </tr> </thead> <tbody> <tr> <td>20 - 200</td> <td>0.1 g²/Hz</td> <td>2 minutes minimum</td> </tr> <tr> <td>200 - 2000</td> <td>-6.0 db/oct</td> <td>per axis</td> </tr> <tr> <td></td> <td>rolloff</td> <td></td> </tr> </tbody> </table>							Frequency-Hz	Level	Rate or Time	20 - 200	0.1 g ² /Hz	2 minutes minimum	200 - 2000	-6.0 db/oct	per axis		rolloff	
Frequency-Hz	Level	Rate or Time																
20 - 200	0.1 g ² /Hz	2 minutes minimum																
200 - 2000	-6.0 db/oct	per axis																
	rolloff																	
				OPERATOR <i>R.A. Mallet 7/11/73</i> INSPECTOR <i>F. HOCKENBERRY</i> (2) (58)														

AT - NRL-0.2		SER. NO. 00003	
Hamilton Standard <small>Div. of UNITED STATES CORP.</small>		TEST DATE 7/11/73	
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET		20 of 54	
REF. SPEC. PARA.	ROOM TEMP (°F)		
4.4	CORR BAR. PRES. (IN. HG)		
	TEST RIG 91		
4.5.8	At conclusion of test remove accelerometer bonding material from REA. Remove Tape Residue.		
* 4.5.9	The REA must pass subsequent Leakage and Performance Test. There shall be no damage or deformation.		
OPERATOR R.A. MICKET 7/11/73		INSPECTOR * F. HOCKESSER	

AT - NRL-0.2

SER. NO.

00003

TEST DATE

7/11/73

21 OF 54

Hamilton Standard

U
A₀

SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

ROOM TEMP (°F)

CORR BAR PRES. (THICK)

TEST RIG

91

REF. SPEC. PARA.

4.4




FIGURE 4

AXES ORIENTATION

OPERATOR *R.A. Nickear* 7/11/73

INSPECTOR *H. Hockley*

PR 30

(A)

REF. SPEC. PARA. 4.3.2.2	ROOM TEMP (°F) <u>73</u> CORR BAR. PRES. (IN. HG) <u>29.82</u> TEST RIG <u>NRC 98</u>	Hamilton Standard U SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. <u>02033</u> TEST DATE <u>7-12-73</u> <u>23 OF 54</u>
-----------------------------	---	---	--

AT - NRI-0.2

LEAKAGE (Continued)

4.4 Internal Leakage

1. Set up and calibrate a helium mass spectrometer using a maximum helium calibrated leak rate standard of 10^{-4} scc/sec. If direct reading (NRC) mass spectrometer is used, adjust gain control to make meter read value of calibrated leak and record. If indirect reading (Veeco) mass spectrometer is used record scale reading.
2. Install REA in a test setup as shown in Figure 3. REA valve is to be closed for this test.
3. Evacuate the mass spectrometer to its operating pressure.
4. Close helium supply shutoff (SO1) valve, open the vacuum pump shutoff (SO2) and evacuate the pressurization line to less than 0.5 psia. Record background reading.
5. Close vacuum pump shutoff (SO2), open helium supply shutoff valve (SO1) and pressurize the REA inlet to 100 psia by applying GHe pressure to the inlet (pressurization rate 100 psi/minute maximum).
6. Record the helium leakage rate at the start and end of a 15 minute minimum period. If direct reading (NRC) mass spectrometer is used, read and record leakage rate. If indirect reading (Veeco) mass spectrometer is used, record scale deflection of meter. If an indirect reading (Veeco) mass

OPERATOR R. Patrick
 INSPECTOR E. SHANNON 7/12/73

REF. SPEC. PARA. 4.3.2.2		ROOM TEMP (°F) 73	SER. NO. 00003		AT - NRL-0.2
CORR BAR. PRES. (IN. HG) 29.82		TEST DATE 7-12-73			
TEST RIS NRC 98		TEST DATE 24 0.54			

Hartilton Standard
U A₀
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

LEAKAGE (Continued)

4.4 Continued

7. Spectrometer is used compute leakage rate from meter deflection as follows:

$$\text{Leak Rate scc/sec} = \frac{\text{Standard Leak Rate (scc/sec)} \times \text{Scale Deflection}}{\text{Scale Deflection - due to Unknown Leak - due to Background Scale Deflection due to Standard Leak}}$$

8. Back off regulator to depressurize REA.

OPERATOR
INSPECTOR
7/12/73

AT - NRL-0.2


SER. NO. 00003

TEST DATE 7-12-73

25 OF 54

Hamilton Standard
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

REF. SPEC. PARA. 4.3.2.2
ROOM TEMP (°F) 73
CORR BAR. PRES. (IN. HG) 29.82
TEST RIG MRC 98



OPERATOR R. Parvick
INSPECTOR E. SWANMAN 7/16/73

38

FIGURE 3 ~ INTERNAL LEAKAGE

REF. SPEC. PARA. 4.3.2.2	ROOM TEMP (°F)	73	Hamilton Standard U A₀ SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO.	00003
	CONN BAR. PRES. (IN. HG)	29.82		TEST DATE	7-12-73
	TEST RIG	NRC 98			26 OF 54

AT - NRL-0.2

INTERNAL LEAKAGE (Continued)

TABLE 3

4.4 (Continued)

PARAMETER	MINIMUM ALLOWABLE	ACTUAL	MAXIMUM ALLOWABLE
Standard Leakage Rate	100 psia	.62 x 10 ⁻⁴	105 psia
Scale Reading of Standard Leakage Rate	100 psia	.62 x 10 ⁻⁴	1 x 10⁻⁶ scc/sec
Scale Reading of Background	100 psia	0	1 x 10⁻⁶ scc/sec
Inlet Pressure	100 psia	10 ±	105 psia
Item Helium Leakage Rate (Initial)	100 psia	0	1 x 10⁻⁶ scc/sec
Item Helium Leakage Rate (Final)	100 psia	.4 x 10 ⁻⁷	1 x 10⁻⁶ scc/sec
Duration	15 minutes	15 MIN.	15.25 minutes

OPERATOR *R. PATRICK*
INSPECTOR * *F. SULLIVAN* 7/12/73

REF. SPEC. PARA. 4.5.2.2	ROOM TEMP (°F)	74	Hamilton Standard A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO.	00003	AT - NRI-0.2
	CORR BAR. PRES. (IN. HG)	29.98		TEST DATE	7-13-73	
	TEST RIG	H-2			270-54	

4.6 Performance Test

- A. Install REA in firing fixture SVSK77657T001.
- B. Install K type temperature thermocouple on bed of REA as shown in Figure 5.
- C. Install valve temperature (T Type) thermocouple as shown in Figure 5.
- D. Install the REA in a simulated Altitude Test Facility (H-2) and connect per Figure 6. Install indirect forced GN₂ cooling over bed.
- E. Propellant flow diagram and instrumentation signal routing are shown in Figures 6 and 7.
- F. Set up Visicorder in accordance with Figure 8.
- G. Set up Digital Instrumentation in accordance with Figure 9.

4.6.1 Sensor Installation Check

Prior to firing test perform following checks:

- A. Valve Voltage and Current Pin 1 Pos. Pin B Neg. Pin C Case GND.
 - 1. Install a 180 ohm (approximate) resistor in test cell at REA valve driver output. Actuate valve driver in pulse mode. Verify that valve voltage and valve current traces are obtained on Visicorder. Measure voltage supplied to valve via a voltage divider using a differential voltmeter, while the valve driver is actuated in Steady State Mode. Set valve supply voltage to 28 ± 2 vdc. Record power supply voltage using Fluke Voltmeter and valve supply voltage on Log Sheet. Use facility driver circuit for all firing tests.

OPERATOR	S Kibbe
INSPECTOR	

AT - NRL-0.2

REF. SPEC. PARA. 4.5.2.2	ROOM TEMP (°F) 74	Hamilton Standard U A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00003
	CORR BAR. PRES. (IN. HG) 29.85		TEST DATE 7-13-73
	TEST RIG H-2		28 JF 54

4.6.1 Continued

B. Servomanometer

Measure initial and final voltage level of servomanometer on differential voltmeter for each steady state and pulse run. Record these values on digital data log.

C. REA Chamber Pressure

With the test cell at altitude conditions (8.35 mm Hg vacuum pressure) verify that the reading for chamber pressure is 0 ± 5 psia. Use a differential voltmeter to measure the transducer output.

D. Inlet Pressure

Prior to each steady state run record inlet pressure transducer output on digital data log. Use a differential voltmeter to measure the transducer output (must be ± 3 psi from gage reading).

E. Tank Pressure

Prior to each pulsing run record tank pressure transducer output on digital data log. Use a differential voltmeter to measure the transducer output (must be ± 3 psi from gage reading).

(S8)	OPERATOR 5 Lines
	INSPECTOR

REF. SPEC. PARA.		ROOM TEMP (°F)	74	Hamilton Standard DIVISION OF UNITED TECHNOLOGIES CORPORATION U A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO.	0000J	AT - NRL-0.2
4.5.2.2		CORR BAR. PRES. (IN. HG)	21.85		TEST DATE	7-13-73	
		TEST RIG	H-2		27 OF 54		

4.6.1 Continued

F. Excitation Voltage

Measure excitation supply voltage for cell where data is being acquired from and record on digital data log once per cell setup.

G. Fuel Inlet Temperature

Read fuel temperature using differential voltmeter and record on digital data log for each run.

H. Set rig relief valve to 450 psia maximum.

4.6.2 Evacuate propellant system as follows: (See alternate method Step 4.4.2.1 before proceeding)

- A. Transfer fuel from servo back to run tank as follows: Close Valves 3, 5 and 6, open Valves 1, 2, 4 and 14. Slowly pressurize servo with GN₂, purge fuel back to run tank. Close Valves 1, 2, 4, and 14.
- B. At approximately 15 psig purge fuel from system by opening the following valves: 8, 9, 12, 13, 10.
- C. When fuel is no longer observed at the drain line, close Valves 12 and 10, open Valves 1, 2, 4 and 6 and continue to purge remaining fuel back to run tank. Close Valves 1, 2, 4 and 6. Reduce purge pressure to ambient.
- D. Open the following valves: 2, 4, 6 and 12. Close all remaining valves.

OPERATOR	S. KISSE
INSPECTOR	

REF. SPEC. PARA. 4.5.2.2.	ROOM TEMP (°F) 74 CORR BAR. PRES. (IN. HG) 29.85 TEST RIG H. 2	Hamilton Standard U A SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00003 TEST DATE 7-13-73 30 OF 54	AT - NRI-0.2
<p>4.6.2 Continued</p> <p>i. Connect outlets of Valve 15 to a vacuum source. Open Valves 11, 13 and 15 and evacuate at less than 1 psia for 30 minutes minimum.</p> <p>f. Close Valve 15. Shut off vacuum source. Verify Valves 3, 5, 8, 9, 10, 12, 13 and 15 are closed.</p> <p>g. Pressurize supply tank to approximately 10 psig and open Valve 1 to fill lines with fuel.</p> <p>ii. Open Valves 2, 4 and 14 to fill servo, then close Valves 2 and 4.</p> <p>1. Open Valves 14 and 6, and all other valves closed pressurize servo to 295 ± 5 psia. Depressurize servo to ambient pressure and note the difference in output voltage. Voltage change must be less than .24 vdc. (If not, repeat Step 4.6.2 until voltage change is acceptable).</p> <p><u>4.6.2.1 Rig evacuation alternate method:</u></p> <p>A. This step is to be used only if REA installation takes place within 8 hours of removal of previous REA and test rig valve positions are the same and test rig fuel system has not been broken into.</p> <p>B. Connect Valves 11, 13 and 15 to a vacuum source. All other valves are closed. Open Valves 11, 13 and 15 and evacuate at 1 psia or less for 30 minutes minimum.</p>				
				OPERATOR S. KIRK INSPECTOR

REF. SPEC. PARA. 4.5.2.2 4.6.2.1	ROOM TEMP (°F) 74 <hr/> CORR BAR. PRES. (IN. HG) 29.65 <hr/> TEST RIG H-2	Hamilton Standard U A SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00003 <hr/> TEST DATE 7-13-73 <hr/> 31 OF 54	AT - NRL-0.2
--	--	--	---	--------------

4.6.2.1 Continued

C. Close Valves 11, 13 and 15, open Valves 1, 2, 4 and 6 with N2H4 supply tank pressurized to approximately 10 psig. Perform system check per Step 4.6.2(I). If this step is not performed, cross out this step and write "N/A".

4.6.3 Establish the following initial conditions:

- A. Fuel temperature - $70 \pm 15^{\circ}\text{F}$
- B. Vacuum pressure - 8.35 mm Hg
- C. Valve voltage supply - 26 - 30 vdc
- D. PTANK = 250 ± 10 psia. Pressurize by opening tank GN2 supply valve, Valves 1, 2, 4 and 6. Slowly increase GN2 pressure using regulator to specified value as indicated by P_{in} transducer output.

4.6.4 Acquire Visicorder data as follows:

- A. Pulsing at 2 ips except 20 ips for pulses 1 through 10, 45 through 55, and 90 through 100.
- B. For Steady State - first two seconds out of each ten at 20 ips. Remainder at 2 ips. Last two seconds at 20 ips.

4.6.5 All runs are to be made from the Servomanometer (no flowmeters required). To pressurize for run, open Valves 14 and 6 and slowly pressurize to required value (indicated on P_{in} transducer output, for S.S. runs, P_{tank} transducer output for pulse runs.

REF. SPEC. PARA.		ROOM TEMP (°F)	SER. NO.		AT - NRL-0.2
4.5.2.2		74	00003		
		CORR BAR. PRES. (IN. HG)	TEST DATE		
		29.85	7-13-73		
		TEST RIG	TEST SHEET		
		H-2	52 OF 54		

Hamilton Standard
A.
 SLS ACCEPTANCE TEST
 OPERATIONS/LOG SHEET

4.6.6 Acquire all data on digital tape as follows:

A. Steady State runs:

Acquire 3 second lead-in plus entire run plus 11 second trailer.

B. Pulse Runs:

Acquire 3 second lead-in, all pulses from 1 second before to 11 seconds after each pulse train inclusive.

4.6.7 Firing Sequence

RUN	P _T /P _I TRANSDUCER	T _{ON}	T _{OFF}	CHAMBER PRESSURE	T _{FUEL}	T _{BED}	N PULSES	SEQUENCE TAPE
1	250 ± 5	40	-	8.35 mm Hg	70 ± 15	70 ± 10	1	NRL-LT-1
2	250 ± 5	0.06	0.94	8.35 mm Hg Max.	70 ± 15	70 ± 10	100	NRL-LT-2
3	250 ± 5	60	-	8.35 mm Hg	70 ± 15	70 ± 10	1	NRL-LT-3

A. Bed may be indirectly cooled with GN2 between runs after temperature has decreased to 600°F.

OPERATOR	K. SELL
INSPECTOR	

AT - NRL-0,2

REF. SPEC. PARA. 4.5.2.2	ROOM TEMP (°F) 74	SER. NO. 00003	
	CORR BAR. PRES. (IN. HG) 29.83		TEST DATE 7-13-73
	TEST RIG		

Hamilton Standard
 DIVISION OF UNITED TECHNOLOGIES CORPORATION
U A.
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

4.6.8 Test Shutdown

After completion of the firing test, close Valve 7, apply 10-15 psig GN₂ through Valves 8 & 9, open Valves 12 and 13 to drain fuel from rig. Close Valves 12 and 13, and actuate REA valve for 120 seconds followed by 25 pulses 1 second on, 1 second off.

D. Brown 7/13/73
Remove REA from test stand and remove heat shield from REA.

4.6.9 Flush -


1. Install REA in a flush rig as shown in Figure 10.
2. Open H₂O supply valve, pressurize H₂O to 10-15 psig, and actuate the REA at an approximate duty cycle of 50 seconds on, 10 seconds off, for 15 pulses. Apply 28 ± 2 vdc to actuate the valve, Pin A+, Pin B- for Steps 2, 3, and 4.
3. Close H₂O supply valve, open isopropyl alcohol supply valve. Pressurize IPA to 10-15 psig and actuate the REA at an approximate duty cycle of 50 seconds on, 10 seconds off for 5 pulses.
4. Purge REA with GN₂ (valve held open with 20 ± 2 vdc after opening) at 10-15 psig until IPA ceases flowing from valve. Close valve.
5. Install the REA in a vacuum desiccator and vacuum dry valve at 1500 microns Hg or less for one hour minimum. Record data in the data table.

D. Brown 7/13/73

W. Murphy 7/13/73

OPERATOR <i>W. Murphy 7/13</i>
INSPECTOR

AT - 381-0.2	SER. NO. 00003	
	TEST DATE 2/13/53	
	37 OF 54	
REF. SPEC. PARA. 4.5.2.2	MOOM TEMP (°F) 74	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET
	CORR BAR. PRES. (IN. HG) 27.85	
	TEST RIG H-2	



OPERATOR F. LARREZ
INSPECTOR

58

THERMOCOUPLE LOCATIONS ~ FIGURE 5

AT - N11-0.2

SER. NO. 00003

TEST DATE 7-13-73

35 JI 54

Hamilton Standard ENGINEERING CORPORATION

U

A8

SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET


REF. SPEC. PARA. 4.5-2.2.

ROOM TEMP (°F) 74

CORR BAR. PRES. (IN.HG) 29.85

TEST RIG H-2

RIG H-2



OPERATOR K/SEL

INSPECTOR D/TUCKER

(EW) (58)


PROPELLANT FLOW DIAGRAM - FIGURE 6

7/13/73

AT - NKL-0.2	REF. SPEC. PARA. 4.5.2.2	ROOM TEMP (°F) 74	SER. NO. 00003
	CORN BAR. PRES. (IN. HG) 29.85	H-2	TEST DATE 7-13-73
	TEST RIG		PG. OF 54

Hamilton Standard
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET

PERFORMANCE (Continued)



OPERATOR *LAFREY*
 INSPECTOR *TUCKER* (EW)
 7/13/73

INSTRUMENTATION SIGNAL ROUTING - FIGURE 7

REF. SPEC. PARA. 4.5.2.2	ROOM TEMP (°F) 74	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET		AT- NKL-0.2
CORR BAR. PNC3. (IN. HG) 2985	TEST RIG H-2	SER. NO. 00003		TEST DATE 7-13-73
				39 OF 54

PERFORMANCE (Continued)

VISICORDER SETUP		
PARAMETER	CAL RANGE	APPROXIMATE SCALE FACTOR
Valve Voltage	0-30 vdc	3" Span
Valve Current	0-0.5 amp	3" Span
Inlet Pressure	0-300 psia	60 psi/inch
Chamber Pressure	0-450 psia	50 psi/inch
Chamber Temperature	0-1500°F	300°F/inch
Valve Temperature	0-500°F	100°F/inch

OPERATOR LAFFERT
INSPECTOR TUCKER

FIGURE 8

7-13-73

AT - NAL-0.2

SER. NO. 06003

TEST DATE 7-13-73

38 OF 54

Hamilton Standard
U
A₀
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET

ROOM TEMP (°F) 74
 CORR BAR. PRES. (IN.HG) 29.85
 TEST RIG H-2

REF. SPEC. PARA. 4.5.2.2.

PERFORMANCE (Continued)

INSTRUMENTATION DIGITAL

PARAMETER	MEASUREMENT DEVICE	MANUFACTURER	MODEL NO.	CAL. RANGE	ACCURACY	CHANNEL 1-20	CHANNEL 20-40	GAIN
Valve Voltage	Divider	IIS	SVSK79575	0-30 vdc	-	1	21	5
Fuel Flow	Servomanometer	Exactel	TS 40 in .312" Bore	0-.1 lbm	± 1% R	2	22	1
Inlet Pressure	Transducer	Statham	PA8019 PA850 PA861	0-300 psia	± 1% FS	3	23	200
Chamber Press.	Transducer	Statham	PA8019	0-300 psia	± 0.3% FS	4	24	200
Valve Current	Divider	IIS	SVSK79575	0-1 amp	-	5	25	50
Tank Pressure	Transducer	Statham	PA822	0-300 psia	± 1% FS	6	26	200
FLOW METER Temperature	Thermocouple		Type T	0-200°F	± 5°F	7	27	1000
	Excitation Volt.			10 vdc nom		11	31	.5
Fuel Temp.	Thermocouple		Type T	0-200°F	± 5°F	12	32	1000

OPERATOR *Lafferty*
 INSPECTOR *Tucker* **EW**

58

FIGURE 9

7-13-73

AT - ARL-0.2

SER. NO. 00003
 TEST DATE 7-13-73
 59 JF 54

Hamilton Standard
 SLS ACCEPTANCE TEST
 OPERATIONS/LOG SHEET

ROOM TEMP (°F) 74
 CYCLE BAR. PRES. (IN.HG) 29.85
 TEST RIG H-2

PERFORMANCE (Continued)

INSTRUMENTATION DIGITAL


PARAMETER	MEASUREMENT DEVICE	MANUFACTURER	MODEL NO.	CAL. RANGE	ACCURACY	CHANNEL	GAIN
Chamber Temperature	Thermocouple		Type K .020"	0-1500°F	± 10°F	1-20 14 34	200
Vacuum Pressure	Gage	Hastings	VT-4	0-20 mm Hg	± 2% Ang Def.	8	1000
Tank Pressure	Gage	Heise	C	0-300 psia	± .5% FS		
Valve Temp.	Thermocouple		Type T	0-500°F	± 5°F	16	1000

OPERATOR LAFFERT
 INSPECTOR D TUCKER

FIGURE 9 (Continued)

7-13-73

AT - MIL-U.2	SER. NO. 00003	Hamilton Standard U 1-10	ROOM TEMP (°F) 74	TEST DATE 7-13-73
4.5.2.2	CORR BAR. PRES. (IN. HG) 29.85	SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	TEST RIG CWS #4	90 OF 54



OPERATOR D. Sullivan
INSPECTOR J. Tucker (E)

58

FIGURE 10 - REAR FLUSH

7-13-73

REF. SPEC. PARA. 4.5.2.2	ROOM TEMP (°F) 74	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00003	AT - NRL-0.2
CORR BAR. PRES. (IN.HG) 27.65	TEST DATE 7-13-73			
TEST RIG H 2	41 01 54			

TABLE 7

INITIAL PERFORMANCE DATA

PARAMETER	ACTUAL	SPEC
Servo Deflection (vdc)	.19	0.24 Max.
Valve Voltage (vdc)	28.0	26 - 30

OPERATOR K. ILL
INSPECTOR * D. TUCKER
WITNESSED 7-13-73

38

SPACE & LIFE SYSTEMS LABORATORY

LOG OF TEST

TYPE OF TEST: *Performance Test*
TEST ENGINEER: *W. Smith*
NAME OF RIG: *H-2*
PROJECT & ENG. ORDER NO.: *A69-100-300A*

SHEET 1 OF 1
TEST PLAN NO. *SPS 6007*
MODEL NO. *NRK*
PART NO. *ST 155427-6*
SERIAL NO. *00003*
OPERATOR: *Libbe*

Time	Run #	Rate	Flow	Temp	Pressure	Flow	Temp	Pressure	Flow	Temp	Pressure	Flow	Temp	Pressure	Flow	Temp	Pressure
1525	2447	250	247	250	182	40	-	1	1.5	69	67	335	1.65	1.70			
1623	2447	241	247	241	111	01	.14	100	1.75	70	71	366	329	.37			
1701	2447	250	247	247	185	60	-	1	1.6	70	76	310	131	259			
1742	-	28	29	29	Package	120	1	1									
1749	-	28	29	29	Package	1	1	25									

REMARKS: *TRANS DUCERS
PI 2834
PC 147*

*START 15:00
15:00
15:19*

9268

REF. SPEC. PARA. 4.5.2.2	ROOM TEMP (°F) 74	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00003
CORR BAR. PRES. (IN. HG) 29.65	TEST DATE 7-13-73		
TEST RIG CWS #4			
		AT - NRL-0.2	
		43 OF 54	

TABLE 8
VALVE FLUSH

4.6.9 Continued

PARAMETER	MINIMUM ALLOWABLE	ACTUAL	MAXIMUM ALLOWABLE
H ₂ O Flush	Inlet Pressure	12.	15 psig
	Supply Voltage	20.	30 vdc
IPA Flush	No. of Pulses	15.	15
	Duration	15.	17 minutes
GN ₂ Purge	Inlet Pressure	12.	15 psig
	Supply Voltage	20.	30 vdc
Vacuum Dry	No. of Pulses	5.	5
	Duration	5.	7 minutes
Vacuum Dry	Inlet Pressure	12.	15 psig
	Supply Voltage	20.	22 vdc
Vacuum Dry	Vacuum Pressure Start	2230	1500 Hg
	Vacuum Pressure End	0900	1500 Hg
Vacuum Dry	Duration	10.5	1 hour

D TUCKER 7/13/73
D BARNETT 7/13/73

OPERATOR
W. MURPHY 7-18-73
INSPECTOR
C. HASTINGS 7-14

REF. SPEC. PARA.		ROOM TEMP (°F)	Hamilton Standard		SER. NO.	AT - NRL-0.2	
4.3.2.1		73	U		00003		
		CORR BAR. PRES. (IN. HG)	A ₀		TEST DATE	7-17-73	
		29.89	SLS ACCEPTANCE TEST				
		TEST RIG	OPERATIONS/LOG SHEET			44 OF 54	
		NAC 98					

- 4.3 Leakage
- 4.3.1 External Leakage
- 4.3.1.1 Set up and calibrate a mass spectrometer using a maximum helium calibrated leak rate standard of 10^{-4} scc/sec. If direct reading (NRC) mass spectrometer is used, adjust gain control to make meter read value of calibrated leak and record. If indirect reading (VEECO) mass spectrometer is used, record scale reading.
- * 4.3.1.2 Install engine in setup as shown schematically in Figure 2 and as described below:
- A. Connect supply line to REA inlet (18 micron filter already installed).
 - B. Connect the Thrust Control Valve (TCV) power electrical connector to a D.C. power supply polarity Pin A Pos. Pin B Neg. Pin C Case GND.
 - C. Connect a portable voltmeter to the binding posts on the power supply.
 - D. Install a nozzle plug . . . into nozzle.
 - E. Connect bleed valve and line as shown in schematic.
- * 4.3.1.3 Energize the TCV by applying $28 \pm .5$ vdc to the valve using power supply and indicated on voltmeter. Then reduce voltage to $20 \pm .5$ vdc.

OPERATOR
E. LASZCZYK

INSPECTOR
A. GILL 7-17-73

REF. SPEC. PARA.		ROOM TEMP (°F)	SER. NO.		AT - NRL-0.2
4.3.2.1	CORR BAR. PRES. (IN.HG)	73	00003		
	TEST RIG	29.69 NRC 98	TEST DATE		
			7-17-73		
Hamilton Standard			45 OF 54		
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET					

- 4.3.1.4 Verify that Rig Valves S01, S03 and S05 are closed. Valves S02 and S04 are to be open.
- 4.3.1.5 Using the vacuum source evacuate the engine pressure to less than 0.5 psia.
- 4.3.1.6 Close Rig Valves S02 and S04. Open Valves S01 and S03.
- 4.3.1.7 Slowly pressurize the engine to 300 psia (pressurization rate 100 psi/min. max.). "SNIFF" all external leakage areas for gross leakage. Correct any test setup leakage found. If any gross engine leakage noted, record location and report failure.
- 4.3.1.8 Depressurize the system by closing Rig Valve S01 and slowly opening Bleed Valve S05 (Depressurization rate 100 psi/min. max.).
- 4.3.1.9 Place bell jar over engine and evacuate the bell jar to proper operating pressure of mass spectrometer (approximately 0.5 psia). Record background reading. If direct reading (NRC) mass spectrometer is used, adjust zero control to make meter read zero and record. If indirect reading (VEECO) mass spectrometer is used, record scale deflection of meter.
- * 4.3.1.10 Open Rig Valve S01 and close Bleed Valve S05. Then slowly pressurize the engine to 300 psia. Record leakage reading at the start and end of a 15 minute test period. If a direct reading (NRC) mass spectrometer is used read and record leakage rate. If an indirect reading (VEECO) mass spectrometer is used, record meter deflection and compute leakage rate as follows and record.

OPERATOR	F. LISZCZYK
INSPECTOR	A. GILL 7-17-73
58	

REF. SPEC. PARA. 4.3.2.1	ROOM TEMP (°F) 73	Hamilton Standard U A SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00003	AT - NRL-0.2
	CORR BAR. PRES. (IN.HG) 29.85		TEST DATE 7-17-73	
	TEST RIG NRC 98		16 OF 54	

4.3.1.10 (Continued)

Standard Leak Rate (scc/sec) = X Scale Deflection due to Unknown Leak - due to Background Scale Deflection due to Standard Leak Rate

NOTE: If leakage exceeds specification:

- A. Return bell jar to ambient pressure.
- B. "SNIFF" all external leakage areas (engine and test setup) for leaks. If leakage was found in setup, depressurize item as described in Paragraph 4.3.1.8, repair leak, reinstall bell jar, evacuate bell jar and repeat Paragraph 4.3.1.10. If leakage was found in engine, terminate test and report failure.

4.3.1.11 Record data as required in Table 2.

4.3.1.12 When testing is completed

- A. Close Rig Valve S01 and slowly open Bleed Valve S05 to relieve the pressure within the engine (depressurization rate 100 psi/min. max.).
- B. De-energize the TCV by turning off D.C. power supply.
- C. Back off regulator to ambient. Shut off vacuum supply.
- D. Remove engine from test setup.

OPERATOR E. LAZARCYK
INSPECTOR A. GILL
7-17-73

AT - NNL-0.2

SER. NO. 00003

TEST DATE 7-17-73

47 OF 54

Hamilton Standard
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET


ROOM TEMP (°F)

CURR BAR. PRES. (IN. HG)

TEST RIG

REF. SPEC. PARA.

4.3.2.1



OPERATOR E. LAJZCZYK

INSPECTOR (TH) A. CIEL 7-17-73

FIGURE 2 - EXTERNAL LEAKAGE

AT - NRL-0.2

SER. NO. 00003
 TEST DATE 7-17 73
 48 OF 54

Hamilton Standard ~~U~~ **A0**
 SLS ACCEPTANCE TEST
 OPERATIONS/LOG SHEET

ROOM TEMP (°F) 73
 CORR BAR. PRES. (IN. HG) 29.84
 TEST RIG NRC 98

REF. SPEC. PARA. 4.3.2.1

EXTERNAL LEAKAGE (Continued)

TABLE 2

Complete the following table:

PARAMETER	MINIMUM ALLOWABLE	ACTUAL	MAXIMUM ALLOWABLE
Standard Leakage Rate	300	6.2×10^{-4}	310
Scale Reading of Standard Leakage Rate	300	6.2×10^{-5}	310
Scale Reading of Background	300	LESS THAN 2×10^{-7}	310
Inlet Pressure	300 psia	300.	310 psia
Item Helium Rate (Initial)	300	LESS THAN 2×10^{-7}	1×10^{-4} scc/sec
Item Helium Rate (Final)	300	6.5×10^{-6}	1×10^{-4} scc/sec
Test Duration	15 minutes	15	15.25 minutes
REA Valve Actuation Voltage	27.7 vdc	28.0	28.3 vdc
REA Valve Running Voltage	19.7 vdc	20.0	20.3 vdc
REA Valve Cycles	3	3	3

OPERATOR E. CASSELLA
 INSPECTOR (RH) A. GIEC 7/17/73

AT - NRL-0.2	
REF. SPEC. PARA.	ROOM TEMP (°F)
4.3.2.2	73
	CORR BAR. PRES. (IN. HG)
	29.89
	TEST RIG
	NRC 90
Hamilton Standard U A	
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	
SER. NO.	TEST DATE
00003	7-17-73
49 CF 54	

LEAKAGE (Continued)

4.4 Internal Leakage

1. Set up and calibrate a helium mass spectrometer using a maximum helium calibrated leak rate standard of 10^{-4} scc/sec. If direct reading (NRC) mass spectrometer is used, adjust gain control to make meter read value of calibrated leak and record. If indirect reading (Veeco) mass spectrometer is used record scale reading.

2. Install REA in a test setup as shown in Figure 3. REA valve is to be closed for this test.

3. Evacuate the mass spectrometer to its operating pressure.

4. Close helium supply shutoff (S01) valve, open the vacuum pump shutoff (S02) and evacuate the pressurization line to less than 0.5 psia. Record background reading.

5. Close vacuum pump shutoff (S02), open helium supply shutoff valve (S01) and pressurize the REA inlet to 100 psia by applying GHe pressure to the inlet (pressurization rate 100 psi/minute maximum).

6. Record the helium leakage rate at the start and end of a 15 minute minimum period. If direct reading (NRC) mass spectrometer is used, read and record leakage rate. If indirect reading (Veeco) mass spectrometer is used, record scale deflection of meter. If an indirect reading (Veeco) mass

(A)

OPERATOR	R. PATRICK
INSPECTOR	(RH) A. GIBEL 7-17-73
(38)	

REF. SPEC. PARA. 4.3.2.2	ROOM TEMP (°F) 73	Harrison Standard	SER. NO. 00007	AT - NHL-0.2
	CORR BAR. PRES. (IN. HG) 29.89	U	TEST DATE 7-17-73	
	TEST RIG NRC 98	A ₀		
		SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET		
			50 CF 54	

LEAKAGE (Continued)

4.4 Continued

7. spectrometer is used compute leakage rate from meter deflection as follows:


$$\text{Leak Rate scc/sec} = \frac{\text{Standard Leak Rate (scc/sec)} \times \text{Scale Deflection X due to Unknown Leak - due to Background}}{\text{Scale Deflection due to Standard Leak}}$$

8. Back off regulator to depressurize REA.

OPERATOR <i>K. Forick</i>
INSPECTOR (EM) <i>A GIEL 7-17 73</i>

REF. SPEC. PARA.	ROOM TEMP (°F)	73	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO.	00003
	CORR BAR. PRES. (IN. HG)	29.89		TEST DATE	7-17-73
4.3.2.2	TEST RIG	NAC 98			51 OF 54

AT - NHL-0-2



OPERATOR	P. PATRICK
INSPECTOR	(IN) A. GREE 7-17-73

FIGURE 3 - INTERNAL LEAKAGE

AT - NRL-0.2

SER. NO. 01003
TEST DATE 7-17-73

Hamilton 43 Standard
SI 3 ACCEPTANCE TEST OPERATIONS/LOG SHEET

ROOM TEMP (°F) 73
CORR BAR. PRES. (IN.HG) 29.89
TEST RIS NCC 98

520F54

INTERNAL LEAKAGE (Continued)

TABLE 3

4.4 (Continued)

PARAMETER	MINIMUM ALLOWABLE	ACTUAL	MAXIMUM ALLOWABLE
Standard Leakage Rate	100 psia	.62 x 10 ⁻⁷	105 psia
Scale Reading of Standard Leakage Rate	100 psia	.62 x 10 ⁻⁷	105 psia
Scale Reading of Background	100 psia	0	105 psia
Inlet Pressure	100 psia	100.	105 psia
Item Helium Leakage Rate (Initial)	1 x 10⁻⁶ scc/sec	655 THAN .2 x 10 ⁻⁷	1 x 10⁻⁶ scc/sec
Item Helium Leakage Rate (Final)	1 x 10⁻⁶ scc/sec	655 THAN .2 x 10 ⁻⁷	1 x 10⁻⁶ scc/sec
Duration	15 minutes	15	15.25 minutes

OPERATED BY F. LAZZERINI
INSPECTOR A. CARL 7-17-73

AT - NRL-0.2

SER. NO. 00003
 TEST DATE 7-10-73
 53 JF 54

Hamilton Standard **U**
A.
 SLS ACCEPTANCE TEST
 OPERATIONS/LOG SHEET

ROOM TEMP (°F) ~
 CORR BAR. PRES. (IN. HG) ~
 TEST RIS BENCH

- # 4.7 Post Test Inspection
 4.7.1 Visually examine the unit for defects.
 4.7.2 Damage or discoloration as a result of firing is not permitted with the following exceptions:
 A. Nozzle and chamber discoloration as a result of firing is permissible provided it is scale free.
 B. Superficial marking of areas immediately around bolt holes is permissible.
 C. Wrench marking at the Pc tap is permissible.

- 4.7.3 Post Test Inspection
 List observations and comments below.
 LESS NAMEPLATE FOR Unit History # 2.

OPERATOR

INSPECTOR

28

AT - NRL-0.2

SER. NO.
TEST DATE

Hamilton Standard
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET

ROOM TEMP (°F)
CORR BAR. PRES. (IN.HG)
TEST RIG

REF. SPEC. PARA.
N/A

54 OF 54

TABLE 9 VALVE CYCLE SUMMARY

Valve S/N _____

TEST PARA. NO.	VALVE CYCLES	REA STARTS (FIRING)	REA VALVE ON TIME (SEC)
4.2 (Proof)	2	—	120
4.3 (Leakage)*			
4.6 (Performance)	128.1	168.	157.
4.5 (Flush)			
TOTALS:			

7-9-73

* Total of all valve cycles listed in each external leakage test.

OPERATOR
INSPECTOR

58

**Hamilton
Standard**

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A.

SVHSER 6305

APPENDIX B

QUALIFICATION TEST PROCEDURES

QT6017

APPENDIX A

OVERSTRESS TEST PROGRAM

0.2 lb_f RMA

APPROVED BY:

A.P. [Signature]
Engineering

6/18/73
Date

APPROVED BY:

A.B. [Signature]
Quality Assurance

6/6/73
Date

Applicable Spec

SVHS6017 Revision A Amendment #
SV755437 Revision 1/C

Reproduced from
best available copy.

Hamilton Standard

WINDSOR LOCKS CONNECTICUT • U.S.A.

QUALIFICATION TEST PROCEDURE
OVERSTRESS TEST PROGRAM
NRL/MSD 0.2 lb_f RMA

PREP BY	QUALITY	SIZE	CODE IDENT NO.	QT - 6017 Appendix A
		A	70000	
GR.				SHEET X-1-a

A1.0 SCOPE

This test procedure defines the requirements for overstress tests, supplementing the Qualification Program defined in the basic procedure.

A2.0 GENERAL NOTES

A2.1 Handling

The handling of the REA shall be in such a manner to prevent damage to external surfaces. The REA shall only be handled by personnel wearing white, lint free, dacron, rayon, or cotton gloves.

A2.2 Cleanliness

1. An 18 micron or less absolute filter is installed directly upstream of the REA valve inlet as part of final assembly. This filter shall remain installed for all testing described herein. Removal of the filter shall be accomplished only in a Class 10,000 clean work station.
2. In addition to the filter, the REA shall be protected at all times when out of the test rig by taping clean nylon film securely in place over all openings and double-bagging the unit.
3. Rig cleanliness shall satisfy the requirements of SVP 114, 129, 130, and 133. Inspection shall verify the current status of rig cleanliness prior to performance tests.

A2.3 Retests

In the event of a failure, malfunction or out of tolerance condition during or after a test, the test sequence shall be discontinued and the deficiency shall be documented on a unit history form. The deficiency shall be corrected and the REA shall be retested with the approval of Engineering and Quality Assurance.

A2.4 Installation Check

Prior to firing tests the following checks must be performed:

1. Valve Voltage and Current - Install a 210 ohm (approximate) resistor in the test cell at the REA valve driver output. Actuate the valve driver in pulse mode and verify that valve voltage and current traces are obtained on the visicorder. Measure the voltage supplied to the valve via a voltage divider using a differential voltmeter, while the valve driver is actuated in steady state mode. Set valve supply voltage to $20 \pm .25$ vdc. Record power supply voltage using Fluke Voltmeter and Valve Supply Voltage on Log Sheet.

NOTE: USE UD2 RIG DRIVER.

A2.4 continued

2. BEA Chamber Pressure - With the test cell at altitude conditions (5.12 mmHg vacuum pressure) verify that the reading for chamber pressure is 0 ± 5 psia. Use a differential voltmeter to measure the transducer output.
3. Inlet Pressure - Prior to each steady state run record inlet pressure transducer output on digital data log. Use a differential voltmeter to measure the transducer output (must be ± 3 psi from gage reading).
4. Tank Pressure - Prior to each pulsing run record tank pressure transducer output on digital data log. Use a differential voltmeter to measure the transducer output (must be ± 3 psi from gage reading).
5. Excitation Voltage - Measure excitation supply voltage for cell where data is being acquired from the record on digital data log once per cell setup.
6. Fuel Inlet Temperature - Read fuel temperature using differential voltmeter and record on digital data log for each run.
7. Chamber Temperature - Read chamber temperature on differential voltmeter. Verify reading is acceptable prior to each run.

A3.0 QUALIFICATION TEST

A3.1 Program Description

Testing shall be conducted on two engines; the Qualification engine and the Reliability engine. The program described below is shown in data sheet Figure DS1. Enter the part number and serial number of the engine at the top of the appropriate sequence. Inspector shall verify that prerequisite testing is complete.

A3.2 Qualification Engine Sequence

The engine previously having completed the basic Qualification Program shall be subjected to these further overstress tests in the sequence indicated.

<u>Test</u>	<u>Reference Para.</u>
Thrust Calibration	A4.2.1
Critical Soakback	A4.2.2

NOTE: Before soakback but after thrust, the engine shall be gold plated per separate instructions.

A3.3 Reliability Engine Sequence

The reliability engine shall have successfully completed Acceptance Tests per SVHS 6001. The engine shall then be subjected to the following overstress tests in the sequence indicated.

Hamilton Standard

SIZE
A

CONSISTENT I.S.
7000

QT-6017
Appendix A

NET 8-3

A3.3 continued

<u>Test</u>	<u>Reference Para.</u>
Qual Vibration	A4.2.3
Performance Map	A4.2.4
Baseline	4.2.4
Combined Life	A4.2.5

A3.4 Inspection

1. For each test listed above, record number of valve cycles in table at end of this procedure.
2. Points at which acceptance by Inspection is required are indicated on the log sheets by an asterisk (*) at the detailed step and in the "inspection" block at the lower right hand corner. Other portions of the test are subject to surveillance by Inspection on a non-mandatory basis.

Reproduced from
best available copy.

REF. SPEC. PANA. SVHS 6017 4.2.4	ROOM TEMP (°F) 75 CORR BAR. PRES. (IN. HG) 29.85 TEST RIG 91	Hamilton Standard SER. NO. 0003 TEST DATE 7/19/73 A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	QC 17 Appendix A
--	--	---	---------------------

VIBRATION

A4.2.3

A. General

- *1. The REA shall be prepared for vibration in a clean work station (Class 10,000).
- *2. The pc tap and nozzle shall be taped closed using polyethylene. The inlet tube (SV 755437-CT-001) must shall be securely taped to the tube and the tube end taped closed with polyethylene.
- *3. Move the REA into the Vibration Lab and install the REA on the test fixture (SVSK 77886) as shown in Figure 3.2.1.
- *4. Install accelerometers per Figure 3.2.1.
REA axis orientation is per Figure 3.2.1.
- 5. A triaxial accelerometer shall be used as the control accelerometer for both sinusoidal and random vibration testing. The control accelerometer shall be located to provide the following input:
 - (1) The control input shall maintain levels at the test frequency within ± 3 db of the requirements.
 - (2) The minimum level at other input locations is within ± 4 db of the requirements at the test frequency.
 - (3) For random inputs the GRMS shall be within $\pm 10\%$ of the nominal specification level. For sinusoidal inputs the peak G shall be within $\pm 10\%$ and the frequencies shall be within $\pm 2\%$.


 INSPECTOR

4-5

REF. SPEC. PARA. SVHS 6017 4.2.4	ROOM TEMP (°F) 75°	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 0003	QT-6017 Appendix A
	CON. BAR. PRES. (IN. HG) 29.85		TEST DATE 7/19/73	
	TEST NO. 91			

A4.2.1(Continued)

VIBRATION (Continued)

A. 6. Instrumentation

Indigenous instrumentation of the vibration facility necessary for vibration monitoring.

7. Special Test Equipment

<u>SITE</u>	<u>Identification</u>
Vibration Fixture Vibration Rig	SVSK 66611/SVSK 77886 MB4 or Ling

8. Data Required

- a. Response of all accelerometers shall be recorded. The control accelerometer shall be filtered and recorded during all tests, with the initial portions of the run concurrently monitored on a plot of g or g^2/cps , as applicable, vs. frequency. The ambient temperature shall be recorded at the start and end of the test.
- b. Response accelerometer reduction shall only be done at Engineering request.
- c. Test Set-Up Sketch - In the space provided in HS Form 175.7, a sketch of the test item and fixture shall be made including the definition of the three orthogonal axes. The sketch shall also include location of both control and response accelerometers. Format for the sketch shall be in accordance with Form HSP-175.7.

Witnessed
 Inspector: *[Signature]* 7-20-77
 Date: 7-20-77

REF. SPEC. PARA. SVHS 6017 4.2.4	ROOM TEMP. (°F) 75°	Hamilton Standard U A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	QT-6017 Appendix A
CONN BAR. PRES. (IN. HG) 27.85	SER. NO. 0003		
TEST RIG 9185	TEST DATE 7/19/73		

A4.2.3(Continued)

VIBRATION (Continued)

- d. Log Sheet - An operator's log sheet, form HSF-175.1A, shall be provided for each run. The log sheet shall contain run number, starting time of run, axis, mode (sinusoidal or random), scan rate, 'g's peak and paragraph number of the test specification which delineates the vibration level requirements.
- e. Photographs - Photographs shall be taken which clearly illustrate the test item and setup for each orthogonal axis. Polaroids are acceptable.
- 9. General REA Mounting Requirements - The REA shall be hard mounted on a vibration fixture with control accelerometers located in each of the orthogonal axes near the fixture/engine interface. The following torque table will be used as a guide when installing an engine on its vibration fixture and when installing the fixture to the exciter.

<u>Bolt Size</u>	<u>Torque, in-lb</u>
#6	15
#8	28
#10	40
1/4	100
5/16	350
3/8	350
1/2	850
3/4	2100

B. Fixture Evaluation and Resonance Search - The location of the control accelerometer shall be determined from a fixture evaluation and resonance search as required by the Initial Acceptance Test of these units. No further test effort shall be required.

OPERATOR
[Signature]
INSPECTOR
[Signature]
7-20-73

Witnessed

REF. SPEC. PARA. SVHS 6017 4.2.4	ROOM TEMP (°F) 75	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00003
CORR BAR. RES. (IN. WOL) 29.85	TEST DATE 7/19/73		
TEST RID 91			

QT-6017
Appendix A

A4.2.3

C. Vibration Levels

Vibrate the REA, each axis, per the schedule below. The sequence of runs shall be dictated by maximum testing efficiency. All testing shall be conducted at ambient temperature and pressure.

	Frequency - Hz	Level	Rate or Time
Sinusoidal	25 - 2000	11 g	1 oct/min (up only)
Random	20 - 200	0.1 g ² /Hz	2 mins. minimum per axis
	200 - 2000	-6.0 db/oct	roll off

D. Acceptance Criteria

- a. The item shall pass a subsequent performance test.
- * b. There shall be no damage or permanent deformation.
- c. There shall be evidence of catalyst within the valve/thrust chamber interface.

INSPECTOR
*G. J. 17-R-73

Witnessed

REF. SPEC. PARA. SVIS 6.17 4.2.4	ROOM TEMP (°F) 75	SER. NO. 20013	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET
CORR BAR. PRES. (IN. H ₂ O) 29.85	TEST RIG 91	TEST DATE 7/19/73	

6-0017
Appendix A

REF: - BENDIX JTH-8-3P(101)




Figure 3.2.1

Operator
Inspector
Date: 7-20-73

W. J. ...

REF. SPEC. PARA. SVHS 6017 Appendix A A4.2.4		ROOM TEMP (°F) 73	Hamilton Standard U A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. C2203	QT-6017 Appendix A
CORR BAR. PRES. (IN. H ₂ O) 30		TEST DATE 7-23-23			
TEST RIG H. 2					

Performance Map

A4.4

I. Performance Map (H2)

1. Install the REA in firing fixture P/N SVSK 776571-001 with nozzle plug installed in REA nozzle. Verify that a 10 micron absolute filter has been installed at the REA inlet. Cap the Pc tap.
2. Actuate the REA valve by applying 28 ± 2 vdc to the valve power connector. Pin A+, Pin B-.
3. Pressurize the REA to 50 ± 5 psia and check for external leakage using a leak detecting fluid. If none, write "None".
4. Deactuate the REA valve, bleed pressure through the Pc tap by slowly removing the Pc tap cap. Remove nozzle plug.
5. Install a chamber temperature thermocouple on the REA as shown in Figure A4.3-1. Install valve temperature thermocouple as shown.
- * 6. Verify rig cleanliness satisfied HS 3150 CE-5 (no metallic particles over 50 microns) and note this on log sheet.
7. Record throat diameter on the data sheet.
8. Install the REA in a simulated altitude test facility (Cell H3) and instrument per Table A4.3-2 and Figures A4.3-1 and A4.3-4.
9. Set up visicorder per Table A4.3-5.
10. Take a photograph of the unit set up in the test cell.
11. Set rig relief valve to 450 psia maximum.

WITNESSED
 J. H. ...
 ...

OPERATOR J. H. ...
INSPECTOR ...

WITNESSED

010

REF. SPEC. PARA. SVHS 6017 Appendix A A4.2.4		ROOM TEMP (°F) 73	Hamilton Standard SERVOVALVE COMPANY		QT-6017 Appendix A
CORR BAR. PRES. (IN. HG) 30		TEST RIG H-2	SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET		SER. NO. 20003
					TEST DATE 7-23-73

A4.4 I. continued

12. Evacuate and backfill the propellant system as follows: (See Figure A4.3-6).

- a. To purge fuel from the servomanometer, open the fuel bleed, vacuum shutoff, manual bleed, arming, bypass, both flowmeter shutoffs servomanometer supply, servomanometer manual shutoffs, sightglass shutoff, servomanometer pressure and tank pressure valves. All other valves shall be closed. Slowly pressurize the servomanometer until fuel has been removed. Close tank and servomanometer pressure valves, small servo and sight glass manual valves, small servo supply valves.
- b. To evacuate the system, open the vacuum shutoff and turn on the vacuum source. Evacuate to a pressure of 1 psia or less for 30 minutes minimum.
- c. To back fill the system, close the vacuum and manual bleed shutoff valves. Open the tank pressurization valve and slowly pressurize the tank to 20-25 psia. Open the tank (solenoid) shutoff valve. Close the flowmeter shutoff valves as soon as the lines are filled. Open the servomanometer shutoff valve until the servo is filled; then close the supply valve. Close the tank (solenoid) shutoff.
- d. To check for system hardness, open the servo. Pressurization valve and then the servo supply valve. Read and record the servomanometer voltage. Pressurize the system to 270 ± 10 psia at a rate of approx. 100 psi/minute. Read and record the servo voltage. The allowable servo deflection for the propellant system shall not exceed .08 volts. Record on the data sheet.

13. Set the following initial conditions:

Valve voltage - 28 ± 2 vdc
 Vacuum pressure = 8.12 mmHg maximum
 Fuel temperature = 70 ± 15°F

B-11

OPERATOR J. H. ...
INSPECTOR ...

7-24-73
 WITNESSED

QT-6017
Appendix A

REF. SPEC. PARA. SVHS 6017 Appendix A A4.2.4	ROOM TEMP (°F) <u>73</u>	Hamilton Standard U A SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. <u>02003</u>
	CORR SAN. PRES. (IN. HG) <u>30</u>		TEST DATE <u>7-23-73</u>
	TEST RIG <u>H-2</u>		

A4.4 I. Continued

14. Acquire all data on digital tape as follows:

Steady state runs: Acquire 3 second lead-in, plus entire run, plus 11 second trailer.

Pulse runs: Acquire 3 second lead-in, all pulses and 11 second trailer.

15. Acquire visicorder data as follows:

Steady state runs: Acquire 0-2, 18-20, 28-30, 38-40, 48-50, 58-60 seconds at 20 ips. Remainder at 2 ips.

Pulse runs: Acquire pulses 1-10, 45-55, 90-100 at 20 ips. Remainder at 2 ips.

16. Fire the REA to the duty cycles specified in Table A-4.3-7 with the following stipulations:

- a. The nozzle diameter shall be transcribed on the data log sheet from the Acceptance Test Data.
 - b. The fuel inlet pressure shall be within 3 psi of the tank pressure, prior to running.
 - c. The test sequence for the performance map test is defined in Table A4.3-7.
 - d. The analog data shall be reviewed after each firing for potential problems in instrumentation or engine performance.
 - e. The map test shall be immediately followed by a baseline test per para. A4.2.4
- Record data on log sheet provided. Record initial pressure and chamber temperature prior to each part run.

17. After completion of the firing test, close the arming valve, apply 10-15 psig GN_2 , purge pressure. With REA valve shut drain fuel from rig. Close drain valve and actuate REA valve for 120 seconds followed by 25 pulses - 1 second on, 1 second off. (Reference Figure A4.3-6).


N/A
7-24-73

B-12

OPERATOR
J. H. HICKMAN
INSPECTOR
J. P. MILLER
7-24-73

QT-6017
Appendix A

REF. SPEC. PARA. SVHS 6017 Appendix A A4.2.4	ROOM TEMP (°F)	73
	CORR BAR. PRES. (IN. HG)	30.
TEST RIG		H 2

Hamilton Standard

SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET

SER. NO.	00003
TEST DATE	7.23.73

A4.4 continued

II. Flush

1. Install the REA in a flush rig as shown in Figure A4.3-8.
2. Open the H₂O supply valve, pressurize H₂O to 10-15 psig, and actuate the REA valve at an approximate duty cycle of 50 seconds on, 10 seconds off, for 15 pulses. Apply 28 ± 2 vdc to actuate the valve, Pin A+, Pin B- for Steps 2, 3 and 4.
3. Close H₂O supply valve, open isopropyl alcohol supply valve. Pressurize IPA to 10-15 psig and actuate the REA valve at an approximate duty cycle of 50 seconds on, 10 seconds off for 5 pulses.
4. Purge REA with GN₂ (REA valve held open with 20 ± 2 vdc after opening) at 10-15 psig until IPA ceases flowing from REA. Close REA valve.
5. Install the REA in a vacuum dessicator and vacuum dry the REA at 1500 microns Hg or less for one hour minimum. Record data in the data table.

MA
7.24.73

III. Complete valve cycle record for Performance Map test.

OPERATOR	
INSPECTOR	

QT-6017
Appendix A

SER. NO. 00063
TEST DATE 7.23.73

Hamilton Standard
U A.
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

ROOM TEMP (°F) 73
CORE BAR. INCH. (IN. IN) 30
TEST RIS H. 2

REF. SPEC. PARA.
SVHS 6017
Appendix A
A4.2.4

OPERATOR L. H. HARRIS
INSPECTOR W. P. JONES
7-24-73

- T_C = Chamber Temp.
- T_V = Valve Temp.
- T_P = Propellant Temp.
- P_C = Chamber Press.
- P_I = Inlet Press.
- P_T = Tank Press.
- V_V = Valve Voltage
- A = Valve Current

MS33584 1/4 in.
Tube Flare Joint

Connector
Bendix JTIH-8-3P (101)
Pin A+
Pin B-
Pin C Case Ground




FIGURE A4.3-1

PERFORMANCE MAP TEST SETUP AND INSTRUMENTATION

B14

QT-6017
Appendix A

REF. SPEC. PARA. SVS 6017 Appendix A A4.2.4

ROOM TEMP. (°F) 73

CORR BAR. PRES. (IN. HG) 30

TEST RIG HZ

Manufacturer Standard **U**

SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET

SER. NO. 22003

TEST DATE 7.23.73

PERFORMANCE MAP
INSTRUMENTATION TABLE A4.3-2

PARAMETER	MEASUREMENT DEVICE	MANUFACTURER	MODEL NO.	CAL. RANGE	ACCURACY	CHANNEL
						1-20 20-40
Valve Voltage Divider	HSD		SVSK79575	0-30 vdc	-	1 21 5
Inlet Pressure	Servomanometer	Exactel	T5 40 1/2 .312" bore	0-.1 lmb	± 1% R	2 22 1
Chamber Press. Transducer	Transducer	Statham	PA822	0-300 psia	± 1% FS	3 23 200
Valve Current	Divider	HSD	SVSK79575	0-1 amp	-	4 24 200
Tank Pressure	Transducer	Statham	PA822	0-300 psia	± 1% FS	5 25 50
Inlet Prop. Temp.	Thermocouple		Type T	0-200°F	± 5°F	7 27 1000
Excitation Vcvt.				10 vdc nom.	-	11 31 .5
Fuel Temp. (Tank)	Thermocouple		Type T	0-200°F	± 5°F	8 28 1000
Chamber Temperature	Thermocouple		Type K .020"	0-1500°F	± 10°F	14 34 200

OPERATOR L. ADAMS 73

INSPECTOR F. Fuchs

7-14-73

REF. SPEC. PARA.	ROOM TEMP (°F)	73	QT-6017 Appendix A
SWS 6017 Appendix A A4.2.4	COAR. GAR. PRS. (IN. HG)	30	SER. NO. 0000
	TEST RIG	A 2-	TEST DATE 7-23-73

Hammer: Standard
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

PERFORMANCE MAP
INSTRUMENTATION TABLE A4.3-2 (Concluded)

PARAMETER	MEASUREMENT DEVICE	MANUFACTURER	MODEL NO.	CAL. RANGE	ACCURACY	CHANNEL	GAIN
Vacuum Pressure	Gage	Hastings	VT-4	0-20 mmHg	± 2% Ang Def.	19	39
Tank Pressure	Gage	Heise	C	0-300 psia	± 5% FS	--	--
Valve Temp.	Thermocouple	--	Type T	0-500°F	± 5°F	16	36
						1-20	20-40
							1000

Do not install a throat temperature thermocouple on the REA.


OPERATOR - H. H. H.
INSPECTOR K. P. K.

7-24-73


REF. SPEC. PARA. SVHS 6017 Appendix A A4.2.4	ROOM TEMP (°F) 73	SCR. NO. 60003
CORR BAR. PRES. (IN. HG) 30	TEST DATE 7-23-73	14 of 50
TEST RIG H 2-	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	

PERFORMANCE MAP

VACUUM CHAMBER



DATA ACQUISITION SYSTEM



INSTRUMENTATION SIGNAL ROUTING - FIGURE A4.3-4

OPERATOR
A. H. H. S.
INSTRUMENTOR
R. P. H. S.

7-24-73

B-17

REF. SPEC. PARA. SVHS 6017 Appendix A A4.2.4	ROOM TEMP (°F)	73.
	CORN BAR. PRES. (IN. HG)	70.
	TEST RIG	1.2

QT-6017 Appendix A
SER. NO. 00003
TEST DATE 7-23-73

Hamilton Standard
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

PERFORMANCE MAP
VISICORDER SET-UP


<u>Parameter</u>	<u>Cal. Range</u>	<u>Approx. Scale Factor</u>
Valve Voltage	0 - 30 V _{AC}	3" span
Valve Current	0 - 0.5 amp	2" span
Inlet Pressure	0 - 300 psia	60 psi/in.
Chamber Pressure	0 - 250 psia	50 psi/in.
Chamber Temperature	0 - 1500°F	3000°F/in.
Valve Temperature	0 - 500°F	1000°F/in.

TABLE A4.3-5

OPERATOR L. Adams
INSPECTOR J. Miller

7-24-73

REF. SPEC. PARA.	ROOM TEMP (°F)	Hamilton Standard	
SVIS 6017	73	SLS ACCEPTANCE TEST	
Appendix A	CORR BAR. PRES. (IN. HG)	OPERATIONS/LOG SHEET	
A4.2.4	TEST RIG	SER. NO. 10000	
	H. S.	TEST DATE 7-23-73	
		2T-6017	
		APPX. A	



OPERATOR	INSPECTION
<i>[Signature]</i>	<i>[Signature]</i>
7-7-73	

Figure A4.3-6

Rig 112 Propellant Flow Diagram

QT-6017
Appendix A

SER. NO.

TEST DATE

Hamilton Star/lard
MEMBER OF UNITED STATES STEEL CORPORATION

**SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET**


ROOM TEMP (°F)

CORR BAR. PRES. (100 PSI)

TEST RIG

REF. SPEC. PARA.

SVHS 6017
Appendix A
A4.2.4



NA DB 7-24-73

OPERATOR

INSPECTOR

FIGURE A4.3-8 ~ REA FLUSH

REF. SPEC. PARA. SVHS 6017 4.2.4	ROOM TEMP. (°F) 73 CORR BAR. PRES. (IN. HG) 30 TEST RIG A2	Hamilton Standard U.S. AIR FORCE A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	S.L.R. NO. 0000 TEST DATE 7-24-73	QT-6017 Appendix A
<p><u>BASELINE PERFORMANCE</u></p>				
<p>A. Performance Test (H2)</p> <ul style="list-style-type: none"> * 1. Install the REA in firing fixture P/N SVSK 77657-T-001 with nozzle plug installed in REA nozzle. Cap the Pc tap. * 2. Actuate the REA valve by applying 20 ± 2 psi to the valve power connector. Pin A+, Pin B-. * 3. Pressurize the REA to 50 ± 5 psia and check for external leakage using a leak detecting fluid. If none, write "None". * 4. Deactuate the REA valve, bleed pressure through the Pc tap by slowly removing the Pc tap cap. Remove nozzle plug. * 5. Install a chamber temperature thermocouple on the REA as shown in Figure 3.3.2. Install valve temperature thermocouple as shown. * 6. Verify rig cleanliness satisfied HS 3150 CE-5 (no metallic particles over 50 microns) and note this on log sheet. * 7. Record throat diameter on the data sheet. * 8. Install the REA in a simulated altitude test facility (Cell H-3) and instrument per Table 4.4.1 and Figures 4.4.2 and 4.4.3. * 9. Set up visicorder per Table 4.4.4. * 10. Take a photograph of the unit set up in the test cell. <p>NOTE: Bed may be indirectly cooled with GN₂ between runs after temperature has decreased to 600°F.</p>				
				OPERATOR [Signature] INSPECTOR [Signature]

B-21

REF. SPEC. PARA. SVHS 6017 41: 11	NO. 1 TEMP (°F): 73	Hamilton Standard F10 SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00002	QT-6017 Appendix A
	CORR. BAR. PRES. (IN. HG) 30		TEST DATE 12473	
TEST N.O. H 2				

A4.2.4 (Continued)

BASELINE PERFORMANCE (Continued)

- A. 13. Rig evacuation alternate method:
- This step is to be used only if REA installation takes place within 8 hours of removal of previous REA and test rig valve positions are the same and test rig fuel system has not been broken into.
 - Connect Valves 11 and 13 to a vacuum source. All other valves are closed. Open Valves 11 and 13 and evacuate at 15 in. Hg or less for 30 minutes maximum.
 - Close Valves 11 and 13, open Valves 1, 2, 4 and 6 with N₂H₄ supply tank pressurized to approximately 10 psig. Perform system check per Step 12g. If this step (16) is not performed, cross out this step and write "N/A."
14. Set the following initial conditions:
- Valve Voltage = 28 ± 2 vdc
 - Vacuum Pressure = 8.35 mm Hg maximum
 - Fuel Temperature = 70 ± 15°F
15. Fire the REA to the duty cycles specified below with the following stipulations:
- Use UD2 rig driver circuit to fire the REA. Record driver identification on Log Sheet.
 - Runs are to be made using the servomanometer (flowmeter not required - valve 7 deactivated). Verify that the tank pressure gage and inlet pressure transducer agree within ± 3 psi prior to running.
 - To pressurize the system for a run, open valves 14 and 6 and slowly increase the regulated GN2 supply to the servomanometer, as indicated by the inlet pressure transducer.
 - Use the firing sequence tape designated for each run.

OPERATOR Bill [unclear]
INSPECTOR [unclear]

WITNESSED

7-24-77

REF. SPEC. PARA. SVHS 6017 4 2 4	NO. TEMP (°F)	73	Hamilton Standard U A SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00003	TEST DATE 1-24-73
	CORR. AR. PRES. (IN. HG)	30			
	TEST R.	H2			

QT-6017
Appendix A

A4.2.4 (Continued)

BASELINE PERFORMANCE (Continued)

- e. Acquire all data on digital tape as follows:
 - Steady state runs: Acquire 3 second lead-in, plus entire run, plus 11 second trailer.
 - Pulse runs: Acquire 3 second lead-in, all pulses and 11 second trailer.
- f. Acquire visicorder data as follows:
 - Steady state runs: Acquire 0-2, 10-20, 26-30, 38-40, 48-50, 58-60 seconds at 20 ips. Remainder at 2 ips.
 - Pulse runs: Acquire pulses 10-10, 45-55, and 90-100 at 20 ips. Remainder at 2 ips.
- g. Pulse and steady state firings at the same inlet pressure will be fired as a continuous run. Combine the two sequences with a five minute delay between sequences to adjust pressure and switch from tank to servo as follows:
 - NRL-IT-2 100 pulses
 - NRL-IT-3 60 second steady state
- h. Firing Sequence - Fire runs per Table 4.4.6.
 - Record data in Log sheet provided. Record initial pressure and chamber temperature prior to each part run.

OPERATOR
D. L. London
INSPECTOR
J. F. Fisher

1-24-73

REF. SPEC. PARA. SVHS 6017 4.2.4	ROOM TEMP (°F) 73	SER. NO. 60003	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	QT-6017 Appendix A
CORR. PAR. PRES. (IN. HG) 30	TEST DATE 7-24-73			
TEST RI. H2				

A4.2.4 Continued)

BASELINE PERFORMANCE (Continued)

16. After completion of the firing test, close Valve 6, apply 10-15 psig GN2 through Valves 8 and 9, open Valves 12 and 13 to drain fuel from rig. Close Valves 12 and 13, and actuate REA valve for 120 seconds followed by 25 pulses - 1 second on, 1 second off. (Reference Figure 4.4.5).

B. Flush

1. Install the REA in the flush rig as shown in Figure 4.4.7.
2. Open the H2O supply valve, pressurize H2O to 10-15 psig, and actuate the REA valve at an approximate duty cycle of 50 seconds on, 10 seconds off, for 15 pulses. Apply 28 ± 2 vdc to actuate the valve, Pin A+, Pin B- for Steps 2, 3 and 4.
3. Close H2O supply valve, open isopropyl alcohol supply valve. Pressurize IPA to 10-15 psig and actuate the REA valve at an approximate duty cycle of 50 seconds on, 10 seconds off for 5 pulses.
4. Purge REA with GN2 (REA valve held open with 20 ± 2 vdc after opening) at 10-15 psig until IPA ceases flowing from REA. Close REA valve.
5. Install the REA in a vacuum desiccator and vacuum dry the REA at 1760 microns Hg or less for one hour minimum. Record data in the data table.

C. Complete valve cycle record for baseline performance test.

Handwritten signature and date: N/A 7-24-73

OPERATOR FOR PULLMAN
INSPECTOR K. H. BACH

6677-555E

7-24-73

OT-6017
Appendix A

SER. NO. 00005
TEST DATE 7-24-73

Hamilton Standard
SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET

ROOM TEMP (°F) 73
CORR. FAN. PRES. (IN. HG) #2 30
TEST RIG H2

REF. SPEC. PARA. SVIS 6017 4.2.4

BASELINE PERFORMANCE INSTRUMENTATION TABLE 4.4.1

PARAMETER	MEASUREMENT DEVICE	MANUFACTURER	MODEL NO.	CAL. RANGE	ACCURACY	CHANNEL	GAIN
						1-20	20-40
Valve Voltage	Divider	HSD	SVSK79575	0-30 vdc	-	1	21 5
Fuel Flow	Servomanometer	Exactel	T5 40 In .312" Bore	0-.1 lmb	± 1% R	2	22 1
Inlet Pressure	Transducer	Statham	PA822	0-300 psia	± 1% FS	3	23 200
Chamber Press.	Transducer	Statham	PA822	0-500 psia	± 0.3%	4	24 200
Valve Current	Divider	HSD	SVSK79575	0-1 amp	-	5	25 50
Tank Pressure	Transducer	Statham	PA822	0-300 psia	± 1% FS	6	26 200
Inlet Prop. Temp.	Thermocouple	-	Type T	0-1000°F	± 5°F	7	27 1000
Excitation Volt.	-	-	-	10 vdc nom.	-	11	31 .5
Fuel Temp. (Tank)	Thermocouple	-	Type T	0-200°F	± 5°F	12	32 1000
Chamber Temperature	Thermocouple	-	Type K .020"	0-1500°F	± 10°F	14	34 200

OPERATOR E. ALBERT
INSPECTOR R. TA...

7-24-73

5145

REF. SPEC. PARA. SWIS 6017 4.2.4	ROOM TEMP (°F) 73	Hamilton Standard U A SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00003
	CORR BAR. PRES. (IN. HG) 30		TEST DATE 7-24-73
	TEST RIG H.L.		

BASELINE PERFORMANCE
INSTRUMENTATION TABLE 4.4.1 (Concluded)

PARAMETER	MEASUREMENT DEVICE	MANUFACTURER	MODEL NO.	CAL. RANGE	ACCURACY	CHANNEL	GAIN
Vacuum Pressure	Cage	Hastings	VT-4	0-20 mmHg	± 2% Ang Def.	8	28 1000
Tank Pressure	Cage	Heise	C	0-300 psia	± 5% FS	--	--
Valve Temp.	Thermocouple	--	Type T	0-500°F	± 5°F	i6	36 1000

OPERATOR
E. Carrol
INSPECTOR
R. Tallin

7-24-73

QT6017
Appendix A

SER. NO.
P0003

TEST DATE
7-24-73

Hamilton Standard
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

ROOM TEMP (°F) 73

CORR. AIR PRES. (IN. HG) 30

TEST RIG H-2

REF. SPEC. PARA.

SVHS6017
Appendix A
A4.2.3

TABLE A 4.3.7

PERFORMANCE MAP TEST CONDITIONS

Run Ident.	Pin psia ± 5	t _{on} Seconds	t _{off}	N Pulses	Pulse Pend Seconds	Tape Des. (NRL-LTM)
A ✓	315	0.06	0.94	100	1.00	2
B ✓	315	60.0	-	1	-	3
C ✓	250	0.06	1.19	100	1.25	10
D ✓	250	0.06	0.69	100	0.75	11
E ✓	250	0.075	0.925	100	1.00	12
F ✓	250	.045	0.955	100	1.00	13
G ✓	170	0.06	1.19	100	1.25	10
H ✓	170	0.06	0.69	100	0.75	11
I ✓	170	0.075	0.925	100	1.00	12
J ✓	170	0.045	0.955	100	1.00	13
K ✓	125	0.06	1.19	100	1.25	10
L ✓	125	0.06	0.69	100	0.75	11
M ✓	125	0.075	0.925	100	1.00	12
N ✓	125	0.045	0.955	100	1.00	13
O ✓	95	0.06	0.94	100	1.00	2
P ✓	95	60.0	-	1	-	3
Q ✓	60	0.06	1.19	100	1.25	10
R ✓	60	0.06	0.69	100	0.75	11
S ✓	60	0.075	0.925	100	1.00	12
T ✓	60	0.045	0.955	100	1.00	13


Note: Initial chamber temperature shall be 90° ± 10° F. Artificial cooling is permissible after chamber reaches 600° max.

Bullard
6-14-73

7-24-73

REF. SPEC. PARA. SVHS 6017 A4.2.4	ROOM TEMP (°F) 73	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 0003
CORR BAR. PRES. (IN. HG) 32.2	TEST DATE 7-21-73		
TES. RIG H 2			

BASELINE PERFORMANCE (Continued)



OPERATOR
INTECTOR

INSTRUMENTATION SIGNAL ROUTING - FIGURE 4.4.3

724-73

REF. SPEC. PARA. SYHS 6017 A4.2.4	ROOM TEMP (°F)	73	SER. NO. 0003	TEST DATE 7-24-73
	TORR BAR. PRES. (IN. HG)	30		
TEST RIG		H 2	Hamilton Standard J SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	

QT-6017
Appendix A

BASELINE PERFORMANCE
VISICORDER SETUP TABLE A4.4.4

PARAMETER	CAL RANGE	APPROXIMATE SCALE FACTOR
Valve Voltage	0-30 vdc	2" Span
Valve Current	0-0.5 ma	2" Span
Inlet Pressure	0-300 psia	60 psi/inch
Chamber Pressure	0-250 psia	50 psi/inch
Chamber Temperature	0-1500°F	300°F/inch
Valve Temperature	0-500°F	100°F/inch

OPERATOR
INSPECTOR

7-24-73


REF. SPEC. PARA.
SVHS 6017
4.2.4

ROOM TEMP (°F) 73
CORR BAR. PRES. (in.Hg) 30.
TEST RIG H2

Hamilton Standard
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

SIR. NO. 0002
TEST DATE 7-24-73

QT 127
Appendix A



Rig H2 - Propellant Flow Diagram
Figure 4.4.5

OPERATOR Bullerton
INSPECTOR [Signature]
7-24-73

REF. SPEC. PARA. SVHS6017 para.4.2.5	ROOM TEMP (C): 17 CORR BAR. PRES (IN.HG) 30 TEST RIG HZ	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. C472 TEST DATE 7.24.73	QT6017 Appendix A
--	---	--	--	----------------------

FIRING SEQUENCE - TABLE 4.4.6

Run	Pt P1 Transducer (psia)	T _{on} (sec)	T _{off} (sec)	N Pulses	Sequence Type	Notes
1	250 ± 5	0.06	0.94	100	NRL-LT-2	
2	250 ± 5	60	--	1	NRL-LT-3	Acceptable to combine with run 1
3	170 ± 5	0.06	0.94	100	NRL-LT-2	
4	125 ± 5	0.06	0.94	100	NRL-LT-2	
5	125 ± 5	60	--	1	NRL-LT-3	Acceptable to combine with run 4
6	60 ± 5	0.06	0.94	100	NRL-LT-2	

NOTES: Initial chamber wall temperature 90 ± 10°F Artificial cooling is permissible after chamber reaches 600° max.

OPERATOR
D. H. ...
INSPECTOR
A. B. ...

7-24-73

SER. NO.

TEST DATE

Hamilton Standard
U
P.O.

SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET


ROOM TEMP (°F)

CORR BAR. PRES. (IN.HG)

TEST RIG

REF. SPEC. PARA.

S7HS 6017



NA DB 7-24-73

OPERATOR

INSPECTOR

FIGURE A.4.6 ~ REA FLUSH

REF. SPEC. PARA. SVHS 6017 Appendix A A4.2.5	ROOM TEMP (°F)	73	SER. NO. 0003	TEST DATE 7-25-73	Q1-17 Appendix A
	CORR BAR. PRES. (IN. HG)	30			
TEST RIG		A-2	Hamilton Standard SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET		

A4.2.5

COMBINED LIFE

A. Performance Test (H2)

1. Install the REA in firing fixture P/N SVSK 77657-T-001 with nozzle plug installed in REA nozzle. Verify that a 10 micron absolute filter has been installed at the REA inlet. Cap the Pc tap.
2. Actuate the REA valve by applying 28 ± 2 vdc to the valve power connector. Pin A+, Pin B-.
- * 1-17 3. Pressurize the REA to 50 ± 5 psia and check for external leakage using a leak detecting fluid. If none, write "None".
4. Deactuate the REA valve, bleed pressure through the Pc tap by slowly removing the Pc tap cap. Remove nozzle plug.
- * 1-17 5. Install a chamber temperature thermocouple on the REA as shown in Figure 4-1. Install valve temperature thermocouple as shown.
6. Verify rig cleanliness satisfies HS 3150 CE-5 (no metallic particles over 50 microns) and note this on log sheet.
7. Record throat diameter on the data sheet.
- * 1-17 8. Install the REA in a simulated altitude test facility (Cell H2) and instrument per Table A4.4.1 and Figures A4.4.2 and A4.4.3.
9. Set up visicorder per Table A4.4.4
10. Take a photograph of the unit set up in the test cell.
11. Set rig relief valve to 450 psia maximum.

OPERATOR	1-2-73
INSPECTOR	1-2-73

1-25-73

REF. SPEC. PARA. SVHS 6017 Appendix A A4.2.5	ROOM TEMP (°F)	73	Hamilton Standard U A SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO.	00003
	CORR BAR. PRES. (IN. H ₂ O)	30.		TEST DATE	7.25.73
	TEST RIG	HZ			

A4.2.5 continued

A. 12. Evacuate and backfill the propellant system per standard rig operating procedures including hardness check.

COMBINED LIFE (continued)

- 13. a. Acquire baseline data only on digital tape as follows:
 Steady state runs: Acquire 3 second lead-in, plus 3 sec/100 sec, plus 11 second trailer.
- b. Acquire baseline data only on visicorder as follows:
 Steady state runs: Acquire at 0.1 ips except 20 ips for 1 second out of each 150 seconds.

OPERATOR
Bullington
 INSPECTOR

REF. SPEC. PARA SVHS 6017 Appendix A A4.2.5		ROOM TEMP (°F) 73.	Hamilton Standard SERIES OF JET ENGINE COMPONENTS U A. SLS ACCEPTANCE TEST OPERATIONS/LOG SHEET	SER. NO. 00565	QT-6017 Appendix A
CORR BAR. PRES. (IN. HG) 30.		TEST DATE 7-25-73			
TEST RIG H-2					

COMBINED LIFE (continued)

- A. 15. c. To pressurize the system for a run, open the servomanometer and tank pressure valves and slowly increase the regulated GM₂ supply to the servomanometer, as indicated by the inlet pressure transducer.
- d. Use the firing sequence tape designated for each run.
16. After completion of the firing test, close the arming valve. Apply 10-15 psig GM₂ through the GM₂ source to HX valve. Open bleed, vacuum and fuel bleed valves; to drain fuel from the rig. Close both bleed and the vacuum valves and actuate the REA valve for 120 seconds followed by 25 pulses - 1 second on, 1 second off (Reference Figure 4.5.1).
- B. Flush
1. Install the REA in a flush rig as shown in Figure A4.4.6
 2. Open the H₂O supply valve, pressurize H₂O to 10-15 psig, and actuate the REA valve at an approximate duty cycle of 50 seconds on, 10 seconds off, for 15 pulses. Apply 28 ± 2 vdc to actuate the valve, Pin A+, Pin B- for Steps 2, 3 and 4.
 3. Close H₂O supply valve, open isopropyl alcohol supply valve. Pressurize IPA to 10-15 psig and actuate the REA valve at an approximate duty cycle of 50 seconds on, 10 seconds off for 5 pulses.
 4. Purge REA with GM₂ (check valve held open with 20 ± 2 vdc after opening) at 10-15 psig until IPA ceases flowing from REA. Close REA valve.
 5. Install the REA in a vacuum desiccator and vacuum dry the REA at 1500 microns Hg or less for one hour minimum. Record data in the data table.

INTERIM
PURGE
7-27-73
D 1814 MS

Start
Down

B. Flush

INTERIM
FLUSH
7-27-73
D -

Start
Down

Start
Down

Reproduced from
best available copy.

CREATOR
8-23-73

INSTRUCTOR
[Signature]

8-23-73

QT-6017
Appendix A

SER. NO.

TEST DATE

Hamilton Standard
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

ROOM TEMP (°F)
CORR BAR. PRES. (IN. HG)
TEST RIG

REF. SPEC. PARA.
SVHS 6017
Appendix A
A4.2.5

OPERATOR
INSPECTOR

TABLE 4.5.1 (continued)

Pressure psia ± 5	Mode Pulse/S.S.	t	Tape Designation	Runs
Comp 10 8-16-73	13.75K pulses	-	NRL-LT-15	1
Comp 8-16-73	Baseline Test	-	-	-
Comp 210 8-16-73	S.S.	2 hr.	NRL-LT-16	3
Comp - 8-16-73	Baseline Test	-	-	2
Comp 170 8/17/73	20K pulses	-	NRL-LT-14	1 55
Comp - 8/17/73	Baseline Test	-	-	2
Comp 170 8-17-73	20K pulses	-	NRL-LT-14	1 55
Comp 8-17-73	Baseline Test	-	-	2
Comp 170 8-17-73 B	20K pulses	-	NRL-LT-14	1 55
Comp - 9-18-73 B	Baseline Test	-	-	2
Comp 170 9-18-73	20K pulses	-	NRL-LT-14	1 55
Comp 9-18-73	Baseline Test	-	-	2
Comp 240 8-18-73 B	13.75K pulses	-	NRL-LT-15	1 3
Comp - 9-18-73 B	Baseline Test	-	-	2
Comp 170 9-19-73 B	S.S.	2 hr.	NRL-LT-16	3 7
Comp - 8/20/73	Baseline	-	-	2
Comp 125 8-20-73	20K pulses	-	NRL-LT-14	1 55
Comp 8-20-73	Baseline Test	-	-	2
Comp 125 8-20-73 B	20K pulses	-	NRL-LT-14	1 55
Comp - 8-20-73 B	Baseline Test	-	-	2

NSF-1270 1/67

B-38 61.0

QT-6017
Appendix A

SER. NO.

TEST DATE

OPERATOR

INSPECTOR

Hamilton Standard
U.S. AIR FORCE
SLS ACCEPTANCE TEST
OPERATIONS/LOG SHEET

TABLE 4.5.1 (continued)

Pressure psia \pm 5	Mode Pulse/S.S.	t minutes	Tape Designation	Runs
125 <i>Comp 8/21/73</i>	20K pulses	-	NRL-LT-14	1
<i>Comp 8/21/73</i>	Baseline Test	-	-	-
<i>Comp 8-21-73</i>	20K pulses	-	NRL-LT-14	1
<i>Comp. 8-21-73</i>	Baseline Test	-	-	-
<i>Comp 125 8-21-73</i>	13.75K pulses	-	NRL-LT-15	1
<i>Comp 8-21-73</i>	Baseline Test	-	-	-
125 <i>Comp 8/21/73</i>	S.S.	2 hr.	NRL-LT-6	3
<i>Comp 8/21/73</i>	Baseline Test	-	-	-

5.5
2.
5.5
2
3
2.
7.
2.
24.0

ROOM TEMP (°F)

CORR BAR. PRES. (IN. HG)

TEST RIS

REF. SPEC. PARA.
SVHS 6017
Appendix A
A4.2.5

**Hamilton
Standard**

U
DIVISION OF UNITED AIRCRAFT CORPORATION
A.

SVHSER 6305

APPENDIX C

QUALIFICATION DATA CURVES

TABLE IC

Thrust Overshoot
 S/N 00003
 Inlet Pressure = 250 psia

Run Number	Cumulative Operating Time (hours)	Thrust Overshoot (lb _f)			Fuel Temperature (°F)
		1. Steady State	2. Pulse 1	3. Pulses 2 - 100	
2483	.097	0.22	0.41	0.24	68.5 - 70.2
2487	.427	0.22	0.41	0.24	68.7 - 70.2
2491	.757	0.22	0.41	0.27	68.6 - 70.3
2495	1.087	0.23	0.41	0.25	68.8 - 70.5
2499	1.417	0.22	0.37	0.22	68.1 - 69.5
2503	1.647	0.22	0.37	0.23	68.4 - 70.6
2507	7.647	0.22	0.38	0.24	74.0 - 75.6
2511	7.977	0.21	0.37	0.25	77.6 - 78.2
2516	8.307	0.21	0.37	0.23	76.0 - 77.2
2520	8.637	0.21	0.37	0.22	75.1 - 76.1
2524	8.967	0.23	0.37	0.25	75.1 - 76.5
2528	9.197	0.23	0.36	0.25	75.4 - 76.4
2532	15.197	0.22	0.37	0.24	75.4 - 77.2
2536	15.527	0.21	0.37	0.23	75.3 - 76.4
2540	15.857	0.21	0.37	0.22	74.9 - 79.7
2544	16.187	0.20	0.37	0.32	76.5 - 77.6
2548-9	16.517	0.22	0.37	0.26	75.6 - 76.5
2553	16.747	0.20	0.37	0.24	75.7 - 77.3
2557	22.747	0.20	0.25	0.28	75.7 - 77.4
2561	23.077	0.20	0.30	0.25	75.5 - 76.9
2565	23.407	0.20	0.32	0.21	76.4 - 77.3
2569	23.737	0.20	*	*	75.5 - 77.2
2573	24.067	0.21	0.35	0.25	76.3 - 77.3
2577	24.297	0.20	0.37	0.23	75.6 - 77.0
2582	30.297	0.20	0.0	0.23	75.5 - 77.0

1. Specification requires that steady state thrust overshoot not exceed 0.57 lb_f.
2. Specification requires that first pulse thrust overshoot not exceed 0.57 lb_f.
3. Specification requires that thrust overshoot for pulses 2-N not exceed 0.44 lb_f.

* Digital data not available.

21 BASELINE RUNS

P1=250 P.S.I.A.




Figure 1C

23 BASELINE RUNS

PI = 125 P.S.I.A.




Figure 2C

21 BASELINE RUNS

P1=250 P.S.I.A.




Figure 3C

C-4

23 BASELINE RUNS

P1 = 125 P.S.I.A.




Figure 4C

e-5

21 BASELINE RUNS

P1=250 P.S.I.A.




Figure 5C

C-6

23 BASELINE RUNS

P1 = 125 P.S.I.A.




Figure 6C

21 BASELINE RUNS

P1=250 P.S.I.A.




Figure 7C

2-8

24 BASELINE RUNS PJ=170 P.S.I.A.




Figure 8C

C-9

29 BASELINE RUNS

P1 = 125 P.S.I.A.




Figure 9C

C-10

21 BASELINE RUNS

P1=250 P.S.I.A.




Figure 10C

C-11

24 BASELINE RUNS PI=170 P.S.I.A.




Figure 11C

23 BASELINE RUNS

PI = 125 P.S.I.A.




Figure 12C

C-13

24 BASELINE RUNS

PI = 60 P.S.I.A.




Figure 13C

2.14

21 BASELINE RUNS

P1=250 P.S.I.A.




Figure 14C

Q-15

24 BASELINE RUNS

P1 = 170 P.S.I.A.




Figure 15C

2:16

23 BASELINE RUNS

PJ = 125 P.S.I.A.




Figure 16C

C-17

24 BASELINE RUNS

P1 = 60 P.S.I.A.




Figure 17C

2-18

21 BASELINE RUNS - P1=250 P.S.I.A.




Figure 18C

24 BASELINE RUNS PI=170 P.S.I.A.




Figure 19C

23 BASELINE RUNS P1=125 P.S.I.A.




Figure 20C

24 BASELINE RUNS P1= 60 P.S.I.A.




Figure 21C

21 BASELINE RUNS

P1=250 P.S.I.A.




Figure 22C

24 BASELINE RUNS

P1=170 P.S.I.A.




Figure 23C

c-24

23 BASELINE RUNS P1=125 P.S.I.A.




Figure 24C

e-25

24 BASELINE RUNS P1= 60 P.S.I.,A.




Figure 25C

e-26

21 BASELINE RUNS

P1=250 P.S.I.A.




Figure 26C

24 BASELINE RUNS

PI=170 P.S.I.A.




Figure 27C

C-28

29 BASELINE RUNS P1 = 125 P.S.I.A.




Figure 28C

C-29

24 BASELINE RUNS

P1 = 00 P.S.I.A.




Figure 29C

C-39

21 BASELINE RUNS

PI=250 P.S.I.A.




Figure 30C

C.31

24 BASELINE RUNS

P1 = 170 P.S.I.A.




Figure 31C

23 BASELINE RUNS

P1 = 125 P.S.I.A.




Figure 32C

24 BASELINE RUNS

P1 = 60 P.S.I.A.




Figure 33C

C-34

RUNS=24-67.71.75.81 TON=.045 SEC-TOFF=.955




Figure 34C

C-35

RUNS=24-67.71.75.81 TON=.045 SEC=TOFF=.955




Figure 35C

RUNS=24-67.71.75.81 TON=.045 SEC-TOFF=.955




Figure 36C

RUNS=24-67.71.75.81 TON=.045 SEC=TOFF=.955




Figure 37C

RUNS=24-67.71.75.81 TON=.045 SEC-OFF=.955




Figure 38C

C-29

RUNS=24-67.71.75.81 TON=.045 SEC-TOFF=.955




Figure 39C

e-to

RUNS=24-67.71.75.81 TON=.045 SEC-OFF=.955




Figure 40C

c.41

RUN5-24-84.68.72.78 TON=.060 SEC=TOFF=1.18




Figure 41C

C.42

RUNS=24-64.68.72.78 TON=.060 SEC-TOFF=1.19




Figure 42C

c.43

RUNS=24-64.68.72.78 TON=.060 SEC-OFF=1.19




Figure 43C

c.44

RUNS=24-64.68.72.78 TON=.060 SEC=TOFF=1.19




Figure 44C

C-45

RUNS=24-64.68.72.78 TON=.060 SEC=TOFF=1.19




Figure 45C

c.46

RUNS=24-64.68.72.78 TON=.060 SEC-OFF=1.19




Figure 46C

c 47

RUNS=24-64.68.72.78 TON=.060 SEC-TOFF=1.19




Figure 47C

C.48

RUNS=24-65.69.73.78 TON=.080-TOFF=.690




Figure 48C

C49

RUNS=24-65, 69, 73, 79 TON=.060-TOFF=.690




Figure 49C

e.50

RUNS=24-65.69.73.78 TON=.060-TOFF=.690




Figure 50C

C-51

RUNS=24-65.68.79.79 TON=.060-TOFF=.690




Figure 51C

c-52

RUNS=24-65.69.73.79 TOM=.060-TOFF=.690




Figure 52C

C-53

RUNS=24-65.69.73.79 TON=.060-TOFF=.690




Figure 53C

0.54

RUNS=24-65.69.73.79 TON=.060-TOFF=.690




Figure 54C

C-55

RUNS=24-66.70.74.80 TON=.075-TOFF=.925




Figure 55C

2-56

RUNS=24-86.70.74.80 TON=.075-TOFF=.925




Figure 56C

RUNS=24-66.70.74.80 TON=.075-TOFF=.925




Figure 57C

C-58

RUNS=24-66.70.74.80 TON=.075-TOFF=.925




Figure 58C

C-59

RUNS=24-66.70.74.80 TON=.075-TOFF=.925




Figure 59C

C-60

RUNS=24-66.70.74.80 TON=.075-TOFF=.925




Figure 60C

0.61

RUNS=24-66.70.74.80 TON=.075-TOFF=.925




Figure 61C

APPENDIX D

VIBRATION TEST REPORTS

APPENDIX D

Memo No. NRL-2LB-1244

Page No. 3 of 3

Memorandum to: Structures Group

Date of Test: 7-19-73

Date of Memo: 11-12-73

Program: NRL

Type of Test: QUAL - OST

Test Item(s): .2LB REA

S/N: 00003

Remarks:

Short Term No Data available
[Signature] 11/12/73

Operational Test Engineer _____

Date _____

Received - Date _____

TER No. _____

Returned to S. Mehmed jr

Action Taken - Date _____

PROGRAM	N.R.L
TEST	QUAL
UNIT	.2LB REA
S/N	00003
DATE	11-12-73

D-1-a

Memo File Code NRL-2LB-1294

Memorandum to: EARL K. MOORE

Page 1 of 3

Program N.R.L

Test Item(s) .2LB REA

Date of Test 7-19-73

Serial No.(s) 00003

Name of Test QUAL-OST

Specification QT6017

Subject:

THE TEST UNIT WAS MOUNTED TO VIBRATION
FIXTURE SVSK 77886 WHICH IN TURN WAS
SECURED TO THE VIBRATION GENERATOR.

SINUSOIDAL AND RANDOM TESTING WAS
PERFORMED PER THE ABOVE SPECIFIED SPECIFICATION.

TEST DEVIATIONS

1) CONDITION - UNDERTEST FROM 1800 - 2000HZ
DURING SINUSOIDAL RUN 7 IN THE Z AXIS

REASON - LACK OF CONTROL
CAUSE - COMPRESSOR SETTING ON SERVO
CONTROL UNIT WAS NOT PROPERLY
ADJUSTED.

CON'T

Test Engineer S. MEHMED JR

Signature *Sami Mehmeh*

Date of Report 11-12-73

Approved *Sami Mehmeh* Date 11/13/73

Table of Contents

Test Background	Section I
A) Instrumentation and Calibration List	
B) Block Diagram of Test System	
C) Random Analysis Outline	
X - Axis	Section II
A) Sine Data	
B) Random Data	
Y - Axis	Section III
A) Sine Data	
B) Random Data	
Z - Axis	Section IV
A) Sine Data	
B) Random Data	
Logs	Section V
A) Operator Log	
B) Instrumentation Master & Running Log	
C) Illustration of Transducer Location	

Section I

Test Background

- A) Instrumentation and Calibration List
- B) Block Diagram of Test System
- C) Illustration of Item & Transducer Location
- D) Random Analysis Outline

Laboratory Operations Engineering

TEST EQUIPMENT

Item	Manufacturer	Accuracy	Model	S/N	Calibrated
Accelerometer	Endevco	±2%	2222	AC13	5-28-73 A
Accelerometer	Endevco	±2%	2222	AC26	5-28-73 A
Accelerometer	Endevco	±2%	2222	BJ30	5-28-73
Accelerometer	Endevco	±2%	2222	BJ66	5-28-73 A
Accelerometer	Endevco	±2%	2222	BJ69	5-28-73 A
Accelerometer	Endevco	±2%	2222	BJ70	5-28-73 A
Accelerometer	Endevco	±2%	2222	BJ72	5-28-73 A
Accelerometer	Endevco	±2%	2226	PC37	5-28-73 A
Accelerometer	Endevco	±2%	2226	TD35	5-28-73 A
Accelerometer	Endevco	±2%	2226	TD36	5-28-73 A

Standard calibration period is 2 months.

A = Used for this test.

TEST EQUIPMENT
RIG 91 LING 40 (continued)


<u>ITEM</u>	<u>MANUFACTURER</u>	<u>MODEL</u>	<u>S/N</u>
Multi-Level Programmer	Ling Electronics	MLP-101-5A	164
Manual Selector Switch	Ling Electronics	SSM-100A	113
Low Frequency Equalizer	Ling Electronics	5LF-80A	175
Control Panel	Ling Electronics	CP-10B	175
Channel Mode Selector	Ling Electronics	CM-40B	276
Channel Mode Selector	Ling Electronics	CM-40B	281
Spectrum Equalizer	Ling Electronics	SE-80C	116
Spectrum Equalizer	Ling Electronics	SE-80D	116
Meter Range Selector	Ling Electronics	MR-40B	254
Meter Range Selector	Ling Electronics	MR-40B	290
Power Distribution	Ling Electronics	FB10	176
Shaker	Ling Electronics	340	12
Heat Exchanger	Ling Electronics	279	13
Power Amplifier	Ling Electronics	PP70/120VC	12
Console	Ling Electronics	RC-120	80
Auto Tape Degausser	Hewlett-Packard	3603A	644-00193
Remote Control	Ling Electronics	RCP-100	
Random Console	Ling Electronics	ASDE-80	164
Slip Table	Ling Electronics	4348-DS-8	34

Reproduced from
best available copy.

LABORATORY OPERATIONS ENGINEERING
TEST EQUIPMENT
RIG 91 LING 340

<u>ITEM</u>	<u>MANUFACTURER</u>	<u>ACCURACY</u>	<u>MODEL</u>	<u>S/N</u>
Driver Amplifier	Ling Electronics		A-10	172
Dual Noise Generator	Ling Electronics		GRN200B	164
Spectrum Analyzer	Ling Electronics		SA100	A-295-66
Spectrum Analyzer	Ling Electronics		SA100	A-324-66
Power Supply	Ling Electronics		APS102	37
Power Supply	Ling Electronics		APS10A	175
Power Supply	Ling Electronics		APS1130	114
Power Supply	Ling Electronics		APS103	29
Sine Wave Center	Ling Electronics		SCO-100	27
Tape Recorder	Ampex		FR1200	185
Line Amplifier	Ling Electronics		LA-102	18
X-Y Recorder	Hewlett-Packard	±5%	7030A	823-D1267
Log Converter	Hewlett-Packard	±5%	7561A	825-00940
Log Converter	Hewlett-Packard	+5%	7561A	825-00944
Tracking Filter	Spectral Dynamics		SD101-B-1	19
Tracking Filter	Spectral Dynamics		SD101-B-1	242
*Voltmeter	B&K	±1% F.S.	VTVM-Z	186525
Charge Amplifier	Unholtz-Dickie		8PMCVA	405
Oscilloscope	Hewlett-Packard	+5%	122AR	141-04179
*Counter	Anadex	±1 count	CF600R	30952

Standard calibration period - Entire system 2 months and also item * are 4 months.



SSD VIBRATION GENERATING SYSTEM RIG 91 / LING 340

RANDOM VIBRATION ANALYSIS

METHOD A

The power spectrum density analyser consists of one, eighty-five (85) channel filter system - Ling Electronics Model ASDE-80.

1. FILTER BANDWIDTHS

<u>Frequency Range</u>	<u>Bandwidth</u>
10-20 cps	10 cps
20-31	11
31-43	12
43-56	13
56-70	14
70-84	14
84-99	15
99-115	16
115-132	17
132-150	18
150-175	25
175-2025	25 cps each

2. DETECTOR TIME CONSTANT

RC = 5 seconds (average of combined operating modes)

3. SWEEP RATES

The sweep rate is variable.

Minimum Sweep Time - 36 seconds

Maximum Sweep Time - Infinity

4. DEGREES OF FREEDOM

$$N = 4 \times (BW) \times (RC)$$

10 cps BW; N = 200 Minimum average

25 cps BW; N = 500 Maximum average

5. CONFIDENCE LEVEL

At 25 cps BW: Confidence level = 95%
Error = 20%

Section II

X - Axis

A) Sine Data

B) Random Data


SINE VIBRATION TEST

Hamilton Standard
DIVISION OF UNITED TECHNOLOGY CORPORATION

HSF-1633, 1 2/69

RIG 91	OPERATOR R. MICKET	WITNESS <i>A. Guil</i>	TEST NO. 3
TEST ENGINEER K. BRADFORD	CHECKED BY	DATE 7-19-73	TIME 1410
	PROJECT NRL		


INPUT LEVEL 11	LXCIT. AXIS X
3-CELL W/F TD35	SENSING AXIS X
ACCEL SENSITIVITY 2.655	MV RMS GP
	COL GP
FILTER 10-100-200	HZ B.W.
FILTER CROSSOVER 70-700	HZ
SWEPT RATE 1	OCT/MIN
TAPE REEL NO. 041447	LIVE FROM TAPE <input checked="" type="checkbox"/>
COMPR. SPEED VAR	DR/SEC.
CHG. @ - HZ TO - DB/SEC.	
CHG. @ - HZ TO - DB/SEC.	
NON OPERATING CONTROL <input checked="" type="checkbox"/>	RESPONSE <input type="checkbox"/>
TEMP. 75	
LOCATION AX	
SPECIAL CONDITIONS	
REPORT NO.	



ITEM 25-2000 HE	CODE —	SERIAL NO. 00003	DATE RT-6017	TEST NO. 4.2.3
ACTION SHEET NO.	TYPE OF TEST QUAL - OST	NAME OF TEST SINE		

**RANDOM VIBRATION TEST
 ANALYSIS METHOD A**

PLOTTED BY R. MICKET	CHECKED BY	TEST ENGINEER K. BRADFORD	WITNESS
PROJECT NRL	ITEM .2LB REA	CODE	WITNESS N. Guil 7-19-73
SPEC. QT-6017	PARA. 4.2.3	ATA NO.	TYPE OF TEST QUAL-05T
	PHASE	ACTION SHEET NO.	TEST NO. 3
			DATE 7-19-73



EXCITATION ALONG AXIS X	REPORT NO.
LINE INPUT 6.0	
TEMPERATURE 75 °F	
METHOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	
DURATION OF TEST 2 MIN.	
ACCEL. SERIAL NO. TD35	
ACCEL. SENSITIVITY MV RMS / GP 2.655	
ACCEL. SENSING X	
ACCEL. LOCATION AX	
SPECIAL CONDITIONS	

Section III

Y - Axis

A) Sine Data


B) Random Data

SINE VIBRATION TEST

MSF-1639.1 2/69

RIG 91	OPERATOR R. MICKET	WITNESS <i>P. Ford</i>	TEST NO. 6
TEST ENGINEER K. BRADFORD	CHECKED BY	PROJECT NRL	DATE 7-19-73
			TIME 1525

INPUT LEVEL EXCIT. AXIS 11	Y
ACCEL. SENS. SENSING AXIS TD36	Y
ACCEL. SENSITIVITY MV RMS	GP
	COL
	GP
2.785	
FILTER 10-100-200 HZ B.W.	
FILTER CROSS-OVER 70-700 HZ	
SWEEP RATE 1	OCT/MIN
TAP REEL NO. <input checked="" type="checkbox"/>	LIVE FROM TAPE
COMPR. SPEEL VAR	DI/SEC.
CHG. ① - HZ TO - DE/SEC.	
CHG. ② - HZ TO - DE/SEC.	
NON OPERATING <input checked="" type="checkbox"/>	CONTROL
TEMP. 75 %	RESPONSE
LOCATION AY	
SPECIAL CONDITIONS	
REPORT NO.	




FREQ. RANGE & DIRECTION 25-2000 HZ	ITEM .2LB REA	CODE —	SERIAL NO. 00003	SPEC. QT-6017	PARAM. A.2.3	AMPLND. —
ACTION SHEET NO.	DATA NO.	TYPE OF TEST QUAL - CST	NAME OF TEST SINE		I.	

**RANDOM VIBRATION TEST
 ANALYSIS METHOD A**

PLOTTED BY R. MICKET	CHECKED BY K. BRADFORD	TEST ENGINEER K. BRADFORD	RIG NO. 91	WITNESS <i>A. Gail 7-19-73</i>
PROJECT NRL	ITEM .2LB REA	CODE	SERIAL NO. 00003	TYPE OF TEST QUAL - OST
SPEC. QT-6017	PARA. 4.2.3	ATA NO.	ACTION SHEET NO.	TEST NO. 5
	PHASE		DATE 7-19-73	

VIBRATION AXIS Y	GRAV. INPUT 6.0	TEMP. 75.0
NON-OPERATING	START <input checked="" type="checkbox"/> END <input type="checkbox"/>	DURATION OF TEST 2 MIN.
ACCEL. SENSITIVITY	ACCEL. SERIAL NO. TD36	ACCEL. LOCATION AY
MV RMS 2.785	GP	COL GP
ACCEL. SENSING Y	SPECIAL CONDITIONS	
ACCEL. LOCATION AY	REPORT NO.	



Section IV

Z - Axis

A) Sine Data


B) Random Data

SINE VIBRATION TEST

HSF-1633.1 2/69

RIG 91	OPERATOR R. MICKET	WITNESS O. Guil	TEST NO. 7
TEST ENGINEER K. BRADFORD	CHECKED BY	PROJECT NRL	DATE 7-19-73
			TIME 1545

INPUT LEVEL 11	SCIT. AXIS Z
ACCEL S/N PC37	SENSING AXIS Z
ACCEL SENSITIVITY 2.615	MV RMS GP COL GP
FILTER 10-100-200	HZ B.W.
FILT. CROSSOVER 70-700	HZ
SWEEP RATE 1	OCT/MIN
TAPE REEL NO. 041447	LIVE FRESH TAPE
COMPR. SPEED VAR	DB/SEC.
CHG. @ - HZ TO - DB/SEC.	
CHG. @ - HZ TO - DB/SEC.	
NON OPERATING CONTROL <input checked="" type="checkbox"/>	RESPONSE
TEMP. 75°	
LOCATION AZ	
SPECIAL CONDITIONS	



FREQ. RANGE & DIRECTION 25-2000 HZ	ITEM 2LB REA	CODE —	SERIAL NO. 00003	SPEC. QT-6017	PARA. A.2.3	AMEND. —
ACTION SHEET NO.	ATA NO.	TYPE OF TEST QUAL - DST	NAME OF TEST SINE			

**ANDOM VIBRATION TEST:
 ANALYSIS METHOD A**

MSF-1614A	PLOTTED BY R. MICKET		CHECKED BY K. BRADFORD	TEST ENGINEER K. BRADFORD	ATA NO.	WITNESS 7-19-73 <i>P. Ford</i>
PROJECT NRL	ITEM .2LB REA	CODE	SERIAL NO. 00003	ACTION SHEET NO.	TYPE OF TEST QUAL-OST	WITNESS
SPEC. QT-OST	PARA. 4.2.3	PHASE	DATE 7-19-73	TEST NO. 8		

EXCITATION ALONG AXIS Z	TEMP. 75	PERIOD OF TEST <input checked="" type="checkbox"/> START <input type="checkbox"/> END	ACCEL. SENSITIVITY PC37
GEN'S INPUT 5.0	INCORP. - PATING	DEVIATION OF TEST 2	M.V. RMS GP 2.615
ACCEL. SERIAL NO.	COL. GP	MIN.	COL. GP
ACCEL. SENSING AXIS Z	SPECIAL CONDITIONS		
ACCEL. LOCATION AZ	REPORT NO.		

• SPECTRAL DENSITY G/Hz

VAR BW

10 100 150

FREQUENCY Hz

25 CPS BANDWIDTH


1000

Section V

Logs

- A) Operator Log
- B) Instrumentation Master & Running Log
- C) Data Reduction Log

NO	MEASUREMENT			TRANSDUCER			FULL SCALE ESTIMATE	RECORDED		REMARKS
	UNIT	LOC	TYPE	NO	TYPE	SP		TYPE	SP	
1	Cal	AX	2226	T035						
2	"	AY	2226	T036						
3	"	AZ	2226	P037						
4	Accel	AX	2222	RT1			1.076 - 2.192			
5	"	AY	2222	RT2			1.199 - 2.378			
6	"	AX	2222	AC13			1.218 - 2.476			
7	"	AY	2222	AC24			1.437 - 2.854			
8	"	AZ	2222	RT4			1.288 - 2.576			
9										
10										
11										
12										
13										
14										
15										
16										
17										
18										
19										
20										
21										
22										



VIBRATION TEST LOG

PROJECT N R L ITEM 02 LB REB S/N 00003
TEST TITLE QUAL - OST ENGINEER R K Bradford

DATE 7-19-73

OPERATOR R M G K & E

TEST NO	TIME	TEST CODE	REMARKS												REMARKS				
			1	2	3	4	5	6	7	8	9	10	11	12					
1	1400	CAL	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	15	91	0.707 VRMS @ 200 HZ
2	1410	RUN	30	10	10	10	10	10	10	10	10	10	10	10	10	10	1/100	1	5-2000 Hz SINE SCAN
3	1440	RUN	30	10	10	10	10	10	10	10	10	10	10	10	10	10	1/100	1	25-2000 Hz SINE
4	1440	RUN	30	10	10	10	10	10	10	10	10	10	10	10	10	10	1/100	1	20-2000 Hz RANDOM
5	1520	RUN	30	10	10	10	10	10	10	10	10	10	10	10	10	10	1/100	1	20-2000 Hz RANDOM
6	1525	RUN	30	10	10	10	10	10	10	10	10	10	10	10	10	10	1/100	1	25-2000 Hz SINE
7	1545	RUN	30	10	10	10	10	10	10	10	10	10	10	10	10	10	1/100	1	25-2000 Hz SINE
8	1555	RUN	30	10	10	10	10	10	10	10	10	10	10	10	10	10	1/100	1	20-2000 Hz RANDOM
9		CAL	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000			0.707 VRMS @ 200 HZ

2000

MAP 1718