

AD-A054 502

ARINC RESEARCH CORP HONOLULU HI
ADVANCE OVERHAUL PLANNING FOR USS APACHE (ATF-67); USS COCOPA (---ETC(U)
OCT 74

F/G 13/10

N00140-73-D-0074

UNCLASSIFIED

1020-01-1-1303

NL

1 OF 2
AD
A054502



FOR FURTHER TRAINING

Otero

6

SC

SUMMARY REPORT:

ADVANCE OVERHAUL PLANNING FOR
USS APACHE (ATF-67), USS COCOPA (ATF-101),
USS MOLALA (ATF-106), AND USS QUAPAW (ATF-110)

October 1974

DDC
MAY 31 1978
RECEIVED
F

Prepared for

PERA(CSS)
Hunters Point Naval Shipyard
San Francisco, Calif.

Under Contract N00140-73-D-0074
Delivery Orders 0004, 0006, & 0010

Publication 1020-01-1-1303

AD A 054502

AD No. _____

DDC FILE COPY

ARINC RESEARCH CORPORATION

This document has been approved
for public release and sale; its
distribution is unlimited.

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE | | READ INSTRUCTIONS BEFORE COMPLETING FORM |
|---|-----------------------|---|
| 1. REPORT NUMBER 1020-01-1-1303 [✓] | 2. GOVT ACCESSION NO. | 3. RECIPIENT'S CATALOG NUMBER |
| 4. TITLE (and Subtitle) ADVANCE OVERHAUL PLANNING FOR USS APACHE (ATF-67), USS COCOPA (ATF-101), USS MOLALA (ATF-106), AND USS QUAPAW (ATF-110) | | 5. TYPE OF REPORT & PERIOD COVERED |
| 7. AUTHOR(s) Not Listed | | 6. PERFORMING ORG. REPORT NUMBER 1020-01-1-1303 |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS ARINC Research Corporation [✓] 2551 Riva Road Annapolis, Maryland 21401 | | 8. CONTRACT OR GRANT NUMBER(s) N00140-73-D-0074 ^{MLW} |
| 11. CONTROLLING OFFICE NAME AND ADDRESS PERA(CSS) Hunters Point Naval Shipyard San Francisco, Calif. | | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) PERA(CSS) Hunters Point Naval Shipyard San Francisco, Calif. | | 12. REPORT DATE October 1974 |
| | | 13. NUMBER OF PAGES 144 |
| | | 15. SECURITY CLASS. (of this report) UNCLASSIFIED |
| | | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE |
| 16. DISTRIBUTION STATEMENT (of this Report) UNCLASSIFIED/UNLIMITED | | |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) | | |
| 18. SUPPLEMENTARY NOTES | | |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number) | | |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Postoverhaul analysis reports of four fleet ocean tugs of the Service Force, Pacific, are presented. The reports relate to the 1974 regular overhauls of the USS APACHE (ATF-67), USS COCOPA (ATF-101), USS MOLALA (ATF-106), and USS QUAPAW (ATF-110). | | |

DD FORM 1473
1 JAN 73

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| | |
|--|---|
| REPORT DOCUMENTATION PAGE | |
| REPORT NUMBER 1000-01-1-1303 | |
| ADVANCE OVERHAUL TRAINING FOR USS APACHE (ATF-67), USS COCOBA (ATF-101), USS MOATA (ATF-106), AND USS QAPAW (ATF-110) | |
| PERFORMING ORG REPORT NUMBER 1000-01-1-1303 | |
| CONTRACT OR GRANT NUMBER N0010-93-D-0074 | Not Indexed |
| PERFORMING ORG NAME(S) AND ADDRESS ARINC Research Corporation 2521 Riva Road Annapolis, Maryland 21401 | |
| REPORT DATE October 1974 | THRA(022) Hunters Point Naval Shipyard San Francisco, Calif. |
| REPORT TYPE AND DATES COVERED Final | THRA(022) Hunters Point Naval Shipyard San Francisco, Calif. |
| SECURITY CLASSIFICATION OF THIS REPORT UNCLASSIFIED | |
| UNCLASSIFIED/UNLIMITED | |
| <p>Postoverhaul analysis reports of four fleet ocean tugs of the Pacific Force, Pacific, are presented. The reports relate to the 1974 regular overhauls of the USS APACHE (ATF-67), USS COCOBA (ATF-101), USS MOATA (ATF-106), and USS QAPAW (ATF-110).</p> | |

6

9 SUMMARY REPORT,

6 ADVANCE OVERHAUL PLANNING FOR
USS APACHE (ATF-67), USS COCOPA (ATF-101),
USS MOLALA (ATF-106), AND USS QUAPAW (ATF-110)

11 October 1974

12 146p

Prepared for

PERA(CSS)
Hunters Point Naval Shipyard
San Francisco, Calif.

75 Under Contract N00140-73-D-0074
Delivery Orders 0004, 0006, & 0010

DDC
RECEIVED
MAY 31 1978
F

ARINC RESEARCH CORPORATION

HONOLULU SUPPORT OFFICE
245 Fort Street, Suite 211
Honolulu, Hawaii 96801

HEADQUARTERS
2551 Riva Road
Annapolis, Maryland 21401

14 Publication 1020-01-1-1303

This document has been approved
for public release and sale; its
distribution is unlimited.

410 572

JOB

ABSTRACT

Postoverhaul analysis reports of four fleet ocean tugs of the Service Force, Pacific, are presented. The reports relate to the 1974 regular overhauls of the USS APACHE (ATF-67), USS COCOPA (ATF-101), USS MOLALA (ATF-106), and USS QUAPAW (ATF-110).

| | |
|---------------------------------|---|
| ACCESSION for | |
| NTIS | Write Station <input checked="" type="checkbox"/> |
| DDC | B. H. Section <input type="checkbox"/> |
| UNANNOUNCED | <input type="checkbox"/> |
| JUSTIFICATION | |
| BY | |
| DISTRIBUTION/AVAILABILITY CODES | |
| BY | OFFICIAL |
| A | |

SUMMARY

Under Delivery Orders 0004, 0006, and 0010 of Contract N00140-73-D-0074, ARINC Research Corporation performed selected tasks for PERA(CSS) in support of the 1974 regular overhauls of four fleet ocean tugs of the Service Force, Pacific.

The Corporation's support included assistance in advance overhaul planning and the preparation of postoverhaul analysis reports.

The postoverhaul reports, prepared to a format prescribed by PERA(CSS), were individually submitted to that activity as completed. These reports are compiled in this document in the sequence in which they were issued, as follows:

- a. USS APACHE (ATF-67), Publication 1020-01-1-1303A
- b. USS QUAPAW (ATF-110), Publication 1020-01-1-1303B
- c. USS MOLALA (ATF-106), Publication 1020-01-1-1303C
- d. USS COCOPA (ATF-101), Publication 1020-01-1-1303D



USS APACHE (ATF-67)
OVERHAUL PLANNING ANALYSIS REPORT

July 1974

USS APACHE (ATF-67)
OVERHAUL PLANNING ANALYSIS REPORT

APPROVED: _____

DATE: _____

Distribution:

NAVSHIPS 427
COMSERVPAC
COMSERVGRU ONE
PERA (CSS)

Prepared by

ARINC Research Corporation
Ships and Ordnance Division
Honolulu Support Office

Contract N00140-73-D-0074-0010

Publication 1020-01-1-1303A

USS APACHE (ATF-67)
OVERHAUL PLANNING ANALYSIS REPORT

TABLE OF CONTENTS

- I. General Information - Preface
- II. Management Summary
- III. A. Planning Process
 - 1. Ideal Vs. Actual Milestones
 - 2. Impact
 - 3. Recommendations
- B. Work Package
 - B.1 Summary Sheet
 - B.2 Cost Summary Sheet, naval or civilian yard
 - B.3 ALT Summary Sheet
 - B.4 TYCOM Repair Package
 - B.5 PERA Screening Summary
 - B.6 Preoverhaul Material Condition
- C. Deferred Work/Long Range Maintenance Actions
- D. Recommendations
- E. Evaluation/Usefulness

I. General Information and Preface

General Information:

Ref: (a) COMSERVPAC Overhaul Planning General Task Index and Tasks,
dated 15 September 1972.

(b) PERA(CSS) Milestone Charts, dated August 1972; forwarded by
PERA(CSS) Letter Ser 1800-262 of 4 May 1973.

Preface:

The USS APACHE (ATF-67) was scheduled to be overhauled during the period
15 February - 15 June 1974 at SUPSHIP 13.

In planning the overhaul of USS APACHE, PERA(CSS), acting as TYCOM and
NAVSHIPS' maintenance management agent, utilized advance planning milestones,
references (a) and (b), which commenced 9-1/2 months prior to the then-scheduled
overhaul start date. The goal of the planning effort has been to identify, in advance,
potential and existing problem areas; and provide the detailed preoverhaul guidance,
planning, and coordination necessary to achieve a successful yard overhaul. The
purpose of this report is to evaluate the management judgments and decisions associ-
ated with the planning effort during this period.

The overhaul of the USS APACHE was put in a hold status on 18 December 1973
and cancelled on 9 February 1974. The ship has since been decommissioned. Prior
to being put in a hold status, the overhaul planning effort had progressed through the
work definition conference.

II. Management Summary

Ref. (a) lists the management milestones used in planning the overhaul of the USS APACHE. Deviations from the milestones which affected the planning, and non-programmed factors which contributed to the planning outcome, are discussed in Section III. A.

It is felt that all the work required to ensure that the APACHE received a thorough overhaul was identified and authorized. Since the ship was not overhauled, the adequacy of the final work package cannot be determined.

Considerable effort was expended during the planning phase to develop a ship alteration to replace the ship's service generators because the ship had only 300 kilowatts available. The project was terminated because of the projected cost (about \$250,000) and the limited time available before the ROH start.

The COMSERVPAC budget for the overhaul was \$1,477,200. Of that amount, \$170,000 was allocated to SUPSHIP 13 prior to the work definition conference to be used for GFM, design, and travel. The work authorized at the conference had an associated cost estimate of \$1,045,760. A 25% growth allowance was added by SUPSHIP 13 to this figure to yield the total COMSERVPAC obligation. After the ROH cancellation, \$147,000 was salvaged by using on another ATF overhaul the tow machine and evaporators purchased with APACHE funds.

Sections III. A through III. E tabulate/discuss in detail the overhaul planning process for APACHE.

III. OVERHAUL DETAILS

A. Planning Process

1. Ideal Vs. Actual Milestones

Table III.A.1 depicts the ideal vs. actual dates of completing the key planning milestones of reference (a). Comments relating to these milestones are given below.

PERA (CSS) contracted ARINC Research Corporation to conduct the pre-overhaul planning for the USS APACHE. The work was performed under Contract N00140-73-D-0074 with the Naval Regional Procurement Office, Philadelphia, Pa., and commenced on 18 January 1973.

The USS APACHE was part of the Integral Operating Unit (IOU) which included WHITE SANDS (AGDS-1) and TRIESTE II (DSV-1), under the command of COMSUBDEVGRU ONE. Due to the ship's operating schedule, the orderly progression of milestones could not be followed.

At the time the above contract was let, the ship was scheduled for an overhaul from 1 November 73 until 1 February 74 at SUPSHIP 11. In July, the overhaul schedule was shifted to SUPSHIP 13 with a 7 January 74 start. During the period July to October, the overhaul start was advanced to 19 November 73, returned to 7 January, and then changed to 15 February through 15 June 1974. The number and frequency of the above changes had a significant effect on the planning process.

A POT/I RAV was scheduled with DATC for the period 30 July - 10 Aug 1973. The ship's operating schedule prevented this from occurring. However, it is felt that adequate work requests were received from the ship for all items that were to be subject to a POT/I. An electronics POT/I was conducted by NAVELEX in late November, and another

inspection was conducted by SUPSHIP 13 in early December.

Manufacturer technical representatives inspected the tow machine and gyro.

The initial work package was received on 27 August. The ship had been on an operational assignment for several weeks, which prevented earlier submission of the package. The entire industrial work package was submitted to SUPSHIP 13 on 31 October. This was an acceptable date to them for an ROH start on 15 February 1974.

Personnel from SUPSHIP 13 conducted a shipcheck in early December. The work definition conference was held on 14 December, with representatives of SUPSHIP 13, USS APACHE, COMSERGRU ONE, PERA(CSS), and ARINC Research Corporation present. All the work screened to the industrial activity was approved. The overhaul was subsequently put in a hold status on 18 December 1973, and cancelled on 9 February 1974.

2. Impact

In addition to the problems mentioned above in the context of advanced overhaul planning, a far more serious one, had the overhaul occurred, was the late identification of shipalts and the tasking for the development of first-time Basic Alteration Class Drawings (BACD's).

Specifically:

- (a) The initial NAVSHIPS K-alt authorization message was issued 31 August 1973, 80 days prior to the then-scheduled overhaul start.
- (b) The 180-day letter was issued on 20 September 1973, 60 days prior to the 19 November ROH start.

(c) Ten first-time shipalts for the ATF-67 class were authorized. Drawings for shipalt ATF-226K (Collecting/Holding Tank), were being prepared by M. Rosenblatt & Sons under a NAVSHIPS contract. The planning yard was unable to develop drawings for the remaining nine alterations in time to support the overhaul start, and SUPSHIP 13 was tasked to develop these BACD's. Due to lack of time and manpower, the decision was made to modify MOLALA drawings for APACHE. No BACD's were developed for the ATF-67 Class.

In addition, review of the 180-day letter revealed that several equipments for shipalts ATF-236K (Food Service Line) and ATF-237K (Galley Mods) being supplied required 230 Vdc voltage. Ship's service voltage aboard APACHE was 115 Vdc. SPCC was notified of the error and began to take steps to procure the correct equipment. Some of the existing equipment was then scheduled for overhaul. Due to non-availability of galley equipment, this would have been a major problem had the overhaul taken place.

3. Recommendations

The preoverhaul planning for the USS APACHE (ATF-67) pointed out the need for early identification of authorized shipalts. The planning yard should be tasked to develop BACD's in accordance with the milestones specified in reference (b).

For the 180-day letter to be of value, it must be issued as close to its scheduled issuance date as possible.

Although problems with operational commitments and industrial activity overloads are recognized, steps should be taken to minimize overhaul-activity and schedule changes.

TABLE III.A.1. IDEAL VS. ACTUAL MILESTONES FOR ROH OF USS APACHE (ATF-67) (Sheet 1 of 2)

| Milestone | Milestone Target Date | Contract Target Date | Actual Start | Completion | Remarks |
|--|-----------------------|----------------------|--------------|------------|---|
| PERA Contract Start Date | | | 1/18/73 | | |
| Obtain Historical Data, Review Alt Package | Immed. | Immed. | 1/18/73 | 3/15/73 | CSMP, 3M material history report, shipalt, AERS, INSURV reports, CASREPs. |
| Brief Ship on Overhaul Preparation | Prior to deployment | 4/1/73 | | 4/3/73 | |
| Receive Work Package | Immed | 7/1/73 | 8/27/73 | 10/8/73 | Ship was on extended operation and not available. |
| NavShips Issue Tentative K-Alts, Task First-Time Alt Dwgs | A-10 | 1/1/73 | | 8/31/73 | |
| Screen Work Package, Determine Known Work, Conduct Shipcheck | A-9 to A-6 | 7/1/73 | 8/27/73 | 10/31/73 | Complete work package delivered to SUPSHIP 13 on 31 October. |
| Determine POT/I Requirements | A-6 | 4/8/73 | | 4/15/73 | |
| Conduct POT/I | A-6 to A-3 | 7/30/73 8/10/73 | | | Ship's schedule precluded full POT/I RAV. Electronics POT/I was performed in late November. |
| NavShips Issue 180-Day Letter | A-6 | 5/19/73 | | 9/20/73 | Start 11/19/73 at time of issue. |
| Conduct Work Definition Conference | A-2 | 12/15/73 | | 12/14/73 | |

TABLE III.A.1 (Sheet 2 of 2)

| Milestone | Milestone Target Date | Contract Target Date | Actual Start | Completion | Remarks |
|-----------------------|-----------------------|----------------------|--------------|------------|---|
| Overhaul | | 2/15/74- 6/15/74 | | | Overhaul site changed from SS11 to SS13. Overhaul dates changed four times. Overhaul cancelled. |
| Complete Final Report | C+2 | 8/15/74 | | | |

III. B. Work Package

- B-1. Summary Sheet
- B-2. Cost Summary Sheet
- B-3. ALT Summary Sheet
- B-4. TYCOM Repair Package
- B-5. PERA Screening Summary
- B-6. Narrative of Material Condition Prior to ROH

SUMMARY SHEET - USS APACHE (ATF-67)

Scheduled Start Date: 15 Feb 74

Scheduled Completion Date: 15 June 74

*Actual Start Date: Overhaul Cancelled

Actual Completion Date: (Not applicable)

**Overhaul Extended: (Not applicable) Days

*Overhaul Start Date delayed due to: Overhaul put in hold status on 18 December 1973 and cancelled on 9 February 1974.

**Overhaul extended due to: (Not applicable)

COST SUMMARY SHEET - USS APACHE (ATF-67)
(for civilian yard)

| 1. SUMMARY OF OVERHAUL COSTS | <u>NAVSHIPS</u> | <u>COMSERVPAC</u> |
|------------------------------|--------------------|-------------------|
| (a) BUDGET | (\$) 436,119 | 1,477,200 |
| (b) ESTIMATED COST | (\$) Not available | 1,215,760 |
| (c) BID PRICE | (\$) | |
| (d) TOTAL COST | (\$) | |
| (e) GROWTH COST | (\$) | |
| (f) PERCENT GROWTH | | |

2. BREAKDOWN OF ESTIMATED COSTS BY EIC SYSTEM:

| EIC SYSTEM | ESTIMATED COST (\$) | PCT. OF TOTAL | PCT. GROWTH EST/ACT |
|-----------------|---------------------|---------------|---------------------|
| 1000* | 240,850 | 19.8 | N/A |
| 3000 | 24,000 | 2.0 | |
| 4000 | 25,500 | 2.1 | |
| 8000 | 0 | 0 | |
| A000* | 103,650 | 8.5 | |
| C000* | 184,020 | 15.1 | |
| G000 | 0 | 0 | |
| L000 | 14,100 | 1.2 | |
| M000 | 20,400 | 1.7 | |
| N000 | 1,900 | 0.2 | |
| P000 | 2,600 | 0.2 | |
| Q000 | 20,970 | 1.7 | |
| R000 | 1,250 | 0.1 | |
| T000* | 448,880 | 36.9 | |
| U000* | 106,500 | 8.8 | |
| W000 | 0 | 0 | |
| Y000 | 0 | 0 | |
| TOTALS** | 1,194,620 | 98.3 | |

*Further broken down to subsystem level in para. 3. **Difference between totals and (b) above represent design and travel expenditures.

3. BREAKDOWN OF ESTIMATED COSTS BY EIC SUBSYSTEM:

| EIC SUBSYSTEM | ESTIMATED COST (\$) | PCT. OF TOTAL | PCT. GROWTH EST/ACT |
|---------------|---------------------|---------------|---------------------|
| 1100 | 2,500 | 0.2 | N/A |
| 1600 | 8,350 | 0.7 | |
| 1A00 | 12,600 | 1.0 | |
| 1C00 | 217,400 | 17.9 | |
| 1000 | 240,850 | 19.8 | |
| A000 | 50,000 | 4.1 | |
| A300 | 5,000 | 0.4 | |
| A500 | 11,600 | 0.9 | |
| A700 | 8,150 | 0.7 | |
| A900 | 19,500 | 1.6 | |
| AB00 | 9,400 | 0.8 | |
| A000 | 103,650 | 8.5 | |
| C100 | 70,820 | 5.8 | |
| C300 | 6,050 | 0.5 | |
| C400 | 22,150 | 1.8 | |
| C600 | 6,400 | 0.5 | |
| C700 | 12,900 | 1.1 | |
| C800 | 3,200 | 0.3 | |
| CB00 | 29,500 | 2.4 | |
| CC00 | 27,000 | 2.2 | |
| CE00 | 6,000 | 0.5 | |
| C000 | 184,020 | 15.1 | |
| T100 | 30,800 | 2.5 | |
| T300 | 24,250 | 2.0 | |
| T400 | 5,700 | 0.5 | |
| T500 | 17,050 | 1.4 | |
| T700 | 20,550 | 1.7 | |
| T800 | 47,540 | 3.9 | |
| TB00 | 18,000 | 1.5 | |
| TC00 | 7,000 | 0.6 | |

| EIC SUBSYSTEM | ESTIMATED COST (\$) | PCT. OF TOTAL | PCT. GROWTH EST/ACT |
|------------------|------------------------|------------------|------------------------|
| TD00 | 7,450 | 0.6 | N/A |
| TF00 | 5,430 | 0.4 | |
| TH00 | 12,000 | 1.0 | |
| TK00 | 57,600 | 4.7 | |
| TL00 | 16,850 | 1.4 | |
| TM00 | 171,660 | 14.1 | |
| TS00 | 7,000 | 0.6 | |
| T000 | 448,880 | 36.9 | |
| U500 | 2,000 | 0.2 | |
| U600 | 2,300 | 0.2 | |
| U700 | 33,000 | 2.7 | |
| U800 | 10,500 | 0.9 | |
| UF00 | 42,000 | 3.4 | |
| UG00 | 2,500 | 0.2 | |
| UH00 | 5,000 | 0.4 | |
| UJ00 | 9,200 | 0.8 | |
| U000 | 106,500 | 8.8 | |

ALT Summary Sheet - USS APACHE (ATF-67) (Sheet 1 of 3)

| SHIP ALT # | FMP EST (\$) | NAVSHIPS EST (\$) | SUPSHIP EST (\$) | ACT COST (\$) | REMARKS |
|--|--------------|-------------------|------------------|---------------|---|
| ATF-205K | 15,805 | 15,646 | | | Partial to complete |
| INSTALL VHF/UHF SECURE VOICE | | | | | |
| ATF-B212K | 11,554 | 11,438 | | | |
| GENERAL WEIGHT & MOMENT COMPENSATION | | | | | |
| ATF-216K | 87,200 | 86,328 | | | SUPSHIP estimates for K-altS were not made** |
| INSTALL MACH SPACE AFFP/PKP FIRE FIGHTING SYSTEM | | | | | |
| ATF-226K | 150,093* | 110,880 | | | Partial system |
| P/A SEWAGE CHT | | | | | |
| ATF-227K | 10,573 | 10,467 | | | |
| P/A BILGE RISER PUMP SYSTEM | | | | | |
| ATF-229K | 78,698 | 77,911 | | | |
| P/A TANK LEVEL INDICATORS | | | | | |
| ATF-232K | 2,071 | 2,050 | | | |
| P/A BILGE HIGH LEVEL ALARM | | | | | |
| ATF-236K | 21,037 | 20,827 | | | |
| H/I FOOD SERVICE | | | | | |
| ATF-237K | 47,306 | 46,833 | | | |
| H/I GALLEY MODS | | | | | |
| ATF-243K | 54,282 | 53,739 | | | |
| H/I SAN SPACE VENT & SHEATH | | | | | |
| ATF-208D | | | 5,400 | | |
| INSTALL DUAL TASK LIGHTS | | | | | |

*FMP estimate based on complete installation; **This comment applies to all K-altS.

ALT Summary Sheet - USS APACHE (ATF-67) (Sheet 2 of 3)

| SHIP ALT # | FMP EST (\$) | NAVSHIPS EST (\$) | SUPSHIP EST (\$) | ACT COST (\$) | REMARKS |
|-----------------------|-----------------|----------------------|---------------------|------------------|------------------------------------|
| ATF-209D | | | 2,400 | | |
| | | | | | |
| ATF-217D | | | 1,100 | | |
| | | | | | |
| ATF-246D | | | 13,550 | | |
| | | | | | |
| ATF-256D | | | 40,000 | | |
| | | | | | |
| ATF-242F | | | 1,400 | | |
| | | | | | |
| (No Ship- alt no.) | | | 100,000 | | PERA(CSS) 030008Z Nov 73 refers |
| AER ATF-71 | | | 2,200 | | |
| | | | | | |
| AER ATF-64 | | | 4,600 | | |
| | | | | | |
| AER ATF-76 | | | 500 | | |
| | | | | | |
| AER ATF-84 | | | 50,000 | | |

ALT Summary Sheet - USS APACHE (ATF-67) (Sheet 3 of 3)

| SHIP ALT # | FMP EST (\$) | NAVSHIPS EST (\$) | SUPSHIP EST (\$) | ACT COST (\$) | REMARKS |
|----------------|-----------------|----------------------|---------------------|------------------|---------|
| AER ATF-85 | | | 57,000 | | |
| AER ATF-89 | | | 1,800 | | |
| AER ATF-96 | | | 7,500 | | |
| AER ATF-101 | | | 2,500 | | |
| AER ATF-95 | | | 5,700 | | |

TYCOM REPAIR PACKAGE - USS APACHE (ATF-67)

| | <u>No.</u> | <u>Pct</u> |
|---|------------|------------|
| 1. Total Work Requests Screened | 584 | |
| Total Automated Work Requests | 257 | 44.0 |
| 2. (a) Number of Work Requests Deferred | 19 | 3.3 |
| (b) Number of Work Requests Disapproved | 58 | 9.9 |
| (c) Number of Work Requests Duplicated, Etc. | 118 | 20.2 |
| (d) Number of Work Requests Approved | 389 | 66.6 |
| 3. Total Work Requests Approved | 389 | |
| Number Work Requests Screened: Priority One (1) | 19 | 4.9 |
| Number Work Requests Screened: Priority Two (2) | 122 | 31.4 |
| Number Work Requests Screened: Priority Three (3) | 219 | 56.3 |
| TOTAL | <hr/> 360 | <hr/> 92.6 |
| B. Number of Approved Work Requests by Type Work | 389 | 100.0 |
| Repair (including Remove, Replace, Manufacture, Drydock, POT/I and Calibration) | 347 | 89.2 |
| Ship Alteration | 16 | 4.2 |
| TYCOM AER | 13 | 3.3 |
| Habitability | 7 | 1.8 |
| Routines | 6 | 1.5 |
| C. Number of Approved Work Requests Insurance Items: | | |
| As Insurance items were identified, the ship was advised to include them in the work package. Separate identity was not maintained. | | |
| D. Number of Approved Work Requests Accomplished | NA | NA |
| Number of Approved Work Requests not Accomplished and not entered in CSMP | NA | NA |

PERA SCREENING SUMMARY, USS APPACHE (ATF-67)

| | <u>PERA</u> | <u>TYCOM</u> |
|--|-------------|--------------|
| 1. (a) NUMBER WORK REQUESTS SCREENED ONE (1) | 192 | See Comments |
| (b) NUMBER WORK REQUESTS SCREENED TWO (2) | 79 | |
| (c) NUMBER WORK REQUESTS SCREENED THREE (3) | 118 | |
| (d) NUMBER WORK REQUESTS SCREENED FOUR (4) | 0 | |
| (e) NUMBER WORK REQUESTS SCREENED FIVE (5) | 0 | |
| (f) NUMBER WORK REQUESTS SCREENED SIX (6) | 0 | |
| (g) NUMBER WORK REQUESTS SCREENED SEVEN (7) | 0 | |
| (h) NUMBER WORK REQUESTS SCREENED EIGHT (8) | 19 | |
| (i) NUMBER WORK REQUESTS SCREENED NINE (9) | 58 | |
| (j) NUMBER WORK REQUESTS SCREENED ZERO (0) | 118 | |
| (*) | | |

2. TOTAL NUMBER WORK REQUESTS TYCOM CONCURRED See Comments

TOTAL NUMBER WORK REQUESTS TYCOM SCREENED OTHERWISE

See Comments

3. See Comments % AGREEMENT IN SCREENING.

4. ANALYSIS OF SCREENING DIFFERENCES:

(Not applicable)

5. COMMENTS/RECOMMENDATIONS

Screening actions were reviewed with the overhaul manager prior to being finalized. No distinction was made between PERA and TYCOM screening actions. It can be stated generally that the overhaul manager concurred with the recommended screening.

(*)LEGEND: SCREENING ACTION (APPENDIX 17 OPNAV 43P23)

1. SHIPYARD ACCOMPLISH
2. TENDER OR REPAIR SHIP ACCOMPLISH
3. SHIPS FORCE - (TENDER OR REPAIR SHIP/YARD) ASSIST
4. ACCOMPLISH AS ALTERATION EQUIVALENT TO A REPAIR
5. SHIP TO SHOP
6. ACCOMPLISH WITH MODIFICATION
7. YARD OPEN INSPECT -- ADVISE TYCOM -- PROCEED WITH MINIMUM REPAIRS
8. DEFERRED
9. DISAPPROVED
0. OTHER - SPECIFY IN REMARKS

NARRATIVE OF MATERIAL CONDITION PRIOR TO ROH (subjective overview)

The USS APACHE was the oldest fleet tug in the U.S. Navy, and had been out of overhaul for more than three years while this overhaul planning process was underway. Indicative of the ship's condition were the following:

- (a) The main propulsion engines all had more than 5000 operating hours since their last overhaul.
- (b) Considerable difficulty had been experienced with the ship's service generator engines.
- (c) Most of the auxiliary pumps, motors and controllers, switchboards, reefers, steering gear, deck machinery, and many electronic equipments, required a complete overhaul.
- (d) The tow machine was in such poor condition that it was a mission-degrading INSURV discrepancy.
- (e) The ship did not have a twinned-agent firefighting system in its machinery spaces.
- (f) No pollution abatement shipalts had been completed.
- (g) The ship did not meet current habitability standards, and in addition had a great deal of combustibile sheathing and carpeting aboard.

III. C. Deferred Work/Long Range Maintenance Actions

(Not applicable)

III. D. Recommendations

1. Ship: None
2. Class: The ATF-67 class of ships is very limited in ship's service power, having a total of only 300 kilowatts available. This should have been the subject of a shipalt for the USS APACHE. However, it is very doubtful that any ships of the class will be active long enough to warrant changing the power configuration.
3. Standardized Work Packages: The experience gained in the preparation of the work package for the USS MOLALA (ATF-106) was utilized in preparation of the work package for the USS APACHE. The latter work package has been added as another data source in the continuing development of a standard ATF ROH workbook.
4. PERA:
 - (a) Late identification of authorized shipalts and late tasking of development of BACD's affected the preoverhaul planning procedures. PERA should continue to take an active role in preventing this from recurring.
 - (b) It is recommended that NMMFO and SOAP be added to the distribution list of the FILS letter.

III. E. Evaluation/Usefulness

1. PERA products to ship/industrial activity

- (a) SSDI. The SSDI was found very useful by the ship and enabled them to assemble a complete work package.
- (b) FILS. The information provided by the FILS program was not utilized by the industrial activity.
- (c) IWP. The IWP was utilized by the ship and the type commander as a record of screening action and as a tool in updating the CSMP.
- (d) POT/I Plan. The ship's operating schedule precluded performing the POT/I's originally planned. The electronics POT/I was very beneficial, as it identified not only industrial work items but tender/DATC and ship's force work as well.



USS QUAPAW (ATF-110)
POST OVERHAUL ANALYSIS REPORT
OVERHAUL DATES
1 August 1973 - 1 February 1974

USS QUAPAW (ATF-110)
POST OVERHAUL ANALYSIS REPORT

Approved: _____

Date: _____

Distribution:

PERA (CSS)
COMSERVPAC
COMSERVGRU FIVE
USS QUAPAW (ATF-110)

Prepared by
ARINC RESEARCH CORPORATION
Ships and Ordnance Division
Honolulu Support Office
Contract N00140-73-D-0074-0010

Publication 1020-01-1-1303B

USS QUAPAW (ATF-110)
POST OVERHAUL ANALYSIS REPORT

TABLE OF CONTENTS

- I. General Information - Preface
- II. Management Summary
 - A. Authorized vs. Accomplished Work
 - B. Planned vs. Actual Completion Times
 - C. Planned vs. Actual Completion Costs
 - D. Major Configuration Changes
 - E. Follow-on Work Required
- III. Overhaul Details
 - A. Planning Process
 - A.1 Ideal vs. Actual Milestones
 - (a) Advance Overhaul Planning
 - (b) Tradeoff Conferences
 - (c) Overhaul Phase
 - (d) Postoverhaul Phase
 - A.2 Impact
 - A.3 Recommendations
 - B. Work Package
 - B.1 Summary Sheet
 - B.2 Cost Summary Sheet
 - B.3 Alteration Summary Sheet
 - B.4 Type Commander Repair Package
 - B.5 PERA Screening Summary
 - B.6 Major Alterations
 - B.7 Major Repair Items
 - B.8 Preoverhaul Material Condition
 - B.9 Postoverhaul Material Condition
 - C. Deferred Work/Long Range Maintenance Items

D. Recommendations

D.1 Ship

D.2 Class

D.3 Standardized ROH 2K Packages

D.4 PERA(CSS)

E. Evaluation/Usefulness

E.1 Overhaul Products to Ship Industrial Activity

(a) Ship System Definition and Index (SSDI)

(b) Integrated Work Package Summary Reports

(c) Preoverhaul Test and Inspection Reports

(d) Tradeoff Analysis

(e) LLT Material and FILS Reports

(f) Periodic Overhaul Planning Status Reports

E.2 Resource Effectiveness

I. General Information and Preface

General Information:

Ref: (a) Contract N00140-73-D-0074.

(b) PERA(CSS) Milestone Charts, dated August 1972; forwarded by
PERA(CSS) Letter Ser. 1800-262 of 4 May 1973.

Preface:

The USS QUAPAW (ATF-110) was overhauled from 1 August 1973 through 1 February 1974 under the direction of the Supervisor of Shipbuilding, Pearl Harbor Naval Shipyard. The overhaul was accomplished in two phases: a Drydock Phase at Dillingham Shipyard and a Topside Phase at Pacific Marine Shipyard, both in Honolulu, Hawaii.

In planning the overhaul of USS QUAPAW, PERA(CSS), acting as TYCOM and NAVSHIPS maintenance management agent, established advance planning milestones (references a and b), which commenced six months prior to the overhaul start date. The goal of the planning effort has been to identify, in advance, potential and existing problem areas; and provide the detailed preoverhaul guidance, planning, and coordination necessary to achieve a successful yard overhaul. The purpose of this report is to evaluate the management judgments and decisions associated with the planning effort during this period.

II. Management Summary

References (a) and (b) list the management milestones used in planning the overhaul of USS QUAPAW. Deviations from the milestones which affected the overhaul, and nonprogrammed factors that contributed to the final overhaul outcome, are discussed below.

A. Authorized vs. Accomplished Work

The repair portion of the QUAPAW work package was essentially completed as authorized. The authorized alteration work package was the controlling factor in the overhaul. When the ship departed the overhaul shipyard, the galley and tank-level indicating system alterations were not complete because all of the required equipment had not been received.

B. Planned vs. Actual Completion Time

The overhaul period was extended 62 days as a result of late receipt of drawings for first time alteration material, and changes required in the collecting/holding tank (CHT) installation.

C. Planned vs. Actual Completion Costs

The SUPSHIP departure report had not been released as of the preparation of this report, so a comparison of the actual vs. planned costs for QUAPAW overhaul cannot be presented herein. A supplement to this report will be prepared and forwarded after receipt of the departure report.

D. Major Configuration Changes

The QUAPAW completed the overhaul with the following major configuration changes:

- (a) New main propulsion diesel engines
- (b) New waste heat evaporators
- (c) New AFFF fire protection system
- (d) New pollution abatement features (including partial CHT)
- (e) New habitability improvements in galley, mess decks, and sanitary spaces
- (f) Improved salvage capability
- (g) Upgraded communication and radar systems.

E. Follow-on Work Required

The major follow-on work still required to complete the QUAPAW overhaul is the installation of missing equipments for the galley improvement and tank level indicating system alterations.

III. Overhaul Details

A. Planning Process

1. Ideal vs. Actual Milestones

Advanced overhaul planning for the USS QUAPAW commenced in January 1973. The overhaul planning procedures used for the QUAPAW overhaul are defined in the COMSERVPAC Overhaul Planning Task Chart, Task Index, and Tasks, dated 15 September 1972; and Combatant Support Ship Overhaul Advance Planning Milestones. These advance planning milestones provide for accomplishment of 53 tasks, of which 36 tasks are PERA action responsibility. The ideal target dates for these tasks range from start of overhaul minus 20 months (A-20), to completion of overhaul plus 2 months (C+2).

With the QUAPAW overhaul scheduled to start 5 July 1973, ARINC Research commenced advance planning for the overhaul at about A-6 months. This made it necessary to compress the time frame of the planning milestones and combine some tasks. All required tasks were completed. Table III.A-1 shows the dates for the accomplishment of the principal milestones for QUAPAW. The following paragraphs summarize the advance planning for the overhaul.

- (a) Advance Overhaul Planning. Overhaul planning was initiated by ARINC Research with a survey of the available maintenance history of the QUAPAW as contained in the Current Ships Maintenance Program (CSMP) and the Maintenance and Material Management (3M) Program Material History Report. Programmed ship alterations (shipalts) and TYCOM alterations were reviewed, along with other pertinent maintenance history documents such as last overhaul records, departure reports, Board of Inspection and Survey (INSURV) reports, and casualty reports (CASREPs).

Concurrent with the review of the QUAPAW's maintenance history, the ship's work request package was reviewed and screened. Before being changed to 5 July 1973, the start date for the QUAPAW overhaul had been 9 April 1973; therefore the ship's work requests had been submitted and had received a preliminary screening by

COMSERVGRU FIVE maintenance personnel. Advance copies of the work requests had been provided to SUPSHIP 14. On completion of screening by ARINC Research, shipyard work requests were delivered to SUPSHIP 14 beginning on 20 March 1973. By mid-April, approximately 80% of the shipyard-accomplish work requests had been delivered.

Preoverhaul Test and Inspection (POT/I) requirements were identified as the work package was screened. These tests and inspections were performed by PHNSY during a two-week RAV from 9-20 April 1973. New work requests resulting from the POT/I were screened to SUPSHIPS for inclusion in the work package, and by mid-May the integrated alteration/repair work package was essentially complete.

NAVSHIPS-funded alterations were initially authorized in November 1972 for the overhaul starting in April 1973. Following the rescheduling of the overhaul to a 5 July 1973 start date, additional alterations were authorized in January 1973 and three first-time habitability improvement alterations were authorized by the Type Commander in May and June 1973.

(b) Tradeoff Conferences. The overhaul tradeoff conference was scheduled by SUPSHIP 14 for 18 May 1973. The overhaul was to be conducted in two phases: a one-month Drydock Phase followed by a Topside Phase. The tradeoff conference for the Drydock Phase was held on 23 May 1973, and for the Topside Phase on 8 Aug 1973. Job specifications and estimates were not available to support an earlier conference for the Topside Phase. The package was still not complete on 8 August because of the late receipt by SUPSHIP of first-time shipalt design packages. As a result of the tradeoff conferences, a work package with an estimated cost of \$1,652,821, including \$354,631 for NAVSHIPS-funded alterations, was authorized. Of this total, \$205,067 was for the Drydock Phase.

(c) Overhaul Phase. ARINC Research's main planning responsibility during the QUAPAW overhaul was monitoring its progress and assisting in the management of SERVGRU resources in light of additional requirements developed during and as a result of the

overhaul. To accomplish this, ARINC Research personnel attended the SUPSHIP weekly progress conferences and provided liaison between the SERVGRU FIVE maintenance staff, SUPSHIP, and the ship.

- (d) Postoverhaul Phase. ARINC Research Corporation's responsibility following completion of the overhaul consisted of analyzing the overhaul records and the preparation of final reports. The final report was delayed because of the late distribution by SUPSHIP of the departure report with return cost data.

2. Impact.

The advance overhaul planning milestones call for early identification of alterations to be accomplished during the overhaul, and early authorization by the planning yard to have first time shipalt drawings developed. For QUAPAW the NAVSHIPS alteration planning message was issued 9 March 1973. Drawings for seven first-time alterations were developed by SUPSHIP/San Diego to support both MOLALA (ATF-106) and QUAPAW as a result of tasking by PHNSY on 30 March. This late start for plan development and the resultant late ordering of material had a direct effect on the start date of overhaul. Plans were still being received after the overhaul started.

3. Recommendations.

As a result of the review of the planning process for QUAPAW as discussed above, the following recommendations are offered.

- (a) Review the advance-planning milestone target dates and determine which should be made more realistic, in light of the QUAPAW overhaul and general overhaul experience.
- (b) Continue to emphasize early submittal of the ship's work package to SUPSHIP to permit development of estimates and specifications to support a work definition conference based on accurate and complete data.
- (c) Reconsider the requirement for postoverhaul reports to contain final cost data. Under present conditions, these data are not available by the milestone date (C+2) for submitting the final report.

- (d) Continue to work toward early definition and firming up of the ship alteration package and the authorization to develop required drawings.
- (e) Increase PERA participation in the overhaul management phase.

TABLE III.A.1. IDEAL VS. ACTUAL MILESTONES FOR ROH OF USS QUAPAW (ATF-110) (Sheet 1 of 2)

| Milestone | Milestone Target Date * | Contract Target Date | Actual Start | Completion | Remarks |
|--|-------------------------|----------------------|--------------|------------|---|
| Contract Start Date | | | 1-18-73 | | |
| Obtain Historical Data, Review Alt Package | Immed. | Immed. | 1-18-73 | 2-15-73 | |
| Receive Ship Work-Request Package | Immed. | Immed. | 1-18-73 | | Ship submitted by letter 12-15-72 for a 9 April ROH. COMSERVGRU FIVE had completed preliminary screening and provided advance copies to SUPSHIP 14. |
| Screen Work Requests, Determine Known Work, Identify LLT Actions | A-9 to A-6 | 2-23-73 | 1-18-73 | 3-19-73 | |
| Brief Ship, Shipcheck Selected Work Items | Immed. | 2-12-73 | 2-12-73 | 3-16-73 | Includes ship's 30-day stand-down period. |
| Determine Preoverhaul Test & Inspection Requirements | A-6 | 2-23-73 | 2-12-73 | 3-6-73 | |
| Submit Screened Work Requests to SERVGRU and SUPSHIP | A-9 to A-6 | 4-6-73 | 3-20-73 | 4-13-73 | Initial work package. Approximately 80% of final package. |
| Receive New Work Requests; Screen, Submit to SERVGRU & SUPSHIP | A-6 | As developed | 3-19-73 | 5-11-73 | Essentially completed package except for late items. |
| Conduct Preoverhaul Tests and Inspections | A-6 to A-3 | 4-9-73 | 4-9-73 | 4-20-73 | |

TABLE III.A.1. (Sheet 2 of 2)

| Milestone | Milestone Target Date * | Contract Target Date | Actual Start | Completion | Remarks |
|---|-------------------------|----------------------|--------------|------------|---|
| Complete Drydock Phase Tradeoff Analysis and Work Definition Conference | A-2 | 5-18-73 | | 5-23-73 | |
| Complete Topside Phase Tradeoff Analysis and Work Definition Conference | A-2 | 5-18-73 | | 8-8-73 | Conference with SERVGRU and Ship's Force held 8-6-73 to review specification. |
| Overhaul - Drydock Phase | A | 7-5-73 8-5-73 | 8-1-73 | 8-30-73 | |
| Overhaul - Topside Phase | A+30 | 8-6-73 11-5-73 | 8-31-73 | 2-1-74 | |
| Complete Final Report | C+2 | 1-4-74 | 2-1-74 | | |

*COMSERVPAC overhaul planning task index and task dated 15 September 1972.

III. B. Work Package

- B.1 Summary Sheet
- B.2 Cost Summary Sheet
- B.3 Alteration Summary Sheet
- B.4 TYCOM Repair Package
- B.5 PERA Screening Summary
- B.6 Narrative of Major Alteration Items
- B.7 Narrative of Major Repair Items
- B.8 Narrative of Material Condition Prior to ROH
- B.9 Narrative of Material Condition After ROH

B.1 Summary Sheet — USS QUAPAW (ATF-110)

DRYDOCK PHASE

Scheduled Start Date: 5 July 73 Scheduled Completion Date: 30 Aug 73

Actual Start Date*: 1 Aug 73 Actual Completion Date: 30 Aug 73

TOPSIDE PHASE

Scheduled Start Date: 31 Aug 73 Scheduled Completion Date: 30 Nov 73

Actual Start Date: 31 Aug 73 Actual Completion Date: 1 Feb 74

Overhaul Extended 62 days**

*The QUAPAW overhaul was scheduled for the period 5 July 73 to 5 November 73, with the Drydock Phase scheduled for the first month. In June 73, SUPSHIP 14 requested the availability be changed to 6 August to 30 November 73, based on an estimated delivery date of 25 August 73 for replacement main engines and late receipt of first-time alteration drawings. This change in availability was authorized. To fit the availability of the drydock, the Drydock Phase actually started on 1 August 73.

**The Topside Phase of the QUAPAW overhaul was extended 62 days because of late receipt of 1) a main engine to replace one of the original set damaged in shipment, 2) first-time alteration drawings, 3) tank level indicating equipment, and 4) galley equipment; and extensive changes in CHT installation.

SIGNIFICANT CAPABILITY CHANGES

- a. Upgraded communications/radar
- b. Pollution abatement features (including partial CHT)
- c. Habitability improvements: galley, mess decks, and sanitary spaces
- d. New main propulsion engines
- e. New waste heat evaporators
- f. Improved salvage capability
- g. Machinery space AFFF installation
- h. New 200-kW S.S. generator diesel engine

B.2 Cost Summary Sheet — USS QUAPAW (ATF-110) (for civilian yard)

| 1. SUMMARY OF OVERHAUL COSTS | <u>K-ALT</u> | <u>REPAIR</u> |
|------------------------------|---------------------------|----------------------|
| (a) BUDGET | (\$) <u>Not available</u> | <u>Not Available</u> |
| (b) ESTIMATED COST | (\$) <u>354,631</u> | <u>1,298,190</u> |
| (c) BID PRICE | (\$) <u>164,474*</u> | <u>972,722</u> |
| (d) TOTAL COST | (\$) <u>Not available</u> | <u>Not available</u> |
| (e) GROWTH COST | (\$) _____ | _____ |
| (f) PERCENT GROWTH | _____ | _____ |

*The complete alteration package, as estimated, was not included in the initial bid specifications.

2. BREAKDOWN OF OVERHAUL COSTS BY EIC CATEGORY

| EIC | | EST. COST (\$) | | PCT. TOTAL COST | | PCT. GROWTH | |
|--------|---------|----------------|---------|-----------------|---------|-----------------|---------|
| SYSTEM | SUBSYS. | SYSTEM | SUBSYS. | SYSTEM | SUBSYS. | SYSTEM | SUBSYS. |
| 1000 | | 248,676 | | 15.8 | | (Not Available) | |
| | 1A00 | | 1,942 | | 0.1 | | |
| | 1B00 | | 114,680 | | 7.3 | | |
| | 1C00 | | 49,946 | | 3.2 | | |
| | 1100 | | 14,003 | | 0.9 | | |
| | 1300 | | 5,000 | | 0.3 | | |
| | 1500 | | 4,842 | | 0.3 | | |
| | 1600 | | 2,433 | | 0.2 | | |
| | 1700 | | 50,257 | | 3.2 | | |
| | 1800 | | 3,471 | | 0.2 | | |
| | 1900 | | 2,102 | | 0.1 | | |
| 3000 | | 79,868 | | 5.1 | | | |
| | 3100 | | 78,101 | | 5.0 | | |
| | 3300 | | 1,767 | | 0.1 | | |

(Cont.)

2. BREAKDOWN OF OVERHAUL COSTS BY EIC CATEGORY (Continued)

| EIC | | EST. COST (\$) | | PCT. TOTAL COST | | PCT. GROWTH | |
|--------|---------|----------------|---------|-----------------|---------|-------------|---------|
| SYSTEM | SUBSYS. | SYSTEM | SUBSYS. | SYSTEM | SUBSYS. | SYSTEM | SUBSYS. |
| 4000 | | 29,845 | | 1.9 | | | |
| | 4100 | | 16,390 | | 1.0 | | |
| | 4300 | | 4,467 | | 0.3 | | |
| | 4400 | | 1,055 | | 0.1 | | |
| | 4700 | | 7,933 | | 0.5 | | |
| A000 | | 137,964 | | 8.8 | | | |
| | AA00 | | 950 | | 0.1 | | |
| | AB00 | | 4,006 | | 0.3 | | |
| | AD00 | | 6,985 | | 0.4 | | |
| | A000 | | 23,501 | | 1.5 | | |
| | A100 | | 11,740 | | 0.8 | | |
| | A600 | | 556 | | - | | |
| | A700 | | 6,920 | | 0.4 | | |
| | A800 | | 3,516 | | 0.2 | | |
| | A900 | | 79,790 | | 5.1 | | |
| C000 | | 324,198 | | 20.6 | | | |
| | CB00 | | 45,964 | | 3.0 | | |
| | CC00 | | 43,045 | | 2.7 | | |
| | C100 | | 196,812 | | 12.5 | | |
| | C400 | | 23,799 | | 1.5 | | |
| | C700 | | 13,578 | | 0.9 | | |
| G000 | | 0 | | 0 | | | |
| L000 | | 11,022 | | 0.7 | | | |
| | LB00 | | 6,875 | | 0.4 | | |
| | LH00 | | 1,257 | | 0.1 | | |
| | LJ00 | | 1,350 | | 0.1 | | |
| | L100 | | 1,540 | | 0.1 | | |
| M000 | | 9,932 | | 0.6 | | | |
| | M500 | | 8,180 | | 0.5 | | |
| | M600 | | 1,752 | | 0.1 | | |
| N000 | | 805 | | 0.1 | | | |
| | N400 | | 805 | | 0.1 | | |

2. BREAKDOWN OF OVERHAUL COSTS BY EIC CATEGORY (Continued)

| EIC | | EST. COST (\$) | | PCT. TOTAL COST | | PCT. GROWTH | |
|--------|---------|----------------|---------|-----------------|---------|-------------|---------|
| SYSTEM | SUBSYS. | SYSTEM | SUBSYS. | SYSTEM | SUBSYS. | SYSTEM | SUBSYS. |
| P000 | | 9,003 | | 0.6 | | | |
| | P100 | | 6,161 | | 0.4 | | |
| | P600 | | 2,842 | | 0.2 | | |
| Q000 | | 39,728 | | 2.6 | | | |
| | QB00 | | 4,695 | | 0.3 | | |
| | QD00 | | 6,520 | | 0.4 | | |
| | QE00 | | 10,664 | | 0.7 | | |
| | Q000 | | 4,351 | | 0.3 | | |
| | Q300 | | 13,498 | | 0.9 | | |
| R000 | | 1,278 | | 0.1 | | | |
| | R500 | | 1,278 | | 0.1 | | |
| T000 | | 448,008 | | 28.4 | | | |
| | TA00 | | 4,995 | | 0.3 | | |
| | TB00 | | 6,823 | | 0.4 | | |
| | TC00 | | 0 | | 0 | | |
| | TD00 | | 4,284 | | 0.3 | | |
| | TF00 | | 16,368 | | 1.0 | | |
| | TK00 | | 120,295 | | 7.7 | | |
| | TL00 | | 12,456 | | 0.8 | | |
| | TM00 | | 56,783 | | 3.6 | | |
| | TS00 | | 6,361 | | 0.4 | | |
| | TT00 | | 0 | | 0 | | |
| | T100 | | 7,024 | | 0.4 | | |
| | T300 | | 72,106 | | 4.6 | | |
| | T400 | | 5,019 | | 0.3 | | |
| | T500 | | 6,795 | | 0.4 | | |
| | T700 | | 74,419 | | 4.7 | | |
| | T800 | | 54,280 | | 3.5 | | |
| | T900 | | 0 | | - | | |

2. BREAKDOWN OF OVERHAUL COSTS BY EIC CATEGORY (Continued)

| EIC | | EST. COST (\$) | | PCT. TOTAL COST | | PCT. GROWTH | |
|---|---------|----------------|---------|-----------------|---------|-------------|---------|
| SYSTEM | SUBSYS. | SYSTEM | SUBSYS. | SYSTEM | SUBSYS. | SYSTEM | SUBSYS. |
| U000 | | 222,367 | | 14.2 | | | |
| | UA00 | | 42,210 | | 2.7 | | |
| | UC00 | | 22,127 | | 1.4 | | |
| | UF00 | | 84,980 | | 5.4 | | |
| | UH00 | | 10,437 | | 0.7 | | |
| | UJ00 | | 16,967 | | 1.1 | | |
| | U000 | | 31,808 | | 2.0 | | |
| | U400 | | 659 | | 0.1 | | |
| | U500 | | 2,101 | | 0.1 | | |
| | U600 | | 900 | | 0.1 | | |
| | U800 | | 10,178 | | 0.6 | | |
| W000 | | 0 | | | 0 | | |
| Y000 | | 7,278 | | 0.5 | | | |
| | YA00 | | 1,795 | | 0.1 | | |
| | YC00 | | 5,483 | | 0.4 | | |
| TOTAL = \$1,569,972* | | | | | | | |
| *This total differs from summary sheet total because contingency is not included, and some late estimates are included. | | | | | | | |

3. COST AVOIDANCE SUMMARY.

(a) Screening Actions. For the QUAPAW overhaul, 780 work requests were received from the ship and screened by PERA. These work requests had been screened by the ship as follows:

- (1) Shipyard Accomplish: 57%
- (2) Tender Accomplish: 3%
- (3) Ship's Force Accomplish: 37%
- (4) Not Specified: 3%

As a result of screening by PERA and with the approval of the overhaul manager, the final screening of these work requests for the overhaul was:

- (1) Shipyard Accomplish: 39%
- (2) Tender Accomplish: 6%

- (3) Ship's Force Accomplish: 38%
- (4) Deferred 3%
- (5) Disapproved 4%
- (6) Miscellaneous 10%

The 17% reduction in the size of the work package (deferred, disapproved and miscellaneous screening) was realized through detailed shipchecks, discussions with ship personnel, and analysis of the work requested; and represents a cost avoidance to the type commander. In addition to reducing the size of the work package, the remaining work requests, particularly those screened to SUPSHIPS, were edited to ensure that the work requested was accurately described and supported by reference material such as plans, sketches, and APL's. It should be noted that the ship was more realistic in screening work for its accomplishment than is normally the case.

Although an accurate cost estimate cannot be placed on all these actions, cost avoidance was realized in the following areas:

- (1) Work requested and not authorized
- (2) Reduced SUPSHIP manhours required to:
 - a. Prepare estimates and job specifications
 - b. Research reference material
 - c. Shipcheck
- (3) Reduced manhours required by the overhaul manager to:
 - a. Screen total work package
 - b. Research incomplete work requests
 - c. Research past maintenance history

Based on the ROH estimates for QUAPAW, the cost of a repair work item (not including contingency allowance) averaged approximately \$3,900 per item. Using this figure, the 142 items originally screened by ship's force for shipyard work but not authorized would represent \$553,800 in saved costs.

- (b) Tradeoff Analysis. In preparation for the work definition conference, a tradeoff analysis was performed. The following work items were deleted from the shipyard work package with the overhaul manager's approval.

3(b). QUAPAW ITEMS DELETED DURING TRADEOFF ANALYSIS

| EIC | JOB IDENT NUMBER | JOB DESCRIPTION | ESTIMATED COST (\$) |
|--------------------------------------|------------------|----------------------------------|---------------------|
| 1108 | DA01/0238 | Renew Jackstaff Stowage Bracket | 282 |
| 1403 | DA01/0236 | Fab Aluminum Sea Ladder | 2,857 |
| 1503 | OE01/0836 | Inst Sliding Door; Trans. Room | 2,088 |
| 1601 | XX02/0279 | Dk Cover, Wardroom Pantry | 2,219 |
| 1601 | XX02/0297 | Renew Deck Covering | 1,231 |
| 1601 | XX02/0077 | Deck Covering; Scullery & Galley | 5,225 |
| 191N | OE01/0827 | Inst. Workbench/Storage Locker | 4,669 |
| 1A01 | XX02/0209 | Inst. Coaming; Washing Machine | 497 |
| 1B03 | EA01/0129 | Renew Dishwashing Machine | 1,446 |
| 1C00 | ON01/0558 | Tile & Sheathing, Pilothouse | 10,707 |
| 1C00 | 699-10 | Delete Certain Requirements | 1,976 |
| 1C01 | XX02/0275 | Install Transom Berth | 5,047 |
| 1C03 | OE01/0837 | Remove Deck, Radio Room | 448 |
| GBV6 | WG01/0138 | Replace Gun Mount | 4,102 |
| T300 | 599-21 | Delete Certain Vents | 2,000 |
| T800 | 599-23 | Delete Certain Motors/Cont. | 7,000 |
| T801 | ER01/0220 | Insp. P-250 Flywheels | 55 |
| TB00 | 599-19 | Delete One Pump Repair | 2,000 |
| TC06 | XX02/0176 | DK Drain Steam Conn | 572 |
| U000 | Routine | Office Space | 800 |
| UF00 | DA01/0198 | SB/Preserve Topside | 29,250 |
| UF00 | OE01/0831 | Paint Radio Central | 6,305 |
| UF00 | ON01/0507 | Paint Chart House | 4,129 |
| Y30V | DA01/0223 | Replace Canopy | 3,589 |
| TOTAL | | | 101,392 |
| Note: Cost estimates are by SUPSHIP. | | | |

B.3 Alt Summary Sheet - USS QUAPAW (ATF-110) (Sheet 1 of 5)

| SHIP ALT # | FMP EST (\$) | NAVSHIPS EST (\$) | SUPSHIP EST (\$) | ACTUAL COST (\$) | REMARKS |
|------------|--------------|-------------------|------------------|------------------|--|
| ATF-185K | 26,160 | 26,260 | 2,476 | | |
| ATF-194K | 15,805 | | | | Late authorization |
| ATF-196K | 37,823 | | | | |
| ATF-205K | 15,805 | 16,160 | 2,949 | | Late authorization; provide plans only |
| ATF-206K | 18,966 | 19,190 | 6,161 | | |
| ATF-211K | 36,733 | 37,370 | 3,539 | | |
| ATF-212K | 11,554 | 12,120 | | | |
| ATF-216K | 87,200 | 87,870 | 29,114 | | |
| ATF-266K | 150,093 | 112,896 | 72,755 | | Partial; pumps not installed |

Alt Summary Sheet - USS QUAPAW (ATF-110) (Sheet 2 of 5)

| SHIP ALT # | FMP EST (\$) | NAVSHIPS EST (\$) | SUPSHIP EST (\$) | ACTUAL COST (\$) | REMARKS |
|-------------------------------------|--------------|-------------------|------------------|------------------|---------|
| ATF-227K | 10,573 | 11,110 | 4,547 | | |
| P/A INST BILGE WTR DISCHARGE RISER | | | | | |
| ATF-229K | 78,698 | 79,790 | 79,790 | | |
| P/A INST FUEL TANK LEVEL IND SYSTEM | | | | | |
| ATF-232K | 2,071 | 2,020 | 4,186 | | |
| P/A BILGE FLOODING ALARM CKT FD | | | | | |
| ATF-236K | 21,037 | 21,210 | 21,210 | | |
| H/I FOOD SERVICE LINE MODS | | | | | |
| ATF-237K | 47,306 | 47,470 | 47,470 | | |
| H/I CREW GALLEY MODS | | | | | |
| ATF-243K | 54,282 | 54,540 | 54,540 | | |
| H/I SAN SPACES VENT & SHEATH | | | | | |
| ATF-244K | 14,061 | 14,140 | | | |
| H/I SAN SPACES REL REL HW HTR | | | | | |
| ATF-188K | 38,150 | 10,080 | | | |
| INST MF, HF AND MF/HF SSB COMM EQPT | | | | | |
| ATF-203K | | | 4,684 | | |
| NONSEC TTY | | | | | |
| K-ALT TOTAL* | | | | | |
| ATF-208D | | | 1,350 | | |
| INSTALL DUAL TASK LIGHT ARRAY | | | | | |

Partial; receivers not installed

Partial to complete

Alt Summary Sheet - USS QUAPAW (ATF-110) (Sheet 3 of 5)

| SHIP ALT # | FMP EST (\$) | NAVSHIPS EST (\$) | SUPSHIP EST (\$) | ACTUAL COST (\$) | REMARKS |
|--------------|--------------|-------------------|------------------|------------------|--|
| ATF-209D | | | 1,257 | | |
| ATF-210D | | | N/A | | Not accomplished; new non-standard compressor installed |
| ATF-213D | | | 196,812 | | Partial - main eng only. D. gen. sets not available. New 200 kW gen. eng. installed. |
| ATF-217D | | | 2,026 | | |
| ATF-246D | | | 19,000 | | |
| ATF-256D | | | 46,000 | | |
| D-ALT TOTAL* | | | | | |
| ATF-207F | | | 3,919 | | |
| ATF-242F | | | 640 | | |
| F-ALT TOTAL | | | 4,559 | | |

Alt Summary Sheet - USS QUAPAW (ATF-110) (Sheet 4 of 5)

| SHIP ALT # | FMP EST (\$) | NAVSHIPS EST (\$) | SUPSHIP EST (\$) | ACTUAL COST (\$) | REMARKS |
|------------|--------------|-------------------|------------------|------------------|--------------------------------|
| ATF AER-75 | | | N/A | | Included with boiler repairs |
| ATF AER-76 | | | 2,441 | | |
| ATF AER-84 | | | 23,501 | | |
| ATF AER-85 | | | 117,285 | | |
| ATF AER-86 | | | | | |
| ATF AER-89 | | | 12,144 | | |
| ATF AER-91 | | | N/A | | Ship force accomp est 18 MD |
| ATF AER-94 | | | | | |
| ATF AER-95 | | | 5,019 | | |
| ATF AER-97 | | | 3,987 | | |

Alt Summary Sheet - USS QUAPAW (ATF-110) (Sheet 5 of 5)

| SHIP ALT # | FMP EST (\$) | NAVSHIPS EST (\$) | SUPSHIP EST (\$) | ACTUAL COST (\$) | REMARKS |
|---|-----------------|----------------------|---------------------|---------------------|---------|
| ATF AER-98 INST PIPELINE AFTER PEAK TANK | | | | | |
| ATF AER-100 MOD 30 kW M/G CONT CIRCUIT | | | | | |
| ATF AER-101 SAF-T-CLIMB FALL PROTECTION SYSTEM | | | | | |
| TYCOM AER TOTAL * | | | | | |

*Totals not provided because of unavailability of NAVSHIPS/SUPSHIPS estimated costs for some alterations.

B.4 TYCOM REPAIR PACKAGE - USS QUAPAW (ATF-110)

| | <u>No.</u> | <u>Pct</u> |
|---|------------|------------|
| 1. Total Work Requests Screened | 780 | 100 |
| Total Automated Work Requests | 0 | 0 |
| 2. (a) Number of Work Requests Deferred | 27 | 4 |
| (b) Number of Work Requests Disapproved | 30 | 4 |
| (c) Number of Work Requests Duplicated, etc. | 80 | 10 |
| (d) Number of Work Requests Approved | 643 | 82 |
| TOTAL | <u>780</u> | <u>100</u> |
| 3. Total Work Requests Approved | 643 | |
| Number Work Requests Screened: Priority One (1) | 12 | 2 |
| Number Work Requests Screened: Priority Two (2) | 107 | 17 |
| Number Work Requests Screened: Priority Three (3) | 244 | 38 |
| Number Work Requests Screened: Priority Four (4) | 241 | 37 |
| Number Work Requests Screened: Priority Five (5) | 38 | 6 |
| Number Work Requests Screened: Priority Six (6) | <u>1</u> | <u>-</u> |
| TOTAL | 643 | 100 |
| B. Number of Approved Work Requests by Type Work | | |
| Repair (including Remove, Replace, Manufacture, Drydock, POT/I and Calibration) | 559 | 87 |
| Ship Alteration | 32 | 5 |
| TYCOM AER | 14 | 2 |
| Habitability | 22 | 3 |
| Routines | <u>16</u> | <u>3</u> |
| TOTAL | 643 | 100 |
| C. Number of Approved Work Requests Insurance Items: | | |
| As Insurance items were identified, the ship was advised to include them in the work package. Separate identity was not maintained. | | |
| D. Number of Approved Work Requests Accomplished | NA | NA |
| Number of Approved Work Requests not Accomplished and not entered in CSMP | NA | NA |

B.5 PERA SCREENING SUMMARY, USS QUAPAW (ATF-110)

| 1. SCREENING ACTION | <u>PERA</u> | <u>TYCOM</u> |
|---|-------------|--------------|
| (a) Number Work Requests Screened One (1) | 296 | See Comments |
| (b) Number Work Requests Screened Two (2) | 49 | |
| (c) Number Work Requests Screened Three (3) | 294 | |
| (d) Number Work Requests Screened Four (4) | 0 | |
| (e) Number Work Requests Screened Five (5) | 0 | |
| (f) Number Work Requests Screened Six (6) | 0 | |
| (g) Number Work Requests Screened Seven (7) | 4 | |
| (h) Number Work Requests Screened Eight (8) | 27 | |
| (i) Number Work Requests Screened Nine (9) | 30 | |
| (j) Number Work Requests Screened Zero (0) | 80 | |
| (*) | | |

2. TOTAL NUMBER WORK REQUESTS TYCOM CONCURRED See Comments
TOTAL NUMBER WORK REQUESTS TYCOM SCREENED OTHERWISE See
Comments

3. See Comments % AGREEMENT IN SCREENING.

4. ANALYSIS OF SCREENING DIFFERENCES:
See comments

5. COMMENTS/RECOMMENDATIONS

Screening actions were reviewed with the overhaul manager prior to being finalized. No distinction was made between PERA and TYCOM screening actions. It can be generally stated that the overhaul manager concurred with the recommended screening.

(*)LEGEND: SCREENING ACTION (APPENDIX 17 OPNAV 43P2)

1. Shipyard accomplish
2. Tender or repair ship accomplish
3. Ships Force - (tender or repair ship/yard) assist
4. Accomplish as alteration equivalent to a repair
5. Ship to shop
6. Accomplish with modification
7. Yard open inspect -- advise TYCOM -- Proceed with minimum repairs
8. Deferred
9. Disapproved
0. Other - Specify in remarks

B.6 NARRATIVE OF MAJOR ALTERATION ITEMS

- (a) Pollution Abatement. The following pollution-abatement alterations were accomplished for QUAPAW:

S/A ATF-226K Sewage CHT (Partial)
-227K Bilge Water Discharge Riser
-229K Fuel Tank Level Indicating System
-232K Bilge Flooding Alarm Circuit FD

The sewage collecting/holding tank was installed except for the required pumps. Extensive changes to the installation developed midway through the overhaul, contributing to a delay in completion.

Equipments for the fuel tank level indicating system were received late (receivers and power panels had not been received by the end of the overhaul), and also contributed to delaying the overhaul completion.

- (b) Habitability Improvement. The following habitability-improvement alterations were accomplished:

S/A ATF-236K Food Service Line Modification
-237K Crew Galley Modifications
-242F Install Electric Hand Dryer
-243K Sanitary Spaces Ventilation and Sheathing
-244K Sanitary Spaces, Relocate Hot Water Heater
-246D Install Lavatories and Fixtures
-256D Modify Crew's Mess

These were all first-time alterations. The necessary plans were developed by SUPSHIP/San Diego for both the QUAPAW and USS MOLALA (ATF-106), which was being overhauled at the same time as QUAPAW. Because of the late authorization, these drawings were still being developed at the start of the QUAPAW overhaul. Galley equipment identification and purchase were late, and equipments were still being received at the end of the overhaul.

(c) Other: Other major alterations included:

S/A ATF-210D Replace Air Compressor with Naval Standard
Compressor
-213D Replace Main Propulsion Engines and Diesel
Generator Sets

Because of the unavailability of a naval standard compressor, a new non-standard compressor was installed.

Late delivery of the propulsion engines contributed to delaying the start of the QUAPAW overhaul, and late receipt of a replacement engine for one damaged in shipment contributed to delaying the completion of overhaul. The portion of this shipment to replace the ship service generating sets could not be accomplished due to nonavailability of equipment. A new 200-kW S.S. generator set diesel engine was installed.

B.7 Narrative of Major Repair Items

Following is a listing of the major repair work items accomplished during the QUAPAW overhaul. Work on these items progressed satisfactorily and did not impact on the overhaul completion date.

| <u>Cost Range</u> | <u>Item</u> | <u>Estimated Cost</u> |
|-------------------|---------------------------------|-----------------------|
| \$100K | (None) | |
| \$50K - \$100K | Replace No. 1 S/S Gen Dsl Eng | \$ 60,733 |
| \$25K - \$50K | Propulsion Gen | 45,964 |
| | Propulsion Mtrs | 43,045 |
| | F.W. Tank (2), Clean & Preserve | 41,000 |
| | Hull Preservation | 37,570 |
| \$10K - \$25K | Stern Shafting | 22,496 |
| | Mach Space Access Openings | 22,127 |
| | Bhd Sheathing W. R. | 20,543 |
| | Drydocking | 15,967 |
| | Sheathing CPO | 15,515 |
| | Seaplane Winch | 15,377 |
| | Temp Mess & Berthing | 14,753 |
| | Vent Motors | 13,372 |

| <u>Cost Range</u> | <u>Item</u> | <u>Estimated Cost</u> | |
|-------------------|---------------------|-----------------------|-----|
| \$10K - \$25K | Ovhd Sheath CPO | 12,953 | |
| | Towing Machine | 12,943 | |
| | IC Swbd | 12,900 | |
| | Steering Gear | 12,456 | |
| | Anchor Windlass | 11,921 | |
| | Sheathing CPO | 11,199 | |
| | F.O. Purifier | 11,141 | |
| | Ovhd Sheathing W.D. | 10,889 | |
| | RPL Air Compressor | 10,547 | |
| | Capstan | 10,110 | |
| | ASF | 10,000 | |
| | | \$497,521 | 30% |

B.8 Narrative of Material Condition Prior to ROH

The QUAPAW was considered to be in average material condition for a ship of her class and due for an overhaul. The main propulsion diesel engines were obsolete and difficult to maintain. Main motors and generators required complete overhaul. The number 1 ship service generator diesel engine required replacement. All ship's service generators and switchboards required overhaul. There was some hull plating and frame damage on the starboard side. The communication and radar systems were in need of updating. No pollution abatement ship alterations had been accomplished, and improved habitability installations were required.

B.9 Narrative of Material Condition After ROH

The QUAPAW deficiencies noted in Section B.8 were corrected during the overhaul. New main propulsion engines and most of the pollution abatement requirements were installed, and habitability levels were raised considerably. The QUAPAW received a thorough overhaul, and should be able to operate with a minimum of outside maintenance assistance until her next overhaul.

III.C Long Range Maintenance Requirements

An essential element of overhaul maintenance planning is assuring continuity from one overhaul to the next. An influential factor in attaining this continuity is the Long Range Maintenance Plan (LRMP). Using the completion date of the QUAPAW overhaul as a starting point, and utilizing the records of that overhaul, PERA prepared a plan identifying long range maintenance requirements for the QUAPAW. This plan addresses the period between overhauls, and specifies major maintenance requirements that should be targeted for accomplishment during the next overhaul.

Together with the LRMP, a second group of work, that deferred during the overhaul, was identified and the associated information was provided to the ship for inclusion in and updating of the current Ships Maintenance Projects (CSMP). The LRMP does not discuss the work entered into the CSMP, although planning for and accomplishment of that work is an integral part of long-range maintenance planning.

Probably the most important aspect of long-range maintenance planning is ship's force scheduling and accomplishment of 3M Planned Maintenance Subsystem (PMS) requirements. If ship's force pursues this program thoroughly and conscientiously, maintenance problem areas can be identified promptly and corrected before major deficiencies develop.

The long-range maintenance requirements identified for QUAPAW are shown in Table III.C-1. Section A of that table lists work defined during the recent overhaul. Ship's force and/or the overhaul manager (COMSERVPAC/COMSERVGRU) should start now to plan and budget for its accomplishment. Section B is work recommended for accomplishment during the next overhaul that requires actions by the overhaul manager early in the ROH requirements planning phase. Long-lead-time material must be ordered, or preoverhaul testing and inspection has to be scheduled to firm up repair requirements. Section C is work that should be given high priority for accomplishment during the next overhaul. For most of this work, preoverhaul testing should not be required. Section D identifies PMS-related actions whose accomplishment during the period between overhauls is considered especially important in preparation for the next overhaul.

No attempt has been made to include programmed ship alterations into this plan. It is considered that these are adequately handled by existing programs under the FMP.

The work deferred had no impact on the overall quality of the QUAPAW overhaul, or on the ability of QUAPAW to perform its assigned tasks and missions.

TABLE III. C. 1. LONG-RANGE MAINTENANCE REQUIREMENTS (Sheet 1 of 2)

| EIC | DESCRIPTION | REMARKS | EST. COST (\$)* |
|---|---|---|-----------------|
| A. WORK DEFINED AND DEFERRED DURING FY 74 REGULAR OVERHAUL | | | |
| 1B00 | Galley Modifications | Complete the installation | Incl. in Ovhl |
| 4100 | Switchboard Splash Shields | INSURV deficiency | 3,000 |
| A900 | Tank Level Indicating System | Complete the installation | Incl. in Ovhl. |
| B. REPAIRS RECOMMENDED FOR NEXT REGULAR OVERHAUL REQUIRING LONG LEAD TIME MATERIAL | | | |
| T100 | Auxiliary Boiler | Procure replacement boiler | 25,000* |
| C. OTHER LONG RANGE MAINTENANCE REQUIREMENTS | | | |
| 1000 | Conduct Habitability Study | Conduct at least 12 months before next overhaul to define deficiencies and establish priorities | 5,000* |
| 3000 | Conduct Electrical Power Requirements Study | Conduct as early as possible to define requirements | 25,000* |
| T300 | Ventilation/Exhaust System Survey | Conduct at least 12 months before next overhaul to define requirements | 3,000* |
| D. PMS ITEMS (SHIP'S FORCE ACCOMPLISHMENT) | | | |
| 1806 | Salvage Equipment | | |
| 1807 | Diving Equipment | | |
| *PERA estimates. Other estimates were developed during overhaul planning just concluded. | | | |

TABLE III. C. 1. LONG-RANGE MAINTENANCE REQUIREMENTS (Sheet 2 of 2)

| EIC | DESCRIPTION | REMARKS | EST. COST (\$)* |
|--|--------------------------------|---------|-----------------|
| D. PMS ITEMS (SHIP'S FORCE ACCOMPLISHMENT) (Cont) | | | |
| 310U | Ship Service Diesel Generation | | |
| 4000 | Electrical Safety Devices | | |
| 4400 | Power Distribution Cabling | | |
| C000 | Main Propulsion Diesel Engines | | |
| | Reduction Gears | | |
| | Main Propulsion Generators | | |
| | Main Propulsion Motors | | |
| T100 | Auxiliary Boiler/Steam Piping | | |
| T500 | Refrigeration System | | |
| T800 | Firemain Piping and Valves | | |
| TF00 | Compressed Air Systems | | |
| TK00 | Evaporators | | |
| TM00 | Deck Machinery | | |
| | Towing Machine | | |
| *PERA estimates. Other estimates were developed during overhaul planning just concluded. | | | |

III. D. Recommendations

D.1 For the Ship.

It is recommended that QUAPAW ship's force personnel take the following actions:

- (a) Ensure that the CSMP is up-to-date and accurately reflects the condition of the ship following overhaul. Deferred work items accomplished during the overhaul should have completed actions submitted. Work that was not completed should be reviewed and revised as necessary to reflect its status at the end of overhaul.
- (b) Follow-up and ensure receipt of updated record plans and documents that reflect the condition of the ship at the end of overhaul.
- (c) Take action as necessary to accomplish deferred work/long range maintenance items, Section III. C.

D.2 For the Class.

It is recommended that for the ATF-96 class ships, the type commander, with assistance from PERA and the ships, accomplish the following:

- (a) Plan for and accomplish a series of habitability studies and incorporate the results into future alteration and overhaul planning. The objective of this action is to update priority of accomplishment and obtain the necessary data to authorize early development of plans and ordering of material.
- (b) Review existing alterations to determine new equipment/material requirements and take action as needed to obtain these items, e.g., replacement of auxiliary S/S generator sets and air compressors.
- (c) Take follow-up actions as required to resolve electrical power availability/requirements for these ships, and provide for accomplishment of any modifications during the next overhaul.

D.3 Standardized ROH Work Requests (Form 4790.2K).

It is recommended that the program to develop standardized ATF class work requests and overhaul specifications be actively pursued. ARINC

Research is currently developing such a proposed standard work package under contract with COMSERVPAC.

D.4 For PERA(CSS).

It is recommended that PERA take the following actions with respect to advanced overhaul planning:

- (a) Revise the planning milestone tasks to incorporate the most recent procedures and techniques.
- (b) Analyze the reports and documents required to support overhaul planning, and issue appropriate specifications for their preparation and distribution.
- (c) Actively pursue relationships with various SUPSHIP organizations to develop better understanding of the PERA functions and the need for interchange of advance planning data.
- (d) Review the need for more active participation of PERA during the overhaul management phase.
- (e) Increase the emphasis on advance material definition and procurement for overhauls.

III. E. Evaluation/Usefulness

E.1 PERA Products to Ship/Industrial Activity.

- (a) Ship Systems Definition and Index (SSDI). The SSDI was used by the ship and ARINC Research as an aid in assuring complete work-package coverage. These block diagrams of the ship's systems by EIC provide a systematic method of organizing and reviewing the work package. Development of SSDI for other ship classes is recommended.
- (b) Integrated Work Package Summary Reports. Computerized work package summary reports prepared in accordance with PERA(CSS) procedures were issued periodically throughout the overhaul planning phase. These reports were used by the ship, overhaul manager, and ARINC Research to progress the development of the overhaul package. The ability to produce these reports in various sequences such as work center-job sequence number, EIC category, type commander screening action, and industrial activity item number proved to be a valuable aid in managing the overhaul work package. They also served as an expedient method of keeping ship's force advised as to the screening action for its work requests.
- (c) Preoverhaul Test and Inspection Report. As the QUAPAW work package was reviewed and screened, the requirements for pre-overhaul testing and inspection were identified. The overhaul activity was advised of these requirements through the overhaul manager. The usefulness of these tests in many instances was marginal because of the poor quality of the reports received following the tests and inspections. For future overhauls, the results expected from specific preoverhaul tests and inspections should be better defined.
- (d) Tradeoff Analysis. A tradeoff analysis was prepared and provided to the overhaul manager prior to each tradeoff conference. For the QUAPAW overhaul, these analyses provided an approximation of what the two phases of the overhaul would cost. An analysis

of the depth intended by the overhaul planning task definition could not be made, however, for the following reasons:

- (1) SUPSHIP job estimates for all jobs were not available, and in some instances were of the ball-park type.
- (2) The time interval between receipt of SUPSHIP job estimates and the tradeoff conference was extremely short.
- (3) Complete man-hour estimates for ship's force jobs were not available.
- (4) Tender man-hour availability was not identified.
- (5) Identification of costs associated with the following was difficult:
 - a. Advance planning expenditures by SUPSHIP
 - b. Design service contract costs
 - c. PHNSY farm-in costs
- (e) LLTM and FILS Reports. A Fleet Integrated Logistics Support (FILS) report was issued for the QUAPAW overhaul. ARINC Research could not determine if its contents were of use to the SUPSHIP office.
- (f) Periodic Overhaul Planning Status Reports. Periodic overhaul planning status reports were prepared by ARINC Research and distributed to PERA(CSS) and the overhaul manager. It is believed that they served a useful purpose in documenting the overhaul planning effort, and in keeping overhaul/planning management personnel advised of the program status.

E.2 Resource Effectiveness

Evaluation of resource effectiveness for the QUAPAW overhaul planning requires considering four organizations:

- (a) Ship's force
- (b) PERA
- (c) SUPSHIP
- (d) Overhaul manager


Ship's force was prompt in submitting its work package, cooperative in resolving problems with specific work items and in the planning effort, and efficient in progressing its work throughout the overhaul. Delays in starting and completing the overhaul were beyond their control. It is the opinion of ARINC Research that the ship managed their resources very well.

PERA personnel, starting with less than the desired lead time for planning, screened the work package to SUPSHIP expeditiously. Designation of the alteration package was late, and together with the large number of first time shipalts, this had a delaying effect on the overhaul start. Preoverhaul test and inspection requirements were defined early and conducted with sufficient time to identify work requirements. A lack of understanding of all concerned of the specific responsibilities during the overhaul period resulted in a partial breakdown of communication. Additional follow-up and redefinition of PERA responsibilities during overhaul would help correct this situation.

SUPSHIP received approximately 80% of the work package in mid-April and by mid-May had essentially the complete package. Late tasking of first-time alteration design work resulted in a large portion of the overhaul being undefined by the time of the August tradeoff. Job specifications and estimates should have been prepared earlier than was the case; however the end of the fiscal year, with its accompanying increase in general work requirements, probably had an effect.

The POT/I produced results of lower quality in most cases which was due partly to incompletely or poorly defined requirements. More specific guidelines need be developed to better define what is expected from these tests and inspections. Following the overhaul, the departure report was not available at C+4 months.

The overhaul manager and the COMSERVGRU FIVE maintenance officer and his staff were efficient and cooperative in supporting their function in the overhaul planning. In a few instances new work went directly to SUPSHIP, with the result of not being considered as part of the complete package. During the overhaul, more effective use could have been made of available PERA services. This again reinforces the need to redefine the PERA functions and responsibilities during the overhaul period.



USS MOLALA (ATF-106)
POST OVERHAUL ANALYSIS REPORT
OVERHAUL DATES
13 August 1973 - 29 December 1973

USS MOLALA (ATF-106)
POST OVERHAUL ANALYSIS REPORT

Approved: _____

Date: _____

Distribution:

PERA (CSS)
COMSERVPAC
COMSERVGRU ONE
USS MOLALA
NAVSHIPS 427

Prepared by
ARINC RESEARCH CORPORATION
Ships and Ordnance Division
Honolulu Support Office
Contract N00140-73-D-0074-0010

Publication 1020-01-1-1303C

USS MOLALA (ATF-106)
POST OVERHAUL ANALYSIS REPORT

TABLE OF CONTENTS

| | | |
|------|---|----|
| I. | General Information and Preface | 1 |
| | A. General Information | 1 |
| | B. Preface | 1 |
| II. | Management Summary | 2 |
| | A. Authorized Vs. Accomplished Work | 2 |
| | B. Planned Vs. Actual Completion Times | 2 |
| | C. Planned Vs. Actual Completion Costs | 2 |
| | D. Major Configuration Changes | 2 |
| | E. Follow-on Work Required | 3 |
| III. | Details of Overhaul | 4 |
| | A. Planning Process | 4 |
| | 1. Ideal Vs. Actual Milestones | 4 |
| | a. Advance Overhaul Planning | 4 |
| | b. Tradeoff Conference | 7 |
| | c. Overhaul Phase | 7 |
| | d. Postoverhaul Phase | 8 |
| | 2. Impact of Planning Milestone Slippages | 8 |
| | 3. Recommendations. | 8 |
| | B. Work Package | 9 |
| | 1. Summary Sheet | 10 |
| | 2. Cost Summary Sheet. | 11 |
| | 3. Alteration Summary Sheet | 14 |
| | 4. TYCOM Repair Package | 18 |
| | 5. PERA Screening Summary. | 19 |
| | 6. Narrative of Major Alteration Items | 20 |
| | 7. Narrative of Major Repair Items. | 21 |
| | 8. Narrative of Material Condition Prior to ROH | 22 |
| | 9. Narrative of Postoverhaul Material Condition | 23 |
| | C. Long-Range Maintenance Requirements | 24 |

| | |
|--|----|
| D. Recommendations | 28 |
| 1. For the Ship | 28 |
| 2. For the Class | 28 |
| 3. Standardized ROH Work Requests | 29 |
| 4. For PERA(CSS) | 30 |
| E. Evaluation/Usefulness | 31 |
| 1. PERA Products to Ship/Industrial Activity | 31 |
| a. Ship System Definition and Index (SSDI) | 31 |
| b. Integrated Work Package (IWP) Summary Reports | 31 |
| c. Preoverhaul Test and Inspection (POT/I) Reports | 31 |
| d. Tradeoff Analysis | 31 |
| e. FILS Report | 31 |
| 2. Resource Effectiveness | 31 |

I. GENERAL INFORMATION AND PREFACE

A. GENERAL INFORMATION

Ref: (a) Contract N00140-73-D-0074-0010.

(b) PERA(CSS) Milestone Charts, dated August 1972; forwarded by PERA(CSS) Ltr Ser. 1800-262 of 4 May 1973.

B. PREFACE:

The USS MOLALA (ATF-106) was overhauled from 13 August 1973 through 29 December 1973 under the direction of SUPSHIP 11. The overhaul was accomplished by National Steel and Shipbuilding Company, San Diego, California.

In planning the overhaul of the MOLALA, PERA(CSS), acting as TYCOM and NAVSHIPS maintenance management agent, established advance planning milestones (references a and b) which commenced six months prior to the overhaul start date. The goal of the planning effort has been to identify, in advance, potential and existing problem areas; and provide the detailed preoverhaul guidance, planning, and coordination necessary to achieve a successful yard overhaul. The purpose of this report is to evaluate the management judgments and decisions associated with the planning effort during this period.

II. MANAGEMENT SUMMARY

References (a) and (b) list the management milestones used in planning the overhaul of USS MOLALA (ATF-106). Deviations from the milestones which affected the overhaul, and nonprogrammed factors that contributed to the final overhaul outcome, are discussed below.

A. AUTHORIZED VS. ACCOMPLISHED WORK

Essentially all of the required work was authorized and accomplished. The ship completed its overhaul in the authorized availability period. Several items were not completed, mainly due to late delivery of GFM. These were carried as exceptions to the overhaul contract and completed by the contractor on a case basis. However, the turbo charger for the No. 1 auxiliary diesel has continued to present problems and should be replaced.

B. PLANNED VS. ACTUAL COMPLETION TIME

The MOLALA overhaul was completed on schedule. The overhaul start date was delayed due to late completion of first-time alteration drawings and scheduled delivery dates of replacement main engines.

C. PLANNED VS. ACTUAL COMPLETION COSTS

Significant cost changes almost exclusively involved shipalts. A comparison of planned and actual costs for the MOLALA overhaul cannot be presented herein because the SUPSHIP departure report had not been released as of the preparation of this report. A supplement to this report will be prepared and forwarded after receipt of the departure report.

D. MAJOR CONFIGURATION CHANGES

The MOLALA completed the overhaul with the following major configuration changes:

1. Replacement of main propulsion engine
2. New pollution abatement features
3. New habitability improvements
4. Installation of modernized tow machine
5. Upgraded communication capabilities.

E. FOLLOW-ON WORK REQUIRED

The major follow-on work still required to complete the MOLALA overhaul is the development of several shipalts to modernize the electrical power generating plant.

III. DETAILS OF OVERHAUL

A. PLANNING PROCESS

1. Ideal Vs Actual Milestones

Advanced overhaul planning for the USS MOLALA commenced in January 1973. The overhaul planning procedures used for the MOLALA overhaul are defined in the COMSERVPAC Overhaul Planning Task Chart, Task Index, and Tasks, dated 15 September 1972; and Combatant Support Ship Overhaul Advance Planning Milestones. These advance planning milestones provide for accomplishment of 53 tasks, of which 36 tasks are PERA action responsibility. The ideal target dates for these tasks range from start of overhaul minus 20 months (A-20), to completion of overhaul plus 2 months (C+2).

With the MOLALA overhaul scheduled to start 1 August 1973, ARINC Research commenced the advance planning for the overhaul at about A-7 months. This made it necessary to compress the time frame of the planning milestones and combine some tasks. All required tasks were completed. Table III.A-1 shows the dates for the accomplishment of the principal milestones for MOLALA. The following paragraphs summarize the advance planning for the overhaul.

- a. Advance Overhaul Planning. Overhaul planning was initiated by ARINC Research with a survey of the available maintenance history of the MOLALA as contained in the Current Ships Maintenance Program (CSMP) and the Maintenance and Material Management (3M) Program Material History Report. Programmed ship alterations (shipalts) and Type Commander alterations were reviewed, along with other pertinent maintenance history documents such as last overhaul records, departure reports, Board of Inspection and Survey (INSURV) reports, and casualty reports (CASREPs).

The entire work package, minus those items subject to a Preoverhaul Test and Inspection (POT/I), was screened and delivered to SUPSHIP 11 by 30 April 1973. For the POT/I, a two-week restricted availability (RAV) was conducted from 30 April to 13 May 1973, with Campbell Industries performing the tests. New work

TABLE III.A-1. IDEAL VS. ACTUAL MILESTONES FOR ROH OF USS MOLALA (ATF-106)
(Sheet 1 of 2)

| Milestone | COMSERVPAC Target Date | Contract Target Date | Actual Start | Completion | Remarks |
|--|------------------------|----------------------|--------------|------------|--|
| PERA Contract Start Date | | | 1/18/73 | | |
| Obtain Historical Data, Review Alt Package | Immed. | Immed. | 1/18/73 | 2/15/73 | CSMP, 3M-material history report, shipalts, AERs, INSURV reports, CASREPs. |
| Brief Ship on Overhaul Preparation | Prior to deployment | 3/12/73 | | 3/12/73 | |
| Receive Ship Work Request Package | Immed. | 3/21/73 | 3/19/73 | 4/23/73 | Ship's operating schedule necessitated receiving incremental work package. |
| NAVSHIPS Issue Tentative K-Alts, Task First-Time Alt Dwgs | A-10 | 10/1/72 | 2/9/73 | | First-time alt drawings not completed until approximately 8/1/73. |
| Screen Work Request Package; Determine Known Work; Shipcheck | A-9 to A-6 | 3/21/73 | 3/19/73 | 4/30/73 | Entire work package, except equipment subject to POT/I submitted to SUPSHIP 11 by 4/30/73. |
| Determine Preoverhaul Test and Inspection (POT/I) Requirements | A-6 | 2/23/73 | 2/12/73 | 3/8/73 | |
| Conduct POT/I | A-6 to A-3 | 4/30/73 | 4/30/73 | 5/13/73 | Supplemental work requests submitted to SUPSHIP 11 by 5/15/73. |
| NAVSHIPS Issue 180-Day Letter | A-6 | 2/1/73 | | 5/9/73 | Advance copy promulgated 5/9/73 |

TABLE III. A-1. (Sheet 2 of 2)

| Milestone | COMSERVPAC Target Date | Contract Target Date | Actual Start | Completion | Remarks |
|------------------------------------|------------------------|----------------------|--------------|------------|--|
| Conduct Work Definition Conference | A-2 | 6/11/73 | | 6/25/73 | Conference delayed by late plan completion. |
| Perform Overhaul | | 8/1/73 - 12/3/73 | 8/13/73 | 12/29/73 | Overhaul availability changed to 8/13/73 - 12/31/73. |
| Complete Final Report | C+2 | 2/29/73 | | | Report delayed due to lack of actual cost information. |

requests resulting from the POT/I were screened to SUPSHIP for inclusion in the work package, and by the end of May the integrated alteration/repair work package was essentially complete. The completeness of this package is demonstrated by the fact that only one minor item was added after the overhaul contract was awarded.

The major difficulty in the preoverhaul planning process was the late identification of first-time shipalts and the subsequent late tasking and completion of basic alteration class drawings (BACDs). The initial NAVSHIPS K-alt authorization message was issued on 9 February 1973 and included nine first-time alts. Pearl Harbor Naval Shipyard indicated on 7 March 1973 that they could not complete the BACDs in time to support the ROH start dates of MOLALA and QUAPAW. SUPSHIP 11 accepted the task of developing MOLALA drawings that were also utilized for QUAPAW and COCOPA. These drawings were not completed until approximately 1 August 1973, delaying the overhaul start date until 13 August 1973.

- b. Tradeoff Conference. The tradeoff conference was originally scheduled for 11 June 1973; however late completion of plans delayed the conference until 25 June. At the conference, attended by representatives of SUPSHIP 11, USS MOLALA (ATF-106), COMSERVGRU ONE, PERA (CSS) and ARINC Research Corporation, 61 Priority 3 work items were deferred due to lack of funds. COMSERVPAC subsequently authorized the additional funds and the complete overhaul work package was included in the invitation for bid.
- c. Overhaul Phase. ARINC Research's main responsibility during the MOLALA overhaul was monitoring its progress and assisting in the management of SERVGRU resources in light of additional requirements developed during and as a result of the overhaul. To accomplish this, ARINC Research personnel attended several SUPSHIP weekly progress conferences and provided liaison between the SERVGRU ONE maintenance staff, SUPSHIP, and the ship.

d. Postoverhaul Phase. ARINC Research Corporation's responsibility following completion of the overhaul consisted of analyzing the overhaul records and preparation of final reports. The final report was delayed because of the late distribution of the departure report with return cost data.

2. Impact of Planning Milestone Slippages

The advance overhaul planning milestones call for early identification of alterations to be accomplished during the overhaul, and early authorization by the planning yard to have first-time shipalt drawings developed. For MOLALA, the NAVSHIPS alteration planning message was issued 9 February 1973. Drawings for seven first-time alterations were developed by SUPSHIP 11 to support the overhaul as a result of tasking by PHNSY on 30 March. This late start for plan development and the resultant late ordering of material had a direct effect on delaying the start date of overhaul. Plans were still being received after the overhaul started.

3. Recommendations

As a result of the review of the planning process for MOLALA as discussed above, the following recommendations are offered.

- a. Review advance-planning milestone target dates and establish dates that can be feasibly accomplished.
- b. Continue to emphasize early submittal of the ship's work package to SUPSHIP to facilitate development of cost estimates and work specifications in support of a work definition conference based on accurate and complete data.
- c. Review the requirement for postoverhaul reports to contain final cost data. Under present conditions, these data are not available by the milestone date (C+2) for submittal of the final report.
- d. Continue to work toward early definition and firming up of the ship alteration package and the authorization to develop required drawings.
- e. Increase PERA participation in the overhaul management phase.

B. WORK PACKAGE

1. Summary Sheet
2. Cost Summary Sheet
3. Alteration Summary Sheet
4. TYCOM Repair Package
5. PERA Screening Summary
6. Narrative of Major Alteration Items
7. Narrative of Major Repair Items
8. Narrative of Material Condition Prior to ROH
9. Narrative of Postoverhaul Material Condition

1. Summary Sheet — USS MOLALA (ATF-106)

Scheduled Start Date: 1 Aug 73 Scheduled Completion Date: 3 Dec 73

Actual Start Date:* 13 Aug 73 Actual Completion Date: 29 Dec 73

Overhaul Extended: 0 days

*Overhaul period changed to 8/13/73 through 12/31/73 by CNO on 15 August 1973. Overhaul start date delayed due to late completion of BACDs and uncertain delivery status of new main engine.

SIGNIFICANT CAPABILITY CHANGES:

- a. The MOLALA received four new Caterpillar D-399 main propulsion engines during the ROH. In a companion alteration, waste heat evaporators replaced the existing solo-shell evaporators.
- b. A rebuilt and modernized A.A. Johnson Series 222 tow machine was installed.
- c. The AFFF/PKP fire-fighting system was installed in the machinery spaces.
- d. Pollution abatement shipalts accomplished included 1) a partial CHT system, 2) installation of tank level indicators, 3) a bilge flooding alarm circuit, and 4) a bilge water discharge riser.
- e. Several habitability shipalts (both titles D and K) were accomplished including galley, food service, and mess decks modernization. All sanitary spaces were refurbished.
- f. A secure voice system was installed in the electronics area. In addition, non-secure teletype and type-G crypto system shipalts were completed.

2. Cost Summary Sheet — USS MOLALA (ATF-106)

| a. <u>Summary of Overhaul Costs</u> | <u>K-Alt</u> | <u>Repair</u> |
|-------------------------------------|---------------|---------------|
| 1) Budget | \$402,409 | \$1,610,000 |
| 2) Industrial Activity Est. | 280,219 | 1,084,364 |
| 3) Design and GFM | 39,161 | 234,067 |
| 4) Total Estimate | 319,380 | 1,318,431 |
| 5) Bid Price | 280,849 | 972,940 |
| 6) Bid Price + Design + GFM | 320,010 | 1,207,007 |
| 7) Total Cost | Not Available | Not Available |
| 8) Growth Cost | Not Available | Not Available |
| 9) Percent Growth | Not Available | Not Available |

b. Estimated Overhaul Costs by EIC Category

| EIC | | Est. Cost (\$) | | Pct. Total Cost | | Pct. Growth | |
|--------|---------|----------------|---------|-----------------|---------|-----------------|---------|
| System | Subsys. | System | Subsys. | System | Subsys. | System | Subsys. |
| 1000 | | 206,621 | | 12.6 | | (Not Available) | |
| | 1A00 | | 15,103 | | 0.9 | | |
| | 1B00 | | 98,885 | | 6.0 | | |
| | 1C00 | | 48,721 | | 3.0 | | |
| | 1600 | | 7,371 | | 0.5 | | |
| | 1700 | | 25,049 | | 1.5 | | |
| | 1800 | | 11,492 | | 0.7 | | |
| 3000 | | 67,946 | | 4.2 | | | |
| | 3100 | | 67,946 | | 4.2 | | |
| 4000 | | 17,854 | | 1.1 | | | |
| | 4100 | | 11,617 | | 0.7 | | |
| | 4400 | | 96 | | 0.0 | | |
| | 4700 | | 6,141 | | 0.4 | | |
| A000 | | 166,915 | | 10.2 | | | |
| | AB00 | | 14,635 | | 0.9 | | |
| | AC00 | | 13,620 | | 0.8 | | |
| | A000 | | 6,429 | | 0.4 | | |
| | A100 | | 9,338 | | 0.6 | | |

b. (Continued)

| EIC | | Est. Cost (\$) | | Pct. Total Cost | | Pct. Growth | |
|--------|---------|----------------|---------|-----------------|---------|-------------|---------|
| System | Subsys. | System | Subsys. | System | Subsys. | System | Subsys. |
| C000 | A700 | | 5,984 | | 0.4 | | |
| | A800 | | 19,785 | | 1.2 | | |
| | A900 | | 97,124 | | 5.9 | | |
| | | 429,830 | | 26.3 | | | |
| | CD00 | | 26,375 | | 1.6 | | |
| | CE00 | | 141,459 | | 8.7 | | |
| | C100 | | 218,762 | | 13.4 | | |
| | C400 | | 8,886 | | 0.5 | | |
| | C600 | | 7,852 | | 0.5 | | |
| | C700 | | 9,682 | | 0.6 | | |
| L000 | C800 | | 15,802 | | 0.9 | | |
| | C900 | | 1,012 | | 0.1 | | |
| | | 20,900 | | 1.3 | | | |
| | LF00 | | 312 | | — | | |
| M000 | LH00 | | 2,061 | | 0.1 | | |
| | LJ00 | | 18,527 | | 1.2 | | |
| | | 4,066 | | 0.2 | | | |
| N000 | M500 | | 3,636 | | 0.2 | | |
| | M600 | | 430 | | — | | |
| P000 | N000 | | 1,040 | | 0.1 | | |
| | N400 | | 1,040 | | 0.1 | | |
| Q000 | | 3,410 | | 0.2 | | | |
| | P100 | | 2,769 | | 0.2 | | |
| | P600 | | 641 | | 0.0 | | |
| Q000 | | 34,660 | | 2.1 | | | |
| | QD00 | | 11,268 | | 0.7 | | |
| | QE00 | | 3,515 | | 0.2 | | |
| | Q100 | | 764 | | 0.1 | | |
| | Q300 | | 16,925 | | 1.0 | | |
| | Q900 | | 2,188 | | 0.1 | | |

b. (Continued)

| EIC | | Est. Cost (\$) | | Pct. Total Cost | | Pct. Growth | |
|---|---------|-------------------|---------|-----------------|---------|-------------|---------|
| System | Subsys. | System | Subsys. | System | Subsys. | System | Subsys. |
| R000 | | 2,669 | | 0.2 | | | |
| | R500 | | 2,669 | | 0.2 | | |
| T000 | | 591,565 | | 36.2 | | | |
| | TA00 | | 9,531 | | 0.6 | | |
| | TB00 | | 14,051 | | 0.9 | | |
| | TC00 | | 624 | | — | | |
| | TD00 | | 58,527 | | 3.6 | | |
| | TF00 | | 22,167 | | 1.4 | | |
| | TK00 | | 65,911 | | 4.0 | | |
| | TL00 | | 34,669 | | 2.1 | | |
| | TM00 | | 180,003 | | 11.0 | | |
| | TS00 | | 1,842 | | 0.1 | | |
| | T100 | | 32,637 | | 2.0 | | |
| | T300 | | 25,030 | | 1.5 | | |
| | T400 | | 4,890 | | 0.3 | | |
| | T500 | | 14,364 | | 0.9 | | |
| | T700 | | 65,064 | | 4.0 | | |
| | T800 | | 22,645 | | 1.4 | | |
| | T900 | | 39,610 | | 2.4 | | |
| U000 | | 79,706 | | 4.9 | | | |
| | UE00 | | 2,596 | | 0.2 | | |
| | UF00 | | 21,480 | | 1.3 | | |
| | UH00 | | 5,000 | | 0.3 | | |
| | UJ00 | | 14,054 | | 0.9 | | |
| | U500 | | 630 | | 0.0 | | |
| | U600 | | 1,561 | | 0.1 | | |
| | U700 | | 27,162 | | 1.7 | | |
| | U800 | | 7,223 | | 0.4 | | |
| Y000 | | 7,516 | | 0.5 | | | |
| | UC00 | | 7,516 | | 0.5 | | |
| TOTAL | | 1,634,698* | | | | | |
| *This total differs from summary sheet total because of some revised estimates. | | | | | | | |

c. Cost Avoidance Summary

Screening Actions. For the MOLALA overhaul, 426 work requests were received from the ship and screened by PERA. Of this total, 19 percent were screened as deferred, duplicated, disapproved, etc., as a result of shipchecks, discussions with ship personnel, and analysis of the work requested. This represents a substantial cost avoidance to the type commander as well as a considerably lightened workload for the overhauling activity and overhaul manager.

During the screening process, a large number of work requests were screened for intermediate maintenance activity (IMA) or ship's force accomplishment. This allowed funding for work requests that a shipyard can best accomplish.

Job specifications were reviewed as they were being written at SUPSHIP 11. A considerable number (about 30%) were edited to ensure that the work requested was adequately described, to correct errors, to expand coverage, etc. This effort reduced substantially the number of change orders issued on repair jobs.

3. Alteration Summary Sheet

The alteration summary sheet for the USS MOLALA is shown in Table III.B-1.

TABLE III. B-1. ALTERATION SUMMARY SHEET - USS MOLALA (ATF-106) (Sheet 1 of 3)

| Alteration | FMP Est. (\$) | NAVSHIP Est. (\$) | SUPSHIP Est. (\$) | Actual Cost (\$) | Remarks |
|---|---------------|-------------------|-------------------|------------------|---|
| ATF-193K Increase Salvage Pump | 22,127 | 18,018 | 8,685 | | Partial; GFM not received |
| ATF-203K Install Nonsecure Teletype (partial to complete) | 14,606 | 12,280 | 11,706 | | Complete |
| ATF-205K Install UHF/VHF Secure Voice (partial to complete) | 15,805 | 13,104 | 11,268 | | Complete |
| ATF-211K Install Type G Teletype (partial to complete) | 36,951* | 5,733 | | | Complete; estimate included in S/A ATF-203K |
| ATF-212K General Weight and Moment Compensation | 11,554 | 9,828 | 14,370 | | Complete |
| ATF-216K Install Mach. Space AFF/PKP Fire-Fighting System | 87,200 | 71,253 | 39,610 | | Complete |
| ATF-226K P/A Sewage CHT (partial system) | 149,984* | 91,728 | 68,875 | | Complete; S/A ATF-263K will complete installation |
| ATF-227K Install Bilge Water Discharge Riser | 11,009 | 9,009 | 8,649 | | Complete |

*FMP estimate based on complete installation

TABLE III. B-1. (Sheet 2 of 3)

| Alteration | FMP Est. (\$) | NAVSHIP Est. (\$) | SUPSHIP Est. (\$) | Actual Cost (\$) | Remarks |
|--|---------------|-------------------|-------------------|------------------|---|
| ATF-229K Install Fuel Tank Level Indicating System | 78,698 | 64,701 | 37,168 | | Partial; minor mods required |
| ATF-232K Install Bilge Flooding Alarm Circuit FD | 2,071 | 1,638 | 3,636 | | Complete |
| ATF-236K H/I Food Service | 21,037 | 17,199 | 26,015 | | Partial; GFM not received |
| ATF-237K H/I Galley Mods | 47,306 | 48,493 | 67,615 | | Partial; S/A ATF-225K will complete. GFM sink heater not received. |
| ATF-243K H/I Sanitary Space Vent & Sheathing | 54,282 | 44,226 | 20,745 | | Complete |
| ATF-165D Modify Boiler Air Casing | | | | | Complete; estimate included in boiler replacement job. |
| ATF-205D Install Dual Task Lights | | | 13,676 | | Complete; shipalt being revised and may be redone. |
| ATF-213D Replace Main and Auxiliary Engines | | | 218,762 | | Partial; main engines replaced. Auxiliary engines to be subject of revised shipalt. |
| ATF-246D Replace Sanitary Space Fixtures | | | 52,160 | | Complete |
| ATF-256D H/I Crews Mess Rearrangement | | | 27,976 | | Complete |

TABLE III. B-1. (Sheet 3 of 3)

| Alteration | FMP Est. (\$) | NAVSHIP Est. (\$) | SUPSHIP Est. (\$) | Actual Cost (\$) | Remarks |
|---|---------------|-------------------|-------------------|------------------|---|
| ATF-27 Install Permanent Depth Gauge | | | 882 | | Complete |
| ATF-64 Install Strip Heaters in Topside Motors | | | 3,909 | | Complete |
| AER-ATF-71 Modify Fuel Oil Service System Piping | | | | | Complete; estimate included in S/A ATF-213D |
| AER-ATF-75 Install Cutout Valve in Boiler Fuel Supply Line | | | | | Complete; estimate included in boiler replacement job. |
| AER-ATF-85 Install Waste Heat Evaporators | | | 65,911 | | Partial; "Hagevap" installation required. |
| AER-ATF-89 Install Remote Start-Stop Stations for Fire Pumps | | | 613 | | Complete |
| AER-ATF-97 Relocate Fresh Water Pumps | | | 3,366 | | Complete |
| AER-ATF-102 Crews Clothing Lockers | | | 3,150 | | Partial; lockers ordered for ship's force installation. |

4. TYCOM Repair Package — USS MOLALA (ATF-106)

| | <u>No.</u> | <u>Pct.</u> |
|---|------------|-------------|
| 1. Total Automated Work Requests | 0 | |
| 2. Total Work Requests Screened | 426 | |
| a. Number of Work Requests Deferred | 23 | 5.4 |
| b. Number of Work Requests Disapproved | 31 | 7.3 |
| c. Number of Work Requests Duplicated, etc. | 27 | 6.3 |
| d. Number of Work Requests Approved | 345 | 81.0 |
| TOTAL | 426 | 100.0 |
| 3. Total Work Requests Approved | 345 | |
| a. Number Work Requests Screened: Priority One (1) | 14 | 4.1 |
| b. Number Work Requests Screened: Priority Two (2) | 91 | 26.4 |
| c. Number Work Requests Screened: Priority Three (3) | 195 | 56.5 |
| d. Number Work Requests Screened: Priority Four (4) | 38 | 11.0 |
| e. Number Work Requests Screened: Priority Five (5) | 6 | 1.7 |
| f. Number Work Requests Screened: Priority Six (6) | 1 | 0.3 |
| TOTAL | 345 | 100.0 |
| 4. Number of Approved Work Requests by Type Work | 345 | |
| a. Repair (including Remove, Replace, Manufacture, Drydock, POT/I, and Calibrate) | 309 | 89.7 |
| b. Ship Alteration | 16 | 4.6 |
| c. TYCOM AER | 8 | 2.3 |
| d. Habitability | 6 | 1.7 |
| e. Routines | 6 | 1.7 |
| TOTAL | 345 | 100.0 |
| 5. Number of Approved Work Requests Insurance Items: | NA | NA |
| As insurance items were identified, the ship was advised to include them in the work package. Separate identity was not maintained. | | |
| 6. Number of Approved Work Requests Accomplished | NA | NA |
| 7. Number of Approved Work Requests Not Accomplished and Not Entered in CSMP | NA | NA |

5. PERA Screening Summary, USS MOLALA (ATF-106)

| 1. Screening Action | <u>PERA</u> | <u>TYCOM</u> |
|---|-------------|--------------|
| a. Number of Work Requests Screened One (1) | 164 | See Comments |
| b. Number of Work Requests Screened Two (2) | 62 | |
| c. Number of Work Requests Screened Three (3) | 119 | |
| d. Number of Work Requests Screened Four (4) | 0 | |
| e. Number of Work Requests Screened Five (5) | 0 | |
| f. Number of Work Requests Screened Six (6) | 0 | |
| g. Number of Work Requests Screened Seven (7) | 0 | |
| h. Number of Work Requests Screened Eight (8) | 23 | |
| i. Number of Work Requests Screened Nine (9) | 31 | |
| j. Number of Work Requests Screened Zero (0) | 27 | |

(*)

2. Total Number Work Requests TYCOM Concurred: See Comments
3. Total Number Work Requests TYCOM Screened Otherwise: See Comments
4. See Comments % Agreement in Screening
5. Analysis of Screening Differences: See Comments
6. Comments/Recommendations:

Screening actions were reviewed with the overhaul manager prior to being finalized. No distinction was made between PERA and TYCOM screening actions. It can be generally stated that the overhaul manager concurred with the recommended screening.

(*) LEGEND: Screening Action (Appendix 17, OPNAV 43P2)

1. Shipyard accomplish
2. Tender or repair ship accomplish
3. Ship's force — (tender or repair ship/yard) assist
4. Accomplish as alteration equivalent to a repair
5. Ship to shop
6. Accomplish with modification
7. Yard open inspect — advise TYCOM — proceed with minimum repairs
8. Deferred
9. Disapproved
0. Other — specify in remarks

6. Narrative of Major Alteration Items

While accomplishing the approved shipalts, problems with design and late arrival of government furnished material during the MOLALA overhaul were encountered. These problems are discussed below.

- a. S/A ATF-226K, P/A CHT. The drawings for this shipalt were provided by SUPSHIP 11. A major revision to the pollution abatement collecting and holding tank, relocation of the overboard discharge, occurred during the drydock period and disrupted the orderly progression of piping work throughout the ship. Twenty-one change orders were issued on this work item. The CHT system will be completed with accomplishment of shipalt ATF-263K.
- b. S/A ATF-229K, P/A Tank Level Indicators. The drawings developed for this shipalt did not reflect all of the shipalt material. The blueprints were revised to indicate the installation of transmitters. The receivers for this shipalt did not arrive until approximately two months after completion of ROH.
- c. S/A ATF-236K, Food Services; Line Modifications; and S/A ATF-237K, Crew Galley Mods. Late delivery of galley equipment was a major disruptive influence during the overhaul, despite early attempts to determine what equipment was to be provided and assurances that these items would arrive on schedule. Several months after ROH completion, some equipment had not yet been delivered, and the equipment received was often different from that indicated on the drawings. As a result, prefabricated items had to be modified to suit the supplied equipment. In addition, several items of galley equipment not required for the shipalt were supplied, adding to the confusion. The deep fat fryer firefighting system was omitted from the class drawings; accomplishment of S/A ATF-255K will add this feature. Twenty change orders were issued on these two jobs.
- d. S/A ATF-213D, Replace Main Propulsion Engines and Diesel Generator Sets. Due to nonavailability of engines and generators, the auxiliary engine portion of this alteration was cancelled for all FY 74 ATF overhauls. Threatened late delivery of the replacement

main engines was one of the causes of a 13-day delay in the ROH start and several design changes occurred during the installation. Twenty change orders were issued on this job.

7. Narrative of Major Repair Items

The major repair items were:

- a. Installation of a new boiler as a maintenance replacement item
- b. Installation of a rebuilt and updated tow machine
- c. Overhaul of the main propulsion generators and switchboard
- d. Overhaul of the ship's service generators, engines, and switchboard.

In addition, most of the pumps, motors and controllers, all deck machinery, reefers, steering gear, and several electronic equipments were repaired. In general, these items progressed satisfactorily and presented no major problems during the overhaul.

The following is a listing of the major repair work items accomplished during the MOLALA overhaul.

| <u>Cost Range</u> | <u>Item</u> | <u>Estimated Cost</u> |
|-------------------|--|-----------------------|
| >\$100K | Repair Main Propulsion Generators & Switchboards | \$141,459 |
| | Replace Tow Machinery | 132,776 |
| \$50-100K | None | |
| \$25-50K | Repair No. 2 and No. 3 S/S Gen. Engines | 37,045 |
| | Replace Boiler | 28,029 |
| | Temporary Services | 27,162 |
| | Replace Main Generator Cabling | 26,375 |
| | Hab. Mods in WR, CPO Quarters and Staterooms | 25,049 |
| \$10-25K | Repair No. 1 S/S Generator Engine | 23,283 |
| | Topside and Underwater Preservation | 21,480 |
| | Repair Steering Gear | 18,194 |
| | Rudder and Propeller Repairs | 16,475 |
| | FO Manifolds, Suction and Sluice Valve Repairs | 16,000 |

AD-A054 502

ARINC RESEARCH CORP HONOLULU HI
ADVANCE OVERHAUL PLANNING FOR USS APACHE (ATF-67), USS COCOPA (---ETC(U)
OCT 74

F/G 13/10

N00140-73-D-0074

UNCLASSIFIED

1020-01-1-1303

NL

2 OF 2
AD
A064 502



END
DATE
FILMED
6-78
DDC

| <u>Cost Range</u> | <u>Item</u> | <u>Estimated Cost</u> |
|--------------------|---|-----------------------|
| \$10-25K (Cont) | Repair Seaplane Winch | \$ 15,652 |
| | Repair Sea Valves | 14,635 |
| | Reefer Repairs | 14,364 |
| | Dry Docking | 14,054 |
| | Replace Sanitary Drains | 12,904 |
| | Preserve Shaft Alley | 12,629 |
| | Repair Fire Flushing and Bilge Pumps | 11,352 |
| | Clean and Preserve 4 Freshwater Tanks | 11,016 |
| | Repair Anchor Windlass | 10,906 |
| | Total | \$630,839 |
| | Percent of total estimate for repair items: | 38.5 |

8. Narrative of Material Condition Prior to ROH

Approximately 9 months prior to the ROH, the USS MOLALA underwent an RAV during which the main motors were completely overhauled. As a result, no work was required on this major item.

The ship was in above-average material condition for a 30-year-old vessel, three years out of overhaul. However, the main propulsion engines were obsolete and difficult to maintain and replacement was definitely warranted. The ship's service generators and engines, main propulsion generators, and all switchboards were in need of overhaul. Also, most of the auxiliary pumps, reefers, steering gear, purifiers, and deck machinery required an overhaul to ensure three more years of service.

Mission-degrading INSURV items included:

- a. Absence of twinned-agent fire protection system in the machinery spaces
- b. Inoperative or degraded-surface search radar and communication equipment
- c. Nonaccomplished electronics shipalts

- d. No pollution abatement shipalts completed
- e. Ship did not meet current habitability standards and, in addition, had a great deal of combustible sheathing and carpeting aboard.

9. Narrative of Postoverhaul Material Condition

With the exception of replacing aluminum deck plates, the items listed in Table III. C-1 as defined and deferred during the ROH were deferred at the tradeoff conference due to lack of funds and their low ranking on the ship's priority list. Their deferral has not reduced the MOLALA's ability to perform its mission. Replacement of aluminum deck plates became a requirement during the overhaul; however, material was not available and the work item was deferred.

During the ROH, the problems mentioned in Section B. 8 were corrected. Four new engines, new main propulsion compressors, new evaporators, and a new boiler were installed. A rebuilt, modernized tow machine and a rebuilt gun mount were installed. Environmental protection capability and habitability levels were raised considerably. The MOLALA received a thorough overhaul and should be able to operate until its next overhaul with a minimum of outside assistance.

Due to the age of the ship, ship's force will have to maintain a program of replacing steam and drain piping, and power distribution cabling. Also, extensive fire-main piping replacement will be required during the next ROH. Finally, as will be discussed under "Recommendations", the electrical power generating plant needs to be upgraded.

C. LONG-RANGE MAINTENANCE REQUIREMENTS

An essential element of overhaul maintenance planning is assuring continuity from one overhaul to the next. An influential factor in this continuity is the Long-Range Maintenance Plan (LRMP). Using the completion date of the MOLALA overhaul as a starting point, together with the records of that overhaul, PERA prepared a plan identifying long-range maintenance requirements for the MOLALA. This plan addresses the period between overhauls, and specifies major maintenance requirements that should be targeted for accomplishment during the next overhaul.

Together with the LRMP, a second group of work, that deferred during the overhaul, was identified and provided to the ship for inclusion in and updating of the Current Ships Maintenance Project (CSMP). The LRMP does not discuss the work entered into the CSMP, although planning for and accomplishment of that work is an integral part of the long-range maintenance planning.

Probably the most important part of long-range maintenance planning is the ship's force scheduling and accomplishment of 3M Planned Maintenance Subsystem (PMS) requirements. If ship's force pursues this program *thoroughly and conscientiously*, maintenance problem areas can be identified promptly and corrected before major deficiencies develop.

The long-range maintenance requirements identified for MOLALA are shown in Table III.C-1. Section A of that table lists work defined during the recent overhaul. Ship's force and/or the overhaul manager (COMSERVPAC/COMSERVGRU) should start now to plan and budget for its accomplishment. Section B is work recommended for accomplishment during the next overhaul that requires actions by the overhaul manager early in the ROH requirements planning phase. Long-lead-time material (LLTM) must be ordered, or preoverhaul testing and inspection has to be scheduled to firm up repair requirements. Section C is work that should be given high priority for accomplishment during the next overhaul. For most of this work, preoverhaul testing should not be required. Section D identifies PMS-related actions whose accomplishment during the period between overhauls is considered especially important in preparation for the next overhaul.

No attempt has been made to include programmed ship alterations into this plan. It is considered that these are adequately handled by existing programs under the FMP.

The work deferred had no impact on the overall quality of the MOLALA overhaul, or on the ability of MOLALA to perform its assigned tasks and missions.

TABLE III. C-1. DEFERRED WORK/LONG-RANGE MAINTENANCE ACTIONS - USS MOLALA (ATF-106)
(Sheet 1 of 2)

| EIC | Description | Remarks | Est. Cost (\$)* |
|---|----------------------------------|---|-----------------|
| A. WORK DEFINED AND DEFERRED DURING 1973 OVERHAUL | | | |
| 4100 | Switchboard Splash Shields | Blueprints available; install during deployment RAV. | 3,000 |
| 3301 | 2.5-kw Emergency Generator | Develop shipalt to replace with a larger, modern unit. | |
| A501 | Deck Plates B-1, B-2 | Aluminum deck plates must be replaced with steel long-lead-time material (LLTM). Replace as material becomes available. Complete at next ROH. | 30,000 |
| AD01 | Water-Tight Doors | Repair/replace seven (7). | 7,000 |
| LK01 | 24" Searchlight | Repair. | 2,500 |
| TM05 | Beach Gear Rollers | Repair seven (7). | 4,000 |
| B. REPAIRS RECOMMENDED FOR NEXT ROH REQUIRING LLTM | | | |
| T801 | Fire Main Piping and Valves | Inspect, repair, replace. Copper-nickel pipe required (LLTM). | 30,000 |
| C. OTHER LONG-RANGE MAINTENANCE REQUIREMENTS | | | |
| 310U | No. 1 Ship Service Diesel Engine | Replace turbo charger. | No. est. |
| 310W | Ship Service Generator Mufflers | Inspect, repair three. | 7,500 |
| CC01 | Main Motors | Inspect, repair two. | 40,000 |
| LJ00 | Navigation Lights | Modify navigation lights to conform with 1972 international regulations. Shipalt being prepared. | No est. |
| *Values are PERA (CSS) estimates. | | | |

TABLE III. C-1. (Sheet 2 of 2)

| EIC | Description | Remarks | Est. Cost (\$) * |
|---|---|---|------------------|
| D. PMS ITEMS (SHIP'S FORCE ACCOMPLISHMENT) | | | |
| 1806 | Salvage Equipment | | |
| 1807 | Diving Equipment | | |
| 310U | Ship Service Diesel Generators | | |
| 4000 | Electrical Safety Devices | | |
| 4400 | Power Distribution Cabling | | |
| C000 | Main Propulsion Diesel Engines Reduction Gears | A program to replace power cable should be initiated. | |
| | Main Propulsion Generators | | |
| | Main Propulsion Motors | | |
| T100 | Auxiliary Boiler/Steam Piping | S/F replace pipe. | |
| T500 | Refrigeration System | | |
| T800 | Firemain Piping and Valves | S/F replace pipe. | |
| TA03 | Bilge Drainage Piping, Valves, and Manifold | | |
| TF00 | Compressed Air Systems | | |
| TK00 | Evaporators | | |
| TM00 | Deck Machinery | | |
| *Values are PERA (CSS) estimates. | | | |

D. RECOMMENDATIONS

1. For the Ship

It is recommended that MOLALA ship's force personnel take the following actions:

- a. Maintain a vigorous program of replacing steam and drain piping, and power distribution cabling.
- b. Ensure that the CSMP is up-to-date and accurately reflects the condition of the ship following overhaul. Deferred work items accomplished during the overhaul should have completed actions submitted. Work that was not completed should be reviewed and revised as necessary to reflect its status at the end of overhaul.
- c. Follow-up and ensure receipt of updated record plans and documents that reflect the condition of the ship at the end of overhaul.
- d. Take action as necessary to accomplish deferred work/long-range maintenance items as discussed in Section III. C.

2. For the Class

It is recommended that for the ATF-106 class ships, the type commander, with assistance from PERA and the ships, accomplish the following:

- a. Plan for and accomplish a series of habitability studies and incorporate the results into future alteration and overhaul planning. The objective of this action is to update priority of accomplishment and obtain the necessary data to authorize early development of plans and ordering of material.
- b. Review existing alterations to determine new equipment/material requirements and take action as needed to obtain these items, e. g. , replacement of auxiliary S/S generator sets and air compressors.
- c. Take follow-up actions as required to resolve electrical power availability/requirements for these ships, and provide for accomplishment of any modifications during the next overhaul.

The major problems of the ATF-106 class ships lie in the electrical power generating system. Shipalt ATF-213D called for replacement of

two Superior diesel generator sets. This was cancelled due to lack of new engines and generators and the uncertainty as to optimum installation. A revised shipalt is being prepared to replace the old engines. The No. 1 ship's service generator on the MOLALA, as well as on the COCOPA and CHOWANOC, is rated at 300 kW; however, the switchboard circuit breaker is only 200 kW. This should be the subject of a companion shipalt to that mentioned above.

Shipalt ATF-185K was intended to add two 30-kW motor generator (MG) sets to the one already installed. However, MOLALA, as well as COCOPA and CHOWANOC, have only two 30-kW MG sets and the shipalt status is listed as complete while other ships in the class have a total of three 30-kW MG sets. A third 30-kW MG set should be added on the ships without it. Also the ac distribution system should be altered to balance the load among the MG sets and standardize the class by removing the accumulation of 30 years of "jury rigs" and other changes.

The 2.5-kW emergency generator has been a Part I INSURV discrepancy on all ships of the class. In addition to being inadequate, the equipment is obsolete. A shipalt is required.

- d. Analyze INSURV reports and request shipalts or AERs be prepared as required. Several Part I INSURV discrepancies have been noted on all ships of the class. Some examples are the 2.5-kW emergency generator; lack of machinery-space access trunks, thermopneumatic magazine sprinkler system, and switchboard splash shield; several magazine discrepancies, etc.
3. Standardized ROH Work Requests (Form 4790.2K)

It is recommended that the program to develop standardized ATF class work requests and overhaul specifications be actively pursued. ARINC Research is currently developing such a proposed standard work package under contract with COMSERVPAC. Experience gained on MOLALA was utilized on other ATF overhauls in FY-74.

4. For PERA (CSS)

It is recommended that PERA take the following actions with respect to advanced overhaul planning:

- a. Revise the planning milestone tasks to incorporate the most recent procedures and techniques.
- b. Analyze the reports and documents required to support overhaul planning, and issue appropriate specifications for their preparation and distribution.
- c. Actively pursue relationships with various SUPSHIP organizations to develop better understanding of the PERA functions and the need for interchange of advance planning data.
- d. Review the need for more active participation of PERA during the overhaul management phase.
- e. Increase the emphasis on advance material definition and procurement for overhauls.
- f. Select and task an organization to develop and maintain type commander AER-class drawings. One of the difficulties encountered in the planning process was obtaining drawings for the type commander's AER's. No activity is tasked to maintain class drawings for these alterations. This leads to delays and unnecessary expenditure of design funds.
- g. Increase distribution of the Fleet Integrated Logistics Support (FILS) report, for example to the Naval Maintenance Management Field Office and Supply Operations Assistance Program teams.

E. EVALUATION/USEFULNESS

1. PERA Products to Ship/Industrial Activity

- a. Ship Systems Definition and Index (SSDI). The SSDI was found very useful by the ship and enabled assembly of a comprehensive work package.
- b. Integrated Work Package (IWP) Summary Reports. The IWP was utilized by the ship and the type commander as a record of screening action and as a tool in updating the CSMP.
- c. Preoverhaul Test and Inspection (POT/I) Reports. The POT/I reports on deck machinery were of marginal use to the ship because of their poor quality. For future overhauls, the results expected from specific tests and inspections should be more clearly defined. The electronics POT/I was very beneficial as it identified not only industrial activity work items, but tender/DATC and ship's force work as well.
- d. Tradeoff Analysis. A tradeoff analysis was prepared and provided to the overhaul manager prior to the tradeoff conference. This provided the overhaul manager with the data necessary to authorize the most effective overhaul work package.
- e. FILS Report. The information provided by the FILS program was not utilized by the industrial activity.

2. Resource Effectiveness

Evaluation of resource effectiveness for the MOLALA overhaul planning requires consideration of four sources:

- a. Ship's force
- b. SUPSHIP
- c. Overhaul manager
- d. PERA

Although the ship's operating schedule hindered the submission of the work package, the ship diligently attacked the problem and assembled a

good package. The key shipboard personnel had been through overhauls in the past and realized what had to be done. It is felt that ship's force accomplished its work and monitored the shipyard work in an outstanding manner.

SUPSHIP 11 personnel were extremely cooperative in providing estimates and incorporating PERA suggestions into the job specifications. This had a significant impact on producing a successful ROH. However, due to the workload at SUPSHIP, several frustrating delays in resolving design problems occurring during the ROH.

PERA personnel, starting with less than the desired lead time for planning, screened the work package to SUPSHIP within their planning time frame. In the course of preoverhaul planning, PERA presented several completed tasks (including a screened work package, a POT/I plan, and a tradeoff analysis) to the overhaul manager for his concurrence. This effort removed a large burden from an already overloaded maintenance staff.



USS COCOPA (ATF-101)
POST OVERHAUL ANALYSIS REPORT
OVERHAUL DATES
6 November 1973 — 30 May 1974

USS COCOPA (ATF-101)
POST OVERHAUL ANALYSIS REPORT

Approved: _____

Date: _____

Distribution:

PERA (CSS)
COMSERVPAC
COMSERVGRU ONE
USS COCOPA (ATF-101)

Prepared by
ARINC RESEARCH CORPORATION
Ships and Ordnance Division
Honolulu Support Office
Contract N00140-73-D-0074-0010

Publication 1020-01-1-1303D

USS COCOPA (ATF-101)
POST OVERHAUL ANALYSIS REPORT

TABLE OF CONTENTS

| | | |
|------|--|----|
| I. | General Information and Preface | 1 |
| A. | General Information | 1 |
| B. | Preface | 1 |
| II. | Management Summary | 2 |
| A. | Authorized Vs. Accomplished Work | 2 |
| B. | Planned Vs. Actual Completion Time | 2 |
| C. | Planned Vs. Actual Completion Costs | 2 |
| D. | Major Configuration Changes | 2 |
| E. | Follow-on Work Required | 3 |
| III. | Details of Overhaul | 4 |
| A. | Planning Process | 4 |
| 1. | Ideal Vs. Actual Milestones | 4 |
| a. | Advance Overhaul Planning | 4 |
| b. | Tradeoff Conference | 7 |
| c. | Overhaul Phase | 7 |
| d. | Postoverhaul Phase | 7 |
| 2. | Impact of Planning Milestone Slippages | 7 |
| a. | Shipalt Drawings | 7 |
| b. | 180-Day Letter | 8 |
| c. | Late Authorization of Shipalts | 8 |
| d. | Late Availability of Specifications | 8 |
| 3. | Recommendations | 9 |
| B. | Work Package | 10 |
| 1. | Summary Sheet | 11 |
| 2. | Cost Summary Sheet | 12 |
| 3. | Alteration Summary Sheet | 15 |
| 4. | TYCOM Repair Package | 19 |
| 5. | PERA Screening Summary | 20 |
| 6. | Narrative of Major Alteration Items | 21 |
| 7. | Narrative of Major Repair Items | 22 |

| | | |
|----|---|----|
| 8. | Narrative of Material Condition Prior to Overhaul | 26 |
| 9. | Narrative of Material Condition After Overhaul | 26 |
| C. | Long Range Maintenance Requirements | 28 |
| D. | Recommendations | 32 |
| 1. | For the Ship | 32 |
| 2. | For the Class | 32 |
| 3. | Standardized ROH Work Requests | 33 |
| 4. | For PERA (CSS) | 33 |
| E. | Evaluation/Usefulness | 35 |
| 1. | PERA Products to Ship/Industrial Activity | 35 |
| a. | Ship Systems Definition and Index (SSDI) | 35 |
| b. | Integrated Work Package (IWP) Summary Report | 35 |
| c. | POT/I Plan | 35 |
| d. | Tradeoff Analysis | 35 |
| e. | FILS Report | 35 |
| 2. | Resource Effectiveness | 35 |
| a. | Ship's Force | 35 |
| b. | RESUPSHIP | 35 |
| c. | PERA (CSS) | 36 |

I. GENERAL INFORMATION AND PREFACE

A. GENERAL INFORMATION

Ref: (a) Contract N00140-73-D-0074-0010.

(b) PERA(CSS) Milestone Charts, dated August 1972; forwarded by PERA(CSS) Letter, Ser. 1800-262, dated 4 May 1973.

B. PREFACE

The USS COCOPA (ATF-101) was overhauled from 6 November 1973 through 30 May 1974 under the direction of the Resident Supervisor of Shipbuilding (RESUPSHIP), Long Beach, CA. The overhaul was accomplished at the Harbor Boat Building Company, Long Beach.

In planning the overhaul of the COCOPA, PERA(CSS), acting as TYCOM and NAVSHIPS maintenance management agent, established advance planning milestones (References a and b) which commenced 10-1/2 months prior to the overhaul start date. The goal of the planning effort was to identify in advance any potential and existing problem areas, and to provide the detailed preoverhaul guidance, planning, and coordination necessary to achieve a successful yard overhaul. The purpose of this report is to evaluate the management judgments and decisions associated with the planning effort.

II. MANAGEMENT SUMMARY

References a and b list the management milestones in planning the FY 1974 regular overhaul (ROH) of the USS COCOPA (ATF-101). Deviations from the milestones that affected the overhaul, and unanticipated factors that contributed to the final overhaul outcome, are discussed below.

A. AUTHORIZED VS. ACCOMPLISHED WORK

The repair portion of the COCOPA work package was essentially completed as authorized. Exceptions were the following: 1) The tank level indicators were not calibrated by the shipyard; 2) the navigation lights, though certified, required modification; 3) the newly installed side rollers will have to be relocated; and 4) extensive electrical work is still needed.

B. PLANNED VS. ACTUAL COMPLETION TIME

The overhaul start date was delayed five days to allow Long Beach contractors more time in San Diego for shipchecking the extensive package. The completion of overhaul was delayed 62 days due to generally slow progress during the overhaul; late delivery of contractor-furnished material for overhauling the main motors, and of certain items of government-furnished material; failure of the No. 3 main generator after reinstallation aboard ship; and design problems.

C. PLANNED VS. ACTUAL COMPLETION COSTS

The SUPSHIP departure report had not been released as of the preparation of this report, so a comparison of actual versus estimated costs for COCOPA overhaul cannot be presented herein. A supplement to this report will be prepared and forwarded after receipt of the departure report.

D. MAJOR CONFIGURATION CHANGES

The major configuration changes to the COCOPA involved replacing the main propulsion engines and accomplishing several pollution-abatement shipalts. Habitability was significantly upgraded. A modernized towing machine was installed. Communication capabilities were greatly enhanced.

E. FOLLOW-ON WORK REQUIRED

In addition to completing the items noted in paragraph A above and in the Long-Range Maintenance Plan, the development of several shipalts for modernizing the electrical power generating plant is required.

III. DETAILS OF OVERHAUL

A. PLANNING PROCESS

1. Ideal Vs. Actual Milestones

Advanced overhaul planning for the USS COCOPA commenced in January 1973. The overhaul planning procedures used for the COCOPA overhaul are defined in the COMSERVPAC Overhaul Planning Task Chart, Task Index, and Tasks, dated 15 September 1972; and the Combatant Support Ship Overhaul Advance Planning Milestones. These advance planning milestones provide for accomplishment of 53 tasks, of which 36 tasks are PERA action responsibility. The ideal target dates for these tasks range from start of overhaul minus 20 months (A-20), to completion of overhaul plus 2 months (C+2).

With the COCOPA overhaul scheduled to start 3 December 1973, ARINC Research commenced advance planning for the overhaul at about A-10-1/2 months. This made it necessary to compress the timeframe of the planning milestones and to combine some tasks. All required tasks were completed. Table III.A-1 shows the dates for the accomplishment of the principal milestones for COCOPA. The following paragraphs summarize the advance planning for the overhaul.

- a. Advance Overhaul Planning. Overhaul planning was initiated by ARINC Research with a survey of the available maintenance history of the COCOPA as contained in the Current Ships Maintenance Program (CSMP) and the Maintenance and Material Management (3M) Program Material History Report. Programmed ship alterations and TYCOM alterations were reviewed, along with other pertinent maintenance history documents such as last overhaul records, departure reports, and casualty reports (CASREPs). An INSURV inspection was conducted in June and the report was used as reference in the screening of the work package.

At the time ARINC Research began its planning efforts, the COCOPA overhaul was scheduled to commence on 3 December 1973 at SUPSHIP 11. Subsequently the overhaul start date was advanced to 4 September, then delayed to 28 January 1974, then advanced

TABLE III.A-1. IDEAL VS. ACTUAL MILESTONES FOR ROH OF USS COCOPA (ATF-101)

| Milestone | COMSERVPAC Target Date | Contract Target Date | Actual Start | Completion | Remarks |
|---|------------------------|----------------------|--------------|------------|--|
| PERA Contract Start Date | | 1/18/73 | | | |
| Obtain Historical Data; Review Alt Package | Immed. | Immed. | 1/18/73 | 3/1/73 | CSMP, 3M material history reports, shipalts, AERs, CASREPs. |
| Brief Ship on Overhaul Preparation | Prior to deployment | 3/15/73 | | 3/15/73 | |
| Receive Work Package | Immed. | 4/15/73 | 7/3/73 | 7/20/73 | INSURV inspection conducted in mid-June. |
| NAVSHIPS Issue Tentative K-Alts; Task First-Time Alt Drawings | A-10 | 2/3/73 | | 1/30/73 | ROH dates 12/3/73 - 3/4/74 at time of issue. |
| Screen Work Package; Determine Known Work; Conduct Shipcheck | A-9 to A-6 | 4/15/73 | 7/3/73 | 8/3/73 | Work package delivered to RESUPSHIP on 8/3/73. |
| Determine POT/I Requirements | A-6 | 6/28/73 | | 4/21/73 | ROH start date 1/28/74 at that time. |
| Conduct POT/I | A-6 to A-3 | 8/1/73 | 9/4/73 | 9/17/73 | DATC performed POT/I. RESUPSHIP conducted several inspections. |
| NAVSHIPS Issue 180-Day Letter | A-6 | 5/1/73 | | 8/20/73 | ROH start date 11/1/73 at time of issue. |
| Conduct Work Definition Conference | A-2 | 9/1/73 | | 9/26/73 | |
| Perform Overhaul | | 11/1/73 -3/29/74 | 11/6/73 | 5/30/74 | |
| Complete Final Report | C+2 | 7/30/74 | | 8/15/74 | |

again to 1 November 1973. The responsible organization was changed to the Resident Supervisor of Shipbuilding, Long Beach. The overhaul duration was increased from three to five months, the interval being 1 November 1973 through 29 March 1974.

In March 1973, an ARINC Research representative briefed COCOPA personnel on overhaul planning procedures. Subsequently, while the ship was in port for an extended upkeep period, ARINC Research assisted ship's force in preparing for the INSURV inspection and in developing the overhaul work package. The entire work package, except for electronic repairs, was delivered by the ship to PERA(CSS) on 3 July 1973. The package was then shipchecked, screened, and delivered to RESUPSHIP on 3 August 1973, a month in advance of the requested date.

A review by PERA(CSS) of the INSURV report, the ship's work package, and the authorized K-alt list revealed that shipalts calling for the installation of type G and N cryptographic equipment had not been scheduled by NAVSHIPS for accomplishment. The type commander and COCOPA personnel were strongly in favor of these shipalts, and on 13 August COMSERVGRU ONE recommended that they be accomplished. The shipalts (S/A 211K for type G and 196K for type N crypto equipment) were authorized on 8 November 1973, shortly after the overhaul had begun.

A restricted availability for Preoverhaul Test and Inspection (POT/I) of the ship deck machinery was scheduled with the Development and Training Center (DATC), San Diego, for 4-17 September 1973. During this same period, RESUPSHIP conducted POT/I on navigation lights, electronics, main propulsion electrical equipment, and degaussing equipment; and manufacturer technical representatives inspected the tow machinery and gyro. The resulting reports were used by RESUPSHIP in developing work specifications for the overhaul.

RESUPSHIP planners and estimators conducted their shipcheck from 1-14 September. Estimates, but not specifications, were prepared in time for a 26 September work definition (tradeoff) conference.

- b. Tradeoff Conference. The overhaul tradeoff conference on 26 September 1973 was attended by representatives of RESUPSHIP, USS COCOPA, COMSERVGRU ONE, PERA(CSS), and ARINC Research. At the conference, overhaul work in the amount of \$1,499,450 was approved.
- c. Overhaul Phase. For the shipyard portion of the overhaul, the Harbor Boat Building Company of Long Beach was the low bidder at \$1,150,555. Because this bid was less than expected, five work items that had been deferred at the tradeoff conference were authorized, at an anticipated cost of about \$15,000.

The shipyard work remained continuously behind schedule from the start of overhaul phase, and by mid-January the work accomplished was 13% below the goal. COMSERVGRU ONE requested PERA(CSS) to provide a representative full-time for two months in Long Beach to assist the ship and provide liaison between RESUPSHIP and COMSERVGRU ONE. This representative made daily contact with ship's force personnel, government inspectors, RESUPSHIP, and COMSERVGRU ONE. He monitored the progress of work, helped to expedite solutions to problems, made recommendations to COMSERVGRU ONE as to what action to take on proposed change orders, monitored GFM delivery, and attended the weekly progress meetings.

- d. Postoverhaul Phase. ARINC Research Corporation's responsibilities following completion of the overhaul were to analyze the overhaul records and prepare a final report.

2. Impact of Planning Milestone Slippages

Actions or occurrences impacting on the overhaul schedule are discussed below.

- a. Shipalt Drawings. The advance overhaul planning milestones call for early identification of alterations to be accomplished during the overhaul and early authorization to develop shipalt drawings. The NAVSHIPS K-alt authorization message was issued early enough to

permit an adequate design effort. However, when the overhaul start was delayed to 28 January 1974, SUPSHIP 11 decided, because of a design overload situation and the problems inherent in carrying funds into a new fiscal year, to wait until July 1973 to begin developing working drawings for COCOPA. Subsequently, when the overhaul location was shifted to RESUPSHIP and the start date moved forward by three months, there was no time to develop these drawings. With the exception of S/A ATF 226K (Sewage CHT) and a few other isolated cases, working drawings had not been developed for the COCOPA. RESUPSHIP requested a delay in the overhaul start to provide their required design effort, but this was denied. The overhaul contract was let utilizing MOLALA (ATF-106) blueprints. This caused several major problems during the overhaul.

- b. 180-Day Letter. Delayed receipt of the NAVSHIPS 180-day letter, together with the change in overhaul location, resulted in late ordering and delivery of GFM.
- c. Late Authorization of Shipalts. Late authorization of shipalts 196K and 211K (type N and G cryptos) resulted in a substantial amount of new work being approved well after the overhaul had started. When the alterations were authorized, Long Beach Naval Shipyard began developing the required prints. The final work specifications were issued 14 January 1974. Seven new work items with a total price of \$32,696 were issued.
- d. Late Availability of Specifications. The fact that only estimates and not specifications were available for the work definition conference severely hindered ARINC Research in conducting the work-item tradeoff analysis. A review of the estimates indicated that in several cases the intent of the work request had not been carried out. Conversations were conducted with individual estimators in lieu of a review of the specifications. Specifications were not available to the overhaul manager, the ship, or ARINC Research until after the invitation for bid was issued. This made review of the specifications, and any desired changes of the specification articles, difficult and in some cases impossible.

3. Recommendations

As a result of the review of the planning process for the COCOPA overhaul, ARINC Research recommends that efforts be directed toward:

- a. Ensuring that the development of ship alteration drawings and the ordering of material progresses according to the PERA (CSS) milestones.
- b. Reviewing the FMP to ensure that all required shipalts are programmed.
- c. Developing both estimates and specifications early enough to support the overhaul tradeoff conference.
- d. Increasing PERA (CSS) participation in the overhaul management phase.
- e. Minimizing changes in overhaul location and start date.

B. WORK PACKAGE

1. Summary Sheet
2. Cost Summary Sheet
3. Alteration Summary Sheet
4. TYCOM Repair Package
5. PERA Screening Summary
6. Narrative of Major Alteration Items
7. Narrative of Major Repair Items
8. Narrative of Material Condition Prior to Overhaul
9. Narrative of Material Condition After Overhaul

1. Summary Sheet - USS COCOPA (ATF-101)

Scheduled Start Date: 1 Nov 73 Scheduled Completion Date: 29 Mar 74

Actual Start Date:* 6 Nov 73 Actual Completion Date: 30 May 74

Overhaul Extended:** 62 days

*Overhaul start date delayed to allow contractors more time to inspect ship.

**Overhaul extended due to relatively slow progress during the overhaul, major problems in the overhaul of main generators and motors, late delivery of GFM, and design problems.

SIGNIFICANT CAPABILITY CHANGES:

- a. The COCOPA received four new Caterpillar D-399 main propulsion engines during the overhaul. In a companion alteration, waste heat evaporators replaced the existing solo-shell type.
- b. A rebuilt and modernized A. A. Johnson Series 222 tow machine was installed.
- c. An AFFF/PKP firefighting system was installed in the machinery spaces.
- d. Several pollution abatement shipalts were accomplished, including a partial CHT system, installation of tank level indicators, a bilge flooding alarm circuit, and a bilge water discharge riser.
- e. Several habitability shipalts (both title D and K) were accomplished, including galley, food service, and mess-deck modernization. All sanitary spaces were refurbished.
- f. A secure voice system and type G and N teletypes were installed.

2. Cost Summary Sheet — USS COCOPA (ATF-101)

| a. <u>Summary of Overhaul Costs</u> | <u>K-Alt</u> | <u>Repair</u> |
|-------------------------------------|---------------|---------------|
| 1) Budget | \$366,575 | \$1,618,000 |
| 2) Estimated Cost | 271,542 | 1,299,516* |
| 3) Bid Price | 230,226 | 920,329 |
| 4) Total Cost | Not Available | Not Available |
| 5) Growth Cost | Not Available | Not Available |
| 6) Percent Growth | Not Available | Not Available |

*Includes \$171,675 design and GFM estimate.

b. Estimated Overhaul Costs by EIC Category

| EIC | | Est. Cost (\$) | | Pct. Total Cost | | Pct. Growth | |
|--------|---------|----------------|---------|-----------------|---------|-----------------|---------|
| System | Subsys. | System | Subsys. | System | Subsys. | System | Subsys. |
| 1000 | | 115,631 | | 7.0 | | (Not Available) | |
| | 1A00 | | 4,416 | | 0.3 | | |
| | 1B00 | | 77,556 | | 4.7 | | |
| | 1C00 | | 2,925 | | 0.2 | | |
| | 1600 | | 5,486 | | 0.3 | | |
| | 1700 | | 25,248 | | 1.5 | | |
| 3000 | | 29,270 | | 1.8 | | | |
| | 3100 | | 29,270 | | 1.8 | | |
| 4000 | | 54,106 | | 3.3 | | | |
| | 4100 | | 16,328 | | 1.0 | | |
| | 4300 | | 17,532 | | 1.1 | | |
| | 4400 | | 6,684 | | 0.4 | | |
| | 4700 | | 13,562 | | 0.8 | | |
| A000 | | 120,200 | | 7.2 | | | |
| | AB00 | | 9,005 | | 0.5 | | |
| | AC00 | | 8,382 | | 0.5 | | |
| | A000 | | 12,926 | | 0.8 | | |
| | A100 | | 15,800 | | 0.9 | | |
| | A500 | | 5,227 | | 0.3 | | |

b. (Continued)

| EIC | | Est. Cost (\$) | | Pct. Total Cost | | Pct. Growth | |
|--------|---------|----------------|---------|-----------------|---------|-------------|---------|
| System | Subsys. | System | Subsys. | System | Subsys. | System | Subsys. |
| | A600 | | 2,554 | | 0.2 | | |
| | A700 | | 2,944 | | 0.2 | | |
| | A900 | | 63,362 | | 3.8 | | |
| C000 | | 433,169 | | 25.9 | | | |
| | CB00 | | 230,600 | | 13.9 | | |
| | C100 | | 157,167 | | 9.4 | | |
| | C400 | | 27,222 | | 1.6 | | |
| | C600 | | 7,338 | | 0.4 | | |
| | C700 | | 5,386 | | 0.3 | | |
| | C800 | | 5,456 | | 0.3 | | |
| L000 | | 25,484 | | 1.5 | | | |
| | LB00 | | 4,504 | | 0.3 | | |
| | LH00 | | 5,880 | | 0.3 | | |
| | LJ00 | | 15,100 | | 0.9 | | |
| M000 | | 53,307 | | 3.2 | | | |
| | M500 | | 52,247 | | 3.1 | | |
| | M600 | | 1,060 | | 0.1 | | |
| N000 | | 338 | | — | | | |
| | N400 | | 338 | | — | | |
| Q000 | | 77,713 | | 4.7 | | | |
| | Q100 | | 24,642 | | 1.5 | | |
| | Q300 | | 8,054 | | 0.5 | | |
| | QF00 | | 6,411 | | 0.4 | | |
| | QO00 | | 38,606 | | 2.3 | | |
| R000 | | 1,127 | | 0.1 | | | |
| | R500 | | 1,127 | | 0.1 | | |
| T000 | | 581,479 | | 34.9 | | | |
| | TA00 | | 6,423 | | 0.4 | | |
| | TB00 | | 4,790 | | 0.3 | | |

b. (Continued)

| EIC | | Est. Cost (\$) | | Pct. Total Cost | | Pct. Growth | |
|--|---------|---------------------|---------|-----------------|---------|-------------|---------|
| System | Subsys. | System | Subsys. | System | Subsys. | System | Subsys. |
| | TC00 | | 1,860 | | 0.1 | | |
| | TD00 | | 6,212 | | 0.4 | | |
| | TF00 | | 19,259 | | 1.1 | | |
| | TK00 | | 62,578 | | 3.8 | | |
| | TL00 | | 48,495 | | 2.9 | | |
| | TM00 | | 201,653 | | 12.1 | | |
| | T100 | | 29,157 | | 1.7 | | |
| | T300 | | 12,939 | | 0.8 | | |
| | T400 | | 15,411 | | 0.9 | | |
| | T500 | | 8,805 | | 0.5 | | |
| | T700 | | 71,145 | | 4.3 | | |
| | T800 | | 64,961 | | 3.9 | | |
| | T900 | | 27,791 | | 1.7 | | |
| U000 | | 172,798 | | 10.4 | | | |
| | UA00 | | 28,800 | | 1.7 | | |
| | UB00 | | 6,850 | | 0.4 | | |
| | UF00 | | 59,295 | | 3.6 | | |
| | UG00 | | 2,500 | | 0.1 | | |
| | UH00 | | 5,000 | | 0.3 | | |
| | UJ00 | | 9,955 | | 0.6 | | |
| | U500 | | 1,428 | | 0.1 | | |
| | U700 | | 35,828 | | 2.2 | | |
| | U800 | | 23,142 | | 1.4 | | |
| TOTAL | | \$1,664,622* | | | | | |
| <p>*This total differs from the summary sheet total because estimates for new work, as well as late estimates, are included.</p> | | | | | | | |

- c. Cost Avoidance Summary. Screening Actions – For the COCOPA overhaul, 411 work requests were received from the ship and screened by PERA. Of this total, approximately 32 percent were screened as deferred, duplicated, disapproved, etc., as a result of shipchecks, discussions with ship personnel, and analysis of the work requested. This represents a substantial cost avoidance to the type commander as well as a considerably lightened workload for the overhauling activity and overhaul manager.

During the screening process, a large number of work requests were screened for intermediate maintenance activity (IMA) or ship's force accomplishment. This allowed funding for work requests that a shipyard can best accomplish.

3. Alteration Summary Sheet

The alteration summary sheet for the USS COCOPA is shown in Table III. B-1.

TABLE III. B-1. ALTERATION SUMMARY SHEET - USS COCOPA (ATF-101) (Sheet 1 of 3)

| Alteration | FMP Est (\$) | NAVSHIP Est (\$) | SUPSHIP Est (\$) | Actual Cost (\$) | Remarks |
|---|--------------|------------------|------------------|------------------|---|
| ATF-205K Install UHF/VHF Secure Voice (Partial to Complete) | 15,805 | 12,945 | 6,411 | | Complete |
| ATF-216K Install Mach Space AFFP/PKP Fire Fighting System | 87,200 | 71,417 | 27,791 | | Complete |
| ATF-226K P/A Sewage CHT (Partial System) | 150,093* | 85,994 | 44,112 | | Complete. S/A ATF-263K will complete installation. |
| ATF-227K P/A Install Bilge Water Discharge Riser | 10,573 | 8,659 | 6,423 | | Complete |
| ATF-229K P/A Install Fuel Tank Level Indicating Sys | 78,698 | 64,453 | 60,810 | | Partial. Minor mods required. Calibration required. |
| ATF-232K Install Bilge Flooding Alarm Circuit FD | 2,071 | 1,697 | 9,009 | | Complete |
| ATF-236K H/I Food Service | 21,037 | 17,230 | 9,223 | | Complete |
| ATF-237K H/I Galley Mods | 47,306 | 38,743 | 51,994 | | Partial. S/A ATF-255K will complete. |
| ATF-243K H/I Sanitary Space Vent & Sheathing | 54,282 | 44,457 | 42,597 | | Complete |
| ATF-244K H/I Relocate Hot Water Heater | 14,061 | 11,516 | 4,790 | | Complete |

*FMP estimate based on complete installation.

TABLE III. B-1. (Sheet 2 of 3)

| Alteration | FMP Est (\$) | NAVSHIP Est (\$) | SUPSHIP Est (\$) | Actual Cost (\$) | Remarks |
|--|--------------|------------------|------------------|------------------|---|
| ATF-181D 26" MWB Safety Slings | | | 3,193 | | Complete |
| ATF-209D Install Wind Indicating System | | | 5,880 | | Complete |
| ATF-213D Replace Main & Auxiliary Engines | | | 157,167 | | Partial. Main engines replaced. Auxiliary engines to be subject of revised shipalt. |
| ATF-217D Install Ac Shore Power Connection (Partial to Complete) | | | 17,532 | | Complete. Estimate and actual cost include additional job to balance ac power load. |
| ATF-246D H/I Replace Sanitary Space Fixtures | | | 19,057 | | Complete |
| ATF-256D H/I Crews Mess Rearrangement | | | 16,339 | | Complete |
| AER ATF-75 Install Cutout Valve in Boiler Fuel Supply Line | | | | | Complete. Estimate included in boiler replacement job. |
| AER ATF-84 Improve Salvage Capability | | | 12,926 | | Partial. Side rollers must be relocated. |
| AER ATF-85 Install Waste Heat Evaporators | | | 57,141* | | Complete. |
| AER ATF-95 Install CPO A/C Unit | | | 15,411 | | Complete |
| AER ATF-94 Install Task Light Dimmer Switch | | | | | Complete. Estimate included in navigation light repair job. |

* Estimate includes GFM purchased by SUPSHIP 11.

TABLE III. B-1. (Sheet 3 of 3)

| Alteration | FMP Est (\$) | NAVSHIP Est (\$) | SUPSHIP Est (\$) | Actual Cost (\$) | Remarks |
|---|-----------------|---------------------|---------------------|---------------------|---|
| AER ATF-89 Install Remote Start- Stop Stations for Fire Pumps | | | 2,185 | | Complete |
| ATF-165D Modify Boiler Air Casing | | | | | Complete. Estimate included in boiler replacement job. |
| AER ATF-102 Crew's Clothing Lockers | | | 2,925 | | Partial. Lockers ordered for ship's force installation. |
| ATF-196K Type N Crypto | | | 24,642 | | Both shipalts completed utilizing type commanders funds. To assist ship's force as necessary. |
| ATF-211K Type G Crypto | | | | | |

4. TYCOM Repair Package - USS COCOPA (ATF-101)

| | <u>No.</u> | <u>Pct.</u> |
|---|------------|-------------|
| 1. Total Automated Work Requests | 0 | |
| 2. Total Work Requests Screened | 411 | |
| a. Number of Work Requests Deferred | 29 | 7.1 |
| b. Number of Work Requests Disapproved | 52 | 12.6 |
| c. Number of Work Requests Duplicated, etc. | 49 | 11.9 |
| d. Number of Work Requests Approved | 281 | 68.4 |
| TOTAL | 411 | 100.0 |
| 3. Total Work Requests Approved | 281 | |
| a. Number Work Requests Screened: Priority One (1) | 17 | 6.0 |
| b. Number Work Requests Screened: Priority Two (2) | 92 | 32.7 |
| c. Number Work Requests Screened: Priority Three (3) | 139 | 49.5 |
| d. Number Work Requests Screened: Priority Four (4) | 28 | 10.0 |
| e. Number Work Requests Screened: Priority Five (5) | 5 | 1.8 |
| f. Number Work Requests Screened: Priority Six (6) | 0 | 0 |
| TOTAL | 281 | 100.0 |
| 4. Number of Approved Work Requests by Type Work | 281 | |
| a. Repair (including Remove, Replace, Manufacture, Drydock, POT/I, and Calibrate) | 244 | 86.8 |
| b. Ship Alteration | 8 | 2.9 |
| c. TYCOM AER | 11 | 3.9 |
| d. Habitability | 10 | 3.6 |
| e. Routines | 8 | 2.8 |
| TOTAL | 281 | 100.0 |
| 5. Number of Approved Work Requests Insurance Items: | NA | NA |
| As insurance items were identified, the ship was advised to include them in the work package. Separate identity was not maintained. | | |
| 6. Number of Approved Work Requests Accomplished | NA | NA |
| 7. Number of Approved Work Requests Not Accomplished and Not Entered in CSMP | NA | NA |

5. PERA Screening Summary, USS COCOPA (ATF-101)

| 1. Screening Action | PERA | TYCOM |
|---|------|--------------|
| a. Number of Work Requests Screened One (1) | 116 | See Comments |
| b. Number of Work Requests Screened Two (2) | 58 | |
| c. Number of Work Requests Screened Three (3) | 107 | |
| d. Number of Work Requests Screened Four (4) | 0 | |
| e. Number of Work Requests Screened Five (5) | 0 | |
| f. Number of Work Requests Screened Six (6) | 0 | |
| g. Number of Work Requests Screened Seven (7) | 29 | |
| h. Number of Work Requests Screened Eight (8) | 52 | |
| i. Number of Work Requests Screened Nine (9) | 49 | |
| j. Number of Work Requests Screened Zero (0) | | |

(*)

2. Total Number Work Requests TYCOM Concurred: See Comments
3. Total Number Work Requests TYCOM Screened Otherwise: See Comments
4. See Comments % Agreement in Screening
5. Analysis of Screening Differences: See Comments
6. Comments/Recommendations:

Screening actions were reviewed with the overhaul manager prior to being finalized. No distinction was made between PERA and TYCOM screening actions. It can be generally stated that the overhaul manager concurred with the recommended screening.

(*) LEGEND: Screening Action (Appendix 17, OPNAV 43P2)

1. Shipyard accomplish
2. Tender or repair ship accomplish
3. Ship's force — (tender or repair ship/yard) assist
4. Accomplish as alteration equivalent to a repair
5. Ship to shop
6. Accomplish with modification
7. Yard open inspect — advise TYCOM — proceed with minimum repairs
8. Deferred
9. Disapproved
0. Other — specify in remarks

6. Narrative of Major Alteration Items

Inadequate design drawings and late delivery of government furnished material were the primary problems associated with the accomplishment of shipalts for the COCOPA. Shipalts in which major difficulties were experienced are discussed below.

- a. S/A ATF-215K, AFFF/PKP. After the new AFFF/PKP fire-fighting system was installed on the ship, it was discovered that the locations of the fire stations were not in compliance with the shipalt brief. The necessary modifications were made just prior to the end of the overhaul.
- b. S/A ATF-226K, P/A CHT. Nine change orders were issued to correct drawing problems associated with the installation of the pollution-abatement collecting and holding tank. Accomplishment of shipalt ATF-263K will complete the installation.
- c. S/A ATF-229K, P/A Tank Level Indicators. The receivers for the pollution-abatement tank level indicators arrived too late in the overhaul to be calibrated by manufacturer personnel. A technical representative of the manufacturer was summoned and gave ship's force one day's instruction in calibration. Ship's force will be required to calibrate all receivers, and should receive outside technical assistance for that task.
- d. S/A ATF-236K, Food Service Line Modifications; and S/A ATF-273K, Crew Galley Mods. Drawings for the ATF-106 (MOLALA) were used for these shipalts. Many design problems resulted, which took a substantial amount of time to resolve. Thirty-two change orders were required to solve problems relating to the inadequate drawings. GFM was delivered late, and specific items were often different than that specified on the drawings. Several excess items of galley equipment were provided, adding to the confusion.
- e. S/A ATF-213D, Replace Main Propulsion Engines and Diesel Generator Sets. Due to the present scarcity of engines and generators, and uncertainty as to the optimum means of installing

them, the auxiliary engine portion of this shipalt was cancelled for all FY 74 ATF overhauls. For the main-engine replacement, the contractor experienced considerable trouble locating some items of contractor-furnished material. Drawing inadequacies led to the issuance of 21 change orders.

- f. S/A ATF-217D, Install Ac Shore Power Connection. This shipalt was not a first-time alteration, and was authorized for accomplishment by COMSERVPAC in January 1973. At the work definition conference, this shipalt and a related work item, to balance the ac power load, were approved. These jobs were not issued to the contractor until 8 January 1974, two months after start of overhaul. This was one of the few work items for which suitable drawings were developed for the overhaul.
- g. AER ATF-84, Improve Salvage Capability. After the overhaul was completed, it was noted that several discrepancies existing in the installation required correction. The wrong type (in fact, an ~~usable~~) pad had been welded on the "H" bitt. The contractor was directed to manufacture the right type and forward it to the ship. Additionally, the new side rollers were mounted such that it is difficult to use them with the warping capstan. Proper drawings are available and the installation must be modified.

7. Narrative of Major Repair Items

The COCOPA overhaul continuously lagged behind schedule in all work areas. From the beginning of the overhaul, the work fell behind schedule an average of 2% per week.

The RESUPSHIP specifications required submission of reports of conditions found. In mid-January, it was discovered that several of these reports were up to six weeks delinquent. It was suspected that work was not progressing satisfactorily on subcontracted work items, and this was subsequently confirmed by the late return of generators, motors, pumps, engines, electronic equipment and other items.

Repair items causing the most serious problems in the COCOPA overhaul are summarized below.

- a. Main Propulsion Switchboard. In response to an "as-found" report from the contractor, the wrong type of conduit was specified for use in rewiring the switchboard. The wire heated up during testing, and the board had to be rewired.
- b. Main Propulsion Equipment. Rewinding of the armatures of the main propulsion motors was the time-controlling factor in this job because of delays in obtaining the copper wire. The main propulsion equipment was not returned to the shipyard until the original overhaul completion date had almost expired. Further, the No. 3 main generator failed under load aboard the ship after having been rewound. These problems with the main propulsion equipment were the major causes for extension of the overhaul until 30 May.
- c. Service Generators. All three ship service generators experienced failures of various magnitude while undergoing load tests. For example, the pedestal bearing was wiped in the No. 1 generator.
- d. Motors and Controllers. In general, ship motors and controllers were returned to the ship at least a month late. A review of the required reports indicated that the subcontractors were late in beginning the work.
- e. Navigation Lights. The navigation lights were repaired in accordance with the POT/I report and were certified. However, accomplishment of AER ATF-101 (Saf-T-Climb) will nullify this certification. In addition, the dual task-light arrangement is unsatisfactory.
- f. Electronics. Work on electronic repairs and shipalts progressed slowly throughout the overhaul, a situation compounded by the late authorization of the two crypto shipalts.

- g. IC Switchboard. Repairs to the IC switchboard presented a major problem. The prints used to rewire the board did not reflect the 30 years of changes aboard COCOPA. As on all ships of the class, the ac distribution system requires revision.
- h. Air Compressors. At the overhaul conference, the COCOPA's main propulsion air compressors were assigned to DATC for repair. DATC could not complete the repairs in time to support light-off. A new work item was then approved for the shipyard contractor to provide new air compressors.
- i. Power Distribution Cabling. During the overhaul, the contractor submitted several inspection discrepancy reports (IDRs) recommending wholesale renewal of the power distribution cabling. The estimate for performing this work was approximately \$140,000. The cables were inspected by COMSERVGRU and ARINC Research personnel and core samples were taken. The bulk of the cabling was found to be adequate. Change orders were issued to correct major deficiencies noted.
- j. Miscellaneous.
 - 1) Test memorandums for the sea plane winch, warping capstan, and tow machine were incorrect and required major revision on a rush basis.
 - 2) The ship was several weeks late in undocking, due to late delivery of contractor furnished material, inclement weather, and the extensive hull repairs required.

Following is a list of the major repair work accomplished during the COCOPA overhaul, grouped according to cost range.

| <u>Cost Range</u> | <u>Item</u> | <u>Estimated Cost</u> |
|-------------------|--|-----------------------|
| >\$100K | Repair and rewind four main generators and two main motors | \$230,600 |
| | Replace tow machinery | 152,136 |
| >\$50K-\$100K | None | |
| >\$25K-\$50K | Temporary Services | 33,832 |
| | Topside preservation | 33,515 |
| | Firemain and valve repair and replacement | 30,270 |
| | Replace boiler | 29,157 |
| | Design services | 28,800 |
| | Habitability modifications in WR, CPO quarters, and CO's stateroom | 25,248 |
| >\$10K-25K | Rudder repairs | 22,090 |
| | Repair steering gear | 18,210 |
| | Repair propeller and shaft | 18,045 |
| | Clean and preserve four fresh water tanks | 18,033 |
| | Preserve underwater hull | 17,673 |
| | Hull inspection | 15,800 |
| | Repair MP air piping and flasks | 15,159 |
| | Repair navigation lights | 15,100 |
| | Overhaul #3 auxiliary engine | 14,890 |
| | Overhaul three auxiliary generators | 14,380 |
| | Overhaul several vent motors | 12,939 |
| | Overhaul two fire bilge and salvage pumps | 10,139 |
| | Total | \$756,016 |

8. Narrative of Material Condition Prior to Overhaul

The COCOPA was in average material condition for a ship of its class and due for an overhaul. The main propulsion engines were obsolete and difficult to maintain; their replacement was definitely warranted. According to the POT/I report, the main propulsion generators were all heavily oil-soaked, and the main propulsion motors had been thoroughly salted.

The main and ship's service switchboards required major overhaul. The ship service generators and No. 3 auxiliary engine required major rework. The Nos. 1 and 2 auxiliary engines had been recently overhauled and required only minor attention.

Most of the ship's pumps, motors, controllers, reefers, steering gear, purifiers, and deck machinery needed overhauling. The ship's boiler had many discrepancies and the tow machine required extensive modification. The electronics POT/I indicated that considerable work was required in that area.

Mission-degrading INSURV items included lack of a twinned-agent fire fighting system in the machinery spaces, and lack of a secure voice system.

Finally, COCOPA had no pollution abatement equipment; did not meet current habitability standards; and had a great deal of combustible sheathing and carpeting aboard.

9. Narrative of Material Condition After Overhaul

The problems noted in paragraph III. B. 8 were corrected during the overhaul. Installed were four engines, new MP (medium pressure) air compressors, new evaporators, a new boiler, and a rebuilt and modernized towing machine. Extensive repairs to electronic equipment were made. Environmental protection capability and habitability levels were raised considerably. Overall, COCOPA received a thorough overhaul and should be able to operate until its next overhaul with a minimum of outside assistance.

The problem now outstanding for ATF-96 class ships is the electrical power generating system. S/A ATF-213D called for the replacement of two Superior generator sets, in addition to the replacement of the main propulsion engines. The generator portion of the shipalt was cancelled due to nonavailability of new engines and generators, and uncertainty as to the optimum installation required. A revised shipalt is being prepared to replace existing generator set engines. Also needing corrective action is the generator circuit breaker. The No. 1 service generator on COCOPA, as well as on MOLALA and CHOWANOC, is rated at 300 kW but the switchboard circuit breaker on these ships is rated at only 200 kW. The breaker size should be corrected when the new engines are installed.

Shipalt ATF-185K called for the addition of two 30-kW motor-generator (MG) sets to the one already installed. However, COCOPA, as well as MOLALA and CHOWANOC, have only two 30-kW MG sets installed, and the shipalt status is listed as complete. Other ships in the class have three 30-kW MG sets, and a third should be installed in those ships that require it. Additionally, the ac distribution system should be modified to balance the load among the MG sets and to standardize the class by removing the accumulation of 30 years of "jury rigs" and other changes.

The 2.5-kW emergency generator has been a Part I INSURV discrepancy on all ships of the class. This equipment is both physically inadequate and obsolete. A corrective shipalt is required.

In addition to the problems with the electrical power generating system mentioned above, and due to the advanced age of the COCOPA, it is important that ship's force initiate and carry out a program to replace the power distribution cabling.

C. LONG RANGE MAINTENANCE REQUIREMENTS

An essential element of overhaul maintenance planning is assuring continuity from one overhaul to the next. An influential factor in attaining this continuity is the Long Range Maintenance Plan (LRMP). Using the completion date of the COCOPA overhaul as a starting point, and utilizing the records of that overhaul, PERA prepared a plan identifying long range maintenance requirements for the COCOPA. This plan addresses the period between overhauls, and specifies major maintenance requirements that should be targeted for accomplishment during the next overhaul.

Together with the LRMP, a second group of work (that deferred during the overhaul) was identified and the associated information was provided to the ship for inclusion in and updating of the Current Ships Maintenance Projects (CSMP). The LRMP does not discuss the work entered into the CSMP, although planning for and accomplishment of that work is an integral part of long-range maintenance planning.

Probably the most important aspect of long-range maintenance planning is ship's force scheduling and accomplishment of 3M Planned Maintenance Subsystem (PMS) requirements. If ship's force pursues this program thoroughly and conscientiously, maintenance problem areas can be identified promptly and corrected before major deficiencies develop.

The long-range maintenance requirements identified for COCOPA are shown in Table III.C-1. Section A of that table lists work defined and deferred during the recent overhaul. Ship's force and/or the overhaul manager (COMSERVPAC/COMSERVGRU) should start now to plan and budget for its accomplishment. Section B is work recommended for accomplishment during the next overhaul that requires actions by the overhaul manager early in the ROH requirements planning phase. Long-lead-time material must be ordered, or preoverhaul testing and inspection has to be scheduled to firm up repair requirements. Section C is work that should be given high priority for accomplishment during the next overhaul. For most of this work, preoverhaul testing should not be required. Section D identifies PMS-related actions whose accomplishment during the period between overhauls is considered especially important in preparation for the next overhaul.

No attempt has been made to include programmed ship alterations into this plan. It is considered that these are adequately handled by existing programs under the FMP.

The work deferred had no impact on the overall quality of the COCOPA overhaul, or on the ability of the ship to perform its assigned tasks and missions.

TABLE III.C-1. DEFERRED WORK/LONG-RANGE MAINTENANCE ACTIONS,
USS COCOPA (ATF-101) (Sheet 1 of 2)

| EIC | Description | Remarks | Est. Cost. (\$) |
|---|--|---|-----------------|
| A. WORK DEFINED AND DEFERRED DURING 1973/74 ROH | | | |
| 3300 | Power Distribution Cabling | Ship's force must initiate a program to pull old cabling and replace many distribution cables. Some cable replacement will be required during the next ROH. | 50,000 |
| 4701 | 2.5-kW Emergency Generator | Develop a shipalt to replace generator with a larger, modern unit. | |
| A100 | Shell Plating | Extensive repairs conducted during this ROH; marginal areas deferred to next ROH. | 30,000 |
| B. REPAIRS RECOMMENDED FOR NEXT ROH REQUIRING LLTM | | | |
| YC04 | Boat Davits | Repair or replace. | |
| C. OTHER LONG-RANGE MAINTENANCE REQUIREMENTS | | | |
| 310U | Nos. 1 & 2 Ship Service Diesel Engines | Overhaul | 40,000 |
| 310W | Ship Service Generator Mufflers | Inspect/repair three (3). | 7,500 |
| A501 | Deck Plates B-1, B-2 | Aluminum deck plates must be replaced with steel. Lower level B-1 complete. Ship's force has deck plate material on order. | |
| C805 | Lube Oil Settling Tank | Replace coils. | |
| LJ00 | Navigation Lights | Modify navigation lights to conform with 1972 international regulations. Shipalt being prepared. Present dual tasks light array is unsatisfactory. | |

TABLE III. C-1. (Sheet 2 of 2)

| EIC | Description | Remarks | Est. Cost (\$) |
|--|--|---|----------------|
| C. (Continued) | | | |
| T10A | Steam Heat Piping | Ship's force replace. | |
| TH00 | Steam Supply and Drain Piping | | |
| TM03 | Anchor Chain | Replace six shots. Ship's force should order chain. | |
| D. PMS ITEMS (SHIP'S FORCE ACCOMPLISHMENT) | | | |
| 1806 | Salvage Equipment | | |
| 1807 | Diving Equipment | | |
| 310U | Ship Service Diesel Generators | | |
| 4000 | Electrical Safety Devices | | |
| 4400 | Power Distribution Cabling | | |
| C000 | Main Propulsion Diesel Engine, Reduction Gears, Generators, Motors | | |
| T100 | Auxiliary Boiler | | |
| T500 | Refrigeration System | | |
| TF00 | Compressed Air Systems | | |
| TK00 | Evaporators | | |
| TM00 | Deck Machinery Tow Machine | | |

D. RECOMMENDATIONS

1. For the Ship

It is recommended that ship's force personnel of the COCOPA take the following actions:

- a. Maintain an active program of replacing steam and drain piping and power distribution cabling.
- b. Ensure that the CSMP is up to date and accurately reflects the condition of the ship following overhaul. Completed action reports should be submitted for previously deferred work items accomplished during the overhaul. Work items not accomplished should be reviewed and revised as necessary to reflect their status at the end of the overhaul.
- c. Follow-up on and ensure receipt of updated record plans and documents that reflect the condition of the ship at the end of overhaul.
- d. Take action as necessary to accomplish deferred work/long range maintenance items, as discussed in Section III. C.

2. For the Class

It is recommended that for ATF-96 class ships, the type commander, with assistance from PERA and the ships, accomplish the following:

- a. Plan for and accomplish a series of habitability studies and incorporate the results into future alteration and overhaul planning. The objective of this action is to update priority of accomplishment and obtain the necessary data to authorize early development of plans and ordering of material.
- b. Review existing alterations to determine new equipment/material requirements and take action as needed to obtain these items, e. g., replacement of auxiliary ship-service generator sets and air compressors.
- c. Take follow-up actions as required to resolve electrical power requirements and availability for these ships, and provide for accomplishment of any modifications during the next overhaul.

- d. Analyze as required INSURV reports and requests that shipalts or AERs be prepared. Several Part I INSURV discrepancies have been noted on all ships of the class. Some examples are the obsolete 2.5 kW emergency generator; lack of machinery-space access trunks, a thermopneumatic magazine sprinkler system, and a switchboard splash shield; several magazine discrepancies, etc.

3. Standardized ROH Work Requests (Form 4790.2K)

It is recommended that a program to develop standardized work requests and overhaul specifications for ATF class ships be actively pursued. ARINC Research is currently developing a standard-work package under contract with COMSERVPAC. Experience gained on COCOPA was utilized on other ATF overhauls in FY 74.

4. For PERA (CSS)

It is recommended that PERA take the following actions with respect to advance overhaul planning:

- a. Revise the planning milestone tasks to incorporate the most recent procedures and techniques.
- b. Analyze the reports and documents required to support overhaul planning, and issue appropriate specifications for their preparation and distribution.
- c. Actively pursue relationships with various SUPSHIP organizations to develop better understanding of the PERA functions and the need for interchange of advance planning data.
- d. Review the need for more active participation of PERA during the overhaul management phase.
- e. Increase the emphasis on advance material definition and procurement for overhauls.
- f. Select and task an organization to develop and maintain type commander AER-class drawings. One of the difficulties encountered in the planning process was obtaining drawings for the type commander's AERs. No activity is tasked to maintain class drawings

for these alterations. This situation leads to delays and unnecessary expenditure of design funds.

- g. Increase distribution of the Fleet Integrated Logistics Support (FILS) report, for example to the Naval Material Management Field Office and Supply Operations Assistance Program teams.

E. EVALUATION/USEFULNESS

1. PERA Products to Ship/Industrial Activity

- a. Ship Systems Definition and Index (SSDI). The SSDI was found very useful by ship's force, supporting them in assembling a comprehensive work package.
- b. Integrated Work Package (IWP) Summary Report. The IWP was utilized by the ship and the type commander as a record of screening action and as a tool in updating the CSMP.
- c. POT/I Plan. The POT/I reports on deck machinery were of marginal use to the ship because of their poor quality. For future overhauls, the results expected from specific tests and inspections should be better defined. The electronics POT/I was very beneficial, as it identified not only industrial activity work items but tender/DATC and ship's force work as well.
- d. Tradeoff Analysis. Results of a tradeoff analysis were provided to the overhaul manager prior to the overhaul tradeoff conference, giving him the data necessary to authorize the most effective overhaul work package.
- e. FILS Report. FILS program information was not utilized by the industrial activity.

2. Resource Effectiveness

- a. Ship's Force. Ship's force personnel were hindered in preparing their work package by the late scheduling of the INSURV inspection. However they did generate an adequate package.
- b. RESUPSHIP. RESUPSHIP was cooperative in providing estimates and making personnel available to discuss the unwritten specifications. During the overhaul, it became apparent that their workload prevented timely response and investigation of IDR's and design problems.

- c. PERA(CSS). PERA(CSS) personnel screened the work package and presented it to RESUPSHIP approximately one month ahead of the requested date. PERA conducted several major tasks in behalf of the overhaul manager for his concurrence, including a screened work package, a POT/I plan, and a tradeoff analysis. This contribution, together with continuous liaison, permitted the overhaul manager to concentrate his efforts on the management of the overhaul.