

AD-A056 548

O'BRIEN AND GERE ENGINEERS INC PHILADELPHIA PA JUSTIN--ETC F/G 13/2
PHASE I INSPECTION REPORT. NATIONAL DAM SAFETY PROGRAM, BOONTON--ETC(U)
MAY 78 J J WILLIAMS DACW61-78-C-0052


UNCLASSIFIED

NL

1 OF 1
AD
A056548



END
DATE
FILMED
9-78
DDC



AD A056548

AD No. _____
ENC FILE COPY

LEVEL II

①

PASSAIC RIVER BASIN
ROCKAWAY RIVER & TROY BROOK,
MORRIS COUNTY

NEW JERSEY
BOONTON DAM


&

PARSIPPANY DIKE

PHASE I INSPECTION REPORT

NATIONAL DAM SAFETY PROGRAM

NJ00354 & NJ00546



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE - 2D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

MAY 78 07 14 027

Approved for public release;
distribution unlimited

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NJ00354 & NJ00546	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report, National Dam Safety Program, Boonton Dam & Parsippany Dike, Morris County, New Jersey		5. TYPE OF REPORT & PERIOD COVERED 9 FINAL rept.
6. AUTHOR(s) John J. Williams, P.E.	7. CONTRACT OR GRANT NUMBER(s) 15 DACW61-78-C-0052	8. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS O'Brien & Gere Engineers, Inc., Justin & Courtney Division 1617 J.F. Kennedy Blvd., Phila., PA 19103	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, Pennsylvania 19106	12. REPORT DATE 11 MAY 1978	13. NUMBER OF PAGES 88 12/95p.
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)	15. SECURITY CLASS. (of this report) Unclassified	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) D D C RECEIVED JUL 19 1978 RESOLVED E		
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia, 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) National Dam Safety Program Dam Inspection Report Phase I Boonton Dam, N.J. Parsippany Dike, N.J. Dams - N.J.		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's ade- quacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE-2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

IN REPLY REFER TO

NAPEN-D

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, New Jersey 08621

ACCESSION for	
NTIS	White Section ☒
DOC	Buff Section ☐
UNANNOUNCED	☐
JUSTIFICATION	
BY	
DISTRIBUTION/AVAILABILITY CODES	
Dist.	AVAIL. and/or SPECIAL
A	

3 JUL 1978

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Boonton Dam and Parsippany Dike Dam in Morris County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given on the first three pages of the report.

Based on visual inspection, available records, calculations and past operational performance, Boonton Dam and Parsippany Dike are judged to be in good condition. However, the spillway is considered to be inadequate as the Probable Maximum Flood (PMF) would overtop the dam embankment by 1.1 feet (spillway gates down) or 1.5 feet (spillway gates up). With gates down, the spillway will accommodate approximately 1/2PMF. The dike would not be overtopped under either PMF or 1/2PMF. To insure adequacy of the structures, the following actions, as a minimum, are recommended:

a. Hydrologic and hydraulic investigations and engineering studies should be initiated within three months of the date of approval of this report to determine corrective action required to increase the capacity of the spillway and obtain adequate freeboard to prevent overtopping of the dam. Construction of an improved spillway should commence in calendar year 1979. An engineering study and necessary modifications to automate the operation of the bascule gates should also be accomplished within this time frame. Due to the potential for overtopping of the dam, a detailed emergency operation, drawdown and warning system should be developed by the owner within the next two months.

b. Engineering investigations should be initiated within four months of the date of approval of this report to determine the need for post-

NAPEN-D

Honorable Brendan T. Byrne

tensioned tendons, to design the necessary slope protection repairs, to investigate the condition of the gates, to install piezometers to monitor pore pressures, to monitor the seepages from the south embankment and dike, and to investigate the cause of the sinkholes downstream of the gravity dam. Any corrective action deemed necessary as a result of these investigations should be initiated during calendar year 1979.

c. Within one year of the date of approval of this report, the below noted actions should be initiated and substantially completed:


- (1) Removal of refuse dump at toe of dam.
- (2) Removal of trees and brush from the embankment and replacement thereof with suitable ground cover.
- (3) Clean or replace screens at intakes.
- (4) Establish regular observation of minor surface subsidences in earth embankment extensions and seepages at surface cracks in dam.

Two copies of the report are being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congresswoman Millicent Fenwick of the Fifth District. Under the provisions of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, thirty days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia, 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Safety Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely yours,


HARRY V. DUTCHYSHYN
Colonel, Corps of Engineers
District Engineer

1 Incl
As stated

Cy Furn:
Mr. Dirk C. Hofman, P.E.
New Jersey Dept. of Environmental Protection

PASSAIC RIVER BASIN

**Name of Dam: Boonton Reservoir Dam
County and State: Morris County, State of New Jersey
Inventory Number: NJ 00354**

**Name of Dam: Parsippany Dike
County and State: Morris County, State of New Jersey
Inventory Number: NJ 00546**

**PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**

**Prepared by: O'Brien & Gere Engineers, Inc.
Justin & Courtney Division**

**For: United States Army Engineer District, Philadelphia
United States Custom House
2nd & Chestnut Street
Philadelphia, Pennsylvania 19106**

Date: May 14, 1978

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Boonton Reservoir Dam
Parsippany Dike

State Located New Jersey
County Located Morris County
Stream Rockaway River
Date of Inspection April 14, 1978

ASSESSMENT OF
GENERAL CONDITIONS


Boonton Reservoir Dam, according to construction drawings, is a masonry gravity structure about 2,150 feet long and 120 feet high at its' maximum section. A 300 foot gated spillway is constructed at the northern end of the structure. The masonry dam is extended on both ends by earth embankments. Parsippany Dike, a 3,200 foot long earth dike with a maximum height of 30 feet is located at the southern end of the reservoir and completes the impoundment facility.

A visual inspection of the reservoir complex revealed no external evidence of structural or embankment instability. The stone facing on the non-overflow section of the masonry dam is in excellent condition. However, items requiring remedial work or further investigation were noted and are described within this report.

Limited hydrological and hydraulic investigations of the watershed area and dam were performed. In accordance with the Recommended Guidelines for Safety Inspection of Dams, the Probable Maximum Flood (PMF) was developed and routed through the reservoir. The results indicate that the PMF would overtop the non-overflow section of the masonry dam and earth embankments by 1.1 feet with the spillway gates in the lowered position and 1.5 feet with the gates in the raised position; the PMF, however, would not overtop the dike. Further analysis indicates that the spillway could accommodate approximately the $\frac{1}{2}$ PMF without overtopping the dam and earth extensions provided that the bascule gates are in the lowered position.

Stability analyses of the masonry gravity dam (non-overflow section) were performed with consideration of seven different loading conditions (See Appendix A-48). The analyses indicate that the resultant falls slightly outside the middle third under normal loading conditions and significantly outside the middle third under severe loading conditions. Tensile stresses are developed in the upstream face under all loading conditions analyzed. The analysis also indicates that the structure appears safe relative to sliding under the assumed conditions.

O'BRIEN & GERE ENGINEERS INC.
JUSTIN & COURTNEY DIVISION


John J. Williams, P.E.
Vice President




Based on visual inspection, available records, calculations and past operational performance, Boonton Dam and Parsippany Dike are judged to be in good condition. However, the spillway is considered to be inadequate as the Probable Maximum Flood (PMF) would overtop the dam embankment by 1.1 feet (spillway gates down) or 1.5 feet (spillway gates up). With gates down, the spillway will accommodate approximately $\frac{1}{2}$ PMF. The dike would not be overtopped under either PMF or $\frac{1}{2}$ PMF. To insure adequacy of the structures, the following actions, as a minimum, are recommended:

a. Hydrologic and hydraulic investigations and engineering studies should be initiated within three months of the date of approval of this report to determine corrective action required to increase the capacity of the spillway and obtain adequate freeboard to prevent overtopping of the dam. Construction of an improved spillway should commence in calendar year 1979. An engineering study and necessary modifications to automate the operation of the bascule gates should also be accomplished within this time frame. Due to the potential for overtopping of the dam, a detailed emergency operation, drawdown and warning system should be developed by the owner within the next two months.

b. Engineering investigations should be initiated within four months of the date of approval of this report to determine the need for post-tensioned tendons, to design the necessary slope protection repairs, to investigate the condition of the gates, to install piezometers to monitor pore pressures, to monitor the seepages from the south embankment and dike, and to investigate the cause of the sinkholes downstream of the gravity dam. Any corrective action deemed necessary as a result of these investigations should be initiated during calendar year 1979.

c. Within one year of the date of approval of this report, the below noted actions should be initiated and substantially completed:

- (1) Removal of refuse dump at toe of dam.
- (2) Removal of trees and brush from the embankment and replacement thereof with suitable ground cover.
- (3) Clean or replace screens at intakes.
- (4) Establish regular observation of minor surface subsidences in earth embankment extensions and seepages at surface cracks in dam.


APPROVED: 

HARRY V. DUTCHYSHYN
Colonel, Corps of Engineers
District Engineer

DATE: 3 July 1978



VIEW ALONG DOWNSTREAM FACE OF DAM



OVERFLOW SPILLWAY AND DOWNSTREAM CHANNEL

TABLE OF CONTENTS

<u>TEXT</u>	<u>PAGE</u>
Assessment of General Conditions	
Section 1 - Project Information	1
Section 2 - Visual Inspection	6
Section 3 - Hydraulic/Hydrologic	9
Section 4 - Structural Stability	10
Section 5 - Assessment/Recommendations/ Remedial Measures	12

FIGURES

Figure 1 - Vicinity Map
Figure 2 - Area Map
Figure 3 - Geologic Map
Figure 4 - Plan of the Dam
Figure 5 - Plan and Section of the Dam through Sluice-way
Figure 6 - Plan and Section of the Dam through Lower Gate House
Figure 7 - Plan and Cross-Sections of Parsippany Dike

PHOTOGRAPHS

APPENDIX

Field Inspection Report	A-1 to A-14
Hydrologic and Hydraulic Calculations	A-15 to A-43
Stability Analyses	A-44 to A-55

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
NAME OF DAMS BOONTON RESERVOIR DAM ID# NJ00354
PARSIPPANY DIKE ID# NJ00546

SECTION I - PROJECT INFORMATION

1.1 GENERAL

a. Authority - This report is authorized by the Dam Inspection Act, Public Law 92-367, and has been prepared in accordance with contract #DACW 61-78-C-0052 between O'Brien and Gere Engineers, Inc., Justin and Courtney Division, and the United States Army Corps of Engineers, Philadelphia District.

b. Purpose of Inspection - The purpose of this inspection is to evaluate the structural and hydraulic conditions of Boonton Reservoir Dam, Parsippany DiKE, and appurtenant structures, and to determine if the dam or dike constitute a hazard to human life or property.

1.2 PROJECT DESCRIPTION (Information was provided by Jersey City Water Works)

a. General - Boonton Reservoir Dam and Parsippany DiKE are located on the Rockaway River; the axis of the main dam intersects the southern corporate limits of the town of Boonton in Morris County, New Jersey. The dam and dike are owned and operated by the Jersey City Water Works and are used to store and supply water for the community of Jersey City, New Jersey. Construction of the impoundment and water intake works began in 1892, and the entire project was completed in 1905.

The main dam is predominantly a masonry gravity structure (cyclopean masonry construction) extended at each end by earth embankments which tie into the abutments. The spillway of the masonry dam is an overflow structure equipped with a crest hinged (Bascule) gate which is supported at midpoint by a concrete and masonry pier. Parsippany DiKE is an earthen structure with a concrete core wall; the dike is located at the southern end of the reservoir. The upstream face of the dike consists of riprap covered with a grout surface.

In order to meet system demands, water is withdrawn from the reservoir through four gates located at two levels of an intake tower. Four butterfly valves located in the lower gate house structure at the toe of the dam are used to control the flow. Renovations are underway to automate the water supply system.

Two forty-eight inch diameter pipes are located through the base of the masonry dam and are used periodically to flush sediment from the reservoir bottom.

Bascule gates installed on the spillway crest in 1955 are normally raised in the spring of each year to increase reservoir storage. The gates are lowered in the fall when additional storage is not required.

Routine inspection of the dam is conducted by operating personnel. No flood warning system is in existence.

b. Dam Size and Hazard Classification - The maximum height of the dam is approximately 120 ft.. The reservoir volume to the top of the dam is about 32,000 acre feet. Therefore, the dam is in the large size category as defined by the Recommended Guidelines for Safety Inspection of Dams.

The Boonton Reservoir Dam is located upstream of a residential community and a significant loss of life and damage to property could be expected if the dam were to fail. Therefore, the dam is in the high hazard category as defined by the Recommended Guidelines for Safety Inspection of Dams. The spillway design flood required for hydraulic analysis is the Probable Maximum Flood (PMF).

c. Dike Size and Hazard Classification - The maximum height of the dike is approximately 30 ft.. The reservoir volume within this range is about 14,000 acre feet. Therefore, the dike is in the intermediate size category as defined by the Recommended Guidelines for Safety Inspection of Dams.

Parsippany Dike is located adjacent to a commercially developed area and a significant loss of life and damage to property could be expected if the dike were to fail. Therefore, the dike is in the high hazard category as defined by the Recommended Guidelines for Safety Inspections of Dams. The design flood required for hydraulic analysis is the Probable Maximum Flood (PMF).

1.3 PERTINENT DATA

a. Drainage Area - According to United States Geological Survey data, the total drainage area contributing to Boonton Reservoir is about 119 square miles. Several impoundments are located within the drainage area which serve to reduce inflow to the reservoir.

b. Discharges at Damsite - According to the records of the Jersey City Water Works (J.C.W.W.) average demand varies between 56

and 62 mgd with a peak demand of 75 mgd. Spillway flows, with the reservoir at maximum pool elevation, (310.25), are approximately 11,000 cfs and 5,000 cfs with gates in the lowered and raised positions respectively. The maximum average daily discharge according to J.C.W.W. records dating from January 1950 was about 500 cfs and occurred on April 8, 1969. The State of New Jersey DEP requires a minimum discharge of 7 mgd (11 cfs) for low flow augmentation downstream.

c. Elevations (above MSL) (from drawings supplied by J.C.W.W.)

Top of masonry dam and earth embankment - 310.25
Spillway crest (bascul gates lowered) 305.25
(bascul gates raised) - 307.25
Top of dike at southern end of reservoir - 312.25

d. Reservoir Data (from USGS Quad Sheets - 7.5 minute series and drawing provided by J.C.W.W.)

Storage @ maximum pool (el. 310.25) - 32,000 ac.ft.
Storage @ spillway crest (el. 305.25) - 28,000 ac.ft.
Storage @ spillway crest with bascul gates raised (el. 307.25) - 29,500 ac.ft.
Surface area @ maximum pool (el. 310.25) - 850 ac.
Surface area @ spillway crest (el. 305.25) - 800 ac.

e. Dam Data (from drawings supplied by J.C.W.W.)

Masonry Dam

Type - masonry gravity (cyclopean masonry construction)
Length - 2,150 feet
Height - 120 feet
Top Width - 17 feet
Side slopes - upstream - 1 horizontal:20 vertical (below el. 255), downstream - .56 horizontal:1 vertical (below el. 297.75)

Earth Embankment Extensions (from drawings supplied by J.C.W.W.)

Type - earth embankment
Length- south embankment - 500 feet, north embankment 600 feet
Height - 45 feet maximum (estimated from plan drawings)
Top Width - 17 feet (estimated)
Side slopes - 2 horizontal:1 vertical (estimated from plan drawings)
Impervious Core - No information available.
Cutoff - No information available.

Dike At Southern End of Reservoir (Parsippany Dike)

(from drawings supplied by J.C.W.W.)

Type - earth embankment

Length - 3,200 feet

Height - 30 feet maximum (estimated from plan drawings)

Top Width - 12 feet

Side Slopes - 2 horizontal:1 vertical

Impervious Core - concrete (to el. 306.75)

Cutoff - concrete (to depth determined by the Engineer during construction)

f. Outlet Data - (from drawings supplied by J.C.W.W.) A water intake tower is located at the masonry dam about 200 feet from the south end. The tower consists of parallel risers each with a 4 foot by 4 foot gated opening at elevation 268.75 and a 8 foot by 4 foot gated opening at elevation 259.75. Flow from the intake tower is regulated by four butterfly valves located at the downstream toe of the dam and is released to the water supply aqueduct supplying Jersey City. (See Figure 6)

Two forty-eight inch diameter pipes, extending through the masonry dam are used to flush bottom sediment deposits. The invert for the intake is at elevation 205 and the discharge elevation is 201.88. Flow is regulated by two thirty-six inch valves in series in each pipe (See Figure 5)

g. Spillway Data (from drawings supplied by J.C.W.W.)

Type - concrete overflow weir

Length - 300 feet

Gates - bascule

Crest Elevation - bascule gates lowered 305.25

bascule gates raised -307.25

Downstream Channel - The downstream channel is surfaced with granitic type rock set in grout. An energy dissipator consisting of large rocks set in place has been constructed about 400 feet downstream of the dam.

h. Flood Elevations at the Dam and Dike (Local Datum)

Flood crest elevation were developed for the probable maximum flood with the bascule gates in the lowered and raised positions.(See Hydraulic/HYdrologic Section)

PMF Elevation (feet)

--bascule gates lowered - 311.3

--bascule gates raised - 311.7

i. Engineering Data - The engineering data made available for review of Boonton Reservoir Dam included:

--Survey sheet of dam and impoundment dated April 6, 1915.

--Sketch showing section through sluice way and proposed new 36" gates at end of same dated 1914.

--Parsippany Dike, general plan and cross-sections dated August 1, 1902.

--Main Dam at Boonton, plans of intake and foundations of lower gate house approved April 14, 1902.

--Plan showing layout of dam and lower gate house with new piping installation; Boonton, New Jersey dated September 21, 1934.

The drawings reproduced herein were provided by the J.C.W.W. but do not necessarily represent existing conditions due to lack of updating.

SECTION 2 - VISUAL INSPECTION

2.1 FINDINGS

a. General - The field inspection for Boonton Dam, Parsippany Dike and reservoir, was conducted on April 14, 1978. The air temperature was about 50°F with partly cloudy skies. Wind speed was about 30 mph at reservoir surface. The depth of water flowing over the spillway at the time of inspection was about 0.2 feet.

No underwater areas were inspected.

b. Dam - The masonry dam is a gravity structure of cyclopean masonry. The alignment of the dam crest appeared straight, which would indicate no significant settlement or lateral movement of the structure. The large granitic stones used for the facing of the structure appear to be in excellent condition. Some evidence of joint deterioration was found in the stone coping on the south side of the masonry dam.

The concrete serviceway along the crest is cracked and has deteriorated in several areas. Pipe extensions, that appear to be filled with grout, were found at three locations along the serviceway. However, according to the owner's representative, no known internal grouting of the structure has taken place.

The bascule gates located on the overflow spillway were in the lowered position during the inspection. According to J.C.W.W. personnel, the gates are operated by a manually controlled hydraulic system and only raised during normally high runoff periods to provide additional storage capacity during the summer months.

The gate house located above the intake tower contains the controls for the four sluice gates. The equipment is antiquated, and one gate which has been removed is corroded and in very poor condition. Operating personnel indicated that it was difficult to remove the gate: The shaft had to be flame-cut in order to complete the task. It was also stated that the screens in the intake area are unable to be cleaned and cannot be removed.

Flowing water was located at the toe of the masonry dam (non-overflow section) at the south embankment. The exact source of the flow was not apparent; however, flow was clear and estimated at two to three gallons per minute. The drain channel extends for about 150 feet and terminates at an area where random fill and trash has been dumped. This fill or "dump" is located between the lower gate house and the toe of the dam.

Water was observed seeping through the downstream face of the masonry dam (non-overflow section) at three locations between the south embankment and the spillway. The seep is sufficient to keep the stone damp. The fill adjacent to the downstream toe for most of the length of the dam is in a moist condition and readily settles when subject to foot traffic.

A crack in the jointing was located on the downstream face about 300 feet from the north embankment. Water is seeping from the crack at a rate to keep the stone moist.

A number of sinkholes in the toe area to the north of the spillway were noted. The largest concentration appeared in an area approximately thirty feet by twenty feet. Operating personnel indicated that they were aware of this condition and have monitored the holes in an effort to detect indications of flowing water. The sinkholes have apparently existed for a long time and may have occurred soon after construction was completed. Another sinkhole was located at the toe of the masonry dam (non-overflow section) just south of the bottom discharge structure. The hole was about three feet deep and twenty inches in diameter and appears to be a result of surface drainage. No evidence of water was detected in any of the sinkholes.

Some vegetation in the form of vines was observed on the downstream face of the dam. In addition, the toe area was fairly well covered with brush and small trees.

Water was observed discharging from a small pipe located in the bottom discharge structure. According to operating personnel, the discharge is from the valve chamber located within the dam (see Figure 5)

c. Earth Embankment Extensions - The masonry dam (non-overflow section) is extended on each end by earth embankments. The downstream slope of the embankments are covered with grass and no indication of erosion was noted. The south abutment, however, contained a number (nine were counted) of holes apparently caused by burrowing rodents. Operating personnel are aware of this problem and are actively engaged in a program to eliminate the rodents.

The upstream slope of the embankment is protected by a facing of grouted riprap. Failure of this facing was noted at a few areas along both embankments. A subsidence in the riprap facing, extending into the top of the embankments, is noticeable in both earth embankment extensions, approximately fifty feet from either end of the masonry dam (non-overflow section). In both cases, the subsidence is not appreciable.

d. Parsippany Dike Parsippany Dike, an earthen structure approximately 3,200 feet long, is located at the southern end of the reservoir. The upstream slope is protected by riprap covered with a grout surface. Wave action has apparently eroded the fill just below the grouted surface material, and bridging of the grout surface is evident. This bridging has broken down in certain areas exposing the stone and random fill. A few small holes, probably caused by rodents, and two small tree stumps were also noted along the crest.

The downstream slope is grass covered along most of its length. A well established growth of brush and fairly large sized trees are located on the downstream slope at the right end (looking toward the reservoir) of the dike. Seepage and moisture, at the toe of the dike, were noted in localized areas for a total of about one half the embankment length.

e. Reservoir Area - The reservoir perimeter is uninhabited and access to the reservoir is discouraged by fencing.

f. Downstream Channel - The spillway channel is lined with rock set in place. An energy dissipator is constructed about 400 feet downstream of the dam. The immediate area below the dam is sparsely populated, however, the community of Lower Montville is located about three miles downstream of dam and has a considerable population that could be exposed to flooding.

2.2 EVALUATION

The masonry dam (non-overflow section) shows no significant external signs of deterioration. The large surface stones used in the cyclopean construction, the joints and the joint material all appear to be in excellent condition. However, the upstream surface material of the earth embankments has collapsed in certain areas of the dike and is showing signs of deterioration in areas along the extensions of the main dam.

SECTION 3 - HYDROLOGY AND HYDRAULICS

In accordance with the criteria established by the Recommended Guidelines for Safety Inspection of Dams, the Spillway Design Flood used to evaluate the hydraulic capabilities of Boonton Reservoir Dam is the Probable Maximum Flood (PMF).

The PMF was calculated from probable maximum precipitation data as published in Hydrometeorological Report No. 33.

The rainfall data was modified to account for basin size and storm characteristics by using standard reduction factors. The HEC I computer program was employed to develop the inflow hydrograph and flood route the PMF through the reservoir facility. Two separate routings were performed: The results indicate that the dam and earth embankment extensions would be overtopped by 1.1 feet when the bascule gates are in the lowered position and 1.5 feet when the bascule gates are in the raised position. The peak discharges are about 26,900 cfs and 26,800 cfs respectively. The analysis also indicates that the PMF would not overtop the dike based on the crest elevation shown on the drawings provided (see Figure 7)

A drawdown analysis was performed to estimate the time required to drain the reservoir by means of the bottom discharge structure (2 - 48 inch diameter pipes). The water surface was assumed to be at the spillway crest (bascule gates lowered) with no inflow to the reservoir. Under these conditions, the estimated time to drain the reservoir is about twenty-five days. This represents a minimum time with no consideration given to downstream constraints such as safe discharge velocities or flows.

SECTION 4 - STRUCTURAL STABILITY

4.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observation - No significant indications of structural instability were noted during the inspection of the masonry gravity dam, earth embankment extensions or dike.

b. Design and Construction Data - Drawings, design data and construction history relative to the Boonton Dam and Parsippany Dike were provided by J.C.W.W.. Cross section drawings of the masonry dam were made available, and the maximum section was used for analyses. Information pertaining to the design of the spillway apparently is not available.

c. Operating Records - Inspection of the operating records of the J.C.W.W. revealed reservoir water surface elevations dating from to 1950. The maximum water surface elevation recorded for the period of record is 307.89. Operating personnel also reported that layers of ice up to twenty-four inches in thickness had developed during severe winter weather conditions.

d. Post Construction Changes - The original piping arrangement for the water supply system was revised in 1934. Renovations are underway to automate the water supply system.

Crest hinged (Bascule) gates were installed on the existing spillway in 1955 to increase reservoir storage. Under normal operating procedures, the gates are raised in the spring and lowered in the fall.

e. Seismic Stability - The dam is located in the Triassic Highlands physiographic subprovince of northern New Jersey and is founded on fine to medium grained, red sandstone and shale of the Triassic Newark Group, Brunswick formation (lithofacies), as described on the Geologic Map of New Jersey, 1950.

Rock outcrops were observed downstream of the masonry dam in the discharge area and consists of medium thick to thin beds of red shale and sandstone dipping upstream at a shallow angle. No bedrock was observed in the dike area location at the southern end of the reservoir.

Although the dam is in proximity of the Ramapo fault, which trends northeast-southwest, crossing the Rockaway River approximately one mile upstream, there does not appear to be any seismic stress related problems within the structures inspected. However, since

recent studies have indicated an increase in recorded seismic activity along the Ramapo fault, consideration should be given to its possible effects on the stability of the Boonton Reservoir Main Dam structure.

The dam and dike are located in seismic zone 1, as shown on the Seismic Zone Map of the Contiguous United States. Under the Recommended Guidelines for Safety Inspection of Dams, further analysis relative to seismic loading is not required for Phase I investigation. However, due to the proximity of the Ramapo fault, a seismic analysis was conducted using the more conservative Seismic Zone 2 coefficient.

Factual data pertaining to foundation investigations are not available. Therefore, design assumptions concerning foundation rock characteristics were based on information obtained from general geologic maps and field observations made during the course of the inspection.

f. Evaluation - Analyses of the structural stability of the non-overflow section of the main dam considered seven different loading conditions. The results of these analyses are summarized in the appendix. The resultant falls slightly outside the middle third for normal loading conditions. Under severe loading conditions (earthquake and PMF), the resultant falls a significant distance outside the middle third of the base.

SECTION 5 - ASSESSMENT/RECOMMENDATIONS/REMEDIAL MEASURES

5.1 ASSESSMENT

The spillway is incapable of passing the PMF: overtopping of the non-overflow sections of the main dam would occur for about forty hours and considerable damage to the earth embankment extensions could reasonably be expected. However, the spillway appears to be capable of passing the $\frac{1}{2}$ PMF providing the bascule gates are in the lowered position. Parsippany Dike would not be overtopped by the PMF based on the hydrological/hydraulic computations made.

The manual operation of the spillway gates significantly reduces the spillway capacity from that proposed in the original design and severely limit the ability of the spillway to pass major flows without overtopping the non-overflow sections of the main dam.

The masonry gravity dam (non-overflow section) is considered structurally adequate under normal loading conditions, although the resultant of forces falls slightly outside the middle third. However, under severe loading conditions such as earthquake and PMF, the resultant of forces falls a significant distance outside the middle third.

The earth embankment extensions and dike appear to be stable although the upstream facing of both the main dam embankment extensions and the earth dike are in need of remedial work.

Seepage was noted at the north end of the south embankment and in localized areas along the dike. These flows are not being monitored according to operating personnel.

Sinkholes were located in the toe area downstream of the masonry gravity dam (non-overflow section). A detailed investigation of the sinkholes has not been performed.

There is no procedure for drawdown under emergency conditions, nor is there any system for flood warning.

5.2 RECOMMENDATIONS/REMEDIAL MEASURES

Additional investigations, remedial measures and recommended actions are as follows:

1. Install post-tensioned tendons to eliminate tension in the upstream face of the masonry dam and increase the overall structural stability.

2. Excavate the sinkhole area, located near the downstream toe of the masonry gravity dam (non-overflow section), to determine the cause of the depressions and need for remedial work.

3. Implement a maintenance program to repair all sections of the upstream facing of the earth embankment extensions and dike that have collapsed or show significant deterioration; or, in lieu of this, place riprap protection on the upstream face.

4. Develop an emergency drawdown procedure that could be accomplished in a minimum time taking into consideration all constraints relating to allowable downstream flows and velocities. This could include a flood warning system.

5. Continue program to protect against damage due to burrowing rodents.

6. Remove refuse dump at toe of dam.

7. Remove trees and brush from earth embankment extensions and dike.


8. Install several piezometers to monitor pore pressures in earth embankments and Parsippany Dike.

9. Initiate a system to monitor seepage that is occurring at the toe of the earth embankment extensions and Parsippany Dike.

10. Clean or replace screens at the intakes and inspect gates to determine condition and repairs required.

11. Provide for automation of bascule gates in order to restore full spillway capacity during high runoff and also allow for maximum storage when desired.

FIGURES







FIGURE 2
AREA MAP

SCALE 1"=2,000'




LEGEND

-  Trb- Brunswick Formation - shale with sandstone beds
-  Trbs- Basalt Flows - fine-grained rock
-  Trc- Brunswick Formation - conglomerate beds with quartzite or limestone pebbles
-  gpx- Pyroxene Gneiss - coarse-grained rock
-  gh- Hornblende Granite & Gneiss - fine and coarse-grained rock
-  gd- Granodiorite Gneiss - coarse-grained rock
-  hqa- Hypersthene-Quartz-Andesine Gneiss - coarse-grained rock
-  am- Amphibolite - coarse-grained rock


FIGURE 3
GEOLOGIC MAP

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC



QUALITY PRACTICABLE
ED TO DDC

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC



Length of Dam 2150 ft
Height of Dam 122 ft

APPROX 16.3 ACRES
ACQUIRED FROM T.A. DESMOND & CO.
AUG. 17, 1963 KNOWN AS PLOT A
SEE MAP PAGE 6 DESCRIPTION IN FILE

CONTAINING APPROX 31.7 ACRES
FROM CITY OF JEROME CITY PRESERVATION
& CO. AUG. 17, 1963 WITH PRESERVATION
IN FILE SEE MAP PAGE 6 DESCRIPTION IN FILE

THIS AREA
CONVERTED
TO T.A. DESMOND

IS BEST QUALITY PRACTICABLE
FURNISHED TO DDC

Length of Dam 2150 ft
Height of Dam 122.0 ft

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

Scale = 1 inch = 200 feet


CHECK SURVEY BY F.P.J.R. AND W.C.M. AUG AND SEPT. 1911

PLAN NO. 131	DATE APRIL 6 1915
PREPARED BY F. PANSING	
CHECKED BY	
APPROVED	MARCH 6 1915
CHIEF ENGINEER	
APPROVED	
DIRECTOR	
DEPT OF STREETS & PUBLIC IMPROVEMENTS	
Rev sed Dec 21-1925 PP	

Traced by F. Pansing

FIGURE 4

THIS PAGE IS BE
FROM COPY FURN




THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

SKETCH
showing section through Sluice-way and
proposed new 36" Gate at end of same

Scale 1/8" = 1 ft

B. S. S. S. S.



Section

Section through A B
showing concrete around Steel Pipe

Plan




FIGURE 5

PLAN 19-43 TR 2 CH 19

APPROVED [Signature] 19

APPROVED [Signature] 19

DEPT OF STREETS & PUBLIC IMPROVEMENT

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

SECTION THROUGH DRY AT
CENTER OF SOUTH BAY

FRONT ELEVATION

Concrete Foundation


PLAY VIEW

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG




THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

Scale of Plan, 1 inch = 80 feet



THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC


Scale of Plan, 1 inch = 30 feet



Section at G-H



Section at A-B



Original Surface

Scale of Sections, 1 inch = 10 ft



Contract No 5
Jersey City Water Supply Co
Jersey City, N.J.
Parsippany Dike
General Plan & Cross-Sections
Scale as indicated
Aug. 1, 1906

FIGURE 7

H. H. Hudson
Eng'g

PHOTOGRAPHS



CRACK AND SEEPAGE AT NORTH END OF DAM



EMBANKMENT DAMAGE BY BURROWING RODENTS
AT SOUTH END OF DAM



DISLOCATION OF GROUTED RIP RAP SLOPE PROTECTION
AT NORTH END OF DAM



FAILURE OF SLOPE PROTECTION AT DIKE ALONG THE
SOUTHERN END OF THE RESERVOIR

APPENDIX

FIELD INSPECTION REPORT

Check List
Visual Inspection
Phase 1

Name Dam Boonton Reservoir Dam County Morris State New Jersey Coordinators Mr. L. Woscyna
Parsippany Dike

Date(s) Inspection 4/14/78 Weather Partly Cloudy Temperature 50°F

Pool Elevation at Time of Inspection About 305.45 M.S.L. Tailwater at Time of Inspection N/A M.S.L.

Inspection Personnel:

Mr. J.J. Williams Mr. L.H. DeHeer Mr. R.E. Horvath
Mr. A.J. Depman Mr. C.A. Schwalbe
Mr. G.C. Elias Mr. R.E. Horvath Recorder

Accompanied By:

Mr. V. Calvarese - Chief Structural Engineer, U.S. Army Corps of Engineers, Philadelphia District
Mr. C. Brozowski - Supervising Principle Engineer, Jersey City Water Works
Mr. G. Plastoris - Watershed Superintendent, Jersey City Water Works
Mr. L. Woscyna - Civil Engineer, New Jersey Department of Environmental Protection

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SEE PAGE ON LEAKAGE		
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	Surface subsidence was noted on the crest of both earth embankment extensions about 50 feet from the ends of the masonry dam. The subsidence extends into the grouted riprap slope protection.	The subsidence is minor in both cases but should be observed at frequent intervals to detect further settlement.
DRAINS	Seepage was located at the toe of the non-overflow masonry dam near the south embankment extension. About 3 inches (2 to 3 gpm) of clear water was present at the time of inspection.	Flow should be monitored to detect any significant variations in flow quality or quantity.
WATER PASSAGES	The spillway surfacing shows no indication of deterioration and appears to be in good condition. Some repair of the grouted joints appears to have been done.	None
FOUNDATION	Not observed	None

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	The concrete serviceway located on the masonry dam crest is cracked and has deteriorated in several locations. Cracks in the downstream face of the structure were noted in four locations.	Seepage was observed at each surface crack in the downstream face of the dam. Seepage should be visually observed to detect any significant increases in flow quantities.
STRUCTURAL CRACKING	None observed	
VERTICAL AND HORIZONTAL ALIGNMENT	Vertical and horizontal alignment of the masonry dam appeared to be good.	None
MORTAR JOINTS	Not applicable	
CONSTRUCTION JOINTS	No movement could be detected in the construction joints. Deterioration of joint material was observed at some locations.	

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None Noted Holes in the earth embankments caused by burrowing rodents were noted in several locations.	Operating personnel are aware of the problem and are actively engaged in eliminating the rodents.
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None Noted	
SLOUGHING OR EROSION OF EMBANKMENT AND ADJUTENT SLOPES	See riprap failures	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Vertical and horizontal alignment of the crest appeared to be good.	
RIPRAP FAILURES	Failure of the grouted riprap slope protection on the earth embankments was noted in several locations. Some cracking of joints due to settlement was also evident. Failure of the grout surfacing on the earth dike was observed at several locations	Slope protection should be repaired.

EMBANKMENT

REMARKS OR RECOMMENDATIONS

OBSERVATIONS

VISUAL EXAMINATION OF

JUNCTION OF EMBANKMENT
AND ABUTMENT, SPILLWAY
AND DAM

No settlement or erosion was
noted at either the main dam
or Parsippany Dike locations.

ANY NOTICEABLE SEEPAGE

-Seepage was observed in the toe area at the
southern earth embankment extension junc-
tion with the masonry dam. Flow was clear
and estimated at 2-3 gpm.
-Seepage was observed in isolated areas in
the toe area of the Parsippany Dike.

Seepage flows should be
monitored to detect any
changes in flow quantity
or quality.

A6

STAFF GAGE AND RECORDER

None Noted.

DRAINS

None Noted.

GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	The sill appeared to be in good condition. No indication of distress in the masonry was noted.	
APPROACH CHANNEL	Not observed.	
DISCHARGE CHANNEL	The discharge channel is constructed of rock set in place w/grouted joints. No indication of erosion or undue settlement was noted.	Some of the grouted joints appeared to have undergone repair.
BRIDGE AND PIERS	The bridge and piers over the south half of the gated spillway appeared to be in good condition. No indications of deterioration were noted.	
GATES AND OPERATION EQUIPMENT	Gates and operational equipment appear to be in good condition. No equipment was operated during the inspection. *Note: At the time of inspection, the spillway way actively discharging under a head of about 0.2'. The bascule gates were in the lowered position.	The gate controls are being refitted for electrical operators. However, remote activation will not be provided.

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	A highway bridge is located about 4,000 feet downstream of the dam-site.	
SLOPES	No indications of slope failure were noted.	
APPROXIMATE NO. OF HOMES AND POPULATION	The area immediately downstream of the main dam is sparsely populated. However, the community of Lower Montville is located about 3 miles below the main dam. The area immediately below the Parsippany Diike is commercially developed.	A flood warning system should be implemented.

RESERVOIR

REMARKS OR RECOMMENDATIONS

OBSERVATIONS

VISUAL EXAMINATION OF

SLOPES

No indication of slope failure was observed.

SEDIMENTATION

Two 48 inch diameter drain pipes are operated periodically to flush bottom deposits.

ITEM	REMARKS
MONITORING SYSTEMS	None Noted
MODIFICATIONS	Crest hinged (bascule) gates were installed on the overflow spillway in 1955.
HIGH POOL RECORDS	High pool records dating from 1950 are available.
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None Noted
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None Noted
MAINTENANCE OPERATION RECORDS	None Noted

ITEM	REMARKS
DESIGN REPORTS	None Noted
GEOLOGY REPORTS	None Noted
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	None Noted
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None Noted
POST-CONSTRUCTION SURVEYS OF DAM	A general plan of the dam and reservoir area was prepared in 1915 and was available for review.
BORROW SOURCES.	None Noted

INSTRUMENTATION

VISUAL EXAMINATION NONUNENTATION/SURVEYS	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
	None Noted	
OBSERVATION WELLS	None Noted	
WEIRS	None Noted	
PIEZOMETERS	None Noted	
OTHER	A water surface elevation indicator is located in the upper gate house.	The indicator system is old but appears to be operational.

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
PLAN OF DAM	Not available
REGIONAL VICINITY MAP	Not available
CONSTRUCTION HISTORY	A brief description was furnished verbally by representatives of the Jersey City Water Works.
TYPICAL SECTIONS OF DAM	Typical sections of the masonry dam (non-overflow section) and dike were made available for review.
HYDROLOGIC/HYDRAULIC DATA	The reservoir stage-storage table (limited to the elevations within the operational range of the bascule gates) was provided.
OUTLETS - PLAN	Plans and details of the reservoir sluice gates and water supply gates were furnished. A minimum discharge of 7 cfs must be maintained for augmentation of downstream water supply.
- DETAILS	The spillway rating table was provided.
-CONSTRAINTS	Rainfall/reservoir records are available and a sample was provided for review.
-DISCHARGE RATINGS	
RAINFALL/RESERVOIR RECORDS	

*All information described herein was furnished by the J.C.W.W.

ITEM

REMARKS

SPILLWAY PLAN

SECTIONS

DETAILS

Not available for review.

OPERATING EQUIPMENT
PLANS & DETAILS

Crest hinged (bascule) gates are located on the overflow spillway. They are operated between the raised and lowered positions by a manually controlled hydraulic system.

HYDROLOGIC AND HYDRAULIC CALCULATIONS

SUBJECT	SHEET	BY	DATE	JOB NO
BOUNTON RESERVOIR DAM	1	RBH	6/15/78	1822.001.195

PROBABLE MAXIMUM FLOOD CALCULATIONS

DRAINAGE AREA $\approx$ 119 sq miles

① Ref: Hydrometeorological

PMP - 6 Hour Duration - 10 sq miles

Report # 33

= 26" Zone 6

② EM 1110-2-1405 dtd

8/31/59

Basin size reduction = 13%

③ DESIGN OF SMALL DAM

④ USGS QUAD SHEET

Depth Area Duration (use 6 hr duration) = 78%

Adjusted PMP $\approx$ 17.6"

Time (hrs)	% 6 Hr PMP	$\pm$ 24 Hr PMP	INC PMP	
2	65	11.4	11.4	0-6hr -78%
4	85	15.0	3.6	0-12hr -85%
6	100	17.6	2.6	0-24hr -94%
8	103	18.1	.5	
10	106	18.7	.6	
12	109	19.2	.5	
14	111	19.5	.3	
16	113	19.9	.4	
18	115	20.2	.3	
20	117	20.6	.4	
22	119	20.9	.3	
24	121	21.3	.4	

SUBJECT	SHEET	BY	DATE	JOB NO
BOONTON RESERVOIR DAM	2	REH	6/15/78	1800 001-125

Rainfall				Run-off	
Time (Hrs)	%	Σ	INCR	Σ	INCR
2	2	.4	.4	0	0
4	2	.7	.3	0	0
6	2	1.1	.4	0	0
8	3	1.6	.5	.1	.1
10	3	2.1	.5	.3	.2
12	3	2.6	.5	.5	.2
14	15	5.3	2.7	2.3	1.8
16	65	16.7	11.4	12.5	10.2
18	20	20.7	3.5	15.8	3.5
20	2	20.6	.4	16.2	.4
22	2	20.9	.3	16.5	.3
24	2	21.3	.4	16.9	.4

Increments are ranked in the
order 4, 2, 1, 3 in accordance
with E1110-2-163 (Draft)

SUBJECT	SHEET	BY	DATE	JOB NO
() BOONTON RESERVOIR DAM	3	REIT	6/15/78	1800.001.195

SNYDER'S PARAMETER'S

(Provided by U.S. Army Corps
of Engr Phil Dist.)

$$C_t = 2.90$$

$$640 C_p = 282$$

$$L = 40 \text{ MILES (estimated from quad sheets)}$$

$$L_{CA} = 20 \text{ MILES (estimated from quad sheets)}$$

$$T_p = C_t (L L_{CA})^{0.3} = 21.5$$

$$C_p = .44$$

SUBJECT	SHEET	BY	DATE	JOB NO
BOUNTON RESERVOIR DAM	4	REH	6/15/78	120000119

Stage - Discharge

Spillway Elev = 303.25

Elev (ft)	Water	(Overtopping)		cfs	
	Supply 92 cfs (avg)	$Q=300(3.33)H^{7/2}$ Spillway Release (cfs)	$Q=3200(3)H^{7/2}$ (cfs)	Sluice Gates 2-49" ϕ	TOTAL (cfs)
303.25	93	0		1040	1133
306.25		999		1046	2138
307.25		2826		1053	3972
308.25		5191		1058	6342
309.25		7992		1063	9148
310.25		11169	0	1068	12330
311.25		14682	9600	1076	25451
312.25		18502	27153	1080	46828
313.25		22605	49883	1086	73667
314.25	Y	26973	76800	1091	104957

See Sheet A25

for development of

Sluice Gate Discharge

- Avg water supply quantity was provided by IC W.W.
- Spillway and overtopping discharges were developed from information furnished by IC W.W. and generalized equations.

SUBJECT	SHEET	BY	DATE	JOB NO
BOONTON RESERVOIR DAM	5	REH	6/18/78	1000.001 195

STAGE - DISCHARGE

Spillway Elev 307.25

Elev (Ft)	Water Supply 93 cfs (ava)	Spillway Release - cfs	$Q = 32w(2) 4\frac{3}{4}$ cfs	Sluice Gates 2-48" d. cfs	TOTAL - cfs
307.25	93	0		1053	1146
308.25		299		1058	2150
309.25		2826		1063	3982
310.25		5191	0	1068	6352
311.25		7992	2600	1076	18761
312.25		11169	27153	1080	39495
313.25		14682	49322	1086	65744
314.25		18502	76800	1091	96486

SUBJECT	SHEET	BY	DATE	JOB NO.
BUNTON RESERVOIR DAM	6	REL	6/12/78	19001001.12

Stage - Storage

Assume 867 ACF/Ft relationship

Stage	Storage (ACF)	Stage	Storage (ACF)
Crest @ 305.25	0	Crest @ 307.25	0
306.25	867	308.25	867
307.25	1734	309.25	1734
308.25	2601	310.25	2601
309.25	3468	311.25	3468
310.25	4335	312.25	4335
311.25	5202	313.25	5202
312.25	6069	314.25	6069
313.25	6936		
314.25	7803		

Stage - Storage relationship was developed from
information furnished by J.C.W.W.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

JUSTIN & COURTNEY, INC.
Division of O'Brien & Gere Engineers, Inc.
PHILADELPHIA, PA

SHEET NO. 7 OF

DATE 4/21/78


COMP. BY PEH

CHECKED BY

NAME OF CLIENT USACE

PROJECT BOONTON RESERVOIR DAM

STAGE - STORAGE - AREA



JUSTIN & COURTNEY, INC.
Division of O'Brien & Gere Engineers, Inc.
PHILADELPHIA, PA

SHEET NO. 8 OF

DATE 6/20/78

COMP. BY REH


CHECKED BY

NAME OF CLIENT USACE

PROJECT BRYANTON RESERVOIR DAM

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

DETERMINATION OF SPILLWAY CAPACITY



SUBJECT	SHEET	BY	DATE	JOB NO.
BOONTON RESERVOIR DAM	9	ZEH	6/20/78	1800.001 15

PMF Summary (See HEC-I Printout)

Crest Elev	Flood Crest El.	Max Discharge (cfs)	Duration of Overtopping (h)
305.25	311.3	26883	40
307.25	311.7	26798	66

Spillway Capacity

Crest El @ 305.25	- 50 % PMF
Crest El @ 307.25	- 28 % PMF

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

SUBJECT	SHEET	BY	DATE	JOB NO
BOONTON RESERVOIR DAM	10	REH	5/1/78	1800.001 5

RESERVOIR DRAWDOWN ANALYSIS

2 - 48" DIA STEEL PIPES LENGTH = 233'

Assume OUTLET CONTROL - pipe flowing full - $Q = AV$

$$H = \frac{V^2}{2g} \left(1 + K_e + K_{\text{contr}} + K_{\text{valve}} + K_{\text{exp}} + \frac{29n^2L}{r^{1.33}} \right)$$

From KING & BRATER

	$K_e = .5$ (sq corner ent flush with wall)	
2-36 VALVES	$K_{\text{contr}} \left(\frac{d_2}{d_1} = \frac{48}{36} = 1.33 \right)$	$\approx .14 \times 2 = .28$
	K_{valve} (ASSUME VALVE IS OPEN)	$\approx .10 \times 2 = .20$
	$K_{\text{exp}} \left(\frac{d_2}{d_1} = 1.33 \right)$	$\approx .16 \times 2 = .32$
n		$\approx .02$

$$H = \frac{V^2}{2g} \left(1 + 1.3 + \frac{2.7}{2.5} \right) = 3.38 \frac{V^2}{2g}$$

$$V = \sqrt{19 H}$$

Begin drawdown at 303, Assume Water Surface
Elevation at discharge ≈ 215

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

SUBJECT	DATE	BY	DATE	JOB NO
BOONTON RESERVOIR DAM	11	REL	5/1/78	1800.001 155

WATER SURFACE EL (Ft)	HEAD (Ft)	VEL (FPS)	DISCHARGE (CFS)	DISCHARGE CFS
305	90	41	1030	
295	80	39	980	968
285	70	36	905	
275	60	34	855	842
265	50	31	779	
255	40	28	704	691
245	30	24	603	
235	20	19	477	301
225	10	14	351	
215	0	0	0	

Storage @ Elev 215 ≈ 0 A-Ft

Storage @ Elev 305 ≈ 25.770 A-Ft

Assume linear relationship

$$\frac{\Delta \text{ Stor}}{\Delta \text{ Elev}} \approx 286 \text{ A-Ft/Ft}$$

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

SUBJECT	DATE	BY	DATE	JOB NO.
BOUNTON RESERVOIR DAM	12	REH	5/1/78	1500 001 155

EL	STORAGE (ACFT)	INCR. STORAGE		DISCHARGE	TIME
		ACFT	CF	CFS	HRS
305	25,770				
		5,750	250×10^6	968	72
285	20,020				
		5,720	249×10^6	842	82
265	14,300				
		5,720	249×10^6	691	100
245	8,580				
		8,580	374×10^6	301	345
215	0				
					593 Hrs
					~ 25 days

CALCULATIONS INDICATE A MINIMUM DRAWDOWN TIME OF 25 DAYS TO DRAIN THE RESERVOIR BASED ON THE ASSUMPTIONS STATED. HOWEVER, THIS TIME FOR DRAWDOWN IS NOT REALISTIC DUE TO THE DAMAGE THAT WOULD BE CAUSED DOWNSTREAM. SOME CONSTRAINT WOULD BE REQUIRED TO INSURE SAFE DISCHARGES.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

.....
HEC-I VERSION DATED JAN 1973
UPDATED AUG 74
CHANGE NO. 01
.....

PMF ROUTING 305.25 - SLOWLY CREST EL
ADAMTON DAN + PARSHIPPANY DIKE
O-ORIE + GERE - JUSTIN + COURTNEY DIV

JOB SPECIFICATION
NQ NHR NMN IDAY IHR IMIN METRC IPLT IPRT NSTAN
48 2 0 1 0 0 0 0 2 0
JOPEL NWI
5

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 1 NRTIO= 9 LRTIO= 1

RTIOS= .10 .20 .30 .40 .50 .60 .70 .80 1.00

SUB-AREA RUNOFF COMPUTATION

ISTAO ICOMP ITECON ITAPE JPLT JPRJ INAME

HYDROGRAPH DATA

IMYOG IJMG IAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL

PRECIP DATA

NP STORM DAJ DAK
12 0.00 0.00 0.00

PRECIP PATTERN

0.00 0.00 0.00 .10 .20 .20 1.00 10.20 3.50 .40

LOSS DATA

STRKR OLTKR PTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSHX RTIMP

UNIT HYDROGRAPH DATA

TP= 21.50 CP= .44 NTA= 0

RECESSION DATA

STRTO= 0.00 ORCSN= 0.00 RTIOR= 1.00

APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNTOR CP AND TP ARE .10-11.19 AND R-17.61 INTERVALS.

UNIT HYDROGRAPH 100 END-OF-PERIOD DRAINATES, LAG= 21.56 HOURS, CP= .44 VOL= 1.00

40.	151.	311.	500.	712.	939.	1156.	1337.	1571.
1611.	1574.	1491.	1408.	1331.	1257.	1186.	1122.	1060.
946.	894.	845.	790.	754.	712.	673.	636.	601.
536.	507.	479.	452.	427.	404.	381.	360.	322.
304.	287.	271.	256.	242.	229.	216.	204.	193.
172.	163.	154.	145.	137.	130.	122.	116.	103.
98.	92.	87.	82.	78.	73.	69.	66.	62.
55.	52.	49.	47.	44.	42.	39.	37.	35.
31.	30.	28.	26.	25.	24.	22.	21.	20.
17.	16.	15.	14.	13.	12.	11.	10.	9.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

		END-OF-PERIOD FLOW					
		TIME	RAIN	EXCS	COMP Q		
2	1	2	0	0.00	0.00	0.	
	1	4	0	0.00	0.00	0.	
	1	6	0	0.00	0.00	0.	
	1	8	0	0.10	0.10	4.	
	1	10	0	0.20	0.20	23.	
	1	12	0	0.20	0.20	69.	
	1	14	0	1.80	1.80	214.	
	1	16	0	10.20	10.20	913.	
	1	18	0	3.50	3.50	2575.	
	1	20	0	0.40	0.40	5058.	
	1	22	0	0.30	0.30	8097.	
	2	0	0	0.40	0.40	11537.	
	2	2	0	0.00	0.00	15222.	
	2	4	0	0.00	0.00	18808.	
	2	6	0	0.00	0.00	21922.	
	2	8	0	0.00	0.00	28385.	
	2	10	0	0.00	0.00	26106.	
	2	12	0	0.00	0.00	26932.	
	2	14	0	0.00	0.00	26658.	
	2	16	0	0.00	0.00	25592.	
	2	18	0	0.00	0.00	26320.	
	2	20	0	0.00	0.00	23045.	
	2	22	0	0.00	0.00	21794.	
	3	0	0	0.00	0.00	20592.	
	3	2	0	0.00	0.00	19455.	
	3	4	0	0.00	0.00	18381.	
	3	6	0	0.00	0.00	17366.	
	3	8	0	0.00	0.00	16408.	
	3	10	0	0.00	0.00	15502.	
	3	12	0	0.00	0.00	14646.	
	3	14	0	0.00	0.00	13837.	
	3	16	0	0.30	0.00	13073.	
	3	18	0	0.00	0.00	12352.	
	3	20	0	0.00	0.00	11670.	
	3	22	0	0.00	0.00	11025.	
	4	0	0	0.00	0.00	10417.	
	4	2	0	0.00	0.00	9841.	
	4	4	0	0.00	0.00	9298.	
	4	6	0	0.00	0.00	8785.	
	4	8	0	0.00	0.00	8300.	
	4	10	0	0.00	0.00	7842.	
	4	12	0	0.00	0.00	7409.	
	4	14	0	0.00	0.00	7000.	
	4	16	0	0.00	0.00	6613.	
	4	18	0	0.00	0.00	6248.	
	4	20	0	0.00	0.00	5903.	
	4	22	0	0.00	0.00	5577.	
	5	0	0	0.00	0.00	5269.	
SUM		17.10	17.10	17.10	566083.		
PEAK		26932.	26566.	23301.	15177.	566086.	
3FS		26932.	26566.	23301.	15177.	566086.	
INCHES		2.00	2.00	2.00	14.24	14.25	
AC-FT		13180.	46241.	90350.	33616.	33616.	
HYDROGRAPH AT STA		1 FOR PLAN 1, RTIO 1					
0.		0.	2.	21.	91.	506.	
010.		1522.	1881.	2192.	2438.	2611.	259.
2432.		2179.	2059.	1966.	1838.	1737.	2666.
1354.		1307.	1167.	1103.	1042.	984.	1580.
784.		700.	661.	625.	590.	558.	1468.
							878.
							527.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

3									
HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 2									
0.	0.	1.	5.	14.	43.	181.	515.	1012.	
1619.	2307.	3044.	4384.	4877.	5221.	5386.	5332.	5118.	
4868.	4609.	4359.	3891.	3676.	3473.	3282.	3108.	2929.	
2767.	2615.	2470.	2334.	2205.	2083.	1968.	1860.	1660.	
1560.	1482.	1400.	1323.	1250.	1181.	1115.	1054.		
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME									
5386.	5313.	4660.	3035.	113217.					
INCHES	42.	1.46.	2.85.	2.95.					
AC-FT	2636.	9249.	18872.	18723.					
HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 3									
0.	0.	1.	7.	21.	64.	274.	773.	1518.	
2429.	3461.	4566.	5643.	6577.	7315.	7832.	7997.	7678.	
9728.	9218.	8538.	7837.	7037.	6210.	5210.	4922.	4396.	
4151.	3922.	3705.	3308.	3125.	2952.	2789.	2635.	2490.	
2352.	2223.	2100.	1984.	1874.	1771.	1673.	1581.		
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME									
8080.	7970.	6990.	4553.	169826.					
INCHES	62.	2.19.	4.27.	4.43.					
AC-FT	3954.	13872.	27107.	28085.					
HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 4									
0.	0.	2.	9.	28.	86.	365.	1030.	2023.	
3239.	4615.	6089.	7523.	8769.	9754.	10442.	10773.	10683.	
9728.	9218.	8538.	7837.	7037.	6210.	5210.	4922.	4396.	
5535.	5229.	4941.	4668.	4410.	4167.	3937.	3719.	3514.	
3137.	2963.	2800.	2645.	2499.	2361.	2231.	2108.		
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME									
10773.	10626.	9320.	6071.	226434.					
INCHES	83.	2.91.	5.69.	5.90.					
AC-FT	5272.	18496.	36143.	37446.					
HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 5									
0.	0.	2.	12.	35.	107.	457.	1288.	2529.	
4043.	5768.	7611.	10961.	12192.	13053.	13466.	13329.	12796.	
12168.	11522.	10897.	9728.	9191.	8683.	8204.	7751.	7321.	
6919.	6537.	6176.	5835.	5513.	5208.	4921.	4649.	4392.	
3921.	3706.	3500.	3307.	3124.	2952.	2789.	2635.		
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME									
13466.	13283.	11650.	7589.	283043.					
INCHES	1.04.	3.64.	7.12.	7.38.					
AC-FT	6530.	23120.	45179.	46608.					
HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 6									
0.	0.	2.	14.	42.	129.	548.	1545.	3035.	
4858.	6922.	9133.	11285.	13153.	14631.	15666.	16159.	15355.	
14592.	13827.	13077.	12355.	11673.	11029.	10420.	9845.	9301.	
8382.	7844.	7411.	7002.	6615.	6250.	5905.	5579.	5271.	
4705.	4445.	4200.	3988.	3749.	3542.	3366.	3162.		
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME									
16159.	15939.	13941.	9106.	339651.					
INCHES	1.25.	4.37.	8.54.	8.65.					
AC-FT	7908.	27746.	54215.	56170.					
HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 7									

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

HYDROGRAPH AT STA 1 FOR PLAN 1, RYIO 8									
PEAK		6-HOUR		24-HOUR		72-HOUR		TOTAL VOLUME	
3FS	18853.	14596.	16311.	10624.	396260.				
INCHES		1.45	5.18	9.97	10.33				
AC-FT	2226.	32368.	63250.	65531.					
HYDROGRAPH AT STA 1 FOR PLAN 1, RYIO 8									
PEAK		6-HOUR		24-HOUR		72-HOUR		TOTAL VOLUME	
3FS	18853.	14596.	16311.	10624.	396260.				
INCHES		1.45	5.18	9.97	10.33				
AC-FT	2226.	32368.	63250.	65531.					
HYDROGRAPH AT STA 1 FOR PLAN 1, RYIO 9									
PEAK		6-HOUR		24-HOUR		72-HOUR		TOTAL VOLUME	
3FS	21546.	21252.	18641.	12142.	452869.				
INCHES		1.66	5.83	11.39	11.80				
AC-FT	10544.	36992.	72286.	74893.					
HYDROGRAPH AT STA 1 FOR PLAN 1, RYIO 9									
PEAK		6-HOUR		24-HOUR		72-HOUR		TOTAL VOLUME	
3FS	21546.	21252.	18641.	12142.	452869.				
INCHES		1.66	5.83	11.39	11.80				
AC-FT	10544.	36992.	72286.	74893.					

[illegible]

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
2433. 2228. 1499. 55149.
INCHES .19 .78 1.41 1.44
AC-FT 1287. 4422. 8925. 9128.

STATION 2. PLAN 1, RTIO 2
0. 0. 0. 12. 46. 357.
681. 1116. 1644. 2227. 3328. 3848. 4721. 4907.
4938. 4864. 4724. 4585. 4339. 3939. 3772. 3599. 3425.
3253. 3086. 2924. 2769. 2628. 2479. 2344. 2216. 2089. 1968.
1843. 1735. 1636. 1543. 1456. 1374. 1298. 1226.

STOR
0. 0. 2. 5. 19. 60. 145.
276. 452. 567. 989. 1169. 1438. 1672. 1872. 2088. 2076.
2887. 2868. 2889. 1944. 1871. 1795. 1718. 1639. 1558. 1475.
1394. 1315. 1239. 1165. 1085. 984. 867. 795.
747. 704. 663. 626. 598. 557. 526. 497.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
4938. 4983. 4423. 2998. 118296.
INCHES .38 1.38 2.81 2.47
AC-FT 2432. 8776. 17849. 18248.

STATION 2. PLAN 1, RTIO 3
0. 0. 6. 18. 69. 223. 535.
1822. 1673. 2426. 3223. 4109. 5154. 6046. 6809. 7328. 7543.
7519. 7344. 7083. 6777. 6452. 6152. 5861. 5568. 5280. 5001.
4732. 4476. 4232. 4000. 3817. 3638. 3460. 3285. 3114. 2950.
2793. 2642. 2499. 2363. 2234. 2108. 1977. 1859.

STOR
0. 0. 2. 7. 28. 90. 217.
415. 679. 1083. 1380. 1744. 2167. 2493. 2745. 2906. 2972.
2965. 2911. 2830. 2735. 2635. 2531. 2425. 2318. 2212. 2119.
2812. 1918. 1829. 1744. 1661. 1576. 1492. 1403. 1329. 1251.
1177. 1105. 1038. 973. 912. 855. 802. 754.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
7543. 7469. 6787. 4496. 165485.
INCHES .58 2.10 4.22 4.31
AC-FT 3785. 13318. 26767. 27354.

STATION 2. PLAN 1, RTIO 4
0. 0. 8. 24. 92. 297. 714.
1363. 2228. 3152. 4303. 5728. 7124. 8379. 9339. 9880. 10199.
18898. 9807. 9416. 8995. 8579. 8152. 7729. 7318. 6923. 6546.
6207. 5903. 5601. 5308. 5024. 4753. 4495. 4249. 4016. 3829.
3650. 3472. 3296. 3125. 2961. 2803. 2652. 2508.

STOR
0. 0. 3. 18. 37. 121. 289.
553. 986. 1346. 1855. 2373. 2843. 3238. 3528. 3695. 3756.
3727. 3648. 3541. 3421. 3292. 3160. 3038. 2983. 2788. 2688.
2552. 2448. 2330. 2223. 2119. 2028. 1925. 1835. 1758. 1666.
1582. 1497. 1414. 1334. 1256. 1181. 1118. 1042.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
18199. 18892. 8999. 5989. 228338.
INCHES .79 2.81 5.62 5.74
AC-FT 5887. 17859. 35656. 36437.

STATION 2. PLAN 1, RTIO 5
0. 0. 9. 30. 115. 372. 892.
1784. 2718. 3894. 5576. 7489. 9178. 10777. 11933. 13089. 13864.
12412. 12090. 11645. 11178. 10635. 10048. 9552. 9047. 8595. 8149.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDG

7715	7298	6901	6523	6187	5802	5581	5288	5005	4734
4477	4232	4000	3817	3638	3459	3284	3114		
0.	0.	0.	0.	0.	4.	12.	47.	151.	362.
691.	1137.	1697.	2321.	2931.	3474.	3912.	4227.	4380.	4384.
4348.	4272.	4159.	4021.	3873.	3724.	3578.	3437.	3297.	3159.
3025.	2896.	2774.	2657.	2544.	2433.	2323.	2215.	2112.	2013.
1919.	1829.	1744.	1661.	1576.	1492.	1409.	1328.		
STOR									
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
3.	3.	3.	3.	3.	3.	3.	3.	3.	3.
4.	4.	4.	4.	4.	4.	4.	4.	4.	4.
5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
7.	7.	7.	7.	7.	7.	7.	7.	7.	7.
8.	8.	8.	8.	8.	8.	8.	8.	8.	8.
9.	9.	9.	9.	9.	9.	9.	9.	9.	9.
10.	10.	10.	10.	10.	10.	10.	10.	10.	10.
11.	11.	11.	11.	11.	11.	11.	11.	11.	11.
12.	12.	12.	12.	12.	12.	12.	12.	12.	12.
13.	13.	13.	13.	13.	13.	13.	13.	13.	13.
14.	14.	14.	14.	14.	14.	14.	14.	14.	14.
15.	15.	15.	15.	15.	15.	15.	15.	15.	15.
16.	16.	16.	16.	16.	16.	16.	16.	16.	16.
17.	17.	17.	17.	17.	17.	17.	17.	17.	17.
18.	18.	18.	18.	18.	18.	18.	18.	18.	18.
19.	19.	19.	19.	19.	19.	19.	19.	19.	19.
20.	20.	20.	20.	20.	20.	20.	20.	20.	20.
21.	21.	21.	21.	21.	21.	21.	21.	21.	21.
22.	22.	22.	22.	22.	22.	22.	22.	22.	22.
23.	23.	23.	23.	23.	23.	23.	23.	23.	23.
24.	24.	24.	24.	24.	24.	24.	24.	24.	24.
25.	25.	25.	25.	25.	25.	25.	25.	25.	25.
26.	26.	26.	26.	26.	26.	26.	26.	26.	26.
27.	27.	27.	27.	27.	27.	27.	27.	27.	27.
28.	28.	28.	28.	28.	28.	28.	28.	28.	28.
29.	29.	29.	29.	29.	29.	29.	29.	29.	29.
30.	30.	30.	30.	30.	30.	30.	30.	30.	30.
31.	31.	31.	31.	31.	31.	31.	31.	31.	31.
32.	32.	32.	32.	32.	32.	32.	32.	32.	32.
33.	33.	33.	33.	33.	33.	33.	33.	33.	33.
34.	34.	34.	34.	34.	34.	34.	34.	34.	34.
35.	35.	35.	35.	35.	35.	35.	35.	35.	35.
36.	36.	36.	36.	36.	36.	36.	36.	36.	36.
37.	37.	37.	37.	37.	37.	37.	37.	37.	37.
38.	38.	38.	38.	38.	38.	38.	38.	38.	38.
39.	39.	39.	39.	39.	39.	39.	39.	39.	39.
40.	40.	40.	40.	40.	40.	40.	40.	40.	40.
41.	41.	41.	41.	41.	41.	41.	41.	41.	41.
42.	42.	42.	42.	42.	42.	42.	42.	42.	42.
43.	43.	43.	43.	43.	43.	43.	43.	43.	43.
44.	44.	44.	44.	44.	44.	44.	44.	44.	44.
45.	45.	45.	45.	45.	45.	45.	45.	45.	45.
46.	46.	46.	46.	46.	46.	46.	46.	46.	46.
47.	47.	47.	47.	47.	47.	47.	47.	47.	47.
48.	48.	48.	48.	48.	48.	48.	48.	48.	48.
49.	49.	49.	49.	49.	49.	49.	49.	49.	49.
50.	50.	50.	50.	50.	50.	50.	50.	50.	50.
51.	51.	51.	51.	51.	51.	51.	51.	51.	51.
52.	52.	52.	52.	52.	52.	52.	52.	52.	52.
53.	53.	53.	53.	53.	53.	53.	53.	53.	53.
54.	54.	54.	54.	54.	54.	54.	54.	54.	54.
55.	55.	55.	55.	55.	55.	55.	55.	55.	55.
56.	56.	56.	56.	56.	56.	56.	56.	56.	56.
57.	57.	57.	57.	57.	57.	57.	57.	57.	57.
58.	58.	58.	58.	58.	58.	58.	58.	58.	58.
59.	59.	59.	59.	59.	59.	59.	59.	59.	59.
60.	60.	60.	60.	60.	60.	60.	60.	60.	60.
61.	61.	61.	61.	61.	61.	61.	61.	61.	61.
62.	62.	62.	62.	62.	62.	62.	62.	62.	62.
63.	63.	63.	63.	63.	63.	63.	63.	63.	63.
64.	64.	64.	64.	64.	64.	64.	64.	64.	64.
65.	65.	65.	65.	65.	65.	65.	65.	65.	65.
66.	66.	66.	66.	66.	66.	66.	66.	66.	66.
67.	67.	67.	67.	67.	67.	67.	67.	67.	67.
68.	68.	68.	68.	68.	68.	68.	68.	68.	68.
69.	69.	69.	69.	69.	69.	69.	69.	69.	69.
70.	70.	70.	70.	70.	70.	70.	70.	70.	70.
71.	71.	71.	71.	71.	71.	71.	71.	71.	71.
72.	72.	72.	72.	72.	72.	72.	72.	72.	72.
73.	73.	73.	73.	73.	73.	73.	73.	73.	73.
74.	74.	74.	74.	74.	74.	74.	74.	74.	74.
75.	75.	75.	75.	75.	75.	75.	75.	75.	75.
76.	76.	76.	76.	76.	76.	76.	76.	76.	76.
77.	77.	77.	77.	77.	77.	77.	77.	77.	77.
78.	78.	78.	78.	78.	78.	78.	78.	78.	78.
79.	79.	79.	79.	79.	79.	79.	79.	79.	79.
80.	80.	80.	80.	80.	80.	80.	80.	80.	80.
81.	81.	81.	81.	81.	81.	81.	81.	81.	81.
82.	82.	82.	82.	82.	82.	82.	82.	82.	82.
83.	83.	83.	83.	83.	83.	83.	83.	83.	83.
84.	84.	84.	84.	84.	84.	84.	84.	84.	84.
85.	85.	85.	85.	85.	85.	85.	85.	85.	85.
86.	86.	86.	86.	86.	86.	86.	86.	86.	86.
87.	87.	87.	87.	87.	87.	87.	87.	87.	87.
88.	88.	88.	88.	88.	88.	88.	88.	88.	88.
89.	89.	89.	89.	89.	89.	89.	89.	89.	89.
90.	90.	90.	90.	90.	90.	90.	90.	90.	90.
91.	91.	91.	91.	91.	91.	91.	91.	91.	91.
92.	92.	92.	92.	92.	92.	92.	92.	92.	92.
93.	93.	93.	93.	93.	93.	93.	93.	93.	93.
94.	94.	94.	94.	94.	94.	94.	94.	94.	94.
95.	95.	95.	95.	95.	95.	95.	95.	95.	95.
96.	96.	96.	96.	96.	96.	96.	96.	96.	96.
97.	97.	97.	97.	97.	97.	97.	97.	97.	97.
98.	98.	98.	98.	98.	98.	98.	98.	98.	98.
99.	99.	99.	99.	99.	99.	99.	99.	99.	99.
100.	100.	100.	100.	100.	100.	100.	100.	100.	100.

7

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
SFS	21650.	21201.	18466.	11990.	44824.
INCHES		1.66	5.77	11.25	11.49
AC-FT		10518.	36650.	71382.	72901.

STATION		2. PLAN 1, R110 9			
0.	1.	5.	19.	61.	231.
3256.	5501.	8704.	12800.	21201.	23370.
26772.	23561.	22292.	21071.	19907.	18808.
14159.	13377.	12638.	12167.	11786.	11290.
8689.	8240.	7803.	7382.	6981.	6599.
					6250.
					5945.

STOR		2.				25.				94.			
0.	1.	5.	19.	61.	231.	0.	1.	5.	19.	61.	231.	0.	1.
1396.	2294.	3331.	4366.	4922.	5065.	5202.	5260.	5255.	5220.	5255.	5220.	5255.	5220.
5157.	5077.	4993.	4913.	4836.	4763.	4694.	4630.	4568.	4511.	4451.	4386.	4325.	4266.
4456.	4404.	4355.	4291.	4227.	4162.	4097.	4032.	3967.	3902.	3837.	3772.	3707.	3642.
3326.	3187.	3052.	2922.	2798.	2680.	2567.	2456.	2345.	2234.	2123.	2012.	1901.	1790.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
SFS	26883.	26518.	23333.	14999.	551566.
INCHES		2.07	7.30	14.07	14.37
AC-FT		13156.	46305.	89297.	91215.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

PEAK FLOW SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS

OPERATION	STATION	PLAN	RATIOS APPLIED TO FLOWS								
			.10	.20	.30	.40	.50	.60	.70	.80	1.00
HYDROGRAPH AT	1	1	2693.	5386.	8888.	10773.	13466.	16159.	18853.	21546.	26932.
	2	2	0.	0.	0.	0.	0.	0.	0.	0.	0.
ROUTED TO	1	1	2448.	4938.	7543.	10199.	13068.	16103.	18771.	21450.	26883.
	2	2	0.	0.	0.	0.	0.	0.	0.	0.	0.

.....
 HEC-1 VERSION DATED JAN 1973
 UPDATED AUG 74
 CHANGE NO. 01

PHF ROUTING - 307.25 - SPILLWAY CRABST EI.
 BOOMTOWN DAM + PASSIPPANY DIKE
 D. BRIEN + GERE - JUSTIN + COURTNEY DIV

JOB SPECIFICATION
 HQ MNR MMIN IDAY IHR IMIN METRC IPLT IPRT MSTM
 68 2 0 1 0 0 0 0 2 0
 JOPER NMT
 5 0

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 1 NRTIO= 9 LRTIO= 1

RTIOS= .10 .20 .30 .40 .50 .60 .70 .80 1.00

SUB-AREA RUNOFF COMPUTATION
 ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME
 1 0 0 0 1 0 0

HYDROGRAPH DATA
 INVOG IUNG TAREA SNAP TRSDA TRSPC RATIO ISHOW ISAME LOCAL
 0 1 119.00 0.00 0.00 0.00 0.00 0 0 0 0

PRECIP DATA
 MP STORM DAK
 12 0.00 0.00 0.00

PRECIP PATTERN
 .20 .20 1.00 10.20 3.50 .40

LOSS DATA

STKR DLTR RTIO ERASH STRKS RTIO STRIL CNSTL ALSHX RTIMP
 0.00 0.00 1.00 0.00 0.00 1.00 0.00 0.00 0.00 0.00

UNIT HYDROGRAPH DATA
 TP= 21.50 CP= .44 NTA= 0

RECESSION DATA
 STRIO= 0.00 ORCSN= 0.00 RTIO= 1.00
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNOYER CP AND TP ARE TC=11.19 AND R=17.61 INTERVALS

UNIT HYDROGRAPH 100 END-OF-PERIOD ORIGINATES, LAG= 21.56 HOURS, CP= .44 VOL= 1.00
 40. 151. 311. 1491. 1400. 712. 939. 1156. 1317. 1477. 1571.
 1611. 1574. 1491. 1400. 712. 939. 1156. 1317. 1477. 1571.
 946. 946. 845. 790. 754. 712. 673. 636. 681. 1060.
 936. 507. 479. 452. 427. 404. 381. 360. 348. 568.
 304. 207. 271. 256. 242. 229. 216. 204. 193. 322.
 172. 163. 154. 145. 137. 130. 122. 116. 109. 183.
 98. 92. 87. 82. 78. 73. 69. 66. 62. 59.
 55. 52. 49. 47. 44. 42. 39. 37. 35. 33.
 31. 30. 28. 26. 24. 22. 21. 20. 19. 19.
 17. 16. 14. 13. 12. 11. 11.

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDG

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

END-OF-PERIOD FLOW			
TIME	RAIN	EXCS	COMP 0
1 2 0	0.00	0.00	0.
1 4 0	0.00	0.00	0.
1 6 0	0.00	0.00	0.
1 8 0	0.10	0.10	4.
1 10 0	0.20	0.20	23.
1 12 0	0.20	0.20	69.
1 14 0	1.80	1.80	214.
1 16 0	10.20	10.20	913.
1 18 0	3.50	3.50	2575.
1 20 0	0.40	0.40	5058.
1 22 0	0.30	0.30	8097.
2 0 0	0.40	0.40	11537.
2 2 0	0.00	0.00	15222.
2 4 0	0.00	0.00	18008.
2 6 0	0.00	0.00	21922.
2 8 0	0.00	0.00	24305.
2 10 0	0.00	0.00	26106.
2 12 0	0.00	0.00	26932.
2 14 0	0.00	0.00	26658.
2 16 0	0.00	0.00	25592.
2 18 0	0.00	0.00	24320.
2 20 0	0.00	0.00	23045.
2 22 0	0.00	0.00	21796.
3 0 0	0.00	0.00	20592.
3 2 0	0.00	0.00	19455.
3 4 0	0.00	0.00	18381.
3 6 0	0.00	0.00	17366.
3 8 0	0.00	0.00	16408.
3 10 0	0.00	0.00	15502.
3 12 0	0.00	0.00	14646.
3 14 0	0.00	0.00	13837.
3 16 0	0.00	0.00	13073.
3 18 0	0.00	0.00	12352.
3 20 0	0.00	0.00	11670.
3 22 0	0.00	0.00	11025.
4 0 0	0.00	0.00	10417.
4 2 0	0.00	0.00	9841.
4 4 0	0.00	0.00	9298.
4 6 0	0.00	0.00	8785.
4 8 0	0.00	0.00	8300.
4 10 0	0.00	0.00	7842.
4 12 0	0.00	0.00	7409.
4 14 0	0.00	0.00	7000.
4 16 0	0.00	0.00	6613.
4 18 0	0.00	0.00	6246.
4 20 0	0.00	0.00	5903.
4 22 0	0.00	0.00	5577.
5 0 0	0.00	0.00	5269.

SUM	17.10	17.10	566003.
PEAK	6-HOUR	24-HOUR	72-HOUR
26932.	26566.	23301.	15177.
CFS	2.08	7.29	14.24
INCHES	13100.	46241.	90358.
AC-FT			

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 1

0.	0.	21.	91.
1522.	1881.	2192.	2430.
		2611.	2693.
			2559.
			258.
			506.

A-38

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
2693. 2657. 2330. 151A. 56809.
INCHES .21 .73 1.4A
AC-FT 1310. 4624. 9036. 9362.

HYDROGRAPH AT STA 1 FOR PLAN 1- RTIO 2

0.	1.	5.	14.	43.	515.	1012.
1619.	2307.	3762.	4384.	4877.	5221.	5366.
4869.	4110.	3891.	3676.	3473.	3282.	3108.
2767.	2615.	2334.	2205.	2003.	1860.	1757.
1568.	1402.	1323.	1250.	1101.	1115.	1054.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
5306. 5313. 4680. 3035. 113217.
INCHES .42 1.46 2.85 2.95
AC-FT 2636. 9244. 10072. 18721.

HYDROGRAPH AT STA 1 FOR PLAN 1- RTIO 3

0.	1.	7.	21.	64.	773.	1514.
2429.	3461.	5643.	6577.	7315.	7832.	8000.
7298.	6913.	6170.	5837.	5514.	5210.	4922.
4151.	3922.	3705.	3501.	3300.	3125.	2952.
2352.	2223.	2100.	1984.	1874.	1771.	1673.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
8080. 7978. 6990. 4553. 169826.
INCHES .62 2.19 4.27 4.43
AC-FT 3954. 13072. 27107. 28085.

HYDROGRAPH AT STA 1 FOR PLAN 1- RTIO 4

0.	2.	9.	28.	86.	1030.	2023.
3239.	4615.	7523.	8769.	9754.	10442.	10773.
9720.	8218.	8237.	7702.	7353.	6947.	6563.
5533.	5229.	4941.	4680.	4410.	3917.	3719.
3137.	2963.	2800.	2645.	2499.	2361.	2231.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
18773. 10626. 9320. 6071. 226434.
INCHES .03 2.91 5.69 5.90
AC-FT 5272. 10496. 36143. 37446.

HYDROGRAPH AT STA 1 FOR PLAN 1- RTIO 5

0.	2.	12.	35.	107.	1200.	2929.
4049.	5768.	7611.	9408.	10961.	13053.	13466.
12160.	11522.	10497.	10296.	9720.	9191.	8683.
6919.	5537.	4176.	5835.	5913.	5208.	4921.
3921.	3704.	3500.	3307.	3124.	2952.	2789.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
13466. 13203. 11650. 7509. 243043.
INCHES 1.04 3.64 7.12 7.1A
AC-FT 6590. 23120. 45179. 46408.

HYDROGRAPH AT STA 1 FOR PLAN 1- RTIO 6

0.	2.	14.	42.	129.	1545.	3035.
4050.	6922.	9133.	11205.	13153.	14631.	15684.
14592.	13027.	12355.	11073.	11029.	10420.	9945.
8302.	7044.	7411.	7002.	6615.	5905.	5579.
4705.	4445.	4200.	3968.	3749.	3542.	3346.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
16159. 15939. 13981. 9106. 339651.
INCHES 1.25 4.37 8.54 8.85
AC-FT 7900. 27744. 54215. 56170.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
2449. 2435. 2229. 1499. 55159.
CFS 19. 70 1.41 1.44
INCHES 1206. 4424. 8926. 9122.
AC-FT

STATION 2. PLAN 1. RTIO 2

0.	0.	0.	1.	4.	12.	46.	149.	358.
68.	1119.	1649.	2233.	3331.	3842.	4347.	4720.	4906.
4937.	4063.	4724.	4545.	4139.	3941.	3773.	3608.	3426.
3256.	3087.	2925.	2769.	2479.	2344.	2216.	2087.	1958.
1841.	1734.	1634.	1541.	1373.	1296.	1224.		

STOR

0.	0.	0.	2.	5.	19.	60.	144.
278.	451.	665.	1165.	1426.	1668.	1867.	2072.
2084.	2056.	2005.	1940.	1791.	1714.	1635.	1471.
1390.	1310.	1234.	1160.	1023.	959.	898.	798.
742.	699.	659.	622.	554.	523.	494.	

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
4937. 4902. 4423. 2998. 110315.
CFS 38 1.38 2.81 2.87
INCHES 2432. 8778. 17851. 18243.
AC-FT

STATION 2. PLAN 1. RTIO 3

0.	0.	0.	2.	18.	70.	224.	537.
1026.	1679.	2432.	4100.	5154.	6046.	7522.	7817.
7459.	7075.	6897.	6344.	6019.	5777.	5515.	4980.
4719.	4467.	4227.	3997.	3639.	3460.	3285.	2951.
2793.	2643.	2508.	2364.	2106.	1976.	1857.	

STOR

0.	0.	0.	2.	7.	28.	98.	217.
414.	677.	1001.	1377.	2163.	2489.	2683.	2701.
2678.	2652.	2625.	2598.	2479.	2391.	2295.	2099.
2006.	1912.	1823.	1739.	1572.	1487.	1324.	1246.
1171.	1100.	1032.	968.	869.	797.	749.	

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
8082. 7887. 6714. 4496. 165433.
CFS 61 2.10 4.22 4.31
INCHES 3873. 13325. 26770. 27358.
AC-FT

STATION 2. PLAN 1. RTIO 4

0.	0.	0.	2.	24.	93.	299.	716.
1368.	2227.	3156.	4304.	8331.	10246.	10725.	10427.
9945.	9433.	8929.	8440.	7974.	7533.	7117.	6724.
6035.	5795.	5533.	5264.	4997.	4736.	4484.	4242.
3650.	3472.	3296.	3126.	2961.	2803.	2652.	2509.

STOR

0.	0.	0.	3.	10.	37.	120.	289.
552.	904.	1343.	1852.	2370.	2739.	2907.	2886.
2852.	2816.	2781.	2747.	2694.	2654.	2627.	2558.
2483.	2397.	2301.	2203.	2105.	2010.	1918.	1829.
1577.	1493.	1410.	1329.	1251.	1176.	1105.	1037.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
10725. 10597. 9145. 5990. 220362.
CFS 83 2.86 5.62 5.74
INCHES 5257. 18148. 34659. 36442.
AC-FT

STATION 2. PLAN 1. RTIO 5

0.	0.	0.	3.	10.	30.	116.	895.
1710.	2716.	3898.	5577.	11787.	12693.	13307.	13036.
9742.	11702.	11451.	10460.	9462.	8417.	7402.	7487.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

[illegible]

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DCC

		STATION		2. PLAN 1, RTIO 9		TOTAL VOLUME	
		1.		5.		61.	
		0.		0.		232.	
		0.		0.		746.	
		0.		0.		1791.	
		0.		0.		25904.	
		0.		0.		15006.	
		0.		0.		8504.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	
		0.		0.		5826.	


THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

PEAK FLOW SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS

STATION	PLAN	RATIOS APPLIED TO FLOWS							
		.16	.20	.30	.40	.50	.60	.70	.80
OROGRAPH AT	1	2693.	5366.	8080.	10773.	13466.	16159.	18853.	21546.
	2	0.	0.	0.	0.	0.	0.	0.	0.
UTED TO	1	2449.	4937.	8082.	10725.	13405.	16086.	18769.	21450.
	2	0.	0.	0.	0.	0.	0.	0.	0.


STABILITY ANALYSES

SUBJECT	SHEET	BY	DATE	JOB NO
BOUNTON RESERVOIR DAM	1	REH	5/3/78	120000 195



- SEISMIC LOADINGS APPLIED: HORIZONTAL INERTIAL FORCES DEVELOPED BY THE WEIGHT OF THE DAM AND THE HYDROSTATIC LOADING. INCLUSION OF THE SEISMIC SILT LOADING HAS A NEGLIBLE EFFECT ON THE RESULTS AND HAS BEEN OMITTED FROM THE ANALYSES.
- SLIDING PLANE: FOR SIMPLIFICATION OF THE ANALYSES, THE DAM SECTION HAS BEEN EXTENDED DOWN TO THE APPROXIMATE BASE ELEVATION OF THE SHEAR KEY.

SUBJECT	SHEET	BY	DATE	JOB NO
BARTON RESERVOIR DAM	1A	REH	5/3/78	1ew m. 19!



ASSUME TOTAL HEIGHT
OF DAM = 120'

$$\therefore \text{BASE WIDTH} = 17' + .56(107.5) + 64.73/20$$

$$= 17' + 60.2' + 3.24 = 80.4 \quad \text{USE } 80'$$

$$\begin{aligned} \text{AREA OF MAX DAM SECTION} &= \frac{1}{2}(3.24)(15.25) + 17(120) + \frac{1}{2}(60.2)(107.5) \\ &= 105.7 + 2040 + 3235.8 \\ &= 5381.5 \end{aligned}$$

$$\text{WEIGHT OF DAM/UNIT LENGTH} = 893.3 \text{ kips}$$

$$\begin{aligned} \text{C.G.} &= \frac{105.7(78.28) + 2040(68.7) + 3235.8(40.13)}{5381.5} \end{aligned}$$

$$\text{C.G.} = 51.7' \quad \text{UPSTREAM OF TOE}$$

SUBJECT	SHEET	BY	DATE	JOB NO.
BOONTON RESERVOIR DAM	2	REH	5/3/78	1800.001

ANALYSES ASSUMPTIONS:

UNIT WEIGHT OF MASONRY - 166 PCF
UNIT WEIGHT OF SILT - 86 PCF
SILT, INTERNAL $\angle$ OF FRICTION - 30°
ICE PRESSURE - 5 KSF
 $\angle$ OF FRICTION, MASONRY/FOUNDATION - 30°
SHEAR RESISTANCE, MASONRY/FOUNDATION - 100 PSI
SEISMIC COEFF. OF ACCELERATION - .05g
ALLOWABLE BEARING CAPACITY - 200 PSI
ALLOWABLE TENSILE STRESS - 25 PSI

ASSUMPTIONS HAVE BEEN BASED ON FURNISHED DATA
AND GENERALIZED SITE CONDITIONS.

MORE COMPREHENSIVE ANALYSIS OF THE EXISTING DAM
AND FOUNDATION MAY REVEAL A MORE CRITICAL
STRUCTURAL CONDITION.

SUBJECT	SHEET	BY	DATE	JOB NO
BOUNTON RESERVOIR DAM	3	REH	5/3/78	1800 001 12

STABILITY ANALYSES - SUMMARY

LOADING CONDITION	S.F. - OVERTURNING	S.F. - SLIDING	BEARING PRESSURE
NORMAL POOL	1.50	3.39	113.4 psi - 5.0 psi
NORMAL POOL - ICE	1.50	3.43	113.5 psi - 6.3 psi
NORMAL POOL - PMF	1.36	3.06	130.4 psi - 24.7 psi
NORMAL POOL - EARTHQUAKE	1.37	2.94	133.1 psi - 24.7 psi
RAISED POOL	1.45	3.28	118.7 psi - 11.2 psi
RAISED POOL - PMF	1.35	3.05	131.5 psi - 25.9 psi
RAISED POOL - EARTHQUAKE	1.33	2.86	138.7 psi - 31.2 psi

NORMAL POOL ELEV (BASCULE GATES DOWN) - 305.25

RAISED POOL ELEV (BASCULE GATES UP) - 307.25

Negative bearing pressures indicate tension at the upstream face.

NATIONAL DAM INSPECTION PROGRAM - BOONTON RESERVOIR DAM
 STABILITY ANALYSIS: FULL SECTION, NORMAL POOL - EL - 109.25

BASE ELEVATION= 190.00 FT. TOP ELEVATION= 310.25 FT. BASE WIDTH= 80.60 FT. DENSITY= 166.00 PCF
 HEADWATER ELEVATION= 305.25 FT. TAILWATER ELEVATION= 0.00 FT. EARTHQUAKE ACCELERATION= .0005 (HORIZ) .0000 (VERT)
 SILT ELEVATION= 240.00 FT. SILT DENSITY (SUBMERGED)= 86.00 PCF SILT PRESSURE COEFFICIENT (K)= .33
 SHEAR STRESS= 100.00 PSI SHEAR WIDTH= 80.60 FT. FRICTION FACTOR= .58

LOADING	FORCE (KIPS)	ARM (FEET)	STABILIZING MOMENT	OVERTURNING MOMENT
HEIGHT OF DAM	436.43	51.79	46421.74	
HEADWATER UPLIFT	414.42 289.82	38.38 53.73		15904.56 15573.07
SILT	35.80	16.67		596.63
WATER SURCHARGE	16.80	79.20	1330.56	
SOIL SURCHARGE	5.40	79.80	430.92	
			40163.22	32074.26

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

NET HORIZONTAL FORCE= 450.21 KIPS
 NET VERTICAL FORCE= 628.81 KIPS
 NET MOMENT= 16108.96 KIP-Feet
 X-BAR OF FOUNDATION REACTION= 25.62 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 14.68 FEET
 FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE
 TENSION AT NEEL OF DAM
 FOUNDATION REACTION PRESSURES= 113.39 PSI
 HEEL= 5.03 PSI
 OVERTURNING FACTOR OF SAFETY= 1.50
 SLIDING FACTOR OF SAFETY= .61
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .72
 SLIDING WITH SHEAR FACTOR OF SAFETY= 3.39 (SHEAR ACROSS FULL BASE WIDTH)

2/5/78

.....
 NATIONAL DAM INSPECTION PROGRAM - BOONTON RESERVOIR DAM
 STABILITY ANALYSIS, FULL SECTION, NORMAL POOL - PMF

BASE ELEVATION= 190.00FT. TOP ELEVATION= 310.25FT. BASE WIDTH= 80.60FT. DENSITY= 166.00PCF
 HEADWATER ELEVATION= 311.30FT. TAILWATER ELEVATION= 0.00FT. EARTHQUAKE ACCELERATION= .000G (HORIZ) .000G (VERT)
 SILT ELEVATION= 240.00FT. SILT DENSITY(SUBMERGED)= 86.00PCF. SILT PRESSURE COEFFICIENT(K)= .33
 SHEAR STRESS= 100.00PSI SHEAR WIDTH= 80.60FT. FRICTION FACTOR= .58

LOADING	FORCE(KIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM				
HEADWATER	896.43	51.79	46421.74	18557.47
UPLIFT	459.03	40.43		16390.58
SILT	305.04	53.73		596.63
WATER SURCHARGE	35.00	16.67		
SOIL SURCHARGE	16.80	79.20	1330.56	
	5.40	79.80	430.92	
			48183.22	35544.67

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

.....
 NET HORIZONTAL FORCE= 494.83 KIPS
 NET VERTICAL FORCE= 613.59 KIPS
 NET MOMENT= 12638.55 KIP-Feet
 X-CAR OF FOUNDATION REACTION= 20.60 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 19.70 FEET
FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE.....TENSION AT HEEL OF DAM.....
 FOUNDATION REACTION PRESSURES.....TOE= 130.40 PSI.....HEEL= -24.67 PSI.....
 OVERTURNING FACTOR OF SAFETY= 1.36
 SLIDING FACTOR OF SAFETY= .72
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .61
 SLIDING WITH SHEAR FACTOR OF SAFETY= 3.06 (SHEAR ACROSS FULL BASE WIDTH)

.....
 NATIONAL DAM INSPECTION PROGRAM - NOONTON RESERVOIR DAM
 STABILITY-ANALYSIS, FULL SECTION, NORMAL POOL-ICE LOADING

.....
 BASE-ELEVATION= 190.00FT, TOP-ELEVATION= 310.25FT, BASE WIDTH= 80.60FT, DENSITY= 166.00PCF
 HEADWATER ELEVATION= 303.25FT, TAILWATER ELEVATION= 0.00FT, EARTHQUAKE ACCELERATION= .000G (HORIZ) .000G (VERT)
 SILT ELEVATION= 240.00FT, SILT DENSITY(SUBMERGED)= 86.00PCF, SILT PRESSURE COEFFICIENT(K)= .33
 SHEAR STRESS= 100.00PSI, SHEAR WIDTH= 80.60FT, FRICTION FACTOR= .58

LOADING	FORCE(KIPS)	ARM(FEET)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	996.63	51.79	46421.74	
HEADWATER	400.16	37.71		15090.84
UPLIFT	284.79	51.73		15302.83
SILT	35.80	16.67		596.63
ICE LOADING	10.00	114.25		1142.50
WATER SURCHARGE	16.80	79.20	1330.56	
SOIL SURCHARGE	5.40	79.80	430.92	
			*****	*****
			48183.22	32132.79

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

.....
 NET HORIZONTAL FORCE= 445.96-KIPS
 NET VERTICAL FORCE= 533.83 KIPS
 NET MOMENT= 16050.43KIP-Feet
 X-BAR-OF-FOUNDATION REACTION= 25.32 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 14.98 FEET
 *****FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE*****TENSION AT HEEL OF DAM*****
 FOUNDATION REACTION PRESSURES*****TOE=-115.50 PSI*****HEEL= -8.28 PSI*****
 OVERTURNING FACTOR OF SAFETY= 1.50
 SLIDING FACTOR OF SAFETY= .82
 DEVELOPED-FRICTION-FACTOR-(NO SHEAR)= .70
 SLIDING WITH SHEAR FACTOR OF SAFETY= 3.43(SHEAR ACROSS FULL BASE WIDTH)

 NATIONAL DAM INSPECTION PROGRAM - BOONTON RESERVOIR DAM
 STABILITY ANALYSIS, FULL SECTION, NORMAL POOL - EARTHQUAKE

BASE ELEVATION= 190.00 FT. TOP ELEVATION= 310.25 FT. BASE WIDTH= 80.60 FT. DENSITY= 166.00 PCF
 HEADWATER ELEVATION= 305.25 FT. TAILWATER ELEVATION= 0.00 FT. EARTHQUAKE ACCELERATION= .050G (HORIZ), .000G (VERT)
 SILT ELEVATION= 240.00 FT. SILT DENSITY (SUBMERGED)= 86.00 PCF SILT PRESSURE COEFFICIENT(K)= .33
 SHEAR STRESS= 100.00 PSI SHEAR WIDTH= 80.60 FT. FRICTION FACTOR= .58

LOADING	FORCE (KIPS)	ARM (FEET)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	896.43	51.79	46421.74	
HEADWATER	414.42	38.38		15904.56
UPLIFT	289.82	53.73		15573.07
EARTHQUAKE-INDUCED LOADINGS				
INERTIA-WATER	21.06	46.10		1063.10
HORIZONTAL INERTIA-DAM	44.82	44.80		2007.90
SILT	35.80	16.67		596.63
WATER SURCHARGE	16.80	79.20	1330.56	
SOIL SURCHARGE	5.40	79.80	430.92	
			*****	*****
			44183.22	35145.45

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

 NET HORIZONTAL FORCE= 518.10 KIPS
 NET VERTICAL FORCE= 528.81 KIPS
 NET MOMENT= 13037.77 KIP-Feet
 X-BAR OF FOUNDATION REACTION= 20.73 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 19.57 FEET
 ***** FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE ***** TENSION AT HEEL OF DAM *****
 FOUNDATION REACTION PRESSURES ***** TOE= 133.09 PSI ***** HEEL= -24.73 PSI *****
 OVERTURNING FACTOR OF SAFETY= 1.37
 SLIDING FACTOR OF SAFETY= .70
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .82
 SLIDING WITH SHEAR FACTOR OF SAFETY= 2.94 (SHEAR ACROSS FULL BASE WIDTH)

.....
 NATIONAL DAM INSPECTION PROGRAM - MONTON RESERVOIR DAM
 STABILITY ANALYSIS, FULL SECTION, POOL ELEVATION - 107.25

.....
 BASE ELEVATION= 190.00FT, TOP ELEVATION= 310.25FT, BASE WIDTH= 80.60FT, DENSITY= 166.00PCF
 HEADWATER ELEVATION= 307.25FT, TAILWATER ELEVATION= 0.00FT, EARTHQUAKE ACCELERATION=.000G (HORI), .000G (VERT)
 SILT ELEVATION= 240.00FT, SILT DENSITY(SUBMERGED)= 86.00PCF, SILT PRESSURE COEFFICIENT(K)= .31
 SHEAR STRESS= 100.00PSI, SHEAR WIDTH= 80.60FT, FRICTION FACTOR= .58

LOADING	FORCE(KIPS)	ARM(FEET)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	896.43	51.79	46421.74	16747.01
HEADWATER	428.92	39.04		15843.72
UPLIFT	294.85	53.73		596.63
SILT	35.80	16.67		
WATER SURCHARGE	17.20	79.30	1363.96	
SOIL SURCHARGE	5.40	79.80	430.92	
			48216.62	33166.96

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

.....
 NET HORIZONTAL FORCE= 464.72 KIPS
 NET VERTICAL FORCE= 524.10 KIPS
 NET MOMENT= 15029.66 KIP-Feet
 X-BAR OF FOUNDATION REACTION= 24.08 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 16.22 FEET
 FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE..... TENSION AT HEEL OF DAM.....
 FOUNDATION REACTION PRESSURES..... TOE= 118.72 PSI..... HEEL= -11.16 PSI.....
 OVERTURNING FACTOR OF SAFETY= 1.45
 SLIDING FACTOR OF SAFETY= .74
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .74
 SLIDING WITH SHEAR FACTOR OF SAFETY= 3.28 (SHEAR ACROSS FULL BASE WIDTH)

.....
 NATIONAL DAM INSPECTION PROGRAM - BONTON RESERVOIR DAM
 STABILITY ANALYSIS, FULL SECTION, POOL EL -307.25 -PMF

BASE ELEVATION= 190.00FT. TOP ELEVATION= 310.25FT. BASE WIDTH= 80.60FT. DENSITY= 166.00PCF
 HEADWATER ELEVATION= 311.70FT. TAILWATER ELEVATION= 0.00FT. EARTHQUAKE ACCELERATION= .000G (HORIZ) .000G (VERT)
 SILT ELEVATION= 240.00FT. SILT DENSITY(SUBMERGED)= 86.00PCF SILT PRESSURE COEFFICIENT(K)= .33
 SHEAR STRESS= 100.00PSI SHEAR WIDTH= 80.60FT. FRICTION FACTOR= .58

LOADING	FORCE(KIPS)	ARM(FEET)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	896.43	51.79	46421.74	18737.93
HEADWATER	452.03	40.56		16444.63
UPLIFT	306.04	53.73		596.63
SILT	35.80	16.67		
WATER SURCHARGE	17.20	79.30	1363.96	
SOIL SURCHARGE	5.40	79.80	430.92	
			*****	*****
			44216.62	35779.18

.....
 THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

NET HORIZONTAL FORCE= 497.83 KIPS
 NET VERTICAL FORCE= 612.99 KIPS
 NET MOMENT= 12437.44 KIP-Feet
 X-BAR OF FOUNDATION REACTION= 20.29 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 20.01 FEET
 *****FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE*****TENSION AT HEEL OF DAM*****
 FOUNDATION REACTION PRESSURES*****TOE= 131.49 PSI*****HEEL= -25.86 PSI*****
 OVERTURNING FACTOR OF SAFETY= 1.35
 SLIDING FACTOR OF SAFETY= .71
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .81
 SLIDING WITH SHEAR FACTOR OF SAFETY= 3.05(SHEAR ACROSS FULL BASE WIDTH)

 NATIONAL DAM INSPECTION PROGRAM - BOONTON RESERVOIR DAM
 STABILITY ANALYSIS, FULL SECTION, POOL-EL-307.25-EARTHQUAKE

BASE-ELEVATION=130.00FT, TOP-ELEVATION=310.25FT, BASE-WIDTH=80.60FT, DENSITY=146.00PCF
 HEADWATER ELEVATION=307.25FT, TAILWATER ELEVATION= 0.00FT, EARTHQUAKE ACCELERATION=.050G (HORIZ),.000G (VERT)
 SILT ELEVATION= 240.00FT, SILT DENSITY(SUBMERGED)= 86.00PCF, SILT PRESSURE COEFFICIENT(K)= .33
 SHEAR STRESS= 100.00PSI, SHEAR-WIDTH= 80.60FT, FRICTION FACTOR=.58

LOADING FORCE(KIPS) ARM(Feet) STABILIZING MOMENT OVERTURNING MOMENT

WEIGHT-OF-DAM 896.43 51.79 46421.74
 HEADWATER 428.92 39.04 16747.01
 UPLIFT 294.85 53.73 15843.32

EARTHQUAKE-INDUCED LOADINGS

INERTIA-WATER 23.67 45.90 1110.03
 HORIZONTAL-INERTIA-DAM 46.82 44.80 2007.90

SILT 35.80 16.67 596.63
 WATER-SURCHARGE 17.20 79.30 1363.96
 SOIL SURCHARGE 5.40 79.80 430.92

 48216.62 36306.89

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

NET HORIZONTAL FORCE= 533.21 KIPS

NET VERTICAL FORCE= 324.18 KIPS

NET MOMENT= 11911.73 KIP-Feet

X-BAR OF FOUNDATION REACTION= 19.08 FEET

ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 21.22 FEET

*****FOUNDATION REACTION NOT IN CENTRAL-THIRD OF BASE*****TENSION AT HEEL OF DAM*****

FOUNDATION REACTION PRESSURES*****TOE= 138.71 PSI*****HEEL= -31.16 PSI*****

OVERTURNING FACTOR OF SAFETY= 1.33

SLIDING FACTOR OF SAFETY= .68

DEVELOPED FRICTION FACTOR (NO SHEAR)= .85

SLIDING WITH SHEAR FACTOR OF SAFETY= 2.86(SHEAR ACROSS FULL BASE WIDTH)

DATE
FILMED

9-7