

AD-A065 932

ARMY COMMUNICATIONS COMMAND FORT HUACHUCA ARIZ  
STANDARD ENGINEERING INSTALLATION PACKAGE, TERMINAL VHF OMNIDIR--ETC(U)  
FEB 79

F/G 17/7


UNCLASSIFIED


ACC-SEIP-012

NL

3  
OF  
AD  
A085832







14  
ACC-SEIP-012

6

**LEVEL**

9 Final rept.

6

**STANDARD**

**ENGINEERING INSTALLATION PACKAGE**

**TERMINAL**

**VHF OMNIDIRECTIONAL RANGE**

**(TVOR) SYSTEM**

**AN/FRN-41**

DDC  
RECEIVED  
MAR 19 1979  
C

12

150 P. 48.

11

16 FEBRUARY 1979

DDC FILE COPY, ADAO 65932

VOICE OF THE ARMY

APPROVED FOR PUBLIC RELEASE. DISTRIBUTION UNLIMITED.

**HEADQUARTERS  
U. S. ARMY COMMUNICATIONS COMMAND  
FORT HUACHUCA, ARIZONA 85613**

408 562 79 03 16 007  
7B

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER SEIP 012	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Standard Engineering Installation Package Terminal VHF Omnidirectional Range (TVOR) System AN/FRN-41	5. TYPE OF REPORT & PERIOD COVERED Final, Indefinite	
	6. PERFORMING ORG. REPORT NUMBER	
7. AUTHOR(s)	8. CONTRACT OR GRANT NUMBER(s)	
9. PERFORMING ORGANIZATION NAME AND ADDRESS US Army Communications-Electronics Engineering Installation Agency, ATTN: CCC-CED-SEP Ft Huachuca, AZ 85613	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
11. CONTROLLING OFFICE NAME AND ADDRESS US Army Communications Command ATTN: CC-PA-AMP Fort Huachuca, AZ 85613	12. REPORT DATE 16 February 1979	
	13. NUMBER OF PAGES	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) US Army Communications Command ATTN: CC-OPS-SM Fort Huachuca, AZ 85613	15. SECURITY CLASS. (of this report)  Unclassified	
	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT (of this Report)		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Terminal VHF Omnidirectional Range Equipment, TVOR system, Site Survey Data, Transmitting Set, Radio AN/FRN-41, Siting Criteria, Installation Specifica- tions and Instructions, Quality Assurance Procedures, Automatic Terminal Information System.		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This Standard Engineering Installation Package (SEIP) provides information for the engineering and installation of TVOR facilities worldwide. Informa- tion provided consists of site survey data, siting criteria, installation specifications and instructions, a bill of materials, quality assurance pro- cedures and completion certification format. Information provided must be adapted to the specific TVOR facility/location by the project engineer.		

### DISPOSITION INSTRUCTIONS

Destroy this document when no longer needed.

Do not return it to the originator

### DISCLAIMER

The use of trade names in this document does not constitute an official endorsement or approval of the use of such commercial hardware or software. This document may not be cited for purpose of advertisement.

### AVAILABILITY

This publication is available to non-Government agencies and may be purchased through the Defense Documentation Center, Cameron Station, Alexandria, VA 22314.

Government activities may requisition copies by writing to the Commander, Headquarters, Fort Huachuca, ATTN: CCH-PCA-ASP, Fort Huachuca, Arizona 85613.

### NEUTRAL LANGUAGE

The word "he" when used in this publication represents both the masculine and feminine genders, unless specifically stated.

ACCESSION		
NTIS	Section <input type="checkbox"/>	
DOC	B. H. Section <input type="checkbox"/>	
UNANNOUNCED	<input type="checkbox"/>	
JUSTIFICATION		
BY		
DISTRIBUTION/AVAILABILITY NOTES		
Dist.	AVAIL.	GENERAL
R		

DEPARTMENT OF THE ARMY  
HEADQUARTERS, U.S. ARMY COMMUNICATIONS COMMAND  
Fort Huachuca, Arizona 85613

USACC SEIP  
No. 012

16 February 1979

Standard Engineering Installation Package  
TERMINAL VHF OMNIDIRECTIONAL RANGE (TVOR) SYSTEM  
AN/FRN-41

Paragraph Page

SECTION 1. GENERAL

1.1	PURPOSE AND SCOPE. . . . .	1-1
1.2	SYSTEM DESCRIPTION . . . . .	1-1
1.3	TECHNICAL DESCRIPTION. . . . .	1-5
1.4	SUPPLEMENTARY EQUIPMENT. . . . .	1-12
1.5	LIST OF APPLICABLE DOCUMENTS . . . . .	1-12
1.6	COMMENTS ON PUBLICATION. . . . .	1-15

SECTION 2. SITE SURVEY DATA AND CHECKLIST

2.1	GENERAL. . . . .	2-1
2.2	SITING CRITERIA . . . . .	2-1
2.3	SITE SURVEY CRITERIA . . . . .	2-2
2.4	SITE SURVEY CHECKLIST. . . . .	2-3
2.5	EQUIPMENT CHARACTERISTICS. . . . .	2-25

SECTION 3. INSTALLATION SPECIFICATIONS AND INSTRUCTIONS

3.1 GENERAL. . . . . 3-1  
 3.2 INSTALLATION INSTRUCTIONS. . . . . 3-1  
 3.3 CHANGES TO SPECIFICATIONS. . . . . 3-14  
 3.4 AS-BUILT DRAWINGS. . . . . 3-15

SECTION 4. ENGINEERING INSTALLATION DRAWINGS

4.1 GENERAL. . . . . 4-1  
 4.2 USACEEIA DRAWINGS. . . . . 4-2

SECTION 5. BILL OF MATERIALS

5.1 GENERAL. . . . . 5-1  
 5.2 MAJOR ITEMS. . . . . 5-1

SECTION 6. QUALITY ASSURANCE PLAN

6.1 GENERAL. . . . . 6-1  
 6.2 QUALITY ASSURANCE PROGRAM. . . . . 6-1  
 6.3 SPECIAL CONSIDERATIONS . . . . . 6-23

SECTION 7. ACCEPTANCE TEST PLAN AND PROCEDURES

7.1 GENERAL. . . . . 7-1  
 7.2 TESTING. . . . . 7-1

SECTION 8. COMPLETION CERTIFICATION

8.1 GENERAL. . . . . 8-1  
 8.2 DISTRIBUTION . . . . . 8-1  
 8.3 WAIVERS. . . . . 8-1

LIST OF ILLUSTRATIONS

Figure No.	Page
1-1 Transmitter Group, OT-117/FRN-41 . . . . .	1-2
1-2 Block Diagram TVOR System, AN/FRN-41. . . . .	1-3
1-3 RF Power Monitor. . . . .	1-4
1-4 Control-Indicator, C-10527/FRN-41 . . . . .	1-6
1-5 Transmitter, Radio, T-1394/FRN-41 . . . . .	1-7
1-6 Transmitter, Sideband, T-1395/FRN-41. . . . .	1-8
1-7 Detector, RF, DT-603/FRN-41 . . . . .	1-9
1-8 Antenna, AS-3323/FRN-41 . . . . .	1-10
1-9 Control-Indicator, C-10526/FRN-41 . . . . .	1-11
1-10 Recorder-Reproducer, TRC-89-4 . . . . .	1-13
2-1 Sample Presite Survey Checklist (6 sheets). . . . .	2-4
2-2 Sample Site Survey Checklist (15 sheets). . . . .	2-10
3-1 Twenty-one Foot Shelter Excavation and Footing. . . . .	3-4
3-2 TVOR Facility Floor Plan. . . . .	3-9
3-3 Antenna Cable Location. . . . .	3-13
5-1 Bill of Materials . . . . .	5-2
6-1 Sample of Cognizant Agency, Command, and Facility Points of Contact. . . . .	6-3
6-2 Sample of Final Installation Inspection Checklist (11 sheets). . . . .	6-4
6-3 Sample of Quality Control Checklist (7 sheets). . . . .	6-16
8-1 Sample of Technical Acceptance Recommendation (6 sheets) . . . . .	8-5

TABLES

Table No.	
2-1.	Equipment Characteristics. . . . . 2-26

SECTION 1. GENERAL

1.1 PURPOSE AND SCOPE. Terminal VHF Omnidirectional Range (TVOR) equipment is used at Army Airfields/Army Heliports (AAF/AHP) to provide a radio navigational aid (NAVAID) to enroute aircraft. A transmitted composite signal whose phase differs in azimuth, provides an infinite number of course radials which enable the aircraft crew to determine their course relative to magnetic north. The TVOR system also provides voice transmission and automatic identification of the facility. It is the purpose of this standard engineering installation package (SEIP) to provide guidance and standard engineering data for the development of an engineering installation package (EIP) for a specific TVOR facility. This SEIP provides site survey data, installation specifications and instructions, typical installation drawings, a bill of materials (BOM), quality assurance (QA) procedures, test and acceptance procedures, and completion certification format. The information will be adapted for the engineering and installation of specific TVOR facilities worldwide.

1.2 SYSTEM DESCRIPTION. The solid state AN/FRN-41 TVOR system is comprised of four basic components: Transmitter Group, OT-117/FRN-41 (electronics assembly), Detector, Radio Frequency, DT-603/FRN-41 (field detector), Antenna, AS-3323/FRN-41, and Control-Indicator, C-10526/FRN-41 (remote control unit). The transmitter group is installed in Shelter, S-597/FRN-41, and the antenna is mounted on the flat roof housed in a fiber glass radome. The roof of the shelter serves as the counterpoise for the antenna with the field detectors mounted on the rim of the shelter roof. Transmitter Group, OT-117/FRN-41 units are modular and mount in a 19-inch rack. All units associated with the electronics assembly, except the TVOR power monitor, are mounted on drawer slides. Each unit has built-in test and calibration features and a self-contained supply.

1.2.1 Functional description. The Transmitter Group, OT-117/FRN-41, figure 1-1, operates in the frequency range of 108-118 MHz with channels spaced every 50 kHz. The course information is omnidirectional and provides the aircraft a bearing to or from the TVOR facility relative to magnetic north. A functional system block diagram is shown in figure 1-2. The RF power monitor, figure 1-3, is a panel-mounted unit located at the top of Equipment Rack, MT-6011, and contains three power sensors. The purpose of this unit is to measure both the forward and reflected power of the carrier and sidebands going to the




Figure 1-1. Transmitter Group, OT-117/FRN-41.




Figure 1-2. Block Diagram TVOR System, AN/FRN-41.




Figure 1-3. RF Power Monitor.

antenna. Control-Indicator, C-10527/FRN-41 (local control), figure 1-4, provides the interface and controls for complete local and remote control of all TVOR system functions. All power for the various units of the TVOR system is applied through Control-Indicator, C-10527. Also, alarm information, transfer and shutdown action is evaluated and controlled by this unit. Transmitter, T-1394/FRN-41 (carrier transmitter), figure 1-5, generates the carrier signal for the composite TVOR signal while Transmitter, T-1395/FRN-41 (sideband transmitter), figure 1-6, replaces the conventional mechanical goniometer and generates two suppressed carrier double sideband signals. The system's four most critical parameters: the 9960 Hz reference, 30 Hz variable signals, and the bearing and identification signals are monitored by Monitor, Phase Modulation, ID-2179/FRN-41. When a malfunction occurs, the ID-2179 initiates an alarm signal. However, when all system parameters are within tolerance, this is indicated by the illumination of a green light. Detector, DT-603/FRN-41, figure 1-7, continuously monitors the radiated signal. A sample of the signal, at a predetermined radial, is fed back to Monitor, ID-2179, where the reference signal, variable signal, modulation levels, bearing accuracy, and identification parameters are evaluated. Antenna, AS-3323/FRN-41, figure 1-8, is a stationary cylindrical slot antenna that radiates two figure-eight patterns at right angles to each other. The two patterns are fed with sidebands that are modulated and this results in a rotating figure-eight pattern that generates the rotating TVOR pattern. Control-Indicator, C-10526/FRN-41, figure 1-9, provides the interfacing and controls for remote operation of all the TVOR system functions. Control-Indicator, C-10526, permits the TVOR facility to be unmanned and remotely controlled via telephone lines using a 2-digit code to activate the command functions.

**1.3 TECHNICAL DESCRIPTION.** The input power requirements for Transmitter Group, OT-117/FRN-41, is 210-260 Vrms, 47-63 Hz. The assembly has a normal power consumption of 600 watts; however, operational requirements may cause this power consumption to reach a maximum of 1200 watts. The system operates in the frequency range of 108-118 MHz with a frequency stability of 0.002 percent and effective radiated power of 50 watts. The system azimuth and ground check azimuth accuracy are  $\pm 2.0$  and  $\pm 0.75$  degrees respectively. The AN/FRN-41 TVOR is an amplitude modulated system that has a maximum modulation distortion rate of 1 percent. Carrier harmonic suppression is -60 dB and subcarrier harmonic suppression ranges from -30 dB for the second harmonic to -60 dB for the fourth harmonic. The maximum sideband power is 5 watts (adjustable) and Antenna, AS-3323, can be continuously tuned to any TVOR channel from 108-118 MHz. The antenna voltage




Figure 1-4. Control-Indicator, C-10527/FRN-41.




Figure 1-5. Transmitter, Radio, T-1394/FRN-41.




Figure 1-6. Transmitter, Sideband, T-1395/FRN-41.

16 February 1979

SEIP 012




Figure 1-7. Detector, RF, DT-603/FRN-41.




Figure 1-8. Antenna, AS-3323/FRN-41.




Figure 1-9. Control-Indicator, C-10526/FRN-41.

standing wave ratio (VSWR) for the carrier or either sideband is less than 1.1 and the antenna can handle carrier powers up to 200 watts. For additional in-depth technical information refer to chapters 1 and 4 of Document No. CM106.

1.4 SUPPLEMENTARY EQUIPMENT. The preponderance of the TVOR systems presently scheduled for installation are programed to receive an automatic terminal information system (ATIS) to tape record AAF/AHP control tower radio transmissions and repetitively rebroadcast the messages. The equipment being provided is Recorder-Reproducer Set, Type TRC-89-4, figure 1-10, manufactured by the Stancil-Hoffman Corporation. Sufficient detail is provided in this document for the installation of the TRC-89-4. Performance testing details for this equipment are found in the commercial service manual for the TRC-89-4, chapter 5.

1.4.1 The TRC-89-4 provides for recording and playback of an audio message information channel on 1/4-inch wide magnetic tape. Examples of routine information provided pilots using this equipment include weather conditions, runway conditions, and time. The TRC-89-4 has a remote control capability with provisions for output monitoring at both the local and remote control stations.

1.4.2 The TRC-89-4 is comprised of five main assemblies: Recorder/Reproducer Assembly, Model TRC-89; Remote Control Assembly, Model CU-89; microphone assembly; cassette assembly; and power cable assembly. The input power for the ATIS is 115/230 Vac +5 V, 50/60 Hz with a normal power consumption of 40 watts (max) for 60 Hz operation, and a power consumption of 60 watts (max) for 50 Hz operation.

1.5 LIST OF APPLICABLE DOCUMENTS.

a. Government documents.

(1) Manuals.

CCTM 105-50-21 -- Telecommunications Engineering-Installation Practices, Installation General.

(2) Regulations.

CCR 702-1-2 -- USACC Quality Assurance Program for Engineering, Installation, and Acceptance of Communications Electronics Equipment and Systems.




Figure 1-10. Recorder-Reproducer, TRC-89-4.

- CCCR 702-1 -- USACEEIA Quality Assurance and Testing Program.
- CCCR 702-2 -- Preparation of Documentation for Test and Evaluation of Communications-Electronics Materiel.
- CCCR 702-3 -- Role of the Test Director
- CCCR 702-4 -- Quality Assurance During On-Site Installation.
- CCCR 702-7 -- Product Assurance Quality Assurance Corrective Actions
- CCP 700-20 -- List of Nonadopted Commercial Items of Equipment.
- USACEI Bn Pamphlet 105-3 -- The Communications-Electronics Installation Planning and Implementation Guide.
- SB700-20 -- Army adopted/other items selected for authorization/list of reportable items
- (3) Technical Bulletins.
- TB 95-1 -- US Army Air Traffic Control and NAVAID Facility Standards.
- (4) Directives.
- DCAC 370-160-2 -- Installations and Construction-Management Responsibility for Site Surveys.
- DCAC 370-160-3 -- Installations and Construction, Site Survey Data Book for Communications Facilities.
- CCC-TED-75-TP-200 -- Quality Assurance Evaluation and Technical Acceptance Test of World-Wide Army Airfields/Heliports Communications and Navigational Aids (Revision 2) Test Plan.
- (5) Air Force Technical Manual (Air Force Communications Service (E-1 Standard), Standard Installation Practices).
- TO 31-10-2 through 31-10-29

16 February 1979

SEIP 012

b. Non-Government documents.

Document No. CM106 -- Technical Manual for VOR Navigational System Part No. 136060-100.

Document No. CMD16-1 -- Supplementary Technical Manual for VOR Navigational System Part No. 136060-100.

(Copies may be obtained from E-Systems Inc., Montek Division, 2268 South 3270 West, Salt Lake City, Utah 84119)

Service Manual-- Service Manual and Circuit Diagrams with Illustrated Part Breakdown Recorder-Reproducer Part No. 10-003-4, Type TRC-89-4.

(Copies can be obtained from The Stancil-Hoffman Corporation, 921 North Highland Ave., Hollywood, CA 90038)

Two copies of each non-Government document or manual listed in this section are provided with Recorder-Reproducer, TRC-89-4 and Transmitting Set, Radio, AN/FRN-41. A government technical manual, TM 11-5825-266-14, Radio Transmitting Set (AN/FRN-41) is being prepared and will replace the AN/FRN-41 commercial document when available. Additionally, all Air Force technical orders are available through normal publication procurement channels.

1.6 COMMENTS ON PUBLICATION.

1.6.1 Users of this publication are invited to submit recommendations for improvement. Comments should be keyed to the drawing, page, paragraph, and line of the text where change is recommended. A mailing card for convenience is bound with this SEIP. Comments should be sent directly to the Commander, Headquarters, US Army Communications-Electronics Engineering Installation Agency, (HQ, USACEEIA), ATTN: CCC-CED-SEP, Fort Huachuca, Arizona 85613.

1.6.2 Requests for USACEEIA regulations and forms should be addressed to the Commander, HQ, USACEEIA, ATTN: CCC-SPT-RM, Fort Huachuca, Arizona 85613.

## SECTION 2. SITE SURVEY DATA AND CHECKLIST

2.1 GENERAL. This section provides the information to accomplish the preliminary engineering, equipment layout, and site surveys associated with the installation of the AN/FRN-41 TVOR system.

2.1.1 Site selection for the AN/FRN-41 is a compromise between ideal conditions and practical necessity. Under ideal conditions, the installation would be located on flat terrain and devoid of metallic fences, overhead power and telephone lines, heavily wooded areas, hangars, and other obstructions for several thousand feet from the facility. Since ideal sites are seldom found in areas where operational conditions require these facilities to be installed, a practical criteria is needed.

2.2 SITING CRITERIA. The following requirements are the siting criteria for the installation of the AN/FRN-41 and pertinent to obtaining optimum technical performance of the equipments. Unless otherwise specified, measurements are made from the center of Shelter, S-597/FRN-41.

2.2.1 The land should be flat to 3000 feet in all directions.

2.2.2 There should be no rise to the ground the first 200 feet; beyond this, no downgrade in excess of 4 percent to 1000 feet.

2.2.3 The contour of the terrain should be as even as possible around the facility. Undulations in the first 1000 feet should not exceed the average grade by more than 1 percent of the distance between the center of the shelter and such undulations.

2.2.4 There should be no object within the first 3000 feet; however, the maximum height of any object within 3000 feet must be below the horizontal plane of the shelter roof. Compromises within these limitations are as follows:

2.2.4.1 No structure elevated more than 5 feet within 750 feet.

2.2.4.2 No structure to extend above a 2° vertical angle measured at ground level at the center of the shelter.

2.2.4.3 No aerial conductors within 750 feet of the shelter.

2.2.4.4 Between 750 and 1200 feet, no aerial conductors unless they continue on a straight line from the shelter on one radial and undulate no more than necessary.

2.2.4.5 Beyond 2000 feet, no aerial conductors should extend above a  $1.5^\circ$  vertical angle, or extend more than  $0.5^\circ$  above the horizontal plane of the shelter roof unless they continue on a line within  $\pm 5^\circ$  of one radial.

2.2.5 No wire fences within 500 feet. Beyond 500 feet, no wire fences extending more than  $0.5^\circ$  above the horizontal plane of the shelter roof unless they continue along one radial.

2.2.6 No groves of trees within 1000 feet of the shelter.

2.2.6.1 Between 1000 and 2000 feet, no groves to extend above a  $2^\circ$  vertical angle measured at ground level at the shelter.

2.2.6.2 An occasional tree not exceeding 35 feet in height may be tolerated beyond 750 feet.

2.2.7 At the AAF/AHP, buildings should be located on a radial that is parallel to their long side.

2.2.7.1 Shelter, S-597/FRN-41, should be located away from areas where aircraft stand and park.

2.2.7.2 The shelter should not be located closer than 400 feet to the center line of a runway or 200 feet to the center line of taxiways.

2.3 SITE SURVEY CRITERIA. When selecting a site, the first step is to make a preliminary field survey or site survey as required by DCAC 370-160-2 and DCAC 370-160-3. The survey should include an actual field inspection of the entire prospective site area noting general topographic features, accessibility, availability of power, and obstructions which cannot be removed. The following information must be obtained during the survey:

2.3.1 Coordinates and other adequate identifying means which furnish the geographical location of the site.

2.3.2 Data for preparation of a site drawing shall include the following three sketches and a horizon profile polar plot:

2.3.2.1 A location sketch to show the location of the site with respect to any AAF/AHP, air base, or town in the vicinity as well as adjacent roads, power and telephone lines.

2.3.2.2 A plot layout sketch to show the natural features and other important details of the site such as plot dimensions, trees, fences, drainage ditches, existing buildings, utility lines, and other obstructions within 2000 feet of the proposed location of the TVOR shelter and antenna. This sketch should also show the proposed location of the access road and power line terminal pole together with the routing of the underground and overhead lines running from the terminal pole.

2.3.2.3 A topographic sketch of the area out a minimum of 1000 feet from the TVOR shelter and antenna which shows contours at 1-foot levels.

2.3.2.4 The horizon profile polar plot to show how mountains and hills affect coverage at the minimum approach altitudes and out to the service volume of the facility.

2.3.3 Direction of prevailing wind.

2.3.4 Climatic conditions.

2.3.5 Availability of telephone communications.

2.3.6 Availability of electrical power.

2.3.7 Availability of civil fire and police protection if the facility is not located on a military installation.

2.3.8 Protection required against vandalism.

2.4 SITE SURVEY CHECKLIST. Prior to conducting the site survey, a checklist will be prepared by the project engineer. The site survey checklist establishes guidelines for the survey team to ensure all pertinent technical data is identified, assembled, and properly documented. The survey team must also have a complete set of drawings to assist them in the conduct of the survey. Figures 2-1 and 2-2 are sample presite survey and site survey checklists, respectively, for the installation of a TVOR system. The site survey checklist, when completed, will aid in preparing the official survey report. The survey report is required as an inclosure to the site concurrence letter (SCL) forwarded to the responsible agencies for approval.

PRESITE SURVEY CHECKLIST  
FOR  
INSTALLATION OF TERMINAL VHF OMNIDIRECTIONAL RANGE (TVOR)  
FACILITIES

1. General. This presite survey is being conducted to determine the most suitable location for a TVOR facility. Worksheets provided by the site survey team contain supplementary data for the installation of this facility.
2. Facility layout. Provide proposed facility layout with specifications and equipment characteristics.
3. Site data.
  - a. Site name or identification: \_\_\_\_\_.
  - b. Site location: Latitude: \_\_\_\_\_ Longitude: \_\_\_\_\_.
  - c. Azimuth of control tower from true north: \_\_\_\_\_.
  - d. Distance to control tower: \_\_\_\_\_ nautical miles.
  - e. Anticipated frequency: \_\_\_\_\_ MHz.
  - f. Type of emission (symbol): \_\_\_\_\_.
  - g. Proposed transmitter power: \_\_\_\_\_ watts.
  - h. The horizon profile polar plot is shown on sheet number \_\_\_\_\_ of drawing \_\_\_\_\_.
  - i. Obstruction points and other critical points requiring detailed investigation.
  - j. Accuracy to which elevations and locations must be determined.
  - k. Other information: \_\_\_\_\_.

Figure 2-1. Sample Presite Survey Checklist (sheet 1 of 6).

16 February 1979

SETP 012

4. Surveying.

a. Baseline azimuth: \_\_\_\_\_ order required.  
(1st, 2d, 3d)

b. Length of base line: \_\_\_\_\_ order required.  
(1st, 2d, 3d)

(3d order accuracy for a and b unless otherwise specified).

c. Site marker elevation accuracy required is: + \_\_\_\_\_ ft.

d. Amount of topographic data required from survey team: \_\_\_\_\_

e. Contour interval required \_\_\_\_\_ ft minimum.

f. Other: \_\_\_\_\_

5. Isolation.

a. Other transmitter stations: \_\_\_\_\_

b. Radio receiver stations: \_\_\_\_\_

c. Ammunition storage area: \_\_\_\_\_

d. POL storage area: \_\_\_\_\_

e. Airfields and glide paths:

(1) For general communication transmitting: \_\_\_\_\_

(2) For aeronautical transmitting at air field: \_\_\_\_\_

f. Main highways: \_\_\_\_\_

g. High-tension power lines (overhead): \_\_\_\_\_

Figure 2-1. Sample Presite Survey Checklist (sheet 2 of 5).

(1) Transmitter station feeders: \_\_\_\_\_.

(2) Transmission lines and large transformer stations: \_\_\_\_\_.

h. Railroads: \_\_\_\_\_.

i. Shipping lanes: \_\_\_\_\_.

6. Real estate. A minimum area of \_\_\_\_\_ acres having an approximate width of \_\_\_\_\_ feet and an approximate length of \_\_\_\_\_ feet will be required to accommodate the proposed facility. Define requirements by drawings, etc., as appropriate.

7. Equipment environmental conditions.

a. Allowable operating temperature: Maximum: \_\_\_\_\_ ° F.  
Minimum: \_\_\_\_\_ ° F.

b. Allowable operating humidity: Maximum: \_\_\_\_\_ percent.  
Minimum: \_\_\_\_\_ percent.

c. RF shielding requirements: Frequency: \_\_\_\_\_.  
Attenuation: \_\_\_\_\_ dB.

8. Buildings.

a. Electronic equipment building:

(1) Length: \_\_\_\_\_ feet x width: \_\_\_\_\_ ft.

(2) Ceiling height: \_\_\_\_\_ feet above finished floor.

(3) Live floor load: \_\_\_\_\_ psf.

(4) Shielding requirements: \_\_\_\_\_

\_\_\_\_\_.

(5) Acoustic requirements: \_\_\_\_\_

\_\_\_\_\_.

Figure 2-1. Sample Presite Survey Checklist (sheet 3 of 6).

- (6) Heating requirement: \_\_\_\_\_ Btu/hr.
- (7) Air-conditioning: \_\_\_\_\_ Btu/hr.
- (8) Ventilating: \_\_\_\_\_ cfm.
- (9) See sketch \_\_\_\_\_ for equipment layout.

b. Power building.

- (1) Length: \_\_\_\_\_ feet x width: \_\_\_\_\_ feet.
- (2) Ceiling height: \_\_\_\_\_ feet above finished floor.
- (3) Live floor load: \_\_\_\_\_ psf.
- (4) Shielding requirements: \_\_\_\_\_

- (5) Acoustic requirements: \_\_\_\_\_

- (6) Heating requirements: \_\_\_\_\_ Btu/hr.
- (7) Ventilating: \_\_\_\_\_ cfm.
- (8) Physical separation of \_\_\_\_\_ feet required from

other buildings. \_\_\_\_\_

- (9) See sketch \_\_\_\_\_ for equipment layout.

9. Power.

a. The anticipated power requirements are as follows:

- (1) Total technical load: \_\_\_\_\_ kW.
- (2) Total nontechnical load: \_\_\_\_\_ kW.
- (3) Total power requirements: \_\_\_\_\_ kW at \_\_\_\_\_ Hz,  
\_\_\_\_\_ phase, \_\_\_\_\_ volts at a power factor of \_\_\_\_\_ percent.

Figure 2-1. Sample Presite Survey Checklist (sheet 4 of 6).

b. Allowable voltage and frequency deviations from rated values:

(1) Voltage: + \_\_\_\_\_ volts or + \_\_\_\_\_ percent.

(2) Frequency: + \_\_\_\_\_ Hz or + \_\_\_\_\_ percent.

c. Standby power requirements: \_\_\_\_\_ Kw at \_\_\_\_\_ Hz, \_\_\_\_\_ phase, \_\_\_\_\_ volts at a power factor of \_\_\_\_\_ percent.

d. No-break power requirements: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

e. Local power company contact: \_\_\_\_\_  
\_\_\_\_\_

10. Physical security List special requirements: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

11. Support.

a. Personnel.

(1) Total personnel required for operation: \_\_\_\_\_

(2) Number for each shift: \_\_\_\_\_ (1st) \_\_\_\_\_ (2d) \_\_\_\_\_ (3d)

(3) Number of personnel required for construction and installation: \_\_\_\_\_

(4) Approximate length of time required for construction and installation: \_\_\_\_\_

Figure 2-1. Sample Presite Survey Checklist (sheet 5 of 6)

b. Storage.

(1) Inside storage (heated, secured):

(a) Binned (sq ft): \_\_\_\_\_.

(b) Bulk (sq ft): \_\_\_\_\_.

(2) Outside storage:

(a) Closed (sq ft): \_\_\_\_\_ 4

(b) Open (sq ft): \_\_\_\_\_

(3) POL storage:

(a) Bulk (gals): \_\_\_\_\_ ✓

(b) Drum (sq ft): \_\_\_\_\_ D

c. Vehicles.

(1) Type and number of vehicles required for installation: \_\_\_\_\_ M

(2) Special cranes or hoists required (specify): \_\_\_\_\_ R

12. Other pertinent data.

\_\_\_\_\_ S  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Figure 2-1. Sample Presite Survey Checklist (sheet 6 of 6).

SITE SURVEY CHECKLIST  
FOR  
INSTALLATION OF TERMINAL VHF OMNIDIRECTIONAL RANGE  
(TVOR) FACILITIES

1. General.

a. Date: \_\_\_\_\_

b. Site location: \_\_\_\_\_  
Installation

City State Country

c. Project number: \_\_\_\_\_

d. Project engineer: \_\_\_\_\_  
Name

Organization Office symbol  
Installation

AUTOVON Commercial Tel No.

e. Classification: \_\_\_\_\_

f. Brief task description: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Figure 2-2. Sample Site Survey Checklist (sheet 1 of 15).

THIS PAGE IS BEST QUALITY PRACTICABLE  
FROM COPY FURNISHED TO DDG

16 February 1979

SEIP 012

g. Personnel contacted or present during survey:

	<u>Name/Grade</u>	<u>Title</u>	<u>Organization</u>	<u>Phone No.</u>
(1)	_____	_____	_____	_____
(2)	_____	_____	_____	_____
(3)	_____	_____	_____	_____
(4)	_____	_____	_____	_____

2. Equipment to be installed:

- a. Contactor furnished and installed ✓
- b. Government furnished and installed. ✓
- c. Government furnished, contractor installed. ✓
- d. Equipment physical description chart.

Qty	Nomenclature	Overall dimensions (in)			wt
		Height	Width	Depth	(lbs)

e. Equipment characteristic chart.

Nomenclature	Operating Conditions		Input Power		Power Consumption
	Temperature	Relative Humidity	Voltage	Frequency	

Figure 2-2. Sample Site Survey Checklist (sheet 2 of 15).

3. Profiles.

a. Location: \_\_\_\_\_.

b. Site marker coordinates:

(1) Latitude: \_\_ degrees \_\_ minutes \_\_ seconds.

(2) Longitude: \_\_ degrees \_\_ minutes \_\_ seconds.

c. Date: \_\_\_\_\_ Temperature: \_\_\_\_\_ Visibility: \_\_\_\_\_.

d. Recorder: \_\_\_\_\_ Instrument man: \_\_\_\_\_.

e. Elevation of ground at instrument: \_\_\_\_\_.

f. Height of instrument above ground: \_\_\_\_\_.

g. The true north used to determine azimuths for the horizon profile data sheet was obtained using reference line established as follows:

(1) Corrected compass north on \_\_\_\_\_ (date)

by \_\_\_\_\_ using compass reading of \_\_\_\_\_ and  
variation of \_\_\_\_\_ (degrees, minutes) east  
west.(2) By \_\_\_\_\_ using \_\_\_\_\_ order  
(surveying firm) (1st, 2d, 3d)  
trigonometric points on \_\_\_\_\_  
(date)(3) By \_\_\_\_\_ using celestial obser-  
vations on \_\_\_\_\_.

Figure 2-2. Sample Site Survey Checklist (sheet 3 of 15).

16 February 1979

SEIP 012

4. Photographs.

a. Title: \_\_\_\_\_

(1) Source: \_\_\_\_\_

(2) Date: \_\_\_\_\_

(3) Shows: \_\_\_\_\_

b. Title: \_\_\_\_\_

(1) Source: \_\_\_\_\_

(2) Date: \_\_\_\_\_

(3) Shows: \_\_\_\_\_

c. Title: \_\_\_\_\_

(1) Source: \_\_\_\_\_

(2) Date: \_\_\_\_\_

(3) Shows: \_\_\_\_\_

d. Title: \_\_\_\_\_

(1) Source: \_\_\_\_\_

(2) Date: \_\_\_\_\_

(3) Shows: \_\_\_\_\_

(Add additional sheets if necessary.)

Figure 2-2. Sample Site Survey Checklist (sheet 4 of 15).

5. Topography.

- a. Make complete topographic map of site with the contour interval of \_\_\_\_\_ feet.
- b. Give narrative description of topography and the degree of natural slope.
- c. Are there any natural or manmade objects which will lie in the radiation field? If so, provide location and estimated size.

6. Ground resistance.

- a. What is the measured ground resistance? \_\_\_\_\_ ohms
- b. Where was it obtained? \_\_\_\_\_

7. Soil characteristics.

- a. Indicate type of geological formation: \_\_\_\_\_
  - b. Indicate type of soil (sand, clay, loam, rock, etc.): \_\_\_\_\_
  - c. Is soil uniform over site? If variations exist, make sketch showing location of different types of soil. \_\_\_\_\_
  - d. Indicate depth of water table below grade: \_\_\_\_\_
  - e. Are there seasonal variations in the water table? \_\_\_\_\_
  - f. Does the water table vary over the area? \_\_\_\_\_
- If so, make sketch.

Figure 2-2. Sample Site Survey Checklist (sheet 5 of 15).

16 February 1979

SEIP 012

8. Isolation.

a. From radio receiving stations or radio astronomy installations, mark on area map:

(1) Type and size: \_\_\_\_\_

(2) Distance and direction: \_\_\_\_\_

(3) Are their antennas beamed? U \_\_\_\_\_

(4) Do any of the beams cover this site? \_\_\_\_\_

b. From airfields, mark on area map:

(1) Type and size: \_\_\_\_\_

(2) Distance and direction: \_\_\_\_\_

(3) Type of aircraft operating from: \_\_\_\_\_

(4) Is this site within the airfield's:

(a) Slide path? \_\_\_\_\_

(b) Holding pattern? \_\_\_\_\_

(c) Airway? \_\_\_\_\_

c. From populated areas, mark on area map:

(1) Extent and population: \_\_\_\_\_

(2) Distance and direction: \_\_\_\_\_

Figure 2-2. Sample Site Survey Checklist (sheet 6 of 15).

(3) Do TV and broadcasts cover area? \_\_\_\_\_.

9. Interconnecting communications.

a. Distance from associated communications station: \_\_\_\_\_.

b. Will right-of-way be necessary for landline cables?  
\_\_\_\_\_.

c. Are leased lines available? \_\_\_\_\_.

d. Is telephone service available? U \_\_\_\_\_.

10. Radio interference.

a. Radio or radar transmitters.

(1) Distance: \_\_\_\_\_ miles.

(2) Direction (azimuth): R \_\_\_\_\_ degrees.

(3) Frequency: \_\_\_\_\_ (kHz, MHz, or GHz).

(4) Type of emission (symbol): M \_\_\_\_\_.

(5) Power: \_\_\_\_\_ kW.

(6) Antenna pattern. (Attach radiation pattern where applicable.) R

b. Radio receiving stations.

(1) Distance: S \_\_\_\_\_ miles.

(2) Direction (azimuth): \_\_\_\_\_ degrees.

(3) Receiving frequencies: \_\_\_\_\_ (kHz, MHz, or GHz).  
(Attach sheets if required.)

(4) Receiver sensitivity or type and model: \_\_\_\_\_  
\_\_\_\_\_.

(5) Type of station or operating organization: \_\_\_\_\_.

Figure 2-2. Sample Site Survey Checklist (sheet 7 of 15).

c. Distance from power lines, railroads, or highways:

\_\_\_\_\_

d. Distance from high-tension power lines: \_\_\_\_\_.

(1) Number, type of wire, and voltage: \_\_\_\_\_.

(2) Height of wire from ground: \_\_\_\_\_.

(3) Type, height, and spacing of towers: \_\_\_\_\_.

\_\_\_\_\_

e. Distance from ordnance areas: \_\_\_\_\_.

f. Distance to airways: \_\_\_\_\_.

g. Existence of airways or traffic patterns in antenna quadrant: \_\_\_\_\_.

h. Average number of flights per day: \_\_\_\_\_.

i. Type of aircraft:

(1) Preponderantly jet: \_\_\_\_\_.

(2) Preponderantly propeller: \_\_\_\_\_.

(3) Commercial airline: \_\_\_\_\_.

(4) Private light plane: \_\_\_\_\_.

j. Anticipated industrial noise level: \_\_\_\_\_.

high: \_\_\_\_\_ low: \_\_\_\_\_.

k. Other: \_\_\_\_\_.

(1) Distance: \_\_\_\_\_.

(2) Direction: \_\_\_\_\_.

(3) Frequency: \_\_\_\_\_.

(4) Power: \_\_\_\_\_.

Figure 2-2. Sample Site Survey Checklist (sheet 8 of 15).

11. Towers (existing).

a. General information.

Number	Type	Use	Height	For location see drawing No.
SAMPLE				

b. Do any of the existing towers appear to be able to support supplementary equipment for the system being investigated? \_\_\_\_\_.

(yes, no)

c. Name and address of tower and foundation design agency:

\_\_\_\_\_

S

d. List of tower foundation design drawings obtained:

\_\_\_\_\_

e. List of tower design drawings obtained: \_\_\_\_\_

\_\_\_\_\_

Figure 2-2. Sample Site Survey Checklist (sheet 9 of 15).

16 February 1979

SEIP 012

f. List of tower fabrication drawings obtained: \_\_\_\_\_

\_\_\_\_\_

g. If the drawings requested in paragraphs 9d, e, or f cannot be obtained during the site survey, where can drawings be obtained? \_\_\_\_\_

12. Buildings (existing).

a. Indicate probable use: ✓ \_\_\_\_\_

b. Available area: \_\_\_\_\_ sq ft, length: \_\_\_\_\_ ft x width: \_\_\_\_\_ ft.

c. Ceiling height: \_\_\_\_\_ ft above finished floor.

d. Allowable floor load: \_\_\_\_\_ psf.

Source of information: \_\_\_\_\_

\_\_\_\_\_

e. Existing shielding: \_\_\_\_\_

\_\_\_\_\_

f. Existing acoustic treatment: \_\_\_\_\_

\_\_\_\_\_

g. Available heating capacity: \_\_\_\_\_ Btu/hr.

h. Available air-conditioning capacity: \_\_\_\_\_ Btu/hr.

Figure 2-2. Sample Site Survey Checklist (sheet 10 of 15).

i. Available ventilating capacity: \_\_\_\_\_ cfm.

j. List of as-built drawings obtained:

(1) Title: \_\_\_\_\_ Date: \_\_\_\_\_

Drawing number: \_\_\_\_\_ Issue: \_\_\_\_\_

(a) Type: \_\_\_\_\_  
(site, architectural, structural, mechanical, electrical, equipment)

(b) Design agency: \_\_\_\_\_

(c) Source: \_\_\_\_\_

(2) Title: \_\_\_\_\_ Date: \_\_\_\_\_

Drawing number: \_\_\_\_\_ Issue: \_\_\_\_\_

(a) Type: \_\_\_\_\_  
(site, architectural, structural, mechanical, electrical, equipment)

(b) Design agency: \_\_\_\_\_

(c) Source: \_\_\_\_\_

(3) Title: \_\_\_\_\_ Date: \_\_\_\_\_

Drawing number: \_\_\_\_\_ Issue: \_\_\_\_\_

(a) Type: \_\_\_\_\_  
(site, architectural, structural, mechanical, electrical, equipment)

(b) Design agency: \_\_\_\_\_

(c) Source: \_\_\_\_\_

(4) Title: \_\_\_\_\_ Date: \_\_\_\_\_

Figure 2-2. Sample Site Survey Checklist (Sheet 11 of 15).

SAMPLE

16 February 1979

SETP 012

Drawing number: \_\_\_\_\_ Issue: \_\_\_\_\_

(a) Type: \_\_\_\_\_  
(site, architectural, structural,  
mechanical, electrical, equipment)

(b) Design agency: \_\_\_\_\_

(c) Source: \_\_\_\_\_

13. Power building (existing).

a. Available area: \_\_\_\_\_ sq ft, length: \_\_\_\_\_ ft x width:  
\_\_\_\_\_ ft.

b. Ceiling height: \_\_\_\_\_ ft above finished floor.

c. Allowable floor load: \_\_\_\_\_ psf.

Source of information: \_\_\_\_\_

d. Existing shielding: \_\_\_\_\_

e. Existing acoustic treatment: \_\_\_\_\_

f. Available heating capacity: \_\_\_\_\_ Btu/hr.

g. Available ventilating capacity: \_\_\_\_\_ cfm.

h. Existing power building: List of as-built drawings  
obtained.  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Figure 2-2. Sample Site Survey Checklist (sheet 12 of 15).

**THIS PAGE IS BEST QUALITY PRACTICABLE  
FROM COPY FURNISHED TO DDC**

SEIP 012

16 February 1979

(1) Title: \_\_\_\_\_ Date: \_\_\_\_\_  
Drawing number: \_\_\_\_\_ Issue: \_\_\_\_\_  
(a) Type: \_\_\_\_\_  
(site, architectural, structural,  
mechanical, electrical, equipment)  
(b) Design agency: \_\_\_\_\_  
(c) Source: \_\_\_\_\_

(2) Title: \_\_\_\_\_ Date: \_\_\_\_\_  
Drawing number: \_\_\_\_\_ Issue: \_\_\_\_\_  
(a) Type: \_\_\_\_\_  
(site, architectural, structural,  
mechanical, electrical, equipment)  
(b) Design agency: \_\_\_\_\_  
(c) Source: \_\_\_\_\_

(3) Title: \_\_\_\_\_ Date: \_\_\_\_\_  
Drawing number: \_\_\_\_\_ Issue: \_\_\_\_\_  
(a) Type: \_\_\_\_\_  
(site, architectural, structural,  
mechanical, electrical, equipment)  
(b) Design agency: \_\_\_\_\_  
(c) Source: \_\_\_\_\_

(4) Title: \_\_\_\_\_ Date: \_\_\_\_\_  
Drawing number: \_\_\_\_\_ Issue: \_\_\_\_\_  
(a) Type: \_\_\_\_\_  
(site, architectural, structural,  
mechanical, electrical, equipment)  
(b) Design agency: \_\_\_\_\_  
(c) Source: \_\_\_\_\_

Figure 2-2. Sample Site Survey Checklist (sheet 13 of 15).

16 February 1979

SEIP 012

14. Expandable building.

- a. On base (give location): \_\_\_\_\_.
- b. Off base (give location): \_\_\_\_\_.
- c. Sketch or marked drawing showing proposed method of expansion: \_\_\_\_\_.

15. Physical security.

- a. If adequate, describe: \_\_\_\_\_.
- b. If inadequate, list steps necessary to make adequate (i.e., fence, lights, alarms, guards, etc.): \_\_\_\_\_.

16. Fence enclosures

- a. Area enclosed: \_\_\_\_\_.
- b. Owner: \_\_\_\_\_.
- c. Type and heights: \_\_\_\_\_.
- d. Identification: \_\_\_\_\_.
- e. Shown in drawing number: \_\_\_\_\_.

Figure 2-2. Sample Site Survey Checklist (sheet 14 of 15).

17. Projection or obstructions.

-----  
-----  
-----  
-----  
-----  
-----

18. Remarks and pertinent data not covered by preceding sheets.

-----  
-----  
-----  
-----  
-----  
-----

S  
A  
M  
P  
L  
E

Site Survey Team Chief

Figure 2-2. Sample Site Survey Checklist (sheet 15 of 15).

16 February 1979

SETP 012

2.5 EQUIPMENT CHARACTERISTICS. The physical and electrical characteristics of the AN/FPN-41 TVOR system and Recorder/Reproducer Set, TRC-89-4, are listed in table 2-1. This table provides the project engineer assistance in determining size, power, and heat dissipation requirements for the TVOR facility.

SEIP 012

16 February 1979

TABLE 2-1. EQUIPMENT CHARACTERISTICS

NOMENCLATURE	Dimensions (in)		Height (lbs)	Operating Temperature	Operating Humidity	Input Power	Power Consumption
	Height	Depth					
Transmitting Set, Radi, AN/FRN-41:	-	-	*	-	-	210-260 Vrms 47-63 Hz	600W, Normal 1200 W, Max
Transmitter, T-1394/FRN-41	8-3/4	19	19-3/4	* -100 to 50° C	95 percent	-	-
Transmitter, T-1395/FRN-41	8-3/4	19	19-3/4	* -100 to 50° C	95 percent	-	-
Monitor, ID-2175/FRN-41	8-3/4	19	19-3/4	* -100 to 50° C	95 percent	-	-
Detector, DT-603/FRN-41	-	-	*	* -550 to 75° C	95 percent	-	-
Antenna, AS-3323/FRN-41	-	-	*	* -550 to 75° C	95 percent	-	-
Control-Indicator, C-10527/FRN-41	8-3/4	19	19-3/4	* -100 to 50° C	95 percent	-	-
RF Power Monitor	8 3/4	19	19 3/4	* -100 to 50° C	95 percent	-	-
Control-Indicator, C-10526/FRN-41	8 1/2	19	19 3/4	* *	*	120Vac 50/60Hz	*
Environmental Control Unit, P/O S-597/FRN-41	-	-	236	* *	*	208/230 Vac 60 Hz	10.7 kw
Recorder/Reproducer Set, Type TRC-89-4	5 1/4	19	15 1/2	37-1/2	*	115/230 Vac 50/60 Hz	40 W (60Hz) 60 W (50Hz)

\* Not available

16 February 1979

THIS PAGE IS BEST QUALITY PRACTICABLE  
FROM COPY FURNISHED TO DDC

SEIP 012

### SECTION 3. INSTALLATION SPECIFICATIONS AND INSTRUCTIONS

3.1 GENERAL. The installation specifications and instructions outlined in this section provide guidance for the engineering and installation of a TVOR facility employing Transmitting Set, Radio, AN/FRN-41 (V).

3.1.1 Applicable documents. Documents listed in 1.5 form a part of this installation package. Unless otherwise indicated, the issue in effect on the date of publication of this document shall apply. When the requirements of these documents conflict, the SEIP shall govern. Further, all drawings referred to in this SEIP are available in Section 4.

3.2 INSTALLATION INSTRUCTIONS. The procedures required to install the TVOR facility will be accomplished in a definite order. This will ensure that all work is completed as represented on the installation drawings ensuring all specifications are adhered to. Minor changes to the installation sequence may be made in consideration of manpower, time, equipment, material and safety. The following steps are recommended:

3.2.1 Preinstallation steps. Prior to starting installation, the following must be accomplished:

3.2.1.1 Coordinate installation tasks with the operating agencies and/or other cognizant organizations. This will include clearance to proceed, logistics, review of support requirements, and request of any other support necessary for the completion of tasks.

3.2.1.2 Verify that all support requirements are complete or will be completed in time to prevent delays.

3.2.1.3 Brief team members on particular hazards that may be encountered. Emphasize safety by reviewing safety procedures and practices.

3.2.1.4 Inventory the BOM to ensure all items are on hand. Missing items or shortages must be noted prior to the arrival of the team onsite.

SEIP 012

16 February 1979

3.2.1.5 Arrange for the transportation of personnel and equipment; determine the methods for control and storage of BOM items, tools, and other required equipment.

3.2.1.6 Review all specifications and drawings to ensure no additional engineering assistance is required prior to the start of installation.

3.2.1.7 Coordinate all outages that may be required for the installation and/or cutover of this facility.

3.2.2 Site preparation. Prior to the erection of Shelter, S-597/FRN-41 and the installation of Transmitting Set, Radio AN/FRN-41 (V) and supplementary equipment, the site must be prepared as follows:

3.2.2.1 Establishing site bearing and trenches. Refer to drawing STD-AF-0125, sheet 3. Drive the ground rod, as a reference stake for positioning the transit, at the center of the selected shelter site leaving approximately 16 inches of the rod above ground.

3.2.2.2 Center the transit over the reference stake, site in the direction of the power source, and place a reference stake for the terminal pole 750 feet from the center of the shelter.

NOTE: Unless otherwise specified, ALL measurements are taken from the center of the selected shelter site.

3.2.2.3 Place a second reference stake 75 feet beyond the terminal pole reference stake, and a third reference stake along this radial 12 feet from the transit.

3.2.2.4 The three reference stakes plotted locate the radial that the power line trench will follow.

3.2.2.5 With the transit properly centered, site on magnetic north and locate reference stakes out 55- and 100-feet respectively. Next, repeat this procedure placing two additional reference stakes on a radial 45 degrees counterclockwise (CCW) from magnetic north.

3.2.2.6 The four reference stakes just located will be used for the orientation of the shelter, radome, and antenna system.

3.2.2.7 When Control-Indicator, C-10526/FRN-41 (remote control unit) is not located in the same direction as the power source, establish a radial to the remote site location using the procedures outlined for locating the power line trench radial. This establishes the radial for the remote control lines trench.

3.2.2.8 The trench from the terminal pole need be no deeper than 24 inches to avoid interference with the TVOR signal. Further, if power and control lines are on the same radial, the power line is placed at the bottom of the trench, the trench is filled with 12 inches of dirt, the control lines are placed in the trench and the remainder of the trench (12 inches) is filled with dirt. This procedure will prevent mutual coupling.

3.2.3 Shelter foundation construction. Refer to drawing STD-AF-0125, sheet 3. Using the reference stake at the center of the site, lay out a circle having a radius of 10 feet, 10 inches. With the circumference of circle as the center line, dig a circular trench 1 foot wide to a minimum depth of 24 inches. This trench must be deep enough to place the bottom of the concrete footings below the frost line.

3.2.3.1 Refer to figure 3-1. Prepare a depression for the centering ring by digging out a circular area around the reference stake 36 inches in diameter, with a minimum depth of 1.5 inches. Bevel the edges of the depression.

3.2.3.2 Ready a depression for the facility sidewalk by marking a circle with a 14-foot radius on the ground and removing 4 inches of soil between this circle and the footing trench.

3.2.3.3 Using the radial established for the power and control line trench, dig a trench outward to accommodate the required conduit(s). Ensure the trench slopes downward toward the outside and terminates several feet from the sidewalk depression.

3.2.3.4 Prior to pouring the concrete footing, block off that portion(s) of the footing trench through which the power and control line conduit(s) will pass.

3.2.3.5 Concrete shall be structural grade with a minimum compression strength after 28 days of curing. Recommended richness of mixture by volume is one part cement to two parts fine aggregate to three parts coarse aggregate. Refer to TO 31-10-5 for methods and other information to ensure standardization of installations, and as a reference for verification and QA procedures.

**THIS PAGE IS BEST QUALITY PRACTICABLE  
FROM COPY FURNISHED TO DDQ**




Figure 3-1. Twenty-one Foot Shelter Excavation and Footing.

16 February 1979

SETP 012

3.2.3.6 Pour the concrete footing, keeping it as level as possible, to whatever level is necessary to place the top of the foundation form 4.5 inches below the grade line.

3.2.3.7 Refer to drawing STD-AF-0125, sheet 1. Establish the location of the shelter door ensuring a foundation ring seam is located approximately in the center of the area selected.

3.2.3.8 Refer to drawing STD-AF-0125, sheet 2, section C-C. Assemble the 14 foundation ring staves to construct a form for the shelter floor.

3.2.3.9 Refer to drawing STD-AF-0125, sheet 1. With the foundation form seams positioned so the wall seams will not fall at the same points, determine the radials of the seven foundation form centering straps will occupy when the form is installed. Remove sufficient soil along the seven radials to allow clearance for the centering straps and permit the foundation form to set solidly on top of the footing.

3.2.3.10 Refer to drawing STD-AF-0125, sheet 2, section D-D. Install the seven centering straps. At points where the centering straps are attached, install a leveling bolt as shown in section B-B; thereafter, fasten the centering straps to the anchor bolt centering ring as shown in section F-F.

3.2.3.11 With the foundation form on top of the footing, ensure the form and center anchor ring are as level as possible and that the foundation form will remain circular within  $\pm 1/4$ -inch during the concrete pour.

3.2.3.12 The ends of the conduit, which terminate inside the shelter, must be as close as possible to the ground rod and extend approximately 3 inches above the finished floor. When the conduits are in the same trench they may be bound together a major portion of their length. The conduits must be securely fastened in the trenches and to the ground rod so they will not move out of position when the concrete floor is poured.

3.2.3.13. Cover the conduit trench with earth, compact the area within the foundation form, and prepare the area as shown in drawing STD-AF-0125, sheet 1, section A-A. After the area is properly prepared, pour the concrete into the form evenly, ensuring the form remains circular within prescribed limits.

3.2.3.14 After sufficient curing time, pour the sidewalk as shown in section A-A of the aforementioned drawing.

3.2.4 Power and control lines. Lay the power and control lines in their trenches up to the shelter foundation. Pull the power and control lines through their conduit allowing a minimum of 6 feet of power line and 8 feet of control line to extend from the ends of the conduits.

3.2.4.1 Coil the lines to the proper size and shape to easily fit through the hole in the base of the shelter pedestal.

3.2.4.2 Backfill the trenches with earth.

3.2.5 Shelter assembly. Refer to drawing STD-AF-0125, sheet 2, section E-E. Remove the nuts and washers from the bolts in the pedestal anchor ring.

3.2.5.1 Reference drawing STD-AF-0126, sheet 3, section A-A. Orientate the antenna pedestal so the openings are opposite the door location, and carefully place the power and control lines in the pedestal's hollow base.

3.2.5.2 Install the pedestal on its base being careful not to damage the power and control lines.

3.2.5.3 Replace the nuts and washers removed from the pedestal anchor ring and hand tighten the nuts so they may be adjusted during the later stages of the shelter assembly.

3.2.5.4 Refer to details C and L. Prior to erecting the shelter wall sections, install the strip gasket and bolts on the foundation flange. Overlap the gasket two holes and tapercut the edge.

3.2.5.5 Refer to section D-D. Before placing a wall section on the foundation flange, install the vertical strip gasket, bolt retainer channel, and bolts on the wall section.

3.2.5.6 Refer to drawing STD-AF-0126, sheet 2, sections H-H, J-J, and K-K. Starting with the door wall section, place it on the foundation flange, align the bolts and holes, install the nuts, and hand tighten. Continue CCW from the inside of the shelter assembling the wall sections using alternate orange and white wall sections as shown on drawing STD-AF-0126, sheet 1.

3.2.5.7 Locate the white wall section with the air conditioner stave between two orange wall sections on the northeast side of the shelter.

16 February 1979

SEIP 012

3.2.5.8 Refer to drawing STD-AF-0126, sheet 3, section A-A. Install the flanged roof support ring on the pedestal, seven support angle braces, and roof landing ring. Do not tighten the roof landing ring nuts since it may require adjustment to position of the roof sections.

3.2.5.9 Refer to drawing STD-AF-0126, sheet 1. The 14 wedge-shaped roof section assembly details are provided in the aforementioned drawing. Prior to raising the first roof section, install bolt retainers, strip gasket, stiffeners, and bolts. Raise the roof section with the small end resting on the pedestal flange and the large end resting on the wall section. Position the roof section edge with the bolts, stiffeners, and gaskets in the center of the wall section to ensure the roof seams will not align with the wall seams.

3.2.5.10 Raise the second roof section after installing the bolt retainers, strip gasket, bolts, and deck stiffeners. Place it to the right side (looking from inside the shelter) of the first section. Apply caulking to the entire length of the roof seam before putting the roof section in place.

3.2.5.11 Align the bolt holes in the left edge of the second section with the captive bolts in the right edge of the first section to form an overlapping seam. Repeat this procedure for the remaining roof sections.

3.2.5.12 With all bolts around the pedestal and landing ring flange inserted from inside the shelter, fasten the roof sections to the pedestal flange. Tighten the flange bolts securely.

3.2.5.13 Fasten the overlapping edges of the roof sections. Tighten the nuts on the captive bolts; however, do not install bolts where roof seams rest on the wall seams and landing ring.

3.2.5.14 Refer to drawing STD-AF-0126, sheet 3, section D-D. Permanently bolt the wall sections together at the seams. Fasten the roof to wall sections as shown in detail G and tighten all bolts securely.

3.2.5.15 Fasten the wall sections to the foundation form as shown on drawing STD-AF-0126, sheet 2, detail L and sheet 3, detail C. Tighten all bolts securely.

3.2.5.16 Inside and outside the shelter, caulk all joints formed by roof sections, overlapping wall sections and the foundation forms.

3.2.6 Environmental equipment. Refer to drawing STD-AF-0128. Install the air conditioning/heating unit as indicated. Also, install the thermostat at a point on the shelter wall approximately 60 inches from the floor and close to the 315-degree radial. The thermostat bracket is installed by removing the two bolts which secure the shelter sidewall joints and installing it between the shelter wall and bolt retainer. The thermostat is then mounted on the bracket. The antenna blower is installed as shown in view A-A.

3.2.7 Electrical. Refer to drawing STD-AF-0129, sheet 1. This is a detailed layout of the shelter power distribution system. Install the electrical wiring as follows:

3.2.7.1 Install the circuit breaker box using the two mounting straps. Install the junction box and flexible conduit between the power conduit in the concrete slab and the circuit breaker box.

3.2.7.2 Install the connecting boxes for the four light fixtures. (Refer to figure 3-2.)

3.2.7.3 Install the environmental unit power conduit on the exterior of the shelter as shown on sheet 2.

3.2.7.4 Install the convenience outlet box on the junction box mounting board.

3.2.7.5 Run the flexible conduit for the four light fixtures, antenna blower assembly and obstruction lights. Attach the conduit with clips and screws to the roof flange.

3.2.7.6 Install the flexible conduit from the circuit breaker box for the electronics assembly and environmental units as shown, attaching the conduits to the deck stiffeners with a clamp. The conduit for the electronics assembly will be attached to the shelter roof and terminate in the approximate location of the electronics assembly as indicated on drawing STD-AF-0550, sheet 1.

3.2.7.7 Install the flexible conduit from the input power line, using the connection box to the circuit breaker as shown on drawing STD-AF-0129.

3.2.7.8 Refer to drawing STD-AF-0551. Using the interconnecting information on this drawing, run wires through the conduits installed and leave enough wire at each terminal to permit proper connection.




Figure 3-2. TVOR Facility Floor Plan.

3.2.8 Detector, RF, DT-603/FRN-41 (field detector). Refer to drawing STD-AF-0553. Set the transit at the center of the shelter roof, ensuring it is level, and site on the magnetic north reference stakes. On this line, install the first detector bracket as shown in detail A.

3.2.8.1 From the magnetic north ( $0^{\circ}$ ) position, rotate clockwise, and every  $22.5^{\circ}$ , install a field detector bracket. Stencil the location of this field checkpoint at a convenient height on the shelter wall.

3.2.8.2 Cable assembly W1 will be installed at  $90^{\circ}$  or  $180^{\circ}$ , whichever is closer to the monitored radial. To install the cable assembly, remove the bolt nearest the roof strut radial inside the shelter, insert the cable assembly into the hole, caulk the hole around the cable assembly, and terminate it at the proper location on the electronics assembly.

3.2.9 Antenna, AS-3323/FRN-41. Refer to drawing STD-AF-0125, sheet 3. Center the transit over the 55-foot magnetic north reference marker and sight to the center of Shelter, S-597/FRN-41, and the 100-foot magnetic north reference marker to verify that the alignment is correct.

3.2.9.1 Refer to drawing STD-AF-0126. After ensuring the three antenna cables are carefully inserted into the antenna pedestal, place Antenna, AS-3323 support pipe into the antenna flanged holder with the black (north) strip facing magnetic north. Adjust the eight jack screws to level the antenna and hold it in position.

3.2.9.2 Using the transit, align the antenna to the magnetic north position and ensure the antenna is vertical from top to bottom. When the alignment is complete, tighten the additional lock nut on each jack screw and double check the antenna orientation.

3.2.10 Radome. Refer to drawing STD-AF-0554. Determine the correct direction of the radome access door and place that half of the radome on the shelter roof.

3.2.10.1 Refer to drawing STD-AF-0128. Align the holes in the bottom of the radome section with the anchor bolt holes in the shelter roof. Place the bolts through the bottom of the radome section, but do not tighten them.

3.2.10.2 Install the rubber gasket on the radome flange, vertical seams, and around the access door.

16 February 1979

SEIP 012

- 3.2.10.3 Place the other radome half-section in position and insert the bolts through the radome flange and the roof. Do not tighten the bolts.
- 3.2.10.4 Bolt the radome halves together.
- 3.2.10.5 Raise the radome and caulk a full bead under the radome flange. Tighten the bolts securing the radome and caulk the seam between the radome flange and the roof.
- 3.2.10.6 Install a rubber gasket on the radome cap flange. Place the radome top cap in position and secure it to the radome.
- 3.2.11 Photo cell and obstruction light assembly. Refer to drawing STD-AF-0554. Install the photo cell and obstruction light assembly as shown. Install the wiring for this assembly in accordance with drawing STD-AF-0551.
- 3.2.12 Insulation kit. Refer to drawing STD-AF-0130. After all electrical wiring and environmental kits have been installed, the insulation kit for the shelter can be installed.
- 3.2.12.1 Attach the stick clips to the roof sections and wall panels. Let the adhesive cure 6 to 8 hours before installing the insulation.
- 3.2.12.2 Install the ceiling panels, cutting around the light fixtures as required. The ceiling panels are cut to the proper size prior to shipment.
- 3.2.12.3 Starting at the left hand side of the door, set the end of the 48-inch wide roll of insulation flush with the door jam and install the wall section insulation.
- 3.2.12.4 Apply the white vinyl tape to all seams between ceiling sections over the door and around the environmental units and thermostat.
- 3.2.12.5 Push all stick clips approximately 1 inch onto the nail and trim the nail flush to the clip.
- 3.2.13 Electronic equipment. Refer to drawing STD-AF-0552. Remove the electrical equipment rack from the shipping container and install it as shown. A recommended floor plan for the TVOR facility is shown in figure 3-2.

THIS PAGE IS BEST QUALITY PRACTICABLE  
FROM COPY FURNISHED TO DDC

3.2.13.1 Refer to drawing STD-AF-0551. Connect the 120 Vac power to the terminal block at the top of the rack. Connection of all power plugs, terminal strips, and coaxial cables are shown in this diagram.

3.2.13.2 Refer to drawing STD-AF-0552. Connect the field detector cable to the terminal block at the top of the rack.

3.2.13.3 Install the three RF cable assemblies between the antenna system and equipment rack to the proper connectors in the antenna, figure 3-3. Route the cable assembly down through the center of the antenna, into the pedestal mount, and out the access hole.

3.2.13.4 All units of the TVOR system, with the exception of the RF power monitor, are mounted in the equipment rack with drawer slides. The RF power monitor is a panel-mounted unit that is an integral part of the equipment rack.

3.2.13.5 Install Transmitter, Sideband, T-1395/FRN-41; Transmitter, Radio, T-1394/FRN-41; Monitor, Phase Modulation, ID-2179/FRN-41; and Control-Indicator, C-10527, in their designated location in Equipment Rack MT-6011, as shown on drawing STD-AF-0552. Make all power plug, terminal strip and coaxial cable connections as shown on drawing STD-AF-0551.

3.2.13.6 Install an electrical ground system for the equipment rack. Refer to drawing STD-AF-0552.

3.2.14 Control-Indicator, C-10526/FRN-41 (remote control). This remote control unit can be located at any facility up to 20 miles using a 16 AWG twisted pair. Refer to drawing STD-AF-0551 for interconnection details.

3.2.15 Supplementary equipment. The following supplementary equipment is optional. However, if a requirement exists for the particular equipment it will be installed using the following standard procedures:

3.2.15.1 Protector terminal block. Affix the required protector terminal block to a blank panel as shown in drawing STD-AF-0552, detail C. Mount the panel in the equipment rack in its designated location and install the wiring as also shown in detail C.




Figure 3-3. Antenna Cable Location.

3.2.15.2 Emergency alarm bell. Refer to drawing STD-AF-0552, detail D. Using the relay and alarm bell as a template, mark the location of the mounting holes to be drilled in the blank panel. Drill the holes in the panel and mount the relay and alarm bell as shown. Install the completed panel in the equipment rack in its designated location and connect the wiring as shown.

3.2.15.3 Automatic terminal information system (ATIS) TRC-89-4. Refer to drawing STD-AF-0580. Recorder/Reproducer, TRC-89-4, is mounted in a standard equipment rack such as the CY-597. A set of slides are provided for installation of the TRC-89-4 in the equipment rack. However, four mounting brackets must be fabricated. Additionally, the remote control cable between the CU-89 and the TRC-89-4 must be locally fabricated to conform to local console/rack configurations.

3.2.15.3.1 Install the TRC-89-4 in the equipment rack as shown in detail B using the four locally fabricated mounting brackets, detail C.

3.2.15.3.2 Install remote control CU-89 in a tower console or equipment rack. Installation will depend on the local rack/console configuration.

3.2.15.3.3 Install the local fabricate remote control cable between the TRC-89-4 and the CU-89.

3.2.15.3.4 Install the cabling between Recorder/Reproducer Set, TRC-89-4, and Control-Indicator, C-10526/FRN-41, as shown in the cabling diagram.

3.2.15.3.5 Install the cabling between the Control-Indicator, C-10526/FRN-41, and Rack, NT-6011/FRN-41, as shown in the cabling diagram.

### 3.3 CHANGES TO SPECIFICATIONS.

3.3.1 Minor changes. The installation team chief is authorized to make minor changes to the requirements and instructions contained in this specification without prior approval of the engineer.

3.3.2 These changes shall be documented by the team chief either on the marked-up drawings or in the letter of transmittal which forwards the marked-up drawings.

16 February 1979

SEIP 012

3.3.3 A minor change is one which DOES NOT:

3.3.3.1 Alter the intended operational capability of the specification.

3.3.3.2 Violate a mandatory standard.

3.3.3.3 Alter the intent or end-result of the required testing.

3.3.4 Major changes. The installation team chief shall not make major changes to the requirements and instructions contained in the specification without the specific approval of the project engineer. Request for an approval of a major change may be made by telephone; however, a followup message or letter is required. These changes shall be documented by the team chief either on the marked-up drawings or in the letter of transmittal. In all cases, the document which authorizes the change shall be included with the marked-up drawings.

3.4 AS-BUILT DRAWINGS.

3.4.1 Upon completion of the installation, the installation team chief shall mark up two sets of drawings to show the "as-built" condition of the facility covered by this specification.

3.4.2 As-built drawings will be prepared using red and yellow pencil. Red for additions and yellow for deletions. Drawings will conform with basic engineering practices.

THIS PAGE IS BEST QUALITY PRACTICABLE  
FROM COPY FURNISHED TO DDO

SECTION 4. ENGINEERING INSTALLATION DRAWINGS

4.1 GENERAL. The standard drawings in this section are applicable to the installation of the AN/FRN-41 TVOR system. The engineer must ensure the system meets operational requirements, while being cognizant of local conditions; therefore, the drawings furnish guidance and standard engineering data to be used in the development of an EIP. The drawings furnished are 10-1/2 by 16 inches, foldout type, and are not in scale format. The scale referenced on these drawings refer to the "D" size drawings only.

4.1.1 Three sets of engineering drawings are furnished to an installation team. One set is used as "working drawings" while a record of approved changes and work completed will be made on the remaining two sets. Information will be recorded on the drawings as follows:

4.1.1.1 Red lines will be used to denote additions and work completed.

4.1.1.2 Yellow lines will be used to indicate deletions.

4.1.1.3 Blue lines will be used to provide notes to the draftsman or engineer.

4.1.2 When the installation is completed, one set of "marked-up" drawings will be left with the local USACC Commander and another "marked-up" set of drawings will be forwarded to the project engineer for review and preparation of "as-installed" drawings.

**THIS PAGE IS BEST QUALITY PRACTICABLE  
FROM COPY FURNISHED TO DDQ**

4.2 USACEEIA DRAWINGS.

<u>DRAWING NO.</u>	<u>TITLE</u>
STD-AF-0125	TVOR Foundation Plan 21-Foot Shelter
STD-AF-0126	TVOR Shelter, 21-Foot Erection Details
STD-AF-0128	TVOR System Shelter Assembly Details
STD-AF-0129	TVOR System Power Distribution and Lighting Kit Installation
STD-AF-0130	21-Foot TVOR Shelter Insulation Kit Installation Details
STD-AF-0551	TVOR System Interconnection Diagram
STD-AF-0552	TVOR Electronic Equipment Installation
STD-AF-0553	TVOR System Detector, DT-603/FRN-41 Installation Detail
STD-AF-0554	TVOR Radome Assembly Installation Details
STD-AF-0580	Automatic Terminal Information System (ATIS) TRC-89-4 Installation Details





8


7

6

5


4

D




**SECTION B-B  
LEVELING BOLT  
(7 PLACES)**

C




**SECTION F-F**

B



**SECTION C-C  
FOUNDATION STAVE JOINT  
(14 PLACES)**

A



**SECTION D-D  
CENTERING TIE STRAP  
(7 REQ'D)**



8

7


6

5

4


5 4 3 2 1

ZONE		REV		REVISION	DATE	APPROVED
2A	A			ADDED THE WORD METRIC	17 OCT 78	[Signature]




SECTION F-F

- NOTES:
- 201. DO NOT USE TOP HOLE.
  - 202. PEDESTAL INSTALLED WITH SHELTER AFTER CONCRETE CURES.



SECTION E-E  
LOCATING RING



D-D  
TIE STRAP

METRIC

IDENT NO. STD-AF-0125			SIZE FRCH NO. D 50470		DRAWING NO.	
SHEET 2 OF 3			SCALE NONE		SHEET OF	
DRAWN BY HILBORN			APPROVED BY [Signature]		DATE 17 OCT 78	

5 4 3 2 1


2

D

C

B

A



8

7

6

5

4

D

C

B

A

MAGNETIC NORTH

100 FOOT MARKER  
(30.5 METERS)

100 FOOT MARKER  
(30.5 METERS)

55 FOOT MARKER  
(16.8 METERS)

55 FOOT MARKER  
(16.8 METERS)

75 FEET  
(22.9 METERS)

750 FOOT MARKER  
(228.6 METERS)

11'4"  
(3.45 METERS)

12 FOOT MARKER  
(3.66 METERS)

45°  
CCW

GROUND ROD

1 FOOT (0.3 METERS) WIDE

4'4"  
(1.32 METERS)

8

7

6

5

4

5

4


3

2

1

REVISION				
ZONE	REV	DESCRIPTION	DATE	APPROVED

TO POWER SOURCE



825 FOOT MARKER

750 FOOT MARKER  
(228.6 METERS)

LEGEND:

--- INDICATES TRENCHING

12 FOOT MARKER  
(3.66 METERS)

GROUND ROD

1 FOOT (0.3 METERS) WIDE

D

C

B


A

METRIC


TVOR FOUNDATION PLAN  
21 FOOT SHELTER

IDENT NO <b>STD-AF-0125</b>	SIZE <b>D</b>	PSCM NO <b>50470</b>	DRAWING NO
DRAWN BY <b>B. ROBINSON</b>	SCALE <b>NONE</b>	SHEET OF	
APPROVED BY <i>[Signature]</i>	DATE		

2










5      4      3      2      1

ZONE REV		REVISION	DATE	APPROVED
A	MINOR REVISIONS		19 OCT 78	<i>[Signature]</i>



D

C


B

A



TVOR SHELTER, 21 FEET  
ERECTION DETAILS

IDENT NO STD-AF-0126 SHEET 2 OF 3	SIZE FROM NO D 50470	DRAWING NO
DRAWN BY M GUNNING	SCALE NONE	SHEET OF

5      4      3      2      1



REVISION				
ZONE	REV	DESCRIPTION	DATE	APPROVED
	A	CHANGED BOLT RETAINER DETAIL	8 MAY 78	<i>[Signature]</i>
	B	MINOR REVISIONS	17 OCT 78	<i>[Signature]</i>



- NOTES:**
- 301. POSITION PEDESTAL SO OPENINGS ARE OPPOSITE DOOR.
  - 302. REINFORCEMENT ANGLE TO BE MOUNTED WITH HARDWARE SUPPLIED WITH AIR CONDITIONING UNIT.
  - 303. APPLY CAULKING BEAD ALONG ENTIRE LENGTH OF DECK SECTION PRIOR TO PLACING NEXT SECTION IN PLACE.

**TVOR SHELTER, 21 FEET  
ERECTION DETAILS**

IDENT NO <b>STD-AF-0126</b>	SIZE FROM NO <b>D 50470</b>	DRAWING NO
DRAWN BY <b>B. SLAVICK</b>	SCALE <b>NONE</b>	SHEET OF
APPROVED <i>[Signature]</i>		

*[Handwritten mark]*

8

7

6

5

4

D

C

B

A

44 14

53 54 55 56 57

49

VIEW A-A

31 196 197 198 199

30

195 39


48

17

32 8 40 9

47

30



VIEW B-B

8

7

6

5

4

5

4


3

2

1

55 56 57

REVISION			
ZONE	REV	DESCRIPTION	DATE
D 6	A	DELETED CABLES EXITING FR DISTR PANEL	8 MAY 78
	B	REVISED ITEM NO 52	17 OCT 78



VIEW B-B

GENERAL NOTE:

1. ALL ITEMS ON THE LIST OF MATERIALS ARE SUPPLIED BY THE EQUIPMENT MANUFACTURER AS PART OF THE TVOR SHELTER.

ITEM	QTY	DESCRIPTION	NSN	U/I	QTY
199	23340K	NUT, HEX 5/16 - 18UNC, GALV		EA	6
198	23339H	WASHER, RING 5/1610		EA	6
197	08131R	WASH, FLAT 5/1616	5310-00-578-2074	EA	6
196	23338G	BOLT, SQ. HD., 5/16 - 18 UNC X 1 3/4		EA	6
195	23337F	SCREW, SP, PH #6 - 5/8 LG		EA	4
61	22838C	FILTER, AIR		EA	1
60	22837B	SPACER, WOOD		EA	2
59	22836A	BRACKET, THERMOSTAT		EA	1
58	22835Z	SCREW, SHEET METAL, NO. 10 - 3/4 LG, GALV		EA	24
57	22834W	NUT, REG, HEX, 1/4 X 20UNC, GALV		EA	6
56	22833H	WASHER, LOCK, 1/4ID, GALV		EA	4
55	22832G	WASHER, FLAT, 1/4ID, GALV		EA	4
54	22831F	BOLT, HEX HEAD, 1/4 - 20 X 1" LG, GALV		EA	4
53	22830E	BLOWER		EA	1
52	22829E	BOLT, SQUARE HEAD, 1/2 - 13 X 1 3/4 GALV		EA	34
51	22828D	ENVIRONMENTAL CONTROL		EA	1
50	22827C	KIT, FIELD DETECTOR, MOUNTING		EA	1
49	22826B	RADOME ASSEMBLY		EA	1
48	22825A	POWER DISTRIBUTION SYSTEM		EA	1
47	22824Z	KIT, INSULATION		EA	1
44	22821G	CLAMP, GROUNDING		EA	1
40	22817D	WASHER, RING, STEEL BACKED NEOP		EA	34
17	22793A	SHELTER, 21' DIA.		EA	1
14	22790K	STAKE, GROUNDING		EA	1
9	00493K	NUT, HEX, 1/2 - 13UNC, GALV	5310-00-768-0318	EA	34
8	16880H	WASHER, FLAT, 1/2ID, GALV	5310-00-088-7647	EA	34

LIST OF MATERIALS

IDENT NO	STD-AF-012B	ORGANIZATION	U S ARMY COMMUNICATIONS - ELECTRONICS ENGINEERING INSTALLATION AGENCY
SHEET	1 OF 1	TVOR SYSTEM SHELTER ASSEMBLY INSTALLATION DETAILS	
DRAWN BY	RK	DATE	11/16/78
CHECKED BY	RK	DATE	11/16/78
DESIGNED BY	CCG	DATE	11/16/78
DESIGN ACTIVITY	CCG-CED-SWA	SIZE	FOUR 1/2
NEXT ASSEMBLY	USED ON	DRAWING NO	D 50470
DWG INDEX NO		SCALE	NONE

2

SHEET 1 OF 1

8

7

6

5


4

D

C


B

A



B	-								
A	-								
1	2	3	4	5	6	7	8	9	10
SHEET NUMBER									
REVISION STATUS									





5

4

3

2

1


REVISION			
ZONE REV	DESCRIPTION	DATE	APPROVED

D

C

B

A



INTERNAL VIEW

**TVOR SYSTEM  
POWER DISTRIBUTION AND  
LIGHTING KIT INSTALLATION**

IDENT NO <b>STD-AF-0129</b>	SIZE FROM NO <b>D 50470</b>	DRAWING NO
DRAWN BY <b>2/2/59</b>	SCALE AS SHOWN <b>1" = 1/2"</b>	SHEET OF
APPROVED BY <i>[Signature]</i>		

2

5

4

3

2

1

8

7

6





5

4

D

C

B



DETAIL A

SECTION A

6

5

4







## TVOR POWER DISTRIBUTION WIRING LIST

WIRE NO.	MAKE FROM BOM NO.	APPROX LENGTH INCHES	FROM		TO		REMARKS
			CIRCUIT POINT	MATERIAL ITEM NO.	CIRCUIT POINT	MATERIAL ITEM NO.	
1			Customer furnished				P/O support construction
2			Customer furnished				P/O support construction
3			Customer furnished				P/O support construction
4	177	7	E1		2A1E5		
5	173	12	2A1CB101		2XDS1E1	182	Include blk wire from XDS1 and wire 6 in splice
6	173	12	2XDS1E1		2XDS2E1	182	Include blk wire from XDS2 and wire 7 in splice
7	173	12	2XDS2E1		2XDS3E1	182	Include blk wire from XDS3 and wire 8 in splice
8	173	12	2XDS3E1		2XDS4E1	182	Include blk wire from XDS4 in splice
9	174	12	2A1E4		2XDS1E2	182	Include wht wire from XDS1 and wire 10 in splice
10	174	12	2XDS1E2		2XDS2E2	182	Include wht wire from XDS2 and wire 11 in splice
11	174	12	2XDS2E2		2XDS3E2	182	Include wht wire from XDS3 and wire 12 in splice
12	174	12	2XDS3E2		2XDS4E2	182	Include wht wire from XDS4 in splice
13	177	12	2A1E5		2XDS1E3		
14	177	12	2XDS1E4		2XDS2E3		
15	177	12	2XDS2E4		2XDS3E3		
16	177	12	2XDS3E4		2XDS4E3		
17	176	2	2A1CB103		2A3E2		Silver colored mtg screw
18	174	2	2A1E4		2A3E1		Gold colored mtg screw
19	177	2	2A1E5		2A3E3		Grn colored mtg screw
20	174	1	2A3E1		2A3E4		Silver colored mtg screw
21	176	1	2A3E2		2A3E5		Gold colored mtg screw
22	173	6	2A1CB104		2B1E1	182	Splice with blk wire from B1
23	174	6	2A1E4		2B1E2	182	Splice with wht wire from B1
24	177	6	2A1E5		2B1E3		Connect to B1 frame
25							
26							
27							
28	176	12	2A1CB102		1A1TB1-1	194	
29	174	12	2A1E4		1A1TB1-2	194	
30	177	12	2A1E5		1A1TB1-3	194	
31	173	13	2A1XK1-4	194	2A4B71	182	Splice in base of XDS1/XDS2
32							
33	174	20	2A1E4		2A4XDS1E2	194	Include wht wire from B1 in splice
34	177	20	2A1E5		2A4E1	194	Connect to A4 frame
35	177	13	2A1XK1-A	194	1A1TB3-10	194	
36	179	13	2A1XK1-5	192	1A1TB3-11	192	
37	178	13	2A1XK1-8	192	1A1TB3-12	192	
38	176	2	2A4DS1E1	194	2A4XDS2E2	194	Include RED wire from B1
39	174	6	2A1CB105		2A1XK1-7	192	
40	174	4	2A4XDS1E2		2A4XDS2E2		Silver colored mtg screw
41	178	2	2A1XK1-8	192	2A1XK16	192	Splice with wire 37 using item 54
101 CONFIGURATION							
100	173	240	2A1CB107		2A6E1		
101	176	240	2A1CB107		2A6E2		
102	177	240	2A1E5		2A6E7		
103	173	240	2A1CB108		2A6E3		
104	177	240	2A1CB108		2A6E4		

5

4

3

2

1

REVISION				
ZONE	REV	DESCRIPTION	DATE	APPROVED
	A	REVISED BOM	29SEP78	<i>[Signature]</i>
	B	REVISED MATERIAL ITEM NO'S.	17 OCT 78	<i>[Signature]</i>

D

C

B

A

splice

54

TVOR SYSTEM  
INTERCONNECTION DIAGRAM

IDENT NO <b>STD-AF-0551</b>	SIZE <b>D</b>	PSCM NO <b>50470</b>	DRAWING NO
SHEET <b>2 OF 2</b>	DRAWN BY <b>RK</b>	SCALE <b>NONE</b>	1" <b>50470</b> SHEET OF
APPROVED BY	ENTERED IN WJACCELTA NO.		

5

4

3

2

2

ENTERED IN WJACCELTA NO.

8


7

6


5

4


D




**DETAIL A**  
ELECTRICAL EQUIPMENT RACK  
ANCHORING



**DETAIL B**  
ELECTRICAL EQUIPMENT RACK  
GROUNDING




C




**DETAIL C**  
PROTECTOR TERMINAL BLOCK MOUNTING PANEL  
(REAR VIEW)

B




**FIGURE 1**  
TVOR  
ELECTRICAL EQUIPMENT RACK

A



FRONT VIEW



REAR VIEW

**DETAIL D**  
EMERGENCY ALARM BELL PANEL

8


7

6

5

4

REVISION				
ZONE	REV	DESCRIPTION	DATE	APPROVED
	A	ADDED DETAIL E	31 JAN 79	[Signature]




**GENERAL NOTES:**

- ITEMS 153-160 ON THE LIST OF MATERIALS ARE SUPPLIED BY THE EQUIPMENT MANUFACTURER AS P/O THE TVOR SYSTEM. THE REMAINING ITEMS MUST BE SUPPLIED BY THE EQUIPMENT INSTALLATION AGENCY / CONTRACTOR.

**NOTES:**


- TELEPHONE CABLE VIA UPPER PEDESTAL OPENING.
- GROUND WIRE TO PEDESTAL.
- DRILL A 15/16" DIA HOLE IN THE TERMINAL MOUNTING PLATE TO ATTACH GROUND LUG.
- GROUND WIRE FROM GROUND LUG TO ANTENNA PEDESTAL.
- GROUND WIRE FROM GROUND LUG TO PROTECTOR BLOCK.
- TERMINAL LUG P/O PROTECTOR BLOCK.
- TO A1TB4 IN THE ELECTRONIC EQUIPMENT RACK. REFER TO DRAWING STD-AF-0551.
- INTERCONNECT FROM PROTECTOR BLOCK TO EMERGENCY ALARM PANEL.
- ALIGNMENT PIN.
- HARDWIRE TO AC SOURCE; TERMINAL BLOCK AITB1; SEE STD-AF-0551, SHEET 1 OF 2.

**DETAIL B**  
ELECTRICAL EQUIPMENT RACK  
GROUNDING



**DETAIL E**  
TVOR CABINET-TOP LEFT SIDE  
CABLE INTERFACE POINTS


**DETAIL C**  
PROTECTOR TERMINAL BLOCK MOUNTING PANEL  
(REAR VIEW)



**DETAIL D**  
EMERGENCY ALARM BELL PANEL

ITEM	AEL	DESCRIPTION	NSN	UI	QTY
160	22935A	ANTENNA, AS-3523 / FRN-41	NSNR	EA	1
158	22933W	MONITOR, PHASE, MOD ID-2179 / FRN-41	NSNR	EA	1
157	22932H	CONTROL-INDICATOR, C-10527 / FRN-41	NSNR	EA	1
156	22931G	TRANSMITTER, T-1394 / FRN-41	NSNR	EA	1
155	22930F	TRANSMITTER, T-1394 / FRN-41	NSNR	EA	1
154	22929F	RACK, MT-8011 / FRN-41	NSNR	EA	1
153	22922W	PANEL BLANK, PART NO. 135922-001	NSNR	EA	1
152	19255Y	SHIELD, EXPANSION, 3/8" RAWL. NO. 6006	NSNR	EA	AR
151	22500E	PANEL BLANK, ALUMINUM, 19" X 11 1/2" X 1/8"	5975-00-056-3984	EA	2
150	02406H	PANEL BLANK, ALUMINUM, 19" X 7" X 1/8"	5970-00-685-9791	EA	2
149	14886J	CABLE, POWER, ELEC, 3 C 16 AWG	6145-00-542-6068	FT	AR
148	00487C	WASHER, FLAT, NO. 8	5310-00-167-0833	HD	AR
147	10425H	NUT, HEX, NO. 8-32	5310-00-619-2480	EA	24
146	22928E	RELAY, POTTER-BRUMFIELD ABC7DY48	NSNR	EA	1
145	07966B	BELL, 117V AC, EDWARDS 340-6MS	6350-00-276-8812	EA	1
144	22503H	CABLE, TELE, 4 C 22 AWG, INSULATED	6145-00-577-8081	FT	AR
143	22504W	CABLE, TELE, 2 C 22 AWG, INSULATED	6145-00-635-1195	FT	AR
142	21872D	CABLE, TELE, 6 PR, BURIAL / DUCT	6145-00-526-2710	FT	AR
141	11526W	TERMINAL LUG, MECHANICAL COMPRESSION	5940-00-225-8860	EA	1
140	10231A	WASHER, LOCK, F/U/W 1/4" BOLT	5310-00-808-5381	EA	25
139	10290Y	WASHER, FLAT, .266 ID	5310-00-619-4898	EA	24
138	00558H	NUT, HEX, 1/4-20	5310-00-285-1850	HD	AR
137	00358F	BOLT, 1/4-20 X 1 1/4" LG	5306-00-141-2883	EA	AR
136	07452Y	TERMINAL LUG, CLAMP TYPE, 2-8 AWG	5940-00-549-6075	PG/IO	1
135	07472Q	SCREW, MACHINE, NO. 10-32 X 3/4" LG	5305-00-993-1848	HD	AR
134	02359E	BOX CONNECTOR, CLAMP	5975-00-152-1144	EA	1
133	05285Y	WIRE, COPPER, INS, 10 AWG, GREEN	6145-00-191-2569	FT	AR
132	03380Q	WIRE, ELEC, BARE, 6 AWG	6145-00-129-9320	FT	AR
131	00488D	WASHER, FLAT NO 10	5310-00-167-0834	HD	AR
130	00560J	NUT, HEX, NO. 10-32	5310-00-840-0830	EA	24
129	10113D	SCREW, MACHINE, NO. 10-32 X 1 1/2" LG	5305-00-995-3441	HD	AR
128	19881M	PROTECTOR BLOCK, 6 PR, RELIABLE R68CI-6P	5940-00-089-7802	EA	1

LIST OF MATERIALS			
IDENT NO	ORGANIZATION	DATE	APPROVED
STD-AF-0552	U.S. ARMY COMMUNICATIONS-ELECTRONICS ENGINEERING INSTALLATION AGENCY	3 OCT 78	[Signature]
DESIGNED BY: W. BESS		DATE: 3 OCT 78	
DRAWN BY: W. BOLLACK		DATE: 30 OCT 78	
CHECKED BY: [Signature]		DATE: 2 Nov 78	
APPROVED BY: [Signature]		DATE: 3 Nov 78	
DESIGN ACTIVITY	USED ON	SIZE FROM NO	DRAWING NO
CCC-CED-SEP		D 50470	
DWG INDEX NO.		SCALE NONE	SHEET OF



5


4

3


2

1

REVISION				
ZONE	REV	DESCRIPTION	DATE	APPROVED
	A	MINOR REVISION	17 OCT 78	<i>[Signature]</i>
	B	CHANGED PICTURE-BOLT DETAIL	31 JAN 79	<i>[Signature]</i>



DETAIL A



SECTION B-B

260.50

DETAIL A


## GENERAL NOTES:

1. ALL ITEMS ON THE LIST MATERIALS ARE SUPPLIED BY THE EQUIPMENT MANUFACTURER AS P/O THE TVOR SYSTEM.

## NOTES:

101. ITEM 111 IS USED WITH ITEM 110 TO STENCIL THE FIELD DETECTOR BRACKET LOCATIONS ON THE SIDE OF THE SHELTER.

FIELD CHECK LOCATIONS



135°

ITEM	AEL	DESCRIPTION	NSN	UI	QTY
111	22911W	PAINT, SPRAY, BLACK	NSNR	EA	AR
110	22910H	MARKING TEMPLATE KIT	NSNR	EA	1
109	22909H	FIELD DETECTOR ASSEMBLY	NSNR	EA	1
108	22908G	CABLE ASSEMBLY W3	NSNR	EA	1
107	22907F	CABLE ASSEMBLY W1	NSNR	EA	1
106	22806E	BRACKET, FIELD DETECTOR	NSNR	EA	17
38	22815B	BOLT, SQHD, 1/2 - 13 X 1.50 LG	NSNR	EA	17

## LIST OF MATERIALS

IDENT NO		ORGANIZATION	
STD - AF - 0553		U S ARMY COMMUNICATIONS-ELECTRONICS	
SHEET 1 OF 1		ENGINEERING INSTALLATION AGENCY	
DESIGNED BY	DATE	TVOR SYSTEM DETECTOR DT - 603 / FRN - 41 INSTALLATION DETAIL	
W. BESS	10/10/78		
DRAWN BY	DATE		
S. GILL	10/10/78		
CHECKED BY	DATE	DRAWING NO	
[Signature]	2/16/79	D 50470	
APPROVED BY	DATE	SIZE	FSCM NO
[Signature]	2/26/79	SCALE NONE	1" [Symbol]
NEXT ASSEMBLY	USED ON	DESIGN ACTIVITY	DRAWING NO
		CCC - CED - SEP	
DWG INDEX NO.		SCALE NONE	SHEET OF

5

4

3

2

1

*[Handwritten mark]*

8


7

6

5


4

D



DETAIL A


C



DETAIL B


OBSTRUCTION LIGHTS ASSEMBLY

B



A


DETAIL D



TO AC SOURCE BY CONDUIT ON OUTSIDE OF ANTENNA. DETAIL C.

DETAIL C

OBSTRUCTION LIGHTS ASSEMBLY



OBSTRUCTION LIGHT WIRES TO RELAY (SEE ADDITIONAL DWG)

DETAIL C  
OBSTRUCTION LIGHT ROUTING

8



7

6

5

4





5


4

3


2

1

REVISION				
ZONE	REV	DESCRIPTION	DATE	APPROVED
	A	REV CABLING DIAGRAM, ADD WIRING DIAGRAM	31JAN79	[Signature]



DETAIL B  
TRC-89-4 RACK MOUNTING




DETAIL C  
TRC-89-4 MOUNTING BRACKETS

GENERAL NOTES:


- ALL ITEMS ON THE LIST OF MATERIALS MUST BE SUPPLIED BY THE EQUIPMENT INSTALLATION AGENCY/CONTRACTOR SINCE THEY ARE NOT P/O THE TVOR SYSTEM.

NOTES:

- PART OF RECORDER/REPRODUCER SET TRC-99-4
- THE TRC-89-4 IS SHIPPED WITH RACK MOUNTING SLIDES ATTACHED; HOWEVER, THE MOUNTING BRACKETS, DETAIL C, MUST BE FABRICATED.
- REMOTE CONTROL CABLE BETWEEN THE REMOTE CONTROL UNIT AND THE RECORDER/REPRODUCER MUST BE LOCALLY FABRICATED.
- USE LOM ITEM 204 AS ALUMINUM STOCK.



BLOCK WIRING DIAGRAM



ITEM	AEL	DESCRIPTION	NSN	U1	QTY
204	11356D	PANEL, ALUMINUM, 19" X 5 3/4" X 3/16"	NSNR	EA	AR
191	22503H	CABLE, 4C, 22 AWG	6145-00-577-8061	FT	AR
190	17398M	CABLE, 1 PR, BELDEN	6145-00-080-1486	FT	AR
183	14549G	CABLE, 18C (9PR), 22 AWG	6145-00-957-8516	FT	AR
164	00483J	WASHER, LOCK SPLIT, NO. 10	5310-00-045-3296	HD	AR
163	00337G	SCREW, MACHINE, NO. 10-32 X 1/2" LG	5305-00-989-7434	HD	AR
162	22937C	REMOTE CONTROL, CU-89	NSNR	EA	1
161	22936B	RECORDER/REPRODUCER, TRC-89-4	NSNR	EA	1
130	00560J	NUT, HEX, NO. 10-32	5130-00-840-0530	EA	AR

LIST OF MATERIALS

IDENT NO <b>STD-AF-0580</b> SHEET 1 OF 1	ORGANIZATION <b>U.S. ARMY COMMUNICATIONS-ELECTRONICS ENGINEERING INSTALLATION AGENCY</b>
DESIGNED BY <b>W. BESS</b>	DATE <b>2 OCT 78</b>
DRAWN BY <b>M. BOLLACK</b>	CHECKED BY <b>[Signature]</b>
APPROVED BY <b>[Signature]</b>	DATE <b>2 JAN 79</b>
<b>(ATIS) TRC-89-4 AUTOMATIC TERMINAL INFORMATION SYS INSTALLATION DETAILS</b>	
NEXT ASSEMBLY <b>DWG INDEX NO. 1</b>	USED ON <b>CCC-CED-SEP</b>
DESIGN ACTIVITY <b>CCC-CED-SEP</b>	SIZE FROM NO <b>D 30470</b>
SCALE <b>NONE</b>	DRAWING NO <b>[Blank]</b>
	SHEET OF <b>[Blank]</b>

5

4

3

2

1

*J*

AD-A065 932

ARMY COMMUNICATIONS COMMAND FORT HUACHUCA ARIZ  
STANDARD ENGINEERING INSTALLATION PACKAGE. TERMINAL VHF OMNIDIR--ETC(U)  
FEB 79

F/G 17/7

UNCLASSIFIED

ACC-SEIP-012

NL

2 of 3  
AD  
A065932



END  
FILED  
5 1979  
DDA  
CONT



SECTION 5. BILL OF MATERIALS

5.1 GENERAL. This section identifies major items of equipment and materials necessary to install the TVOR system. The items identified are intended as a guide for preparing a BOM associated with a particular EIP. Items may be added or deleted as required to meet the requirements of a specific installation.

5.2 MAJOR ITEMS. The major items are listed on DA Form 3071R, Bill of Materials, shown in figure 5-1. The authorized equipment list (AEL) identification and national stock numbers are provided when available; however, when these numbers are not available the nomenclature will include the manufacturer's part number.

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENT CODE	
Per use of this form, see AR 105-22; the procuring agency is the United States Army Communications Command.		DATE	PAGE NO.	NO. OF PAGES	
TELER NUMBER		NONENCLATURE		TOTAL REQ FOR PROJECT	AVAILABLE IN COMMAND
ITEM NO.	STOCK NUMBER	NOTES	UNIT	REQ FOR PROJECT	REQUIRED
1*	MSNR (22781Z)	<p><b>NOTES</b></p> <p>*The following BOM items are P/O E-Systems Inc., VHF Omnidirectional Range System, Part #136060-100, designated as Transmitting Set, Radio AM/FRN-41(V)1; therefore, they do not have to be procured separately when the entire system is required: 1-14, 17-127, 153-160, 170-182, 190-203 and 205-211.</p> <p>** (162) P/O item 161</p> <p>*** (165) Items 165 &amp; 166 to be used in accordance with installation instructions contained in section 3.</p> <p>**** (167) Items 167-194 and 204 to be used at the discretion of the engineer, in order to satisfy local engineering requirements.</p> <p>Foundation Ring Stave Part #136197-001</p> <p>Centering Tie Strap Part #136198-001</p> <p>Ring Location Anchor Bolt Part #136199-001</p> <p>3/4"-10x10" Anchor Bolt Bent, Galv</p> <p>3/4"-10x14" Anchor Bolt Straight Galv</p>	ee	14	
2	MSNR (22782A)		ea	7	
3	MSNR (22783B)		ea	1	
4	MSNR (22784C)		ea	8	
5	MSNR (22785D)		ea	4	

DA FORM 1 APR 76 3071-8 EDITION OF 1 AUG 72 IS OBSOLETE.

Figure 5-1. Bill of Materials (sheet 1 of 20).

16 February 1979

SEIP 012

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENT CODE	
For use of this form, see AR 105-22; the proponent agency is the United States Army Communications Command.					
ITEM NO.	STOCK NUMBER	NOMENCLATURE	DATE	TOTAL AVAILABLE REQ FOR IN PROJECT COMMAND	PAGE NO. NO OF PAGES
6	NSNR (22786E)	1/2"-13x1" Anchor Bolt Straight, Galv	ea	14	
7	NSNR (22787F)	1/2"-13x1" Square Head Bolt, Galv	ea	55	
8	5310-00-088-7647 (16880M)	1/2" Flat Washer, Galv	ea	40	
9	5310-00-768-0318 (00493K)	1/2"-13 Hex Nut, Galv	ea	3750	
10	NSNR (22788G)	Plate Washer, Painted, Part #136196-001	ea	12	
11	NSNR (22780J)	3/4"-10 Hex Nut, Galv	ea	30	
12	5310-00-285-1497 (08354Y)	3/4" Flat Washer, Galv Part #78051-2	ea	15	
13	NSNR (22789H)	1.25 Dia x .56 x 1/8 Spacer Galv	ea	8	
14	NSNR (22790K)	Stake, Grounding Part #910917-001	ea	1	
15	NSNR (22791J)	Conduit, PVC 1-1/4"	ft	AR	
16	NSNR (22792Z)	Conduit, PVC 1"	ft	AR	

DA FORM 1 APR 76 3071-R

EDITION OF 1 AUG 72 IS OBSOLETE.

Figure 5-1. Bill of Materials (sheet 2 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS For use of this form, see DA Form 3071-2, 1 APR 78; the proponent agency is the United States Army Communications Command, WASHINGTON, DC		UNIT	NO. OF PAGES
ITEM NO.		OFFICE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY REQUIRED
17	NSNR (22793A)		Shelter 21' Dia Part #136131-130	ea	1
18	NSNR (22794B)		Pedestal Assembly Part #136180-001	ea	1
19	NSNR (22795C)		Ring Stave Standard, Orange Bottom Part #136185-001	ea	7
20	NSNR (22796D)		Ring Stave Standard, White Bottom, Part #136165-002	ea	5
21	NSNR (22797E)		Air Conditioning Stave, Part #136183-001	ea	1
22	NSNR (22798F)		Door opening Stave, Part #136184-001	ea	1
23	NSNR (22799G)		Flanged Holder, Antenna Part #136186-001	ea	1
24	NSNR (22800H)		Deck Segment Part #136187-001	ea	14
25	NSNR (22801I)		Deck Stiffener, Long, Part #136188-001	ea	14
26	NSNR (22802J)		Deck Stiffener, Short, Part #136188-002	ea	14
27	NSNR (22803A)		Landing Ring, Part #136189-001	ea	1

DA FORM 3071-2 1 APR 78 EDITION OF 1 AUG 72 IS OBSOLETE.

Figure 5-1. Bill of Materials (sheet 3 of 20).

16 February 1979

SEIP 012

CREATION		UNIT ID UNIT CODE	
TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS			
Per use of this form, use DA Form 1 APR 78, the predecessor agency is the United States Army Communications Command.			
ITEM NO.	STOCK NUMBER	NOMENCLATURE	DATE
UNIT	UNIT	TOTAL REQ FOR PROJECT	PAGE NO. (NO. OF PAGES)
28	NSMR (22805C)	Reinforcement Angle, Environmental, Part #136178-001	2
29	NSMR (22806D)	Bolt Retainer, Side Stave Part #136191-005	14
30	NSMR (22807E)	Bolt Retainer, Door Frame (top and bottom), Part #136191-002	2
31	NSMR (22808F)	Bolt Retainer, Door Frame (left and right) Part #136191-003	2
32	NSMR (22809G)	Bolt Retainer, Ceiling "U", Part #136191-004	14
33	NSMR (22810G)	Bolt Retainer Part #136191-001	14
34	NSMR (22811H)	Bolt Retainer, Ceiling "L", Part #136195-001	14
35	NSMR (22812W)	Bolt Retainer, Part #136195-002	14
36	NSMR (22813Z)	Square Head Bolt 1/2"-13x1" Lg, Galv	1650
37	NSMR (22814A)	Square Head Bolt 1/2"-13x1.25" Lg, Galv	1820
38	NSMR (22815B)	Square Head Bolt 1/2"-13x1.50" Lg, Galv, Part #91465A/16	30

EDITION OF 1 AUG 72 IS OBSOLETE.

DA FORM 1 APR 78 3071-R

Figure 5-1. Bill of Materials (sheet 4 of 20).



16 February 1979

SEIP 012

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENT CODE	
For use of this form, see AR 105-22; the procuring agency is the United States Army Communications Command.					
TELER NUMBER		NOMENCLATURE		DATE	PAGE NO.
ITEM NO.	STOCK NUMBER			UNIT	TOTAL REQ FOR PROJECT COMMAND
49	NSNR (22826B)	Racome Assembly Part #136140-101		ea	1
50	NSNR (22827C)	Kit, Field Detector MTG Part #136871-100		ea	1
51	NSNR (22828D)	Environmental Control Part #930092-001		ea	1
52	NSNR (22829E)	Bolt, Square Head, 1/2"-13x13/4" Lg, Galv #91465A718		ea	34
53	NSNR (22830E)	Blower, Part #910476-001		ea	1
54	NSNR (22831F)	Bolt, Hex Head, 1/4"-20x1" Lg, Galv #91465A542		ea	4
55	NSNR (22832G)	Washer, Flat 1/4" ID Galv #90108A029		ea	4
56	NSNR (22833H)	Washer, Lock, 1/4" ID, Galv		ea	4
57	NSNR (22834W)	Nut, Reg Hex, 1/4" x 20UNC, Galv #91841A029		ea	4
58	NSNR (22835Z)	Screws, Sheet Metal, No. 10x3/4" Lg, Galv, pu #50053A245		ea	24
55	NSNR (22836A)	Bracket, thermostat Part #136588-001		ea	1

EDITION OF 1 AUG 72 5 C550LETE

DA FORM 1 APR 78 3071-R

Figure 5-1. Bill of Materials (sheet 6 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT SENT CODE		
Per use of this form, see DA Form 107-22, the predecessor agency is the United States Army Communications Command.						
TELLER NUMBER		NOMENCLATURE		DATE	PAGE NO. NO. OF PAGES	
ITEM NO.	STOCK NUMBER			UNIT	TOTAL REQ FOR PROJECT	
					AVAILABLE IN COMMAND REQUIRED	
60	NSMR (228378)	Spacer, Wood, Part #136989-001		ea	2	
61	NSMR (22838C)	Filter-Air, Part #919019-002		ea	1	
62	NSMR (22835D)	Box, Breaker Part #0016-24MM125		ea	1	
63	NSMR (22855G)	Cover, Part #00C20MM2255		ea	1	
64	NSMR (22853H)	Ground Kit Part #PK1567A		ea	1	
65	NSMR (22656M)	Breaker, 120/240V Single Pole Part #00115		ea	4	
66	NSMR (22857Z)	Breaker, 120/240V Single Pole Part #00120		ea	2	
67	NSMR (22858A)	Strap Part #136031-002		ea	2	
68	NSMR (22859B)	Elbow 1-1/4" Flat Back Part #L8125M		ea	1	
69	NSMR (22860B)	Nipple Part #CN125		ea	1	
70	NSMR (22861C)	Cover Part #K125		ea	1	

DA FORM 1 APR 78 3071-R EDITION OF 1 AUG 72 IS OBSOLETE

Figure 5-1. Bill of Materials (sheet 7 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENT CODE	
For use of this form, see AR 105-22; the proponent agency is the United States Army Communications Command.					
TELER NUMBER		NOMENCLATURE		DATE	PAGE NO. NO. OF PAGES
ITEM NO.	STOCK NUMBER		UNIT	TOTAL PROJECT REQUIRED	AVAILABLE IN COMMAND
71	NSNR (22862D)	Gasket Part #GK125	ea	1	
72	NSNR (22863E)	Connector Part #7484	ea	1	
73	NSNR (22864F)	Connector Part #7384	ea	1	
74	NSNR (22865G)	Box Part #45JD-1-1/4"	ea	1	
75	NSNR (22866H)	Cover Part #8487-K	ea	1	
76	NSNR (22867M)	Connector SMT-C-125	ea	1	
77	NSNR (22868Z)	Connector 7383	ea	1	
78	NSNR (22869A)	Connector 7483	ea	3	
79	NSNR (22870A)	Connector 7481V	ea	9	
80	NSNR (22871B)	Box 4001/2	ea	4	
81	NSNR (22872C)	Lighting Arrestor Part #910925-001	ea	2	

DA FORM 3071-R  
1 APR 78

EDITION OF 1 AUG 72 IS OBSOLETE.

Figure 5-1. Bill of Materials (sheet 8 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENTITY CODE	
For use of this form, see AR 109-22, the appropriate agency in the United States Army Communications Command.					
TELER NUMBER	STOCK NUMBER	NOMENCLATURE	DATE	TOTAL REQ FOR PROJECT	NO. OF PAGES
ITEM NO.			UNTY	AVAILABLE IN PROJECT COMMAND	REQUIRED
82	NSMR (22873D)	Connector 7381V	ea	5	
83	NSMR (22874E)	Nipple CR-50	ea	4	
84	NSMR (22875F)	Fixture Fluorescent KL240	ea	4	
85	NSMR (22876G)	Conduit, Flex, 1-1/4" Alum	ft	AR	
86	NSMR (22877H)	Conduit, Flex, 1" Alum	ft	AR	
87	NSMR (22878M)	Conduit, Flex, 1/2" Alum	ft	AR	
88	NSMR (22879Z)	Connector 605	ea	1	
89	NSMR (22880Z)	Elbow MFL150	ea	1	
90	NSMR (22881A)	Bushing RB150-50	ea	1	
91	NSMR (22882B)	Box RS-1	ea	1	
92	NSMR (22883C)	Breaker Q0260, 120/240 Vac, two pole common trip	ea	2	

EDITION OF 1 AUG 72 S OBSOLETE.

DA FORM 3071-R  
1 APR 78

Figure 5-1. Bill of Materials (sheet 9 of 20).

16 February 1979

SEIP 012

LOCATION		UNIT IDENT CODE			
For use of this form, see AR 108-22; the procuring agency is the United States Army Communications Center.					
TELEPHONE NUMBER	STOCK NUMBER	NOMENCLATURE	DATE		
ITEM NO.			UNIT		
			TOTAL NO. FOR PRESENT COMMAND		
			AVAILABLE IN PRESENT COMMAND		
			NO. OF PARTS		
			REQUIRED		
93	NSMR (22884D)	Nut 5/100	ea	1	
94	NSMR (22885E)	Connector MFL 100	ea	1	
95	NSMR (22886F)	Pipe, Rigid TBE, 1'x2' Lg	ea	1	
96	NSMR (22887G)	Nut, Lock BL100	ea	?	
97	NSMR (22897F)	Connector, 1" 90° Angle, ST90100	ea	1	
98	NSMR (22898G)	Connector, 1" Straight, ST100	ea	3	
99	NSMR (22899H)	Connector ME75-100	ea	1	
100	NSMR (22900W)	Connector RB125-100	ea	1	
101	NSMR (22501Z)	Conduit, L.T., 1" UA	ft	AP	
102	NSMR (22502A)	Clamp 1/2" Part #1211	ea	24	
103	NSMR (22903B)	Clamp 1" Part #u5203	ea	3	

EDITION OF 1 AUG 72 IS OBSOLETE.

DA FORM 1 APR 76 3071-R

Figure 5-1. Bill of Materials (sheet 10 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENT CODE		
Per use of this form, see AR 15-22. The proponent agency is the United States Army Communications Command.						
TELER NUMBER		NOMENCLATURE		DATE	PAGE NO. NO. OF PAGES	
ITEM NO.	STOCK NUMBER			UNIT	TOTAL REQ FOR PROJECT COMMAND	
					AVAILABLE IN PROJECT COMMAND	
					REQUIRED	
104	NSNR (22904C)	Nut Lock BL50 1/2"		ea	4	
105	NSNR (22905D)	Screw, SM, S.T. 1/4x3/4" Lg		ea	3	
106	NSNR (22906E)	Bracket, Field Detector Part #136100-001		ea	17	
107	NSNR (22907F)	Cable Assembly W1 Part #136111-102		ea	1	
108	NSNR (22908G)	Cable Assembly W3 Part #136112-100		ea	1	
109	NSNR (22909H)	Field Detector Assembly Part #136861-100		ea	1	
110	NSNR (22910H)	Marking Template Kit Part #136107-001		ea	1	
111	NSNR (22911W)	Paint, Spray Black Krylon 1601		ea	AR	
112	NSNR (22912Z)	Cap, Radome Part #136141-001		ea	1	
113	NSNR (22913A)	Gasket 1/8"x2" Part #910371-001		ea	1	

DA FORM 1 APR 78 3071-R EDITION OF 1 AUG 72 IS OBSOLETE

Figure 5-1. Bill of Materials (sheet 11 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENTIFY CODE	
For use of this form, see AR 105-22. The procuring agency is the United States Army Communications Command.					
ITEM NO.	STOCK NUMBER	NOMENCLATURE	DATE	PAGE NO. NO. OF PAGES	TOTAL AVAILABLE IN PROJECT COMMAND
114	NSNR (229148)	Bolt, Nylon, 1/2"-13x1-1/2' Lg Part #910372-001	ea	70	70
115	NSNR (22915C)	Nut, Nylon 1/2-13 Part #910373-001	ea	48	48
116	NSNR (22916D)	Washer, Flat, Nylon 1/2" Part #910374-001	ea	118	118
117	NSNR (22917E)	Photo Cell and Obstruction Light Assembly Part #136151-101	ea	1	1
118	(Deleted)				
119	(Deleted)				
120	(Deleted)				
121	NSNR (22921H)	O-Ring Gasket Part #2-204	ea	118	118
122	5306-00-579-1451 (C6237Z)	Bolt, Hex Head Machine Steel 3/8"-16x1" Lg	ea	6	6
123	5310-00-579-2071 (C8766Z)	Washer, Steel, flat 3/8" I.D. 13/21, 00 12/16	ea	6	6
124	NSNR (22924A)	Gasket, Bolt, Membrane Part #910379-001	ea	6	6
125	(Deleted)				

EDITION OF 1 AUG 72 IS OBSOLETE.

DA FORM 1 APR 78 3071-R

Figure 5-1. Bill of Materials (sheet 12 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENT CODES	
For use of this form, see AR 105-72, the appropriate agency is the United States Army Communications Command.					
ITEM NO.	STOCK NUMBER	NOMENCLATURE	DATE	TOTAL REQ FOR PROJECT	NO. OF PAGES
TELER NUMBER			UNIT	AVAILABLE IN COMMAND	REQUIRED
126	MSNR (22926C)	Shell Radome Part #136142-003	ea	1	
127	MSNR (22927D)	Gasket 1/8"x1/2" Part #910371-002	ea	2	
128	5940-00-085-7802 (19851M)	Protector Block, 6 pr, Reliable R66C1-6P	ea	1	
129	5305-00-955-3441 (10113D)	Screw, Machine 10-32x1-1/2"	hd	AP	
130	5310-00-840-0530 (00560J)	Nut, Hex #10-32	ea	24	
131	5310-00-167-0834 (00488D)	Washer, flat #10	hd	AP	
132	6145-00-125-9320 (05300Q)	Wire, Elect, Bare, 6AWG	ft	AR	
133	6145-00-121-2569 (05285Y)	Wire, Copper, Jr, 10AWG, 1000'	ft	AP	
134	{deleted}				
135	5305-00-052-1548 (07472Q)	Screw, Machine #10-32x3/4" Lc	hd	AP	
136	5940-00-111-5075 (07452Y)	Lug, Terminal Clamp Style	pkg	AP	

EDITION OF 1 AUG 72 IS OBSOLETE.

DA FORM 3071-R  
1 APR 78

Figure 5-1. Bill of Materials (sheet 13 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENT CODE	
For use of this form, see AR 105-22, the predominant agency is the United States Army Communications Command.					
TELE NUMBER		NOMENCLATURE		DATE	PAGE NO. NO. OF PAGES
ITEM NO.	STOCK NUMBER			UNIT	TOTAL REQ FOR PROJECT COMMAND
137	5306-00-141-2883 (00358F)	Bolt 1/4"-20x1-1/4" Lq		ea	AR
138	5310-00-285-1650 (00558H)	Nut, Hex 1/4"-20		hd	AR
139	5310-00-819-4698 (10290Y)	Washer, flat .266" ID		ea	24
140	5310-00-808-5381 (10231A)	Washer, Lock FUM 1/4" Bolt		ea	24
141	5940-00-225-8860 (11526H)	Lug, Terminal Mechanical Compression		ea	1
142	6145-00-526-2710 (21872D)	Cable, Tel, 6 pr, 22 ANG		ft	AR
143	6145-00-635-1195 (22504H)	Cable, Tel, 2x22 ANG, Insul		ft	AP
144	6145-00-577-8061 (22503H)	Cable, Tel, 4x22 ANG, Insul		ft	AR
145	6350-00-276-8912 (07596B)	Bell, 117 Vcc, Edwards 340-6M5		ea	1
146	NSNR (22928E)	Relay, Potter & Brumfield, ABC7DY48		ea	1

DA FORM 1 APR 68 3071-R EDITION OF 1 AUG 72 IS OBSOLETE.

Figure 5-1. Bill of Materials (sheet 14 of 20).

LOCATION		UNIT IDENT CODE		
TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS				
For use of this form, see AR 105-22; the procuring agency is the United States Army Communications Command.				
ITEM NO.	STOCK NUMBER	NOMENCLATURE	DATE	
YELER NUMBER			UNIT	
			TOTAL AVAILABLE REQ FOR PROJECT	
			NO. OF PAGES	
			REQUIRE	
147	5310-00-619-2480 (10425H)	Nut, Hex #8-32	ea	24
148	5310-00-167-0833 (00487C)	Washer, flat #8	wa	AR
149	6145-00-542-6068 (14486J)	Cable, Power Elect 3C16AM6	ft	AR
150	5975-00-685-9791 (02409H)	Panel, Blank, Alum, 19"x7"x1/8"	ea	2
151	5975-00-056-3984 (22500E)	Panel, Blank, Alum, 19"x1-1/2"x1/8"	ea	2
152	NSNR (19253Y)	Shield, Expansion 3/8" Rawls #6006	ea	AR
153	NSNR (22922N)	Panel, Blank Part #135922-001	ea	1
154	NSNR (22929F)	Rack MT-6011/FRN-41 Part #136320-102	ea	1
155	NSNR (22530F)	Transmitter, Radio, T-1394/FRN-41 Part #136490-101	ea	1
156	NSNR (225316)	Transmitter, Sideband T-1395/FRN-41 Part #136645-100	ea	1
157	NSNP (22532H)	Control-Indicator C-10527/FRN-41 Part #136740-101	ea	1

DA FORM 3071-R  
1 APR 78

EDITION OF 1 AUG 72 IS OBSOLETE.

Figure 5-1. Bill of Materials (sheet 15 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENT CODE	
Per use of this form, see AR 108-22; the proponent agency is the United States Army Communications Command.					
ITEM NO.	STOCK NUMBER	NOMENCLATURE	DATE	TOTAL REQ FOR PROJECT COMMAND	NO. OF PAGES
158	NSNR (22933M)	Monitor, Phase, Modulation ID-2179/FRN-41 Part #136500-102	ea	1	
159	NSNR (22934Z)	Control-Indicator C-10526/FRN-41 Part #136815-101	ea	1	
160	NSNR (22935A)	Antenna AS-3323/FRN-41 Part #136202-100	ea	1	
161	NSNR (22936B)	Recorder/Reproducer TRC-89-4 Part #10-003-4	ea	1	
162**	NSNR (22937C)	Remote Control Part #10-007-2	ea	1	
163	5305-00-989-7434 (003376)	Screw, Machine 10-32x1/2*	hd	AR	
164	5310-00-045-3296 (00483J)	Washer, Lock Split #10	hd	AR	
165***	NSNR (22938D)	Compound, Caulking Bulyflex 12 9407114-White	ea	AR	
166***	NSNR (22939E)	Gun, Caulking Part #58105	ea	1	
167***3439-00-273-2536 (00015D)		Solder, 60/40 Rosen Center	lb	AR	
168	5975-00-906-2414 (092UbJ)	Ty-rap, TY-35M	ea	AR	

DA FORM 1 APR 78 3071-R

EDITION OF 1 AUG 72 IS OBSOLETE.

Figure 5-1. Bill of Materials (sheet 16 of 20).

OPERATOR		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT QUANTITY CODE	
TRAILER NUMBER		STOCK NUMBER		NOMENCLATURE	
ITEM NO.	STOCK NUMBER	DATE	UNIT	TOTAL REQ FOR PROJECT	PAGE NO. NO. OF PAGES
169	5975-00-944-1699 (07572P)		ee	AR	
170	6145-00-479-7178 (22940E)		ft	AR	
171	NSMR (22941F)		ft	AR	
172	6145-00-479-7173 (22942E)		ft	AR	
173	6145-00-290-1752 (22943H)		ft	AR	
174	6145-00-290-1755 (22944W)		ft	AR	
175	(Deleted)				
176	6145-00-290-1753 (22946A)		ft	AR	
177	6145-00-290-1756 (22947B)		ft	AR	
178	6145-01-017-9694 (22945Z)		ft	AR	
179	NSMR (22948C)		ft	AR	

DA FORM 3071-R  
1 APR 78

EDITION OF 1 AUG 72 IS OBSOLETE.

Figure 5-1. Bill of Materials (sheet 17 of 20).

TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS									
Per use of this form, see AR 108-22; the proponent agency is the United States Army Communications Command.									
UNIT IDAW7 6004									
LOCATION	TELER NUMBER	STOCK NUMBER	NOMENCLATURE	DATE	UNIT	TOTAL REQ FOR PROJECT	AVAIL FOR PROJECT	NO. OF PAGES	NO. OF PAGES REQUIRED
180	NSMR (229490)		Wire, 26AWG, W/Violet, MIL-W-16878/4		ft	AR			
181	NSMR (229500)		Wire 26AWG, W/Grn, MIL-W-16878/4		ft	AR			
182	NSMR (22951E)		Splice, 12AWG Part #30-451		ea	AR			
183	6145-00-957-8516 (145496)		Cable 18c (9 pr) #22AWG		ft	AR			
184	5970-00-740-2972 (128446)		Tubing, Shrinkable, Alpha Wire, FIT-221-1/16"		ft	AR			
185	5970-00-914-3117 (09372J)		Tubing, Shrinkable, Alpha Wire, FIT-221-3/4"		ft	AR			
186	5305-00-282-9498 (11939F)		Screw, Machine 1/4"-28x19/32"		hd	AR			
187	5305-00-206-5122 (00251K)		Screw, Machine 12-24x1/2"RHS		hd	AR			
188	5305-00-775-5140 (08228Z)		Screw, Machine 10-32x3/4"RHS		hd	AR			
189	5305-00-944-5655 (11339W)		Screw, Machine 8-32x1/2"		hd	AR			
190	6145-00-080-1486 (17398F)		Cable, 1 pr Shielded, Belden 8450		ft	AR			

EDITION OF 1 AUG 72 IS OBSOLETE.

DA FORM 1 APR 78 3071-R

Figure 5-1. Bill of Materials (sheet 18 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENT CODE	
For use of this form, see AR 105-22; the procuring agency is the United States Army Communications Command.					
TELE NUMBER		NOMENCLATURE		DATE	PAGE NO. NO. OF PAGES
ITEM NO.	STOCK NUMBER			UNIT	TOTAL PROJECT REQUIRED
					AVAILABLE PROJECT DEMAND
191	6145-00-577-8061 (22503H)	Cable, 4c, 22/MSG		ft	AR
192	5940-00-144-1536 (08240K)	Terminal Lug #22-26 MSG		ea	AR
193	5940-00-557-1629 (07504A)	Terminal Lug 18-22/MSG		hd	AR
194	5940-00-143-4775 (07503A)	Terminal Lug 10-12/MSG		ea	AR
195	MSNR (23337F)	Screw, SH, PH 6x5/8 Lg, Galv		hd	AR
196	MSNR (23338G)	Bolt, Sq Hd, 5/16"-18UNCx1-3/4" Lg		ea	AR
197	5310-00-579-2074 (08131R)	Washer, flat 5/16" I.D. W/Nut		ea	AR
198	MSNR (23339H)	Washer, Ring 5/16" I.D. Steel-backed, Neoprene		ea	AR
199	MSNR (23340K)	Nut, Hex 5/16"-18 UNC, Galv		ea	AR
200	MSNR (23341J)	Clip, Landing Ring Part #136176-001		ea	AR
201	MSNR (23342Z)	Clip, Stave Part #136177-001		ea	AR

DA FORM 1 APR 78 3071-R

EDITION OF 1 AUG 72 IS OBSOLETE.

Figure 5-1. Bill of Materials (sheet 19 of 20).

LOCATION		TELECOMMUNICATIONS DEVELOPMENT PROJECT - BILL OF MATERIALS		UNIT IDENT CODE	
Per use of this form, use AR 105-22; the procuring agency is the United States Army Communications Command.					
ITEM NO.	STOCK NUMBER	DESCRIPTION	DATE	UNIT	TOTAL AVAILABLE FOR PROJECT COMMAND
202	NSNR (22343A)	Punch, Gasket 7/16" Part #910170-001		ea	1
203	NSNR (23344B)	Clamp, Part #910516-001		ea	AR
204	NSNR (11356D)	Panel, Aluminum 19"x5-3/4"x3/16"		ea	AR
205	NSNR (23345C)	Nipple OFN-50		ea	AR
206	5975-00-284-5827 (025156)	Box 45-1/2		ea	1
207	5975-00-296-0021 (12156A)	Cover 5371		ea	1
208	NSNR (14091J)	Receptacle 5262		ea	1
209	NSNR (23353Z)	Screw, Set 1/2"-13x2-1/2"		ea	AR
210	8010-00-527-3192 (04094R)	Paint, international orange		gl	AR
211	8010-00-290-4049 (04087N)	Paint, White		ea	AR

DA FORM 1 APR 78 3071-R

EDITION OF 1 AUG 72 IS OBSOLETE.

Figure 5-1. Bill of Materials (sheet 20 of 20).

## SECTION 6. QUALITY ASSURANCE PLAN

6.1 GENERAL. The quality assurance (QA) program for the AN/FRN-41 TVOR has been developed in CCR 702-1-2, chapter 5. The QA program is to be implemented in accordance with this and the following two sections and will provide the assurance to all concerned that the specified equipment and facilities have been installed in accordance with the requirements and criteria of this SEIP as supplemented through individual engineering installation packages (EIP) and are acceptable for turnover to and use by the operating agency. The requirements and criteria specified here and in sections 7 and 8 constitute the quality assurance plan for the specified AN/FRN-41 TVOR. Individual EIP's will be used to supplement, expand, modify, or otherwise adapt the requirements and criteria to unique situations and circumstances applicable to each site location.

### 6.2 QUALITY ASSURANCE PROGRAM.

6.2.1 The QA program consists of a planned and systematic approach for assessing the quality during the installation and acceptance testing of project implementation and correcting at the earliest time any discrepancies, deficiencies, or shortcomings revealed through inspection and test efforts. The QA and quality control (QC) planning and functions will begin at the earliest stages of project implementation and end after all possible corrective action efforts are completed and the AN/FRN-41 TVOR are released to the operating or user agency. Quality assurance and QC functions are to be performed by personnel operating independently from those charged with the engineering of the installation or involved in the process of installing the AN/FRN-41 TVOR. Under the program, these functions are divided among three participating organizations: (1) the test agency, (2) the installation agency, and (3) the operating agency.

6.2.2 Test agency. As the manager and implementor of the QA program and acceptance testing efforts for the AN/FRN-41 TVOR, the test agency will commence project planning as soon as tasked. The test agency quality assurance representative (QAR)/Test Director is responsible for periodic in-process QA checks, final QA inspections, and acceptance tests in accordance with management provisions of CCCR 702-3 and this SEIP. Quality assurance inspections will be performed at the discretion of this Agency for the purpose of assessing the effectiveness of the QC effort by the installation agency; initiating corrective actions as appropriate; and determining the extent to which the installation effort adheres to the quality requirements. Acceptance testing is conducted in accordance with section 7 and for the purpose of determining if the installed AN/FRN-41 TVOR complies with the technical requirements of this SEIP as amended by individual

16 February 1979

EIP's and the AN/FRN-41 TVOR is suitable for the intended application. At the earliest stages of project initiation, the test agency is to identify a QAR/Test Director. For project continuity and effective management, a single individual should be assigned both roles. This will assure that the QA and test efforts are fully integrated and accomplished in the following manner and sequence to:

a. Implement the QA concepts and requirements identified. Participate in the development of individual EIP's incorporating site particular requirements.

b. Assure that the participating elements and organizations are thoroughly familiar with their respective roles in support of QA, QC, and testing and have been properly tasked.

c. Validate through the use of project oriented reports, formal and informal contacts, project status reviews, onsite inspections, etc., the QC, and installation efforts to assure compliance with the stated requirements and criteria of this SEIP. When an inadequacy is found to exist in the installation agency QC effort, the procedures of CCCR 702-7 will be applied. Follow-up actions will be monitored and those discrepancies or differences which cannot be resolved in a timely manner will be brought to the attention of higher authority.

d. Facilitate responsibilities by identifying and recording this information and data as required by USACEEIA Form 113R (figure 6-1). This form becomes a part of the project files and will be updated to assure orderly project execution. The dissemination of this information with the participants in the QA program is encouraged.

e. Perform a final QA inspection using USACEEIA Form 112R (figure 6-2), tailored to the specifics of this effort. When the installation effort and checkout of the AN/FRN-41 TVOR, this SEIP, individual EIP, and the AFTO series shall be the evaluation criteria for the site inspection efforts. This inspection will consist of thorough visual and mechanical observations of the installed materiel, QC records, onsite inspection, and other factors to evaluate the quality of the work performed and its acceptability.

f. Conduct acceptance tests in accordance with the provisions of section 7, the subsidiary documents specified, and CCCR 702-3, to determine the acceptability of the AN/FRN-41 TVOR, as installed. If the results of any portion of acceptance tests are not satisfactory, corrective action efforts are to be initiated through onsite engineering, installation, and operational participants and in the absence of such representation, through channels. The QAR/Test Director may retest to verify that corrective action efforts have been implemented and that the efforts will preclude recurrence.

COGNIZANT AGENCY, COMMAND, AND  
FACILITY QA POINTS OF CONTACT  
(CCCR 702-2)

	<u>Individual POC</u>	<u>Bldg. No.</u>	<u>Rm. No.</u>	<u>Phone No.</u>	<u>Name of Agency</u>
<u>Installation:</u>					
Team Leader	_____	_____	_____	_____	_____
Assistant Team Leader	_____	_____	_____	_____	_____
Quality Control	_____	_____	_____	_____	_____
<u>Quality Assurance Agency:</u>					
Representative	_____	_____	_____	_____	_____
Testing Activity	_____	_____	_____	_____	_____
<u>Operating Agency:</u>					
Representative	_____	_____	_____	_____	_____
Site Commander	_____	_____	_____	_____	_____

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION (CCCR 702-2)		PAGE 1 OF 11 PAGES		
		DATE (Day, Mo, Year)		
SITE		LOCATION		
PROJECT NAME		TASK NO.		
REFERENCED T.O. FOR QUALITY OBSERVATIONS FOLLOW MAIN PARAGRAPHS		YES	NO	NA
<p>A. <u>Drawings and Specifications</u> (AFTO 31-10-3, 31-10-9, 31-10-27, 31-10-29)</p> <ol style="list-style-type: none"> <li>1. Are floor plan drawings available?</li> <li>2. Are equipment location drawings available?</li> <li>3. Are face layout drawings of equipment in bays available?</li> <li>4. Are drawings for distribution frame block assignments available?</li> <li>5. Are pin connections on terminal blocks shown on drawings?</li> <li>6. Is stenciling of terminal blocks shown on drawings?</li> <li>7. Are drawings of power distribution equipment available?</li> <li>8. Are wire sizes indicated on drawings?</li> <li>9. Are schematic diagrams of circuit types to be installed included in drawings?</li> <li>10. Are drawings of site grounding systems available?</li> <li>11. Are drawings showing arrangement of cable racks, ducts, and trenches available?</li> <li>12. Do specifications contain list of reference material required by installers?</li> <li>13. Do specifications contain cable running list for power distribution?</li> <li>14. Do specifications contain cable running list for signal cabling?</li> </ol>				

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION (CCCR 702-2)	PAGE 2 OF 11 PAGES		
	YES	NO	NA
15. Do specifications contain cable running list for RF cabling?			
16. Do specifications contain detailed information on grounding?			
17. Do specifications contain details on all special instructions for installers?			
18. Do drawings reference all applicable items on BOM?			
B. <u>Tools and Equipment</u> (AFTO 31-10-29)			
1. Is equipment damaged or unserviceable?			
2. Are all installation materials on hand and serviceable?			
3. Are all tools necessary for completion of the job on hand?			
4. Is all test equipment needed for test and checkout of installation available?			
C. <u>General Safety Practice</u> (AFTO 31-10-29)			
1. Are goggles being worn when drilling and grinding?			
2. Are sharp edges left on frame or duct work?			
3. Are all hand tools properly used?			
4. Are electric power tools properly grounded?			
D. <u>Floor Plan Layout</u> (AFTO 31-10-9, 31-10-29)			
1. Are equipment layout plans in accordance with drawings?			
2. Was layout plan completed before equipment was moved into area?			
E. <u>Erecting and Mounting</u> (AFTO 31-10-29)			
1. Is equipment laid out in accordance with floor plan drawing?			

USACEEIA Form 112-R Continued.

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION (CCCR 702-2)	PAGE 3 OF 11 PAGES		
	YES	NO	NA
2. Are equipment bays level and plumbed within tolerances?			
3. Has proper spacing been provided between equipment racks?			
4. Are base angles of frames secured to floor in proper location?			
5. Are all cabinets flush mounted and plumbed?			
6. Has finish of equipment, cabinets, and racks been touched up?			
7. Are bolts and screws free from stripped threads and defaced heads?			
8. Have sufficient clearances been provided between apparatus for heat dissipation?			
9. Are terminal blocks aligned on distribution frames?			
10. Has equipment been installed in cabinets or racks in accordance with face layouts?			
11. Are all nuts and bolts securely tightened?			
12. Are exposed or cut ends of metal filed smooth and painted?			
13. Have lock and flat washers been used?			
14. Is the C-E equipment BOM available at the facility?			
15. Has the C-E equipment been inventoried and discrepancies posted?			
16. Is all required C-E equipment at the site?			
17. Is all C-E equipment installed?			
F. <u>Cable Racks</u> (AFTO 31-10-6)			
1. Location of cable racks:			
a. Are cable racks located in accordance with cable plan drawing?			

Figure 6-2. USACEEIA Form 112-R Continued.

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION (CCCR 702-2)	PAGE 4 OF 11 PAGES		
	YES	NO	NA
b. Does height of cable racks conform to height above floor as indicated on cable plan drawing?			
c. Are cable racks located so that clearance is provided for installation and maintenance of ultimate equipment?			
d. Are cable racks located so cables are not subject to damage or exposure or other detrimental conditions?			
2. Assembly of cable racks:			
a. Are long sections of cable racks used where possible?			
b. Have clamping details been altered other than where necessary to avoid interference?			
c. Are open ends of cable racks properly closed?			
d. Are vertical cable racks properly terminated on floors?			
3. Support of cable racks:			
a. Are cable racks properly supported and fastened?			
b. Are cable racks installed so that no excessive load or binding is imposed on the equipment?			
c. Are horizontal cable racks supported on approximately 5 feet centers but not to exceed 6 feet?			
d. Has support been provided within 3 feet of free end of cable rack?			
e. Are cable racks braced where necessary to prevent sway?			
G. <u>Running Cable</u> (AFTO 31-10-13)			
1. Are cable runs made in accordance with cable running list?			
2. Are cables twisted or crossed on cable rack?			

Figure 6-2. USACEEIA Form 112-R Continued.

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION (CCCR 702-2)	PAGE 5 OF 11 PAGES		
	YES	NO	NA
3. Do cables at turns or bends conform to the bending radii and position?			
4. Is protection provided where cable sheaths contact rough or sharp edges or metal?			
5. Are cables which are turned off over side of cable racks formed with minimum allowable radii?			
6. Are cables turned off rack horizontally and then up?			
7. Do cables to the distribution frame enter on the vertical side?			
8. Are cables serving the horizontal side of a distribution frame secured to the transverse arms near the vertical upright?			
9. Are cable tags properly prepared and in accordance with the cable running list?			
10. Are cable tags secured at each end of cable run?			
11. Have cable tags been removed upon completion of verification and termination?			
12. Are cable butts located as near as practicable to the point where the first wires turn out?			
13. Are cable butts properly treated?			
14. Is insulation of wires undamaged at butt location?			
15. Are unused and spare wires protected at butt location?			
H. <u>Securing Cable</u> (AFTO 31-10-2, 31-10-13)			
1. Is starting stitch properly made and placed?			
2. Is required Kansas City stitch properly made?			
3. Are first and succeeding layers of cable properly secured?			

Figure 6-2. USACEEIA Form 112-R Continued.

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION  
(CCCR 702-2)

PAGE 6 OF 11 PAGES

	YES	NO	NA
4. Are cables secured at every cable rack cross strap?			
5. When cable butt is between securing devices, are cables secured together with an appropriate stitch?			
6. Are lock stitches properly made and spaced?			
7. Are splices in twine properly made?			
I. <u>Sewed Forms</u> (AFTO 31-10-13)			
1. Is proper size twine used for the diameter of the form?			
2. Are proper number of strands used?			
3. Are stitches properly spaced?			
J. <u>Butting and Stripping</u> (AFTO 31-10-13)			
1. Are proper tools used for butting and stripping of cable?			
2. Are cable butts properly dressed?			
3. Is proper distance maintained from cable butt to fanning strip?			
K. <u>Fanned Forms</u> (AFTO 31-10-2)			
1. Are cables fanned and connected to the left side of vertical mounted terminal blocks and to the bottom of horizontal terminal blocks?			
2. Are conductors in fanned forms twisted and bunched?			
3. Are fanned forms straight and taut from butt location to fanning strip?			
4. Is length of skimmers correct?			
5. Has color code been properly followed?			
6. Are spare wires disposed of properly?			
L. <u>Stenciling</u> (AFTO 31-10-27, 31-10-29)			
1. Is equipment correctly identified and stenciled in accordance with floor plan drawings?			

Figure 6-2. USACEEIA Form 112-R Continued.

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION (CCCR 702-2)	PAGE 7 OF 11 PAGES		
	YES	NO	NA
2. Are designations located correctly? 3. Are correct size designations used on particular types of apparatus or equipment?			
<b>M. <u>Strapping</u> (AFTO 31-10-16)</b>			
1. Are straps properly placed? 2. Is correct type of strap wire used? 3. Does insulation extend to terminal? 4. Are straps placed so as not to interfere with operation of apparatus? 5. Is removal of apparatus blocked? 6. Are designations of apparatus obscured?			
<b>N. <u>Connecting and Soldering</u> (AFTO 31-10-7)</b>			
1. Is soldering clamp used when connecting wires? 2. Are connections made on terminal blocks in proper manner? 3. Is all soldering done with standard rosin core solder? 4. Are connections secure and free of foreign substances? 5. Has all unsightly flux and excess globules of solder been removed? 6. Is insulation on skimmers burnt or otherwise damaged? 7. Do skimmers on connected terminals exceed 1/16 in? 8. Are all conductors given a continuity test after connection is made?			
<b>O. <u>Wrapped Connections</u> (AFTO 31-10-7)</b>			
1. Are wrapped connections applied only on suitable terminals? 2. Are connections essentially straight and free of angular bends or crimps?			

Figure 6-2. USACEEIA Form 112-R Continued.

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION (CCCR 702-2)	PAGE 8 OF 11 PAGES		
	YES	NO	NA
3. Are the required number of turns in contact with the terminal in accordance with criteria for gauge of wire used?			
4. Are wrapped connectors soldered where applicable?			
P. <u>Cross Connections</u> (AFTO 31-10-11)			
1. Are jumpers properly routed at distribution frame?			
2. Do jumpers have sufficient slack after connection?			
3. Are conductors twisted between fanning strip and terminal?			
4. Does twist remain in conductors beyond rear of fanning strip?			
5. Are jumpers properly dressed?			
6. Has excess solder been removed from terminals?			
Q. <u>Equipment and Signal Grounds</u> (AFTO 31-10-24, 31-10-29)			
Are equipment and signal grounds installed in accordance with applicable codes and standards and in accordance with installation drawings?			
R. <u>Conduit</u> (AFTO 31-10-12)			
1. Are burrs removed from conduit after cutting?			
2. Is bending radii of conduit adequate?			
3. Are there more than four 90-degree bends in a single conduit run?			
4. Does number of conductors in conduit conform?			
5. Are conduits supported at intervals not exceeding 6 feet?			
6. Have all fittings been tightened after installation?			

Figure 6-2. USACEEIA Form 112-R Continued.

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION (CCCR 702-2)	PAGE 9 OF 11 PAGES		
	YES	NO	NA
<p>S. <u>Ducts (RF Shieldings)</u> (AFTO 31-10-12, 31-10-13)</p> <ol style="list-style-type: none"> <li>1. Are hangers for overhead ducts mounted first?</li> <li>2. Is proper type mallet used in assembly?</li> <li>3. Are flange sections cleaned before installation?</li> </ol>			
<p>T. <u>Coaxial Cables</u> (AFTO 31-10-14)</p> <ol style="list-style-type: none"> <li>1. Is cable inspected for possible damage prior to installation?</li> <li>2. Where required, is cable sewed in same manner as signal cable?</li> <li>3. Is butting and stripping done in same manner as signal cable?</li> <li>4. Do cable tags remain on coaxial cable from antenna to RF patch or equipment?</li> <li>5. Is support spacing of cables installed as prescribed (3 ft for cable 1-5/8 in or smaller and 5 ft for cables 1-11/16 in or greater)?</li> <li>6. Does bending radii of cables meet prescribed standards of the T.O.?</li> </ol>			
<p>U. <u>Waveguides and Antennas</u> (AFTO 31R-10-5, CEEIA PAM 105-3)</p> <ol style="list-style-type: none"> <li>1. Are waveguides stored in a horizontal manner and away from heavy objects?</li> <li>2. Are waveguides inspected for possible damage prior to installation?</li> <li>3. Are waveguides cleaned in the proper manner prior to installation?</li> <li>4. Are hangers installed every 5 feet as prescribed?</li> <li>5. Do waveguide bends conform to T.O. criteria?</li> <li>6. Are antennas and reflectors mounted as prescribed heights?</li> <li>7. Are antennas oriented to the prescribed azimuth?</li> </ol>			

Figure 6-2. USACEIA Form 112-R Continued.

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION (CCCR 702-2)	PAGE 10 OF 11 PAGES		
	YES	NO	NA
<p>V. <u>Outside Plant Inspection</u> (AFTO 31R-10-5, 31-10-5, 31-10-3, 31-10-10, 31-10-21, 31-10-24, 31-10-28)</p> <ol style="list-style-type: none"> <li>1. Are antenna tower locations proper?</li> <li>2. Are footings or pads prepared prior to concrete pour?</li> <li>3. Have concrete pours for footings and pads been accomplished in accordance with specified criteria?</li> <li>4. Has proper cure time been achieved prior to mounting steel?</li> <li>5. Is the tower constructed in accordance with the specified criteria, drawings, etc?</li> <li>6. Are the antenna supports, anchors, pedestals, etc., properly installed in accordance with established criteria?</li> <li>7. Are supporting structures, guy wires, tower lighting kits (when required), termination boxes, and baluns included and properly installed in accordance with established criteria?</li> <li>8. Are antennas properly mounted and aligned?</li> <li>9. Were antenna reflectors properly aligned prior to mounting the feed horn?</li> <li>10. Are antenna curtains for rhombic and log periodics properly installed?</li> <li>11. Are transmission lines, coaxial cables, waveguides, etc., properly installed?</li> <li>12. Has tower and supporting structure been painted in accordance with established criteria?</li> <li>13. Are waveguides, cable runs, etc., properly installed and protected?</li> </ol>			
<p>W. <u>Power Buildings</u> (AFTO 31-10-3, 31-10-29)</p> <ol style="list-style-type: none"> <li>1. Are power buildings and pads properly located and installed?</li> </ol>			

Figure 6-2. USACEEIA Form 112-R Continued.

QUALITY ASSURANCE INSPECTION CHECKLIST - INSTALLATION  
(CCCR 702-2)

PAGE 11 OF 11 PAGES

	YES	NO	NA
2. Are generators and power distribution panels properly located and installed?			
3. Are oil pans properly installed?			
4. Are generators properly vented from the buildings?			
5. Has all required wiring been installed?			
6. Are fuel tanks installed above ground; if so, are they located at the proper distance from generator building?			
7. If fuel tanks were installed underground, was it accomplished in accordance with established procedures?			
8. Is safety equipment located in generator building?			
X. <u>Installation Drawings</u> (AFTO 31-10-29)			
Have drawings been reviewed to assure "as built" accuracy?			
<p style="text-align: center;">_____ TEST ENGINEER/QUALITY ASSURANCE REPRESENTATIVE (QAR)</p>			

Figure 6-2. USACEEIA Form 112-R Continued.

After satisfactory resolution, he may subsequently resume acceptance tests. If these items cannot be resolved by onsite personnel, the QAR/Test Director will take either of the following actions: (1) Reject the AN/FRN-41 TVOR and terminate testing until the matter is corrected or resolved, or (2) Attempt to complete the acceptance tests noting the discrepancies, deficiencies, or shortcomings, as exceptions on the Technical Acceptance Recommendation (TAR), Form 98R at section 8. The participating agencies and organizations will be notified of these discrepancies, deficiencies, and shortcomings at the earliest practical date.

g. Record and analyze test results, determine acceptability of the installed AN/FRN-41 TVOR, record the data and findings on the TAR, and coordinate the data with the designated participants, prepare a final test report and make distribution with the guidance, direction, and format of CCCR 702-2. Project tasking documents must be consulted for modification of the distribution requirements. The acceptance test report will note outstanding installation and operational exceptions, and will recommend corrective actions to be taken by the responsible and participating agency(s). The report will document project completion with correction of the exceptions being documented by correspondence or supplemental test reports as determined by the QAR/Test Director or test agency.

6.2.3 Installation agency. In accordance with the provisions and authority of CCCR-702-4, the installation agency will establish and maintain a QC system. The QC system will assure that assessments of quality are conducted in accordance with the published procedures and that the results of the agency's QC inspections and follow-up actions are adequately recorded. USACEEIA Form 111R (figure 6-3) may be used for this purpose. The records are to be made available for review and evaluation by the test agency's QAR/Test Director. The shakedown checkouts are to be completed and corrections made prior to offering the AN/FRN-41 TVOR for acceptance testing. The installation activities QC system must meet all procedures contained in USACEI Bn Pamphlet 105-3. The installation agency will designate a quality control representative (QCR), who will assure the following actions are performed:

a. Assure that QC procedures are applied on this installation and establish the reporting requirements consistent with this project, the EIP, and all policies. Assure that the corrective action efforts related to the installation are resolved and corrected at the earliest possible point in the installation effort.

b. Assure the availability of test equipment for shakedown in conjunction with participating elements and checkout and acceptance testing. Reliance is to be placed upon the operating agency to supply test equipment when it is common to operations and maintenance functions.

QUALITY CONTROL CHECKLIST - INSTALLATION (CCCR 702-2)		PAGE 1 OF 7 PAGES		
		DATE (Day, Mo, Year)		
SITE	LOCATION	QUALITY CONTROL REPRESENTATIVE (QCR)		
PROJECT NAME		TASK NO.		
A. <u>General Safety Practice</u>		YES	NO	NA
1. Are goggles being worn when using grinding machines?				
2. Are sharp edges left on frame or duct work?				
3. Are all hand tools properly used?				
4. Are electric power tools properly grounded?				
5. Are ground wires securely attached?				
B. <u>Floor Plan Layout</u>				
1. Are layout plans in accordance with drawings?				
2. Was layout plan completed before equipment was moved into area?				
C. <u>Erecting and Mounting</u>				
1. Is equipment laid out in accordance with floor plan drawing?				
2. Are equipment bays leveled and plumbed within tolerances?				
3. Has proper spacing been provided between equipment racks?				
4. Are base angles of frames secured to floor in proper location?				
5. Are all cabinets flush mounted and plumbed?				
6. Has finish of equipment, cabinets, and racks been touched up?				
7. Are bolts and screws free from stripped threads and defaced heads?				

QUALITY CONTROL CHECKLIST - INSTALLATION (CCCR-702-2)	PAGE 2 OF 7 PAGES		
	YES	NO	NA
8. Have sufficient clearances been provided between apparatus for heat dissipation?  9. Are terminal blocks aligned on distributing frames?  10. Has equipment been installed in cabinets or racks in accordance with face layouts?  11. Are all nuts and bolts securely tightened?  12. Are exposed or cut ends of metal filed smooth and painted?			
<b>D. <u>Cable Racks</u></b>			
1. Location of cable racks: <ul style="list-style-type: none"> <li>a. Are cable racks located in accordance with cable plan drawing?</li> <li>b. Does height of cable racks conform to height above floor as indicated on cable plan drawing?</li> <li>c. Are cable racks located so that clearance is provided for installation and maintenance of ultimate equipment?</li> <li>d. Are cables located so they are not subject to damage due to exposure or other detrimental conditions?</li> </ul> 2. Assembly of cable racks: <ul style="list-style-type: none"> <li>a. Are long sections of cable racks used where possible?</li> <li>b. Have clamping details been altered other than where necessary to avoid interference?</li> <li>c. Are open ends of cable racks properly closed?</li> <li>d. Are vertical cable racks properly terminated on floors?</li> </ul> 3. Support of cable racks: <ul style="list-style-type: none"> <li>a. Are cable racks properly supported and fastened?</li> <li>b. Are cable racks installed so that no excessive load or binding is imposed on the equipment?</li> </ul>			

Figure 6-3. USACEEIA Form 111-R Continued.

QUALITY CONTROL CHECKLIST - INSTALLATION (CCCR-702-2)	PAGE 3 OF 7 PAGES		
	YES	NO	NA
<p>c. Are horizontal cable racks supported on approximately 5 feet centers but not to exceed 6 feet?</p> <p>d. Has support been provided within 3 feet of free end of cable rack?</p> <p>e. Are cable racks braced where necessary to prevent sway?</p>			
<p><b>E. Running Cable</b></p> <p>1. Are cable runs made in accordance with cable running list?</p> <p>2. Are oval shaped switchboard cables placed on edge?</p> <p>3. Are cables twisted or crossed on cable rack?</p> <p>4. Do cables conform to the bending radii and position at turns or bends?</p> <p>5. Is protection provided where cable sheaths contact rough or sharp edges or metal?</p> <p>6. Are cables turned off over side of cable racks formed with minimum allowable radii?</p> <p>7. Are cables turned off rack horizontally and then up?</p> <p>8. Do cables to the distributing frame enter on the vertical side?</p> <p>9. Are cables serving the horizontal side of a distributing frame secured to the transverse arms near the vertical upright?</p> <p>10. Are cable tags properly prepared and in accordance with the cable running list?</p> <p>11. Are cable tags secured at each end of cable run?</p> <p>12. Have cable tags been removed upon completion of verification and termination?</p> <p>13. Are cable butts located as near as practicable to the point where the first wires turn out?</p> <p>14. Are cable butts properly treated?</p>			

Figure 6-3. USACEEIA Form 111-R Continued.

QUALITY CONTROL CHECKLIST - INSTALLATION (CCCR-702-2)	PAGE 4 OF 7 PAGES		
	YES	NO	NA
15. Is insulation of wires undamaged at butt location?			
16. Are unused and spare wires protected at butt location?			
<u>F. Securing Cable</u>			
1. Is starting stitch properly made and placed?			
2. Is required Kansas City stitch properly made?			
3. Are first and succeeding layers of cable properly secured?			
4. Are cables secured at every cable rack cross strap?			
5. When cable butt is between securing devices, are cables secured together with an appropriate stitch?			
6. Are lock stitches properly made and spaced?			
7. Are splices in twine properly made?			
<u>G. Sewed Forms</u>			
1. Is proper size twine used for the diameter of the form?			
2. Are proper number of strands used?			
3. Are stitches properly spaced?			
<u>H. Butting and Stripping</u>			
1. Are proper tools used for butting and stripping of cable?			
2. Are cable butts properly dressed?			
3. Is proper distance maintained from cable butt to fanning strip?			
<u>I. Fanned Forms</u>			
1. Are cables fanned and connected to the left side of vertical mounted terminal blocks and to the bottom of horizontal terminal blocks?			
2. Are conductors in fanned forms not twisted and bunched?			

Figure 6-3. USACEEIA Form 111-R Continued.

QUALITY CONTROL CHECKLIST - INSTALLATION (CCCR-702-2)	PAGE 5 OF 7 PAGES		
	YES	NO	NA
3. Are fanned forms straight and taut from butt location to fanning strip?			
4. Is length of skimmers correct?			
5. Has color code been properly followed?			
6. Are spare wires disposed of properly?			
J. <u>Stenciling</u>			
1. Is equipment correctly identified and stenciled in accordance with floor plan drawings?			
2. Are designations correctly located?			
3. Are corrected size designations used on particular types of apparatus or equipment?			
K. <u>Strapping</u>			
1. Are straps properly placed?			
2. Is correct type of strap wire used?			
3. Does insulation extend to terminal?			
4. Are straps placed so as to not interfere with operation of apparatus?			
5. Is removal of apparatus not blocked?			
6. Are designations not obscured?			
L. <u>Connecting and Soldering</u>			
1. Is soldering clamp used when connecting wires?			
2. Are connections made on terminal in proper manner?			
3. Is all soldering done with standard resin core solder?			
4. Are connections secure and free of foreign substances?			
5. Have all unsightly flux and excess globules of solder been removed?			
6. Is insulation on skimmers not burnt or otherwise damaged?			

Figure 6-3. USACEEIA Form 111-R Continued.

QUALITY CONTROL CHECKLIST - INSTALLATION (CCCR-702-2)	PAGE 6 OF 7 PAGES		
	YES	NO	NA
7. Do skinners on connected terminals not exceed 1/16 in?			
8. Are all conductors given a continuity test after connection is made?			
M. <u>Transistor Soldering Techniques</u>			
1. Is caution exercised to assure that excessive heat does not destroy transistors?			
2. Are safeguards in effect to prevent leakage current at the end of an electrical soldering iron from destroying transistors?			
N. <u>Wrapped Connections</u>			
1. Are wrapped connections applied only on suitable terminals?			
2. Are connections essentially straight and free of angular bends or cramps?			
3. Are the required number of turns in contact with the terminal in accordance with criteria for gauge of wire used?			
4. Are wrapped connectors soldered where applicable?			
O. <u>Cross Connections</u>			
1. Are jumpers properly routed at distribution frame?			
2. Do jumpers have sufficient slack after connection?			
3. Are conductors not twisted between fanning strip and terminal?			
4. Does twist remain in conductors beyond rear of fanning strip?			
5. Are jumpers properly dressed?			
6. Has excess solder been removed from terminals?			

Figure 6-3. USACEEIA Form 111-R Continued.  
6-21

QUALITY CONTROL CHECKLIST - INSTALLATION (CCCR-702-2)	PAGE 7 OF 7 PAGES		
	YES	NO	NA
<p>P. <u>Equipment and Signal Grounds</u></p> <p>Are equipment and signal ground installed in accordance with applicable codes and standards and in accordance with installation drawings?</p>			
<p>Q. <u>Conduit</u></p> <ol style="list-style-type: none"> <li>1. Are burrs removed from conduit after cutting?</li> <li>2. Is bending radii in accordance with AFTO 31-10-12?</li> <li>3. Are there no more than four 90 degree bends in a single conduit run?</li> <li>4. Does number of conductors in conduit conform to AFTO 31-10-12?</li> <li>5. Are conduits supported at proper intervals?</li> <li>6. Have all fittings been tightened after installation?</li> </ol>			
<p>R. <u>Ducts (RF Shieldings)</u></p> <ol style="list-style-type: none"> <li>1. Are hangers for overhead ducts mounted first?</li> <li>2. Is proper type mallet used in assembly?</li> <li>3. Are flange sections cleaned before installation?</li> </ol>			
<p>S. <u>Coaxial Cables</u></p> <p>Is cable inspected for possible damage prior to installation?</p>			

Figure 6-3. USACEEIA Form 111-R Continued.

c. Assure that shakedown is accomplished as specified and any corrective action is completed prior to acceptance testing.

d. Advise the QAR/Test Director of the anticipated completion date at the earliest time. This notice should be given not less than 10 days prior to the scheduled completion to permit efficient and expeditious transportation of test personnel and equipment.

e. Assure that an adequate complement of personnel remain onsite to assist in the final QA inspection and acceptance test.

f. Assure the QC inspection records and installation documentation are maintained onsite and readily available to the QAR/Test Director. When the onsite effort is completed, the QC documentation shall be placed in the project files and maintained for one year.

6.2.4 Operating agency. The operating agency will be the site or location cognizant organization element and will be so identified in all project documentation and individual EIP's. Tasking to support the USA/EEIA QA and acceptance test effort will be accomplished through command channels. The operating agency will designate a representative early in the project but no later than the start of installation. He will assure the following actions are taken and completed.

a. Provide administrative and typing support.

b. Serve as interface between the installation, quality assurance, and test personnel and the operating agency.

c. Assist in resolution of discrepancies, deficiencies, and shortcomings.

d. Make operating and maintenance personnel available to assist on an as-required basis.

e. Provide a representative to witness the acceptance test and sign the TAR.

### 6.3. SPECIAL CONSIDERATIONS.

6.3.1 Interruptions. Quality assurance inspections and tests may be interrupted at any point if disrupted by an equipment or system malfunction. They may also be interrupted at a compatible breaking point to permit scheduled duty breaks. Any inspection that is interrupted because of equipment malfunction shall be restarted at a point determined by the QAR/Test Director.

6.3.2 Substitutions. Spare equipment may be substituted for malfunctioning equipment with the approval of the QAR/Test Director. Any equipment which has been replaced shall be repaired and retested. During acceptance tests, any piece of equipment, including cables, conduit, etc., may not be changed or adjusted without the approval of the QAR/Test Director.

6.3.3 Corrections or modifications of documentation. Site plans, specifications, EIP's, drawings, etc., are to be acquired by QA, QC, and test personnel prior to commencement of the specified work effort. At this time the QAR/Test Director will have identified the applicable and non-applicable observation items on USACEEIA Form 112R and will delete the mark "non-applicable" (N/A) those items inappropriate for his QA inspection observation items. These documents shall be used as master documents to mark, record, and identify discrepancies. Any discrepancies noted shall be recorded using yellow markings to record deletions of equipment, cables, or changes in schematic diagrams. All additions shall be noted with red markings. Notes to the draftsman will be in blue. Site documentation will be marked in the same manner. The designated installation agency representative will deliver a copy of the marked-up drawings to the onsite USACEEIA installation engineering element and in the absence of an engineer to Commander, USACEEIA, ATTN: CCC-CED, Fort Huachuca, Arizona 85613 or as amended by the EIP. In all cases a complete set of marked drawings will be left onsite and maintained by the operating agency.

## SECTION 7. ACCEPTANCE TEST PLAN AND PROCEDURES

7.1 GENERAL. This section contains the test procedures and states the special conditions which apply to shakedown, checkout, and acceptance tests for the installed AN/FRN-41 TVOR. Onsite tests are performed to determine if the designated AN/FRN-41 TVOR has been installed correctly, performs in accordance with the technical requirements of this SEIP and subsidiary documents, and is operationally suitable for the intended application.

### 7-2 TESTING.

7.2.1 Shakedown test and checkout. Functional tests will be conducted by the installation agency for the purpose of assuring that the equipment is aligned and operable and the installation is in accordance with the engineering documentation. These tests and checkouts will be conducted in coordination with personnel of the operating agency using the test plan identified in paragraph 7.2.2 and applicable technical bulletins and technical manuals available to the operating agency (the user). These tests will be conducted prior to the installation agency offering the installation for acceptance tests. As stated in section 6, the installation agency is to anticipate the installation completion date and notify the test agency of this completion not less than 10 days of scheduled date.

7.2.2 Onsite acceptance tests. Onsite acceptance testing will be accomplished in accordance with USACEEIA technical publication number CCC-TED-75-TP-200. These tests will be preceded by a thorough QA inspection in accordance with the requirements of section 6. Tests will be conducted in a normal operating environment, as stated in TB 95-1. Abnormal ambient conditions (e.g., temperature, humidity, or barometric pressure) during any test will be noted in the test log with detailed remarks included with the test results. The Test Director will determine if any retesting is required. The operating agency will provide personnel to operate and maintain the equipment during tests. Installation agency will provide personnel to assist the Test Director in the conduct of tests and measurements.

7.2.3 Flight checks. Operational flight checks will be performed by Federal Aviation Administration (FAA) qualified Air Traffic Control (ATC) personnel in conjunction with the acceptance tests and under the direction of the Test Director. Flight checks will determine whether or not the installed AN/FRN-41 TVOR functions correctly and performs in accordance with individual equipment and system mission requirements. This flight check is documented by the FAA. Copies of this report will be furnished participating agencies and included in the test report and retained in project files.

7.2.4 Test equipment. A complete listing of the required test equipment is contained in the appropriate technical manuals. Although the installation agency is responsible for assuring that the required complement of test equipment is available for installation, inspection, and test purposes. This test equipment should be available onsite from the operating agency.

7.2.5 Technical acceptance recommendation. Based on the QA inspections, QC reports and documentation, acceptance test results, and flight check results, the Test Director will determine the acceptability of the work effort. Prior to actual rejection, if the circumstances so warrant, the Test Director will attempt to coordinate his determination with the test agency and other cognizant agencies. The Test Director will prepare and distribute the technical acceptance recommendation (TAR) in accordance with the requirements of section 8. Preparation of the TAR will be accomplished onsite immediately following acceptance tests.

7.2.6 Test results. When one or more tests fail to meet requirements, the Test Director will determine which portion(s) of the test was affected and which portion(s) of the equipment or facility is to be retested. All deficiencies will be corrected, or, if not corrected, the deficiencies will be reported on the TAR and in the final test report.

7.2.7 Final test report. The test agency will prepare and distribute a test report in accordance with CCCR 702-2 as amended by the individual EIP and tasking documents. Copies of the completed TAR and flight inspection report will be included.

## SECTION 8. COMPLETION CERTIFICATION

8.1 GENERAL. The results of the QA inspections and acceptance tests specified in sections 6 and 7 will be documented onsite by the QAR/Test Director using USACEEIA Form 98R, TAR (figure 8-1). The purpose of this technical document is to record the significant project information to include the scope of the effort, results and conclusions of the requisite inspections and tests, exceptions to the technical requirements, and recommendations regarding acceptance with or without exceptions or rejection of the work effort. The TAR also provides other participants to indicate agreement or disagreement with the inspection and test assessments and for user to state a willingness to technically accept the installed AN/FRN-41 TVOR.

8.2 DISTRIBUTION. A copy of the TAR will be provided to the signing participants and the operating agency. The original copy will be maintained in the test agency project files but copies will be reproduced and included as part of the test report.

8.3 WAIVERS. Waivers to include command approvals for individual installations will be recorded in the TAR and copies attached for the purpose of clarifying deviations from this SEIP, the individual EIP, and Technical Bulletin TB-95-1.

INSTRUCTIONSTECHNICAL ACCEPTANCE RECOMMENDATION

1. Entries on the data sheets are to be typed whenever possible to ensure legibility and provide a quality, fully legible product when reproduced. If a typewriter is not available, the forms may be completed by printing with black ink in block letters to ensure legibility. The instructions for completion of this form follow on a block-by-block basis.
2. Pages are to be sequentially numbered to show both the individual page number and the total number of pages constituting the completed TAR. Additionally, each page will be identified by the date, project, and contract number in the appropriate blocks.
3. Instructions for completion of the TAR are delineated in the following subparagraphs and will be completed in accordance with these instructions:
  - a. DATE: Enter the day, month, and year of completion for this action (e.g., 1/1/79 as the first day of the first month of 1979.)
  - b. PROJECT/CONTRACT NUMBER: Enter the appropriate project or contract number. If this is a subproject or part of a subproject, provide all necessary information (i.e., IIP milestone number(s), subproject number(s) as well as subdivision(s) to same).
  - c. TITLE: Enter the project name or title.
  - d. LOCATION: Enter the geographic location where the project was installed.
  - e. FACILITY: Enter the name of the facility and other pertinent identifying information.
  - f. TEST DIRECTOR: Enter the name, title, and grade of the Test Director or QAR assigned to this project.
  - g. OPERATING AGENCY: Enter the name, symbol, and complete mailing address of the organization having O&M responsibility for this project, system, or equipment installation.
  - h. ENGINEERING AGENCY: Enter the name, symbol, and complete mailing address of the organization having engineering cognizance and responsibility.
  - i. INSTALLATION AGENCY: Enter the name, symbol, and complete mailing address of the organization having been tasked to install the TAR materiel.

j. TESTING AGENCY: Enter the name, symbol, and complete mailing address of the QA and testing organization tasked for this project.

k. PROJECT DESCRIPTION: Enter a brief and concise description of the project to which the TAR applies.

l. MAJOR EQUIPMENT INSTALLED/RELOCATED: List the major items of equipment installed or relocated in accordance with the project requirements. Enter the BOM line item number, materiel description, assigned part number or federal stock number, and the quantity of each major item. Components, assemblies, and subassemblies configured into a major item as listed in SB 700-20 or CCP 700-20 should also be recorded. Additional pages, numbered in sequence, may be added as required.

m. DOCUMENTATION: Enter the document identification (i.e., drawing number, technical manual number, etc.), title, and the quantity of each document provided to the operating unit as part of the project.

n. EXCEPTIONS:

(1) Upon completion of installation and testing, any exceptions to the project requirements which require corrective action will be listed. Include complete identification of each missing item. Exceptions must be based on the specified requirements of the project, supportable through the test results or other valid documentation, fully described, and precisely identified.

(2) The appropriate exception block must be annotated and separate sheets should be used for each category of exception.

(3) The Test Director will also enter the suggested action agency for each exception, recognizing that the Test Director may not always be in a position to determine the final action agency.

(4) For facilities that are becoming partially operational, identify installation agency actions remaining for project completion. In this situation, the Materiel Acceptance Record will show the tests that have been made, but will be identified as a partial record. A final Materiel Acceptance Record will be prepared after installation and testing of all remaining project equipment.

o. REMARKS. The remarks section may be used to provide any additional information on or in support of a recommendation, commendation, or criticism in relation to the project installation, engineering, or testing. Entries may include:

16 February 1979

- (1) Shortcomings which do not require corrective action (not considered an exception).
- (2) Recommendations for improving projects of a similar nature.
- (3) Identification of support items that have not been accomplished, and a description of any activity in progress by the operating agency to satisfy the requirement.
- (4) A description of test results with the performing agency and date(s) accomplished.
- (5) A statement to the effect that the installation agency will forward final "as built" drawings when completed.
- (6) A description of the ac power system with identification of source and backup capability.
- (7) A statement to indicate that a list of excess material was provided the operating command for final disposition or to identify material that was excess to the project.

p. CERTIFICATION: Enter the signatures and certification that the project was installed, tested, and accepted for operation with or without exceptions as applicable.

16 February 1979

SEIP 012

TECHNICAL ACCEPTANCE RECOMMENDATION (SUMMARY) (CCCR 702-2)		PAGE            OF            PAGES
		DATE (DAY, MO, YEAR)
PROJECT/CONTRACT NUMBER	TITLE	LOCATION
FACILITY		TEST DIRECTOR
OPERATING AGENCY	ENGINEERING AGENCY	
INSTALLATION AGENCY	TESTING AGENCY	
PROJECT DESCRIPTION		
<p>This Technical Acceptance Recommendation is executed by the onsite representatives of the installation, test and operating agencies. It does not constitute official acceptance of the project but does certify that the MAJOR ITEMS INSTALLED AND DOCUMENTATION PROVIDED are as stated herein. This document further certifies that the project has been installed and performs satisfactorily in accordance with the requirements listed under REFERENCES except as noted under EXCEPTIONS and REMARKS. Upon execution of this TECHNICAL ACCEPTANCE RECOMMENDATION, USACEEIA considers this project complete except for such follow-on action as may be necessary to clear the EXCEPTIONS stated herein.</p>		

USACEEIA FM 98-R            Figure 8-1. Technical Acceptance Recommendation.  
1 Jan 79    Replaces HQ USACEEIA CCC-TED-QA FM 98 which is obsolete



16 February 1979

SEIP 012

TECHNICAL ACCEPTANCE RECOMMENDATION (DOCUMENTATION) (CCCR 702-2)		PAGE OF PAGES
		DATE (DAY, MO, YEAR)
PROJECT/CONTRACT NUMBER	TITLE	LOCATION
PROJECT DOCUMENTATION PROVIDED		
REFERENCE DOCUMENTATION	TITLE	NO. OF COPIES

Figure 8-1. Technical Acceptance Recommendation. Continued.

TECHNICAL ACCEPTANCE RECOMMENDATION (EXCEPTIONS) (CCCR 702-2)		PAGE                      OF                      PAGES
		DATE (DAY, MO, YEAR)
PROJECT/CONTRACT NUMBER	TITLE	LOCATION
EXCEPTIONS ENGINEERING <input type="checkbox"/> INSTALLATION <input type="checkbox"/> OTHER <input type="checkbox"/>		SUGGESTED ACTION AGENCY

Figure 8-1. Technical Acceptance Recommendation Continued.



TECHNICAL ACCEPTANCE RECOMMENDATION (CERTIFICATION)		PAGE            OF            PAGES  DATE (DAY, MO, YEAR)
PROJECT/CONTRACT NUMBER	TITLE	LOCATION
<u>CERTIFICATION</u> Acceptance tests and Quality Assurance Inspections are complete for equipment installed under this project.		
WITHOUT EXCEPTIONS <input type="checkbox"/> WITH NOTED EXCEPTIONS <input type="checkbox"/>		
INSTALLATION AGENCY		SIGNATURE AND TITLE
		PRINTED
OPERATING AGENCY		SIGNATURE AND TITLE
		PRINTED
TEST AGENCY		SIGNATURE AND TITLE
		PRINTED
<u>ACCEPTANCE</u> Equipment herein certified successfully installed and tested, is accepted for operation.		
OPERATING COMMAND		SIGNATURE
		TITLE

Figure 8-1. Technical Acceptance Recommendation Continued.  
8-10

16 February 1979


SEIP 012

(CC-OPS)

FOR THE COMMANDER:

OFFICIAL:

EUGENE J. VITETTA  
Colonel, GS  
Chief of Staff



J. HOSTON  
LTC, AGC  
Adjutant General

DISTRIBUTION:

Special

- 5 - CC-PA-AMP
- 10 - CCC-CED-SEP
- 4 - CCC-CED-SW
- 4 - CCC-TED
- 5 - USACEI Bn
- 10 - USACEEIA-CONUS, ATTN: CCCN-TR, Fort Ritchie, MD 21719
- 10 - USACEEIA-EUR, APO New York 09056
- 10 - US Army Signal School, ATTN: ATSN-CD-MS, Fort Gordon, GA 31905
- 2 - US Army Materiel Development and Readiness Command, ATTN: CCN-PI-P, Washington, DC 20315
- 5 - 5th Signal Command, APO New York 09056
- 5 - 7th Signal Command, Fort Ritchie, MD 21719
- 1 - US Army Communications Command, ATTN: CC-OPS-PT, Fort Huachuca, AZ 85613
- 2 - US Army Training and Doctrine Command, ATTN: ATCE, Fort Monroe, VA 23351
- 2 - US Army Forces Command, ATTN: AFCE, Fort McPherson, GA 30330
- 2 - Defense Communications Agency, Technical Library Center, Code 205, Washington, DC 20305
- 12 - Defense Documentation Center, Cameron Station, Alexandria, VA 22314
- 2 - US Air Force, ATTN: USAFSAAS/TE00A, Keesler AFB, MS 39534
- 2 - 1842 EEG/EEISD, Scott AFB, IL 62225
- 2 - Naval Electronic Systems Command (NAVELEX), Code 51032, Washington, DC 20315

DEPARTMENT OF THE ARMY  
US Army Communications-Electronics  
Engineering Installation Agency  
Fort Huachuca, Arizona 85613

POSTAGE AND FEES PAID  
DEPARTMENT OF THE ARMY  
DoD 314



OFFICIAL BUSINESS  
PENALTY FOR PRIVATE USE \$300

COMMANDER  
US ARMY COMMUNICATIONS-ELECTRONICS  
ENGINEERING INSTALLATION AGENCY  
ATTN: CCC-CED-SEP  
Fort Huachuca, Arizona 85613

DEPARTMENT OF THE ARMY  
US Army Communications-Electronics  
Engineering Installation Agency  
Fort Huachuca, Arizona 85613

POSTAGE AND FEES PAID  
DEPARTMENT OF THE ARMY  
DoD 314



OFFICIAL BUSINESS  
PENALTY FOR PRIVATE USE \$300


COMMANDER  
US ARMY COMMUNICATIONS-ELECTRONICS  
ENGINEERING INSTALLATION AGENCY  
ATTN: CCC-CED-SEP  
Fort Huachuca, Arizona 85613



END

DATE  
FILMED

DDC



AD-A065 932 STANDARD ENGINEERING INSTALLATION PACKAGE TERMINAL VHF  
OMNIDIRECTIONAL RA..(U) ARMY COMMUNICATIONS COMMAND  
FORT HUACHUCA ARIZ 16 FEB 79 ACC-SEIP-012


3/3

UNCLASSIFIED

F/G 17/7

NL

DATE FILMED	SUPPLEMENTARY INFORMATION	[REDACTED]	[REDACTED]	END DATE FILMED 8-83 DTIC
----------------	------------------------------	------------	------------	---------------------------------------



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

**SUPPLEMENTARY**

**INFORMATION**

DEPARTMENT OF THE ARMY  
HEADQUARTERS, US ARMY COMMUNICATIONS-ELECTRONICS  
ENGINEERING INSTALLATION AGENCY  
Fort Huachuca, Arizona 85613

Change  
No. 1

29 July 1983

STANDARD  
ENGINEERING INSTALLATION PACKAGE  
TERMINAL VHF OMNIDIRECTIONAL RANGE (TVOR)  
SYSTEM AN/FRN-41


USACC SEIP 012, 16 February 1979, is redesignated USACEEIA SEIP 012, per USACC Supplement 1 to AR 310-2 is changed as follows:

1. Remove PD Form 1473, Report Documentation Page, and destroy.
2. Make the following pen and ink changes:
  - a. Page 1-12, paragraph 1.5a(1), delete CCTM 105-50-21. Renumber paragraph 1.5a.
  - b. Page 1-15, paragraph 1.6.1, line 7, change office symbol ATTN: CCC-CED-STD to CCC-CE-ES.
  - c. Page 1-15, paragraph 1.6.2, line 2, change office symbol ATTN: CCC-SPT-RM to CCC-DRM-P-R.
  - d. Page 2-3, paragraph 2.4, line 11, change site concurrence letter (SCL) to project coordination letter (PCL).
  - e. Page 3-15, paragraph 3.4.1, line 2, change two sets of drawings to three sets of drawings.
  - f. Page 4-1, paragraph 4.1.2, lines 2 and 3. Change USACC Commander and another "marked-up" to local commander and two "marked-up".
3. After posting this change file the change sheet in front of the basic publication for reference purposes.

FOR THE COMMANDER:

HOWARD C. RICHARDS  
Colonel, Signal Corps  
Deputy Commander

OFFICIAL:

  
DENNIS M. WARREN  
Lieutenant Colonel, Signal Corps  
Executive Officer

AD-A065932

**DISTRIBUTION:**

**Special**

- 3 - CC-PA-AMP
- 10 - CCC-CE-ES
- 4 - CCC-CE-SS
- 4 - CCC-TED
- 5 - USACEI Bn
- 10 - USACEEIA-CONUS, ATTN: CCCN-TR, Fort Ritchie, MD 21719
- 10 - USACEEIA-EUROPE, APO New York 09056
- 10 - US Army Signal School, ATTN: ATSN-CD-MS, Fort Gordon, GA 31905
- 2 - US Army Materiel Development and Readiness Command, ATTN:CCN-PI-P,  
Washington, DC 20315
- 5 - 5th Signal Command, APO NY 09056
- 5 - 7th Signal Command, Fort Ritchie, MD 21719
- 3 - US Army Communications Command, ATTN: CC-OPS-PP, Fort Huachuca, AZ 85613
- 2 - US Army Training and Doctrine Command, ATTN: ATCE, Fort Monroe, VA 23351
- 2 - US Army Forces Command, ATTN: AFCE, Fort McPherson, GA 30330
- 2 - Defense Communications Agency, Technical Library Center, Code 205, Washington,  
DC 20305
- 12 - Defense Documentation Center, Cameron Station, Alexandria, VA 22314
- 2 - Naval Electronic Systems Command (NAVELEX), Code 51032, Washington, DC 20315

EN

DATE  
FILME

8 - 8

DTIC