

AD-A068 882

NAVY UNDERWATER SOUND LAB NEW LONDON CONN  
SYSTEM ENGINEERING OF THE SONAR NOISE AND SOURCE LEVEL METER, M--ETC(U)  
JUL 58 V L WARD  
USL-TM-1230-70-58

F/G 17/1

UNCLASSIFIED

NL

| OF /  
AD  
A0 68882



END  
DATE  
FILMED  
6 --79  
DDC

MOST Project

**LEVEL**

THIS COPY FOR

Buships Code 6128 A

Copy 32 of 57 Copies

USL Problem No. 1-651-00-00

① B.S.

003314

Good B.S.

U. S. NAVY UNDERWATER SOUND LABORATORY  
FORT TRUMBULL, NEW LONDON, CONNECTICUT

⑥

SYSTEM ENGINEERING OF THE SONAR NOISE & SOURCE LEVEL METER, MODEL I.

By

⑩ V. L. WARD

USL Technical Memorandum No. 1230-70-58

⑫ 9 p.

⑪ 21 Jul 1958

DDC  
MAY 23 1979

INTRODUCTION

The Sonar Noise & Source Level Meter, Model 1, is a dual purpose instrument. It provides an absolute measurement of the noise level of the ship as seen in the sonar at any time and for any set of operating conditions. It also measures the source level of the sonar in terms of the output of the sonar transmitter. By comparing the measured values to those which are normal for a given ship and sonar system, the need for corrective maintenance may be determined.

The design of the meter has been tailored for use with the AN/SQS-4 Sonar, however, it can be used with other sonars if their outputs are equivalent to those provided by the AN/SQS-4 Sonar.

SYSTEM ENGINEERING OF THE EQUIPMENT

⑨ Technical memo.

The Sonar Noise & Source Level Meter, Model 1, is composed of a Cathode Follower Unit, a Voltage Divider Unit, and a Sonar Noise & Source Level Meter Unit. The physical layout is best described by referring to Figures 1 through 4; the circuits and the calibration procedures are described in detail in Ref. (a). The design is such that it can serve as a model for production purposes. Drawings have been forwarded to BuShips for use in negotiating for the manufacture of a number of such meters.

⑭ USL-TM-2230-70-58

There are only three operational controls on the meter, namely, power switch, noise level - source level selector switch, and noise level attenuator. The meter is common to both the noise level and the source level measurements. Indicating lights are provided to assist the operator in determining which mode of measurement is in operation.

The noise level for any particular bearing of the sonar listening beam can be measured by a very simple procedure. The operator merely selects the noise level mode of operation and then adjusts the calibrated attenuator until the pointer on the meter is centered over the red mark which is located at the center of the meter face. He then reads the setting of the attenuator. This is a measurement of the self-noise level and may be compared to what is normal for the particular ship and

A068882

1230-70-58

DDC FILE COPY

DISTRIBUTION STATEMENT A

Approved for public release; Distribution Unlimited

254 200

alt

operating speed. Surrounding the attenuator dial is a colored scale which indicates acceptable and unacceptable noise levels for ship speeds of 12, 15 and 18 knots. If the pointer of the attenuator lies in the red region of the scale, for a given ship's speed, the sonar is too noisy; the yellow region indicates an acceptable noise level; the green region indicates a desirably quiet condition. The colored scale has been made adjustable with respect to the attenuator db scale to allow for different sonar operating frequencies. A set screw located behind the front panel prevents this scale from turning with respect to the attenuator db scale; the set screw must be loosened before making an adjustment and must be reset after the adjustment has been made. An Allen wrench is provided for this purpose; it is located inside the front panel.

The source level can be measured by selecting the source level mode of operation, setting the sonar to the transmit mode of operation, and then reading the 105 to 125 db scale on the meter.

The following photographs and drawings have been prepared on the meter:

Photographs

NP24-16469-3-58	Sonar Noise and Source Level Meter, Model 1
NP24-16470-3-58	Right Side of Sonar Noise and Source Level Meter, Model 1, Interior
NP24-16471-3-58	Left Side of Sonar Noise and Source Level Meter, Model 1, Interior
NP24-16472-3-58	Sonar Noise and Source Level Meter, Model 1, Cathode Follower and Voltage Divider

Circuit Diagrams

Drawing No. E-41051-C	Noise and Source Level Meter Mod. 1
E-41063-B	Modification to AN/SQS-4 for Sonar Noise and Source Level Meter
E-41064-B	Interconnection Diagram, Sonar Noise and Source Level Meter to AN/SQS-4
E-40049-A	High-Pass Filter 5k Ohm
E-40050A	Cathode Follower
E-41046-B	Meter Dial

- 41681-D Assembly Noise and Source Level Meter, Model 1
  - 41682-E Chassis
  - 41683-E Assembly, Chassis
  - 41684-E Cabinet
  - 41685-A Identification Disk
  - 41686-A Identification Disk
  - 40347-B Dial - Outer Part
  - 40348-A Dial - Inner Part
  - 40349-A Pointer-Knob
  - 40350-A Spacer-Knob
  - 40351-B Assembly High-Pass Filter - Fk Ohm
  - 40352-C Mounting Board - Assembly
  - 40353-A Mounting Board
  - 40355-A Cover - Modified
  - 39997-B Assembly-Cathode Follower
  - 39998-A Mounting Plate
  - 41702-A Adapter Body
  - 41703-B AN/SQS-4 RCVR Adapter for Sonar Noise & Source Level  
Meter (Assembly)
- Parts lists, Unit No. 6552 (Adapter unit)  
Parts lists, Unit No. 6546 (Noise & Source Level Meter)  
Parts lists, Unit No. 6889 (High-Pass Filter)  
Parts lists, Unit No. 6890 (Plug-in Cathode Follower)
- SK-33045 Outline Drawing for Sonar Noise & Source Level  
Meter and Cathode Follower

APPROVAL BY	
OTIS	White Section <input checked="" type="checkbox"/>
ODD	Grey Section <input type="checkbox"/>
UNANNOUNCED <input type="checkbox"/>	
AUTHORIZATION	
Per Hqs. on File	
BY _____	
DISTRIBUTION/AVAILABILITY CODES	
DEL	AVAIL. MOD. OR SPECIAL
A	

*V. L. Ward*  
V. L. WARD  
Electronic Technician

USL Tech Memo  
No. 1230-70-58

LIST OF REFERENCES

- (a) D. W. Holloway, "Development of Sonar Noise & Source Level Meter, Model 1", USL Technical Memorandum No. 1230-036-58, 21 Jan. 1958, (CONFIDENTIAL)



Fig. 1 Sonar Noise and Source Level Meter, Model 1

USL Tech Memo No. 1230-70-58

U. S. Navy Underwater Sound Laboratory  
NP24 - 16469 - 3 - 58

Official Photograph





Fig. 2 Right Side of Sonar Noise and Source Level Meter, Model 1, Interior

USL Tech Memo No. 1230-70-58

U. S. Navy Underwater Sound Laboratory  
NP24 - 16470 - 3 - 58

Official Photograph



**Fig. 3 Left Side of Sonar Noise and Source Level Meter, Model 1, Interior**

**USL Tech Memo No. 1230-70-58**

**U. S. Navy Underwater Sound Laboratory  
NP24 - 16471 - 3 - 58**

**Official Photograph**



**Fig. 4 Sonar Noise and Source Level Meter, Model 1 - Cathode Follower  
and Voltage Divider**

**USL Tech Memo No. 1230-70-58**

**U. S. Navy Underwater Sound Laboratory  
NP24 - 16472 - 3 - 58**

**Official Photograph**

DISTRIBUTION LIST

Internal

100  
105  
107  
900  
906  
1100  
1200  
1210  
1230  
1230A (3)  
1234  
1235  
1240  
W.C.Hay(1240)  
G.B.Hall(1240)  
G.T.Adkins(1240)  
1245  
D.Holloway (1234)  
V.L.Ward(1235)  
1400  
1410  
1450 (5)

External

BuShips Code 689A (3)  
BuShips Code 688  
BuShips Code 689B  
COUSS WITEK (EDD-848)  
CO USS WALOY(EDE-791)  
CO USS SEAWOLF(SS (N) 575)  
CO USS SKATE (SS(N)578)