

COLUMBIA UNIVERSITY
HUDSON LABORATORIES
CONTRACT 16-012-27-25

COPY 8 OF 44 COPIES

USL Problem
No. 1-151-00-00

U. S. NAVY UNDERWATER SOUND LABORATORY
FORT TRUMBULL, NEW LONDON, CONNECTICUT

(6) THE SAVONIUS WATER CURRENT METER.)

by

(10) George F. Carey |

(9) USL Technical Memorandum No. 922-119-60

(11) 3 November 1960

LEVEL

On 4 August 1960 the author visited the David Taylor Model Basin for the purpose of calibrating five (5) Savonius water current meter rotors in the range of .1 to 1 knot.

The water current meters were developed for Project Artemis by Dr. Victor Anderson of the Marine Physical Laboratory of the Scripps Institution of Oceanography. ←

Figure 1 is a block diagram of the water current meter and its associated equipment. The details of the Savonius rotor are shown in figures 2 thru 4.

The wiring diagram (figure 5) shows that the transmitter consists of a 100 cycle oscillator which is transformer coupled to an amplifier. The Savonius rotor functions as a salt water switch which varies the coupling of the transformer thus it amplitude modulates the 100 cycle oscillator producing six pulses per second per revolution of the rotor.

Figure 6 is a copy of the calibration curves for rotors 1 thru 4 inclusive. This calibration was accomplished by a commercial concern for MPL in Convairs' tank in San Diego, California.

Figure 7 is the calibration curves for rotors 5 thru 9 inclusive. The data for these curves was taken by the author at DTMB on carriage No. 3.

Since the calibration curves group quite well, it would seem that an average curve could be drawn to be used by all future rotors without the necessity of calibration. The maximum variation of 17% from an average occurred at low speeds.

D D C
DISTRIBUTION STATEMENT A

Approved for public release
Distribution Unlimited

AUG 6 1979

79 08 03 114

NOV - 9 1960

AD A 072193

DDC FILE COPY

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO. 922-119-60	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) THE SAVONIUS WATER CURRENT METER		5. TYPE OF REPORT & PERIOD COVERED Tech Memo
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) Carey, George F.		8. CONTRACT OR GRANT NUMBER(s) N6-ONR-27135
9. PERFORMING ORGANIZATION NAME AND ADDRESS Naval Underwater Systems Center New London, CT		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS Office of Naval Research, Code 220 800 North Quincy St. Arlington, VA 22217		12. REPORT DATE 3 NOV 60
		13. NUMBER OF PAGES
14. MONITORING AGENCY NAME & ADDRESS (If different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)		

USL Tech Memo
No. 922-119-60


Caution should be exercised in such a procedure because of the possible occurrence of other rotors like No. 8 which produce erratic nonreproducible data.

George F Carey
G. F. Carey
Mechanical Engineer

Accession For	
NTIS GRA&I	☒
DDC TAB	☐
Unannounced	☐
Justification	
By _____	
Distribution/	
Availability Codes	
Dist.	Avail and/or special
A	

73 08 07 293

FOR WIRING DIAGRAM
SEE FIGURE 5 (SK-37506)



BLOCK DIAGRAM OF SAYONIUS
CURRENT METER ASSOCIATED
EQUIPMENT.




Fig. 2 - Plastic Savonius Rotor

U. S. Navy Underwater Sound Laboratory
NP24 - 19450 - 10 - 60

Official Photograph





Fig. 3 - Savonius Rotor Salt Water Switch

**U. S. Navy Underwater Sound Laboratory
NP24 - 19451 - 10 - 60**

Official Photograph

REVISIONS		
NO.	DESCRIPTION	DATE
1	NOTE 1 MODIFIED	10/9/60



MOUNTING HOLES
NOT TO BE
PLACED

NOTES:

1. MOUNT ROTOR WITH AXIS IN VERTICAL PLANE AND 8"x8" BASE DOWN
2. OVERALL DIMENSIONS ARE APPROXIMATE FOR CLEARANCE ONLY.

FIGURE 4

U. S. NAVY UNDERWATER SOUND LABORATORY Fort Trumbull, New London, Connecticut			
CURRENT METERS ROTOR PLANE ASSEMBLY			
MATL	NO. REQD	ASSOC. NO.	
DATE 7/10/60	SCALE	JOB ORDER	
DATE 7/10/60	FINISH	DATE 10/9/60	
APPD			
DATE			
			SK- 37337

THIS PAGE IS BEST QUALITY REPRODUCTION
FROM COPY FURNISHED TO DDC

COLUMBIA UNIVERSITY
HUDSON LABORATORIES
CONTRACT N6-ONR-27135


2 FEET OF CUMULATIVE WIRE
TO BASE
3 1/8" TRANSMITTER
POTED
16 3/4" FAULT AGE
OUTPUT CUMULATIVE WIRE

3RD-9890-11111
3ND-USNUSL-23


RECEIVER



DRESSEN-BARNES
MOD. 22-104 SUPPLY +300V

SET CURRENT
TO READ 20MA



TRANSMITTER (PLASTIC ENCAPSULATED)





MPL SAVINUS ROTOR
 CURRENT METER

1 KNOT

.5 KNOT

.250 KNOT

.125 KNOT

.0625 KNOT

THIS PAGE IS BEST QUALITY REPRODUCTION
 FROM COPY FURNISHED TO DOD

NOTES: THIS IS A COPY OF
 CURVES FURNISHED
 BY MPL


FIGURE 6
 ROTOR CALIBRATION
 CURVES

CALIBRATED AT COMNAV
 SAN DIEGO, CALIFORNIA
 FOR MPL

11 OCTOBER 1960

Skipped to copy

0.1 1.0
 ROTOR (REVOLUTIONS/SECOND)



MPI SAVONIUS ROTOR CURRENT METER

NOTE: NO. 3 ROTOR WAS NOT
PLOTTED BECAUSE OF
ERRATIC BEHAVIOR

1 KNOT

.5 KNOT

.250 KNOT

.125 KNOT

.0625 KNOT

THIS PAGE IS BEST QUALITY PRACTICALLY
FROM COPY FURNISHED TO DOD

WATER FLOW (FT/SEC.)

FIGURE 7

ROTOR CALIBRATION
CURVES

CALIBRATION POINTS
ON CHART AS INDICATED
4 AUGUST 1960

1.0

0.1

ROTOR (REVOLUTIONS/SECOND)