

AD-A085 759

KAMAN AVIDYNE BUPLINGTON MA

F/G 17/2

STRUCTURAL MODELING AND RESPONSE OF COMMAND, CONTROL AND COMMUN--ETC(U)

MAR 80 J M CALLIGROS, J P WALSH

DAAD05-74-C-0744

UNCLASSIFIED


KA-TK-151


ARBRL-CR-00421

NL

1-3

200-100





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

**(12) LEVEL III**

AD-E430442

AD

ADA 085759

CONTRACT REPORT ARBRL-CR-00421

STRUCTURAL MODELING AND RESPONSE OF  
COMMAND, CONTROL AND COMMUNICATION  
SHELTER SYSTEMS FOR EVENT DICE THROW

Prepared by

Kaman AviDyne  
83 Second Avenue  
Burlington, MA 01803

DTIC  
ELECTE  
JUN 23 1980  
S B D

March 1980



US ARMY ARMAMENT RESEARCH AND DEVELOPMENT COMMAND  
BALLISTIC RESEARCH LABORATORY  
ABERDEEN PROVING GROUND, MARYLAND

Approved for public release; distribution unlimited.

FILE COPY

80 5 27 215

Destroy this report when it is no longer needed.  
Do not return it to the originator.

Secondary distribution of this report by originating  
or sponsoring activity is prohibited.

Additional copies of this report may be obtained  
from the National Technical Information Service,  
U.S. Department of Commerce, Springfield, Virginia  
22151.

The findings in this report are not to be construed as  
an official Department of the Army position, unless  
so designated by other authorized documents.

*The use of trade names or manufacturers' names in this report  
does not constitute endorsement of any commercial product.*

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                                                                   | READ INSTRUCTIONS<br>BEFORE COMPLETING FORM |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------|---------------------------------------------|
| 1. REPORT NUMBER<br>CONTRACT REPORT ARBRL-CR-00421                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 2. GOVT ACCESSION NO.<br>AD-A085759                                               | 3. RECIPIENT'S CATALOG NUMBER               |
| 4. TITLE (and Subtitle)<br>Structural Modeling and Response of Command,<br>Control and Communication Shelter Systems for<br>Event DICE THROW                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 5. TYPE OF REPORT & PERIOD COVERED<br>Final Report<br>26 July 1977 - 1 March 1978 |                                             |
| 7. AUTHOR(s)<br>John M. Calligeros<br>John P. Walsh<br>Raffi P. Yeghiayan                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 6. PERFORMING ORG. REPORT NUMBER<br>KA TR-151 ✓                                   |                                             |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS<br>Kaman Avidyne<br>Division of Kaman Sciences Corporation<br>83 Second Avenue, Burlington, MA 01803                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 8. CONTRACT OR GRANT NUMBER(s)<br>DAAD05-74-C-0744 ✓                              |                                             |
| 11. CONTROLLING OFFICE NAME AND ADDRESS<br>U.S. Army Armament Research & Development Command<br>U.S. Army Ballistic Research Laboratory<br>ATTN: DRDAR-BL<br>Aberdeen Proving Ground, Maryland 21005                                                                                                                                                                                                                                                                                                                                                                                                                                           | 10. PROGRAM ELEMENT, PROJECT, TASK<br>AREA & WORK UNIT NUMBERS                    |                                             |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 12. REPORT DATE<br>MARCH 1980                                                     |                                             |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 13. NUMBER OF PAGES<br>271                                                        |                                             |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 15. SECURITY CLASS. (of this report)<br>UNCLASSIFIED                              |                                             |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 15a. DECLASSIFICATION/DOWNGRADING<br>SCHEDULE                                     |                                             |
| 16. DISTRIBUTION STATEMENT (of this Report)<br><br>Approved for public release; distribution unlimited.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                   |                                             |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                                                                   |                                             |
| 18. SUPPLEMENTARY NOTES<br><br>This research was sponsored by the U.S. Army Project DA No. 1L162118AH75,<br>AMCMS Code 632306.11.H7200, Nuclear Weapons Effects for Army Applications,<br>Blast and Shock.                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                                                                   |                                             |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number)<br><br>Finite Element Modeling                      Blast Response<br>Electronic Equipment Shelter              NASTRAN Modeling<br>Command Control Communication Systems   Structural Dynamics<br>DICE THROW                                      Blast Loading                                                                                                                                                                                                                                                                                            |                                                                                   |                                             |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number)<br><br>Structural finite element models of the Army command, control, and<br>communication systems AN/TRC-117, AN/TRC-110, AN/TCC-61 which utilizes the<br>S-280 shelter, and the AN/TRC-145 and AN/GRC-142B, which utilize the S-250<br>shelter, were developed for NASTRAN. Loading models and dynamic response for<br>overpressure levels experienced in the recent DICE THROW field test were<br>determined for all but the AN/GRC-142B. Comparisons between measured and<br>analytical accelerations are given for the AN/TRC-117 and the AN/TRC-145 at |                                                                                   |                                             |

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

an incident overpressure level of 41.4 kPa. The comparisons were generally poor for the AN/TRC-117 but much more favorable for the AN/TRC-145.

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

## FOREWORD

This work was performed for Ballistic Research Laboratories, Aberdeen Proving Ground, Md., under Contract Number DAAD05-74-C-0744 by Kaman AviDyne, Burlington, MA., a division of Kaman Sciences Corporation. The technical monitor for BRL was Dr. W. Don Allison. Mr. John M. Calligeros was the project leader and principal investigator of the study which was performed in the Structural Mechanics Group of Kaman AviDyne headed by Mr. E. S. Criscione.

The authors are grateful to Dr. W. Don Allison and Dr. William Schuman for their support during the course of the contract and to Mr. Joseph Roma of ECOM, Fort Monmoth, N.J., for providing configurational data on the various shelter-rack systems. The authors also acknowledge the following Kaman AviDyne personnel: Mr. Lawrence J. Mente for developing the structural model of the AN/TRC-145, Mr. Michael Tomayko for processing the NASTRAN runs and machine plots, and Mr. William Lee for computer processing of the various loading models.

|                                 |               |                                            |
|---------------------------------|---------------|--------------------------------------------|
| ACCESSION for                   |               |                                            |
| NTIS                            | White Section | <input checked="checked" type="checkbox"/> |
| DDC                             | Buff Section  | <input type="checkbox"/>                   |
| UNANNOUNCED                     |               | <input type="checkbox"/>                   |
| JUSTIFICATION                   |               |                                            |
| BY                              |               |                                            |
| DISTRIBUTION/AVAILABILITY CODES |               |                                            |
| Dist                            | AVAIL. and/or | SPECIAL                                    |
| A                               |               | -                                          |

# TABLE OF CONTENTS

|                                                                | <u>Page</u> |
|----------------------------------------------------------------|-------------|
| FOREWORD. . . . .                                              | 3           |
| LIST OF ILLUSTRATIONS . . . . .                                | 7           |
| LIST OF TABLES . . . . .                                       | 15          |
| 1. INTRODUCTION . . . . .                                      | 17          |
| 2. STRUCTURAL MODELS . . . . .                                 | 19          |
| 2.1 S-280 Shelter Systems . . . . .                            | 19          |
| 2.1.1 Basic S-280 Shelter . . . . .                            | 19          |
| 2.1.2 AN/TRC-117 Racks . . . . .                               | 31          |
| 2.1.3 AN/TRC-110 Racks . . . . .                               | 39          |
| 2.1.4 AN/TCC-61 . . . . .                                      | 52          |
| 2.1.5 Summary of S-280 Shelter Models . . . . .                | 52          |
| 2.2 S-250 Shelter Systems . . . . .                            | 63          |
| 2.2.1 Basic Shelter Model . . . . .                            | 63          |
| 2.2.1.1 Shelter Model for AN/TRC-145 . . . . .                 | 69          |
| 2.2.1.2 Hardened Shelter Model for AN/TRC-145 . . . . .        | 74          |
| 2.2.1.3 Shelter Model for AN/GRC-142B . . . . .                | 74          |
| 2.2.2 AN/TRC-145 Racks . . . . .                               | 81          |
| 2.2.3 AN/GRC-142B Racks . . . . .                              | 90          |
| 2.2.4 Summary of S-250 Shelter Models . . . . .                | 102         |
| 2.3 Truck Data . . . . .                                       | 108         |
| 3. TRANSIENT RESPONSE . . . . .                                | 115         |
| 3.1 Introduction . . . . .                                     | 115         |
| 3.2 S-280 Systems . . . . .                                    | 115         |
| 3.3 S-250 Systems . . . . .                                    | 132         |
| 3.4 Comparisons with Test Measurements . . . . .               | 132         |
| 3.5 Response of AN/TRC-145 to a 168 TJ (40 KT Blast) . . . . . | 210         |
| 4. SUMMARY AND MAJOR CONCLUSIONS . . . . .                     | 237         |
| APPENDIX A . . . . .                                           | 239         |
| APPENDIX B . . . . .                                           | 249         |
| LIST OF SYMBOLS . . . . .                                      | 257         |
| REFERENCES. . . . .                                            | 259         |
| DISTRIBUTION LIST . . . . .                                    | 261         |

# LIST OF ILLUSTRATIONS

| <u>Figure</u> |                                                                                            | <u>Page</u> |
|---------------|--------------------------------------------------------------------------------------------|-------------|
| 2.1           | S-280 Shelter . . . . .                                                                    | 20          |
| 2.2           | S-280 Roadside and Curbside Wall Dimensions . . . . .                                      | 21          |
| 2.3           | S-280 Floor and Roof Dimensions . . . . .                                                  | 22          |
| 2.4           | S-280 End Wall Dimensions . . . . .                                                        | 23          |
| 2.5           | Coordinate System Definition for AN/TRC-117, AN/TRC-110<br>and AN/TCC-61 Systems . . . . . | 24          |
| 2.6           | S-280 Roadside Wall Grid System . . . . .                                                  | 25          |
| 2.7           | S-280 Curbside Wall Grid System . . . . .                                                  | 26          |
| 2.8           | S-280 Roof Grid System . . . . .                                                           | 27          |
| 2.9           | S-280 Front End Wall Grid System . . . . .                                                 | 28          |
| 2.10          | S-280 Door End Grid System . . . . .                                                       | 29          |
| 2.11          | Typical S-280 Sandwich Panel . . . . .                                                     | 30          |
| 2.12          | Location of the AN/TRC-117 Racks within the S-280<br>Shelter (Top View) . . . . .          | 36          |
| 2.13          | Roadside Wall Racks - AN/TRC-117 . . . . .                                                 | 37          |
| 2.14          | Front End Racks - AN/TRC-117 . . . . .                                                     | 38          |
| 2.15          | Location of the AN/TRC-110 Racks within the S-280<br>Shelter (Top View) . . . . .          | 46          |
| 2.16          | Front End Rack Grid System - AN/TRC-110 . . . . .                                          | 47          |
| 2.17          | Location of the AN/TCC-61 Racks within the S-280<br>Shelter . . . . .                      | 54          |
| 2.18          | Roadside Wall Racks - AN/TCC-61 (Inside View) . . . . .                                    | 55          |
| 2.19          | Curbside Wall Racks - AN/TCC-61 (Inside View) . . . . .                                    | 56          |
| 2.20          | S-250 Shelter . . . . .                                                                    | 65          |
| 2.21          | S-250 Roadside and Curbside Wall Dimensions . . . . .                                      | 66          |
| 2.22          | S-250 Floor and Roof Dimensions . . . . .                                                  | 67          |
| 2.23          | S-250 End Wall Dimensions . . . . .                                                        | 68          |
| 2.24          | Coordinate System Definition for AN/TRC-145 and<br>AN/GRC-142B Systems . . . . .           | 70          |
| 2.25          | S-250 Sandwich Panel Construction . . . . .                                                | 71          |

# LIST OF ILLUSTRATIONS (CONT'D)

| <u>Figure</u> |                                                                                      | <u>Page</u> |
|---------------|--------------------------------------------------------------------------------------|-------------|
| 2.26          | Grid Point System for AN/TRC-145 Rear and Curbside Walls and Roof . . . . .          | 77          |
| 2.27          | Grid Point System for AN/TRC-145 Front and Roadside Walls and Base . . . . .         | 78          |
| 2.28          | Retrofit Concept of S-250 Shelter Walls . . . . .                                    | 79          |
| 2.29          | Grid Point System for AN/GRC-142B Rear and Curbside Walls and Roof . . . . .         | 82          |
| 2.30          | Grid Point System for AN/GRC-142B Front and Roadside Walls and Base . . . . .        | 83          |
| 2.31          | Location of the AN/TRC-145 Racks within the S-250 Shelter (Top View) . . . . .       | 87          |
| 2.32          | AN/TRC-145 Racks Against Front Wall . . . . .                                        | 88          |
| 2.33          | AN/TRC-145 Rack Against Roadside Wall . . . . .                                      | 89          |
| 2.34          | Location of the AN/GRC-142B Racks within the S-250 Shelter (Top View) . . . . .      | 97          |
| 2.35          | Grid Point System for AN/GRC-142B Racks . . . . .                                    | 98          |
| 2.36          | M35A2 2 1/2 Ton Truck . . . . .                                                      | 109         |
| 2.37          | M715 Cargo Truck, 1 1/4 Ton . . . . .                                                | 110         |
| 2.38          | Mass Model Layout . . . . .                                                          | 114         |
| 3.1           | Overpressure Near Center of S-280 Roadside Wall . . . . .                            | 118         |
| 3.2           | Overpressure on S-280 Roadside Wall Near Center of Vertical Edge . . . . .           | 119         |
| 3.3           | Overpressure on S-280 Roadside Wall Near Center of Roof Edge . . . . .               | 120         |
| 3.4           | Overpressure Near Center of S-280 Curbside Wall . . . . .                            | 121         |
| 3.5           | Overpressure on S-280 Curbside Wall Near Center of Vertical Edge . . . . .           | 122         |
| 3.6           | Overpressure on S-280 Curbside Wall Near Center of Roof Edge . . . . .               | 123         |
| 3.7           | Overpressure Near Center of S-280 Roof . . . . .                                     | 124         |
| 3.8           | Overpressure on S-280 Roof Near Center of Intersection with Front End Wall . . . . . | 125         |

# LIST OF ILLUSTRATIONS (CONT'D)

| <u>Figure</u> |                                                                                                 | <u>Page</u> |
|---------------|-------------------------------------------------------------------------------------------------|-------------|
| 3.9           | Overpressure on S-280 Roof Near Center of Roadside Edge . . . . .                               | 126         |
| 3.10          | Overpressure Near Center of S-280 Front End Wall . . .                                          | 127         |
| 3.11          | Translational Accelerations of AN/TRC-117 System at Floor Center (Base Motions) . . . . .       | 128         |
| 3.12          | Angular Accelerations of AN/TRC-117 System (Base Motions) . . . . .                             | 129         |
| 3.13          | Translational Acceleration of AN/TRC-145 System at Floor Center (Base Motions) . . . . .        | 130         |
| 3.14          | Angular Accelerations of AN/TRC System (Base Motions). .                                        | 131         |
| 3.15          | Acceleration Time History in Blast Direction, Near Center of Roadside Wall (NASTRAN) . . . . .  | 133         |
| 3.16          | Acceleration Time History, in Blast Direction, Near Center of Curbside Wall (NASTRAN) . . . . . | 134         |
| 3.17          | Vertical Acceleration Time History, Near Center of Roof (NASTRAN) . . . . .                     | 135         |
| 3.18          | Acceleration Time History in Horizontal Direction, End Wall (NASTRAN) . . . . .                 | 136         |
| 3.19          | Acceleration Time History in Blast Direction, Roadside Rack (NASTRAN) . . . . .                 | 137         |
| 3.20          | Vertical Acceleration Time History, Roadside Rack (NASTRAN) . . . . .                           | 138         |
| 3.21          | Acceleration Time History in Blast Direction, Roadside Rack (NASTRAN) . . . . .                 | 139         |
| 3.22          | Vertical Acceleration Time History Roadside Rack (NASTRAN) . . . . .                            | 140         |
| 3.23          | Acceleration Time History in Blast Direction, Front End Rack (NASTRAN) . . . . .                | 141         |
| 3.24          | Vertical Acceleration Time History, Front End Rack (NASTRAN) . . . . .                          | 142         |
| 3.25          | Rigid Body Acceleration Time History in Blast Direction, Center of Floor (NASTRAN) . . . . .    | 143         |
| 3.26          | Acceleration Time History in Blast Direction, Near Center of Roadside Wall (NASTRAN) . . . . .  | 144         |

# LIST OF ILLUSTRATIONS (CONT'D)

| <u>Figure</u> |                                                                                                | <u>Page</u> |
|---------------|------------------------------------------------------------------------------------------------|-------------|
| 3.27          | Acceleration Time History in Blast Direction, Near Center of Curbside Wall (NASTRAN) . . . . . | 145         |
| 3.28          | Vertical Acceleration Time History, Near Center of Roof (NASTRAN) . . . . .                    | 146         |
| 3.29          | Acceleration Time History in Horizontal Direction, End Wall (NASTRAN) . . . . .                | 147         |
| 3.30          | Acceleration Time History in Blast Direction, Front End Rack (NASTRAN) . . . . .               | 148         |
| 3.31          | Vertical Acceleration Time History, Front End Racks (NASTRAN) . . . . .                        | 149         |
| 3.32          | Acceleration Time History in Blast Direction, Front End Rack (NASTRAN) . . . . .               | 150         |
| 3.33          | Vertical Acceleration Time History, Front End Rack (NASTRAN) . . . . .                         | 151         |
| 3.34          | Acceleration Time History in Blast Direction, Front End Rack (NASTRAN) . . . . .               | 152         |
| 3.35          | Vertical Acceleration Time History, Front End Rack (NASTRAN) . . . . .                         | 153         |
| 3.36          | Rigid Body Acceleration Time History in Blast Direction, Center of Floor (NASTRAN) . . . . .   | 154         |
| 3.37          | Acceleration Time History in Blast Direction, Near Center of Roadside Wall (NASTRAN) . . . . . | 155         |
| 3.38          | Vertical Acceleration Time History, Near Center of Curbside Wall (NASTRAN) . . . . .           | 156         |
| 3.39          | Vertical Acceleration Time History, Near Center of Roof (NASTRAN) . . . . .                    | 157         |
| 3.40          | Acceleration Time History in Horizontal Direction, End Wall (NASTRAN) . . . . .                | 158         |
| 3.41          | Acceleration Time History in Blast Direction, Roadside Rack (NASTRAN) . . . . .                | 159         |
| 3.42          | Vertical Acceleration Time History, Roadside Rack (NASTRAN) . . . . .                          | 160         |
| 3.43          | Acceleration Time History in Blast Direction, Roadside Rack (NASTRAN) . . . . .                | 161         |

# LIST OF ILLUSTRATIONS (CONT'D)

| <u>Figure</u> |                                                                                                | <u>Page</u> |
|---------------|------------------------------------------------------------------------------------------------|-------------|
| 3.44          | Vertical Acceleration Time History, Roadside Rack (NASTRAN) . . . . .                          | 162         |
| 3.45          | Vertical Acceleration Time History, Curbside Rack (NASTRAN) . . . . .                          | 163         |
| 3.46          | Acceleration Time History in Blast Direction, Curbside Rack (NASTRAN) . . . . .                | 164         |
| 3.47          | Acceleration Time History in Blast Direction, Center of Floor (NASTRAN) . . . . .              | 165         |
| 3.48          | Acceleration Time History in Blast Direction, Near Center of Roadside Wall (NASTRAN) . . . . . | 168         |
| 3.49          | Acceleration Time History in Blast Direction, Roadside Rack (NASTRAN) . . . . .                | 169         |
| 3.50          | Vertical Acceleration Time History, Roadside Rack (NASTRAN) . . . . .                          | 170         |
| 3.51          | Acceleration Time History in Blast Direction, Roadside Rack (NASTRAN) . . . . .                | 171         |
| 3.52          | Vertical Acceleration Time History, Roadside Rack (NASTRAN) . . . . .                          | 172         |
| 3.53          | Acceleration Time History in Blast Direction, Front Wall Rack (NASTRAN) . . . . .              | 173         |
| 3.54          | Vertical Acceleration Time History, Front Wall Rack (NASTRAN) . . . . .                        | 174         |
| 3.55          | Overpressure on S-280 Roadside Wall . . . . .                                                  | 176         |
| 3.56          | Overpressure on S-280 Curbside Wall . . . . .                                                  | 177         |
| 3.57          | Overpressure on S-280 Roof . . . . .                                                           | 178         |
| 3.58          | Overpressure on S-280 Front End Wall . . . . .                                                 | 179         |
| 3.59          | Overpressure on S-250 Roadside Wall . . . . .                                                  | 180         |
| 3.60          | Overpressure on S-250 Curbside Wall . . . . .                                                  | 181         |
| 3.61          | Overpressure on S-250 Roof . . . . .                                                           | 182         |
| 3.62          | Overpressure on S-250 End Wall . . . . .                                                       | 183         |
| 3.63          | Comparison of Acceleration Time Histories in Blast Direction, Roadside Rack . . . . .          | 184         |

# LIST OF ILLUSTRATIONS (CONT'D)

| <u>Figure</u> |                                                                                                                                      | <u>Page</u> |
|---------------|--------------------------------------------------------------------------------------------------------------------------------------|-------------|
| 3.64          | Measured Acceleration Time History in Horizontal Direction, Roadside Rack . . . . .                                                  | 185         |
| 3.65          | Acceleration Time History in Blast Direction, Roadside Rack (NASTRAN) . . . . .                                                      | 186         |
| 3.66          | Measured Vertical Acceleration Time History, Roadside Rack . . . . .                                                                 | 187         |
| 3.67          | Measured Vertical Acceleration Time History, Roadside Rack . . . . .                                                                 | 188         |
| 3.68          | Vertical Acceleration Time History, Roadside Rack (NASTRAN) . . . . .                                                                | 189         |
| 3.69          | Measured Acceleration Time History in Blast Direction, Roadside Rack . . . . .                                                       | 190         |
| 3.70          | Acceleration Time History in Blast Direction, Roadside Rack (NASTRAN) . . . . .                                                      | 191         |
| 3.71          | Vertical Acceleration Time History, Roadside Rack (NASTRAN) . . . . .                                                                | 192         |
| 3.72          | Measured Acceleration Time History in Blast Direction, Front End Racks . . . . .                                                     | 193         |
| 3.73          | Acceleration Time History in Blast Direction, Front End Rack (NASTRAN) . . . . .                                                     | 194         |
| 3.74          | Comparison of Acceleration Time Histories, Front End Rack . . . . .                                                                  | 195         |
| 3.75          | Measured Vertical Acceleration Time History, Front End Rack . . . . .                                                                | 196         |
| 3.76          | Vertical Acceleration Time History, Front End Rack (NASTRAN) . . . . .                                                               | 197         |
| 3.77          | Measured Acceleration Time History in Blast Direction, Center of Floor . . . . .                                                     | 198         |
| 3.78          | Measured Acceleration Time History in Blast Direction, Center of Floor . . . . .                                                     | 199         |
| 3.79          | Acceleration Time History in Blast Direction, Center of Floor (NASTRAN) . . . . .                                                    | 200         |
| 3.80          | Comparison of Shock Spectra Based on Measured and Analytical Acceleration Time Histories in Blast Direction, Roadside Rack . . . . . | 201         |

# LIST OF ILLUSTRATIONS (CONT'D)

| <u>Figure</u> |                                                                                                                                        | <u>Page</u> |
|---------------|----------------------------------------------------------------------------------------------------------------------------------------|-------------|
| 3.81          | Shock Spectrum Based on Analytical Vertical Acceleration Time History, Roadside Rack (NASTRAN) . .                                     | 202         |
| 3.82          | Shock Spectrum Based on Analytical Acceleration Time History in Blast Direction, Roadside Rack (NASTRAN) .                             | 203         |
| 3.83          | Shock Spectrum Based on Analytical Vertical Time History, Roadside Rack (NASTRAN) . . . . .                                            | 204         |
| 3.84          | Shock Spectrum Based on Analytical Acceleration Time History in Blast Direction, Front End Rack (NASTRAN) .                            | 205         |
| 3.85          | Comparison of Shock Spectra Based on Measured and Analytical Vertical Acceleration Time History, Front End Rack . . . . .              | 206         |
| 3.86          | Comparison of Shock Spectra Based on Measured and Analytical Acceleration Time Histories in Blast Direction, Center of Floor . . . . . | 207         |
| 3.87          | Comparison of Measured and Analytical Acceleration Time Histories in Blast Direction, Roadside Rack . . .                              | 212         |
| 3.88          | Measured Acceleration Time History in Blast Direction, Roadside Rack . . . . .                                                         | 213         |
| 3.89          | Analytical Acceleration Time History in Blast Direction, Roadside Rack (NASTRAN) . . . . .                                             | 214         |
| 3.90          | Comparison of Measured and Analytical Vertical Acceleration Time Histories, Roadside Rack . . . . .                                    | 215         |
| 3.91          | Measured Vertical Acceleration Time History, Roadside Rack . . . . .                                                                   | 216         |
| 3.92          | Analytical Acceleration Time History Roadside Rack (NASTRAN) . . . . .                                                                 | 217         |
| 3.93          | Measured Acceleration Time History in Blast Direction, Roadside Rack . . . . .                                                         | 218         |
| 3.94          | Analytical Acceleration in Blast Direction, Roadside Rack (NASTRAN) . . . . .                                                          | 219         |
| 3.95          | Comparison of Measured and Analytical Vertical Acceleration Time Histories, Roadside Rack . . . . .                                    | 220         |
| 3.96          | Measured Vertical Acceleration Time History, Roadside Rack . . . . .                                                                   | 221         |

# LIST OF ILLUSTRATIONS (CONCL'D)

| <u>Figure</u> |                                                                                                                                                | <u>Page</u> |
|---------------|------------------------------------------------------------------------------------------------------------------------------------------------|-------------|
| 3.97          | Analytical Vertical Acceleration Time History,<br>Roadside Rack (NASTRAN) . . . . .                                                            | 222         |
| 3.98          | Analytical Acceleration in Blast Direction, Front<br>End Rack (NASTRAN) . . . . .                                                              | 223         |
| 3.99          | Measured Vertical Acceleration Time History, Front<br>End Rack . . . . .                                                                       | 224         |
| 3.100         | Analytical Vertical Acceleration Time History, Front<br>End Rack (NASTRAN) . . . . .                                                           | 225         |
| 3.101         | Measured Acceleration Time History in Blast Direction,<br>Center of Floor . . . . .                                                            | 226         |
| 3.102         | Analytical Acceleration Time History in Blast<br>Direction, Center of Floor (NASTRAN) . . . . .                                                | 227         |
| 3.103         | Comparison of Shock Spectra Based on Measured and<br>Analytical Acceleration Time Histories in Blast<br>Direction, Roadside Rack . . . . .     | 228         |
| 3.104         | Comparison of Shock Spectra Based on Measured and<br>Analytical Vertical Acceleration Time Histories,<br>Roadside Rack . . . . .               | 229         |
| 3.105         | Comparison of Shock Spectra Based on Measured and<br>Analytical Acceleration Time Histories in the Blast<br>Direction, Roadside Rack . . . . . | 230         |
| 3.106         | Comparison of Shock Spectra Based on Measured and<br>Analytical Vertical Acceleration Time Histories,<br>Roadside Rack . . . . .               | 231         |
| 3.107         | Shock Spectrum Based on Analytical Acceleration Time<br>History in Blast Direction, Front End Rack (NASTRAN). . . . .                          | 232         |
| 3.108         | Shock Spectrum Based on Analytical Vertical<br>Acceleration Time History, Front End Rack (NASTRAN) . . . . .                                   | 233         |
| 3.109         | Shock Spectrum Based on Analytical Acceleration Time<br>History in Blast Direction, Center of Floor (NASTRAN) . . . . .                        | 234         |
| 3.110         | Roll Angle Response of AN/TRC-145 to Increased Yield<br>at the Same Incident Overpressure (Truck) . . . . .                                    | 235         |

# LIST OF TABLES

| <u>Table</u> |                                                                                                             | <u>Page</u> |
|--------------|-------------------------------------------------------------------------------------------------------------|-------------|
| 2.1          | S-280 Panel Properties (CQUAD1) . . . . .                                                                   | 32          |
| 2.2          | Properties of S-280 Shelter Beam Elements . . . . .                                                         | 33          |
| 2.3          | CBAR Element Connections for the S-280 Shelter . . .                                                        | 34          |
| 2.4          | Properties of Support Brackets and Rack Beam Elements<br>for AN/TRC-117, AN/TRC-110 and AN/TCC-61 . . . . . | 40          |
| 2.5          | CBAR Element Connections for AN/TRC-117 Racks . . . .                                                       | 41          |
| 2.6          | Constraint Connections Between Racks and Shelter . .                                                        | 42          |
| 2.7          | Rack-supported Equipment for AN/TRC-117 System. . . .                                                       | 43          |
| 2.8          | Mass Breakdown of AN/TRC-117 . . . . .                                                                      | 44          |
| 2.9          | Assumed Distribution of Unspecified Mass for<br>AN/TRC-117 . . . . .                                        | 45          |
| 2.10         | CBAR Element Connections for the AN/TRC-110 Racks . .                                                       | 48          |
| 2.11         | Constraint Connections Between Racks and Shelter<br>Walls AN/TRC-110 System. . . . .                        | 49          |
| 2.12         | Rack Supported Equipment for AN/TRC-110 System . . .                                                        | 50          |
| 2.13         | Mass Breakdown of AN/TRC-110 . . . . .                                                                      | 51          |
| 2.14         | Distribution of Unspecified Mass for AN/TRC-110 . . .                                                       | 53          |
| 2.15         | Constraint Connections Between Racks and Shelter<br>Walls AN/TCC-16 System . . . . .                        | 57          |
| 2.16         | Equipment Masses for AN/TCC-61 System Roadside Wall<br>Racks . . . . .                                      | 58          |
| 2.17         | Equipment Masses for AN/TCC-61 System Curbside Wall<br>Racks . . . . .                                      | 59          |
| 2.18         | Mass Breakdown of AN/TCC-61 . . . . .                                                                       | 60          |
| 2.19         | Distribution of Unspecified Mass for AN/TCC-61 . . .                                                        | 61          |
| 2.20         | Model Summary of S-280 Systems . . . . .                                                                    | 62          |
| 2.21         | Natural Frequencies of S-280 Shelter Systems . . . .                                                        | 64          |
| 2.22         | S-250 Panel Properties (CQUAD1) . . . . .                                                                   | 72          |
| 2.23         | Properties of S-250 Shelter Beam Elements . . . . .                                                         | 73          |
| 2.24         | CBAR Element Connections for the AN/TRC-145 S-250<br>Shelter . . . . .                                      | 75          |

# LIST OF TABLES (CONCL'D)

| <u>Table</u> |                                                                                                        | <u>Page</u> |
|--------------|--------------------------------------------------------------------------------------------------------|-------------|
| 2.25         | S-250 Hardened Panel Properties (CQUAD1) . . . . .                                                     | 80          |
| 2.26         | CBAR Element Connections for the AN/GRC-142B S-250 Shelter . . . . .                                   | 84          |
| 2.27         | Properties of AN/TRC-145 Rack Beam Element . . . . .                                                   | 91          |
| 2.28         | CBAR Element Connctions for AN/TRC-145 Racks . . . . .                                                 | 92          |
| 2.29         | Constraint Connections Between AN/TRC-145 Racks and S-250 Shelter . . . . .                            | 93          |
| 2.30         | Equipment Masses for AN/TRC-145 System . . . . .                                                       | 94          |
| 2.31         | Mass Breakdown of AN/TRC-145 System . . . . .                                                          | 95          |
| 2.32         | Assumed Distribution of Unspecified Masses for an AN/TRC-145 System . . . . .                          | 96          |
| 2.33         | Properties of AN/GRC-142B Rack Beam Element . . . . .                                                  | 99          |
| 2.34         | CBAR Element Connections for AN/GRC-142B Racks . . . . .                                               | 100         |
| 2.35         | Constraint Connections Between AN/GRC-142B Racks and S-250 Shelter . . . . .                           | 101         |
| 2.36         | Equipment Masses for AN/TRC-145 System . . . . .                                                       | 103         |
| 2.37         | Mass Breakdown of AN/GRC-142B System . . . . .                                                         | 104         |
| 2.38         | Assumed Distribution of Unspecified Masses for AN/GRC-142B Equipment . . . . .                         | 105         |
| 2.39         | Summary of AN/TRC-145 and AN/GRC-142B System Models . . . . .                                          | 106         |
| 2.40         | Natural Frequencies of AN/TRC-145 and AN/GRC-142B Systems . . . . .                                    | 107         |
| 2.41         | Truck Mass and Inertia Data . . . . .                                                                  | 111         |
| 2.42         | Shelter-Rack Mass and Inertia Data . . . . .                                                           | 113         |
| 3.1          | Overpressure Levels . . . . .                                                                          | 116         |
| 3.2          | Accelerometer Locations for S-280 Shelter Systems . . . . .                                            | 166         |
| 3.3          | Accelerometer Locations for S-250 Shelter System . . . . .                                             | 167         |
| 3.4          | Frequency Content and Accelerations of Measured and Predicted Responses for the AN/TRC-117 . . . . .   | 208         |
| 3.5          | Frequency Content and Amplitude Ratio of Measured and Predicted Responses for the AN/TRC-145 . . . . . | 236         |

## SECTION I

### INTRODUCTION

An area of major concern to the Army is the blast response of acceleration sensitive equipment systems housed in truck mounted communication shelters. These systems include those for command, control and communications (C<sup>3</sup>) and others such as S<sup>3</sup>, TACFIRE, TOSS, and TRI-TAC. This subject is of considerable importance because the proper functioning of acceleration-sensitive equipment can be restricted by the shock-induced acceleration levels, resulting in negation of the mission of the Army system.

The blast response of electronic equipment housed in communication shelters is inherently complex since the equipment response is affected by the response of the supporting rack structure, the response of the shelter walls and by the motions of the truck. Currently, two complementary efforts are underway at Kaman Avidyne for BRL in this area. One effort, which is the primary subject of this report, is concerned with the detailed structural modeling and response of the shelter and of the equipment racks to the blast loads. Structural models of the shelter and racks are formulated with the finite element code NASTRAN as flexible interconnected structures subjected to the blast overpressure loads and to the base motions of the truck. The companion effort, on the other hand, is concerned with the development of the code TRUCK for predicting the nonlinear gross motions and possible overturning of a truck-shelter-rack system in response to blast. The base motions from the TRUCK code may be used as input data to the NASTRAN model to provide the base excitation experienced by the truck-mounted shelter system.

Several operational Army electronic communication shelter systems were modeled in the current study with NASTRAN for the DICE THROW field test. These include the AN/TRC-117, AN/TRC-110 and the AN/TCC-61 systems which are housed in the S-280 shelter, and the AN/TRC-145 system which is housed in the S-250 shelter. The S-280 systems are mounted on the M35A2 2½ ton truck and the S-250 system on the M715 1½ ton truck. Each of these systems consists of a basic shelter structure whose side walls are of sandwich construction with internal stiffeners. Channel extrusions along each free edge of the shelter provide additional strength and stiffening. The shelters contain electronic equipment racks of open framework construction using standard extrusions. The racks are usually connected to the shelter floor and to an adjacent shelter wall(s). Various electronic equipment are supported on the racks and additional equipment and electrical apparatus are located within the shelter.

Typically, each of the S-280 systems has a mass of approximately 2300 kg, about twice the mass of the S-250 system. The dynamical degrees-of-freedom of the NASTRAN models ranged from approximately 150

for the AN/TRC-145 to 275 for the AN/TCC-61. In essence, the final number of degrees-of-freedom reflects a compromise between the desire to reproduce a high degree of detail in the structural model and the practical considerations regarding computer storage and running times. The NASTRAN version used was Level 15.5.1 for the SCOPE 3.3 operating system. In addition to the above mentioned systems, structural models were developed for the AN/GRC-142B system which utilizes the S-250 shelter and a hardening concept for the AN/TRC-145.

Four major stages were involved in developing each shelter-rack structural model. The first consisted in arriving at an understanding of the internal structural geometry of the system using engineering drawings provided by ECOM and photographs in technical manuals. This resulted in a definition of the structural load paths, connectivity of frame and panel members, structural cross-sections, stiffness and mass distributions, and rack geometry. The second area involved the actual layout of the NASTRAN model, selection of the appropriate NASTRAN structural elements, property calculations, grid point layout, boundary condition selection, etc. The third phase was concerned with the preparation of a blast loading model, starting with pressure-time history information, converting it to forces at the loaded grid points of the shelter and introducing the grid loads into NASTRAN. Finally, the TRUCK code was exercised to determine the base response from which base motion loading tables were prepared for NASTRAN.

Section 2 of the report describes the structural model developed for each system, including pertinent data on the truck. Section 3 discusses the blast loading and presents acceleration time histories for the modeled systems (except the AN/GR-142B for which there was no requirement) as obtained by NASTRAN for several selected overpressure levels of the DICE THROW test. Section 3 also presents comparisons between NASTRAN predictions and the DICE-THROW data for two systems, the AN/TRC-117 and the AN/TRC-145, each at an incident overpressure level of 41.4 kPa (6.0 psi). Finally, a summary and conclusions are given in Section 4.

## SECTION 2

### STRUCTURAL MODELS

#### 2.1 S-280 SHELTER SYSTEMS

The AN/TRC-117, AN/TRC-110 and the AN/TCC-61 systems are each housed in the S-280 electronic equipment shelter. A photograph of the S-280 shelter is shown in Fig. 2.1 and overall dimensions are given in Figs. 2.2-2.4.

The S-280 shelter is basically a closed rectangular box whose side walls are of sandwich construction with internal hat stiffeners, containing channel extrusions along each edge of the shelter. The three systems mentioned above differ from each other with respect to the internally mounted electronic equipment, the rack frames used to support this equipment and in the installation of the rack frames within the shelter. The basic shelter, however, is structurally the same for each system.


##### 2.1.1 Basic S-280 Shelter

A NASTRAN finite element model of the S-280 shelter was developed from engineering drawings provided by ECOM. The shelter walls and roof were modeled as flexible structures using the NASTRAN plate (CQUAD1) and beam (CBAR) elements; the floor, however, was assumed rigid. Though the shelter has mass symmetry, the inclusion of the rack structure destroys the symmetry of the complete system. Therefore, it was necessary to model the entire shelter structure without the benefit of symmetry for reducing the dynamical degrees-of-freedom. Previous S-280 shelter models prepared under the current effort made use of symmetry because they had symmetric rack arrangements.

The basic coordinate system of the structure was located as shown in Fig. 2.5 and in Figs. 2.2-2.4. The blast wave is assumed to travel in direction 3, impinging upon the roadside wall and subsequently enveloping the entire shelter. Figures 2.6-2.10 show the grid systems for the shelter walls and roof. Dimensions are shown to the midplanes of the walls and roof and to the centerlines of the beam members. A typical cross-section of a wall or roof panel is depicted in Fig. 2.11. The sandwich panel is constructed of 0.813 mm aluminum facing sheets with a urethane foam core. The density of the urethane core is  $64 \text{ kg/m}^3$  in the roof and in the two outer bays of the roadside and curbside walls, and  $32 \text{ kg/m}^3$  in the remaining bays of the curbside and roadside walls and in the front end and door end walls.



FIGURE 2.1. S-280 SHELTER




NOTE: All dimensions in metres

FIGURE 2.2 S-280 ROADSIDE AND CURBSIDE WALL DIMENSIONS



### FIGURE 2.3 S-280 FLOOR AND ROOF DIMENSIONS



NOTE: All dimensions in metres

FIGURE 2.4. S-280 END WALL DIMENSIONS






FIGURE 2.5. COORDINATE SYSTEM DEFINITION  
FOR AN/TRC-117, AN/TRC-110  
AND AN/TCC-61 SYSTEMS






NOTE: ALL DIMENSIONS IN METRES

FIGURE 2.7. S-280 CURBSIDE WALL GRID SYSTEM




NOTE: ALL DIMENSIONS IN METRES

FIGURE 2.8. S-280 ROOF GRID SYSTEM



NOTE: ALL DIMENSIONS IN METRES

FIGURE 2.9. S-280 FRONT END WALL GRID SYSTEM



NOTE: ALL DIMENSIONS IN METRES

FIGURE 2.10. S-280 DOOR END GRID SYSTEM




FIGURE 2.11. TYPICAL S-280 SANDWICH PANEL

The sandwich panel was modeled with the CQUAD1 plate element, which reproduced the bending, extensional and shear stiffnesses. Table 2.1 lists the panel properties, referring to the dimensions given in Fig. 2.11. Also tabulated is the panel mass density  $\rho$

$$\rho = \frac{\rho_F t_F + 2\rho_S t_S}{T_1} \quad (2.1)$$

where  $\rho_F, t_F$  are the urethane core density and thickness,  $\rho_S, t_S$  are the skin density and thickness, and  $T_1$  is the reference membrane thickness. It is seen that the core density affects only the panel mass density and the transverse shear stiffness. CQUAD1 plate elements were connected between the grid points of each surface in Figs. 2.6-2.10, i.e., 35 elements were used for the roadside wall, 21 for the curbside wall, 35 for the roof, 12 for the front end and 9 for the door end.

The shelter has vertical and horizontal beam members along its edges and within each wall panel and the roof. Table 2.2 lists the section properties of these beam members (CBAR elements) and Table 2.3 identifies their grid point connections.\* Figures 2.6-2.10 may also be referred to for beam element identification.

The total weight of the modeled shelter structure as determined by the structural NASTRAN elements was 137 kg less than the actual weight, due to miscellaneous items such as hardware, weldments, fasteners, paint and adhesive which were not accounted for in the model. Concentrated mass cards (CONM2) were used to distribute the 137 kg at the grid points of the shelter walls and roof. The total weight of the S-280 shelter is 613 kg (Ref. 1).

The NASTRAN shelter model thus developed was used in each of the AN/TRC-117, AN/TRC-110 and AN/TCC-61 systems. Each system was then modeled by incorporating the appropriate racks and equipment within the basic shelter model. A description of each rack model is given in the following sections.

#### 2.1.2 AN/TRC-117 Racks

The AN/TRC-117 system consists of two equipment racks located at the roadside wall and a double rack at the front end wall. The rear of each rack is bolted to the wall and the rack bases to the floor. A schematic of the rack arrangement is shown in Fig. 2.12 and the grid systems of the racks are given in Figs. 2.13 and 2.14 (dimensions shown are to the centerlines of structural members).

---

\* Cross-section dimensional data may be obtained from the referenced ECOM drawings in Table 2.2.

Reference 1. Private Communication from Mr. Joe Roma of ECOM, Fort Monmouth, N. J.

TABLE 2.1  
S-280 PANEL PROPERTIES (CQUAD1)

| PROPERTY                                           | CORE DENSITY                 |                              |
|----------------------------------------------------|------------------------------|------------------------------|
|                                                    | $\rho_F = 32 \text{ kg/m}^3$ | $\rho_F = 64 \text{ kg/m}^3$ |
| I ( $\text{cm}^4/\text{cm}$ )                      | 2.70                         | 2.70                         |
| T <sub>1</sub> (mm)                                | 1.63                         | 1.63                         |
| T <sub>3</sub> (mm)                                | 50.4                         | 50.4                         |
| E (GPa)                                            | 68.9                         | 68.9                         |
| G (MPa)                                            | 1.38                         | 2.76                         |
| $\nu$                                              | .33                          | .33                          |
| $\rho \left( \frac{\text{Mg}}{\text{M}^3} \right)$ | 3.77                         | 4.77                         |

TABLE 2.2  
PROPERTIES OF S-280 SHELTER BEAM ELEMENTS

| CBAR                                                                                  | $I_{zz}$<br>(cm <sup>4</sup> ) | $I_{yy}$<br>(cm <sup>4</sup> ) | $I_{yz}$<br>(cm <sup>4</sup> ) | J<br>(cm <sup>4</sup> ) | $K_y$ | $K_z$ | A<br>(mm <sup>2</sup> ) | ECOM<br>DRAWING NO.        |
|---------------------------------------------------------------------------------------|--------------------------------|--------------------------------|--------------------------------|-------------------------|-------|-------|-------------------------|----------------------------|
| A    | 10.8                           | 13.3                           | 0                              | 12.7                    | .35   | .65   | 363                     | SM-B-165318                |
| B    | 4.97                           | .951                           | 0                              | .122                    | .50   | .50   | 147                     | SM-B-165440                |
| C    | 4.02                           | 7.34                           | 0                              | .016                    | .63   | .37   | 189                     | SM-B-165439                |
| D    | 14.7                           | 18.3                           | +1.38                          | 13.3                    | .42   | .58   | 454                     | SM-B-508769                |
| E    | 137.0                          | 64.4                           | +5.61                          | .641                    | .60   | .40   | 103                     | SM-B-165304<br>SM-B-165439 |
| F   | 63.6                           | 61.8                           | +1.74                          | 45.8                    | .45   | .55   | 101                     | SM-B-165304<br>SM-B-165310 |
| G  | 24.3                           | 23.0                           | +9.59                          | .362                    | .50   | .50   | 577                     | SM-B-165300<br>SM-B-165437 |

NOTE: The  $\pm$  sign on  $I_{yz}$  is determined by the beam location, since the cross-section may be reversed.


TABLE 2.3

CBAR ELEMENT CONNECTIONS  
FOR THE S-280 SHELTER

| CBAR | GRID POINT<br>CONNECTIONS | NUMBER<br>OF ELEMENTS | LOCATION         |
|------|---------------------------|-----------------------|------------------|
| A    | 2,13,21,29,37,45          | 5                     | ROADSIDE<br>WALL |
|      | 3,14,22,30,38,46          | 5                     |                  |
|      | 4,15,23,31,39,47          | 5                     |                  |
|      | 5,16,24,32,40,48          | 5                     |                  |
|      | 6,17,25,33,41,49          | 5                     |                  |
|      | 7,18,26,34,42,50          | 5                     |                  |
|      | 53,61,69,77               | 3                     | CURBSIDE<br>WALL |
|      | 54,62,70,78               | 3                     |                  |
|      | 55,63,71,79               | 3                     |                  |
|      | 56,64,72,80               | 3                     |                  |
|      | 57,65,73,81               | 3                     |                  |
|      | 58,66,74,82               | 3                     |                  |
|      | 84 → 91                   | 7                     | ROOF             |
|      | 92 → 99                   | 7                     |                  |
|      | 100 → 107                 | 7                     |                  |
|      | 108 → 115                 | 7                     |                  |
|      | 133,130,137,126           | 3                     | FRONT END        |
|      | 135,132,138,128           | 3                     |                  |
|      | 121,119,116               | 2                     | DOOR END         |
|      | 122,120,117               | 2                     |                  |

TABLE 2.3 (CONT'D)

| CBAR | GRID POINT CONNECTIONS           | NUMBER OF ELEMENTS | LOCATION                                       |
|------|----------------------------------|--------------------|------------------------------------------------|
| B    | 126,107                          | 2                  | FRONT END                                      |
|      | 128, 99                          | 2                  |                                                |
|      | 116,100                          | 2                  | DOOR END                                       |
|      | 117, 92                          | 2                  |                                                |
| C    | 125,126,128,129                  | 3                  | FRONT END                                      |
|      | 68,116,117,118                   | 3                  | DOOR END                                       |
| D    | 1,20,118,44                      | 3                  | DOOR END                                       |
|      | 52,60,68,76                      | 3                  |                                                |
|      | 8,141,139,129,51                 | 4                  | FRONT END                                      |
|      | 59,140,136,125,83                | 4                  |                                                |
| E    | 44,84,92,100,108,76              | 5                  | INTERSECTION<br>ROOF AND DOOR END              |
|      | 51,91,99,107,115,83              | 5                  | INTERSECTION<br>ROOF AND FRONT END             |
| F    | 1,12,20,28,118,36,44             | 6                  | INTERSECTION<br>ROADSIDE WALL<br>AND DOOR END  |
|      | 8,19,141,27,139,35,<br>129,43,51 | 8                  | INTERSECTION<br>ROADSIDE WALL<br>AND FRONT END |
|      | 52,60,68,76                      | 3                  | INTERSECTION<br>CURBSIDE WALL<br>AND DOOR END  |
|      | 59,140,67,136,125,75,83          | 6                  | INTERSECTION<br>CURBSIDE WALL<br>AND FRONT END |
| G    | 44 → 51                          | 7                  | INTERSECTION<br>ROADSIDE WALL<br>AND ROOF      |
|      | 76 → 83                          | 7                  | INTERSECTION<br>CURBSIDE WALL<br>AND ROOF      |



NOTE: ALL DIMENSIONS IN METRES

FIGURE 2.12. LOCATION OF THE AN/TRC-117 RACKS WITHIN THE S-280 SHELTER (TOP VIEW)




FIGURE 2.13. ROADSIDE WALL RACKS - AN/TRC-117




FIGURE 2.14. FRONT END RACKS - AN/TRC-117

Due to the stiffness provided by the rack shelves and the manner in which the equipment housing is bolted to the vertical uprights of the racks, it was assumed that a horizontal cross-section of the rack where equipment was mounted remained rigid and plane. This was accomplished by the use of multipoint constraint equations (MPC) in NASTRAN. Thus, for example, grid points 209-212 in Fig. 2.13 were constrained to translate and rotate as a rigid plane. The vertical rack uprights to which each such rigid plane is connected, however were free to bend and twist. This procedure appears justified by the physical constraints imposed by the equipment mounting arrangement and allows for the structural flexibility of the racks while reducing the degrees-of-freedom at each rack grid point. MPC equations were also used to connect the rear of each rack to the wall. Table 2.4 presents the property data for the rack vertical uprights and for the support brackets used in connecting the racks to the wall. Table 2.5 indicates the grid point connections for the vertical uprights and the support brackets and Table 2.6 gives the grid points that were MPC'd to connect the racks to the walls. The base of each rack was MPC'd to a grid point, GP7777, located at the center of the shelter floor.

The equipment supported by each rack is identified in Table 2.7, along with its mass and the grid points to which this mass was equally apportioned. The mass of the roadside rack complete with equipment is 181 kg and the mass of the front end rack complete with equipment is 371 kg which, when combined with the mass of the shelter and the CN-514/GRC results in a total mass of 1385 kg (see Table 2.8). Additional miscellaneous equipment is housed within the shelter to result in a total mass of 2304 kg for the AN/TRC-117 system (Refs 1 and 2). This additional unspecified equipment has a mass of 919 kg and is supported by the walls, roof and floor of the shelter; however, its actual distribution was not known. Working with photographs of the interior of the AN/TRC-117 system in Ref. 1, a rough estimation was made of the distribution of the 919 kg and it was apportioned as indicated in Table 2.9 with CONM2 mass cards. The mass of 919 kg represents 40% of the total system mass and its distribution constitutes a major uncertainty in the dynamic response. In addition, the manner in which this unspecified mass is attached to the shelter walls could affect local stiffness levels significantly, adding additional uncertainty.

### 2.1.3 AN/TRC-110 Racks

The AN/TRC-110 system contains a set of three racks located near the front end wall (see Fig. 2.15). Modeling of the racks followed the same procedures described for the AN/TRC-117 system in subsection 2.1.2. Figure 2.16 presents the rack grid system and Tables 2.10-2.13 present data relevant to the rack beam members, their connectivity, wall connections, equipment and system weight. The complete system has a mass of 2336 kg (Refs 1 and 2), of which 1108 kg (47% of the total system mass)

---

Reference 2. Organizational, DS, GS, and Depot Maintenance Manual For Medium Capacity Tactical Radio Relay system, Department of the Army Technical Manual TM-11-5895-456-15, Headquarters Department of the Army, July 1967.

TABLE 2.4

PROPERTIES OF SUPPORT BRACKETS AND RACK BEAM ELEMENTS  
FOR AN/TRC-117, AN/TRC-110 AND AN/TCC-61

| CBAR                                                                                 | $I_{zz}$<br>(cm <sup>4</sup> ) | $I_{yy}$<br>(cm <sup>4</sup> ) | $I_{yz}$<br>(cm <sup>4</sup> ) | J<br>(cm <sup>4</sup> ) | $k_y$ | $k_z$ | A<br>(cm <sup>2</sup> ) | ECOM<br>DRAWING NO.        |
|--------------------------------------------------------------------------------------|--------------------------------|--------------------------------|--------------------------------|-------------------------|-------|-------|-------------------------|----------------------------|
| H   | 18.3                           | 7.27                           | 0                              | .370                    | .70   | .30   | 491                     | SC-C-585118<br>SC-C-585117 |
| I   | 30.5                           | 2.04                           | 0                              | .129                    | .63   | .37   | 383                     | SC-C-547604<br>SC-C-547606 |
| J   | 2.37                           | 2.37                           | 0                              | 3.49                    | .40   | .40   | 282                     | 1x1x 1/8                   |
| K   | 5.23                           | 111.0                          | 0                              | .208                    | .20   | .80   | 615                     | SC-C-547061                |
| L   | 10.2                           | 207.0                          | 0                              | .333                    | .40   | .60   | 504                     | SC-C-547078                |
| M   | 41.8                           | 29.6                           | $\pm .6751$                    | .529                    | .70   | .30   | 701                     | SC-C-546982                |
| N   | 14.2                           | 14.2                           | 0                              | 20.8                    | .50   | .021  | 606                     | 2x2x1/4 Angle              |
| O  | 27.1                           | 15.4                           | 0                              | 25.0                    | .40   | .0234 | 690                     | SC-C-379522                |

TABLE 2.5

CBAR ELEMENT CONNECTIONS FOR AN/TRC-117 RACKS

| CBAR | GRID POINT<br>CONNECTIONS    | NUMBER<br>OF ELEMENTS | LOCATION                               |
|------|------------------------------|-----------------------|----------------------------------------|
| H    | 36 → 38                      | 2                     | ROADSIDE<br>WALL                       |
|      | 28, 29                       | 1                     |                                        |
| I    | 40, 41                       | 1                     | ROADSIDE<br>WALL                       |
|      | 24 → 27                      | 3                     |                                        |
|      | 17, 18                       | 1                     |                                        |
| J    | 201 → 228                    | 24                    | ROADSIDE WALL RACKS<br>FRONT END RACKS |
|      | 301 → 338                    | 24                    |                                        |
| K    | 402, 433, 410, 416, 422, 428 | 5                     | FRONT END RACKS                        |
|      | 405, 434, 413, 419, 425, 431 | 5                     |                                        |

TABLE 2.6  
CONSTRAINT CONNECTIONS BETWEEN  
RACKS AND SHELTER

AN/TRC-117 SYSTEM

| ROADSIDE WALL RACKS |                    | FRONT END RACKS    |                    |
|---------------------|--------------------|--------------------|--------------------|
| RACK<br>GRID POINT  | WALL<br>GRID POINT | RACK<br>GRID POINT | WALL<br>GRID POINT |
| 223                 | 38                 | 430                | 128                |
| 224                 | 39                 | 424                | 138                |
| 215                 | 22                 | 412                | 132                |
| 216                 | 23                 |                    |                    |
| 207                 | 14                 | 432                | 126                |
| 208                 | 15                 | 426                | 137                |
|                     |                    | 414                | 130                |
| 323                 | 39                 |                    |                    |
| 324                 | 40                 |                    |                    |
| 315                 | 23                 |                    |                    |
| 316                 | 24                 |                    |                    |
| 307                 | 15                 |                    |                    |
| 308                 | 16                 |                    |                    |

TABLE 2.7

## RACK-SUPPORTED EQUIPMENT FOR AN/TRC-117 SYSTEM

| EQUIPMENT    | MASS<br>(kg) | GRID POINT SUPPORTS  | LOCATION                 |
|--------------|--------------|----------------------|--------------------------|
| CV-1548      | 24.5         | 201 → 204; 301 → 304 | ROADSIDE<br>WALL<br>RACK |
| TD-352/v     | 46.3         | 205 → 208; 305 → 308 |                          |
| TSEC/KG-5    | 36.3         | 213 → 216; 313 → 316 |                          |
| TD-202/U     | 22.7         | 217 → 220; 317 → 320 |                          |
| TD-204/U     | 25.4         | 221 → 224; 321 → 324 |                          |
| R-1331(P)GRC | 45.4         | 421,422,424,425      | FRONT<br>END<br>RACK     |
| R-1331(P)GRC | 45.4         | 422,425,423,426      |                          |
| T-893(P)GRC  | 47.6         | 415,418,416,419      |                          |
| T-893(P)GRC  | 47.6         | 416,419,417,420      |                          |
| PP-2054/GRC  | 37.6         | 409,412,410,413      |                          |
| PP-2054/GRC  | 37.6         | 410,413,411,414      |                          |
| SAFE         | 45.4 (EST)   | 401,404,402,405      |                          |
| SPARE PARTS  | 22.7 (EST)   | 433,434,407,408      |                          |
| SPARE PARTS  | 22.7 (EST)   | 402,405,403,406      |                          |
| CN-514/GRC   | 40.5         | 126,128              | FRONT END<br>WALL        |

TOTAL WEIGHT OF EACH ROADSIDE WALL RACK FRAME PLUS SUPPORTED EQUIPMENT = 181 kg

TOTAL WEIGHT OF FRONT END RACK FRAME PLUS SUPPORTED EQUIPMENT = 371 kg


TABLE 2.8  
MASS BREAKDOWN OF AN/TRC-117

| ITEM             | MASS<br>(kg) |
|------------------|--------------|
| SHELTER          | 613          |
| ROADSIDE RACKS   | 361          |
| FRONT END RACK   | 371          |
| CN-514/GRC       | 40           |
| TOTAL            | 1385         |
| SYSTEM MASS      | 2304         |
| UNSPECIFIED MASS | 919          |

TABLE 2.9

ASSUMED DISTRIBUTION OF UNSPECIFIED MASS  
FOR AN/TRC-117

| ITEM          | MASS DISTRIBUTED (kg) |
|---------------|-----------------------|
| ROADSIDE WALL | 136                   |
| CURBSIDE WALL | 181                   |
| ROOF          | 45                    |
| FRONT END     | 136                   |
| DOOR END      | 91                    |
| FLOOR         | 330                   |
| TOTAL         | 919                   |



NOTE: ALL DIMENSIONS IN METRES

FIGURE 2.15. LOCATION OF THE AN/TRC-110 RACKS WITHIN THE S-280 SHELTER  
(TOP VIEW)




FIGURE 2.16. FRONT END RACK GRID SYSTEM - AN/TRC-110

TABLE 2.10

CBAR ELEMENT CONNECTIONS FOR THE AN/TRC-110 RACKS

| CBAR | GRID POINT CONNECTIONS  | NUMBER<br>OF ELEMENTS | LOCATION           |
|------|-------------------------|-----------------------|--------------------|
| J    | 201,209,217,225,233,241 | 5                     | EQUIPMENT<br>RACKS |
|      | 205,213,221,229,237,245 | 5                     |                    |
|      | 204,212,220,228,236,244 | 5                     |                    |
|      | 208,216,224,232,240,248 | 5                     |                    |
| K    | 202,210,218,226,234,242 | 5                     | EQUIPMENT<br>RACKS |
|      | 206,214,222,230,238,246 | 5                     |                    |
|      | 203,211,219,227,235,243 | 5                     |                    |
|      | 207,215,223,231,239,247 | 5                     |                    |
| L    | 99,128                  | 1                     | FRONT END          |
|      | 107,126                 | 1                     |                    |
| M    | 130,132,141             | 2                     | FRONT END          |
|      | 137,138,139             | 2                     |                    |
|      | 126,128,129             | 2                     |                    |
| N    | 132,141                 | 1                     | FRONT END          |
| O    | 21,22                   | 1                     | FRONT END          |

TABLE 2.11

CONSTRAINT CONNECTIONS BETWEEN RACKS  
AND SHELTER WALLS

AN/TRC-110 SYSTEM

| RACK GRID POINT | WALL GRID POINT |
|-----------------|-----------------|
| 245             | 129             |
| 237             | 139             |
| 221             | 141             |
| 248             | 126             |
| 240             | 137             |
| 224             | 130             |
| 246             | 128             |
| 238             | 138             |
| 222             | 132             |

TABLE 2.12

## RACK SUPPORTED EQUIPMENT FOR AN/TRC-110 SYSTEM

| EQUIPMENT   | MASS<br>(kg) | GRID POINT SUPPORTS | LOCATION           |
|-------------|--------------|---------------------|--------------------|
| TD-204/U    | 25.4         | 201,202,205,206     | EQUIPMENT<br>RACKS |
| TD-204/U    | 25.4         | 202,203,206,207     |                    |
| TD-204/U    | 25.4         | 203,204,207,208     |                    |
| TD-202/U    | 22.7         | 209,210,213,214     |                    |
| TD-202/U    | 22.7         | 210,211,214,215     |                    |
| TD-202/U    | 22.7         | 211,212,215,216     |                    |
| PP-2054/GRC | 37.6         | 217,218,221,222     |                    |
| PP-2054/GRC | 37.6         | 218,219,222,223     |                    |
| PP-2054/GRC | 37.6         | 219,220,223,224     |                    |
| T-893(P)    | 47.6         | 225,226,229,230     |                    |
| T-893(P)    | 47.6         | 226,227,230,231     |                    |
| T-893(P)    | 47.6         | 227,228,231,232     |                    |
| R-1331(P)   | 45.4         | 233,234,237,238     |                    |
| R-1331(P)   | 45.4         | 235,236,239,240     |                    |
| CN/514/GRC  | 40.5         | 107,128,126,99      | FRONT END<br>WALL  |
| LS-147/F1   | 4.81         | 38,39,46,47         | CURBSIDE WALL      |

TOTAL WEIGHT OF RACK FRAME PLUS SUPPORTED EQUIPMENT = 569 kg.

TABLE 2.13  
MASS BREAKDOWN OF AN/TRC-110

| ITEM             | MASS<br>(kg) |
|------------------|--------------|
| SHELTER          | 613          |
| RACKS            | 570          |
| CN-514/GRC       | 40           |
| LS-147/F1        | 5            |
| TOTAL            | 1228         |
| SYSTEM MASS      | 2336         |
| UNSPECIFIED MASS | 1108         |

is due to miscellaneous equipment whose mass distribution was unknown. Table 2.14 presents the assumed distribution of the 1108 kg, using photographs of the shelter interior in Ref. 2 as a guide.

#### 2.1.4 AN/TCC-61

The AN/TCC-61 systems consists of eight individual racks, four of which are located near the roadside wall and four near the curbside wall (see Fig. 2.17). Figures 2.18 and 2.19 show the grid point systems for the racks. Racks 3, 4, 5, 6, and 8 are identical to rack 1, and rack 2 is identical to rack 7, in frame construction. The racks differ somewhat with respect to the supported equipment, except for racks 3 and 6, and racks 4 and 8. The vertical uprights of each rack are made from the standard 1x1x1/8 in. extrusion, CBAR=J(Table 2.4).

As with the racks of the AN/TRC-117 and AN/TRC-110, the rear of each rack is bolted to its adjacent wall. Table 2.15 shows the rack and wall grid points which were connected by MPC equations. The masses supported by each rack are given in Tables 2.16 and 2.17 and the system mass breakdown is given in Table 2.18. For the AN/TCC-61, the distribution of 272 kg, i.e., 11% of the total mass of the system was unknown. Distribution of this mass was assumed using the photographs in Ref. 2 as a guide and allocated as shown in Table 2.19. As with the previous two systems, the bases of the AN/TCC-61 racks were MPC'd to grid point 7777 located in the center of the floor.


#### 2.1.5 Summary of S-280 Shelter Models

A summary of the basic structural and mass elements used to construct each model and the corresponding dynamical degrees-of-freedom are given in Table 2.20. The degree of complexity of the model depends strongly on the rack system. Since the AN/TCC-61 has the greatest number of racks it is the most complex model, requiring the largest number of grid points, elements and dynamical degrees-of-freedom. The AN/TRC-110 is the least complex of the three. In Table 2.20, a single point constraint (SPC) represents constraint of motion in any one of the six possible degrees-of-freedom at a grid point, multipoint constraint represents the dependence of motion at a grid point on the motions of another (independent) grid point and omitted coordinates (OMIT) designate degrees-of-freedom which are allowed elastically but are omitted from the inertia forces. The maximum possible degrees-of-freedom are computed as simply 6 times the number of grid points.

The base grid points of the roadside, curbside, front end and door end walls, as well as the base points of the racks, were multipoint constrained to a grid point located at the center of the floor to form a rigid floor. Since the shelter receives a base excitation in the blast


TABLE 2.14  
DISTRIBUTION OF UNSPECIFIED MASS  
FOR AN/TRC-110

| ITEM          | MASS DISTRIBUTED |
|---------------|------------------|
| ROADSIDE WALL | 181              |
| CURBSIDE WALL | 181              |
| ROOF          | 45               |
| FRONT END     | 136              |
| DOOR END      | 91               |
| FLOOR         | 474              |
| TOTAL         | 1108             |




NOTE: DIMENSIONS ARE IN METRES

FIGURE 2.17. LOCATION OF THE AN/TCC-61 RACKS WITHIN THE S-280 SHELTER



THE VERTICAL UPRIGHTS OF EACH RACK ARE CBAR-J ELEMENTS

FIGURE 2.18. ROADSIDE WALL RACKS - AN/TCC-61 (INSIDE VIEW)



THE VERTICAL UPRIGHTS OF EACH RACK ARE CBAR-J ELEMENTS

FIGURE 2.19. CURBSIDE WALL RACKS - AN/TCC-61 (INSIDE VIEW)

TABLE 2.15  
CONSTRAINT CONNECTIONS BETWEEN RACKS  
AND SHELTER WALLS  
AN/TCC-61 SYSTEM

| RACK | ROADSIDE WALL RACKS |                 | CURBSIDE WALL RACKS |                 |
|------|---------------------|-----------------|---------------------|-----------------|
|      | RACK GRID POINT     | WALL GRID POINT | RACK GRID POINT     | WALL GRID POINT |
| 1    | 223                 | 38              | 224                 | 39              |
|      | 219                 | 30              | 220                 | 31              |
|      | 211                 | 14              | 212                 | 15              |
| 2    | 319                 | 39              | 320                 | 40              |
|      | 315                 | 31              | 316                 | 32              |
|      | 307                 | 15              | 306                 | 16              |
| 3    | 423                 | 40              | 424                 | 41              |
|      | 419                 | 32              | 420                 | 33              |
|      | 411                 | 16              | 412                 | 17              |
| 4    | 523                 | 41              | 524                 | 42              |
|      | 519                 | 33              | 520                 | 34              |
|      | 511                 | 17              | 512                 | 18              |
| 5    | 5150                | 63              | 62                  | 5140            |
|      | 5230                | 71              | 70                  | 5240            |
| 6    | 4150                | 64              | 63                  | 4140            |
|      | 4230                | 72              | 71                  | 4240            |
| 7    | 3110                | 65              | 64                  | 3120            |
|      | 3190                | 73              | 72                  | 3200            |
| 8    | 2150                | 66              | 65                  | 2140            |
|      | 2230                | 74              | 73                  | 2240            |

TABLE 2.16  
EQUIPMENT MASSES FOR AN/TCC-61 SYSTEM

ROADSIDE WALL RACKS

| EQUIPMENT  | MASS<br>(kg) | GRID POINT<br>SUPPORTS | LOCATION | TOTAL<br>MASS<br>WITH RACK<br>FRAME (kg) |
|------------|--------------|------------------------|----------|------------------------------------------|
| CN-514/GRC | 47.6         | 201 → 204              | RACK 1   | 232                                      |
| CV-1548/G  | 22.7         | 205 → 208              |          |                                          |
| TD-352/V   | 54.4         | 209 → 212              |          |                                          |
| TIMING     | 18.1         | 213 → 216              |          |                                          |
| TSEC/KG-5  | 36.3         | 217 → 220              |          |                                          |
| TD-204/U   | 25.4         | 221 → 222              |          |                                          |
| SPARES     | 27.2         | 301 → 304              | RACK 2   | 193                                      |
| CV-1548/G  | 22.7         | 305 → 308              |          |                                          |
| TD-352/U   | 54.4         | 309 → 312              |          |                                          |
| TSEC/KG-5  | 36.3         | 313 → 316              |          |                                          |
| TD-204/U   | 25.4         | 317 → 320              |          |                                          |
| SPARES     | 18.1         | 401 → 404              | RACK 3   | 184                                      |
| CV-1548/G  | 22.7         | 405 → 408              |          |                                          |
| TD-352/U   | 54.4         | 409 → 412              |          |                                          |
| TSEC/KG-5  | 36.3         | 417 → 420              |          |                                          |
| TD-204/U   | 25.4         | 421 → 424              |          |                                          |
| SPARES     | 18.1         | 501 → 504              | RACK 4   | 202                                      |
| CV-1548/G  | 22.7         | 505 → 508              |          |                                          |
| TD-352/U   | 54.4         | 509 → 512              |          |                                          |
| TIMING     | 18.1         | 513 → 516              |          |                                          |
| TSEC/KG-5  | 36.3         | 517 → 520              |          |                                          |
| TD-204/U   | 25.4         | 521 → 524              |          |                                          |
| TOTAL (kg) |              |                        |          | 811                                      |

TABLE 2.17

EQUIPMENT MASSES FOR AN/TCC-61 SYSTEM  
CURBSIDE WALL RACKS

| EQUIPMENT  | MASS<br>(kg) | GRID POINT<br>SUPPORTS | LOCATION | TOTAL<br>MASS WITH<br>RACK FRAME (kg) |
|------------|--------------|------------------------|----------|---------------------------------------|
| SPARES     | 18.1         | 5010 → 5040            | RACK 5   | 202                                   |
| CV-1548/G  | 22.7         | 5050 → 5080            |          |                                       |
| TD-352/U   | 54.4         | 5090 → 5120            |          |                                       |
| TIMING     | 18.1         | 5130 → 5160            |          |                                       |
| TSEC/KG-5  | 36.3         | 5170 → 5200            |          |                                       |
| TD-204/U   | 25.4         | 5210 → 5240            |          |                                       |
| SPARES     | 18.1         | 4010 → 4040            | RACK 6   | 184                                   |
| CV-1548/G  | 22.7         | 4050 → 4080            |          |                                       |
| TD-352/U   | 54.4         | 4090 → 4120            |          |                                       |
| TSEC/KG-5  | 36.3         | 4170 → 4200            |          |                                       |
| TD-204/U   | 25.4         | 4210 → 4240            |          |                                       |
| SAFE       | 45.4         | 3010 → 3020            | RACK 7   | 211                                   |
| CV-1548/G  | 22.7         | 3050 → 3080            |          |                                       |
| TD-352/U   | 54.4         | 3090 → 3120            |          |                                       |
| TSEC/KG-5  | 36.3         | 3130 → 3160            |          |                                       |
| TD-204/U   | 25.4         | 3170 → 3200            |          |                                       |
| SPARES     | 18.1         | 2010 → 2040            | RACK 8   | 202                                   |
| CV-1548/G  | 22.7         | 2050 → 2080            |          |                                       |
| TD-352/U   | 54.4         | 2090 → 2120            |          |                                       |
| TIMING     | 18.1         | 2130 → 2160            |          |                                       |
| TSEC/KG-5  | 36.3         | 2170 → 2200            |          |                                       |
| TD-204/U   | 25.4         | 2210 → 2240            |          |                                       |
| TOTAL (kg) |              |                        |          | 799                                   |

TABLE 2.18

## MASS BREAKDOWN OF AN/TCC-61

| ITEM             | MASS<br>(kg) |
|------------------|--------------|
| SHELTER          | 613          |
| ROADSIDE RACKS   | 811          |
| CURBSIDE RACKS   | 799          |
| TOTAL            | 2223         |
| SYSTEM MASS      | 2495         |
| UNSPECIFIED MASS | 272          |

TABLE 2.19  
DISTRIBUTION OF UNSPECIFIED MASS FOR AN/TCC-61

| ITEM          | MASS DISTRIBUTED<br>(kg) |
|---------------|--------------------------|
| ROADSIDE WALL | 21.3                     |
| CURBSIDE WALL | 22.7                     |
| ROOF          | 45.4                     |
| FRONT END     | 68.0                     |
| DOOR END      | 68.0                     |
| FLOOR         | 46.6                     |
| TOTAL         | 272                      |

TABLE 2.20  
MODEL SUMMARY OF S-280 SYSTEMS

| ELEMENTS                               | AN/TRC-117 | AN/TRC-110 | AN/TCC-61 |
|----------------------------------------|------------|------------|-----------|
| BEAM                                   | 287        | 237        | 359       |
| PLATE                                  | 133        | 112        | 158       |
| MASS (CONM2)                           | 227        | 191        | 351       |
| GRID POINTS                            | 224        | 182        | 350       |
| SINGLE POINT CONSTRAINTS (SPC)         | 5          | 5          | 5         |
| MULTIPOINT-CONSTRAINTS (MPC)           | 524        | 444        | 1080      |
| OMITTED COORDINATES (OMIT)             | 581        | 422        | 740       |
| MAXIMUM POSSIBLE<br>DEGREES OF FREEDOM | 1344       | 1092       | 2100      |
| DYNAMICAL DEGREES<br>OF FREEDOM        | 234        | 221        | 275       |

MAXIMUM POSSIBLE DEGREES OF FREEDOM = 6x No. of GRID POINTS

DYNAMICAL DEGREES OF FREEDOM = MAXIMUM POSSIBLE - SPC - MPC - OMIT

direction (direction 3), the remaining five rigid body degrees-of-freedom of the base were SPC'd. This accounts for the five SPC's in Table 2.20. The base excitation is applied to the centroid grid point of the floor (grid point 7777) and the blast overpressure loads are applied to the wall and roof grid points as functions of time.

As an aid in validating the structural models, mode shapes and frequencies were obtained for each system. The first ten natural frequencies of the complete set, as obtained by the Givens Method in NASTRAN, are given in Table 2.21. Prior to executing the mode shape runs, the BANDIT code was run to resequence the numbering of the grid points for the purpose of minimizing matrix bandwidth.

## 2.2 S-250 SHELTER SYSTEMS

The AN/TRC-145 and the AN/GRC-142B systems are each housed in the S-250 electronic equipment shelter. A photograph of the S-250 shelter is shown in Fig. 2.20 and the overall dimensions are given in Figs. 2.21-2.23.

The S-250 shelter is shaped like a rectangular box with the two lower longitudinal edges indented to form a narrower base which fits between the wheel wells of a 1<sup>st</sup> ton truck used to transport it. The shelter sidewalls, roof, and floor are of sandwich construction, with aluminum interior and exterior skins, a urethane foam core, and hat-section internal stiffeners. The stiffeners are mounted vertically within the sidewalls and laterally in the roof and floor. A rear entrance door is provided. Channel extrusions along each edge of the shelter provide the attachment points between the separate panels and add strength and stiffness to the structure. In addition, the shelter sits on two longitudinal skids which form the contact point with the truck bed.

The AN/TRC-145 and the AN/GRC-142B systems differ from each other with respect to the installation of the rack frames mounted within the shelter, and the electronic equipment housed within the shelter on the supporting racks or on the shelter walls, floor, and ceiling. The S-250 shelter structure, however, remains the same for both systems.

### 2.2.1 Basic Shelter Model

Two variants of a NASTRAN finite element model of the S-250 shelter were developed from engineering drawings provided by ECOM. The two models differed from each other in the treatment of the knee panel and floor modeling detail. In addition, a "hardened" version of the shelter, retrofitted with additional sandwich panels on the walls, was modeled for one of the variants. The shelter walls and roof were modeled as flexible structures using the NASTRAN plate (CQUAD1) and beam (CBAR) elements. The floor and vertical knee-panel regions, forming the narrower U-shaped base to fit between the truck wheel wells, were

TABLE 2.21  
NATURAL FREQUENCIES OF S-280 SHELTER SYSTEMS  
(Hz)

| MODE | AN/TRC-117 | AN/TRC-110 | AN/TCC-61 |
|------|------------|------------|-----------|
| 1    | 23.92      | 25.53      | 19.30     |
| 2    | 25.77      | 27.21      | 23.47     |
| 3    | 27.23      | 28.95      | 26.57     |
| 4    | 28.48      | 30.08      | 26.92     |
| 5    | 29.73      | 31.95      | 31.18     |
| 6    | 31.94      | 34.22      | 33.81     |
| 7    | 34.22      | 35.88      | 35.23     |
| 8    | 36.64      | 36.63      | 35.39     |
| 9    | 38.33      | 38.46      | 35.72     |
| 10   | 40.00      | 40.84      | 36.34     |




FIGURE 2.20. S-250 SHELTER




FIGURE 2.21. S-250 ROADSIDE AND CURBSIDE WALL DIMENSIONS





FIGURE 2.22. S-250 FLOOR AND ROOF DIMENSIONS



(DIMENSIONS GIVEN IN METRES)

FIGURE 2.23. S-250 END WALL DIMENSIONS

assumed rigid. Although the shelter has approximate symmetry structurally and inertially, the inclusion of the racks and electronic equipment destroys the symmetry of the complete system under consideration, and makes it necessary to model the entire system, eliminating the benefit of reduced dynamic degrees-of-freedom due to symmetry.

The basic coordinate system of the structure was located as shown in Fig. 2.24. It is assumed that the blast wave will be applied in direction 1, impinging on the roadside wall and subsequently engulfing the entire shelter.

The sandwich panels employed for the construction of the shelter are comprised of 0.813-mm thick aluminum facing sheets with a urethane foam core. The density of the urethane core is  $32 \text{ kg/m}^3$ . A typical cross-section is shown in Fig. 2.25. At certain intervals, the sandwich panels are reinforced with hat-section stiffeners.

The sandwich panels were modeled with the CQUAD1 plate element of NASTRAN, reproducing the bending, extensional, and shear stiffnesses. Table 2.22 lists the panel properties, referring to the dimensions given in Fig. 2.25. The average mass density  $\rho$  for the panel is calculated as shown earlier in Eq. 2.1.

The shelter has vertical and horizontal extrusions along its edges and internal stiffeners within the sandwich panels. These elements were modeled with the CBAR beam element of NASTRAN, reproducing the bending, extensional, torsional, and shear stiffnesses. Table 2.23 lists the properties of the CBAR elements having various cross-sections.

The above structural components result in a total structural mass of the shelter which falls short of the actual mass of the S-250 shelter, since miscellaneous items such as hardware, weldments, fasteners, paint, adhesive, and sealant are not accounted for. To make up this deficit in mass, the concentrated mass input card CONM2 of NASTRAN is employed to locate various masses at specified grid points.

The following two subsections present the two variants of the NASTRAN model of the shelter. They differ in the location of some grid points and the modeling detail of the lower section of the shelter. The retrofitted "hardened" version of the first variant is also described.

#### 2.2.1.1 Shelter Model for AN/TRC-145

Inspection of the shelter structure indicates that the floor and vertical knee sections on either side of the shelter are of relatively strong construction, with twice the number of hat-section stiffeners employed in comparison with the sidewalls and roof. The floor is also supported by two longitudinal skids which add further stiffness to the floor. In addition, the racks for the AN/TRC-145 system rest on beams that span the knee-to-knee space above the floor. It was assumed that





FIGURE 2.24. COORDINATE SYSTEM DEFINITION FOR AN/TRC-145  
AND AN/GRC-142B SYSTEMS



(DIMENSIONS GIVEN IN MILLIMETRES)

FIGURE 2.25. S-250 SANDWICH PANEL CONSTRUCTION

TABLE 2.22  
S-250 PANEL PROPERTIES (CQUAD1)

| PROPERTY                                           | VALUE |
|----------------------------------------------------|-------|
| $I \left( \frac{\text{cm}^4}{\text{cm}} \right)$   | 0.541 |
| $T_1$ (mm)                                         | 1.63  |
| $T_3$ (mm)                                         | 35.7  |
| $E$ (GPa)                                          | 68.9  |
| $G_F$ (MPa)                                        | 1.38  |
| $\nu$                                              | 0.33  |
| $\rho \left( \frac{\text{Mg}}{\text{m}^3} \right)$ | 3.47  |

TABLE 2.23

## PROPERTIES OF S-250 SHELTER BEAM ELEMENTS

| CBAR                                                                                  | $I_{zz}$<br>(cm <sup>4</sup> ) | $I_{yy}$<br>(cm <sup>4</sup> ) | $I_{yz}$<br>(cm <sup>4</sup> ) | J<br>(cm <sup>4</sup> ) | A<br>(mm <sup>2</sup> ) | ECOM<br>DRAWING<br>NUMBER                                              |
|---------------------------------------------------------------------------------------|--------------------------------|--------------------------------|--------------------------------|-------------------------|-------------------------|------------------------------------------------------------------------|
| a    | 3.79                           | 9.29                           | 0.00                           | 4.683                   | 242                     | SM-B-649956                                                            |
| b    | 2.48                           | 1.43                           | 0.00                           | 0.012                   | 143                     | SM-B-649980                                                            |
| c    | 4.83                           | 10.98                          | 0.00                           | 5.444                   | 299                     | SM-B-649955                                                            |
| d    | 35.92                          | 344.18                         | 0.00                           | 0.291                   | 907                     | SC-D-693748                                                            |
| e    | 4.59                           | 37.88                          | 0.00                           | 0.154                   | 464                     | SC-D-693942                                                            |
| f    | 5.44                           | 29.84                          | 0.00                           | 0.150                   | 444                     | SC-D-693721                                                            |
| g    | 89.78                          | 189.34                         | 0.00                           | 0.312                   | 932                     | SC-D-693775                                                            |
| h    | 18.25                          | 13.99                          | -61.52                         | 0.104                   | 565                     | COMPOSITE:<br>SM-B-639957<br>SM-B-649958<br>SM-C-650117                |
| i (mirror<br>image of h)                                                              | 18.25                          | 13.99                          | 61.52                          | 0.104                   | 565                     |                                                                        |
| j   | 47.55                          | 77.46                          | -24.77                         | 10.822                  | 997                     | COMPOSITE:<br>SM-B-649957<br>SM-B-649955<br>SM-B-650106<br>SM-C-650117 |
| k (mirror<br>image of j)                                                              | 47.55                          | 77.46                          | 24.77                          | 10.822                  | 997                     |                                                                        |
| l  | 3.92                           | 63.18                          | 0.00                           | 5.411                   | 257                     | SM-B-650106                                                            |
| m —                                                                                   |                                |                                |                                |                         | 943                     | COMPOSITE: H+L+1/2A                                                    |
| n —                                                                                   |                                |                                |                                |                         | 1118                    | COMPOSITE: J+1/2 A                                                     |
| o —                                                                                   |                                |                                |                                |                         | 483                     | COMPOSITE: 2A                                                          |
| p —                                                                                   |                                |                                |                                |                         | 565                     | COMPOSITE: H,I                                                         |

the combined effects of the above would result in a very stiff structure for the base section of the shelter, and it would be justified to treat this section as a rigid plane in the NASTRAN structural model. Referring to Fig. 2.24, the shaded planar region is considered as a rigid body, and all masses below that plane are lumped into that plane for the inertial model.

Figure 2.26 shows the grid point system for the rear and curbside walls and the roof of the shelter, and Figure 2.27 shows the grid point system for the front and roadside wall and the base of the shelter for the same viewing angle as in Fig. 2.24. The dimensions are shown to the midplanes of the walls, roof and base, and to the centerlines of the stiffeners. The grid point numbering system for the GRID input of NASTRAN is shown. The roadside wall is modeled with more detail than the curbside wall as it faces the blast. The positioning of grid points on the walls is selected to provide the attachment points for the racks. Solid lines represent CBAR beam elements connecting the grid points, and the dashed lines, in addition to the solid lines, represent the boundaries of the CQUAD1 plate elements. Table 2.23 may be referred to for CBAR element cross-section identification and properties. Table 2.24 presents the CBAR element grid point connections for the identified cross-sections. CQUAD1 plate elements were connected between the grid points of each surface in Figures 2.26 and 2.27, resulting in 17 elements for the roadside wall, 8 elements for the curbside wall, 12 elements for the roof, 8 elements for the front wall, 6 elements for the rear wall, and 8 elements for the two horizontal knee panels.

#### 2.2.1.2 Hardened Shelter Model for AN/TRC-145

A hardening concept of the AN/TRC-145 system was also investigated in the current study. The hardening consisted of the addition of 19.1 mm aluminum honeycomb with a face sheet of 2.29 mm of Kevlar 49 epoxy composite material, with filaments running in both perpendicular directions, bonded to the exterior surfaces of the S-250 shelter (excluding the knee section). Figure 2.28 shows the cross-section of a typical S-250 shelter wall panel with the retrofit addition. The retrofit alters the stiffness and mass properties of the CQUAD1 plate elements which make up the wall panels. Table 2.25 presents the properties of the plate elements which were used for the hardened shelter walls. No other modifications were made to the previously described AN/TRC-145 structure to obtain the hardened configuration.

#### 2.2.1.3 Shelter Model for AN/GRC-142B

For the same reasons enumerated in the discussion in subsection 2.2.1.1, it was assumed that the base section of the shelter could justifiably be treated as a rigid region. Unlike the previous modeling variant for the AN/TRC-145 system where the base region was lumped into a rigid plane, additional modeling detail was observed for the AN/GRC-142B system shelter model. This was partly necessitated by the fact

TABLE 2.24

CBAR ELEMENT CONNECTIONS FOR THE  
AN/TRC-145 S-250 SHELTER

| CBAR | GRID POINT CONNECTIONS                   | NUMBER OF<br>ELEMENTS | LOCATION      |
|------|------------------------------------------|-----------------------|---------------|
| a    | 2,7,12,17,26,22                          | 5                     | ROADSIDE WALL |
|      | 3,8,13,18,27,23                          | 5                     |               |
|      | 4,9,14,19,24                             | 4                     |               |
|      | 57,60,63                                 | 2                     | CURBSIDE WALL |
|      | 56,59,62                                 | 2                     |               |
|      | 55,58,61                                 | 2                     |               |
|      | 22,67,64,63                              | 3                     | ROOF          |
|      | 23,68,65,62                              | 3                     |               |
|      | 24,69,66,61                              | 3                     |               |
|      | 2,80,76                                  | 2                     | KNEE PANELS   |
|      | 3,81,77                                  | 2                     |               |
|      | 4,92,78                                  | 2                     |               |
|      | 72,57                                    | 1                     |               |
|      | 73,56                                    | 1                     |               |
|      | 74,82,55                                 | 2                     |               |
| b    | 48,51,54                                 | 2                     | CURBSIDE WALL |
| c    | 28,33,42                                 | 2                     | FRONT WALL    |
|      | 29,36,43                                 | 2                     |               |
|      | 30,39,44                                 | 2                     |               |
|      | 46,49,52                                 | 2                     | REAR WALL     |
|      | 47,50,53                                 | 2                     |               |
|      | 11,49,50,51                              | 3                     |               |
| d    | 15,32,33,34,35,36, }<br>37,38,39,40,41 } | 10                    | FRONT WALL    |
| e    | 71,93,79                                 | 2                     | KNEE PANELS   |
|      | 75,83,70                                 | 2                     |               |

TABLE 2.24 (CONCL'D)

| CBAR | GRID POINT CONNECTIONS | NUMBER OF ELEMENTS | LOCATION      |
|------|------------------------|--------------------|---------------|
| f    | 80,81                  | 1                  | KNEE PANEL    |
| g    | 26,27                  | 1                  | ROADSIDE WALL |
| h    | 1,2,3,4,71,5           | 5                  | ROADSIDE WALL |
|      | 54,63,62,61,45         | 4                  | CURBSIDE WALL |
|      | 21,52,53,54            | 3                  | ROOF          |
|      | 5,28                   | 1                  | KNEE PANEL    |
|      | 30,31                  | 1                  |               |
| i    | 21,22,23,24,25         | 4                  | ROADSIDE WALL |
|      | 48,57,56,55,70,31      | 5                  | CURBSIDE WALL |
|      | 25,42,43,44,45         | 4                  | ROOF          |
|      | 1,46                   | 1                  | KNEE PANEL    |
|      | 47,48                  | 1                  |               |
| j    | 1,6,11,16,21           | 4                  | ROADSIDE WALL |
|      | 31,41,45               | 2                  | CURBSIDE WALL |
| k    | 5,10,15,20,25          | 4                  | ROADSIDE WALL |
|      | 48,51,54               | 2                  | CURBSIDE WALL |
| l    | 21,52,53,54            | 3                  | ROOF          |
|      | 25,42,43,44,45         | 4                  |               |
|      | 1,46                   | 1                  | KNEE PANELS   |
|      | 47,48                  | 1                  |               |
|      | 5,28                   | 1                  |               |
|      | 30,31                  | 1                  |               |




FIGURE 2.26. GRID POINT SYSTEM FOR AN/TRC-145  
REAR AND CURBSIDE WALLS AND ROOF





FIGURE 2.27. GRID POINT SYSTEM FOR AN/TRC-145  
FRONT AND ROADSIDE WALLS AND BASE



$$\rho_F = 32 \text{ kg/m}^3$$

$$G_F = 1.38 \text{ MP}_a$$

URETHANE FOAM

$$\rho_{HC} = 130 \text{ kg/m}^3$$

$$G_{HC} = 345 \text{ MP}_a$$

HONEYCOMB (5056 AL ALLOY)

$$\rho_K = 1.38 \text{ Mg/m}^3$$

$$E_K = 23.7 \text{ GP}_a$$

KEVLAR 49 COMPOSITE

FIGURE 2.28. RETROFIT CONCEPT OF S-250 SHELTER WALLS

TABLE 2.25  
S-250 HARDENED PANEL PROPERTIES (CQUAD1)

| PROPERTY                                           | VALUE |
|----------------------------------------------------|-------|
| $I \left( \frac{\text{cm}^4}{\text{cm}} \right)$   | 3.41  |
| $T_1 (\text{mm})$                                  | 2.41  |
| $T_3 (\text{mm})$                                  | 19.2  |
| $E (\text{GPa})$                                   | 68.9  |
| $G (\text{MPa})$                                   | 345   |
| $\nu$                                              | .33   |
| $\rho \left( \frac{\text{Mg}}{\text{m}^3} \right)$ | 4.68  |

that the racks for this system have vertical columns that rest directly on channels on the floor of the shelter (the 145 system racks had no connections to the floor) and a desire to have an improved definition of the mass distribution in the base region of the shelter for future dynamic response analyses. Thus, the overall shape of the S-250 shelter base region was retained in this modeling variant, with the addition of grid points to define the vertical knee panels and floor of the shelter. In addition, the vertical positioning of grid points on the shelter walls was altered to accommodate the attachment points for the different racks in the AN/GRC-142B system.

Figure 2.29 shows the grid point system for the rear and curbside walls and the roof of the shelter, and Figure 2.30 shows the grid point system for the front and roadside wall and the base of the shelter for the same viewing angle as in Fig. 2.24. Again, the dimensions are shown to the midplanes of the walls, roof, and base sections, and to the centerlines of the stiffeners. It should be noted that the additional stiffeners in the U-shaped base region of the shelter (vertical knee panels and floor) have been accounted for by lumping their mass contribution into their adjacent CBAR elements. The grid point numbering system for the GRID input of NASTRAN is shown. As before, the solid lines represent CBAR beam elements connecting the grid points, and the dashed lines, in addition to the solid lines, represent the boundaries of the CQUAD1 plate elements. Table 2.23 may be referred to for CBAR element cross-section identification and properties. Table 2.26 presents the CBAR element grid point connections for the identified cross-sections. CQUAD1 plate elements were connected between the grid points of each surface in Figs. 2.29 and 2.30, resulting in 16 elements for the roadside wall, 12 elements for the curbside wall, 12 elements for the roof, 10 elements for the front wall, 7 elements for the rear wall, and 22 elements for the knee panels and floor.

#### 2.2.2 AN/TRC-145 Racks

The AN/TRC-145 electronic equipment system employs three equipment racks located against the front wall and one rack located against the roadside wall near the rear of the S-250 shelter. The three racks are bolted at their rear to the front wall, and their bases rest on two beams laterally spanning the space between the knee panels. The single roadside rack is attached to the roadside wall and horizontal knee panel via elastic supports. A schematic of the rack arrangement is shown in Fig. 2.31, with dimensions shown to the neutral axes of structural member cross sections. Figures 2.32 and 2.33 show the grid points and numbering system for the racks.

As described in earlier discussions of equipment rack systems, the equipment support shelves and the equipment attached to the shelves combine to give a reasonably stiff horizontal plane, which may be assumed to translate and rotate as a rigid plane. Multipoint constraint relations (MPC) in NASTRAN are employed to impose the rigidity assumption




FIGURE 2.29. GRID POINT SYSTEM FOR AN/GRC-142B  
REAR AND CUPSIDE WALLS AND ROOF



TABLE 2.26

CBAR ELEMENT CONNECTIONS FOR THE  
AN/GRC-142B S-250 SHELTER

| CBAR | GRID POINT CONNECTIONS | NUMBER OF<br>ELEMENTS | LOCATION      |
|------|------------------------|-----------------------|---------------|
| a    | 2,7,12,17,26,22        | 5                     | ROADSIDE WALL |
|      | 3,8,13,18,27,23        | 5                     |               |
|      | 4,9,14,19,24           | 4                     |               |
|      | 57,174,60,63           | 3                     | CURBSIDE WALL |
|      | 56,173,59,62           | 3                     |               |
|      | 55,172,58,61           | 3                     |               |
|      | 22,67,64,63            | 3                     | ROOF          |
|      | 23,68,65,62            | 3                     |               |
|      | 24,69,66,61            | 3                     |               |
|      | 2,80,76                | 2                     | KNEE PANELS   |
|      | 3,81,77                | 2                     |               |
|      | 4,92,78                | 2                     |               |
|      | 72,57                  | 1                     |               |
|      | 73,56                  | 1                     |               |
|      | 74,82,55               | 2                     |               |
| b    | 48,51,54               | 2                     | CURBSIDE WALL |
| c    | 28,33,42               | 2                     | FRONT WALL    |
|      | 165,29,36,43           | 3                     |               |
|      | 30,39,44               | 2                     |               |
|      | 46,49,52               | 2                     | REAR WALL     |
|      | 47,50,53               | 2                     |               |
|      | 11,49,50,51            | 3                     |               |

TABLE 2.26 (CONT'D)

| CBAR | GRID POINT CONNECTIONS | NUMBER OF<br>ELEMENTS | LOCATION      |
|------|------------------------|-----------------------|---------------|
| h    | 1,2,3,4,71,5           | 5                     | ROADSIDE WALL |
|      | 54,63,62,61,45         | 4                     | CURBSIDE WALL |
|      | 21,52,53,54            | 3                     | ROOF          |
|      | 5,28                   | 1                     | KNEE PANEL    |
|      | 30,31                  | 1                     |               |
| i    | 21,22,23,24,25         | 4                     | ROADSIDE WALL |
|      | 48,57,56,55,70,31      | 5                     | CURBSIDE WALL |
|      | 25,42,43,44,45         | 4                     | ROOF          |
|      | 1,46                   | 1                     | KNEE PANEL    |
|      | 47,48                  | 1                     |               |
| j    | 1,6,11,16,21           | 4                     | ROADSIDE WALL |
|      | 31,171,41,45           | 3                     | CURBSIDE WALL |
| k    | 5,10,15,20,25          | 4                     | ROADSIDE WALL |
|      | 48,175,51,54           | 3                     | CURBSIDE WALL |
| l    | 21,52,53,54            | 3                     | ROOF          |
|      | 25,42,43,44,45         | 4                     |               |
|      | 1,46                   | 1                     | KNEE PANELS   |
|      | 47,48                  | 1                     |               |
|      | 5,28                   | 1                     |               |
|      | 30,31                  | 1                     |               |

TABLE 2.26 (CONCL'D)

| CBAR | GRID POINT CONNECTIONS | NUMBER OF<br>ELEMENTS | LOCATION    |
|------|------------------------|-----------------------|-------------|
| m    | 151,156                | 1                     | FLOOR       |
|      | 155,162,165,164,160    | 4                     |             |
| n    | 151,46                 | 1                     | KNEE PANELS |
|      | 155,28                 | 1                     |             |
|      | 156,47                 | 1                     |             |
|      | 160,30                 | 1                     |             |
| o    | 152,76                 | 1                     | KNEE PANELS |
|      | 153,77                 | 1                     |             |
|      | 154,78                 | 1                     |             |
|      | 157,72                 | 1                     |             |
|      | 158,73                 | 1                     |             |
|      | 159,74                 | 1                     |             |
|      | 152,157                | 1                     | FLOOR       |
|      | 153,180,158            | 2                     |             |
| p    | 154,161,163,159        | 3                     |             |
|      | 151,152,153,154,155    | 4                     | FLOOR       |
|      | 156,157,158,159,160    | 4                     |             |
|      | 46,76,77,78,28         | 4                     | KNEE PANELS |
|      | 47,72,73,74,30         |                       |             |




FIGURE 2.31. LOCATION OF THE AN/TRC-145 RACKS  
WITHIN THE S-250 SHELTER (TOP VIEW)






FIGURE 2.33. AN/TRC-145 RACK AGAINST ROADSIDE WALL

for each shelf. The vertical structural members are assumed to be flexible. Table 2.27 lists the properties of the CBAR beam elements employed in modeling the racks. Table 2.28 presents the CBAR element grid point connections for the identified cross-sections, and Table 2.29 shows the grid point pairs that were connected with MPC relations to model the rack-to-wall attachments.

The pieces of equipment supported by the racks are listed in Table 2.30 along with their masses and the grid points to which the masses are equally apportioned. Table 2.31 presents the mass breakdown of the AN/TRC-145 system. Additional miscellaneous equipment is housed within the shelter to result in a total mass of 975 kg for the entire AN/TRC-145 system (Ref. 2). This additional unspecified equipment mass of 257 kg, representing 26% of the total, was distributed as concentrated masses via CONM2 cards onto the walls, roof, and floor of the shelter, based on estimates of weight and distribution of equipment by inspection of photographs of the interior of the shelter given in Ref. 3. Table 2.32 shows the apportionment of masses to account for this weight deficiency. This arbitrary mass distribution may result in uncertainties in dynamic response analyses. In addition, the presence of pieces of equipment and the method of attachment to the structure may introduce changes in the structural stiffness levels, adding further uncertainties.

#### 2.2.3 AN/GRC-142B Racks

The AN/GRC-142 electronic equipment system employs a set of equipment racks located against the front wall of the S-250 shelter. The rack assembly is bolted at both sides to the roadside and curbside walls, and the base rests on the floor of the shelter. A schematic of the rack arrangement is shown in Fig. 2.34, with dimensions shown to the neutral axes of structural member cross sections. Figure 2.35 shows the grid points and numbering system for the rack assembly.

As the rack structure is composed of upright columns supporting horizontal beam elements which in turn support the equipment mounted on them, the assumption of rigid shelves (employed for the earlier models) is not valid. However, each piece of equipment bolted to the beam elements consists of a relatively rigid rectangular construction. Thus, it is assumed that the base of each piece of equipment provides a rigid plane between the attachment points, which are modeled to translate and rotate as a rigid plane by using the multipoint constraint relations (MPC) in NASTRAN. The structural members are assumed to be flexible. Table 2.33 lists the properties of the CBAR beam elements employed in modeling the racks. Table 2.34 presents the CBAR element grid point connections for the identified cross sections, and Table 2.35 shows the grid point pairs that were connected with MPC relations to model the rack-to-wall or rack-to-floor attachments.

Reference 3. Radio Terminal Sets AN/TRC-145(V) 1, AN/TRC-145(V)2, AN/TRC-145(V)3, AN/TRC-145A(V)2, AN/TRC-145A(V)2, and AN/TRC-145A(V)3 (FSN 5895-791-3365), Department of the Army Technical Manual TM 11-5895-453-14, January 1973.

TABLE 2.27

PROPERTIES OF AN/TRC-145 RACK BEAM ELEMENT

| CBAR                                                                                 | $I_{zz}$<br>(cm <sup>4</sup> ) | $I_{yy}$<br>(cm <sup>4</sup> ) | $I_{yz}$<br>(cm <sup>4</sup> ) | J<br>(cm <sup>4</sup> ) | A<br>(mm <sup>2</sup> ) | COMMENT         |
|--------------------------------------------------------------------------------------|--------------------------------|--------------------------------|--------------------------------|-------------------------|-------------------------|-----------------|
| AA  | 2.37                           | 2.37                           | 0.00                           | 3.49                    | 282                     | (1x1x 1/8 TUBE) |

TABLE 2.28

## CBAR ELEMENT CONNECTIONS FOR AN/TRC-145 RACKS

| CBAR | GRID POINT CONNECTIONS | NUMBER OF<br>ELEMENTS | LOCATION               |
|------|------------------------|-----------------------|------------------------|
| AA   | 95,99,103,107,111      | 4                     | ROADSIDE RACK          |
|      | 96,100,104,108,112     | 4                     |                        |
|      | 97,101,105,109,113     | 4                     |                        |
|      | 94,98,102,106,110      | 4                     |                        |
|      | 87,116,120,124         | 4                     | FRONT/CENTER<br>RACK   |
|      | 89,117,121,125         | 4                     |                        |
|      | 88,114,118,122         | 4                     |                        |
|      | 86,115,119,123         | 4                     |                        |
|      | 91,126,130,134         | 4                     | FRONT/ROADSIDE<br>RACK |
|      | 93,127,131,135         | 4                     |                        |
|      | 92,128,132,136         | 4                     |                        |
|      | 90,129,133,137         | 4                     |                        |
|      | 83,138,142,146         | 4                     | FRONT/CURBSIDE<br>RACK |
|      | 85,139,143,147         | 4                     |                        |
|      | 84,140,144,148         | 4                     |                        |
|      | 82,141,145,149         | 4                     |                        |

TABLE 2.29

CONSTRAINT CONNECTIONS BETWEEN  
AN/TRC-145 RACKS AND S-250 SHELTER

| RACK<br>GRID POINT                                                                                                                                                            | SHELTER<br>GRID POINT | RACK<br>GRID POINT | SHELTER<br>GRID POINT |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--------------------|-----------------------|
| 113*                                                                                                                                                                          | 26                    | 135                | 32                    |
| 112*                                                                                                                                                                          | 27                    | 134                | 34                    |
| 97**                                                                                                                                                                          | 80                    | 125                | 35                    |
| 96**                                                                                                                                                                          | 81                    | 124                | 37                    |
| 95**                                                                                                                                                                          | 77                    | 147                | 38                    |
| 94                                                                                                                                                                            | 76                    | 146                | 40                    |
| * CONSTRAINED IN DIRECTIONS<br>2 AND 3 ONLY. ELASTIC<br>CONNECTION IN DIRECTION 1.<br><br>** CONSTRAINED IN DIRECTIONS<br>1 AND 2 ONLY. ELASTIC<br>CONNECTION IN DIRECTION 3. |                       | 82                 | }                     |
|                                                                                                                                                                               |                       | 83                 |                       |
|                                                                                                                                                                               |                       | 84                 |                       |
|                                                                                                                                                                               |                       | 85                 |                       |
|                                                                                                                                                                               |                       | 86                 | }                     |
|                                                                                                                                                                               |                       | 87                 |                       |
|                                                                                                                                                                               |                       | 88                 |                       |
|                                                                                                                                                                               |                       | 89                 |                       |
|                                                                                                                                                                               |                       | 90                 | }                     |
|                                                                                                                                                                               |                       | 91                 |                       |
|                                                                                                                                                                               |                       | 92                 |                       |
|                                                                                                                                                                               |                       | 93                 |                       |
|                                                                                                                                                                               |                       |                    |                       |
|                                                                                                                                                                               |                       |                    |                       |
|                                                                                                                                                                               |                       |                    |                       |

TABLE 2.30  
EQUIPMENT MASSES FOR AN/TRC-145 SYSTEM

| EQUIPMENT         | MASS<br>(kg) | GRID POINT SUPPORTS | LOCATION               |
|-------------------|--------------|---------------------|------------------------|
| CV-1548/G         | 24.49        | 94,95,96,97         | ROADSIDE RACK          |
| CV-1548/G         | 24.49        | 98,99,100,101       |                        |
| TD-660A/G         | 22.23        | 102,103,104,105     |                        |
| TD-660A/G         | 22.23        | 106,107,108,109     |                        |
| TD-204            | 25.40        | 86,87,88,89         | FRONT/CENTER<br>RACK   |
| TD-204            | 25.40        | 114,115,116,117     |                        |
| CARD STORAGE      | 9.07 (EST)   | 118,119,120,121     |                        |
| PATCH PANEL       | 9.07 (EST)   | 122,123,124,125     |                        |
| T-983(P)          | 19.28 }      | 126,127,128,129     | FRONT/ROADSIDE<br>RACK |
| AM-4320           | 9.43 }       |                     |                        |
| R-1329(P)         | 16.33 }      | 130,131,132,133     |                        |
| AM-4316           | 12.70 }      |                     |                        |
| RT-773            | 3.45         | 134,135,136,137     |                        |
| DA-437/GRC-103(V) | 9.07 (EST)   | 134,135,136,137     |                        |
| T-983(P)          | 19.28 }      | 138,139,140,141     | FRONT/CURBSIDE<br>RACK |
| AM-4320           | 9.43 }       |                     |                        |
| R-1329(P)         | 16.33 }      | 142,143,144,145     |                        |
| AM-4316           | 12.70 }      | 146,147,148,149     |                        |
| RT-773            | 3.45         | 146,147,148,149     |                        |
| DA-437/GRC-103(V) | 9.07 (EST)   | 146,147,148,149     |                        |
| TOTAL             | 303          |                     |                        |

TOTAL MASS OF ROADSIDE RACK FRAME AND SUPPORTED EQUIPMENT = 109 kg

TOTAL MASS OF FRONT RACK FRAMES AND SUPPORTED EQUIPMENT = 264 kg

TABLE 2.31

## MASS BREAKDOWN OF AN/TRC-145 SYSTEM

| ITEM             | MASS<br>(Kg) |
|------------------|--------------|
| SHELTER          | 345          |
| ROADSIDE RACK    | 109          |
| FRONT RACKS      | 264          |
| TOTAL            | 718          |
| SYSTEM MASS      | 975          |
| UNSPECIFIED MASS | 257          |

TABLE 2.32

ASSUMED DISTRIBUTION OF UNSPECIFIED MASSES  
FOR AN/TRC-145 SYSTEM

| ITEM          | MASS DISTRIBUTION<br>(kg) |
|---------------|---------------------------|
| ROADSIDE WALL | 27                        |
| CURBSIDE WALL | 35                        |
| ROOF          | 23                        |
| FRONT WALL    | 23                        |
| REAR WALL     | 36                        |
| FLOOR         | 113                       |
| TOTAL         | 257                       |

AD-A085 759

KAMAN AVIDYNE BURLINGTON MA

F/G 17/2

STRUCTURAL MODELING AND RESPONSE OF COMMAND, CONTROL AND COMMUN--ETC(U)

MAR 80 J M CALLIGRISOS, J P WALSH

DAAD05-74-C-0744

UNCLASSIFIED


KA-TK-151


ARBRL-CR-00421

NL

2 of 3

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A




FIGURE 2.34. LOCATION OF THE AN/GRC-142B RACKS  
WITHIN THE S-250 SHELTER (TOP VIEW)




FIGURE 2.35. GRID POINT SYSTEM FOR AN/GRC-142B RACKS

TABLE 2.33

## PROPERTIES OF AN/GRC-142B RACK BEAM ELEMENT

| CBAR |    | $I_{zz}$<br>(cm <sup>4</sup> ) | $I_{yy}$<br>(cm <sup>4</sup> ) | $I_{yz}$<br>(cm <sup>4</sup> ) | J<br>(cm <sup>4</sup> ) | $K_z$ | $K_y$ | A<br>(mm <sup>2</sup> ) | ECOM<br>DRAWING<br>NUMBER |
|------|-------------------------------------------------------------------------------------|--------------------------------|--------------------------------|--------------------------------|-------------------------|-------|-------|-------------------------|---------------------------|
| A    |    | 17.69                          | 26.54                          | 0.00                           | 0.512                   | 0.719 | 0.281 | 674.8                   | SM-B-603201               |
| B    |    | 5.10                           | 8.25                           | 0.00                           | 0.112                   | 0.706 | 0.294 | 342.6                   | SM-D-613209               |
| C    |    | 88.72                          | 6.20                           | 0.00                           | 0.554                   | 0.530 | 0.470 | 685.8                   | SM-C-613203               |
| D    |    | 56.42                          | 115.29                         | 47.71                          | 1.465                   | 0.408 | 0.592 | 1089.0                  | SM-C-685242               |
| E    |    | 56.42                          | 115.29                         | -47.71                         | 1.465                   | 0.408 | 0.592 | 1089.0                  | SM-C-685242               |
| F    |   | 37.33                          | 59.14                          | -27.61                         | 2.185                   | 0.422 | 0.578 | 1044.5                  | SM-C-685228               |
| G    |  | 37.33                          | 59.14                          | 27.61                          | 2.185                   | 0.422 | 0.578 | 1044.5                  | SM-C-685228               |
| H    |  | 5.01                           | 10.34                          | -4.22                          | 0.304                   | 0.396 | 0.604 | 401.9                   | SM-D-613191               |
| I    |  | 5.01                           | 10.34                          | 4.22                           | 0.304                   | 0.396 | 0.604 | 401.9                   | SM-D-613191               |

TABLE 2.34

## CBAR ELEMENT CONNECTIONS FOR AN/GRC-142B RACKS

| CBAR | GRID POINT CONNECTIONS | NUMBER OF ELEMENTS | LOCATION                         |
|------|------------------------|--------------------|----------------------------------|
| A    | 201,224,234,206        | 3                  | RACK BASE<br>AND TOP<br>CHANNELS |
|      | 211,226,236,216        | 3                  |                                  |
|      | 205,210                | 1                  |                                  |
|      | 215,220                | 1                  |                                  |
| B    | 201 - 205              | 4                  | RACK VERTICAL<br>CHANNELS        |
|      | 206 - 210              | 4                  |                                  |
|      | 211 - 220              | 4                  |                                  |
|      | 216 - 220              | 4                  |                                  |
| C    | 222,223,281,224,225, } | 9                  | RACK SHELF<br>BEAMS              |
|      | 285,226,227,289,228, } |                    |                                  |
|      | 232,233,282,234,235 }  | 9                  |                                  |
|      | 286,236,237,290,238 }  |                    |                                  |
|      | 242,243,283,244        | 3                  |                                  |
|      | 230,245,287,240        | 3                  |                                  |
|      | 246,247,291,248        | 3                  |                                  |
|      | 252,253,284,254        | 3                  |                                  |
|      | 250,255,288,260        | 3                  |                                  |
| D    | 204,209                | 1                  | LOWER SUPPORT<br>ANGLE           |
|      | 214,219                |                    |                                  |
| F    | 221,222,232,231        | 3                  | RACK WALL<br>SUPPORT             |
|      | 241,242,252,251        | 3                  |                                  |
| G    | 229,228,238,239        | 3                  |                                  |
|      | 249,248,258,259        | 3                  |                                  |
| H    | 203,244,254,208        | 3                  | RACK SHELF<br>SUPPORT<br>ANGLE   |
|      | 240,213,260,218        | 3                  |                                  |
| I    | 230,203,250,208        | 3                  |                                  |
|      | 213,246,256,218        | 3                  |                                  |

TABLE 2.35

CONSTRAINT CONNECTIONS BETWEEN  
AN/GRC-142B RACKS AND S-250 SHELTER

| RACK<br>GRID POINT | SHELTER<br>GRID POINT |
|--------------------|-----------------------|
| 205                | 161                   |
| 210                | 162                   |
| 215                | 163                   |
| 220                | 164                   |
| 221                | 14                    |
| 229                | 58                    |
| 231                | 15                    |
| 239                | 41                    |
| 241                | 9                     |
| 249                | 172                   |
| 251                | 10                    |
| 259                | 171                   |

The weight of the structural model totals 197 kg, a shortfall of 148 kg from the known 345 kg total weight of the shelter. To account for the weight of the door hardware, skids, trim angles, castings, fasteners, sealant, etc., the 148 lb weight was appropriately distributed with CONM2 concentrated mass cards onto adjacent grid points.

The equipment supported by the racks are listed in Table 2.36 along with their masses and the grid points to which the weights are equally apportioned, resulting in a total mass of 179 kg including the rack structural mass. Table 2.37 presents the mass breakdown of the AN/GRC-142B system. Additional miscellaneous equipment is housed within the shelter to result in a total mass of 862 kg for the entire AN/GRC-142B system (Ref. 4). This additional unspecified equipment mass of 308 kg, representing 36% of the total, was distributed as concentrated masses via CONM2 cards onto the walls, knee panels, and floor of the shelter, based on estimates of weight and distribution of equipment by inspection of photographs of the interior of the shelter. Table 2.38 shows the apportionment of masses to account for this equipment mass deficiency. Again, the arbitrary distribution of the shelter and equipment mass deficiencies may result in uncertainties in dynamic response analyses with its effect on the inertial and stiffness properties of the model.

#### 2.2.4 Summary of S-250 Shelter Models

A summary of the basic structural and mass elements used to construct each model, the constraint relations employed, and the resulting degrees-of-freedom are presented in Table 2.39. The degree of complexity depends on the detail in modeling the shelter and electronic equipment for the two systems, and the number of constraint relations employed to reduce the total degrees of freedom.

All grid points common with the assumed rigid base region of the shelter were related to a central point on the base via MPC cards to model the rigid body motion of the base, as in the S-280 models. Thus the base motion is described with the maximum possible six degree-of-freedom motion of the central point. For the mode shape and frequency analysis, that point is constrained from motion in six degrees-of-freedom with an SPC card. For the blast loading dynamic analysis runs, a base motion may be imposed on that central point, with appropriate changes in the single point constraints.

The mode shapes and frequencies were obtained for each system as an aid in validating the structural models. The first ten natural frequencies of the complete set, as obtained by the Givens Method in NASTRAN, are presented in Table 2.40.

Reference 4. Radio Teletypewriter Sets AN/GRC-142, AN/GRC-142A, AN/GRC-142B, AN/GRC-122, AN/GRC-122A and AN/GRC-122B,  
Department of the Army Technical Manual TM 11-5815-334-12,  
May 1970.

**TABLE 2.36**  
**EQUIPMENT MASSES FOR AN/TRC-145 SYSTEM**

| <b>EQUIPMENT</b> | <b>MASS<br/>(kg)</b> | <b>GRID POINT SUPPORTS</b> | <b>LOCATION</b> |
|------------------|----------------------|----------------------------|-----------------|
| AN/GRC 106       | 34.02                | 223,233,281,282            | RACK            |
| MD-522A/GRC      | 16.33                | 225,235,285,286            | RACK            |
| SA-1650/GRC      | 4.54                 | 225,235,285,286            | RACK            |
| J-2728/GRC-142   | 1.81                 | 227,237,289,290            | RACK            |
| SB-3358/GRC      | 4.54                 | 227,237,289,290            | RACK            |
| J-2728/GRC-142   | 1.81                 | 243,253,283,284            | RACK            |
| TT-98/FG         | 24.49                | 245,255,287,288            | RACK            |
| PP-4763*/GRC     | 56.70                | 247,257,291,292            | RACK            |
| C-434/GRC        | 2.72                 | 202                        | RACK            |
| <b>TOTAL</b>     | <b>147.0</b>         |                            |                 |

**TOTAL WEIGHT OF RACK FRAME AND SUPPORTED EQUIPMENT = 179 kg.**

TABLE 2.37

## MASS BREAKDOWN OF AN/GRC-142B SYSTEM

| ITEM              | MASS (kg) |
|-------------------|-----------|
| SHELTER           | 345       |
| RACKS             | 179       |
| TT-76A/GGC        | 21        |
| FSN 4520-912-3502 | 7         |
| TA-312/PT         | 2         |
| TOTAL             | 554       |
| SYSTEM MASS       | 862       |
| UNSPECIFIED MASS  | 308       |

TABLE 2.38  
ASSUMED DISTRIBUTION OF UNSPECIFIED MASSES  
FOR AN/GRC-142B EQUIPMENT

| EQUIPMENT                    | ASSUMED<br>MASS<br>(kg) | GRID POINT SUPPORTS                                      | LOCATION                |
|------------------------------|-------------------------|----------------------------------------------------------|-------------------------|
| SHELTER HEATER               | 36.29                   | 1,2,46,76                                                | KNEE PANEL              |
| STANDING WAVE<br>METER       | 13.61                   | 16,17                                                    | ROADSIDE<br>WALL        |
| TAPE ROLLS<br>AND INVERTER   | 13.61                   | 28,78,154,155,161,162                                    | KNEE PANEL<br>AND FLOOR |
| POWER/SIGNAL<br>ENTRANCE BOX | 9.07                    | 39,41,44,45                                              | FRONT WALL              |
| LIGHTS &<br>VENTILATOR       | 4.54                    | 58,59,61,62                                              | CURBSIDE<br>WALL,       |
| CLOCK                        | 3.63                    | 18,19                                                    | ROADSIDE<br>WALL        |
| LOCKERS AND<br>CONTENTS      | 136.07                  | 1-5;46,76,77,78,28;<br>47,72,73,74,30;48,57,<br>56,55,31 | KNEE PANELS             |
| EQUIPMENT ON<br>FLOOR        | 90.72                   | 151-160                                                  | FLOOR                   |
| TOTAL                        | 307.5                   |                                                          |                         |

TABLE 2.39

## SUMMARY OF AN/TRC-145 AND AN/GRC-142B SYSTEM MODELS

| ELEMENTS                            | AN/TRC-145 | AN/GRC-142B |
|-------------------------------------|------------|-------------|
| SPRING (CELAS2)                     | 6          |             |
| BEAM (CBAR)                         | 174        | 225         |
| PLATE (CQUAD1)                      | 59         | 79          |
| MASS (CONM2)                        | 138        | 126         |
| GRID POINTS (GRID)                  | 150        | 161         |
| SINGLE POINT CONSTRAINTS (SPC)      | 6          | 6           |
| MULTIPOINT CONSTRAINTS (MPC)        | 443        | 327         |
| OMITTED COORDINATES (OMIT)          | 304        | 425         |
| MAXIMUM POSSIBLE DEGREES OF FREEDOM | 900        | 966         |
| DYNAMIC DEGREES OF FREEDOM          | 147        | 208         |

MAXIMUM POSSIBLE DEGREES OF FREEDOM:

= 6 X NO. OF GRID POINTS

DYNAMIC DEGREES OF FREEDOM:

= MAXIMUM POSSIBLE D.O.F. - SPC - MPC - OMIT

TABLE 2.40  
NATURAL FREQUENCIES OF AN/TRC-145  
AND AN/GRC-142B SYSTEMS

| MODE | AN/TRC-145 | AN/GRC-142B |
|------|------------|-------------|
| 1    | 33.82      | 54.12       |
| 2    | 37.70      | 57.86       |
| 3    | 40.44      | 60.15       |
| 4    | 43.51      | 65.37       |
| 5    | 44.73      | 68.26       |
| 6    | 45.08      | 69.94       |
| 7    | 45.87      | 71.63       |
| 8    | 50.48      | 75.03       |
| 9    | 50.86      | 78.27       |
| 10   | 55.56      | 78.90       |


### 2.3 TRUCK DATA

The AN/TRC-117, AN/TRC-110 and the AN/TCC-61 systems are mounted on the M35A2 2½ ton truck (Fig. 2.36) and the AN/TRC-145 and the AN/GRC-142 systems are mounted on the M715 1½ ton truck (Fig. 2.37). The base motion excitation experienced by each truck-mounted shelter was found by exercising the TRUCK code. The TRUCK code calculates the nonlinear gross motions (accelerations and displacements) and possible overturning of a truck-shelter-rack system in response to a blast loading (see Ref. 5). The truck, shelter and racks may be treated as rigid masses in the code interconnected by springs and dampers representing their respective suspension systems. The S-280 and S-250 systems which were modeled however, do not have spring and damper connections between the racks, the shelter and the truck bed. Therefore, the racks and shelter were rigidly connected to the truck chassis in the truck model. However, the truck suspension system and the tire flexibility were modeled.

Table 2.41 presents the mass and inertia data for each truck and Table 2.42 presents similar data for the shelter systems. Data for Tables 2.41 and 2.42 were obtained from information furnished by BRL. Figure 2.38 presents a schematic of a typical truck model. The M35A2 has a double-axle bogey in the rear whereas the M715 has a single rear axle. In exercising the TRUCK code, the blast direction was taken as pointing into the x-axis (-x direction) of Fig. 2.38.

Data listings of the TRUCK code for the AN/TRC-117, AN/TRC-110, AN/TCC-61 and the AN/TRC-145 are given in Appendix A. These listings also include the spring-damper data for the truck suspensions. Ref. 5 should be consulted for identifying the various input quantities in the data listings.

Reference 5. Hobbs, N. P., et al, TRUCK - A Digital Computer Program for Calculating the Response of Army Vehicles to Blast Waves, Kaman AviDyne TR-136, March 1977.






TRUCK, CARGO:  
2 1/2 TON, 6 X 6  
M35A2

NOTE: DIMENSIONS IN INCHES

REFERENCE  
VEHICLE TAG NO  
WVW 8735522 - 2220677 1617  
WVW 8736581 - 2220677 1616

FIGURE 2.36. M35A2 2 1/2 TON TRUCK

NOTE  
ALL DIMENSIONS ARE WITH  
VEHICLE UNLOADED AND LEVEL



NOTE: DIMENSIONS IN INCHES

FIGURE 2.37. M715 CARGO TRUCK, 1 1/4 TON

TABLE 2.41

## TRUCK MASS AND INERTIA DATA

| TRUCK                         | M35A2<br>2 1/2 TON | M715<br>1 1/4 TON |
|-------------------------------|--------------------|-------------------|
| CHASSIS MASS (kg)             | 3406               | 1826              |
| $x_{cg}$ (m)                  | 0.0                | 0.0               |
| $y_{cg}$ (m)                  | .475               | .394              |
| $z_{cg}$ (m)                  | -1.65              | -1.40             |
| $I_{xx}$ (Mg-m <sup>2</sup> ) | 13.0               | 1.84              |
| $I_{yy}$ (Mg-m <sup>2</sup> ) | 13.5               | 1.84              |
| $I_{zz}$ (Mg-m <sup>2</sup> ) | 1.40               | .570              |
| $I_{yz}$ (Mg-m <sup>2</sup> ) | .171               | .028              |
| FRONT AXLE MASS (kg)          | 649                | 334               |
| $x_{cg}$ (m)                  | 0.0                | 0.0               |
| $y_{cg}$ (m)                  | .025               | 0.0               |
| $z_{cg}$ (m)                  | 0.0                | 0.0               |
| $I_{xx}$ (Mg-m <sup>2</sup> ) | .035               | 0                 |
| $I_{yy}$ (Mg-m <sup>2</sup> ) | .333               | .293              |
| $I_{zz}$ (Mg-m <sup>2</sup> ) | .321               | .293              |

TABLE 2.41 (CONT'D)  
TRUCK MASS AND INERTIA DATA

| TRUCK                                   | M35A2<br>2 1/2 TON | M715<br>1 1/4 TON |
|-----------------------------------------|--------------------|-------------------|
| FORWARD REAR AXLE MASS (kg)             | 785                | 334               |
| $x_{cg}$ (m)                            | 0.0                | 0.0               |
| $y_{cg}$ (m)                            | 0.0                | 0.0               |
| $z_{cg}$ (m)                            | -3.30              | -3.2              |
| $I_{xx}$ (Mg-m <sup>2</sup> )           | .011               | 0                 |
| $I_{yy}$ (Mg-m <sup>2</sup> )           | .382               | .312              |
| $I_{zz}$ (Mg-m <sup>2</sup> )           | .447               | .312              |
| AFT REAR AXLE MASS (Mg-m <sup>2</sup> ) | 785                |                   |
| $x_{cg}$ (m)                            | 0.0                |                   |
| $y_{cg}$ (m)                            | 0.0                |                   |
| $z_{cg}$ (m)                            | -4.52              |                   |
| $I_{xx}$ (Mg-m <sup>2</sup> )           | .011               |                   |
| $I_{yy}$ (Mg-m <sup>2</sup> )           | .382               |                   |
| $I_{zz}$ (Mg-m <sup>2</sup> )           | .447               |                   |

- NOTE: 1. Centroidal distances are given with respect to an axis system located at the center of the front axle.
2. Inertias are referred to local centroidal axes.

TABLE 2.42  
SHELTER-RACK MASS AND INERTIA DATA

| SYSTEM                                | AN/TRC-117 | AN/TRC-110 | AN/TCC-61 | AN/TCC-145 |
|---------------------------------------|------------|------------|-----------|------------|
| MASS (kg)                             | 2304       | 2336       | 2495      | 5.44       |
| $x_{cg}^*$ (m)                        | 0.0        | 0.0        | 0.0       | 0.0        |
| $y_{cg}$ (m)                          | .889       | .889       | .889      | .937       |
| $z_{cg}$ (m)                          | 0.0        | .152       | 0.0       | 4.94       |
| $I_{xy}^{**}$<br>(Mg-m <sup>2</sup> ) | 3.73       | 3.73       | 4.02      | .737       |
| $I_{yy}$ (Mg-m <sup>2</sup> )         | 4.52       | 4.52       | 4.87      | .880       |
| $I_{zz}$ (Mg-m <sup>2</sup> )         | 2.37       | 2.37       | 2.58      | .634       |

\* Measured from center of shelter floor at truck bed height.

\*\* With respect to centroidal axes of system.




FIGURE 2.38. MASS MODEL LAYOUT

## SECTION 3

### TRANSIENT RESPONSE

#### 3.1 INTRODUCTION

The acceleration time history responses of the S-280 and S-250 systems modeled in Section 2, with the exception of the AN/GRC-142B, were obtained for several overpressure levels experienced in the DICE THROW field test. A summary of the overpressure levels for each system is given in Table 3.1. Each system was subjected to the overpressure loading of the blast wave acting on the shelter and to the simultaneous effect of the base motion of the supporting truck. The yield of the DICE THROW charge was 600 tons of ANFO, corresponding to approximately a 4.2 TJ (1KT) nuclear yield.

Section 3.2 presents the responses of the S-280 systems, using the BAAL hydrodynamic code to predict the overpressure loading (Ref. 6). The responses of the S-250 systems are given in Section 3.3, using the SHELTR code to determine the overpressure loading. No comparisons are made between the predicted and measured responses in Sections 3.2 and 3.3. Instead, comparisons are made for two of these systems, the AN/TRC-117 and the AN/TRC-145, in Section 3.4, each at an overpressure level of 6.0 psi (41.4 kPa). For these comparisons, the overpressure model used in the TRUCK code was used for consistency to determine the blast loading.

#### 3.2 S-280 Systems

Acceleration time histories of the S-280 systems subjected simultaneously to the overpressure loading and to the corresponding base motion of the truck were obtained for the overpressure levels indicated in Table 3.1. The BAAL code, which was used to determine the overpressure models for this section of the report, is a three-dimensional transient hydrodynamic code developed by the Los Alamos Scientific Laboratory.

The overpressure time histories for the various overpressure levels indicated in Table 3.1 were obtained by scaling the output of a reference 5.0 psi (34.5 kPa) case of the BAAL code provided by BRL. Following BRL's recommendation for scaling, the estimated values for the overpressure-time history for an incident overpressure  $\Delta p_i$  in Table 3.1 were calculated by multiplying the corresponding overpressures of the 34.5 kPa reference case by the ratio

$$\frac{(\Delta p_r)_i}{(\Delta p_r)_{34.5}} \quad (3.1)$$

Reference 6. Lottero, R.E., Computational Predictions of Shock Diffraction Loading on an S-280 Electrical Equipment Shelter, BRL MR 2599, March 1976. (AD#A022804).

TABLE 3.1  
OVERPRESSURE LEVELS

| SYSTEM                | INCIDENT OVERPRESSURE $\Delta p_i$ |     | OVERPRESSURE MODEL |
|-----------------------|------------------------------------|-----|--------------------|
|                       | kPa                                | psi |                    |
| AN/TRC-117<br>(S-280) | 41.4                               | 6.0 | BAAL, TRUCK        |
| AN/TRC-110<br>(S-280) | 17.9                               | 2.6 | BAAL               |
|                       | 27.6                               | 4.0 | BAAL               |
| AN/TCC-61<br>(S-280)  | 19.3                               | 2.8 | BAAL               |
|                       | 32.4                               | 4.7 | BAAL               |
| AN/TRC-145<br>(S-250) | 50.3                               | 7.3 | SHELTR             |
|                       | 41.4                               | 6.0 | TRUCK              |
|                       | 34.5                               | 5.0 | SHELTR             |
|                       | 20.7                               | 3.0 | SHELTR             |

Note: Reference 34.5 kPa (5.0 psi) case of the BAAL code is used, and its output is appropriately scaled to obtain overpressure time histories for the indicated  $\Delta p_i$ .

where  $(\Delta p_r)_i$  and  $(\Delta p_r)_{34.5}$  are the theoretical one-dimensional reflected overpressures corresponding to the incident overpressure levels  $\Delta p_i$  and 34.5 kPa, respectively. Similarly, the estimated values for time for an incident overpressure  $\Delta p_i$  were calculated by multiplying the time for the 34.5 kPa case by

$$\frac{(V_s)_{34.5}}{(V_s)_i} \quad (3.2)$$

where  $(V_s)_{34.5}$  and  $(V_s)_i$  are the shock wave velocities corresponding to the incident overpressures of 34.5 kPa and  $(\Delta p)_i$ , respectively. The incident wave in the BAAL model consisted of a step profile. However, since the structural accelerations are of interest for a relatively short time period of approximately 30 msec or less, the use of a step wave instead of a decaying incident wave will have a very minor effect on the early-time structural response.

Some representative overpressure-time history plots obtained by scaling the reference 34.5 kPa case in the manner described above are shown in Figs. 3.1-3.10 for the S-280 shelter at 6.0 psi (41.3 kPa). Similar results would be obtained for the other (lower) overpressure levels in Table 3.1.

A loading preprocessor called NALO was developed to convert overpressure-time history data into force data at the loaded grid points of the exposed shelter surfaces in the form required by NASTRAN. The NALO program was used to first convert the overpressure output of the reference 34.5 kPa case from the original BAAL mesh system to the NASTRAN grid system for each loaded surface. The program then performed the overpressure and time scaling indicated in Eqs. 3.1 and 3.2 above, accounting for flow shielding provided by the truck (such as the sidegates, tailgates and cab), and automatically punched out the TLOAD1, TABLED1 and DAREA cards required by NASTRAN, all in one continuous mode. The end product was a set of loading (force) tables as a function of time for each loaded shelter grid point.

The base motion excitation was obtained by exercising the TRUCK code for each overpressure level indicated in Table 3.1 and printing out the accelerations at the center of the shelter floor. Since NASTRAN does not accept an acceleration input directly, the base motion was introduced by locating a large mass (many times greater than the total system mass) at the floor centroid in the NASTRAN model. A base-motion force was then determined by multiplying the base acceleration output from the TRUCK program by this large mass. This base-motion force (as a function of time) was then applied to the large mass located at the floor centroid in NASTRAN. Some typical base accelerations for the AN/TRC-117 system, and also the AN/TRC-145 system, obtained by the TRUCK code (using the data in Tables 2.41 and 2.42) are shown in Figs. 3.11-3.14. Since the gross mass data of the AN/TRC-110 and the AN/TCC-61 are




Figure 3.1. Overpressure Near Center of S-280 Roadside Wall




Figure 3.2. Overpressure on S-280 Roadside Wall  
Near Center of Vertical Edge




Figure 3.3. Overpressure on S-280 Roadside Wall  
Near Center of Roof Edge




FIGURE 3.4. OVERPRESSURE NEAR CENTER OF S-280 CURBSIDE WALL.




FIGURE 3.5. OVERPRESSURE ON S-280 CURBSIDE WALL  
NEAR CENTER OF VERTICAL EDGE




FIGURE 3.6. OVERPRESSURE ON S-280 CURBSIDE WALL  
NEAR CENTER OF ROOF EDGE




FIGURE 3.7 OVERPRESSURE NEAR CENTER OF S-280 ROOF




FIGURE 3.8. OVERPRESSURE ON S-280 ROOF NEAR CENTER OF INTERSECTION WITH FRONT END WALL




FIGURE 3.9. OVERPRESSURE ON S-280 ROOF NEAR  
CENTER OF ROADSIDE EDGE




FIGURE 3.10. OVERPRESSURE NEAR CENTER OF S-280  
FRONT END WALL




FIGURE 3.11. TRANSLATIONAL ACCELERATIONS OF AN/TRC-117 SYSTEM AT FLOOR CENTER (BASE MOTIONS)




FIGURE 3.12. ANGULAR ACCELERATIONS OF AN/TRC-117 SYSTEM  
(BASE MOTIONS)




FIGURE 3.13. TRANSLATIONAL ACCELERATION OF AN/TRC-145 SYSTEM AT FLOOR CENTER (BASE MOTIONS)




FIGURE 3.14. ANGULAR ACCELERATIONS OF AN/TRC SYSTEM  
(BASE MOTIONS)

similar to the AN/TRC-117 system, their base responses will also be similar to the responses shown in Figs. 3.11 and 3.12. Only the base excitation in the blast direction was input to the NASTRAN models for each system since it was felt that it was the most important base motion response, possibly along with the roll acceleration, during the early-time structural response period of 30 msec.

The acceleration time histories of the three S-280 systems as obtained by NASTRAN are shown in Figs. 3.15-3.47 at several selected grid points on each shelter wall and also at grid points on the racks nearest the locations where accelerometers were mounted for the DICE THROW test. The corresponding base acceleration in the blast direction is given in Figs. 3.25, 3.36 and 3.47. Tables 3.2 and 3.3 may be referred to for gage designations and the approximate grid-point correspondence. In Figures 3.15-3.25, the responses for the AN/TRC-117 are also presented for the case where no base motion was applied to the system, i.e., the shelter base was constrained against all motion. It is seen that the inclusion of the base motion is generally unimportant during the early-time structural response of the system. If the roll acceleration were as important as the acceleration in the blast direction, the combined effect if both base accelerations were included would still be minor in Figs. 3.15-3.25.

### 3.3 S-250 SYSTEMS

Overpressure-time histories from the BAAL code were not available for use with the S-250 shelter as they were for the S-280 systems. Therefore, the S-250 shelter loading was determined with the overpressure code SHELTR (option Method 1), which is described in Section 5 of Ref. 6. The preprocessor NALO was used with the SHELTR code to provide NASTRAN loading tables for the AN/TRC-145 in a manner similar to that used for the BAAL code. Figures 3.48-3.54 show the structural acceleration time histories for the AN/TRC-145 and also for the hardened AN/TRC-145 at an overpressure of 7.3 psi (50.3 kPa). Appendix B presents additional response plots for the AN/TRC-145 at overpressure levels of 34.5 kPa and 20.7 kPa.

### 3.4 COMPARISONS WITH TEST MEASUREMENTS

Two cases from Table 3.1 were selected for comparison with measured acceleration data from the DICE THROW test. These were the AN/TRC-117 and the AN/TRC-145, each at an overpressure level of 6.0 psi (41.4 kPa). For consistency, each system used the blast loading as determined by the overpressure model programmed in the TRUCK code. As with the other overpressure models, BAAL and SHELTR mentioned earlier, the preprocessor NALO was used with the TRUCK overpressure model to determine the NASTRAN grid-point loading tables for each system. Each system was also subjected to the base motion in the blast direction as determined by the TRUCK

Reference 7. Calligeros, John M., and Walsh, John P., Finite Element Modeling of Army Electronic Equipment Shelters Subjected to Blast Loading, BRL CR 281, Dec. 1975. (AD#B008904L)

GRID POINT 31

41.4 kPa (6.0 psi)

AN/TRC-117




FIGURE 3.15. ACCELERATION TIME HISTORY IN BLAST DIRECTION, NEAR CENTER OF ROADSIDE WALL (NASTRAN)

GRID POINT 71

41.4 kPa (6.0 psi)

AN/TRC-117




FIGURE 3.16. ACCELERATION TIME HISTORY, IN BLAST DIRECTION, NEAR CENTER OF CURBSIDE WALL (NASTRAN)

GRID POINT 95

41.4 kPa

AN/TRC-117




FIGURE 3.17. VERTICAL ACCELERATION TIME HISTORY, NEAR CENTER OF ROOF (NASTRAN)

GRID POINT 138

41.4 kPa (6.0 psi)

AN/TRC-117




FIGURE 3.18 ACCELERATION TIME HISTORY IN HORIZONTAL DIRECTION, END WALL (NASTRAN)

GRID POINT 326

41.4 kPa (6.0 psi)

AN/TRC-117




FIGURE 3.19. ACCELERATION TIME HISTORY IN BLAST DIRECTION, ROADSIDE RACK (NASTRAN)

GRID POINT 326

41.4 kPa (6.0 psi)

AN/TRC-117




FIGURE 3.20. VERTICAL ACCELERATION TIME HISTORY,  
ROADSIDE RACK (NASTRAN)

GRID POINT 314

41.4 kPa (6.0 psi)

AN/TRC-117




FIGURE 3.21. ACCELERATION TIME HISTORY IN BLAST DIRECTION, ROADSIDE RACK (NASTRAN)

GRID POINT 314

41.4 kPa (6.0 psi)

AN/TRC-117




FIGURE 3.22. VERTICAL ACCELERATION TIME HISTORY  
ROADSIDE RACK (NASTRAN)

GRID POINT 417

41.4 kPa (6.0 psi)

AN/TRC-117




FIGURE 3.23. ACCELERATION TIME HISTORY IN BLAST DIRECTION, FRONT END RACK (NASTRAN)




FIGURE 3.24. VERTICAL ACCELERATION TIME HISTORY,  
FRONT END RACK (NASTRAN)

GRID POINT 7777

41.4 kPa (6.0 psi)

AN/TRC-117




FIGURE 3.25. RIGID BODY ACCELERATION TIME HISTORY IN  
BLAST DIRECTION, CENTER OF FLOOR (NASTRAN)




FIGURE 3.26. ACCELERATION TIME HISTORY IN BLAST DIRECTION,  
NEAR CENTER OF ROADSIDE WALL (NASTRAN)

GRID POINT 71

\_\_\_\_\_ 27.6 kPa (4.0 psi)

..... 17.9 kPa (2.6 psi)

AN/TRC-110




FIGURE 3.27 ACCELERATION TIME HISTORY IN BLAST DIRECTION,  
NEAR CENTER OF CURBSIDE WALL (NASTRAN)




FIGURE 3.28 VERTICAL ACCELERATION TIME HISTORY,  
NEAR CENTER OF ROOF (NASTRAN)

GRID POINT 138

———— 27.6 kPa (4.0 psi)

..... 18.9 kPa (2.6 psi)

AN/TRC-110




FIGURE 3.29 ACCELERATION TIME HISTORY IN HORIZONTAL DIRECTION, END WALL (NASTRAN)




FIGURE 3.30 ACCELERATION TIME HISTORY IN BLAST DIRECTION,  
FRONT END RACK (NASTRAN)




FIGURE 3.31. VERTICAL ACCELERATION TIME HISTORY,  
FRONT END RACKS (NASTRAN)




FIGURE 3.32. ACCELERATION TIME HISTORY IN BLAST DIRECTION, FRONT END RACK (NASTRAN)




FIGURE 3.33. VERTICAL ACCELERATION TIME HISTORY,  
FRONT END RACK (NASTRAN)




FIGURE 3.34. ACCELERATION TIME HISTORY IN BLAST DIRECTION, FRONT END RACK (NASTRAN)




FIGURE 3.35. VERTICAL ACCELERATION TIME HISTORY,  
FRONT END RACK (NASTRAN)




FIGURE 3.36 RIGID BODY ACCELERATION TIME HISTORY IN  
BLAST DIRECTION, CENTER OF FLOOR (NASTRAN)




FIGURE 3.37. ACCELERATION TIME HISTORY IN BLAST DIRECTION,  
NEAR CENTER OF ROADSIDE WALL (NASTRAN)




FIGURE 3.38 VERTICAL ACCELERATION TIME HISTORY,  
NEAR CENTER OF CURBSIDE WALL (NASTRAN)




FIGURE 3.39. VERTICAL ACCELERATION TIME HISTORY,  
NEAR CENTER OF ROOF (NASTRAN)




FIGURE 3.40. ACCELERATION TIME HISTORY IN HORIZONTAL DIRECTION, END WALL (NASTRAN)




FIGURE 3.41. ACCELERATION TIME HISTORY IN BLAST DIRECTION,  
ROADSIDE RACK (NASTRAN)




FIGURE 3.42. VERTICAL ACCELERATION TIME HISTORY,  
ROADSIDE RACK (NASTRAN)




FIGURE 3.43. ACCELERATION TIME HISTORY IN BLAST DIRECTION, ROADSIDE RACK (NASTRAN)

GRID POINT 425

----- 32.4 kPa (4.7 psi)

..... 19.3 kPa (2.8 psi)

AN/TCC-61




FIGURE 3.44. VERTICAL ACCELERATION TIME HISTORY,  
ROADSIDE RACK (NASTRAN)




FIGURE 3.45. VERTICAL ACCELERATION TIME HISTORY,  
CURBSIDE RACK (NASTRAN)




FIGURE 3.46. ACCELERATION TIME HISTORY IN BLAST DIRECTION, CURBSIDE RACK (XASTRAN)




FIGURE 3.47 ACCELERATION TIME HISTORY IN BLAST  
DIRECTION, CENTER OF FLOOR (NASTRAN)

TABLE 3.2  
ACCELEROMETER LOCATIONS FOR S-280 SHELTER SYSTEMS

| SYSTEM     | NEAREST<br>GRID POINT | GAGE DESIGNATION | LOCATION           |
|------------|-----------------------|------------------|--------------------|
| AN/TRC-117 | 326                   | 02/1H*<br>02/1V  | Roadside<br>Racks  |
|            | 314                   | 02/2H<br>02/2V   | Roadside<br>Racks  |
|            | 417                   | 02/4H<br>02/4V   | Front End<br>Racks |
|            | 7777                  | 02/3H<br>02/3V   | Floor              |
| AN/TRC-110 | 228                   | 04/4H<br>04/4V   | Front End<br>Racks |
|            | 241                   | 04/1H<br>04/1V   | Front End<br>Racks |
|            | 244                   | 04/2V<br>04/2H   | Front End<br>Racks |
|            | 7777                  | 04/3V<br>04/3H   | Floor              |
| AN/TCC-61  | 413                   | 08/1H<br>08/1V   | Roadside<br>Rack   |
|            | 425                   | 08/2H<br>08/2V   | Roadside<br>Rack   |
|            | 3140                  | 08/4H<br>08/4V   | Curbside<br>Rack   |
|            | 7777                  | 08/3H<br>08/3V   | Floor              |

\* H denotes blast direction  
V denotes vertical direction

TABLE 3.3  
ACCELEROMETER LOCATIONS  
FOR S-250 SHELTER SYSTEM

| SYSTEM     | NEAREST GRID POINT | GAGE DESIGNATION    | LOCATION          |
|------------|--------------------|---------------------|-------------------|
| AN/TRC-145 | 111                | 01/1H*<br>01/1V     | Roadside<br>Rack  |
|            | 103                | 01/2H<br>01/2V      | Roadside<br>Rack  |
|            | 122                | 01/4H (NA)<br>01/4V | Front End<br>Rack |
|            | 150                | 01/3H<br>01/3V      | Floor             |

\* H denotes blast direction  
V denotes vertical direction

GRID POINT 13

50.3 kPa (7.3 psi)

AN/TRC-145




FIGURE 3.48. ACCELERATION TIME HISTORY IN BLAST DIRECTION,  
NEAR CENTER OF ROADSIDE WALL (NASTRAN)

GRID POINT 103

50.3 kPa (7.3 psi)

AN/TRC-145




FIGURE 3.49. ACCELERATION TIME HISTORY IN BLAST DIRECTION, ROADSIDE RACK (NASTRAN)

GRID POINT 103

50.3 kPa (7.3 psi)

AN/TRC-145




FIGURE 3.50. VERTICAL ACCELERATION TIME HISTORY,  
ROADSIDE RACK (NASTRAN)

GRID POINT 111

50.3 kPa (7.3 psi)

AN/TRC-145




FIGURE 3.51. ACCELERATION TIME HISTORY IN BLAST DIRECTION, ROADSIDE RACK (NASTRAN)

GRID POINT 111

50.3 kPa (7.3 psi)

AN/IRC-145




FIGURE 3.52. VERTICAL ACCELERATION TIME HISTORY,  
ROADSIDE RACK (NASTRAN)

GRID POINT 122

50.3 kPa (7.3 psi)

AN/TRC-145




FIGURE 3.53. ACCELERATION TIME HISTORY IN BLAST DIRECTION, FRONT WALL RACK (NASTRAN)

GRID POINT 122

50.3 kPa (7.3 psi)

AN/TRC-145




FIGURE 3.54. VERTICAL ACCELERATION TIME HISTORY,  
FRONT WALL RACK (NASTRAN)

code, i.e., the force in the blast direction shown in Fig. 3.11 for the AN/TRC-117 and in Fig. 3.13 for the AN/TRC-145.

Representative overpressure time histories at the overpressure level of 41.4 kPa are given for the S-280 shelter in Figs. 3.55-3.58, and for the S-250 shelter in Figs. 3.59-3.62 using the TRUCK code overpressure model. The overpressure plots for the S-250 shelter also include predictions from the SHELTR code for comparison.

Biaxial accelerometers were located at three points on the rack frames and also at the center of the floor for each system (see Tables 3.2 and 3.3 for gage locations). Generally, the available measured data extended out to a duration between 60 and 100 msec. These data were reprocessed to obtain shorter duration plots ranging from 8 to 10 msec. No data were available for gages 02/2V and 01/4H, and short duration plots were not available for gages 02/2H, 02/4H, 01/2H, 01/4V and 01/3H. In addition to acceleration time histories, maxi-max shock spectra\* of the measured acceleration time histories were available for a limited number of gages, i.e., 01/1H, 01/1V, 01/2H, 01/2V, 02/1H, 02/3H, and 02/4V.

The comparisons between the NASTRAN predictions and the measured data are given in Figures 3.63-3.86 for the AN/TRC-117 and in Figures 3.89-3.109 for the ANTRC-145. The order of presentation consists of first comparing the time histories for the shorter time duration, followed by a plot of the long duration experimental response and then by a 30 msec plot of the NASTRAN response for each gage. In several cases it was not possible to overlap the analytical and test responses because of significant differences in the amplitude scale, and the plots were kept separate. The final set of plots for each system consists of an overlaid comparison of the limited experimental shock spectra data. A complete set of NASTRAN shock spectra is presented, however.

Figures 3.63-3.71 show the accelerations at the two gages located on one of the roadside racks of the AN/TRC-117, and Figures 3.72-3.76 show the accelerations at the gage located on the front end rack. Generally, the peak measured accelerations at these stations are significantly greater than the corresponding analytical responses. In addition, the frequency content of the measured responses is higher than the frequency of the analytical responses. Table 3.4 presents the approximate dominant frequency, as can best be determined from the response plots, and the ratio of the measured peak acceleration to the predicted peak acceleration for each gage. It may be noted that except for gage 02/1V, the frequencies of the measured rack responses are 1500 Hz or greater, whereas the frequencies of the predicted responses are generally less than 500 Hz, except for gage 02/2V. The best comparison on peak accelerations is at gage 02/1H where the measured response is twice as big as the predicted response. The worst comparison is at gage 02/1V (same location but in the vertical direction) where the measured response is 30 times greater than the predicted response.

\*The Maxi-Max shock spectrum is the maximum absolute acceleration experienced by a single degree of freedom oscillator as a function of its own natural frequency in response to a shock or vibration input.




FIGURE 3.55. OVERPRESSURE ON S-280 ROADSIDE WALL




FIGURE 3.56. OVERPRESSURE ON S-280 CURBSIDE WALL




FIGURE 3.57. OVERPRESSURE ON 5-280 ROOF




FIGURE 3.58. OVERPRESSURE ON S-280 FRONT END WALL




FIGURE 3.59. OVERPRESSURE ON S-250 ROADSIDE WALL




FIGURE 3.60. OVERPRESSURE ON S-250 CUPBSIDE WALL




FIGURE 3.61. OVERPRESSURE ON S-250 ROOF




FIGURE 3.62. OVERPRESSURE ON S-250 END WALL




FIGURE 3.63. COMPARISON OF ACCELERATION TIME HISTORIES IN BLAST DIRECTION, ROADSIDE RACK




FIGURE 3.64. MEASURED ACCELERATION TIME HISTORY IN HORIZONTAL DIRECTION, ROADSIDE RACK

GRID POINT 326

AN/TRC-117

02/1H

41.4 kPa (6.0 psi)




FIGURE 3.65. ACCELERATION TIME HISTORY IN BLAST DIRECTION, ROADSIDE RACK (NASTRAN)




FIGURE 3.66. MEASURED VERTICAL ACCELERATION TIME HISTORY, ROADSIDE RACK




FIGURE 3.67. MEASURED VERTICAL ACCELERATION TIME HISTORY, ROADSIDE RACK

GRID POINT 326

AN/TRC-117

02/1V




FIGURE 3.68. VERTICAL ACCELERATION TIME HISTORY,  
ROADSIDE RACK (NASTRAN)




FIGURE 3.69. MEASURED ACCELERATION TIME HISTORY IN BLAST DIRECTION, ROADSIDE RACK

GRID POINT 314

AN/TRC-117

02/2H





FIGURE 3.70. ACCELERATION TIME HISTORY IN BLAST DIRECTION, ROADSIDE RACK (XASTRAN)

GRID POINT 314

AN FRC-117

01.24

41.4 KPa (6.0 psi)



RECORDING OF SEISMIC ACTIVITY AT GRID POINT 314, AN FRC-117, 01.24, 41.4 KPa (6.0 psi)

AD-A085 759

KAMAN AVIDYNE BURLINGTON MA

F/G 17/2

STRUCTURAL MODELING AND RESPONSE OF COMMAND, CONTROL AND COMMUN--ETC(U)

MAR 80 J M CALLIGEROS, J P WALSH

DAAD05-74-C-0744

UNCLASSIFIED

KA-TR-151

ARBRL-CR-00421

NL

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3

3 3


3 3

END

DATE

7-80

DTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A




FIGURE 3.72. MEASURED ACCELERATION TIME HISTORY IN BLAST DIRECTION, FRONT END RACKS

GRID POINT 417

AN/TRC-117

02/4H




FIGURE 3.73. ACCELERATION TIME HISTORY IN BLAST DIRECTION, FRONT END RACK (NASTRAN)




FIGURE 3.74. COMPARISON OF VERTICAL ACCELERATION TIME HISTORIES, FRONT END RACK




FIGURE 3.75. MEASURED VERTICAL ACCELERATION TIME HISTORY, FRONT END RACK

GRID POINT 417

AN/TRC-117

02/4V

41.4 kPa (6.0 psi)




FIGURE 3.76. VERTICAL ACCELERATION TIME HISTORY,  
FRONT END RACK (NASTRAN)




FIGURE 3.77. MEASURED ACCELERATION TIME HISTORY IN BLAST DIRECTION, CENTER OF FLOOR




FIGURE 3.78. MEASURED ACCELERATION TIME HISTORY IN BLAST DIRECTION, CENTER OF FLOOR

GRID POINT 7777

AN/TRC-117

02/3H

41.4 kPa (6.0 psi)

RIGID BODY




FIGURE 3.79. ACCELERATION TIME HISTORY IN BLAST DIRECTION, CENTER OF FLOOR (NASTRAN)




FIGURE 3.80. COMPARISON OF SHOCK SPECTRA BASED ON MEASURED AND ANALYTICAL ACCELERATION TIME HISTORIES IN BLAST DIRECTION, ROADSIDE RACK




FIGURE 3.81. SHOCK SPECTRUM BASED ON ANALYTICAL VERTICAL ACCELERATION  
TIME HISTORY, ROADSIDE RACK (NASTRAN)




FIGURE 3.82. SHOCK SPECTRUM BASED ON ANALYTICAL ACCELERATION TIME HISTORY  
IN BLAST DIRECTION, ROADSIDE RACK (NASTRAN)




FIGURE 3.83. SHOCK SPECTRUM BASED ON ANALYTICAL VERTICAL TIME HISTORY,  
ROADSIDE RACK (NASTRAN)




FIGURE 3.84. SHOCK SPECTRUM BASED ON ANALYTICAL ACCELERATION TIME HISTORY  
IN BLAST DIRECTION, FRONT END RACK (NASTRAN)




FIGURE 3.85. COMPARISON OF SHOCK SPECTRA BASED ON MEASURED AND ANALYTICAL VERTICAL ACCELERATION TIME HISTORY, FRONT END RACK




FIGURE 3.86. COMPARISON OF SHOCK SPECTRA BASED ON MEASURED AND ANALYTICAL ACCELERATION TIME HISTORIES IN BLAST DIRECTION, CENTER OF FLOOR

TABLE 3.4  
FREQUENCY CONTENT AND ACCELERATIONS OF MEASURED  
AND PREDICTED RESPONSES FOR THE AN/TRC-117

| GAGE  | APPROXIMATE DOMINANT FREQUENCY (Hz) |            | ACCELERATION<br>AMPLITUDE RATIO |
|-------|-------------------------------------|------------|---------------------------------|
|       | MEASURED                            | PREDICTED  | MEASURED/PREDICTED              |
| 02/1H | 2000                                | 170        | 2                               |
| 02/1V | 700                                 | 400        | 30                              |
| 02/2H | 2500                                | 120        | 11                              |
| 02/2V | -                                   | 1000       | -                               |
| 02/4H | 1500                                | 130        | 8                               |
| 02/4V | 1500                                | 500        | 6                               |
| 02/3H | 1000                                | rigid body | 5                               |

The higher frequency content of the measured data may be due to structural accelerations which are being sensed by the accelerometer gage at its mounting location. This is evidenced by gage 02/3H (Figures 3.77 and 3.78) which was installed for the purpose of measuring the rigid body acceleration of the center of the shelter floor. The high frequency content at gage 02/3H is not representative of a rigid body response but rather is characteristic of a response containing localized structural frequencies. The corresponding analytical rigid body response is shown in Figure 3.79, having a peak one fifth of the measured peak and decaying to nearly zero after 30 msec.

The complete set of shock spectra plots is given in Figures 3.80-3.86 for the AN/TRC-117. Comparisons are shown in Figures 3.80, 3.85 and 3.86, using the corresponding measured and analytical acceleration time histories in Figures 3.63-3.76. The disparity noted earlier between the measured time-history data and the analytical predictions is also reflected in the shock spectra, i.e., the experimental shock spectra are significantly higher than the analytical predictions over most of the frequency range. The closest agreement is in the frequency range between 100 Hz and 300 Hz in Figure 3.80 and between 200 Hz and 700 Hz in Figure 3.85. The shock spectrum comparison in Figure 3.86 is meaningless because the floor accelerometer does not reflect realistically the rigid body response of the system.

The measured and predicted accelerations for the AN/TRC-145 are shown in Figures 3.87-3.97 for the two gages located on the roadside rack, and in Figures 3.98-3.100 for the gage located on the front end rack. A summary of the dominant frequency and acceleration amplitude ratio for each gage as determined from these plots is given in Table 3.5.

The comparison in peak acceleration between measured and predicted responses is much more favorable for the AN/TRC-145 than it was for the AN/TRC-117. As can be seen in Table 3.5, the greatest discrepancy occurs at gage 01/2V, where the measured peak acceleration is 1.8 times greater than the predicted value. Very good comparisons are seen for gages 01/1V and 01/2H. The measured frequencies, however, are significantly greater than the predicted frequencies, as was also the case for the AN/TRC-117. A good comparison in frequency is seen in Figure 3.87, however, at a level of 400 Hz. The measured response in that figure, though, also has a higher frequency of about 2200 Hz which is not present in the predicted curve. As in the case for the AN/TRC-117, the floor gage (01/3H, Figure 3.101) had a high frequency content characteristic of a local structural response rather than the rigid body response. The measured floor acceleration was four times greater than the predicted rigid body acceleration, consistent with the results for the AN/TRC-117.

The shock spectra for the AN/TRC-145 are shown in Figures 3.103-3.109 and comparisons are given in Figures 3.103-3.106. The shock spectra comparisons are generally more favorable for the AN/TRC-145 than they were for the AN/TRC-117 because of the better agreement of the acceleration time histories. This is apparent also at the higher frequencies (1000 Hz or greater). It should be noted that the AN/TRC-145 is inherently a stiffer structure and has higher structural frequencies than the AN/TRC-117 (See Tables 2.21 and 2.40), and this would contribute to a higher shock spectrum at the higher frequencies for the AN/TRC-145.

A post test examination of the shelters revealed that the AN/TRC-117 had received moderate to heavy damage to the roadside wall and moderate to light buckling of the remaining shelter walls. The racks along the roadside wall sustained heavy damage, with the rack upright members bowing outward toward the center. The roadside wall was in contact with the racks in many places. On the other hand, the AN/TRC-145, being a more compact shelter system, received very little damage. The damage to the exterior walls varied from light buckling to no visible damage and the racks appeared to suffer no damage at all.

The damage received by the AN/TRC-117 should thus be considered as a major factor for the poor comparison with analytical predictions. The AN/TRC-145, which had received very little damage, compared much better in the acceleration peaks. However, the measured acceleration time histories for both systems consistency had higher frequencies than the analytical predictions. It is suspected that the gages were sensing localized high frequency structural inputs, as was shown for the gages intended to sense the rigid body response. A lack of greater detail in the structural model would also result in lower frequencies in the analytical results. Increasing the structural modeling detail could result in higher frequencies, at the expense of longer computer running times and storage requirements.

### 3.5 RESPONSE OF AN/TRC-145 TO A 168 TJ (40 KT BLAST)

The response of the AN/TRC-145 had been found for a 4.2 TJ (1KT) blast at an incident overpressure of 41.4 kPa (6.0 psi). The results were shown in Figures 3.12-3.13 for the gross accelerations and in Figures 3.87-3.102 for the structural accelerations, using the overpressure model of the TRUCK code. It was of further interest to investigate the response of the system to a blast of a higher yield, 168 TJ (40 KT), while maintaining the same incident overpressure of 41.4 kPa. The effect of increasing the yield results in a larger positive phase duration and a more severe loading condition during the drag phase.

The roll angle responses obtained by the TRUCK code at the 168 TJ and 4.2 TJ yields, each at an incident overpressure of 41.4 kPa, are shown in Figure 3.110. It is seen that increasing the yield resulted in a significantly higher roll angle and subsequent overturning of the system due to the greater positive-phase drag forces. At the smaller yield, the roll angle peaked at 0.36 radians and no overturning resulted.

The NASTRAN model of the AN/TRC-145 was also exercised for the 4.2 TJ yield at 41.4 kPa after new loading tables were prepared using the TRUCK pressure model and the corresponding base motion. A comparison with the accelerations for the smaller yield at 41.4 kPa in Figures 3.87-3.102 showed that increasing the yield had generally no discernible effect on the structural accelerations of the walls and racks during the first 30 msec of response. This result is to be expected since increasing the yield has a minor effect on the early time diffractive loading during which the structural accelerations are excited.

GRID POINT 111

AN/TRC-145

01/1H

41.4 kPa (6.0 psi)




FIGURE 3.87. COMPARISON OF MEASURED AND ANALYTICAL ACCELERATION  
TIME HISTORIES IN BLAST DIRECTION, ROADSIDE RACK




FIGURE 3.88. MEASURED ACCELERATION TIME HISTORY IN BLAST DIRECTION,  
ROADSIDE RACK

GRID POINT 111

AN/TRC-145

01/1H

41.4 kPa (6.0 psi)




FIGURE 3.89. ANALYTICAL ACCELERATION TIME HISTORY IN BLAST DIRECTION, ROADSIDE RACK (NASTRAN)




FIGURE 3.90. COMPARISON OF MEASURED AND ANALYTICAL VERTICAL ACCELERATION  
TIME HISTORIES, ROADSIDE RACK




FIGURE 3.91. MEASURED VERTICAL ACCELERATION TIME HISTORY, ROADSIDE RACK

GRID POINT 111

AN/TRC-145

01/1V

41.4 kPa (6.0 psi)




FIGURE 3.92. ANALYTICAL ACCELERATION TIME HISTORY  
ROADSIDE RACK (NASTRAN)




FIGURE 3.93. MEASURED ACCELERATION TIME HISTORY IN  
BLAST DIRECTION, ROADSIDE RACK




FIGURE 3.94. ANALYTICAL ACCELERATION IN BLAST  
DIRECTION, ROADSIDE RACK (NASTRAN)




FIGURE 3.95. COMPARISON OF MEASURED AND ANALYTICAL VERTICAL ACCELERATION  
TIME HISTORIES, ROADSIDE RACK




FIGURE 3.96. MEASURED VERTICAL ACCELERATION TIME HISTORY, ROADSIDE RACK




FIGURE 3.97. ANALYTICAL VERTICAL ACCELERATION TIME HISTORY, ROADSIDE RACK (NASTRAN)

GRID POINT 122

AN/TRC-145

01/4H

41.4 kPa (6.0 psi)




FIGURE 3.98. ANALYTICAL ACCELERATION IN BLAST DIRECTION,  
FRONT END RACK (NASTRAN)




FIGURE 3.99. MEASURED VERTICAL ACCELERATION TIME HISTORY, FRONT END RACK

GRID POINT 122

AN/TRC-145

01/4V

41.4 kPa (6.0 psi)




FIGURE 3.100. ANALYTICAL VERTICAL ACCELERATION TIME HISTORY, FRONT END RACK (NASTRAN)




FIGURE 3.101. MEASURED ACCELERATION TIME HISTORY IN BLAST DIRECTION,  
CENTER OF FLOOR

GRID POINT 150

AN/TRC-145

01/3H

41.4 kPa (6.0 psi)




FIGURE 3.102. ANALYTICAL ACCELERATION TIME HISTORY  
IN BLAST DIRECTION, CENTER OF FLOOR (NASTRAN)




FIGURE 3.103. COMPARISON OF SHOCK SPECTRA BASED ON MEASURED AND ANALYTICAL ACCELERATION TIME HISTORIES IN BLAST DIRECTION, ROADSIDE RACK




FIGURE 3.104. COMPARISON OF SHOCK SPECTRA BASED ON MEASURED AND ANALYTICAL VERTICAL ACCELERATION  
TIME HISTORIES, ROADSIDE RACK




FIGURE 3.105. COMPARISON OF SHOCK SPECTRA BASED ON MEASURED AND ANALYTICAL ACCELERATION TIME HISTORIES IN THE BLAST DIRECTION, ROADSIDE RACK




FIGURE 3.106. COMPARISON OF SHOCK SPECTRA BASED ON MEASURED AND ANALYTICAL VERTICAL ACCELERATION TIME HISTORIES, ROADSIDE RACE




FIGURE 3.107. SHOCK SPECTRUM BASED ON ANALYTICAL ACCELERATION TIME HISTORY  
IN BLAST DIRECTION, FRONT END RACK (NASTRAN)




FIGURE 3.108. SHOCK SPECTRUM BASED ON ANALYTICAL VERTICAL ACCELERATION TIME HISTORY,  
FRONT END RACK (NASTRAN)




FIGURE 3.109. SHOCK SPECTRUM BASED ON ANALYTICAL ACCELERATION TIME HISTORY IN  
BLAST DIRECTION, CENTER OF FLOOR (NASTRAN)




FIGURE 3.110. ROLL ANGLE RESPONSE OF AN/TRC-145 TO INCREASED YIELD AT THE SAME INCIDENT OVERPRESSURE (TRUCK)

TABLE 3.5  
FREQUENCY CONTENT AND AMPLITUDE RATIO OF MEASURED  
AND PREDICTED RESPONSES FOR THE AN/TRC-145

| GAGE  | APPROXIMATE DOMINANT FREQUENCY (Hz) |            | ACCELERATION<br>AMPLITUDE RATIO |
|-------|-------------------------------------|------------|---------------------------------|
|       | TEST                                | NASTRAN    | MEASURED/PREDICTED              |
| 01/1H | 400                                 | 400 & 2200 | .5                              |
| 01/1V | 2000                                | 600        | 1.0                             |
| 01/2H | 1400                                | 67         | .80                             |
| 01/2V | 2500                                | 300        | 1.8                             |
| 01/4H | -                                   | 500        | -                               |
| 01/4V | 2000                                | 1200       | 1.4                             |
| 01/3H | 1000                                | rigid body | 4                               |

## SECTION 4

### SUMMARY AND MAJOR CONCLUSIONS

This report has presented a description of the finite element structural models of several Army command, control and communication shelter systems (C<sup>3</sup>) that were fielded in the recent DICE THROW test. The models were developed for the AN/TRC-117, AN/TRC-110 and the AN/TCC-61, which utilize the S-280 shelter, and for the AN/TRC-145 which utilizes the S-250 shelter. Various overpressure models were used to prepare loading tables for these systems, and base motion excitation was provided by the TRUCK code. Structural accelerations were determined with the NASTRAN code for several incident overpressure levels experienced in DICE THROW and comparisons with measured responses were made for two systems, the AN/TRC-117 and the AN/TRC-145. In addition to the above mentioned systems, a structural model of the AN/GRC-142B, which also utilizes the S-250 shelter, was developed but no responses were obtained.

The three S-280 systems differed from each other primarily with respect to the internal racks and equipment. This was also the case for the two S-250 systems. It was thus convenient to develop a single S-280 shelter structural model which could be used with the rack configurations of the AN/TRC-117, AN/TRC-110 and the AN/TCC-61. To some extent, a similar procedure was also used for the S-250 shelter model in conjunction with the racks of the AN/TRC-145 and the AN/GRC-142B. Since none of the systems modeled has mass or structural symmetry, it was necessary to model the entire shelter-rack-equipment structure without the benefit of symmetry for reducing the degrees-of-freedom.

The comparison of the measured and analytically determined rack accelerations for the AN/TRC-117 and AN/TRC-145 at an incident overpressure of 41.4 kPa (6.0 psi) revealed the following major conclusions:

1. The comparison for the AN/TRC-117 was poor, with regard to peak accelerations and frequency content. The measured peak accelerations and the frequency content of the measured data exceeded considerably the values for the analytical predictions. The best comparison indicated a factor of 2.0 between the measured and analytical acceleration peaks.
2. The comparison of peak accelerations for the AN/TRC-145 was much more favorable than for the AN/TRC-117. Acceleration peaks compared within a factor 0.5 to 2.0, and even matched closely for two gages. However, as in the case of the AN/TRC-117, the frequency content of the measured accelerations was in general considerably higher than the analytical frequencies.

3. It is suspected that the higher frequency content in the measured data may be due to localized structural frequencies near the gage mount. This is supported by the general high frequency character of the response sensed by the gage intended to pick up the rigid body accelerations for both shelter systems. On the other hand, the lower frequency content in the analytical response can be attributed to insufficient detail of the rack structural model near the gage mount.
4. The AN/TRC-117 racks had sustained considerable damage whereas the AN/TRC-145 racks appeared to suffer no damage. This is also a major consideration for the poor comparison in the AN/TRC-117 acceleration levels.
5. A major uncertainty in the modeling was the unknown distribution of a considerable portion of the total mass of each system. For the AN/TRC-117, for example, this portion represents 40% of the total mass.
6. The base motion does not appear to contribute meaningfully to the structural acceleration response of the shelter walls and equipment racks during the first 30 msec or so.
7. Increasing the yield while maintaining the overpressure constant, i.e., effectively increasing the drag phase loading without affecting the diffractive loading significantly, resulted in overturning of the AN/TRC-145 system but did not affect the early-time structural response.
8. The AN/TRC-145, by nature of its more compact design, appears to be less vulnerable to blast-induced structural damage than the larger, more flexible, S-280 systems.

APPENDIX A

DATA LISTINGS FOR TRUCK CODE

AN/TRC-117 & AN/TRC-110

AN/TCC-61

AN/TRC-145

# DATA LISTING FOR AN/TRC-117 AND AN/TRC-110

M35A2-S280 SHELTER, SHELTER AND HEAVY WALKS RIG. ATTACHED. (110, 117)

|         | 0       | 0      | 0      | 3      | 1        | 0 |
|---------|---------|--------|--------|--------|----------|---|
|         | 1       | 2      | 2      |        |          |   |
|         | 2       | 1      | 1      |        |          |   |
| 32.67   | 0.      | 39.04  | -99.38 |        |          |   |
| 3.705   | 0.      | 1.     | 0.     |        |          |   |
| 4.085   | 0.      | 0.     | -130.  |        |          |   |
| 4.405   | 0.      | 0.     | -178.  |        |          |   |
| -32129. |         |        |        |        |          |   |
| 224451. | 215454. | 53400. |        |        |          |   |
| 312.    | 2452.   | 2844.  |        |        |          |   |
| 93.20   | 5381.   | 3900.  |        |        |          |   |
| 93.20   | 5381.   | 3900.  |        |        |          |   |
| 15.4    | 10.8    | 0.0    | 15.4   | 5.6    | 0.0      |   |
| 15.4    | 11.17   | -10.76 | 15.4   | -1.4   | -3.24    |   |
| 20.24   | 5.0     | -130.0 | 20.24  | 0.0    | -130.0   |   |
| 20.24   | 5.0     | -178.0 | 20.24  | 0.0    | -178.0   |   |
| 0.0     | 0.0     |        |        |        |          |   |
| 33.675  |         |        |        |        |          |   |
| 0.0     | -130.0  |        |        |        |          |   |
| 29.200  | 40.75   |        |        |        |          |   |
| 0.0     | -175.0  |        |        |        |          |   |
| 29.200  | 40.75   |        |        |        |          |   |
|         | 20.24   |        |        |        |          |   |
| -10000. | 42000.  | 0.0    | 0.0    | 10000. | -82000.  |   |
| -10000. | 150000. | 0.0    | 0.0    | 10000. | -328000. |   |
| -10000. | 0.      | 10000. | 0.     |        |          |   |
| -10000. | 0.      | 10000. | 0.     |        |          |   |
| -10000. | 84000.  | 0.0    | 0.0    | 10000. | -164000. |   |
| 2.48    | 2.48    |        |        |        |          |   |
| -6.2    | 6243.   | 0.0    | 0.0    | 100.   | -100700. |   |
| -100.   | 0.0     | 100.   | 0.0    |        |          |   |
| -5.0    | 0.0     | 100.   | 0.0    |        |          |   |
| -5.0    | 0.0     | 100.   | 0.0    |        |          |   |
| -6.2    | 7181.   | 0.0    | 0.0    | 100.   | -115500. |   |
| -8.5    | 28900.  | -1.125 | 80.0   | 0.0    | 0.0      |   |
| 0.0     | 0.0     | .125   | 52.5   | 10.0   | 12700.   |   |
| 20.375  | 1.5     | 386.0  |        |        |          |   |
| 0.0     | 0.0     | 1000.  |        |        |          |   |
| .05     | .00015  |        |        |        |          |   |
|         | 3       | 1      |        |        |          |   |
|         | 1       | 1      | 1      |        |          |   |
|         | 4       |        |        |        |          |   |

DATA LISTING FOR AN/TRC-117 AND AN/TRC-110 (CONT'D)

|        |        |        |        |
|--------|--------|--------|--------|
| 29.57  | 12.36  | 0.06   | 1285.7 |
| 20.02  | 37.07  | 78.06  | 12.36  |
| 29.57  | 37.07  | 8.06   | 1285.7 |
| 20.02  | 12.36  | 78.06  | 37.07  |
| 29.57  | 37.07  | -43.96 | 1285.7 |
| 78.06  | 12.36  | 20.02  | 37.07  |
| 29.57  | 12.36  | -43.96 | 1285.7 |
| 78.06  | 37.07  | 20.02  | 12.36  |
| 4      |        |        |        |
| 21.25  | 15.89  | 34.08  | 1350.2 |
| 53.75  | 33.54  | 17.93  | 15.89  |
| -21.25 | 15.89  | 34.08  | 1350.2 |
| 17.93  | 33.54  | 63.75  | 15.89  |
| -14.79 | 40.50  | 34.08  | 521.9  |
| 14.79  | 0.83   | 44.36  | 40.59  |
| 14.79  | 40.50  | 34.08  | 521.9  |
| 44.36  | 0.83   | 14.79  | 40.59  |
| b      |        |        |        |
| 1      |        |        |        |
| 0.0    | 49.42  | -17.96 | 8846.0 |
| 1      |        |        |        |
| 0.0    | 0.0    | -17.96 | 8846.0 |
| b      |        |        |        |
| 46.5   | 11.0   | -200.5 | 1122.0 |
| 127.5  | 101.17 | 25.5   | 11.0   |
| 46.5   | 11.0   | -149.5 | 1122.0 |
| 76.5   | 101.17 | 76.5   | 11.0   |
| 46.5   | 11.0   | -98.5  | 1122.0 |
| 25.5   | 101.17 | 127.5  | 11.0   |
| 46.5   | 33.0   | -98.5  | 1122.0 |
| 25.5   | 79.17  | 127.5  | 33.0   |
| 46.5   | 33.0   | -149.5 | 1122.0 |
| 76.5   | 79.17  | 76.5   | 33.0   |
| 46.5   | 33.0   | -200.5 | 1122.0 |
| 127.5  | 79.17  | 25.5   | 33.0   |
| 4      |        |        |        |
| -44.5  | 15.89  | -73.0  | 127.1  |
| 2.0    | 96.24  | 91.0   | 15.89  |
| -36.04 | 37.89  | -73.0  | 207.1  |
| 8.07   | 74.29  | 84.54  | 37.89  |
| 36.04  | 37.89  | -73.0  | 207.1  |
| 84.54  | 74.29  | 0.47   | 37.89  |
| 44.5   | 15.89  | -73.0  | 127.1  |
| 91.0   | 96.24  | 2.0    | 15.89  |
| 4      |        |        |        |
| 23.25  | 11.0   | -226.0 | 1023.0 |
| 23.25  | 101.17 | 69.75  | 11.0   |
| 23.25  | 33.0   | -226.0 | 1023.0 |
| 23.25  | 79.17  | 69.75  | 33.0   |
| -23.25 | 33.0   | -226.0 | 1023.0 |
| 69.75  | 79.17  | 23.25  | 33.0   |
| -23.25 | 11.0   | -226.0 | 1023.0 |
| 69.75  | 101.17 | 23.25  | 11.0   |

DATA LISTING FOR AN/TRC-117 AND AN/TRC-110 (CONCL'D)

|        |      |         |        |
|--------|------|---------|--------|
| 44.65  | 30.0 | -149.5  | 566.67 |
| 0.0    | 30.0 | -75.73  | 466.47 |
| -44.65 | 30.0 | -149.5  | 566.67 |
| 0.0    | 30.0 | -223.28 | 466.47 |

|     |     |        |         |
|-----|-----|--------|---------|
| 0.0 | 0.0 | -149.5 | 14229.0 |
|-----|-----|--------|---------|

|        |       |         |         |
|--------|-------|---------|---------|
| 42.80  | 61.04 | -196.87 | 1614.49 |
| 118.42 | 51.13 | 23.68   | 61.04   |
| 42.80  | 61.04 | -149.50 | 1614.49 |
| 71.05  | 51.13 | 71.05   | 61.04   |
| 42.80  | 61.04 | -102.13 | 1614.49 |
| 23.68  | 51.13 | 118.42  | 61.04   |
| 42.80  | 95.13 | -102.13 | 1614.49 |
| 23.68  | 17.04 | 118.42  | 95.13   |
| 42.80  | 95.13 | -149.50 | 1614.49 |
| 71.05  | 17.04 | 71.05   | 95.13   |
| 42.80  | 95.13 | -196.87 | 1614.49 |
| 118.42 | 17.04 | 23.68   | 95.13   |

|        |       |        |         |
|--------|-------|--------|---------|
| 36.18  | 78.09 | -78.45 | 901.55  |
| 78.98  | 34.08 | 6.62   | 78.09   |
| 0.0    | 80.80 | -78.45 | 3711.04 |
| 42.80  | 31.37 | 42.80  | 80.80   |
| -36.18 | 78.09 | -78.45 | 901.55  |
| 6.62   | 34.08 | 78.98  | 78.09   |

|        |       |         |         |
|--------|-------|---------|---------|
| -21.40 | 61.04 | -220.55 | 1458.67 |
| 64.19  | 51.13 | 21.40   | 61.04   |
| 21.40  | 61.04 | -220.55 | 1458.67 |
| 21.40  | 51.13 | 64.19   | 61.04   |
| 21.40  | 95.13 | -220.55 | 1458.67 |
| 21.40  | 17.04 | 64.19   | 95.13   |
| -21.40 | 95.13 | -220.55 | 1458.67 |
| 64.19  | 17.04 | 21.40   | 95.13   |

|     |        |        |          |
|-----|--------|--------|----------|
| 0.0 | 112.17 | -149.5 | 12162.54 |
|-----|--------|--------|----------|

|    |    |    |    |     |       |
|----|----|----|----|-----|-------|
| 0  | 0  | 1  | 0  | 0.8 | 4250. |
| 6. | 0. | 0. | 0. |     |       |

END

# DATA LISTING FOR AN/TCC-61

MESSAGE-5240 SHELTER, SHELTER AND HEAVY KACKS R13. ATTACHED.

|         | (61)    | (ENGULF UK2) |         |        |          |
|---------|---------|--------------|---------|--------|----------|
| 1       | 2       | 2            | 5       | 1      | 0        |
| 35.7    | 0.      | 39.96        | -100.94 |        |          |
| 5.705   | 0.0     | 1.0          | 0.0     |        |          |
| 4.483   | 0.0     | 0.0          | -130.0  |        |          |
| 4.483   | 0.0     | 0.0          | -178.0  |        |          |
| -33657. |         |              |         |        |          |
| 231538. | 222210. | 56067.       |         |        |          |
| 312.0   | 2952.0  | 2844.0       |         |        |          |
| 93.26   | 3381.0  | 5960.0       |         |        |          |
| 43.26   | 3381.0  | 5960.0       |         |        |          |
| 15.4    | 10.8    | 0.0          | 15.4    | 5.6    | 0.0      |
| 15.4    | 11.19   | -10.76       | 15.4    | -1.4   | -5.24    |
| 20.24   | 5.0     | -130.0       | 20.24   | 0.0    | -130.0   |
| 20.24   | 5.0     | -178.0       | 20.24   | 0.0    | -178.0   |
| 0.0     | 0.0     |              |         |        |          |
| 33.475  |         |              |         |        |          |
| 0.0     | -130.0  |              |         |        |          |
| 29.266  | 40.75   |              |         |        |          |
| 0.0     | -178.0  |              |         |        |          |
| 29.265  | 40.75   |              |         |        |          |
|         | 20.24   |              |         |        |          |
| -10000. | 42000.  | 0.0          | 0.0     | 10000. | -82000.  |
| -10000. | 168000. | 0.0          | 0.0     | 10000. | -328000. |
| -10000. | 0.      | 10000.       | 0.      |        |          |
| -10000. | 0.      | 10000.       | 0.      |        |          |
| -10000. | 34000.  | 0.0          | 0.0     | 10000. | -164000. |
| 2.48    | 2.48    |              |         |        |          |
| -0.2    | 6243.   | 0.0          | 0.0     | 100.   | -100700. |
| -100.   | 0.0     | 100.         | 0.0     |        |          |
| -5.0    | 0.0     | 100.         | 0.0     |        |          |
| -5.0    | 0.0     | 100.         | 0.0     |        |          |
| -0.2    | 7151.   | 0.0          | 0.0     | 100.   | -115500. |
| -8.7    | 25400.  | -0.125       | 80.0    | 0.0    | 0.0      |
| 0.0     | 0.0     | .125         | 32.5    | 10.0   | 12700.   |
| 20.575  | 0.0     | 380.0        |         |        |          |
| 0.0     | 0.0     | 1000.        |         |        |          |
| .05     | .0001   |              |         |        |          |
| 10      |         |              |         |        |          |
| 5       | 1       |              |         |        |          |
| 1       | 1       | 1            |         |        |          |
| 4       |         |              |         |        |          |

# DATA LISTING FOR AN/TCC-61 (CONT'D)

|        |        |        |        |
|--------|--------|--------|--------|
| 29.57  | 12.35  | 8.06   | 1285.4 |
| 26.02  | 37.07  | 78.06  | 12.36  |
| 29.57  | 37.07  | 8.06   | 1285.4 |
| 26.02  | 12.35  | 78.06  | 37.07  |
| 29.57  | 37.07  | -43.98 | 1285.4 |
| 78.06  | 12.35  | 26.02  | 37.07  |
| 29.57  | 12.35  | -43.98 | 1235.4 |
| 78.06  | 37.07  | 26.02  | 12.36  |
| 4      |        |        |        |
| 21.25  | 15.49  | 34.08  | 1350.2 |
| 63.75  | 33.54  | 17.43  | 15.84  |
| -21.25 | 15.49  | 34.08  | 1350.2 |
| 17.93  | 33.54  | 63.75  | 15.84  |
| -14.74 | 40.59  | 34.08  | 521.4  |
| 14.74  | 4.83   | 44.36  | 40.59  |
| 14.74  | 40.59  | 34.08  | 521.4  |
| 44.36  | 4.83   | 14.74  | 40.59  |
| 0      |        |        |        |
| 1      |        |        |        |
| 0.0    | 49.42  | -17.96 | 8840.0 |
| 1      |        |        |        |
| 0.0    | 0.0    | -17.96 | 8840.8 |
| 5      |        |        |        |
| 45.5   | 11.0   | -200.5 | 1122.0 |
| 127.5  | 101.17 | 25.5   | 11.0   |
| 45.5   | 11.0   | -149.5 | 1122.0 |
| 76.5   | 101.17 | 76.5   | 11.0   |
| 45.5   | 11.0   | -98.5  | 1122.0 |
| 25.5   | 101.17 | 127.5  | 11.0   |
| 45.5   | 33.0   | -98.5  | 1122.0 |
| 25.5   | 74.17  | 127.5  | 33.0   |
| 45.5   | 33.0   | -149.5 | 1122.0 |
| 76.5   | 74.17  | 76.5   | 33.0   |
| 45.5   | 33.0   | -200.5 | 1122.0 |
| 127.5  | 74.17  | 25.5   | 33.0   |
| 4      |        |        |        |
| -44.5  | 15.84  | -73.0  | 127.1  |
| 2.0    | 91.6   | 91.6   | 15.84  |
| -38.04 | 37.84  | -73.0  | 207.1  |
| 8.47   | 74.24  | 84.54  | 37.84  |
| 38.04  | 37.84  | -73.0  | 207.1  |
| 84.54  | 74.24  | 8.47   | 37.84  |
| 44.5   | 15.84  | -73.0  | 127.1  |
| 91.6   | 91.6   | 2.0    | 15.84  |
| 4      |        |        |        |
| 23.25  | 11.0   | -226.0 | 1023.0 |
| 23.25  | 101.17 | 64.75  | 11.0   |
| 23.25  | 33.0   | -226.0 | 1023.0 |
| 23.25  | 74.17  | 64.75  | 33.0   |
| -23.25 | 33.0   | -226.0 | 1023.0 |
| 64.75  | 74.17  | 23.25  | 33.0   |
| -23.25 | 11.0   | -226.0 | 1023.0 |
| 64.75  | 101.17 | 23.25  | 11.0   |

# DATA LISTING FOR AN/TCC-61 (CONCL'D)

|        |      |         |        |
|--------|------|---------|--------|
| 44.55  | 30.0 | -149.5  | 566.87 |
| 0.0    | 30.0 | -75.73  | 466.47 |
| -44.55 | 30.0 | -149.5  | 566.87 |
| 0.0    | 30.0 | -223.28 | 466.47 |

|     |     |        |         |
|-----|-----|--------|---------|
| 0.0 | 0.0 | -149.5 | 14229.0 |
|-----|-----|--------|---------|

|        |       |         |         |
|--------|-------|---------|---------|
| 42.80  | 61.04 | -196.87 | 1614.49 |
| 118.42 | 51.13 | 23.68   | 61.04   |
| 42.80  | 61.04 | -149.50 | 1614.49 |
| 71.05  | 51.13 | 71.05   | 61.04   |
| 42.80  | 61.04 | -102.13 | 1614.49 |
| 23.68  | 51.13 | 118.42  | 61.04   |
| 42.80  | 95.13 | -102.13 | 1614.49 |
| 23.68  | 17.04 | 118.42  | 95.13   |
| 42.80  | 95.13 | -149.50 | 1614.49 |
| 71.05  | 17.04 | 71.05   | 95.13   |
| 42.80  | 95.13 | -196.87 | 1614.49 |
| 118.42 | 17.04 | 23.68   | 95.13   |

|        |       |        |         |
|--------|-------|--------|---------|
| 36.16  | 78.09 | -78.45 | 901.55  |
| 78.98  | 34.08 | 6.62   | 78.09   |
| 0.0    | 80.80 | -78.45 | 3711.04 |
| 42.80  | 31.57 | 42.80  | 80.80   |
| -36.16 | 78.09 | -78.45 | 901.55  |
| 6.62   | 34.08 | 78.98  | 78.09   |

|        |       |         |         |
|--------|-------|---------|---------|
| -21.40 | 61.04 | -220.55 | 1458.67 |
| 64.19  | 51.13 | 21.40   | 61.04   |
| 21.40  | 61.04 | -220.55 | 1458.67 |
| 21.40  | 51.13 | 64.19   | 61.04   |
| 21.40  | 95.13 | -220.55 | 1458.67 |
| 21.40  | 17.04 | 64.19   | 95.13   |
| -21.40 | 95.13 | -220.55 | 1458.67 |
| 64.19  | 17.04 | 21.40   | 95.13   |

|     |        |        |          |
|-----|--------|--------|----------|
| 0.0 | 112.17 | -149.5 | 12162.34 |
|-----|--------|--------|----------|

|     |    |    |    |    |          |
|-----|----|----|----|----|----------|
| 2.8 | 0. | 0. | 0. | 1. | E6 4250. |
|-----|----|----|----|----|----------|

END

# DATA LISTING FOR AN/TRC-145

715 WITH S250 RIGIDLY ATTACHED, RACKS RIGIDLY MOUNTED

(PRICE THRU)

|         | 1      | 0       | 0       | 2      | 0       | 0 |
|---------|--------|---------|---------|--------|---------|---|
|         | 2      | 5       |         |        |         |   |
|         | 2      | 2       |         |        |         |   |
| 15.87   | 0.0    | 50.03   | -77.52  |        |         |   |
| 1.91    | 0.0    | 0.0     | 0.0     |        |         |   |
| 1.91    | 0.0    | 0.0     | -126.0  |        |         |   |
| -9753.  |        |         |         |        |         |   |
| 44847.  | 34555. | 17088.  |         |        |         |   |
| 0.      | 2591.  | 2591.   |         |        |         |   |
| 0.      | 2754.  | 2754.   |         |        |         |   |
| 25.13   | 4.78   | 0.0     | 17.0    | 1.28   | 0.0     |   |
| 17.8    | 15.52  | -3.07   | 17.8    | -2.07  | -3.07   |   |
| 25.13   | 11.11  | -126.0  | 25.13   | 4.81   | -126.0  |   |
| 10.42   | 10.55  | -157.26 | 18.52   | -3.10  | -126.05 |   |
| 0.      | 0.     |         |         |        |         |   |
| 33.5    | 33.5   |         |         |        |         |   |
| 0.      | -126.0 |         |         |        |         |   |
| 33.5    | 33.5   | 33.5    |         |        |         |   |
|         | 0      |         |         |        |         |   |
| -10000. | 9810.  | -13.3   | 47.     | -4.7   | 25.     |   |
| 0.0     | 0.0    | 4.7     | -50.    | 10000. | -10000. |   |
|         | 0      |         |         |        |         |   |
| -10000. | 38040. | -13.3   | 183.    | -4.7   | 102.    |   |
| 0.0     | 0.0    | 4.7     | -226.   | 10000. | -64100. |   |
|         | 0      |         |         |        |         |   |
| -10000. | 7740.  | -13.3   | 26.     | 0.0    | 0.0     |   |
| 4.7     | -32.   | 10000.  | -13400. |        |         |   |
|         | 0      |         |         |        |         |   |
| -10000. | 30450. | -13.3   | 103.    | 0.0    | 0.0     |   |
| 4.7     | -130.  | 10000.  | -53700. |        |         |   |
| 1.35    | 1.35   |         |         |        |         |   |
|         | 0      |         |         |        |         |   |
| -8.5    | 6130.  | -3.0    | 1730.   | -0.125 | 250.    |   |
| 0.0     | 0.0    | 100.    | -50000. |        |         |   |
|         | 0      |         |         |        |         |   |
| -100.   | 0.0    | 100.    | 0.0     |        |         |   |
|         | 0      |         |         |        |         |   |
| -8.5    | 6200.  | -3.0    | 2360.   | -0.125 | 390.    |   |
| 0.0     | 0.0    | 100.    | -50000. |        |         |   |
|         | 0      |         |         |        |         |   |
| -100.   | 0.0    | 100.    | 0.0     |        |         |   |
|         | 0      |         |         |        |         |   |
| -8.5    | 6568.  | -0.125  | 25.5    | 0.0    | 0.0     |   |

DATA LISTING FOR AN/TRC-145 (CONT'D)

|        |    |       |       |        |      |       |
|--------|----|-------|-------|--------|------|-------|
| 0.0    | 3  | 0.0   | 0.125 | 10.2   | 10.0 | 4046. |
| 17.0   |    | 0.8   | 386.  |        |      |       |
| 0.0    |    | 0.0   | 1000. |        |      |       |
| .05    |    | .0001 |       |        |      |       |
|        | 10 |       |       |        |      |       |
|        | 2  |       | 1     |        |      |       |
|        | 1  |       | 1     |        |      |       |
|        | 4  |       |       |        |      |       |
| 41.5   |    | 9.75  | 1.9   | 999.4  |      |       |
| 25.6   |    | 29.2  | 76.9  | 9.75   |      |       |
| 41.5   |    | 9.75  | -49.4 | 999.4  |      |       |
| 76.9   |    | 29.2  | 25.6  | 9.75   |      |       |
| 41.5   |    | 29.25 | 1.9   | 999.4  |      |       |
| 25.6   |    | 9.75  | 25.6  | 29.2   |      |       |
| 41.5   |    | 29.25 | -49.4 | 999.4  |      |       |
| 76.9   |    | 9.75  | 76.9  | 29.2   |      |       |
|        | 2  |       |       |        |      |       |
| -20.8  |    | 19.5  | 27.5  | 1618.5 |      |       |
| 20.8   |    | 19.5  | 62.2  | 19.5   |      |       |
| 20.8   |    | 19.5  | 27.5  | 1618.5 |      |       |
| 62.2   |    | 19.5  | 20.8  | 19.5   |      |       |
|        | 2  |       |       |        |      |       |
| 40.75  |    | 19.5  | -75.0 | 58.5   |      |       |
| .75    |    | 19.5  | 82.25 | 19.5   |      |       |
| -40.75 |    | 19.5  | -75.0 | 58.5   |      |       |
| 85.25  |    | 19.5  | .75   | 19.5   |      |       |
|        | 1  |       |       |        |      |       |
| 0.0    |    | 39.   | -23.5 | 8466.  |      |       |
|        | 1  |       |       |        |      |       |
| 0.0    |    | 0.0   | -23.5 | 8466.  |      |       |

# DATA LISTING FOR AN/TRC-145 (CONCL'D)

|       |       |        |       |     |       |
|-------|-------|--------|-------|-----|-------|
|       | 9     |        |       |     |       |
| 40.   | 15.25 | -95.8  | 904.8 |     |       |
| 123.3 | 28.   | 74.2   | 15.25 |     |       |
| 40.   | 15.25 | -125.5 | 904.8 |     |       |
| 153.  | 50.4  | 44.5   | 15.25 |     |       |
| 40.   | 15.25 | -155.2 | 904.8 |     |       |
| 183.  | 76.25 | 14.8   | 15.25 |     |       |
| 40.   | 45.75 | -95.8  | 904.8 |     |       |
| 14.8  | 45.75 | 74.2   | 45.75 |     |       |
| 40.   | 45.75 | -125.5 | 904.8 |     |       |
| 44.5  | 45.75 | 44.5   | 45.75 |     |       |
| 40.   | 45.75 | -155.2 | 904.8 |     |       |
| 74.2  | 45.75 | 14.8   | 45.75 |     |       |
| 40.0  | 76.25 | -95.8  | 904.8 |     |       |
| 14.8  | 15.25 | 74.2   | 76.25 |     |       |
| 40.   | 76.25 | -125.5 | 904.8 |     |       |
| 44.5  | 15.25 | 44.5   | 76.25 |     |       |
| 40.   | 76.25 | -155.2 | 904.8 |     |       |
| 74.2  | 15.25 | 14.8   | 76.25 |     |       |
|       | 2     |        |       |     |       |
| -20.  | 65.25 | -81.   | 2100. |     |       |
| 20.   | 26.25 | 60.    | 65.25 |     |       |
| 20.   | 65.25 | -81.   | 2100. |     |       |
| 60.   | 26.25 | 20.    | 65.25 |     |       |
|       | 4     |        |       |     |       |
| 20.   | 22.9  | -170.  | 1830. |     |       |
| 20.   | 68.6  | 60.    | 22.9  |     |       |
| -20.  | 22.9  | -170.  | 1830. |     |       |
| 60.   | 68.6  | 20.    | 22.9  |     |       |
| 20.   | 68.6  | -170.  | 1830. |     |       |
| 20.   | 22.9  | 60.    | 68.6  |     |       |
| -20.  | 68.6  | -170.  | 1830. |     |       |
| 60.   | 22.9  | 20.    | 68.6  |     |       |
|       | 1     |        |       |     |       |
| 0.    | 91.5  | -125.5 | 6920. |     |       |
|       | 1     |        |       |     |       |
| 0.    | 0.    | -125.5 | 6920. |     |       |
|       | 0     | 1      |       |     |       |
| 6.0   | 0.    | 0.     | 0.    | 0.8 | 4250. |
| 0.0   |       |        |       |     |       |
| END   |       |        |       |     |       |

APPENDIX B

ACCELERATION TIME HISTORIES FOR AN/TRC-145

34.5 kPa (5.0 psi)

20.7 kPa (3.0 psi)

SHELTR LOADING MODEL

GRID POINT 13

AN/TRC-145




FIGURE B.1. ACCELERATION TIME HISTORY IN BLAST DIRECTION  
NEAR CENTER OF ROADSIDE WALL PANEL

GRID POINT 103

AN/TRC-145




FIGURE B.2. ACCELERATION TIME HISTORY IN BLAST DIRECTION, ROADSIDE RACK

GRID POINT 103

AN/TRC-145




FIGURE B.3. VERTICAL ACCELERATION TIME HISTORY, ROADSIDE RACK

GRID POINT 111

AN/TRC-145




FIGURE B.4. ACCELERATION TIME HISTORY IN BLAST DIRECTION,  
ROADSIDE RACK

GRID POINT 111

AN/TRC-145




FIGURE B.5. VERTICAL ACCELERATION TIME HISTORY,  
ROADSIDE RACK

GRID POINT 122

AN/TRC-145




FIGURE B.6. ACCELERATION TIME HISTORY IN BLAST DIRECTION, FRONT WALL RACK




FIGURE B.7. VERTICAL ACCELERATION TIME HISTORY,  
FRONT WALL RACK

# LIST OF SYMBOLS

|          |                                                       |
|----------|-------------------------------------------------------|
| A        | Cross sectional area                                  |
| CBAR     | Beam element                                          |
| CELAS2   | Linear spring element                                 |
| CONM2    | Concentrated mass                                     |
| CQUAD1   | Quadrilateral plate element                           |
| D.O.F.   | Degrees of freedom                                    |
| E        | Modulus of elasticity of wall panel                   |
| $E_K$    | Modulus of elasticity of Kevlar 49                    |
| G        | Shear modulus of wall panel                           |
| $G_F$    | Shear modulus of urethane foam                        |
| $G_{HC}$ | Shear modulus of honeycomb core                       |
| GRID     | Grid point                                            |
| $I_{xx}$ | Moment of inertia about x centroidal axis             |
| $I_{yy}$ | Moment of inertia about y centroidal axis             |
| $I_{yz}$ | Cross moment of inertia                               |
| $I_{zz}$ | Moment of inertia about z centroidal axis             |
| J        | Torsional constant                                    |
| $k_y$    | Transverse shear stiffness coefficient in y-direction |
| $k_z$    | Transverse shear stiffness coefficient in z-direction |
| MPC      | Multipoint constraint                                 |
| OMIT     | Coordinates omitted from inertia forces               |
| SPC      | Single point constraint                               |
| $t_F$    | Urethane foam thickness                               |
| $t_s$    | Skin thickness                                        |

# LIST OF SYMBOLS (Cont.)

|                                                                          |                                                                 |
|--------------------------------------------------------------------------|-----------------------------------------------------------------|
| $T_1$                                                                    | Reference membrane thickness                                    |
| $T_3$                                                                    | Transverse shear thickness                                      |
| $V_s$                                                                    | Shock wave velocity                                             |
| $\left. \begin{matrix} x_{cg} \\ y_{cg} \\ z_{cg} \end{matrix} \right\}$ | Mass centroidal coordinates in x, y, z directions, respectively |
| $\beta$                                                                  | Yaw angle of truck-shelter system                               |
| $\Delta p_i$                                                             | Incident overpressure                                           |
| $\Delta p_r$                                                             | Reflected overpressure                                          |
| $\nu$                                                                    | Poisson's ratio                                                 |
| $\rho$                                                                   | Sandwich panel mass density                                     |
| $\rho_F$                                                                 | Urethane foam mass density                                      |
| $\rho_{HC}$                                                              | Honeycomb core mass density                                     |
| $\rho_K$                                                                 | Kevlar 49 mass density                                          |
| $\rho_S$                                                                 | Skin mass density                                               |
| $\phi$                                                                   | Pitch angle of truck-shelter system                             |
| $\chi$                                                                   | Roll angle of truck-shelter system                              |

## REFERENCES

1. Private Communication from Mr. Joe Roma of ECOM, Fort Monmouth, N.J.
2. Organization, DS, GS, and Depot Maintenance Manual For Medium Capacity Tactical Radio Relay System, Department of the Army Technical Manual TM-11-5895-456-15, Headquarters Department of the Army, July 1967.
3. Radio Terminal Sets AN/TRC-145(V) 1, AN/TRC-145(V) 2, AN/TRC-145(V) 3, AN/TRC-145A(V) 2, AN/TRC-145A(V) 2, and AN/TRC-145A(V) 3 (FSN 5895-791-3365), Department of the Army Technical Manual 7M 11-5895-453-14, January 1973.
4. Radio Teletypewriter Sets AN/GRC-142, AN/GRC-142A, AN/GRC-142B, AN/GRC-122, AN/GRC-122A and AN/GRC-122B, Department of the Army Technical Manual TM 11-5815-334-12, May 1970.
5. Hobbs, N.P., et al, TRUCK - A Digital Computer Program for Calculating the Response of Army Vehicles to Blast Waves, Kaman Avidyne TR-136, March 1977.
6. Lottero, R.E., Computational Predictions of Shock Diffraction Loading on an S-280 Electrical Equipment Shelter, U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, BRL MR 2599, March 1976. (AD#A022804).
7. Calligeros, John M., and Walsh, John P., Finite Element Modeling of Army Electronic Equipment Shelters Subjected to Blast Loading, U.S. Army Ballistic Research Laboratory, Aberdeen Proving Ground, BRL CR 281, Dec. 1975. (AD#B0089041).

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                       | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                             |
|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------|
| 12                       | Commander<br>Defense Technical Info Center<br>ATTN: DDC-DDA<br>Cameron Station<br>Alexandria, VA 22314                                    | 1                        | Director<br>Weapons Systems Evaluation Group<br>ATTN: Document Control<br>Washington, DC 20305                                                  |
| 4                        | Director of Defense<br>Research & Engineering<br>ATTN: DD/TWP<br>DD/S&SS<br>DD/I&SS<br>AD/SW<br>Washington, DC 20301                      | 1                        | Director<br>National Security Agency<br>ATTN: E.F. Butala, R15<br>Ft. George G. Meade, MD 20755                                                 |
| 2                        | Asst. to the Secretary of<br>Defense (Atomic Energy)<br>ATTN: Document Control<br>Donald R. Cotter<br>Washington, DC 20301                | 3                        | Director<br>Joint Strategic Target Planning<br>Staff JCS<br>ATTN: Sci & Tech Info Lib<br>JLTW-2<br>DOXT<br>Offut AFB<br>Omaha, NB 68113         |
| 3                        | Director<br>Defense Advanced Research<br>Projects Agency<br>ATTN: Tech Lib<br>NMRO<br>PMO<br>1400 Wilson Boulevard<br>Arlington, VA 22209 | 1                        | Director<br>Defense Communications Agency<br>ATTN: Code 930<br>Washington, DC 20305                                                             |
| 2                        | Director<br>Defense Civil Preparedness<br>Agency<br>ATTN: Mr. Goerge Sisson/RF-SR<br>Technical Library<br>Washington, DC 20301            | 5                        | Director<br>Defense Nuclear Agency<br>ATTN: STSI/Archives<br>SPAS/Mr.J. Moulton<br>STSP<br>STVL/Dr.La Vier<br>RATN<br>Washington, DC 20305      |
| 4                        | Director<br>Defense Intelligence Agency<br>ATTN: DT-1B<br>DB-4C/E.O. Farrell<br>DT-2/Wpns & Sys Div<br>RDS-3A4<br>Washington, DC 20301    | 6                        | Director<br>Defense Nuclear Agency<br>ATTN: DDST/Dr. Conrad<br>DDST/Dr. Oswald<br>STTL/Tech Lib (2 cys)<br>SPSS (2 cys)<br>Washington, DC 20305 |
|                          |                                                                                                                                           | 2                        | Commander<br>Field Command, DNA<br>ATTN: FCPR<br>FCTMOF<br>Kirtland AFB, NM 87115                                                               |

261

PRECEDING PAGE BLANK-NOT FILLED

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                                              | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                                                                |
|--------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1                        | Commander<br>Field Command, DNA<br>Livermore Branch<br>ATTN: FCPRL<br>P.O. Box 808<br>Livermore, CA 94550                                                                        | 2                        | Office, Chief of Engineers<br>Department of the Army<br>ATTN: DAEN-MCE-D<br>DAEN-RDM<br>890 South Pickett Street<br>Alexandria, VA 22304                                                           |
| 1                        | Director<br>Institute for Defense Analysis<br>ATTN: IDA Librarian,<br>Ruth S. Smith<br>400 Army-Navy Drive<br>Arlington, VA 22202                                                | 1                        | Commander<br>US Army Engineering Center<br>ATTN: ATSEN-SY-L<br>Fort Belvoir, VA 22060                                                                                                              |
| 2                        | HDQA (DAMA-AR; NCL Div)<br>Washington, DC 20310                                                                                                                                  | 1                        | Division Engineer<br>US Army Engineering Division<br>ATTN: HNDSE-R/M.M. Dembo<br>Huntsville Box 1600<br>Huntsville, AL 35804                                                                       |
| 1                        | Program Manager<br>US Army BMD Program Office<br>ATTN: John Shea<br>Alexandria, VA 22333                                                                                         | 1                        | Division Engineer<br>US Army Engineering Division<br>Ohio River<br>ATTN: Docu Cen<br>P.O. Box 1159<br>Cincinnati, OH 45201                                                                         |
| 2                        | Director<br>US Army BMD Advanced<br>Technology Center<br>ATTN: CRDABH-X<br>CRDABH-S<br>Huntsville, AL 35807                                                                      | 5                        | Commander<br>US Army Engineer Waterways<br>Experiment Station<br>ATTN: Technical Library<br>William Flathau<br>John N. Strange<br>Guy Jackson<br>Leo Ingram<br>P.O. Box 631<br>Vicksburg, MS 39180 |
| 1                        | Commander<br>US Army BMD System Command<br>ATTN: BDMSC-TFN/N.J. Hurst<br>P.O. Box 1500<br>Huntsville, AL 35807                                                                   |                          |                                                                                                                                                                                                    |
| 2                        | Deputy Chief of Staff for<br>Operations and Plans<br>ATTN: Technical Library<br>Director of Chemical<br>and Nuclear Operations<br>Department of the Army<br>Washington, DC 20310 | 1                        | Commander<br>US Army Materiel Development<br>& Readiness Command<br>ATTN: DRCDMD-ST<br>5001 Eisenhower Avenue<br>Alexandria, VA 22333                                                              |

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                           | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                                                                                 |
|--------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1                        | Commander<br>US Army Materiel Development<br>& Readiness Command<br>ATTN: Technical Library<br>5001 Eisenhower Avenue<br>Alexandria, VA 22333 | 6                        | Commander<br>US Army Electronics Research<br>& Development Command<br>ATTN: DELSD-L<br>DELEW-E, W.S. McAfee<br>R. Freiberg<br>DELS-D-EI, J. Roma<br>DELS-D-EM, A. Sigismondi<br>C. Goldy<br>Fort Monmouth, NJ 07703 |
| 3                        | Commander<br>US Army Armament Research<br>& Development Command<br>ATTN: DRDAR-LCN-F, W. Reiner<br>DRDAR-TSS (2 cys)<br>Dover, NJ 07801       | 5                        | Commander<br>US Army Harry Diamond Labs<br>ATTN: Mr. James Gaul<br>Mr. L. Belliveau<br>Mr. J. Gwaltney<br>Mr. F.N. Wimenitz<br>Mr. Bill Vault<br>2800 Powder Mill Road<br>Adelphi, MD 20783                         |
| 1                        | Director<br>US Army ARRADCOM<br>Benet Weapons Laboratory<br>ATTN: DRDAR-LCB-TL<br>Watervliet, NY 12189                                        |                          |                                                                                                                                                                                                                     |
| 1                        | Commander<br>US Army Armament Materiel<br>Readiness Command<br>ATTN: DRSAR-LEP-L, Tech Lib<br>Rock Island, IL 61299                           | 5                        | Commander<br>US Army Harry Diamonds Labs<br>ATTN: DRXDO-TI<br>DRXDO-TI/012<br>DRXDO-NP<br>DRXDO-RBH/P.Caldwell<br>DELHD-RBA/J. Rosado<br>2800 Powder Mill Road<br>Adelphi, MD 20783                                 |
| 1                        | Commander<br>US Army Aviation Research<br>& Development Command<br>ATTN: DRSAR-E<br>P.O. Box 209<br>St. Louis, MO 63166                       | 3                        | Commander<br>US Army Missile Command<br>ATTN: DRDMI-R<br>DRDMI-YDL<br>Chief Scientist<br>Redstone Arsenal, AL 35809                                                                                                 |
| 1                        | Director<br>US Army Air Mobility Research<br>& Development Laboratory<br>Ames Research Center<br>Moffett Field, CA 94035                      | 2                        | Commander<br>US Army Natick Research &<br>Development Command<br>ATTN: DRXRE/Dr.D. Sieling<br>DRXNM-UE, Arthur Johnson<br>Natick, MA 01762                                                                          |
| 1                        | Commander<br>US Army Communications Research<br>& Development Command<br>ATTN: DRDCO-PPA-SA<br>Fort Monmouth, NJ 07703                        |                          |                                                                                                                                                                                                                     |

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                               | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                           |
|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------|
| 1                        | Commander<br>US Army Tank Automotive Research<br>& Development Command<br>ATTN: DRDTA-UL<br>Warren, MI 48090                                      | 2                        | Director<br>US Army TRADOC Systems Analysis<br>Activity<br>ATTN: LTC John Hesse<br>ATAA-SL, Tech Lib<br>White Sands Missile Range<br>NM 88002 |
| 1                        | Commander<br>US Army Foreign Science and<br>Technology Center<br>ATTN: Rsch & Concepts Branch<br>220 7th Street, NE<br>Charlottesville, VA 22901  | 1                        | Commander<br>Combined Arms Combat<br>Developments Activity<br>ATTN: ATCA-CO/Mr.L.C. Pleger<br>Fort Leavenworth, KS 66027                      |
| 1                        | Commander<br>US Army Logistical Center<br>ATTN: ATCL-SCA, Robert Cameron<br>Fort Lee, VA 23801                                                    | 1                        | Chief of Naval Research<br>ATTN: N. Perrone<br>Department of the Navy<br>Washington, DC 20360                                                 |
| 3                        | Commander<br>US Army Materials and Mechanics<br>Research Center<br>ATTN: Technical Library<br>John Mescall<br>Richard Shea<br>Watertown, MA 02172 | 2                        | Chief of Naval Operations<br>ATTN: OP-03EG<br>OP-985F<br>Department of the Navy<br>Washington, DC 20350                                       |
| 2                        | Commander<br>US Army Nuclear Agency<br>ATTN: ACTA-NAW<br>Technical Library<br>7500 Backlick Road, Bldg 2073<br>Springfield, VA 22150              | 1                        | Chief of Naval Material<br>ATTN: MAT 0323<br>Department of the Navy<br>Arlington, VA 22217                                                    |
| 1                        | Commander<br>US Army Research Office<br>P.O. Box 12211<br>Research Triangle Park<br>NC 27709                                                      | 3                        | Director<br>Strategic Systems Projects Ofc<br>ATTN: NSP-43, Tech Lib<br>NSP-273<br>NSP-272<br>Department of the Navy<br>Washington, DC 02360  |
| 1                        | Commander<br>US Army Training and Doctrine<br>Command<br>ATTN: ATCD-SA/Mr. Oscar Wells<br>Fort Monroe, VA 23651                                   | 1                        | Commander<br>Naval Electronic Systems Command<br>ATTN: PME 117-21A<br>Washington, DC 20360                                                    |

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                                              | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                                                       |
|--------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 3                        | Commander<br>US Naval Facilities<br>Engineering Command<br>ATTN: Code 03A<br>Code 04B<br>Technical Library<br>Washington, DC 20360                                               | 3                        | Commander<br>Naval Surface Weapons Center<br>ATTN: Code WA501/Navy Nuclear<br>Programs Office<br>Code WX21/Tech Lib<br>Code 240/C.J. Aronson<br>Silver Spring, MD 20910                   |
| 2                        | Commander<br>Naval Sea Systems Command<br>ATTN: ORD-91313 Library<br>Code 03511<br>Department of the Navy<br>Washington, DC 20362                                                | 2                        | Commander<br>Naval Weapons Center<br>ATTN: Code 533/Tech Lib<br>Code 31804/M. Keith<br>China Lake, CA 94555                                                                               |
| 4                        | Officer-in-Charge<br>Civil Engineering Laboratory<br>Naval Constr Btn Ctr<br>ATTN: Stan Takahashi<br>R.J. Odello<br>John Crawford<br>Technical Library<br>Port Hueneme, CA 93041 | 2                        | Commander<br>Naval Ship Research & Development<br>Center Facility<br>Underwater Explosions Research<br>Division<br>ATTN: Code 17/W.W. Murray<br>Technical Library<br>Portsmouth, VA 23709 |
| 2                        | Commander<br>Naval Ship Engineering Center<br>ATTN: Technical Library<br>NSEC 6105G<br>Hyattsville, MD 20782                                                                     | 2                        | Commander<br>Naval Weapons Evaluation Facility<br>ATTN: Document Control<br>R. Hughes<br>Kirtland AFB<br>Albuquerque, NM 87117                                                            |
| 1                        | Commander<br>David W. Taylor Naval Ship<br>Research & Development Center<br>ATTN: Lib Div, Code 522<br>Bethesda, MD 20084                                                        | 2                        | Director<br>Naval Research Laboratory<br>ATTN: Code 2027/Tech Lib<br>Code 8440/F. Rosenthal<br>Washington, DC 20375                                                                       |
| 1                        | Commander<br>Naval Surface Weapons Center<br>ATTN: DX-21, Library Br.<br>Dahlgren, VA 22448                                                                                      | 1                        | Superintendent<br>Naval Postgraduate School<br>ATTN: Code 2124/Tech Rpts Lib<br>Monterey, CA 93940                                                                                        |
|                          |                                                                                                                                                                                  | 1                        | HQ USAF (IN)<br>Washington, DC 20330                                                                                                                                                      |
|                          |                                                                                                                                                                                  | 1                        | HQ USAF(PRE)<br>Washington, DC 20330                                                                                                                                                      |

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                 | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                       |
|--------------------------|-----------------------------------------------------------------------------------------------------|--------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------|
| 2                        | AFSC (DLCAW; Tech Lib)<br>Andrews AFB<br>Washington, DC 20331                                       | 4                        | FTD (TDFBD; TDPMG; ETET/<br>CPT R.C. Husemann;<br>TD-BTA/Lib)<br>Wright-Patterson AFB, OH 45433                                                           |
| 1                        | AFATL (DLYV, P. Nash)<br>Eglin AFB, FL 32542                                                        | 1                        | AFIT (Lib Bldg. 640, Area B)<br>Wright-Patterson AFB<br>OH 45433                                                                                          |
| 1                        | AFATL (DLYV, Jim Flint)<br>Eglin AFB, FL 32542                                                      | 1                        | Director<br>US Bureau of Mines<br>ATTN: Technical Library<br>Denver Federal Center<br>Denver, CO 80225                                                    |
| 2                        | ADTC (ADBRL-2; Tech Lib)<br>Eglin AFB, FL 32542                                                     | 1                        | Director<br>US Bureau of Mines<br>Twin Cities Research Center<br>ATTN: Technical Library<br>P.O. Box 1660<br>Minneapolis, MN 55111                        |
| 2                        | RADC (EMTLD/Docu Lib; EMREC/<br>R.W. Mair)<br>Griffis AFB, NY 13340                                 | 1                        | US Energy Res & Dev Admin<br>Albuquerque Operations Office<br>ATTN: Doc Control for Tech Lib<br>P.O. Box 5400<br>Albuquerque, NM 87115                    |
| 1                        | AFWL/R. Henny<br>Kirtland AFB, NM 87117                                                             | 1                        | US Energy Research & Development<br>Administration<br>Nevada Operations Office<br>ATTN: Doc Control for Tech Lib<br>P.O. Box 14100<br>Las Vegas, NV 89114 |
| 1                        | AFWL/DE-I<br>Kirtland AFB, MN 87117                                                                 | 1                        | Director<br>Lawrence Livermore Lab<br>ATTN: L.W. Woodruff/L-96<br>P.O. Box 808<br>Livermore, CA 94550                                                     |
| 1                        | AFWL/DEX<br>Kirtland AFB, NM 87117                                                                  | 1                        | Director<br>Lawrence Livermore Lab<br>ATTN: Jack Kahn/L-7<br>P.O. Box 808<br>Livermore, CA 94550                                                          |
| 1                        | AFWL/SUL(Jimmie L. Bratton)<br>Kirtland AFB, NM 87117                                               |                          |                                                                                                                                                           |
| 1                        | AFWL/SUL(M.A. Plamondon)<br>Kirtland AFB, NM 87115                                                  |                          |                                                                                                                                                           |
| 1                        | Interservice Nuclear Weapons<br>School<br>ATTN: Technical Library<br>Kirtland, AFB, NM 87115        |                          |                                                                                                                                                           |
| 2                        | Commander-in-Chief<br>Strategic Air Command<br>ATTN: NRI-STINFO Lib<br>XPFS<br>Offutt AFB, NB 68113 |                          |                                                                                                                                                           |

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                          | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                                                          |
|--------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1                        | Director<br>Lawrence Livermore Lab<br>ATTN: Tech Info Dept L-3<br>P.O. Box 808<br>Livermore, CA 94550                                                        | 6                        | Sandia Laboratories<br>ATTN: Doc Control for 3141<br>Sandia Rpt Collection<br>A.M. Chaban<br>M.L. Merritt<br>L.J. Vortman<br>W. Roherty<br>L. Hill<br>P.O. Box 5800<br>Albuquerque, NM 87115 |
| 1                        | Director<br>Lawrence Livermore Lab<br>ATTN: R.G. Dong/L-90<br>P.O. Box 808<br>Livermore, CA 94550                                                            | 1                        | Sandia Laboratories<br>Livermore Laboratory<br>ATTN: Doc Control for Tech Lib<br>P.O. Box 969<br>Livermore, CA 94550                                                                         |
| 1                        | Director<br>Lawrence Livermore Lab<br>ATTN: Ted Butkovich/L-200<br>P.O. Box 808<br>Livermore, CA 94550                                                       | 1                        | Director<br>National Aeronautics and<br>Space Administration<br>Scientific and Technical<br>Information Facility<br>P.O. Box 8757<br>Baltimore/Washington International<br>Airport, MD 21240 |
| 1                        | Director<br>Lawrence Livermore Lab<br>ATTN: Robert Schock/L-437<br>P.O. Box 808<br>Livermore, CA 94550                                                       | 3                        | Aerospace Corporation<br>ATTN: Tech Info Services(2 cys)<br>P.N. Mathur<br>P.O. Box 92957<br>Los Angeles, CA 90009                                                                           |
| 1                        | Director<br>Lawrence Livermore Lab<br>ATTN: J.R. Hearst/L-205<br>P.O. Box 808<br>Livermore, CA 94550                                                         | 1                        | Agbabian Associates<br>ATTN: M. Agbabian<br>250 North Nash Street<br>El Segundo, CA 90245                                                                                                    |
| 4                        | Director<br>Los Alamos Scientific Lab<br>ATTN: Doc Control for Rpts Lib<br>R.A. Gentry<br>G.R. Spillman<br>Al Davis<br>P.O. Box 1663<br>Los Alamos, NM 87544 | 1                        | Applied Theory, Inc.<br>ATTN: John G. Trulio<br>1010 Westwood Blvd.<br>Los Angeles, CA 90024                                                                                                 |
|                          |                                                                                                                                                              | 1                        | Artec Associates, Inc.<br>ATTN: Steven Gill<br>26046 Eden Landing Road<br>Hayward, CA 94545                                                                                                  |

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                         | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                    |
|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1                        | AVCO<br>ATTN: Res Lib A830, Rm 7201<br>201 Lowell Street<br>Wilmington, MA 01887                                                            | 1                        | The Franklin Institute<br>ATTN: Zemons Zudans<br>20th Street and Parkway<br>Philadelphia, PA 19103                                                     |
| 1                        | The BDM Corporation<br>ATTN: Richard Hensley<br>P.O. Box 9274<br>Albuquerque International<br>Albuquerque, NM 87119                         | 1                        | General American Trans<br>Corporation<br>General American Research Div<br>ATTN: G.L. Neidhardt<br>7449 N. Natchez Avenue<br>Niles, IL 60648            |
| 2                        | The Boeing Company<br>ATTN: Aerospace Library<br>R.H. Carlson<br>P.O. Box 3707<br>Seattle, WA 98124                                         | 1                        | General Electric Company-TEMPO<br>ATTN: DASIAC<br>P.O. Drawer QQ<br>Santa Barbara, CA 93102                                                            |
| 1                        | Brown Engineering Co., Inc.<br>ATTN: Manu Patel<br>Cummings Research Park<br>Huntsville, AL 35807                                           | 1                        | General Electric-TEMPO<br>ATTN: E. Bryant<br>220 S. Main Street, Rm 206<br>Bel Air, MD 21014                                                           |
| 2                        | California Research and<br>Technology, Inc.<br>ATTN: Ken Kreyenhagen<br>Technical Library<br>6269 Variel Avenue<br>Woodland Hills, CA 91364 | 2                        | Hazeltine Corp.<br>ATTN: Carl Meinen<br>Greenlawn, NY 11740                                                                                            |
| 1                        | Calspan Corporation<br>ATTN: Technical Library<br>P.O. Box 235<br>Buffalo, NY 14221                                                         | 1                        | J.H. Wiggins Co., Inc.<br>ATTN: John Collins<br>1650 South Pacific Cost Highway<br>Redondo Beach, CA 90277                                             |
| 1                        | Civil/Nuclear Systems<br>Corporation<br>ATTN: Robert Crawford<br>1200 University N.E.<br>Albuquerque, NM 87102                              | 5                        | Kaman Avidyne<br>ATTN: Dr.N.P. Hobbs (4 cys)<br>Mr. S. Criscione<br>83 Second Avenue<br>Northwest Industrial Park<br>Burlington, MA 01830              |
| 1                        | EG&G, Incorporated<br>Albuquerque Division<br>ATTN: Technical Library<br>P.O. Box 10218<br>Albuquerque, NM 87114                            | 3                        | Kaman Avidyne<br>ATTN: John Calligeros<br>John P. Walsh<br>Raffi P. Yeghiayan<br>83 Second Avenue<br>Northwest Industrial Park<br>Burlington, MA 01830 |

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                         | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                           |
|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 3                        | Kaman Sciences Corporation<br>ATTN: Library<br>P.A. Ellis<br>F.H. Shelton<br>1500 Garden of the Gods Road<br>Colorado Spring, CO 80907                      | 1                        | Pacific Sierra Research Corp<br>ATTN: Dr. Harold Brode<br>1456 Cloverfield Boulevard<br>Santa Monica, CA 90404                                                |
| 1                        | Lockheed Missiles & Space Co.<br>ATTN: Technical Library<br>P.O. Box 504<br>Sunnyvale, CA 94088                                                             | 2                        | Pacifica Technology<br>ATTN: G. Kent<br>R. Bjork<br>P.O. Box 148<br>Del Mar, CA 92014                                                                         |
| 2                        | Martin Marietta Aerospace<br>Orlando Division<br>ATTN: G. Fotieo<br>Craig Luongo, Mail Pt 505<br>P.O. Box 5837<br>Orlando, FL 32805                         | 4                        | Physics International Corp.<br>ATTN: Robert Swift<br>Charles Godfrey<br>Larry A. Behrmann<br>Technical Library<br>2700 Merced Street<br>San Leandro, CA 94577 |
| 3                        | McDonnell Douglas Astronautics Corporation<br>ATTN: Robert W. Halprin<br>Mr. C. Gardiner<br>Dr. P. Lewis<br>5301 Bolsa Avenue<br>Huntington Beach, CA 92647 | 1                        | Radkowski Associates<br>ATTN: Peter R. Radkowski<br>P.O. Box 5474<br>Riverside, CA 92517                                                                      |
| 2                        | Merritt Cases, Inc.<br>ATTN: J.L. Merritt<br>Technical Library<br>P.O. Box 1206<br>Redlands, CA 92373                                                       | 2                        | R&D Associates<br>ATTN: Dr. Albert L. Latter<br>William B. Wright<br>P.O. Box 9695<br>Marina del Rey, CA 90291                                                |
| 1                        | Meteorology Research, Inc.<br>ATTN: W.D. Green<br>454 West Woodbury Road<br>Altadena, CA 91001                                                              | 4                        | R&D Associates<br>ATTN: Jerry Carpenter<br>Sheldon Schuster<br>J.G. Lewis<br>Technical Library<br>P.O. Box 9695<br>Marina del Rey, CA 90291                   |
| 1                        | The Mitre Corporation<br>ATTN: Library<br>P.O. Box 208<br>Bedford, MA 01730                                                                                 | 1                        | R&D Associates<br>ATTN: Henry Cooper<br>Suite 500<br>1401 Wilson Boulevard<br>Arlington, VA 22209                                                             |

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                               | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                                                                   |
|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1                        | The Rand Corporation<br>ATTN: C.C. Mow<br>1700 Main Street<br>Santa Monica, CA 90406                                                              | 7                        | TRW Systems Group<br>ATTN: Paul Lieverman<br>Benjamin Sussholtz<br>Norm Lipner<br>William Rowan<br>Jack Farrell<br>Pravin Bhutta<br>Tech Info Ctr/S-1930<br>One Space Park<br>Redondo Beach, CA 92078 |
| 2                        | Science Applications, Inc.<br>ATTN: John Cockayne<br>William Layson<br>1651 Old Meadow Road<br>McLean, VA 22102                                   |                          |                                                                                                                                                                                                       |
| 1                        | Science Applications, Inc.<br>Suite 120<br>2450 Washington Avenue<br>San Leandro, CA 94577                                                        | 1                        | TRW Systems Group<br>San Bernardino Operations<br>ATTN: Greg Hulcher<br>P.O. Box 1310<br>San Bernardino, CA 92402                                                                                     |
| 2                        | Science Applications, Inc.<br>ATTN: Technical Library<br>Michael McKay<br>P.O. Box 2351<br>La Jolla, CA 92038                                     | 2                        | Union Carbide Corporation<br>Holifield National Laboratory<br>Civil Defense Research Proj<br>ATTN: Doc Control for Tech I<br>P.O. Box X<br>Oak Ridge, TN 37830                                        |
| 4                        | Systems, Science & Software<br>ATTN: Donald R. Grine<br>Ted Cherry<br>Thomas D. Riney<br>Technical Library<br>P.O. Box 1620<br>La Jolla, CA 92037 | 1                        | Universal Analytics, Inc.<br>ATTN: E.I. Field<br>7740 W. Manchester Blvd.<br>Playa del Rey, CA 90291                                                                                                  |
| 3                        | Terra Tek, Inc.<br>ATTN: Sidney Green<br>A.H. Jones<br>Technical Library<br>420 Wakara Way<br>Salt Lake City, UT 84108                            | 1                        | Weidlinger Assoc. Consulting<br>ATTN: M.L. Baron<br>110 East 59th Street<br>New York, NY 10022                                                                                                        |
| 2                        | Tetra Tech, Inc.<br>ATTN: Li-San Hwang<br>Technical Library<br>630 North Rosemead Blvd.<br>Pasadena, CA 91107                                     | 1                        | Westinghouse Electric Co.<br>Marine Division<br>ATTN: W.A. Votz<br>Hendy Avenue<br>Sunnyvale, CA 94008                                                                                                |
|                          |                                                                                                                                                   | 2                        | Battelle Memorial Institute<br>ATTN: Technical Library<br>R.W. Klingsmith<br>505 King Avenue<br>Columbus, OH 43201                                                                                    |

# DISTRIBUTION LIST

| <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                                    | <u>No. of<br/>Copies</u> | <u>Organization</u>                                                                                                                                                                                                                                                                                          |
|--------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1                        | California Institute of<br>Technology<br>ATTN: T.J. Ahrens<br>1201 E. California Blvd.<br>Pasadena, CA 91109                                                           | 1                        | University of Dayton<br>Industrial Security<br>Super. KL-505<br>ATTN: H.F. Swift<br>300 College Park Avenue<br>Dayton, OH 45409                                                                                                                                                                              |
| 2                        | Denver Research Institute<br>University of Denver<br>ATTN: Mr. J. Wisotski<br>Technical Library<br>P.O. Box 10127<br>Denver, CO 80210                                  | 1                        | University of Illinois<br>Consulting Engineering Services<br>ATTN: Nathan M. Newmark<br>1211 Civil Engineering Bldg<br>Urbana, IL 61801                                                                                                                                                                      |
| 3                        | ITT Research Institute<br>ATTN: Milton R. Johnson<br>R.E. Welch<br>Technical Library<br>10 West 35th Street<br>Chicago, IL 60616                                       | 2                        | The University of New Mexico<br>The Eric H. Wang Civil<br>Engineering Research Facility<br>ATTN: Larry Bickle<br>Neal Baum<br>University Station<br>Box 188<br>Albuquerque, NM 87131                                                                                                                         |
| 2                        | Lovelace Foundation for<br>Medical Education<br>ATTN: Asst. Dir of Research/<br>Robert K. Jones<br>Technical Library<br>5200 Gibson Blvd., SE<br>Albuquerque, NM 87109 | 2                        | Washington State University<br>Administration Office<br>ATTN: Arthur Miles Hohorf<br>George Duval<br>Pullman, WA 99163                                                                                                                                                                                       |
| 1                        | Massachusetts Institute of Tech.<br>Aeroelastic & Structures Rsch Lab<br>ATTN: Dr. E.A. Witmer<br>Cambridge, MA 02139                                                  |                          | <u>Aberdeen Proving Ground</u><br>Dir, USAMSAA<br>ATTN: DRXSY-D<br>DRXSY-MP, H. Cohen<br>Ben Cummings<br>M. Reches<br>Cdr, USATECOM<br>ATTN: DRSTE-TO-F<br>Dir, Wpns Sys Concepts Team<br>Bldg. E3516, EA<br>ATTN: DRDAR-ACW<br>Cdr, USA Ordnance Ctr & School<br>ATTN: ATSL-CD-CS/LT C.E. Tate<br>Bldg 3072 |
| 2                        | Southwest Research Institute<br>ATTN: Dr. W.E. Baker<br>A.B. Wenzel<br>8500 Culebra Road<br>San Antonio, TX 78206                                                      |                          |                                                                                                                                                                                                                                                                                                              |
| 2                        | SRI International<br>ATTN: Dr. G.R. Abrahamson<br>Carl Peterson<br>333 Ravenswood Avenue<br>Menlo Park, CA 94025                                                       |                          |                                                                                                                                                                                                                                                                                                              |

### USER EVALUATION OF REPORT

Please take a few minutes to answer the questions below; tear out this sheet and return it to Director, US Army Ballistic Research Laboratory, ARRADCOM, ATTN: DRDAR-TSB, Aberdeen Proving Ground, Maryland 21005. Your comments will provide us with information for improving future reports.

1. BRL Report Number \_\_\_\_\_

2. Does this report satisfy a need? (Comment on purpose, related project, or other area of interest for which report will be used.)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

3. How, specifically, is the report being used? (Information source, design data or procedure, management procedure, source of ideas, etc.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

4. Has the information in this report led to any quantitative savings as far as man-hours/contract dollars saved, operating costs avoided, efficiencies achieved, etc.? If so, please elaborate.  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

5. General Comments (Indicate what you think should be changed to make this report and future reports of this type more responsive to your needs, more usable, improve readability, etc.) \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

6. If you would like to be contacted by the personnel who prepared this report to raise specific questions or discuss the topic, please fill in the following information.

Name: \_\_\_\_\_

Telephone Number: \_\_\_\_\_

Organization Address: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

DATE  
FILMED  
-8

