

AD-A104 692

HORNER AND SHIFRIN INC ST LOUIS MO
NATIONAL DAM SAFETY PROGRAM. LAKE POST COMMONS DAM (NO 11278), --ETC(U)
OCT 80
DACW43-80-C-0063

F/8 13/13

NL

UNCLASSIFIED

1 OF 1
AD A
104692

END
DATE
FILMED
10-81
DTIC

LEVEL

12

3 MISSOURI - KANSAS CITY BASIN,

2 LAKE POST COMMONS DAM,

4 ST. LOUIS COUNTY, MISSOURI .

MO 11278

DTIC
ELECTED
SEP 28 1981
H1

AD A104692

PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM



United States Army
Corps of Engineers
... Serving the Army
... Serving the Nation

St. Louis District

"Original contains color
plates: All DTIC reproductions
will be in black and
white"

THIS REPORT IS THE PROPERTY OF THE U.S. ARMY ENGINEER DISTRICT, ST. LOUIS.
IT IS LOANED TO YOU AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT PERMISSION IN WRITING FROM THE U.S. ARMY ENGINEER DISTRICT, ST. LOUIS.

PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

81 9 28 071

OCTOBER 1980

DISTRIBUTION STATEMENT A
Approved for public release;
Distribution Unlimited

FILE COPY

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A104692	
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Lake Post Commons Dam (MO 11278) St. Louis County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
7. AUTHOR(s) Horner & Shifrin, Inc.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) DACW43-80-C-0063
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) National Dam Safety Program. Lake Post Commons Dam (MO 11278), Missouri - Kansas City Basin, St. Louis County, Missouri.		12. REPORT DATE October 1980
16. DISTRIBUTION Phase I Inspection Report.		13. NUMBER OF PAGES Approximately 50
18. SUPPLEMENTARY NOTES Approved for release; distribution unlimited.		15. SECURITY CLASS. (of this report) UNCLASSIFIED DECLASSIFICATION/DOWNGRADING SCHEDULE
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

412555

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

ETI

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

MISSOURI - KANSAS CITY BASIN

LAKE POST COMMONS DAM

ST. LOUIS COUNTY, MISSOURI

MO 11278

PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM



**United States Army
Corps of Engineers**

*... Serving the Army
... Serving the Nation*

St. Louis District

PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

OCTOBER 1980



DEPARTMENT OF THE ARMY

ST. LOUIS DISTRICT, CORPS OF ENGINEERS

210 TUCKER BOULEVARD, NORTH

ST. LOUIS, MISSOURI 63101

REF ID:
ATTENTION ON

LMSED-P

SUBJECT: Lake Post Commons Dam, MO 11278, Phase I Inspection Report

This report presents the results of field inspection and evaluation of the Lake Post Commons Dam (MO 11278):

It was prepared under the National Program of Inspection of Non-Federal Dams.

This dam has been classified as unsafe, non-emergency by the St. Louis District as a result of the application of the following criteria:

- 1) Spillway will not pass 50 percent of the Probable Maximum Flood without overtopping the dam.
- 2) Overtopping of the dam could result in failure of the dam.
- 3) Dam failure significantly increases the hazard to loss of life downstream.

SUBMITTED BY:

SIGNED

Chief, Engineering Division

30 OCT 1960

Date _____

APPROVED BY:

SIGNAL

Colonel, CE, District Engineer

30 OCT 198

Date _____

Association For AIDS Child Project B 1500 Broadway New York, N.Y. 10018	☒ ☐ ☐
By _____	
Distribution/	
Availability Codes	
Dist Avail and/or	
Special	
A-27	

LAKE POST COMMONS DAM
MISSOURI INVENTORY NO. 11278
ST. LOUIS COUNTY, MISSOURI

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

PREPARED BY:

HORNER & SHIFRIN, INC.
5200 OAKLAND AVENUE
ST. LOUIS, MISSOURI 63110

FOR:

U. S. ARMY ENGINEER DISTRICT, ST. LOUIS
CORPS OF ENGINEERS

OCTOBER 1980

HS-8011

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam:	Lake Post Commons Dam
State Located:	Missouri
County Located:	St. Louis
Stream:	Unnamed Tributary of Bonhomme Creek
Date of Inspection:	10 July 1980

The Lake Post Commons Dam was visually inspected by engineering personnel of Horner & Shifrin, Inc., Consulting Engineers, St. Louis, Missouri. The purpose of this inspection was to assess the general condition of the dam with respect to safety and, based upon this inspection and available data, determine if the dam poses a hazard to human life or property.

The following summarizes the findings of the visual inspection and the results of certain hydrologic/hydraulic investigations performed under the direction of the inspection team. Based on the visual inspection and the results of the hydrologic/hydraulic investigations, the present general condition of the dam is considered to be satisfactory. However, the following deficiencies were noticed during the inspection and are considered to have an adverse effect on the overall safety and future operation of the dam:

1. Erosion has created several gullies up to about 3 feet in depth in the downstream face of the dam below the lower berm adjacent to the spillway discharge structure. Loss of embankment material by erosion can be detrimental to the stability of the dam.
2. Several small trees exist at the waterline on the upstream face of the dam. A few patches of brushy undergrowth were also found on the downstream slope. Tree roots can provide passageways for lake seepage which could lead to a piping condition (progressive internal erosion) resulting in failure of the dam. Brushy undergrowth may conceal animal burrows which could also provide passageways for lake seepage.


According to the criteria set forth in the recommended guidelines, the magnitude of the spillway design flood for the Lake Post Commons Dam, which is classified as intermediate in size and of high hazard potential, is specified to be the Probable Maximum Flood (PMF). The Probable Maximum Flood (PMF) is the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

Results of a hydrologic/hydraulic analysis indicated that the spillway is inadequate to pass lake outflow resulting from a storm of PMF magnitude without overtopping the dam. The spillway is capable of passing lake outflow resulting from the one percent probability (100-year frequency) flood and the outflow corresponding to about 35 percent of the PMF. According to the St. Louis District, Corps of Engineers, the length of the downstream damage zone, should failure of the dam occur, is estimated to be two miles. Accordingly, within the possible damage zone are three dwellings, several buildings, a concrete ready-mix plant and a facility for bulk storage of gasoline and oil.

A review of available data did not disclose that seepage or stability analyses of this dam were performed. This is considered a deficiency and should be rectified.

It is recommended that the Owner take the necessary action within a reasonable time to correct or control the deficiencies and safety defects reported herein. The provision of additional spillway capacity should be pursued on a high priority basis.


Ralph E. Sauthoff
P. E. Missouri E-19090


Albert B. Becker, Jr.
P. E. Missouri E-9168



OVERVIEW LAKE POST COMMONS DAM

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
LAKE POST COMMONS DAM - MO 11278

TABLE OF CONTENTS

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
SECTION 1 - PROJECT INFORMATION		
1.1	General	1-1
1.2	Description of Project	1-1
1.3	Pertinent Data	1-4
SECTION 2 - ENGINEERING DATA		
2.1	Design	2-1
2.2	Construction	2-2
2.3	Operation	2-3
2.4	Evaluation	2-3
SECTION 3 - VISUAL INSPECTION		
3.1	Findings	3-1
3.2	Evaluation	3-4
SECTION 4 - OPERATIONAL PROCEDURES		
4.1	Procedures	4-1
4.2	Maintenance of Dam	4-1
4.3	Maintenance of Operating Facilities	4-1
4.4	Description of Any Warning Systems in Effect	4-1
4.5	Evaluation	4-2

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
----------------------	--------------	-----------------

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1	Evaluation of Features	5-1
-----	------------------------	-----

SECTION 6 - STRUCTURAL STABILITY

6.1	Evaluation of Structural Stability	6-1
-----	------------------------------------	-----

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1	Dam Assessment	7-1
7.2	Remedial Measures	7-2

LIST OF PLATES

<u>Plate No.</u>	<u>Title</u>
1	Regional Vicinity Map
2	Lake Watershed Map
3	Dam Embankment*
4	Section Details*
5	Spillway Details*
6	Energy Dissipator*
7	Site Plan*
8	Dam Cross-Section and Spillway Profile
9	Boring Logs**
10	Boring Logs**
11	Boring Logs**

* Construction plans prepared by Reitz & Jens, Inc., 1975.

** Prepared by Reitz & Jens, Inc., 1974.

APPENDIX A - INSPECTION PHOTOGRAPHS

<u>Page No.</u>	<u>Title</u>
A-1 thru A-4	Inspection Photographs

APPENDIX B - HYDROLOGIC AND HYDRAULIC ANALYSES

<u>Page No.</u>	<u>Title</u>
B-1 and B-2	Hydrologic & Hydraulic Computations
B-3 thru B-5	Computer Input Data
B-6 thru B-10	Computer Output Data
B-10	Lake Surface Area, Storage Volume and Elevation; Summary of Dam Safety Analysis

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
LAKE POST COMMONS DAM - MO 11278

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority. The National Dam Inspection Act, Public Law 92-367, dated 8 August 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, directed that a safety inspection of the Lake Post Commons Dam be made.

b. Purpose of Inspection. The purpose of this visual inspection was to make an assessment of the general condition of the dam with respect to safety and, based upon available data and this inspection, determine if the dam poses a hazard to human life or property.

c. Evaluation Criteria. This evaluation was performed in accordance with the "Phase I" investigation procedures as prescribed in "Recommended Guidelines for Safety Inspection of Dams", Appendix D to "Report to the Chief of Engineers on the National Program of Inspection of Non-Federal Dams", dated May 1975.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances. The Lake Post Commons Dam is an earthfill type embankment rising approximately 40 feet above the natural streambed at the downstream toe of the barrier. The embankment has an upstream slope above the waterline of approximately 1v on 2.5h, a crest width

of about 17 feet, and a downstream slope that varies from 1v on 2.8h to 1v on 2.1h. There are two berms in the downstream face of the dam; the upper berm is approximately 8 feet wide and the lower berm is about 23 feet wide. The length of the dam is approximately 400 feet. A plan and a profile of the dam are shown on the construction plans prepared by Reitz & Jens, Inc., and are included as Plates 3 and 4, respectively. A cross-section of the dam as surveyed during the inspection is shown on Plate 8. At normal pool elevation the reservoir impounded by the dam occupies approximately 5 acres.

The spillway, a 4-foot square reinforced concrete drop inlet structure with a 30-inch diameter reinforced concrete outlet pipe, is located within the lake to the right of the center of the dam. A concrete, energy dissipating structure is located at the downstream end of the spillway outlet pipe. Flow passing the energy dissipator discharges to the original stream channel at the toe of the dam. According to the construction plans, a 12-inch lake drawdown pipe enters the drop inlet about 21 feet below the top of the inlet. The 12-inch pipe is controlled by a gate valve located within the structure. Details of the spillway, energy dissipator and drawdown pipe are shown on the construction plans and are included as Plates 6 and 7. A 12-inch concrete pipe storm drainage sewer, which appears to serve the area southeast of the dam, also discharges flow to the channel at the toe of the dam. A concrete headwall protects the bank at the sewer outlet.

b. Location. The dam is located on an unnamed tributary of Bonhomme Creek, about 0.8 mile southwest of the intersection of Clarkson Road and U.S. Highway 40 and approximately 1.4 mile south of Chesterfield, Missouri, as shown on the Regional Vicinity Map, Plate 1. The lake and dam are located within the residential development known as Chesterfield Village. The dam is located in U.S. Survey 2002, approximately 100 feet east and 1,700 feet south of the northwest corner.

c. Size Classification. The size classification based on the height of the dam and storage capacity, is categorized as intermediate (per Table 1, Recommended Guidelines for Safety Inspection of Dams).

d. Hazard Classification. The Lake Post Commons Dam, according to the St. Louis District, Corps of Engineers, has a high hazard potential, meaning that if the dam should fail, there may be loss of life, serious damage to homes, or extensive damage to agricultural, industrial and commercial facilities, important public utilities, main highways, or railroads. The estimated flood damage zone, should failure of the dam occur, as determined by the St. Louis District, extends two miles downstream of the dam. Within the possible flood damage zone are three dwellings, several buildings, a concrete ready-mix plant and a facility for bulk storage of gasoline and oil. Those features lying within the downstream damage zone reported by the Corps of Engineers, St. Louis District, were verified by the inspection team.

e. Ownership. The lake and dam are owned by the Chesterfield Village Association, a Division of Sachs Properties, Inc., Post Office Box 7104, St. Louis, Missouri 63177. Mr. David B. Rosenberg, Development Manager for Sachs Properties, Inc., is the Owner's representative.

f. Purpose of Dam. The dam impounds water for stormwater retention and for recreational use.

g. Design and Construction History. Lake Post Commons is located within Chesterfield Village, a development which includes a large shopping center and numerous condominiums. A comprehensive study of the civil engineering aspects of the development of Chesterfield Village was prepared by Consoer Townsend & Associates, Consulting Engineers, St. Louis, Missouri, for Sachs Properties, the area developers. The study suggested the use of several lakes, including Lake Post Commons, to provide stormwater retention and to reduce erosion resulting from the increased runoff caused by the proposed development within Chesterfield Village.

In 1974 the developers retained Reitz & Jens, Inc., Consulting Engineers, St. Louis, Missouri, to prepare the Chesterfield Village Master Drainage plan for the area, which included Lake Post Commons.

Subsequently, plans for the construction of the dam for Lake Post Commons were prepared in 1975 by Reitz & Jens, Inc. Vic Koepke Excavating and Grading Company of Villa Ridge, Missouri constructed the dam, also during 1975.

h. Normal Operational Procedure. The lake level is unregulated. Lake outflow is governed by the capacity of a drop inlet type spillway.

1.3 PERTINENT DATA

a. Drainage Area. The area tributary to the lake is in various stages of commercial and residential development although most of the residential type development has been completed. Office buildings and two and three story townhouse style condominiums have been constructed in the area south and east of the outer road, Chesterfield Village Parkway, for the Chesterfield Mall Shopping Center. North of the outer road the area is being developed as part of the shopping center with commercial type buildings and parking lots occupying approximately 54 percent of the drainage area. There is some ground without improvements that lies adjacent to the north side of the lake; however this area is relatively small. For the hydrologic/hydraulic investigations performed under the direction of the inspection team and based on existing conditions, the following classes of land use and their respective percents of imperviousness were assumed:

<u>Description</u>	<u>Percent Impervious</u>
Commercial (65.4 Ac.)	55
Residential (42.5 Ac.)	40
Lake (4.5 Acres)	100
Unimproved (8.1 Ac.)	10

Of the total watershed, approximately 121 acres, and based on the above land use and percents of imperviousness, 49 percent of the total area was assumed to be impervious. The watershed area is outlined on Plate 2.

b. Discharge at Damsite.

- (1) Estimated known maximum flood at damsite ... No data available
- (2) Spillway capacity ... 129 cfs.

c. Elevation (Ft. above MSL). The following elevations were determined by survey and are based on the elevation of the top of the drop inlet spillway

structure as shown on Sheet 3 (Plate 5) of the construction plans prepared by Reitz & Jens, Inc.

- (1) Observed pool ... 553.0
- (2) Normal pool ... 553.0
- (3) Spillway crest ... 553.0
- (4) Maximum experienced pool ... No data available
- (5) Top of dam ... 559.9 (min.)
- (6) Streambed at centerline of dam ... 519+ (per construction plans)
- (7) Maximum tailwater ... Unknown
- (8) Observed tailwater ... None

d. Reservoir.

- (1) Length at normal pool (Elev. 553.0) ... 1,100 ft.
- (2) Length at maximum pool (Elev. 559.9) ... 1,300 ft.

e. Storage.

- (1) Normal pool ... 48 ac. ft.
- (2) Top of dam (incremental) ... 39 ac. ft.

f. Reservoir Surface.

- (1) Normal pool ... 5 acres
- (2) Top of dam (incremental) ... 2 acres

g. Dam. The height of the dam is defined to be the overall vertical distance from the lowest point of foundation surface at the downstream toe of the barrier, to the top of the dam.

- (1) Type ... Earthfill, homogeneous*
- (2) Length ... 400 ft.
- (3) Height ... 40 ft.
- (4) Top width ... 17 ft.

*Per construction plans prepared by Reitz & Jens, Inc.

(5) Side slopes

- a. Upstream ... 1v on 2.5h (above waterline)
- b. Downstream ... 1v on 2.1h; 1v on 2.8h; 1v on 2.3h (23-foot berm at Elev. 542₊; 8-foot berm at Elev. 549₊)

(6) Slope protection

- a. Upstream ... Grass and cellular precast concrete blocks
- b. Downstream ... Grass

h. Spillway.

- (1) Type ... Uncontrolled, 4-foot square drop inlet
- (2) Location ... Sta. 2+07, 48 feet upstream of dam centerline (in lake)
- (3) Crest ... Elevation 553.0

i. Emergency Spillway ... None

j. Lake Drawdown Facility. According to the construction plans a 12-inch diameter cast-iron pipe enters the drop inlet spillway at a point 21 feet below the top of the inlet. Flow is controlled by a cast-iron gate valve located within the drop inlet.

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

a. Subsurface Investigations. In 1974, test borings were drilled at six locations along the alignment of the dam by Reitz and Jens, Inc., Consulting Engineers. The location of the borings are indicated on Sheet 1, Reference Plate 3, of the construction plans. In addition to classifying the type of material encountered during drilling, the boring logs also present the results of standard penetration and shear vane tests performed on soil samples, as well as the natural moisture content of each of the soil samples examined. The boring logs are included as Plates 9 through 11.

b. Dam. The dam was apparently designed as a compacted earthfill embankment. The seepage cutoff trench was specified to have a minimum width of 14 feet, one scraper width, and have a minimum depth of 10 feet below the original ground surface. Details of the embankment design are shown on Sheet 2, Reference Plate 4, of the construction plans.

Records of the embankment design were unavailable to the inspection team. According to information provided by Reitz and Jens, Inc., the design of the dam was based on their experience with dams of similar size and materials that were constructed in this same general area.

c. Spillway. A drop inlet type spillway with a 30-inch diameter outlet pipe was designed to accommodate lake outflow. Based on design data included in the Master Drainage Plan Report prepared by Reitz & Jens in 1974, the spillway was sized to accommodate runoff from a 100-year frequency, 1-hour duration rainfall, assuming full development of the drainage area. This condition would produce a peak discharge of about 82 cfs. In addition, the dam was designed to accommodate the runoff due to a 100-year, 30-minute duration rainfall, assuming a blocked spillway outlet. This condition would produce a high water level at elevation 556.6 approximately 3.4 feet lower than the minimum top of dam elevation shown on the construction plans.

An outflow structure, with provisions to dissipate flow discharge energy, was provided at the downstream end of the discharge pipe. Three soil-bentonite type anti-seepage collars were provided along the alignment of the spillway outlet pipe. Details of the anti-seepage collars, the drop-inlet spillway, and the energy dissipator, are shown on Sheets 2 through 4, Reference Plates 4 through 6, of the construction plans.

d. Appurtenances. A 12-inch diameter lake drawdown pipe enters the drop inlet, presumably at a point about 21 feet below the inlet top. Flow is controlled by a gate valve located in the spillway inlet structure. Details of the drawdown pipe and valve are shown on Sheet 3, Reference Plate 5, of the construction plans. An 8-inch diameter sanitary sewer traverses the dam along the upper berm in the downstream face. The sanitary sewer enters a small lift station located about 140 west of the right, or north, abutment of the dam. A plan and profile of the sewer are shown on Sheets 1 and 2 respectively, Reference Plates 3 and 4, of the construction plans.

2.2 CONSTRUCTION

As previously indicated, the dam was constructed in 1975 by the Vic Koepke Excavating and Grading Company of Villa Ridge, Missouri. Surveillance of construction activities was performed by Reitz and Jens, Inc.

According to Phil Jozwiak, project engineer for Reitz & Jens at the time the dam was constructed, the dam and spillway structures were constructed in substantial accordance with the construction plans. According to the General Notes shown on Sheet 4 of the plans, compaction of earth for the embankment was specified to be a minimum of 35 percent of the maximum dry density as determined by ASTM D-1557 (Modified Proctor). A review of construction records indicated that 111 compaction tests were made and that 8 of these tests were less than 85 percent, 103 were greater than 85 percent, and that the average of all tests was 88.2 percent.

2.3 OPERATION

The lake level is uncontrolled and governed by the elevation of the top of the drop inlet type spillway. No indication was found that the dam has been overtopped. The representative of the Owner reported that the dam has never been overtopped, but information regarding the highest observed lake level was indefinite and of no significant value.

2.4 EVALUATION

a. Availability. Seepage and stability analysis for assessing the design of the dam were unavailable. Data available is limited to information shown on the construction plans prepared by Reitz & Jens, Inc., in 1975 and on the boring logs obtained by Reitz & Jens in 1974 for design of the dam. Hydraulic/hydrologic data for assessing the design of the spillway and top of dam elevation were available for review.

b. Adequacy. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record. The information shown on the logs of the test borings may have to be supplemented by additional borings to obtain undisturbed samples of foundation materials for determination of necessary shear strengths to be utilized in the stability analyses.

The hydraulic/hydrologic data provided for design of the dam and spillway is considered adequate for their intended purpose. The hydrologic criteria used for the design of the dam and spillway was approved by St. Louis County, Department of Public Works, Division of Wastewater Control, in April of 1974. However, the design of the spillway does not meet the criteria specified in the preceding recommended guidelines. According to the guidelines, the spillway design flood should be the probable maximum flood of 24-hour duration instead of the 100-year frequency storm of 1-hour duration used.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General. A visual inspection of the Lake Post Commons Dam was made by Horner & Shifrin engineering personnel, R. E. Sauthoff, Civil Engineer, and A. B. Becker, Jr., Civil and Soils Engineer, on 10 July 1980. An examination of the dam area was also made by an engineering geologist, Jerry D. Higgins, Ph.D., a consultant retained by Horner & Shifrin for the purpose of assessing the site geology. Also examined at the time of the inspection, were the areas and features below the dam within the potential flood damage zone. Photographs of the dam taken at the time of the inspection are included on pages A-1 through A-4 of Appendix A. The locations of the photographs taken during the inspection are indicated on Plate 3.

b. Site Geology. The Lake Post Commons Dam is located near the border of the Ozark Plateaus Physiographic Province and Dissected Till Plains section of the Central Lowlands Province. The topography is rolling, but urban development has modified much of the original land surface in the vicinity of the lake. There is, nevertheless, approximately 120 feet of relief between the reservoir and the surrounding drainage divide. The bedrock consists of gently northward-dipping Mississippian-age limestones of probably the Burlington-Keokuk formations. No faulting was observed or has been reported in the vicinity of the site.

The Burlington-Keokuk formations consist of light-to-buff colored, coarsely crystalline, medium-bedded limestones. The limestones are fossiliferous and contain abundant chert in the form of layers and nodules. The bedrock is highly susceptible to solution weathering. Sinkholes, caves, and solution-enlarged joints or bedding planes are common and often cause severe leakage of water impoundments. The contact between the bedrock and the overlying soils in the area is very irregular, and bedrock pinnacles or bedrock remnants surrounded by residual clays frequently occur. Solution features, especially sinkholes, are abundant in the general area. None were observed in the immediate area of the dam or reservoir; however, they could be masked by the deep soil deposits.

The unconsolidated surficial materials consist primarily of cherty clay residuum overlain by the deep, silty soils of the Memphis series. The residual soils were formed by in-place weathering of limestone bedrock. According to the Unified Soil Classification System, the soils are considered to be CL-ML material. They consist of red, blocky, cherty clays, are moderately permeable, and often cause seepage from water impoundments. Seepage is generally most severe in areas of very thin soil cover. The Memphis soils overlying the residuum were derived from loess deposits. They consist of dark yellowish-brown, friable silt (ML) in the upper layers, becoming more clayey (ML-CL) with depth. These soils are generally susceptible to erosion, especially on slopes. Much of the area has been disrupted by grading and landscaping which has mixed the loessal soils and residuum.

The most significant geologic conditions at the site are the karst bedrock conditions which may cause reservoir leakage, and erosion of the dam embankment material.

c. Dam. The visible portions of the upstream and downstream faces of the dam (see Photos 2 and 3) as well as the dam crest, were inspected and appeared to be in sound condition. No significant settlement of the crest, sloughing of the slopes, or misalignment of the dam were noted. However, several gullies up to 3 feet in depth and 10 feet in width had been eroded into the downstream face of the embankment below the lower berm in the vicinity of the spillway outlet structure. The erosion appeared to be due to storm water runoff. One gulley was filled with large pieces of concrete rubble (see Photo 8), apparently in an attempt to control the erosion. The visual inspection and survey of the dam indicated elevations along the crest are very near the elevations specified on the construction plans prepared by Reitz & Jens. However, the configuration of the cross-section determined by survey was somewhat different than that shown on the construction plans. The cross-section determined by survey is shown on Plate 8. The sanitary sewer traversing the dam crest was found to be in about the same location as shown on the plans.

The upstream face of the dam was protected from erosion by fescue grass and lespedeza cover, as well as cellular concrete blocks (see Photo 7) which extended about 2 feet above the normal waterline. The grass was as high as 3 feet, and several small willow trees were present along the dam at the waterline. A 6-foot wide asphalt walkway traverses the crest of the dam. The downstream slope had a few patches of brushy undergrowth, but was mostly covered with lespedeza and fescue grass up to 3 feet high. Examination of a soil sample obtained from the downstream face of the dam indicated the material to be a silty lean clay (CL) of low-to-medium plasticity.

The drop inlet spillway structure (see Photo 4) could not be thoroughly inspected because of its lake location; however, the visible portions of the structure appeared to be in satisfactory condition. A large piece of driftwood was lodged on top of the spillway grate at the time of inspection. The location of the structure appeared to be approximately as drawn on the construction plans by Reitz & Jens.

The spillway outlet pipe and the concrete energy dissipator structure (see Photo 5) were inspected and found to be in sound condition. However, due to flow passing the spillway, the lower submerged portions of the energy dissipator could not be inspected. In general, the portions of the spillway which were examined appeared to have been built in accordance with the construction plans. An exception was found to be the level of the riprap immediately downstream of the energy dissipator which was about 18 inches below the outlet end of the dissipator rather than at the same level as the outlet, as indicated on the construction plans. However, there was no evidence of erosion of the downstream channel near the energy dissipator. The concrete headwall for the 12-inch diameter storm sewer (see Photo 6) although overgrown with brush, also appeared to be in satisfactory condition.

d. Appurtenant Structures. No appurtenant structures were observed at the dam site.

e. Downstream Channel. The original stream channel is unimproved. The channel is an irregular section and for the most part tree-lined. The channel joins Bonhomme Creek at the edge of the Missouri River flood plain about 1.3 miles downstream of the dam.

f. Reservoir. The banks surrounding the lake are mostly grass covered and well maintained. Several areas about the lake are protected from erosion by limestone riprap. An asphalt paved walkway about 6 feet wide traverses the perimeter of the lake. At the time of the inspection the lake was at normal pool and cloudy.

A report titled "Subsurface Investigations and Erosion Control Recommendations for the Development of Lake 1, Chesterfield Village" was prepared for the Owner by Reitz & Jens, Inc., in 1975. The report contains recommendations for controlling erosion of the lake shoreline and for minimizing erosion of the ground surface within the watershed by overland drainage. The amount of sediment within the lake could not be determined at the time of the inspection. However, judging by the grass and riprap protection evident about the lake as well as the concern shown by the Owner to prevent erosion of the lake shoreline and drainage area, sedimentation of the lake is believed to be minimal.

3.2 EVALUATION

The deficiencies observed during this inspection and noted herein, are not considered of significant importance to warrant immediate remedial action. The concrete block type slope protection on the upstream face of the dam is considered adequate to prevent erosion by wave action or by a fluctuating lake level.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

The spillway is uncontrolled. The lake surface level is governed by precipitation runoff, evaporation, seepage, and the capacity of the uncontrolled spillway.

4.2 MAINTENANCE OF DAM

According to Mr. David Rosenberg, Development Manager for Sachs Properties, the dam is inspected every three to four months. Mr. Rosenberg did report that a "wet spot" was noticed on the downstream face of the dam sometime earlier in the year and that the condition was being investigated. No evidence of seepage at the downstream slope was observed during the visual inspection.

Judging by the small trees present on the upstream face of the dam, the 3-foot high grass on the slopes of the dam, and the eroded areas of the downstream face of the dam below the lower berm, it appears that routine maintenance of the dam proper could be improved.

4.3 MAINTENANCE OF OPERATING FACILITIES

With the exception of the lake drawdown valve, no outlet facilities requiring operation exist at this dam. A representative (name unknown) of the Owner reported that the valve had been leaking and that measures were being taken to repair it. There is no reservoir regulation plan.

4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

The inspection did not reveal the existence of a dam failure warning system.

4.5 EVALUATION

It is recommended that maintenance of the dam also include removal of trees and periodic cutting of grass on the slopes. Measures should also be taken to prevent further erosion of the downstream face of the dam below the lower berm. It is also recommended that a detailed inspection of the dam be instituted on a regular basis by an engineer experienced in the design and construction of dams and that records be kept of all inspections made and remedial measures taken.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

a. Design Data. Hydraulic/Hydrologic data pertinent to the design of the dam and spillway is discussed in Section 2, paragraph 2.1c.

b. Experience Data. The drainage area and lake surface area were developed using topographic data shown on the construction plans and the 1954 USGS Chesterfield, Missouri, Quadrangle Map, photo revised 1968 and 1974. The proportions and dimensions of the spillway and dam were developed from surveys made during the inspection and from data shown on the construction plans. Records of rainfall, streamflow, or flood data for the watershed were not available.

Due to the fact that the watershed for this reservoir is small and since there is no history of excessive reservoir leakage that would adversely affect the normal operating level of the lake, the lake level was assumed to be at normal pool as a result of antecedent storms prior to occurrence of the PMF and the probabilistic storm.

According to the St. Louis District, Corps of Engineers, the estimated flood damage zone, should failure of the dam occur, extends two miles downstream of the dam.

c. Visual Observations.

(1) The spillway, located to the left of the center of the dam, consists of a 48-inch square reinforced concrete drop inlet with a 30-inch diameter reinforced concrete outlet pipe extending through the dam. Flow from the outlet pipe enters a concrete energy dissipating structure which discharges to the original stream channel at the toe of the dam.

(2) According to the construction plans, a 12-inch diameter cast-iron pipe is provided for lake drawdown. The pipe enters the drop inlet structure 21 feet below the top of the inlet and is controlled by a valve installed within the structure.

d. Overtopping Potential. The spillway is inadequate to pass the probable maximum flood or 1/2 the probable maximum flood without overtopping the dam. The spillway is adequate, however, to pass the 1 percent probability (100-year frequency) flood without overtopping the dam. The results of the dam overtopping analyses are as follows:

(Note: The data appearing in the following table has been extracted from the computer output data appearing in Appendix B. Decimal values have been rounded to the nearest one-tenth in order to prevent assumption of unwarranted accuracy.)

<u>Ratio of PMF</u>	<u>Q-Peak Outflow (cfs)</u>	<u>Max. Lake W.S. Elev.</u>	<u>Max. Depth (Ft.) of Flow over Dam (Elev. 559.9)</u>	<u>Duration of Overtopping of of Dam (Hrs.)</u>
0.50	882	561.1	1.2	3.2
1.00	2,716	562.1	2.2	5.8
1 Percent Probability	125	557.0	0.0	0.0

Elevation 559.9 was found to be the lowest point in the dam crest. The flow safely passing the spillway just prior to overtopping amounts to approximately 129 cfs, which is the routed outflow corresponding to about 35 percent of the probable maximum flood inflow. During peak flow of the probable maximum flood, the greatest depth of flow over the dam is projected to be 2.2 feet and overtopping will extend across the entire length of the dam.

e. Evaluation of Overtopping Effect. Experience with embankments constructed of similar material (a silty lean clay of low-to-medium plasticity) to that used to construct this dam have shown evidence that the material under certain conditions, such as high velocity flow, can be very erodible. An example of such erosion is apparent below the lower berm in the downstream face of the dam. Such a condition exists during the PMF when large lake outflow, accompanied by high flow velocities, occurs. For the PMF condition where the depth of flow over the dam crest and the duration of flow over the dam, 2.2 feet (maximum) and 5.8 hours, respectively, are substantial, damage by erosion to the downstream face of the dam is expected. The extent

of this damage is not predictable within the scope of this report; however, there is a possibility that it could result in failure by erosion of the dam.

f. References. Procedures and data for determining the probable maximum flood, the 1 percent probability flood, and the discharge rating curves for flow passing the spillway are presented on pages B-1 and B-2 of Appendix B. Listings of the HEC-1 (Dam Safety Version) input data for both the probable maximum flood and the 1 percent probability flood are shown on pages B-3 through B-5. Computer output data, including unit hydrograph ordinates, tabulation of PMF rainfall, loss and inflow data are shown on pages B-6 through B-9; tabulation of lake surface area, elevation, and storage volume is shown on page B-10; and tabulations titled "Summary of Dam Safety Analysis" for the PMF and 1 percent probability (100-year frequency) flood are also shown on page B-10.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations. Visual observations of conditions which adversely affect the structural stability of the dam are discussed in Section 3, paragraph 3.1c.

b. Design and Construction Data. With the exception of information shown on the logs of test borings that were taken along the axis of the dam, no design data relating to the structural stability of the dam are known to exist. Available construction data are discussed in Section 2, paragraph 2.2. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.

c. Operating Records. With the exception of the valve on the lake drawdown pipe, no appurtenant structures or facilities requiring operation exist at this dam. According to the Owner's representative, no records are kept of the lake level, spillway discharge, dam settlement, or seepage.

d. Post Construction Changes. The Owner's representative also reported that to his knowledge no significant post construction changes have been made or have occurred which would affect the structural stability of the dam.

e. Seismic Stability. The dam is located within a Zone II seismic probability area. An earthquake of the magnitude that might occur in this area would not be expected to cause structural damage to a well constructed earth dam of this size provided that static stability conditions are satisfactory and conventional safety margins exist. However, it is recommended that the prescribed seismic loading for this zone be applied in any stability analyses performed for this dam.

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

a. Safety. A hydraulic analysis indicated that the spillway is capable of passing lake outflow of about 129 cfs without the level of the lake exceeding the low point in the top of the dam. A hydrologic analysis of the lake watershed area, as discussed in Section 5, paragraph 5.1d, indicates that for storm runoff of probable maximum flood magnitude, the lake outflow would be about 2,716 cfs, and that for the 1 percent probability (100-year frequency) flood, the lake outflow would be about 125 cfs.

Significant items noticed during the inspection that could adversely affect the safety of the dam consist of the embankment erosion at the downstream toe of the dam and the small trees and patches of undergrowth on the dam slopes.

Seepage and stability analyses of the dam were not available for review and therefore no judgment could be made with respect to the structural stability of the dam.

b. Adequacy of Information. Due to lack of sufficient detailed engineering design and construction data, the assessments reported herein were based largely on external conditions as determined during the visual inspection. The assessment of the hydrology of the watershed and capacities of the spillway were based on a hydraulic/hydrologic study as indicated in Section 5. Seepage and stability analyses comparable to the requirements of "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.

c. Urgency. The remedial measures recommend in paragraph 7.2 for the items concerning the safety of the dam noted in paragraph 7.1a should be accomplished within a reasonable time. The item recommended in paragraph 7.2a concerning provision of additional spillway capacity should be pursued on a high priority basis.

d. Necessity for Phase II. Based on the results of the Phase I inspection, a Phase II investigation is not recommended.

e. Seismic Stability. The dam is located within a Zone II seismic probability area. An earthquake of the magnitude that might occur in this area would not be expected to cause structural damage to a well constructed earth dam of this size provided that static stability conditions are satisfactory and conventional safety margins exist. However, it is recommended that the prescribed seismic loading for this zone be applied in any stability analyses performed for this dam.

7.2 REMEDIAL MEASURES

a. Recommendations. The following actions are recommended:

(1) Based upon criteria set forth in the recommended guidelines, spillway size and/or height of dam should be increased to pass lake outflow resulting from a storm of probable maximum flood magnitude.

(2) Obtain the necessary soil data and perform dam seepage and stability analyses in order to determine the structural stability of the dam for all operational conditions. Seepage and stability analyses should be performed by a qualified professional engineer experienced in the design and construction of earthen dams.

b. Operation and Maintenance (O & M) Procedures. The following O & M Procedures are recommended:


(1) Restore the eroded portions of the downstream face of the dam below the lower berm and provide some form of protection to prevent further erosion of the embankment by overland drainage. Loss of embankment by erosion can impair the stability of the dam.


(2) Remove the small trees and patches of undergrowth that may conceal animal burrows from the upstream and downstream faces of the dam. Tree roots and animal burrows can provide passageways for the lake seepage

that could lead to a piping condition (progressive internal erosion) and failure of the dam.

(3) Provide maintenance of all areas of the dam and spillway including periodic cutting of grass on the dam slopes, on a regularly scheduled basis in order to insure features of being in satisfactory operational condition.

(4) A detailed inspection of the dam should be instituted on a regular basis by an engineer experienced in the design and construction of dams. It is also recommended, for future reference, that records be kept of all inspections made and remedial measures taken.





* RUBBLE SLOPE PROTECTION


Chesterfield Village BM #54

Scale 1"=20'
Contour Interval = 2 ft.

LEGEND

- ⊙ - Location of Drilled Test Holes
- ⊕ - Location of Sounding Made by Electrical Resistivity
- 560- Final Contour
- 540- Existing Contour Line
- ⊙ - Water Level @ Permanent Pool Elevation 5530
- ⊕ - Approximate depth to weathered bedrock
- (BA) - Approximate 1/4 mi. to unweathered bedrock

Chesterfield Village Bench Mark #54
USGS Datum - Top of Concrete Monument 10 S of West End of Richman Rd Elev 585.86



CH
Designed by PAJ
Drawn by JCE
Checked by PAJ
Issue date 12/24/74

SHEET 1 OF 5

PLATE 3

INSPECTION PHOTO
LOCATION & KEY
(SEE APPENDIX A)


12

DATE	BY	NO.	REVISIONS
FINAL SURVEY	NO. OF STATIONS	NO. OF BRANCHES	NO. OF REVISIONS




CROSS SECTION THRU

DATE	BY	NO.	REVISIONS
ORIGINAL SURVEY	NO. OF STATIONS	NO. OF BRANCHES	NO. OF REVISIONS




PROFILE ALONG OF DAM



Minimum width at base = scraper width 14 ft.
Minimum depth from existing ground surface = 0

ION THRU SPILLWAY




SANITARY SEWER PROFILE





Horizontal Scale 1"=50' Vertical Scale 1"=10'




These plans represent final approval for LAKE I
and final approval for the temporary retention basin
in LAKE III.

SPILL CROSS SECTION FULL DOW



SCALE 1/2" = 1"






PLAN VIEW



END VIEW



END DETAIL

GRATE DETAIL

NOTE: ALL CONNECTIONS ARE TO BE MADE WITH GALVANIZED STEEL. ALL GALVANIZED STEEL TO BE THICKENED TO 1/8" MINIMUM AFTER

1/4" EXTENSION STEM - MUELLER FIG 2
BITUMEN COATED

STEM GUIDES - MUELLER
A-26452 SIZE #2
W/ BRONZE BUSHINGS

MUELLER A-2380-3 NRS. WITH FLANGEL
AND 1/4" END O-RING SEALS. GATE VALVE
BRONZE TRIMMED OR APPROX. EQUAL


WIGGINS 4-25-1/2" THINER
BARS AROUND WALL PIPE



SECTION C-C

1/2" LONG 1/4" DIA CI WALL PIPE W/ FLANGE
& BELL END (CLOW F. 420 OR
APPROVED EQUAL)


ELEV 538.0




These plans represent final approval for Lane I
and final approval for the temporary retention
basin in Lane II




APPROVED BY: [Signature]
Revised 8-6-75




PLAN VIEW



SECTION C-C



SECTION A-A



SECTION B-B


Outlet
11" S.P.W.


SIDE VIEW

DETAIL OF ROCK RIP-RAP

END VIEW







20' W. Easement to F.
Sewer Inc.
15' V.C.P.

4270N
4850E

4250N
5110E

4070N
5160E

3995N
5095E

3965N
4985E

3970N
4785E

548.4


551.4

552

520.4

546.7


542




CHESTERFIELD VILLAGE LAKE I SITE PLAN

REITZ & JENS, INC.


JUNE, 1976





DAM CROSS-SECTION STA. 2+32
SCALE: 1"=10' V., 1"=20' H.

NOTE: SPILLWAY PIPE PROFILE SUPERIMPOSED ON DAM SECTION.
ACTUAL LOCATION OF OUTLET PIPE AS NOTED.




S-SECTION STA. 1+90
LES: 1"=10' V., 1"=20' H.


LAKE POST COMMONS
DAM CROSS-SECTION &
SPILLWAY PROFILE

Horner & Shifrin, Inc. August 1980

PLATE 8



Vane Shear Strength
in ksf.



LEGEND

○ - Continuous or remolded vane shear strength.

⊕ - Peak vane shear strength.

+ - Peak vane shear strength in excess of 2.6 ksf.

$\frac{14}{12}$ - Standard Penetration Test. No. of blows over inches of penetration.

γ_d - Dry unit weight in pounds per cu.ft. on undisturbed Shelby tube samples.

W - Natural moisture content in percent.

Drilled 11/22/74

4325N
4550E
Elev. 547.9

Topsoil
16 14.6
12 Brown and gray silt


26 13.5
12 Brown silty clay

28 20.7
12

52 12.2
12

Reddish brown clay w/cherty limestone
rock fragments.

Vane Shear Strength
in ksf.



4" Continuous flight auger
refusal

Drilled 11/27/74

CHESTERFIELD VILLAGE
Lake I

BORING LOGS

Reitz & Jens, Inc.
Consulting Engineers

St. Louis, Mo.
December 1974

Fig. 2-1

PLATE 9

4100N
4600E

Elev. 547.8

550

Topsoil

545

Brown silt

$\frac{17}{12}$ 16.0

540

Brown silty clay

$\frac{24}{12}$ 22.5

535

Brown clayey silt

$\frac{32}{12}$ 20.6

530

17.1

$\frac{40}{12}$

525

Brown silty clay

$\frac{11}{12}$ 23.6

520

Brown and reddish brown clay /cherty
limestone rock fragments.

$\frac{10}{12}$ 21.4


515


4" Continuous flight auger refusal on limestone
boulders or bedrock.

510

Drilled 11/22/74

Vane Shear Strength
in ksf.





Drilled 11/26/74

CHESTERFIELD VILLAGE
Lake I

BORING LOGS

Reitz & Jens, Inc.
Consulting Engineers

St. Louis, Mo.
December 1974

Fig. 2-2

PLATE 10

555

4050N
4650E

Elev. 551.5

Topsoil

550

$\frac{9}{12}$ -25.1

Brown silty clay

545

$\frac{14}{12}$ -26.0

540

$\frac{8}{12}$ -27.7

Brown clayey silt

535

$\frac{9}{12}$ -25.1

530

Reddish brown clay w/small cherty limestone
rock fragments.

$\frac{25}{12}$ -27.8


525

4" Continuous flight auger refusal on
limestone boulders or bedrock.


Drilled 11/22/74

520



Vane Shear Strength
in ksf.



4300N
4650E
Elev. 550.6



Vane Shear Strength
in ksf.



4" Continuous flight auger
refusal on limestone.

Drilled 11/27/74

CHESTERFIELD VILLAGE
Lake I

BORING LOGS

Reitz & Jens, Inc.
Consulting Engineers

St. Louis, Mo.
December 1974

Fig. 2-3

APPENDIX A
INSPECTION PHOTOGRAPHS




NO. 1: UPSTREAM FACE OF DAM



NO. 2: DOWNSTREAM FACE OF DAM



NO. 3: LOWER BERM OF DAM AT ORIGINAL STREAM CHANNEL



NO. 4: DROP INLET SPILLWAY



NO. 5: ENERGY DISSIPATOR AT SULLIVAN OUTLET



NO. 6: 12" PIPE HEADWALL NEAR SULLIVAN OUTLET



NO. 7: CONCRETE BLOCK SLOPE PROTECTION ON UPSTREAM FACE OF DAM



NO. 8: RUBBLE SLOPE PROTECTION NEAR SPILLWAY OUTLET STRUCTURE

APPENDIX B

HYDROLOGIC AND HYDRAULIC ANALYSES

HYDROLOGIC AND HYDRAULIC COMPUTATIONS

1. The HEC-1 Dam Safety Version (July 1978, Modified 26 February 1979) program was used to develop inflow and outflow hydrographs and dam overtopping analyses, with hydrologic inputs as follows:

a. Probable maximum precipitation (200 sq. mile, 24-hour value equals 25.3 inches) from Hydrometeorological Report No. 33. The precipitation data used in the analysis of the 1 percent probability (100-year frequency) flood was provided by the St. Louis District, Corps of Engineers.

b. Drainage area = 0.19 square miles = 120 acres.

c. SCS parameters:

$$\text{Time of Concentration } (T_c) = \left(\frac{11.9L^3}{H} \right)^{0.385} = 0.126 \text{ hours}$$

Where: T_c = Travel time of water from hydraulically most distant point to point of interest, hours.

L = Length of longest watercourse, 0.35 miles

H = Elevation difference, 10 feet

The time of concentration (T_c) was obtained using Method C as described in Figure 30, "Design of Small Dams", by the United States Department of the Interior, Bureau of Reclamation, and was verified using average channel velocity estimates and watercourse lengths.

Lag Time = 0.075 hours (0.60 T_c)

Hydrologic Soil Group = 100% B (Memphis Series per County SCS Soil Report); urban development for entire area, with 49% average imperviousness

Soil type CN = 69 (AMC II, 1 percent probability flood condition)
= 84 (AMC III, PMF condition)

2. Spillway releases for the drop inlet spillway were computed utilizing equations and nomographs presented in "Design of Small Dams" by the U.S. Department of the Interior for drop inlet type spillways. The perimeter of the square inlet was equated to a circular section in order to determine a radius for use in the equations.

The rise of the nappe above the elevation of the crest lip was considered negligible. The following equation was used for crest control:

$$Q = C_o (2 \sqrt{R_s}) H_o^{3/2}$$

where " C_o " is a coefficient obtained from Figure 283 of the above reference, expressed in terms of H_o/R_s , " R_s " is the radius of the spillway crest (2.55 feet), and " H_o " is the depth of flow over the crest.

Flow through the 30-inch diameter outlet pipe was determined using Bernoulli's equation for pressure flow in pipes. A friction factor (n) of 0.013 was used for the 30-inch diameter reinforced concrete pipe. Losses, including entrance, turn, pipe friction and exit losses totaled 2.57 velocity heads. Reference "Handbook of Hydraulics", Fifth Edition, by King & Brater, pages 8-5 and 8-6.

Limiting discharge quantities, determined by the methods described herein, were plotted versus corresponding lake water surface elevations to obtain the discharge rating curve for the drop inlet spillway, and corresponding values were entered into the program on the Y4 and Y5 cards.

3. The profile of the dam crest is irregular and flow over the dam cannot be determined by application of conventional weir formulas. Crest length and elevation data for the dam crest proper were entered into the HEC-1 Program on the \$L and the \$V cards. The program assumes that flow over the dam crest section occurs at critical depth and computes internally the flow over the dam crest and adds this flow to the flow passing the spillway as entered on the Y4 and Y5 cards.

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF											
HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF LAKE POST COMMONS DAM											
RATIOS OF PMF ROUTED THROUGH RESERVOIR											
A1	200	0	5	0	0	0	0	0	0	0	0
A2	5										
A3	1	4	1								
B	.35	.40	.50	1.							
B1	0	INFLOW			1						
J	0	INFLOW HYDROGRAPH									
J1	1	2	.188		1.0						1
K	0	25.3	102	120	130						
K1	0	0.675									
M	0	-1.0	2.0								
P	0	-1.0	2.0								
T	0	0.675									
W2	0	-1.0	2.0								
X	0	0.675									
X1	0	-1.0	2.0								
K	0	0.675									
K1	0	0.675									
Y	0	0.675									
Y1	0	0.675									
Y4	0	0.675									
Y5	0	0.675									
\$A	0	0.675									
\$E	0	0.675									
\$S	0	0.675									
\$D	0	0.675									
\$L	0	0.675									
\$V	0	0.675									
K	0	0.675									

4

B-4

[illegible]

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF
HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF LAKE POST COMMONS DAM
RATIOS OF PMF ROUTED THROUGH RESERVOIR

JOB SPECIFICATION									
NQ	NHR	NMIN	IDAY	IHR	IMIN	METRIC	IPLT	IPRT	NSTAN
288	0	5	0	0	0	0	0	0	0
				JOPEP	NWT	LROPT	TRACT		
				5	0	0	0		

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 1 NRTIO= 4 LRTIO= 1
RTIOS= .35 .40 .50 1.00

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
INFLOW	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

IHYDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	2	.19	0.00	.19	1.00	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	25.30	102.00	120.00	130.00	0.00	0.00	0.00

LOSS DATA

LROPT	STRKR	ILTKR	RTIOL	ERAIN	STRKS	RTIOK	STRTL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	-1.00	-84.00	0.00	.49

CURVE NO = -84.00 WETNESS = -1.00 EFFECT CN = 84.00

UNIT HYDROGRAPH DATA

TC= 0.00 LAG= .03

RECESSION DATA

STRTO= -1.00 GRCSN= -.10 RTIOR= 2.00

TIME INCREMENT TOO LARGE--(NHR IS GT LAG/2)

UNIT HYDROGRAPH 6 END OF PERIOD ORDINATES, TC= 0.00 HOURS, LAG= .08 VOL= 1.00

635. 571. 173. 54. 17. 6.

0							END-OF-PERIOD FLOW						
MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
1.01	.05	1	.01	.01	.01	5.	1.01	12.05	145	.22	.21	.01	182.
1.01	.10	2	.01	.01	.01	8.	1.01	12.10	146	.22	.21	.01	265.
1.01	.15	3	.01	.01	.01	10.	1.01	12.15	147	.22	.21	.01	291.
1.01	.20	4	.01	.01	.01	10.	1.01	12.20	148	.22	.21	.01	300.
1.01	.25	5	.01	.01	.01	10.	1.01	12.25	149	.22	.21	.01	303.
1.01	.30	6	.01	.01	.01	10.	1.01	12.30	150	.22	.21	.01	304.
1.01	.35	7	.01	.01	.01	10.	1.01	12.35	151	.22	.21	.01	305.
1.01	.40	8	.01	.01	.01	10.	1.01	12.40	152	.22	.21	.01	305.
1.01	.45	9	.01	.01	.01	10.	1.01	12.45	153	.22	.21	.01	305.
1.01	.50	10	.01	.01	.01	10.	1.01	12.50	154	.22	.21	.00	306.
1.01	.55	11	.01	.01	.01	10.	1.01	12.55	155	.22	.21	.00	306.
1.01	1.00	12	.01	.01	.01	10.	1.01	13.00	156	.22	.21	.00	306.
1.01	1.05	13	.01	.01	.01	10.	1.01	13.05	157	.26	.25	.00	333.
1.01	1.10	14	.01	.01	.01	10.	1.01	13.10	158	.26	.25	.00	358.
1.01	1.15	15	.01	.01	.01	10.	1.01	13.15	159	.26	.25	.00	365.
1.01	1.20	16	.01	.01	.01	10.	1.01	13.20	160	.26	.25	.00	368.
1.01	1.25	17	.01	.01	.01	10.	1.01	13.25	161	.26	.25	.00	369.
1.01	1.30	18	.01	.01	.01	10.	1.01	13.30	162	.26	.25	.00	370.
1.01	1.35	19	.01	.01	.01	10.	1.01	13.35	163	.26	.25	.00	370.
1.01	1.40	20	.01	.01	.01	10.	1.01	13.40	164	.26	.25	.00	370.
1.01	1.45	21	.01	.01	.01	10.	1.01	13.45	165	.26	.25	.00	370.
1.01	1.50	22	.01	.01	.01	10.	1.01	13.50	166	.26	.25	.00	371.
1.01	1.55	23	.01	.01	.01	10.	1.01	13.55	167	.26	.25	.00	371.
1.01	2.00	24	.01	.01	.01	10.	1.01	14.00	168	.26	.26	.00	371.
1.01	2.05	25	.01	.01	.01	10.	1.01	14.05	169	.32	.32	.00	412.
1.01	2.10	26	.01	.01	.01	10.	1.01	14.10	170	.32	.32	.00	448.
1.01	2.15	27	.01	.01	.01	10.	1.01	14.15	171	.32	.32	.00	460.
1.01	2.20	28	.01	.01	.01	10.	1.01	14.20	172	.32	.32	.00	463.
1.01	2.25	29	.01	.01	.01	10.	1.01	14.25	173	.32	.32	.00	465.
1.01	2.30	30	.01	.01	.01	10.	1.01	14.30	174	.32	.32	.00	465.
1.01	2.35	31	.01	.01	.01	10.	1.01	14.35	175	.32	.32	.00	465.
1.01	2.40	32	.01	.01	.01	11.	1.01	14.40	176	.32	.32	.00	465.
1.01	2.45	33	.01	.01	.01	11.	1.01	14.45	177	.32	.32	.00	466.
1.01	2.50	34	.01	.01	.01	11.	1.01	14.50	178	.32	.32	.00	466.
1.01	2.55	35	.01	.01	.01	11.	1.01	14.55	179	.32	.32	.00	466.
1.01	3.00	36	.01	.01	.01	11.	1.01	15.00	180	.32	.32	.00	466.
1.01	3.05	37	.01	.01	.01	11.	1.01	15.05	181	.20	.19	.00	336.
1.01	3.10	38	.01	.01	.01	11.	1.01	15.10	182	.39	.39	.00	439.
1.01	3.15	39	.01	.01	.01	11.	1.01	15.15	183	.39	.39	.00	528.
1.01	3.20	40	.01	.01	.01	12.	1.01	15.20	184	.59	.58	.00	679.
1.01	3.25	41	.01	.01	.01	12.	1.01	15.25	185	.69	.63	.00	861.
1.01	3.30	42	.01	.01	.01	12.	1.01	15.30	186	1.67	1.66	.01	1573.
1.01	3.35	43	.01	.01	.01	12.	1.01	15.35	187	2.75	2.74	.01	2842.
1.01	3.40	44	.01	.01	.01	12.	1.01	15.40	188	1.03	1.08	.00	2580.
1.01	3.45	45	.01	.01	.01	12.	1.01	15.45	189	.69	.68	.00	1626.
1.01	3.50	46	.01	.01	.01	12.	1.01	15.50	190	.59	.59	.00	1128.
1.01	3.55	47	.01	.01	.01	12.	1.01	15.55	191	.39	.39	.00	815.
1.01	4.00	48	.01	.01	.01	12.	1.01	16.00	192	.39	.39	.00	644.
1.01	4.05	49	.01	.01	.01	13.	1.01	16.05	193	.30	.30	.00	531.

END-OF-PERIOD FLOW (Cont'd)

1.01	4.10	50	.01	.01	.01	13.	1.01	16.10	194	.30	.30	.00	445.
1.01	4.15	51	.01	.01	.01	13.	1.01	16.15	195	.30	.30	.00	445.
1.01	4.20	52	.01	.01	.01	13.	1.01	16.20	196	.30	.30	.00	439.
1.01	4.25	53	.01	.01	.01	13.	1.01	16.25	197	.30	.30	.00	438.
1.01	4.30	54	.01	.01	.01	13.	1.01	16.30	198	.30	.30	.00	437.
1.01	4.35	55	.01	.01	.00	13.	1.01	16.35	199	.30	.30	.00	437.
1.01	4.40	56	.01	.01	.00	13.	1.01	16.40	200	.30	.30	.00	437.
1.01	4.45	57	.01	.01	.00	13.	1.01	16.45	201	.30	.30	.00	437.
1.01	4.50	58	.01	.01	.00	13.	1.01	16.50	202	.30	.30	.00	437.
1.01	4.55	59	.01	.01	.00	14.	1.01	16.55	203	.30	.30	.00	437.
1.01	5.00	60	.01	.01	.00	14.	1.01	17.00	204	.30	.30	.00	437.
1.01	5.05	61	.01	.01	.00	14.	1.01	17.05	205	.24	.24	.00	396.
1.01	5.10	62	.01	.01	.00	14.	1.01	17.10	206	.24	.24	.00	360.
1.01	5.15	63	.01	.01	.00	14.	1.01	17.15	207	.24	.24	.00	348.
1.01	5.20	64	.01	.01	.00	14.	1.01	17.20	208	.24	.24	.00	345.
1.01	5.25	65	.01	.01	.00	14.	1.01	17.25	209	.24	.24	.00	344.
1.01	5.30	66	.01	.01	.00	14.	1.01	17.30	210	.24	.24	.00	344.
1.01	5.35	67	.01	.01	.00	14.	1.01	17.35	211	.24	.24	.00	344.
1.01	5.40	68	.01	.01	.00	14.	1.01	17.40	212	.24	.24	.00	344.
1.01	5.45	69	.01	.01	.00	14.	1.01	17.45	213	.24	.24	.00	344.
1.01	5.50	70	.01	.01	.00	14.	1.01	17.50	214	.24	.24	.00	344.
1.01	5.55	71	.01	.01	.00	14.	1.01	17.55	215	.24	.24	.00	344.
1.01	6.00	72	.01	.01	.00	14.	1.01	18.00	216	.24	.24	.00	344.
1.01	6.05	73	.06	.05	.02	37.	1.01	18.05	217	.02	.02	.00	273.
1.01	6.10	74	.06	.05	.02	58.	1.01	18.10	218	.02	.02	.00	255.
1.01	6.15	75	.06	.05	.02	65.	1.01	18.15	219	.02	.02	.00	238.
1.01	6.20	76	.06	.05	.02	68.	1.01	18.20	220	.02	.02	.00	222.
1.01	6.25	77	.06	.05	.01	70.	1.01	18.25	221	.02	.02	.00	207.
1.01	6.30	78	.06	.05	.01	71.	1.01	18.30	222	.02	.02	.00	193.
1.01	6.35	79	.06	.05	.01	72.	1.01	18.35	223	.02	.02	.00	180.
1.01	6.40	80	.06	.05	.01	73.	1.01	18.40	224	.02	.02	.00	168.
1.01	6.45	81	.06	.05	.01	73.	1.01	18.45	225	.02	.02	.00	157.
1.01	6.50	82	.06	.05	.01	74.	1.01	18.50	226	.02	.02	.00	147.
1.01	6.55	83	.06	.05	.01	75.	1.01	18.55	227	.02	.02	.00	137.
1.01	7.00	84	.06	.05	.01	76.	1.01	19.00	228	.02	.02	.00	128.
1.01	7.05	85	.06	.05	.01	76.	1.01	19.05	229	.02	.02	.00	119.
1.01	7.10	86	.06	.05	.01	77.	1.01	19.10	230	.02	.02	.00	111.
1.01	7.15	87	.06	.05	.01	77.	1.01	19.15	231	.02	.02	.00	104.
1.01	7.20	88	.06	.05	.01	78.	1.01	19.20	232	.02	.02	.00	97.
1.01	7.25	89	.06	.05	.01	78.	1.01	19.25	233	.02	.02	.00	90.
1.01	7.30	90	.06	.05	.01	79.	1.01	19.30	234	.02	.02	.00	84.
1.01	7.35	91	.06	.05	.01	79.	1.01	19.35	235	.02	.02	.00	79.
1.01	7.40	92	.06	.06	.01	80.	1.01	19.40	236	.02	.02	.00	73.
1.01	7.45	93	.06	.06	.01	80.	1.01	19.45	237	.02	.02	.00	68.
1.01	7.50	94	.06	.06	.01	81.	1.01	19.50	238	.02	.02	.00	64.
1.01	7.55	95	.06	.06	.01	81.	1.01	19.55	239	.02	.02	.00	60.
1.01	8.00	96	.06	.06	.01	81.	1.01	20.00	240	.02	.02	.00	56.
1.01	8.05	97	.06	.06	.01	82.	1.01	20.05	241	.02	.02	.00	52.
1.01	8.10	98	.06	.06	.01	82.	1.01	20.10	242	.02	.02	.00	48.
1.01	8.15	99	.06	.06	.01	82.	1.01	20.15	243	.02	.02	.00	45.
1.01	8.20	100	.06	.06	.01	82.	1.01	20.20	244	.02	.02	.00	42.
1.01	8.25	101	.06	.06	.01	83.	1.01	20.25	245	.02	.02	.00	39.
1.01	8.30	102	.06	.06	.01	83.	1.01	20.30	246	.02	.02	.00	37.

END-OF-PERIOD FLOW (Cont'd)

1.01	8.35	103	.06	.06	.01	83.	1.01	20.35	247	.02	.02	.00	34.
1.01	8.40	104	.06	.06	.01	84.	1.01	20.40	248	.02	.02	.00	32.
1.01	8.45	105	.06	.06	.01	84.	1.01	20.45	249	.02	.02	.00	31.
1.01	8.50	106	.06	.06	.01	84.	1.01	20.50	250	.02	.02	.00	31.
1.01	8.55	107	.06	.06	.01	84.	1.01	20.55	251	.02	.02	.00	31.
1.01	9.00	108	.06	.06	.01	84.	1.01	21.00	252	.02	.02	.00	31.
1.01	9.05	109	.06	.06	.00	85.	1.01	21.05	253	.02	.02	.00	31.
1.01	9.10	110	.06	.06	.00	85.	1.01	21.10	254	.02	.02	.00	31.
1.01	9.15	111	.06	.06	.00	85.	1.01	21.15	255	.02	.02	.00	31.
1.01	9.20	112	.06	.06	.00	85.	1.01	21.20	256	.02	.02	.00	31.
1.01	9.25	113	.06	.06	.00	85.	1.01	21.25	257	.02	.02	.00	31.
1.01	9.30	114	.06	.06	.00	86.	1.01	21.30	258	.02	.02	.00	31.
1.01	9.35	115	.06	.06	.00	86.	1.01	21.35	259	.02	.02	.00	31.
1.01	9.40	116	.06	.06	.00	86.	1.01	21.40	260	.02	.02	.00	31.
1.01	9.45	117	.06	.06	.00	86.	1.01	21.45	261	.02	.02	.00	31.
1.01	9.50	118	.06	.06	.00	86.	1.01	21.50	262	.02	.02	.00	31.
1.01	9.55	119	.06	.06	.00	86.	1.01	21.55	263	.02	.02	.00	31.
1.01	10.00	120	.06	.06	.00	86.	1.01	22.00	264	.02	.02	.00	31.
1.01	10.05	121	.06	.06	.00	87.	1.01	22.05	265	.02	.02	.00	31.
1.01	10.10	122	.06	.06	.00	87.	1.01	22.10	266	.02	.02	.00	31.
1.01	10.15	123	.06	.06	.00	87.	1.01	22.15	267	.02	.02	.00	31.
1.01	10.20	124	.06	.06	.00	87.	1.01	22.20	268	.02	.02	.00	31.
1.01	10.25	125	.06	.06	.00	87.	1.01	22.25	269	.02	.02	.00	31.
1.01	10.30	126	.06	.06	.00	87.	1.01	22.30	270	.02	.02	.00	31.
1.01	10.35	127	.06	.06	.00	87.	1.01	22.35	271	.02	.02	.00	31.
1.01	10.40	128	.06	.06	.00	87.	1.01	22.40	272	.02	.02	.00	31.
1.01	10.45	129	.06	.06	.00	87.	1.01	22.45	273	.02	.02	.00	31.
1.01	10.50	130	.06	.06	.00	87.	1.01	22.50	274	.02	.02	.00	31.
1.01	10.55	131	.06	.06	.00	88.	1.01	22.55	275	.02	.02	.00	31.
1.01	11.00	132	.06	.06	.00	88.	1.01	23.00	276	.02	.02	.00	31.
1.01	11.05	133	.06	.06	.00	88.	1.01	23.05	277	.02	.02	.00	31.
1.01	11.10	134	.06	.06	.00	88.	1.01	23.10	278	.02	.02	.00	31.
1.01	11.15	135	.06	.06	.00	88.	1.01	23.15	279	.02	.02	.00	31.
1.01	11.20	136	.06	.06	.00	88.	1.01	23.20	280	.02	.02	.00	31.
1.01	11.25	137	.06	.06	.00	88.	1.01	23.25	281	.02	.02	.00	31.
1.01	11.30	138	.06	.06	.00	88.	1.01	23.30	282	.02	.02	.00	31.
1.01	11.35	139	.06	.06	.00	88.	1.01	23.35	283	.02	.02	.00	31.
1.01	11.40	140	.06	.06	.00	88.	1.01	23.40	284	.02	.02	.00	31.
1.01	11.45	141	.06	.06	.00	88.	1.01	23.45	285	.02	.02	.00	31.
1.01	11.50	142	.06	.06	.00	88.	1.01	23.50	286	.02	.02	.00	31.
1.01	11.55	143	.06	.06	.00	89.	1.01	23.55	287	.02	.02	.00	31.
1.01	12.00	144	.06	.06	.00	89.	1.02	0.00	288	.02	.02	.00	31.

SUM 32.89 31.78 1.11 48641.
(835.) (807.) (28.) (1377.36)

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2042.	516.	169.	169.	48608.
CMS	80.	15.	5.	5.	1376.
INCHES		25.52	33.40	33.40	33.40
MM		648.19	848.47	848.47	848.47
AC-FT		256.	335.	335.	335.
THOUS CU M		315.	413.	413.	413.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TOP OF DAM	
						ELEVATION STORAGE OUTFLOW	559.90 87. 129.
1.00	557.01	0.00	48.	125.	0.00	12.58	0.00

DATE
ILME