

AD-A105 720

NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/8 13/13
NATIONAL DAM SAFETY PROGRAM, SAGAMORE LAKE DAM (INVENTORY NUMBE--ETC(U)
AUG 81 8 KOCH


UNCLASSIFIED

DACWS1-79-C-0001

NL

1 of 2

AD-A105 720



REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A205720	
4. TITLE (and Subtitle)		5. TYPE OF REPORT & PERIOD COVERED
Phase I Inspection Report Sagamore Lake Dam Lower Hudson River Basin, Putnam County, N.Y. Inventory No. 313	(8)	Phase I Inspection Report National Dam Safety Program
6. AUTHOR(s)		6. PERFORMING ORG. REPORT NUMBER
GEORGE KOCH	(15)	
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
New York State Department of Environmental Conservation 50 Wolf Road Albany, New York 12233	(12) 1071	DACW51-79-C-0001
10. CONTROLLING OFFICE NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
Department of the Army 26 Federal Plaza New York District, CofE New York, New York 10287		(11)
11. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE
Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		26 August 1981
		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report)
		UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)		
Approved for public release; Distribution unlimited.		
17. DIS		
National Dam Safety Program. Sagamore Lake Dam (Inventory Number NY 313), Lower Hudson River Basin, Putnam County, New York. Phase I Inspection Report.		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)		
Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability		Sagamore Lake Dam Putnam County Lower Hudson River Basin
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)		
This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to life or prop- erty. However, the dam has some deficiencies which need to be evaluated and remedied.		

LEVEL

DTIC
SELECTED
OCT 22 1981
H

393970

AD A105720

DTIC FILE COPY

Using the Corps of Engineers' Screening Criteria for initial review of spillway adequacy, it has been determined that the dam would be overtopped by all storms exceeding 13% of the Probable Maximum Flood (PMF) inflows. Since failure of the dam would increase the hazard to downstream residents, the spillway capacity is adjudged as seriously inadequate and the dam is assessed as "unsafe; non-emergency".

The classification of "unsafe" means that there appears to be a serious deficiency in spillway capacity and if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard to loss of life downstream of the dam. Due to the severity of the spillway adequacy, it is required that the stop logs on the spillway be removed to lower the reservoir level and to provide additional spillway capacity. The stop logs should not be replaced until appropriate mitigating measures have been taken.

In the interim, a system for providing around-the-clock surveillance of the dam during periods of unusually heavy precipitation should be developed and implemented. An emergency action plan for the notification and evacuation of downstream residents should be also developed.

Structural stability analyses performed for the spillway section of this dam indicate that the factors of safety are below recommended values for all conditions studied. Safety factors fall to critical levels when the dam is subjected to severe loading conditions, such as one half of the PMF.

It is recommended that within 3 months of the date of notification to the owner, investigations into the deficiencies on this structure should be commenced. A detailed hydrologic/hydraulic investigation of the structure is required. In addition, further investigations to better assess the structural stability of the spillway section are needed. Mitigating measures deemed necessary as a result of these investigations should be completed within 18 months.

Accession For	
NTIS GRA&I	☒
DTIC TAB	☐
Unannounced	☐
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	


LOWER HUDSON RIVER BASIN

SAGAMORE LAKE DAM

PUTNAM COUNTY, NEW YORK

INVENTORY NO. N.Y. 313

**PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**



**APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED**

NEW YORK DISTRICT CORPS OF ENGINEERS

JULY 1981

81 10 20

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
SAGAMORE LAKE DAM
I.D. N.Y.313
DEC NO. 213-1113-LH
PUTNAM COUNTY, N.Y.

TABLE OF CONTENTS

		<u>PAGE NO.</u>
-	ASSESSMENT	-
-	OVERVIEW PHOTOGRAPH	-
1	PROJECT INFORMATION	1
1.1	GENERAL	1
1.2	DESCRIPTION OF PROJECT	1
1.3	PERTINENT DATA	2
2	ENGINEERING DATA	4
2.1	GEOTECHNICAL DATA	4
2.2	DESIGN RECORDS	4
2.3	CONSTRUCTION RECORDS	4
2.4	OPERATION RECORDS	4
2.5	EVALUATION OF DATA	5
3	VISUAL INSPECTION	6
3.1	FINDINGS	6
3.2	EVALUATION OF OBSERVATIONS	7
4	OPERATIONS AND MAINTENANCE PROCEDURES	8
4.1	PROCEDURES	8
4.2	MAINTENANCE OF DAM	8
4.3	WARNING SYSTEM IN EFFECT	8
4.4	EVALUATION	8

		<u>PAGE NO.</u>
5	HYDROLOGIC/HYDRAULIC	9
5.1	DRAINAGE AREA CHARACTERISTICS	9
5.2	ANALYSIS CRITERIA	9
5.3	SPILLWAY CRITERIA	9
5.4	RESERVOIR CAPACITY	10
5.5	FLOODS OF RECORD	10
5.6	OVERTOPPING POTENTIAL	10
5.7	EVALUATION	10
6	STRUCTURAL STABILITY	11
6.1	EVALUATION OF STRUCTURAL STABILITY	11
7	ASSESSMENT/RECOMMENDATIONS	13
7.1	ASSESSMENT	13
7.2	RECOMMENDED MEASURES	14

APPENDICES

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC ENGINEERING
DATA AND COMPUTATIONS
- D. STABILITY COMPUTATIONS
- E. REFERENCES
- F. DRAWINGS AND RELATED DOCUMENTS

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam:	Sagamore Lake Dam (I.D. NY 313)
State Located:	New York
County:	Putnam
Watershed:	Lower Hudson River Basin
Stream:	West Branch of Croton River
Date of Inspection:	May 27, 1981

ASSESSMENT

Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to life or property. However, the dam has some deficiencies which need to be evaluated and remedied.

Using the Corps of Engineers' Screening Criteria for initial review of spillway adequacy, it has been determined that the dam would be overtopped by all storms exceeding 13% of the Probable Maximum Flood (PMF) inflows. Since failure of the dam would increase the hazard to downstream residents, the spillway capacity is adjudged as seriously inadequate and the dam is assessed as "unsafe; non-emergency".

The classification of "unsafe" means that there appears to be a serious deficiency in spillway capacity and if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard to loss of life downstream of the dam. Due to the severity of the spillway adequacy, it is required that the stop logs on the spillway be removed to lower the reservoir level and to provide additional spillway capacity. The stop logs should not be replaced until appropriate mitigating measures have been taken.

In the interim, a system for providing around-the-clock surveillance of the dam during periods of unusually heavy precipitation should be developed and implemented. An emergency action plan for the notification and evacuation of downstream residents should be also developed.

Structural stability analyses performed for the spillway section of this dam indicate that the factors of safety are below recommended values for all conditions studied. Safety factors fall to critical levels when the dam is subjected to severe loading conditions, such as one half of the PMF.

It is recommended that within 3 months of the date of notification of the owner, investigations into the deficiencies on this structure should be commenced. A detailed hydrologic/hydraulic investigation of the structure is required. In addition, further investigations to better assess the structural stability of the spillway section are needed. Mitigating measures deemed necessary as a result of these investigations should be completed within 18 months.

Several other deficiencies were noted on this structure. These deficiencies should be corrected within 12 months of the date of notification of the owner. Among the required actions are the following:

1. Brush and trees growing on the embankment should be cut. A follow-up inspection of the dam should be conducted after the embankment has been cleared.
2. The oversteepened downstream slope at the right end of the dam should be flattened.
3. The seepage observed beyond the ends of the wingwalls at both ends of the spillway section should be kept under surveillance. If the rate of seepage increases, remedial actions should be taken.
4. The area behind the downstream end of the right wingwall should be regraded to fill the small scoured area which has developed.
5. The reservoir drain should be operated and if it is not operational, it should be repaired.

George Koch RW

George Koch
Chief, Dam Safety Section
New York State Department
of Environmental Conservation
NY License No 45937

Approved By:

W. M. Smith, Jr.
Col. W. M. Smith, Jr.
New York District Engineer

Date:

26 Aug 81



OVERVIEW
SAGAMORE LAKE DAM
I.D. NO. NY-313

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
SAGAMORE LAKE DAM
I.D.NO. NY-313
#213-1113 LOWER HUDSON RIVER BASIN
PUTNAM COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

This inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2. DESCRIPTION OF PROJECT

a. Description of Dam

The Sagamore Lake Dam (formerly known as the Old Forge Dam) is an earth dam with a concrete corewall. A concrete gravity spillway section is located near the left end of the dam.

The dam is approximately 300 feet long and 20 feet high. The crest width is about 20 feet at the right end of the dam and somewhat less at the left end. A reinforced concrete core wall extends the length of the embankment. This corewall is 1.25 feet wide at the top and 3 feet wide at the base. The depth of embedment of the wall varied with the height of the wall. The plans indicate that the embankment slopes are 1 vertical on 2.5 horizontal on the upstream slope and 1 vertical on 2 horizontal on the downstream slope. The existing embankment slopes appear to be steeper than these values.

The spillway is a 48 foot long ungated concrete overflow section. The section has a rounded crest about 2 feet wide. There is a stoplog slot near the center of the spillway section. This slot is 8.8 feet long and 1.6 feet deep (below the spillway crest). Concrete wingwalls on either side of the spillway separate it from the embankment. A concrete apron extends about 25 feet beyond the downstream toe of the spillway section.

The structure reportedly has a 20 inch diameter steel drain through the base of the spillway section. The outlet from this pipe could not be located but there is a gate stem which rises several feet above the normal water level immediately upstream of the spillway.

b. Location

The Sagamore Lake Dam is located off of Sagamore Drive in the Town of Kent, Putnam County. It is about 0.5 miles south of New York State Route 301 and approximately 2.5 miles east of the Taconic State Parkway. Boyd Corners Reservoir Dam, another "high" hazard structure, is located one mile downstream of this dam.

c. Size Classification

This dam is 20 feet high and has a storage capacity of 1824 acre-feet. Therefore, the dam is in the intermediate size category as defined by the "Recommended Guidelines for Safety Inspection of Dams".

d. Hazard Classification

The dam is classified as "high" hazard due to the presence of several homes located near the stream channel between the dam and Boyd Corners Reservoir. One town road and State Route 301 would also be affected by a dam failure.

e. Ownership

The dam is owned by the Lake Sagamore Community Association. The president of the association is Mr. Ira Nathan. His address is RD2 Carmel, New York 10512. His phone number is (914) 225-4136.

f. Purpose of Dam

This dam is used to maintain the water level in the lake for recreational purposes.

g. Design and Construction History

This dam was originally constructed in 1940. R.J. Crane, Professional Engineer, designed the dam for Antoinette M. Ryder of Carmel, New York. The height of the dam was increased in 1946. These modifications to the structure, which included rebuilding the spillway section, were designed by M. Chazen, Professional Engineer.

h. Normal Operating Procedures

There are no regular operating procedures on this dam. Water flows over the ungated spillway.

1.3

PERTINENT DATA

<u>a. Drainage Area</u>	(sq.miles)	5.91
<u>b. Discharge at Dam</u>	(cfs)	
Spillway (Water @ Top-Dam; stoplogs in place)		983
Stoplogs Out (water @ spillway crest)		43
<u>c. Elevation (USGS Datum)</u>		
Top of Dam		659.45
Spillway Crest		656.
Stoplog Slot - Invert		654.4

- d. Reservoir (Surface Area) (acres)
 Top of Dam 96+
 Spillway Crest 96
- e. Storage Capacity (acre-feet)
 Top of Dam 1824
 Spillway Crest 1492
- f. Dam
 Type: Earth embankment with concrete corewall
 extending into the foundation
- Embankment Length (ft) 250
 Crest Width (ft) Variable
- Design
 Slopes (V:H) Upstream 1 on 2.5
 Downstream 1 on 2
- g. Spillway
 Type: Ungated concrete overflow weir located
 near left end of dam; slot for stop logs
 in center of spillway
- Length of Overflow Weir (ft) 47.9
 Length of Stop Log Slot (ft) 8.8
 Height of Stop Log (below spillway crest) (ft) 1.6
- h. Reservoir Drain
 Type: 20 inch diameter steel pipe through base of spillway
 section; Valve stem to control flow through pipe is
 immediately upstream of spillway.

SECTION 2: ENGINEERING DATA

2.1 GEOTECHNICAL DATA

a. Geology

The Sagamore Lake Dam is located in the Hudson Hills segment of the New England Uplands physiographic province of New York State. These hills, commonly known as the "Highlands of the Hudson", are composed of crystalline rocks similar to those in the Adirondacks. The highlands, which trend northeast-southwest, have been eroded to form very rugged terrain with summit levels reaching 1000 feet above sea level. Bedrock in the area consists of gneiss, quartzite, and marble from the Precambrian era (more than 570 million years ago). A review of the "Brittle Structures Map of New York" indicates that there is a fault trace which runs through the reservoir about 1500 feet to the northwest of the dam.

The surficial soils in this area are the results of glaciations during the Cenozoic Era, the last of which was the Wisconsin glaciation.

b. Subsurface Investigation

No records of any subsurface investigations performed for this structure could be located. Limited subsurface data was included on the application form for the original construction of the dam. This indicated that the foundation consisted of hard pan, clay and rocks.

2.2 DESIGN RECORDS

Limited design information was available for this structure. Applications for the construction in 1940 and the reconstruction in 1946 were available and have been included in Appendix F. Plans were available for both the construction and the reconstruction. The 1940 plans were prepared by R.J. Crane. The 1946 plans were prepared by M. Chazen.

2.3 CONSTRUCTION RECORDS

No construction records were available for this dam. It is believed that the dam was built predominantly according to plans. One discrepancy noted between the plans and the existing conditions was that only one stop log slot exists rather than the four indicated on the 1946 plans. The crest width of the embankment is wider and the slopes are steeper than the plans indicate as well. This appears to be due to fill placed on the embankment after the reconstruction.

2.4 OPERATION RECORDS

No operation records were available for this structure.

2.5 EVALUATION OF DATA

Information used for the preparation of this report was obtained from the Department of Environmental Conservation files. With the exception of the discrepancies noted above, the available information appeared to be reasonably accurate.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

a. General

Visual inspection of the Sagamore Lake Dam was conducted on May 27, 1981. The weather was partly cloudy and the temperature was in the mid-sixties. The water level at the time of the inspection was slightly above the spillway crest.

b. Embankment

Inspection of the embankment was hampered by trees and brush growing on the downstream slope. There was also extensive brush cover on the crest and upstream slope at the left end of the dam. The remainder of the crest and upstream slope had only a minor amount of undesirable growth.

The crest of the dam was somewhat irregular. There was an area to the right of the spillway section where the crest elevation was about one foot higher than it was on the remainder of the dam. This section was about 90 feet long and had resulted from filling operations which had widened the crest and steepened the downstream slope.

The fill that had been used appeared to have been road sweepings, pieces of asphalt and broken concrete. The crest width of the embankment was variable due to this fill material. Several small erosion gullies in this material were observed on the downstream slope.

There was some seepage observed on both ends of the spillway section. At the right end of the spillway, a minor flow was appearing on the edge of the plunge pool, downstream of the concrete wingwall which separated the spillway section from the embankment. The volume of seepage on the left end was somewhat larger. This seepage was flowing under large rocks which had been dumped in this area. The exact cause of the seepage in either area was not readily apparent.

Some embankment material was missing from a small area at the downstream end of the right wingwall. This was probably the result of some minor scouring action from the plunge pool. The embankment behind the right wingwall was covered by the dumped rocks previously mentioned. The rock made it impossible to see the embankment in this area.

c. Spillway

The spillway was in satisfactory condition. Only minor spalling of the concrete was observed. Some efflorescence was noted along the construction joints on each of the wingwalls. Stop logs were in place at the time of inspection. This brought the crest of the stop log slot up to the same level as the remainder of the spillway.

d. Reservoir Drain

No inspection of the reservoir drain facilities was possible. The valve stem rose several feet above the water surface immediately upstream of the spillway section. The outlet to the drain was apparently submerged and could not be located at the time of the inspection.

e. Reservoir

There were no indications of soil instability on this structure.

f. Downstream Channel

The channel downstream of the dam was natural and rock filled. It passed beneath a small highway bridge several hundred feet downstream of the dam.

3.2 EVALUATION OF OBSERVATIONS

Visual observations revealed several deficiencies on this structure. The following items were noted:

1. Brush and trees growing on the downstream slope at the right end of the embankment and on the entire embankment at the left end.
2. An oversteepened downstream slope at the right end of the dam caused by dumping unsuitable material on the crest and slope.
3. Seepage observed beyond the wingwalls at both ends of the spillway section.
4. A small area which had been scoured behind the right wingwall at the downstream end.
5. Rock dumped behind the left wingwall hiding the embankment in this area.
6. It could not be determined whether the reservoir drain was operational.

SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

4.1 PROCEDURES

There are no formal operating procedures for this dam. Stop logs can be removed or added in the stop log slot to vary the water level.

4.2 MAINTENANCE OF DAM

There is no established maintenance plan for this dam.

4.3 WARNING SYSTEM IN EFFECT

No apparent warning system for notification or evacuation of downstream residents is present.

4.4 EVALUATION

The operation procedures on this structure are satisfactory. Maintenance has been unsatisfactory as evidenced by the deficiencies noted in section 3.2.

SECTION 5: HYDROLOGIC/HYDRAULIC

5.1 DRAINAGE AREA CHARACTERISTICS

The delineation of the contributing watershed to this dam is indicated on the map titled "Drainage Area Map - Sagamore Lake Dam" (Appendix C). The irregular but somewhat square, north-south oriented watershed of some 5.91 square miles (3783 acres) is comprised of relatively undeveloped lands, primarily forests and woodlands. No significant land development exists except for those seasonal residences surrounding Sagamore Lake itself. Numerous wetlands are interspersed throughout the watershed. Slopes along the primary drainage paths are moderate (3%-7%). However, the adjacent hillsides have steep slopes, with those hilltops forming the watershed divide ranging from 350 feet to 650 feet in elevations above the reservoir. There are no other sizeable bodies of water within the watershed nor are there any known flow diversions, either into or out of this basin. The outlet stream is known as the West Branch of the Croton River.

5.2 ANALYSIS CRITERIA

No hydrologic/hydraulic information was available regarding the original design for this dam. Therefore, the analysis of the floodwater retarding capability of the dam was performed using the Corps of Engineers HEC-1 computer program, Dam Safety version. The computer program develops an inflow hydrograph using the "Snyder Unit Hydrograph" method and then reservoir routs the hydrograph using the "Modified Puls" flood routing procedure. The spillway design flood selected for analysis was the Probable Maximum Flood (PMF), in accordance with the Recommended Guidelines of the U.S. Army Corps of Engineers. The PMF event is that hypothetical storm event resulting from the most critical combination of rainfall, minimum soil retention, and direct runoff to a specific site that is considered reasonably possible for a particular watershed. Precipitation values used in the analysis were obtained from the Weather Bureau publication HRR 33. Soil retention rates selected were an initial loss of 1.5 inches and a constant loss of 0.1 inches per hour.

5.3 SPILLWAY CAPACITY

The single, ungated concrete spillway was analyzed for weir flow using a discharge coefficient, C , of 3.25. Near the center of the spillway crest is a stoplog slot which can provide about 43 cfs additional flow capacity. Since the slot is not easily accessible from either spillway abutment wall during the occurrence of a large storm event, the analysis does not include the additional 43cfs.

The floodwater analysis performed for this dam indicates that the spillway does not have sufficient capacity for discharging one-half the PMF. For this storm event, the peak inflow is 5181 cfs and the peak outflow is 5019 cfs. The PMF peak inflow and peak outflow are 10363 cfs and 10143 cfs respectively. The computed spillway discharge capacity with the stop logs in place is 983 cfs.

5.4 RESERVOIR CAPACITY

The normal water surface is at or near the spillway crest (elevation 656 -USGS) The impounded capacity at this elevation is 1492 acre-feet. Surge storage capacity to the top-of-dam (elevation 659.45) adds 332 acre-feet which is equivalent to a direct runoff depth of 1.05 inches over the watershed. The total storage capacity is 2306 acre-feet.

5.5 FLOODS OF RECORD

No data was available regarding the occurrence of the maximum known flood at this dam site.

5.6 OVERTOPPING POTENTIAL

Analyses using the PMF and one-half the PMF storm events indicates that the spillway does not have sufficient discharge capacity. The computed depths of overtopping for these two events are 4.90 feet and 2.81 feet respectively. All storm events exceeding 13% of the PMF will result in the dam being overtopped.

5.7 EVALUATION

The spillway capacity is inadequate for the peak outflow from one-half the PMF. Overtopping of the earth embankment is likely to cause dam failure. Therefore, a dam-break analysis, assuming a breaching of the dam, was performed. The analysis indicates that water surface levels downstream of the dam could reach depths which would pose a significant danger to residents. That is, dam failure resulting from overtopping would significantly increase the hazard to loss of life downstream from the dam from that which would exist just before an overtopping failure. Therefore the spillway is adjudged as "seriously inadequate" and the dam is assessed as "unsafe, non-emergency."

SECTION 6: STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations

Visual inspection of the embankment was hampered by trees and brush growing on the slopes. Minor seepage was noted beyond the wingwalls at both ends of the spillway section. The embankment had been modified by the addition of fill material. The crest had been raised by about one foot along a 90 foot long section. The fill has also widened the crest and caused the downstream slope to become oversteepened. There were several small erosion gullies in this material on the downstream slope.

b. Data Review and Stability Evaluation

No design information concerning the stability of either the earth embankment or concrete spillway section was available.

A stability analysis of the spillway section was performed for this report in accordance with the "Recommended Guidelines for the Safety Inspection of Dams." This analysis was based on a cross section shown on the 1946 plans prepared by M. Chazen. The results of the analysis are as follows:

<u>Case</u>	<u>Overturning Safety Factor</u>	<u>Resultant in Middle Third</u>	<u>Sliding Safety Factor</u>
a. Normal Conditions; water surface at spillway crest	1.84	Yes	1.36
b. Case a. plus an ice load of 5,000 lb/ft	1.35	No	1.07
c. Water Surface at Top of Dam; 3.5 feet over spillway crest	1.52	No	1.09
d. 1/2 PMF Water Surface 6.3 feet over spillway crest (2.8 feet over top of dam)	1.35	No	0.92
3. Normal conditions with seismic coefficient of 0.10	1.74	Yes	0.96

The analysis indicates that the spillway section is only marginally stable under most of the conditions analyzed. When subjected to severe loading conditions due to one half the PMF or worse, the section would be unstable.

Further investigations are required to better assess the stability of the spillway section. Subsurface explorations and concrete cores, to obtain information about the condition of the structure and uplift forces, are required. Stability analyses should then be performed using this data. Based on the results of these analyses, required modifications to the structure should be made.

c. Seismic Stability

This structure is located in Seismic Zone 1. However, since there was a fault trace in the vicinity of the dam, a seismic stability analysis was performed assuming a seismic coefficient of 0.1. The results of this analysis (shown on page 11) indicate that the safety factor against sliding fall below 1.0 when seismic considerations are included.

SECTION 7: ASSESSMENT/RECOMMENDATIONS

7.1 ASSESSMENT

a. Safety

The Phase I inspection of the Sagamore Lake Dam revealed that the spillway is seriously inadequate and outflows from all storms exceeding 13% of the Probable Maximum Flood would overtop the dam. Since an overtopping induced failure would significantly increase the hazard to downstream residents, the dam has been assessed as unsafe; non emergency.

In addition, a stability analysis performed for the spillway section indicates that the factors of safety are below recommended values for all conditions analyzed. When the dam is subjected to severe loading conditions, such as one half of the PMF, the safety factors fall to critical levels.

Several other deficiencies were noted which affect the safety of this structure. Trees and brush growing on the embankment prevent a detailed inspection of the dam. Fill has been placed on the downstream slope at the right end of the dam resulting in an oversteepened slope. Minor seepage was noted emerging beyond the ends of the wingwalls at both ends of the spillway section.

b. Adequacy of Information

The information available for the preparation of this report was reasonably complete and accurate. There was very little information available about subsurface conditions in the vicinity of the dam.

c. Need for Additional Investigations

Since the spillway has been assessed as seriously inadequate, additional hydrologic/hydraulic investigations are required to more accurately determine the site specific characteristics of the watershed. Analysis will then be required to determine appropriate mitigating measures in response to the seriously inadequate spillway capacity.

Further investigations are required to better assess the stability of the spillway section. Subsurface explorations and concrete cores to obtain information about the condition of the structure and uplift forces are required. Based on the results of these analyses, required modifications to this portion of the structure should be made.

d. Urgency

The hydrologic/hydraulic investigations and structural stability studies which are required should be commenced within 3 months of the date of notification of the owner. Remedial measures deemed necessary based on the results of the investigations should be completed within 18 months. All other deficiencies noted should be corrected within 12 months of the date of notification.

7.2 RECOMMENDED MEASURES

- a. Due to the seriously inadequate spillway capacity, remove the stop logs on the spillway section pending the results of the detailed hydrologic/hydraulic analysis.
- b. After the hydrologic/hydraulic investigation has been completed, mitigating measures dealing with the seriously inadequate spillway capacity should be taken.
- c. Based on the results of the stability analysis, make the necessary modifications to the spillway section.
- d. Cut brush and trees growing on the embankment to permit a more detailed inspection of the dam.
- e. Flatten the oversteepened slope at the right end of the dam.
- f. The seepage beyond the ends of the wingwalls should be kept under surveillance and remedial actions taken if the conditions worsen.
- g. The small scoured area behind the downstream end of the right wingwall should be filled.
- h. Test the reservoir drain to assure that it is operational and if not it should be repaired.
- i. An emergency action plan for the notification and evacuation of downstream residents should be developed.

APPENDIX A


PHOTOGRAPHS



EMBANKMENT CREST AT RIGHT END OF DAM



EMBANKMENT CREST AT RIGHT END OF DAM ;
AREA WHERE CREST IS HIGHER AND WIDER



DOWNSTREAM SLOPE AT RIGHT END OF DAM
IN AREA OF DUMPED FILL



MINOR SCOUR BEHIND WINGWALL AT RIGHT END OF SPILLWAY



RIGHT END OF SPILLWAY: AREA OF MINOR SEEPAGE
AT END OF WINGWALL



CLOSE UP OF SEEPAGE AREA SHOWN ABOVE



EMBANKMENT CREST AT LEFT END OF DAM
NOTE TREES AND BRUSH GROWING ON EMBANKMENT



AREA OF DUMPED STONE AT LEFT END OF SPILLWAY
SEEPAGE EMERGING FROM BENEATH STONE




SPILLWAY SECTION; NOTE RESERVOIR DRAIN CONTROL STEM
AT LEFT SIDE OF PICTURE



VIEW LOOKING ACROSS SPILLWAY CREST

NEW 2
1



Use 4 # 3/4" V. bars @ 12" o.c. each face, + 3/8" hoops

Δ Δ Δ
Δ Δ Δ
Δ Δ Δ

Δ Δ Δ
Δ Δ Δ
Δ Δ Δ

2'0"

Sp. way 4016

[Faint, illegible handwritten notes]

52-6

2

1-2-3

NEW YORK STATE DEPARTMENT OF
PUBLIC WORKS
DIVISION OF ENGINEERING
ALBANY, N. Y.

This plan for Constructing seen No. 231-1123
approved under the provisions of Section 9-15 of the
Conservation Law.
Examined and recommended for the Chief Engineer for
approval.

APPROVED

John J. Conner
CHIEF ENGINEER
State Department of Public Works
Department of Public Works

4" x 6" x 1/2" c-c each

Constructing to meet the requirements for
the specifications for the project to be
constructed.

Remainder of project to be
constructed in accordance with the
specifications.

Respectfully,
J. J. Conner
CHIEF ENGINEER

△△△
△△△
△△△

250'

See map of area

40'

Sp. way 47' 0"


400'

70'

70'

514

PLAN OF SHAL



2

1-5

4'0"


37.6
100.2 514.00

Section 25
50

312 Refractive wall
1970

100.2 514.00

100.2 514.00
100.2 514.00



Existing Culvert
 New Culvert
 SECTION B-B




Table of
Culvert
Dimensions


H	P
1	6.0
2	6.0
3	6.0
4	6.0
5	6.0
6	6.0
7	6.0
8	6.0
9	6.0
10	6.0
11	6.0
12	6.0
13	6.0
14	6.0
15	6.0
16	6.0
17	6.0
18	6.0
19	6.0
20	6.0
21	6.0
22	6.0
23	6.0
24	6.0
25	6.0
26	6.0
27	6.0
28	6.0
29	6.0
30	6.0

2' 0" 2' 0"
 6' center
 Thread end of bar
 for not to be grouted
 in concrete

POWER PLANT

FOR
 OR

5. 10. 1945



Top of Embankment


Top of Concrete


Original Surface

Use 4- $\frac{3}{8}$ " vertical
bars 4 in in each face
of piers, 4 $\frac{3}{8}$ " hoops


PROFILE LOOKING UP STREAM

Scale 1" = 10'





SECTION B-B



5

MASO

44

g-ctt

de rest
bevestigd

加蓋

dealing

first 5

de la

—

AME

and

44-13
327

500,7

1

1

ONE

43

3577

52.1

11

7

52

45

154

分

1

10

10

1

5. 6.

1

extend into
bank 3-0' min.

SPECIFICATION.

MASONRY FOUNDATIONS

All soft spots, vegetable matter or other perishable material shall be removed from the site of the foundation & excavation carried down to the depths shown or to greater depths where required to obtain firm soil. Foundations on rock shall be bermed or stepped on clean sound rock.

EMBANKMENT FOUNDATION.

All vegetable matter and other perishable material shall be removed and the area shall be ploughed or scored parallel to the center.

CONCRETE

Concrete shall be 1:2½:3 mix. In the spillway sound clean one man stone may be embedded. No stone shall be placed within 6" of another stone or an outside surface.

All reinforcement bars ¾" Bars shall be placed 3" from the surface. All bars to be 15'.

EMBANKMENT


Fill shall be deposited on both sides of the core wall at the same time and the embankments carried up by depositing the materials in 9" layers & compacting to the entire area. Layers to be symmetrical and completed. The surface of previous material shall be rolled in the compact ment upstream. On the river bank fill of trench on the upstream side of core wall shall be packed in successive material.

Embankment shall be placed approximately 24" from the core wall. 4
Berms shall be 15' from the core wall.


PROTECTION OF STEEP SLOPES

At the ends of spillway wing walls, crest intake and side exits 3' or more embankments shall be placed on the steep slopes.

EL 1117 11
Looking South




P.L. 7.4




12"

10"




2



7'-6"


16'-9"
1/4" SCALE

Top of line



Slope


Slots for Planks



1'-3" Top of line

4 OF SPILLWAY


6



8' 8" Bars in bottom of
slab 12" c-c, both ways

bottom flange
extend 2'-0" into
main section of pier.

SECTION B-B



SECTION THRU EMBEDMENT Scale 1"=10'




TABLE OF
CORE WALL
DIMENSIONS

1	2
4	4
6	5-0
7	5-0
8	5-0
9	5-0
10	5-0
11	6-0
12	6-0
13	6-0
14	7-0
15	7-0

Note:
Adjacent core wall
carry bottom of core wall
to same depth as wings.

TYPICAL SECTION CORE WALL

7

of another stone or an outside
surface.
All reinforcement bars $\frac{3}{8}$ " Bars
shall be placed 3" from this surface.
All bars to be 12'.

FOUNDATION
Foundation to be deposited on both
sides of the concrete wall of the dam.
The foundation shall be constructed
by placing a 12" thick layer of 9" sand
over the entire area. The entire area
shall be covered with a 12" layer of
sand. The sand shall be placed in
layers of 12" each. The sand shall
be placed in layers of 12" each. The
sand shall be placed in layers of 12" each.
The sand shall be placed in layers of 12" each.
The sand shall be placed in layers of 12" each.
The sand shall be placed in layers of 12" each.

PROPOSED DAM SLOPES
At the crest of the dam, the
slopes shall be 1:1. The slopes
shall be 1:1. The slopes shall be 1:1.
The slopes shall be 1:1. The slopes
shall be 1:1. The slopes shall be 1:1.
The slopes shall be 1:1. The slopes
shall be 1:1. The slopes shall be 1:1.
The slopes shall be 1:1. The slopes
shall be 1:1. The slopes shall be 1:1.

GENERAL NOTES

Construction to be carried
out so that "High Water" shown
on plan is at least (0.336') below
the top of the dam, as used in
the design.

DESIGN FOR OLD FORGE DAM on property of A. M. RYDER situated in the TOWN OF KENT PUTNAM COUNTY

Scale 1" = 10'
Elevation shown

Cornwall N.Y.
June 26, 1940.

Revised July 15, 1940.

R. J. Grenc P.E. & L.S. No. 12355

APPENDIX B
VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST1) Basic Data

a. General

Name of Dam LAKE SAGAMORE DAM (FORMERLY OLD FORGE DAM)Fed. I.D. # NY 313 DEC Dam No. 213-1113River Basin LOWER HUDSONLocation: Town KENT County PUTNAMStream Name WEST BRANCH OF CROTON RIVER

Tributary of _____

Latitude (N) 41° 28.3' Longitude (W) 73° 46.5'Type of Dam EARTH EMBANKMENT w/ CONCRETE COREWALL & CONCRETE SPILLWAYHazard Category CDate(s) of Inspection 5/27/81Weather Conditions PARTLY CLOUDY 60°FReservoir Level at Time of Inspection SPILLWAY CREST ±b. Inspection Personnel R. WARRENDER W. LYNICK

c. Persons Contacted (Including Address & Phone No.) _____

d. History:

Date Constructed 1940 Date(s) Reconstructed 1946Designer R. J. CRANE M. CHAZEN

Constructed By _____

Owner LAKE SAGAMORE COMMUNITY ASSOCIATION

2) Embankment

a. Characteristics

- (1) Embankment Material CLAY & GLACIAL TILL
- (2) Cutoff Type UNKNOWN
- (3) Impervious Core CONCRETE CORE WALL
- (4) Internal Drainage System NONE
- (5) Miscellaneous _____

b. Crest

- (1) Vertical Alignment IRREGULAR-90' LONG SEGMENT TO RIGHT OF SPILLWAY IS ABOUT 1' HIGHER THAN REST OF CREST - DROPS BACK TO NORMAL
- (2) Horizontal Alignment SATISFACTORY ELEVATION 6' FROM RIGHT END OF SPILLWAY
LEFT SIDE OF SPILLWAY IS AT ^{THE} LOWER CREST LEVEL
- (3) Surface Cracks NONE
- (4) Miscellaneous WIDTH VARIES - WIDEST IN HIGHER (1') SECTION - EMBANKMENT IS WIDER DUE TO DUMPED FILL MATERIAL

c. Upstream Slope

- (1) Slope (Estimate) (V:H) 1:2
- (2) Undesirable Growth or Debris, Animal Burrows BRUSH & TREES MOSTLY ON LEFT END - ONLY ISOLATED INSTANCES ON THE RIGHT END
- (3) Sloughing, Subsidence or Depressions FACE HAS SOME IRREGULARITIES BUT IS GENERALLY OKAY

(4) Slope Protection LARGE OVERSIZED ROCKS & BOULDERS

(5) Surface Cracks or Movement at Toe UNOBSERVABLE

d. Downstream Slope

(1) Slope (Estimate - V:H) 1:1 OR SLIGHTLY STEEPER

(2) Undesirable Growth or Debris, Animal Burrows SUBSTANTIAL GROWTH ON DOWNSTREAM SLOPE; OVERGROWN; A REAL JUNGLE

(3) Sloughing, Subsidence or Depressions NONE; THERE WERE SOME EROSION TYPE GULLIES IN THE AREA OF DUMPED FILL

(4) Surface Cracks or Movement at Toe NONE

(5) Seepage SLIGHT AMOUNT NOTED ON EITHER SIDE OF SPILLWAY FAIRLY MINOR ON RIGHT END AT DOWNSTREAM END OF PLUNGE POOL. MORE SUBSTANTIAL ON LEFT END. FLOW UNDER DUMPED ROCKS & POSSIBLY COMING OUT OF HILLSIDE

(6) External Drainage System (Ditches, Trenches; Blanket) NONE

(7) Condition Around Outlet Structure SEEPAGE AS NOTED IN (5)

(8) Seepage Beyond Toe NONE

e. Abutments - Embankment Contact

THE SEEPAGE AT THE LEFT END OF THE SPILLWAY APPEARS TO BE RELATED TO THIS CONTACT

(1) Erosion at Contact NONE

(2) Seepage Along Contact POSSIBLY ALONG CONTACT
SEE PRIOR DISCUSSION

3) Drainage System

a. Description of System NONE

b. Condition of System _____

c. Discharge from Drainage System _____

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.) _____

NONE

5) Reservoir

- a. Slopes OKAY
- b. Sedimentation NO EVIDENT PROBLEMS
- c. Unusual Conditions Which Affect Dam NONE

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) LOCAL ROAD BRIDGE ON SAGAMORE RD.; STATE RTE 301; SEVERAL HOMES SCATTERED ALONG CHANNEL
- b. Seepage, Unusual Growth NONE
- c. Evidence of Movement Beyond Toe of Dam NONE
- d. Condition of Downstream Channel RELATIVELY NARROW - 15'-20' WIDE BOTTOM W/ STEEP SIDES; BRIDGE WATERWAY = 7.5' W X 10' H

7) Spillway(s) (Including Discharge Conveyance Channel)

CONCRETE GRAVITY OVERFLOW SECTION - FLASHBOARDS IN CENTER WINGWALLS ON EITHER SIDE

- a. General CONCRETE ON OVERFLOW SECTION IN GOOD SHAPE - ONLY MINOR SPALLING OF SURFACE
SOME EFFLORESCENCE ALONG JOINTS ON WINGWALLS
- b. Condition of Service Spillway STOPLOGS IN GOOD CONDITION
SOME MISSING MATERIAL BEHIND RIGHT WINGWALL
AT THE BOTTOM - PROBABLY REMOVED BY SCOUR

c. Condition of Auxiliary Spillway N/A

d. Condition of Discharge Conveyance Channel SOMEWHAT NARROW,
GOES UNDER COUNTY ROAD BRIDGE

8) Reservoir Drain/Outlet

Type: Pipe ✓ Conduit _____ Other _____

Material: Concrete _____ Metal _____ Other _____

Size: _____ Length _____

Invert Elevations: Entrance _____ Exit _____

Physical Condition (Describe): _____ Unobservable ✓

Material: _____

Joints: _____ Alignment _____

Structural Integrity: _____

Hydraulic Capability: _____

Means of Control: Gate ✓ Valve _____ Uncontrolled _____

Operation: Operable _____ Inoperable _____ Other UNKNOWN

Present Condition (Describe): COULD NOT LOCATE THE
OUTLET PIPE

9) STRUCTURAL - CONCRETE DESCRIBED UNDER SPILLWAY SECTION
10 & 11 - NOT APPLICABLE

APPENDIX C
HYDROLOGIC/HYDRAULIC
ENGINEERING DATA AND COMPUTATIONS

SAGAMORE LAKE DAM
NY-313

CHECK LIST FOR DAMS
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	(USGS) <u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>659.45</u>	<u>96 +</u>	<u>1824</u>
2) Design High Water (Max. Design Pool)	<u>N/A</u>	<u> </u>	<u> </u>
3) Auxiliary Spillway Crest	<u>N/A</u>	<u> </u>	<u> </u>
4) Pool Level with Flashboards	<u>N/A</u>	<u> </u>	<u> </u>
5) Service Spillway Crest	<u>656</u>	<u>96</u>	<u>1492</u>
6) STOPLOG SLOT-INN.	<u>654.4</u>	<u>-</u>	<u>-</u>

DISCHARGES

	<u> </u> (cfs)
1) Average Daily	<u>N/A</u>
2) Spillway @ Maximum High Water (STOPLOGS IN-PLACE)	<u>983</u>
3) Spillway @ Design High Water	<u>N/A</u>
4) ~~STOPLOGS OUT; WATER @~~ Spillway Crest Elevation	<u>43</u>
5) Low Level Outlet	<u>N/A</u>
6) ~~MAX.~~ (of all facilities) @ Maximum High Water	<u>1026</u>
7) Maximum Known Flood	<u>N/A</u>
8) At Time of Inspection	<u>± 10</u>

SAGAMORE LAKE DAM
NY-313

2

CREST:

(USGS)
ELEVATION: 659.45

Type: EARTH w/ VEGETATIVE COVER
Width: VARIABLE 20'-27' Length: ±250'
Spillover CONCRETE WEIR
Location NEAR LEFT END OF EMBANKMENT

SPILLWAY:

SERVICE

656 Elevation _____
SHARP-CRESTED WEIR w/ END CONTRACTIONS Type NONE
±2' Width _____
Type of Control _____
✓ Uncontrolled _____
Controlled: _____
ALSO A STOPLOG SLOT BELOW SPILLWAY CREST Type _____
(Flashboards; gate) _____
± 4 STOPLOGS Number _____
1.6' DEEP x 8.8' WIDE Size/Length _____
Invert Material _____
Anticipated Length of operating service _____
N/A Chute Length _____
> 10' Height Between Spillway Crest & Approach Channel Invert (Weir Flow) _____

HYDROMETEROLOGICAL GAGES:

Type : NONE

Location: _____

Records:

Date - _____

Max. Reading - _____

FLOOD WATER CONTROL SYSTEM:

Warning System: NONE

Method of Controlled Releases (mechanisms):

20" Ø DRAIN ; ELEV. UNKNOWN

DRAINAGE AREA: 3783 ACRES 5.91 SQ. MILES

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: UNDEVELOPED w/ FORESTS, WOODLANDS, WETLANDS

Terrain - Relief: MODERATE TO STEEP; HILLTOPS @ 350'-650' ABOVE RESV.

Surface - Soil: GLACIAL DEPOSITS

Runoff Potential (existing or planned extensive alterations to existing
(surface or subsurface conditions)

NONE APPARENT

Potential Sedimentation problem areas (natural or man-made; present or future)

NO

Potential Backwater problem areas for levels at maximum storage capacity
including surcharge storage:

NONE APPARENT

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the
Reservoir perimeter:

Location: NO

Elevation: _____

Reservoir:

Length @ Maximum Pool ± 4500' ± 0.85 (Miles)

Length of Shoreline (@ Spillway Crest) ± 2.80 (Miles)
± 14800'

PROJECT GRID

JOB SAGAMORE LAKE DAM		SHEET NO. NY-313		CHECKED BY		DATE	
SUBJECT WATERSHED PARAMETERS				COMPUTED BY WCL		DATE 6/24/81	
DRAINAGE AREA :							
USGS 7.5 MIN QUAD = OSCAWANA LAKE							
SCALE: 1" = 3000' 1 SQ. IN = 91.827 ACRES							
PLANIMETERED AREAS:				BASIN		LAKE SURFACE	
(SQ INS.)				22.82		1.05	
				18.38			
				41.20			
(ACRES)				3783		96.4 @ ELEV.	
						656	
(SQ MI)				5.91			
TOTAL : WETLANDS (MARSH)							
243 ACRES = 2.65 SQ INS							
% OF BASIN = 6.4							
PRECIPITATION :							
REF: HRR 33				ADJUSTMENT (AREA - DURATION)			
				6 12 24 48			
INDEX RAINFALL = 21.2"							
(ZONE 1)				% OF INDEX			
				III 123 132 142			

PROJECT GRID

JOB SAGAMORE LAKE DAM		SHEET NO. 2/	CHECKED BY	DATE
SUBJECT WATERSHED PARAMETERS		COMPUTED BY WCL		DATE 6/24/81

SNYDER UNIT HYDROGRAPH:

LAG TIME: $t_p = C_t (L \times L_{CA})^{0.3}$

$C_t = 2$
 $L = 3.79$
 $L_{CA} = 5780' = 1.09$

$t_p = 2(3.79 \times 1.09)^{0.3}$

$t_p = 3.06 \text{ HRS}$

UNIT RAIN DURATION: $t_r = \frac{t_p}{5.5}$

$t_r = 0.56$

USE $T_r = 0.5 \text{ HRS}$ ←

ADJUSTED LAG TIME: $TP = t_p + 0.25(T_r - t_r)$

$TP = 3.06 + 0.25(0.5 - 0.56)$

$TP = 3.05 \text{ HRS}$ ←

PEAKING COEFFICIENT: CP

REF: NY DISTRICT - CORPS ENGINEERS
 LOWER HUDSON RIVER BASIN
 HYDRO ROUTING MODEL STUDY

ADJACENT WATERSHEDS:

	SUBBASIN #	640 CP	CP
PEEKSKILL HOLLOW CREEK	1	364	→ 0.57
	2	384	→ 0.60

USE CP = 0.57 ←

PROJECT GRID

JOB SAGAMORE LAKE DAM		SHEET NO. 3/	CHECKED BY	DATE
SUBJECT		COMPUTED BY WCL		DATE 6/24/81

SOIL RETENTION - RAINFALL LOSS RATES:

* REF: LOWER HUDSON RIVER BASIN MODEL STUDY

(SAME) ADJACENT WATERSHEDS: INITIAL = 1.5 INS.
CONSTANT = 0.1 INS./HR

* BASE FLOW:
REF: — SAME:
START Q = 1 cfs/50 MI. → 6 cfs
QRC SN = 0.25
RTIOR = 3

RESERVOIR STORAGE VOLUME:

REF: 5/20/46 APPLICATION (RECONSTRUCTION)

@ ELEV 656: VOL = $65 \times 10^6 \text{ FT}^3$ → 1492 AC-FT CREST

@ ELEV 638 HT ≈ 18' VOL = → 0 AC-FT

@ ELEV 659.45
ΔVOL = $(3.45 \times 96.4) = 332.6 \text{ AC-FT}$ TOP DAM
VOL → 1824.6 AC-FT

PROJECTED VOL = 96.4 AC-FT/FT

@ 664.45 H=5 AV = 482 → 2306.6 AC-FT

@ 666 H=6.55 AV = 631.4 → 2456 AC-FT

PROJECT GRID

JOB SAGAMORE LAKE DAM		SHEET NO. 4/		CHECKED BY	DATE
SUBJECT SPILLWAY - DISCHARGE CAPACITY				COMPUTED BY WCL	DATE 6/24/81
WEIR FLOW: $Q = CLH^{3/2}$				STOPLOGS IN-PLACE	
w/ SIDEWALL CONTRACTION		$C = 3.25$ $L = L' - 2(NK_p + K_g)H$ $L' = 47.9'$ $N = 0$ $K_g = 0.1$ $L = 47.9 - 0.2H$			
ELEV.	H	L	Q		
656	—	47.9	—		
	0.5	47.8	54.9		
	1	47.7	155		
	1.5	47.6	284		
	2	47.5	436		
	2.5	47.4	609		
	3	47.3	798		
TOP DAM	659.45	3.45	47.21	983	
	660	4	47.21	1227	
	660.5	4.5	47.21	1464	
	661	5	47.21	1715	
	662	6	47.21	2255	
	664	8	47.21	3471	
	666	10	47.21	4852	
				ADDITIONAL CAPACITY w/ NO STOPLOGS IN-PLACE:	
				$Q = CLH^{3/2}$ $C = 2.63$ $L = 8.8 - 0.4H$ $H = 1.6'$ $Q = 43.4 cfs$	

PROJECT GRID

JOB SAGAMORE LAKE DAM				SHEET NO. 5/		CHECKED BY		DATE	
SUBJECT DISCHARGE						COMPUTED BY WCL		DATE 6/24/81	

EMBANKMENT OVERTOPPING :				UNEVEN EMB. CREST			
WEIR FLOW		$Q = CLH^{3/2}$		$C = 2.63$			
ELEV.	H	L	Q	H	L	Q	TOTAL Q
659.45	—	160	—				—
660	0.55	160	171				171
660.5	1.05	160	452	—	90	—	452
661	1.55	↑	812	0.50	↑	83	895
662	2.55		1713	1.5		434	2147
664	4.55	↓	4084	3.5	↓	1550	5634
666	6.55	160	7054	5.5	90	3053	10107


TOP OF DAM :

ELEV = 659.45


WEIR FLOW $Q = CLH^{3/2}$

$C = 2.63$

USE L = 0



ELEVATION



SECTION A-A
(THRU STOPLOG SLOT)

SAGAMORE LAKE DAM
NY - 313

[FIELD MEASUREMENTS - MAY 1981]

NY - 313

DAM: SAGAMORE LAKE DAM

SUMMARY OF FLOOD ANALYSIS

By: WCL Date: 7/1/81
Sht: 6/

ANALYSIS CONDITIONS:	RATIO	PEAK		Overtopping Depth @ Dam	STA: 4800 W.S.Elev.	DOWNSTREAM LOCATION	
		INFLOW	OUTFLOW			Inv: 600.0 Flow Depth	Inv: N/A Flow Depth
NO BREACH	0.13	1347	908	-0-	604.3	4.3	
	0.14	1451	993	0.01	604.5	4.5	
	0.15					± 5.0	
	0.50	5181	5019	2.81	608.0	8.0	
	1	10363	10143	4.90	609.9	9.9	
FAIL ELEV. = 659.6:							
BREACH: DEPTH ±10'	0.14	1451	993	0.01	604.5	4.5	
BRWD = 15' BOT.							
BOT. ELEV. = 649	0.15	1554	3256	0.16	607.0	7.0	
TFAIL = 0.5 HRS							
	0.50	5181	4996	1.15	608.0	8.0	
	1	10363	10164	3.28	609.9	9.9	
BREACH: DEPTH ±19'	0.14	1451	993	0.01	604.5	4.5	
BRWD = 15' BOT.							
BOT. ELEV. = 640	0.15	1554	5588	0.16	608.1	8.1	
TFAIL = 2.0 HRS							
	0.50	5181	8527	1.10	609.2	9.2	
	1	10363	10020	1.11	609.8	9.8	

ΔH

-0


-2.0

-3.1

SAGAMORE LAKE DAM NY-313

DOWNSTREAM CHANNEL SECTION

$\Delta H \approx 53'$
 $L \approx 4800'$
 $n \approx 0.045$
 $\% \text{ SLOPE} = 1.10$



NEW YORK STATE
DEPT OF ENVIRONMENTAL CONSERVATION
FLOOD PROTECTION BUREAU

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 26 FEB 79
MODIFIED FOR HONEYWELL APR 79

SAGAMORE LAKE DAM
DEC 213-1113 LH -- WEST BR CROTON RIVER
LAKE SAGAMORE ASSOC
0 30 0 0 0 0 0

LOWER HUDSON RIVER BASIN
PUTNAM COUNTY
SNYDER UH

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

0 0 0 0 0 0 0

31	Y6	0.045	0.045	0.045	600	612	4.100	0.011		
32	Y7	100	612	150	607	230	.05	240	600	600
33	Y7	270	605	350	607	400	.12			
34	K									99
35	A									
36	A									
37	A									
38	A									
39	A									
40	A									
41	A									

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS
RUNOFF HYDROGRAPH AT UASIN
ROUTE HYDROGRAPH TO DAM
ROUTE HYDROGRAPH TO 4800
END OF NETWORK

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 26 FEB 79
MODIFIED FOR HONEYWELL APR 79

NEW YORK STATE
DEPT OF ENVIRONMENTAL CONSERVATION
FLOOD PROTECTION BUREAU

RUN DATE 06/26/81 NY-313 SAGAHORE LAKE DAM
DEC 213-1113 LH -- WEST BR CHOTON RIVER
LAKE SAGAHORE ASSOC

LOWER HUDSON RIVER BASIN
PUTNAM COUNTY
SNYDER UH

JOB SPECIFICATION
NQ NHR NMIM IDAY IHR IMIN METRC IPLT IPRT NSTAN
150 0 30 0 0 0 0 0 0 0 0 0
JOPER NWT LROPT TRACE
5 0 0 0 0 0 0 0 0 0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 1 NR110= 3 LR110= 1
RT105= 0.10 0.11 0.12 0.13 0.14 0.15 0.50 1.00

SUB-AREA RUNOFF CONFIGURATION

INFLOW HYDROGRAPH - DAM
ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO
BASIN 0 0 0 0 0 0 0 0 0 0 0 0

HYDROGRAPH DATA
INVDG IUNG TAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL
1 1 5.91 0. 5.91 0. 0. 0. 0. 0. 1 0

PRECIP DATA
SPFE PRS R6 R12 R24 R48 R72 R96
0. 21.20 111.00 123.00 132.00 142.00 0. 0.

LOSS DATA
LROPT STRKR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP
0 0. 0. 1.00 0. 0. 1.00 1.00 1.50 0.10 0. 0.06

UNIT HYDROGRAPH DATA
TP= 3.05 CP=0.57 NTA= 0

RECESSION DATA
STRTO= 6.00 GRCSN= -0.25 RTIOR= 3.00
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 6.91 AND R= 6.51 INTERVALS

UNIT HYDROGRAPH 39 END-OF-PERIOD ORIGINATES, LAG= 3.06 HOURS, CP= 0.57 VOL= 1.00
42. 156. 311. 480. 624. 719. 653. 560. 480.
412. 353. 303. 260. 223. 191. 164. 140. 120. 103.
88. 76. 65. 56. 48. 41. 35. 30. 26. 22.
19. 14. 12. 10. 9. 8. 6. 6.

END-OF-PERIOD FLOW
MO.DA HR.MU PERIOD RAIN EXCS LOSS COMP 3
1.01 0.30 1 0.00 0.00 0.00 1.00
1.00 0.00 1 0.00 0.00 0.00 1.00

UNIT HYDROGRAPH 32 END-OF-PERIOD ORDINATES, LAG 3.06 HOURS, CP= 0.57 VOL= 1.00

480.
103.
22.

MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW COMP J	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
1.01	0.30	1	0.00	0.00	0.00	5.	1.02	14.00	76	1.13	1.08	0.05	1600.
1.01	1.00	2	0.00	0.00	0.00	5.	1.02	14.30	77	1.41	1.37	0.05	2172.
1.01	1.30	3	0.00	0.00	0.00	4.	1.02	15.00	78	1.41	1.37	0.05	2870.
1.01	2.00	4	0.00	0.00	0.00	4.	1.02	15.30	79	1.72	1.67	0.05	3657.
1.01	2.30	5	0.00	0.00	0.00	4.	1.02	16.00	80	5.44	5.39	0.05	4648.
1.01	3.00	6	0.00	0.00	0.00	4.	1.02	16.30	81	1.32	1.27	0.05	5903.
1.01	3.30	7	0.00	0.00	0.00	4.	1.02	17.00	82	1.32	1.27	0.05	7267.
1.01	4.00	8	0.00	0.00	0.00	3.	1.02	17.30	83	1.04	0.99	0.05	8585.
1.01	4.30	9	0.00	0.00	0.00	3.	1.02	18.00	84	1.04	0.99	0.05	9653.
1.01	5.00	10	0.00	0.00	0.00	3.	1.02	18.30	85	0.08	0.03	0.05	10284.
1.01	5.30	11	0.00	0.00	0.00	3.	1.02	19.00	86	0.08	0.03	0.05	10363.
1.01	6.00	12	0.00	0.00	0.00	3.	1.02	19.30	87	0.08	0.03	0.05	9877.
1.01	6.30	13	0.01	0.00	0.01	3.	1.02	20.00	88	0.08	0.03	0.05	9055.
1.01	7.00	14	0.01	0.00	0.01	3.	1.02	20.30	89	0.08	0.03	0.05	8115.
1.01	7.30	15	0.01	0.00	0.01	3.	1.02	21.00	90	0.08	0.03	0.05	7133.
1.01	8.00	16	0.01	0.00	0.01	3.	1.02	21.30	91	0.08	0.03	0.05	6183.
1.01	8.30	17	0.01	0.00	0.01	3.	1.02	22.00	92	0.08	0.03	0.05	5334.
1.01	9.00	18	0.01	0.00	0.01	4.	1.02	22.30	93	0.08	0.03	0.05	4605.
1.01	9.30	19	0.01	0.01	0.01	4.	1.02	23.00	94	0.08	0.03	0.05	3981.
1.01	10.00	20	0.01	0.00	0.01	5.	1.02	23.30	95	0.08	0.03	0.05	3445.
1.01	10.30	21	0.01	0.00	0.01	5.	1.03	0.	96	0.08	0.03	0.05	2986.
1.01	11.00	22	0.01	0.00	0.01	5.	1.03	0.30	97	0.	0.	0.	2591.
1.01	11.30	23	0.01	0.00	0.01	5.	1.03	1.00	98	0.	0.	0.	2322.
1.01	12.00	24	0.01	0.00	0.01	5.	1.03	1.30	99	0.	0.	0.	2080.
1.01	12.30	25	0.07	0.00	0.07	6.	1.03	2.00	100	0.	0.	0.	1864.
1.01	13.00	26	0.07	0.00	0.07	6.	1.03	2.30	101	0.	0.	0.	1670.
1.01	13.30	27	0.09	0.01	0.08	8.	1.03	3.00	102	0.	0.	0.	1496.
1.01	14.00	28	0.09	0.01	0.08	10.	1.03	3.30	103	0.	0.	0.	1340.
1.01	14.30	29	0.11	0.01	0.10	12.	1.03	4.00	104	0.	0.	0.	1201.
1.01	15.00	30	0.11	0.01	0.10	16.	1.03	4.30	105	0.	0.	0.	1076.
1.01	15.30	31	0.13	0.01	0.12	20.	1.03	5.00	106	0.	0.	0.	964.
1.01	16.00	32	0.41	0.03	0.39	24.	1.03	5.30	107	0.	0.	0.	864.
1.01	16.30	33	0.10	0.01	0.09	30.	1.03	6.00	108	0.	0.	0.	774.
1.01	17.00	34	0.10	0.01	0.09	37.	1.03	6.30	109	0.	0.	0.	693.
1.01	17.30	35	0.08	0.02	0.06	44.	1.03	7.00	110	0.	0.	0.	621.
1.01	18.00	36	0.03	0.03	0.05	52.	1.03	7.30	111	0.	0.	0.	557.
1.01	18.30	37	0.01	0.00	0.01	61.	1.03	8.00	112	0.	0.	0.	499.
1.01	19.00	38	0.01	0.00	0.01	68.	1.03	8.30	113	0.	0.	0.	447.
1.01	19.30	39	0.01	0.00	0.01	73.	1.03	9.00	114	0.	0.	0.	400.
1.01	20.00	40	0.01	0.00	0.01	74.	1.03	9.30	115	0.	0.	0.	359.
1.01	20.30	41	0.01	0.00	0.01	72.	1.03	10.00	116	0.	0.	0.	321.
1.01	21.00	42	0.01	0.00	0.01	66.	1.03	10.30	117	0.	0.	0.	288.
1.01	21.30	43	0.01	0.00	0.01	58.	1.03	11.00	118	0.	0.	0.	258.
1.01	22.00	44	0.01	0.00	0.01	50.	1.03	11.30	119	0.	0.	0.	231.
1.01	22.30	45	0.01	0.00	0.01	44.	1.03	12.00	120	0.	0.	0.	207.
1.01	23.00	46	0.01	0.00	0.01	38.	1.03	12.30	121	0.	0.	0.	186.
1.01	23.30	47	0.01	0.00	0.01	33.	1.03	13.00	122	0.	0.	0.	166.
1.02	0.	48	0.01	0.00	0.01	29.	1.03	13.30	123	0.	0.	0.	149.
1.02	0.30	49	0.05	0.00	0.05	25.	1.03	14.00	124	0.	0.	0.	133.
1.02	1.00	50	0.05	0.00	0.05	22.	1.03	14.30	125	0.	0.	0.	120.
1.02	1.30	51	0.05	0.00	0.05	21.	1.03	15.00	126	0.	0.	0.	107.
1.02	2.00	52	0.05	0.00	0.05	20.	1.03	15.30	127	0.	0.	0.	97.

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
------	--------	---------	---------	--------------

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
------	--------	---------	---------	--------------

ROUTED	OUTFLOW	-	DAM	-	SPILL	CREST	ELEV	656-USGS	--	STOPLOGS	IN
ISTAQ	IICOMP		IECON		ITAPE	JPLT	JPR1			INAME	ISTAGE
1	1		1		1	1	1			1	1
2	2		2		2	2	2			2	2
3	3		3		3	3	3			3	3
4	4		4		4	4	4			4	4
5	5		5		5	5	5			5	5
6	6		6		6	6	6			6	6
7	7		7		7	7	7			7	7
8	8		8		8	8	8			8	8
9	9		9		9	9	9			9	9
10	10		10		10	10	10			10	10
11	11		11		11	11	11			11	11
12	12		12		12	12	12			12	12
13	13		13		13	13	13			13	13
14	14		14		14	14	14			14	14
15	15		15		15	15	15			15	15
16	16		16		16	16	16			16	16
17	17		17		17	17	17			17	17
18	18		18		18	18	18			18	18
19	19		19		19	19	19			19	19
20	20		20		20	20	20			20	20
21	21		21		21	21	21			21	21
22	22		22		22	22	22			22	22
23	23		23		23	23	23			23	23
24	24		24		24	24	24			24	24
25	25		25		25	25	25			25	25
26	26		26		26	26	26			26	26
27	27		27		27	27	27			27	27
28	28		28		28	28	28			28	28
29	29		29		29	29	29			29	29
30	30		30		30	30	30			30	30
31	31		31		31	31	31			31	31
32	32		32		32	32	32			32	32
33	33		33		33	33	33			33	33
34	34		34		34	34	34			34	34
35	35		35		35	35	35			35	35
36	36		36		36	36	36			36	36
37	37		37		37	37	37			37	37
38	38		38		38	38	38			38	38
39	39		39		39	39	39			39	39
40	40		40		40	40	40			40	40
41	41		41		41	41	41			41	41
42	42		42		42	42	42			42	42
43	43		43		43	43	43			43	43
44	44		44		44	44</					

QCLASS	CCLASS	AVG	IRIS	ISAME	IOPT	IPMP	LSTR
0.	0.	0.	1	1	0	0	0

[illegible]

CREL	SPWID	COOW	EXPM	ELEV	COQL	CAREA	EXPL
656.	659.	664.	666.				
656.0	0.	0.	0.	0.	0.	0.	0.

DAM DATA			
TOPEL	COQD	EXPD	DAMVID
659-4	2-6	1-5	0.

STATION OAG, PLAN 1, RATIO 1

END-OF-PERIOD HYDROGRAPH ORDINATES

UNITED STATES

RATIO 8

[illegible]

HYDROGRAPH ROUTING

DAM TO SR-301

QLOSS	CLOSS	AVG	IREC	ISAME	ROUTING DATA	JILT	JPRT	INAME	ISTAGE	IAUTO
0	0	0	1	1	0	0	0	1	0	0
0	0	0	1	1	0	0	0	1	0	0

[illegible]

NORMAL DEPTH CHANNEL ROUTING

QN(1)	QN(2)	QN(3)	ELHVT	ELMAX	RLNTH	SEL
0.0450	0.0450	0.0450	600.0	612.0	4800.	0.01100

CROSS SECTION COORDINATES--STA,ELEV,STA,ELEV--ETC			
100.00	612.00	150.00	607.00
270.00	605.00	350.00	607.00
			400.00
			612.00

	0.	1.48	3.14	4.97	6.97	9.16	11.52	14.05	16.77	21.61
STORAGE	29.96	41.83	56.10	71.27	87.31	104.23	122.04	140.72	160.28	180.71
OUTFLOW	0.	32.75	105.89	212.62	351.47	522.39	725.90	962.81	1238.64	1631.92
	2179.60	2947.23	4055.35	5421.46	7029.83	8877.87	10965.96	13296.23	15871.91	18696.92
STAGE	600.00	600.63	601.26	601.89	602.53	603.16	603.79	604.42	605.05	605.68
	606.32	606.95	607.58	608.21	608.84	609.47	610.11	610.74	611.37	612.00
FLOW	0.	32.75	105.89	212.62	351.47	522.39	725.90	962.81	1238.64	1631.92
	2179.60	2947.23	4055.35	5421.46	7029.83	8877.87	10965.96	13296.23	15871.91	18696.92

STATION 4800, PLAN 1, RTIO 1

OUTFLOW

0 0 0 2
0 0 0 2
0 0 0 1
0 0 0 1
0 0 0 1
0 0 0 1
0 0 0 1
0 0 0 1
0 0 0 0
0 0 0 0

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FORMULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQAWE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS							
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8
				0.10	0.11	0.12	0.13	0.14	0.15	0.50	1.00
HYDROGRAPH AT	BASIN	5.91	1	1036.	1140.	1244.	1347.	1451.	1554.	5181.	10363.
		(8237.39)	(	29.34)(	32.28)(	35.21)(	38.15)(	41.08)(	44.02)(	146.72)(	293.44)(
ROUTED TO	DAM	5.91	1	666.	745.	826.	908.	993.	1113.	5019.	10143.
		(8237.39)	(	18.85)(	21.11)(	23.38)(	25.71)(	28.13)(	31.51)(	142.13)(	287.23)(
ROUTED TO	4800	5.91	1	667.	745.	824.	906.	990.	1114.	5023.	10168.
		(8237.39)	(	18.88)(	21.10)(	23.33)(	25.64)(	28.05)(	31.55)(	142.24)(	287.93)(

SAGAMORE LAKE DAM
 NY-313

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		656.00		656.00		659.45			
OUTFLOW		1492.		1492.		1824.			
		0.		0.		983.			

.....
 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79
 MODIFIED FOR HONEYWELL APR 79

.....
 NEW YORK STATE
 DEPT OF ENVIRONMENTAL CONSERVATION
 FLOOD PROTECTION BUREAU

.....

SAGAMORE LAKE DAM
 DEC 213-1113 LH -- WEST BR CROTON RIVER
 LAKE SAGAMORE ASSOC
 SNYDER-UN
 PUTNAM COUNTY

A1 NY-313
 A2
 A3
 B 150
 B1 5

0 0 0 0 0

30 0 0 0 0

J 2 4 1

J1 0.14 0.15 0.50 1

K 0 BASIN

K1

INFLOW HYDROGRAPH - DAM

M 1 1 5.91

P 21.2 111 123 132 142

T 1.5 0.1 0.064

M 3.05 0.57

X 6 -0.25 3

K 1 DAY

K1

ROUTED OUTFLOW - DAM - SPILLCREST ELEV 656-USGS -- STOPLOGS -IN

Y 1 1

Y1 1

Y4 656 656.5 657 657.5 658 658.5 659 659.45 660 660.5

Y4 661 662 664 666

Y5 0 54.9 155 284 436 619 798 983 1398 1916

Y5 2610 4402 9105 14959

Y5 0 1492 1824 2306 2456

Y5 538 555 659.45 664.45 666

Y5 656

Y5 659.45 2.63 1.5 0

Y5 15 1 649 0.5 656 659.6

Y5 15 1 640 2 656 659.6

K 1 4800

K1 DAM TO SR-301

D/ BREACH

10092.45 2.63 1.5 0
 SR 15 1 649 0.5 656 659.6
 SR 15 1 640 2 656 659.6
 K 1 4800
 K1 DAM TO SR-301

31	Y			1	1	
32	Y1	1				
33	Y6	0.045	0.045	0.045	600	612 4800 0.011
34	Y7	100	612	150	607	230 405 240 600 260 600
35	Y7	270	605	350	607	400 612
36	K	99				
37	A					
38	A					
39	A					
40	A					
41	A					
42	A					
43	A					

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79
 MODIFIED FOR HONEYWELL APR 79

RUN DATE 07/01/81

NY-313 SAGAMORE LAKE DAM
 DEC 213-1113 LH -- WEST BR CROTON RIVER
 LAKE SAGAMORE ASSOC

LOWER HUDSON RIVER BASIN
 PUTNAM COUNTY
 SNYDER VH

JOB SPECIFICATION

NO	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
150	0	30	0	0	0	0	0	0	0
			JOPER	NWT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOS= 0.14 0.15 0.50 1.00
 NPLAN= 2 NRTIO= 4 LRTIO= 1

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH - DAM

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
BASIN	0	0	0	0	0	0	0	0

HYDROGRAPH DATA

IMVGR	IUMG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	5.91	0.	5.91	0.	0.	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.	21.20	111.00	123.00	132.00	142.00	0.	0.

TRSPC COMPUTED BY THE PROGRAM IS 0.800

LOSS DATA

LROPT	STRKR	DLTKR	RTIOL	ERAIN	STRKS	RTIOK	STRIL	CNSTL	ALSMX	RTIMP
0	0.	0.	1.00	0.	0.	1.00	1.50	0.10	0.	0.06

UNIT HYDROGRAPH DATA

TP= 3.05 CP=0.57 NTA= 0

RECESSION DATA

STRIQ= 6.00 GRCSN= -0.25 RTIOR= 3.00
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 6.91 AND R= 6.51 INTERVALS

UNIT HYDROGRAPH 39 END-OF-PERIOD ORDINATES

	LAG=	3.06 HOURS	CP= 0.57	VOL= 1.00
42.	156.	311.	480.	624.
412.	353.	303.	260.	223.
85.	76.	65.	56.	48.
19.	16.	14.	12.	10.

END-OF-PERIOD FLOW

MO-DA	HR-MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO-DA	HR-MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
1	01	0 30	0	0	0	0	1	03	14 00	74	1 12	1 08	0 00

324.52	517.41	535.81	535.88
4025.	6417.	6646.	6647.
4965.	7916.	8197.	8198.

PLAN

END-OF-PERIOD HYDROGRAPH ORDINATES

ALL PLANS HAVE SAME.

QLOSS	CLOSS	AVG	IR5	ISAME	IJPT	[PMP	LSTR
0	0	0	1	1	0	0	0

INSTPS	NSTD	LAG	AMSKK	X	TSK	STORA	ISPRAY
1	0	0	0	0	0	-656	-1

STAGE	454.00	457.00	458.50	657.50	658.00	658.50	659.00	659.45	660.00	660.50
-------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------

Flow	0.	54.90	155.00	284.00	435.00	609.00	798.00	983.00	1398.00	1916.00
------	----	-------	--------	--------	--------	--------	--------	--------	---------	---------

CAPACITY=	0.	1492.	1824.	2306.	2456.
-----------	----	-------	-------	-------	-------

ELEVATION=	638.	656.	659.	664.	666.
------------	------	------	------	------	------

CREL	SPUID	COQW	EXPM	ELE'L	COQL	CAREA	EXPL
0	0	0	0	0	0	0	0
54	0	0	0	0	0	0	0

IOPEL	DAM DATA		DAMWID
	COQD	EXPD	
659.4	2.6	1.5	0.

BRUID	Z	DAM BREACH DATA			WSEL	FAILEL
		ELBM	TFAIL			
15	1.00	649.00	0.50	656.00	659.60	

STATION DAM, 'LAN 1, RATIO 1

OUTFLOW

[illegible]

PLAN 2

BRUID	DAM BREACH DATA			
	Z	ELBM	TFAIL	WSEL
15.	1.00	640.00	2.00	656.00
				659.60

STATION DAM, PLAN 2, RATIO 1

END-OF-PERIOD HYDROGRAPH ORDINATES.

[illegible]

STORAGE

[illegible]

STAGE

[illegible]

•QVN•

HYDROGRAPH ROUTING

DAM TO SR-301
 ISTAQ ICOMP 1
 4800

ALL PLANS HAVE SAME
 ROUTING DATA

QLOSS CLOSS 0.0
 0.0

AVG IRES 1
 0.0

IECON ITAPE 0
 0

JPLT JPRF 0
 0

INAME ISTAGE 1
 0

IPMR 0
 0

LAG AMSKK 0
 0

MSK X 0
 0

STOR 0
 0

ISPRAT 0
 0

NORMAL DEPTH CHANNEL ROUTING

QN(1) QN(2) QN(3) ELNVT ELMAX RLNTH SEL
 0.0450 0.0450 0.0450 600.0 612.0 4800. 0.01100

CROSS SECTION COORDINATES--STA,ELEV,STA,ELEV--ETC
 100.00 612.00 150.00 607.00 230.00 605.00 240.00 600.00 260.00 600.00
 270.00 605.00 350.00 607.00 400.00 612.00

STORAGE	0.0	1.48	3.14	4.97	6.97	9.16	11.52	14.05	16.77	21.61
	29.96	41.83	56.10	71.27	87.31	104.23	122.04	140.72	150.23	180.71
OUTFLOW	0.0	32.75	135.89	212.62	351.47	522.39	725.90	962.81	1238.64	1631.92
	2179.60	2947.23	4055.35	5421.46	7029.83	8877.87	10965.96	13296.23	15871.91	18696.92
STAGE	600.00	600.63	601.26	601.89	602.53	603.16	603.79	604.42	605.05	605.68
	606.32	606.95	607.58	608.21	608.84	609.47	610.11	610.74	611.37	612.00
FLOW	0.0	32.75	105.89	212.62	351.47	522.39	725.90	962.81	1238.64	1631.92
	2179.60	2947.23	4055.35	5421.46	7029.83	8877.87	10965.96	13296.23	15871.91	18696.92

STATION 4800, PLAN 1, RTIO 1

OUTFLOW

0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
17.0	20.0	23.0	27.0	31.0	39.0	48.0	65.0	92.0	130.0	190.0
182.0	254.0	348.0	465.0	589.0	715.0	828.0	965.0	1120.0	1300.0	1500.0
985.0	958.0	922.0	873.0	819.0	765.0	711.0	659.0	608.0	563.0	519.0
520.0	491.0	463.0	430.0	380.0	352.0	326.0	301.0	278.0	259.0	239.0
241.0	223.0	208.0	193.0	179.0	165.0	153.0	144.0	135.0	126.0	117.0
118.0	111.0	104.0	97.0	91.0	85.0	79.0	74.0	69.0	64.0	60.0
59.0	56.0	53.0	51.0	49.0	47.0	45.0	43.0	41.0	39.0	37.0

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FORMULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

W/ BREACH

RATIOS APPLIED TO FLOWS

OPERATION	STATION	AREA	PLAN	RATIO 1	RATIO 2	RATIO 3	RATIO 4
				0.14	0.15	0.50	1.00

HYDROGRAPH AT	BASIN	5.91	1	1451.	1554.	5181.	10363.
	(-0.00)	(41.08)	(44.02)	(146.72)	(293.44)		
			2	1451.	1554.	5181.	10363.
			(41.08)	(44.02)	(146.72)	(293.44)	

ROUTED TO	DAM	5.91	1	993.	3256.	4996.	10166.
	(9743.86)	(28.13)	(92.21)	(141.48)	(287.81)		
			2	993.	5588.	8527.	10020.
			(28.13)	(158.24)	(241.43)	(283.74)	

ROUTED TO	4800	5.91	1	990.	3009.	4990.	10166.
	(9743.88)	(28.05)	(85.20)	(141.29)	(287.88)		
			2	990.	5183.	8056.	10025.
			(28.05)	(146.75)	(228.13)	(283.89)	

SUMMARY OF DAM SAFETY ANALYSIS

W/ BREACH

PLAN 1

ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
STORAGE	656.00	656.00	659.45
OUTFLOW	1492.	1492.	1824.
	0.	0.	983.

RATIO OF PMF	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
0.14	0.01	1825.	993.	0.50	45.00	0.
0.15	0.16	1839.	3256.	1.38	45.00	44.50
0.50	1.15	1935.	4996.	6.00	43.50	40.50
1.00	3.28	2140.	10164.	9.50	43.00	39.00

PLAN 2

ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
STORAGE	656.00	656.00	659.45
OUTFLOW	1492.	1492.	1824.
	0.	0.	983.

RATIO OF PMF	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
0.14	0.01	1825.	993.	0.50	45.00	0.
0.15	0.16	1840.	5588.	1.62	46.50	44.50
0.50	1.10	1930.	8527.	2.35	42.50	40.50
1.00	1.11	1931.	10020.	5.15	43.50	39.00


PLAN 1 STATION 4800

RATIO	MAXIMUM FLOW/CFS	MAXIMUM STAGE/FT	TIME HOURS
0.14	990.	604.5	45.00
0.15	3009.	607.0	45.50
0.50	4990.	608.0	43.50
1.00	10166.	609.9	43.50

PLAN 2 STATION 4800

RATIO	MAXIMUM FLOW/CFS	MAXIMUM STAGE/FT	TIME HOURS
0.14	990.	604.5	45.00
0.15	5183.	608.1	46.50
0.50	8056.	609.2	42.50
1.00	10025.	609.8	43.50

SAGAMORE LAKE DAM
NY-313



DRAINAGE AREA MAP
SAGAMORE LAKE DAM
NY-313

NOTE:
TRIBUTARY STREAMS
AND WETLANDS

APPENDIX D
STABILITY COMPUTATIONS

STRUCTURAL STABILITY ANALYSIS

The analysis was based on a cross section shown on plans. A normal analysis was performed including both overturning and sliding analysis. Due to unknown foundation conditions, full uplift was assumed at the upstream toe, decreasing to the tailwater pressure at the downstream toe.

ANALYSIS CONDITIONS

1. Normal conditions; water surface at spillway crest
2. Same as #1 plus ice load of 5,000 pounds per linear foot
3. Flood Flows water surface at top of dam (3.5 feet above spillway crest).
4. One-half PMF flow-water surface 6.3 feet above spillway crest (2.8 feet above top of dam).
5. Seismic Conditions - Water at Spill Crest with seismic coefficient of 0.1

SAGAMORE LAKE DAM - NY 313

SCALE 1" = 5'

DISTANCE FROM CENTROID
TO DOWNSTREAM TOE (ft)

AREA (ft²)

$$(23.5)(12.5) = 294$$

$$(14)(22.5) = 42.75$$

$$(18.75)(14.5) = 271.9$$


$$(4.75)(7) = 33.25$$

①

②

③

④



STABILITY ANALYSIS PROGRAM - WORK SHEET

INPUT ENTRY

ANALYSIS CONDITION

		1	2	3	4	5
Unit Weight of Dam (K/ft ³)	0	0.15	0.15	0.15	0.15	0.15
Area of Segment No. 1 (ft ²)	1	29.4	29.4	29.4	29.4	29.4
Distance from Center of Gravity of Segment No. 1 to Downstream Toe (ft)	2	17.4	17.4	17.4	17.4	17.4
Area of Segment No. 2 (ft ²)	3	42.75	42.75	42.75	42.75	42.75
Distance from Center of Gravity of Segment No. 2 to Downstream Toe (ft)	4	15.6	15.6	15.6	15.6	15.6
Area of Segment No. 3 (ft ²)	5	271.9	271.9	271.9	271.9	271.9
Distance from Center of Gravity of Segment No. 3 to Downstream Toe (ft)	6	9.7	9.7	9.7	9.7	9.7
Base Width of Dam (Total) (ft)	7	18	18	18	18	18
Height of Dam (ft)	8	24	24	24	24	24
Ice Loading (K/L ft.)	9	—	5.0	—	—	—
Coefficient of Sliding	10	0.5	0.5	0.5	0.5	0.5
Unit Weight of Soil (K/ft ³) (deduct 13)	11	0.055	0.055	0.055	0.055	0.055
Active Soil Coefficient - Ka	12	0.27	0.27	0.27	0.27	0.27
Passive Soil Coefficient - Kp	13	3.69	3.69	3.69	3.69	3.69
Height of Water over Top of Dam or Spillway (ft)	14	—	—	3.5	6.31	—
Height of Soil for Active Pressure (ft)	15	6	6	6	6	6
Height of Soil for Passive Pressure (ft)	16	6	6	6	6	6
Height of Water in Tailrace Channel (ft)	17	7	7	10	10	7
Weight of Water (K/ft ³)	18	0.0624	0.0624	0.0624	0.0624	0.0624
Area of Segment No. 4 (ft ²)	19	33.25	33.25	33.25	33.25	33.25
Distance from Center of Gravity of Segment No. 4 to Downstream Toe (ft)	20	4.75	4.75	4.75	4.75	4.75
Height of Ice Load or Active Water (ft) (does not include 14)	46	24	24	24	24	24
Seismic Coefficient (g)	50	—	—	—	—	0.1
<u>RESULTS OF ANALYSIS</u>						
Factor of Safety vs. Overturning		1.84	1.35	1.52	1.35	1.74
Distance From Toe to Resultant		7.07	4.01	5.63	4.28	6.57
Factor of Safety vs. Sliding		1.36	1.07	1.09	0.92	0.76

APPENDIX E

REFERENCES

APPENDIX E

REFERENCES

- 1) T. S. George and R.S. Taylor: Lower Hudson River Basin, Hydrologic Flood Routing Model, for the Department of the Army, New York District, Corps of Engineers, Water Resources Engineers Inc. January 1977.
- 2) H.W. King and E.F. Brater, Handbook of Hydraulics, 5th edition, McGraw Hill, 1963.
- 3) University of the State of New York, Geology of New York, Education Leaflet 20, Reprinted 1973.

U.S. Army Corp of Engineers:

- 4) HEC-1 Flood Hydrograph Package - Dam Safety Version, September 1978.
- 5) Engineering Manual 1110-2-1405; Flood-Hydrograph Analyses and Computations, August 1959.
- 6) U.S. Department of Agriculture, Soil Conservation Service; National Engineering Handbook; Section 4 - Hydrology, August 1972.
- 7) U.S. Department of Commerce; Weather Bureau;
Hydrometeorological Report No. 33:
Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1,000 Square Miles and Durations of 6, 12, 24 and 48 Hours, April 1956.
- 8) U.S. Department of Interior, BUREC; Design of Small Dams, 2nd edition (rev. reprint), 1977.

AD-A105 720 NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/B 13/13
NATIONAL DAM SAFETY PROGRAM, SAGAMORE LAKE DAM (INVENTORY NUMBE--ETC(U)
AUG 81 @ KOCH DACW51-79-C-0001
UNCLASSIFIED NL

NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/G 13/13
NATIONAL DAM SAFETY PROGRAM, SAGAMORE LAKE DAM (INVENTORY NUMBE--ETC(U)
AUG 81 @ KOCH DACWS1-79-C-0001
NL

AD-A105 720 NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/B 13/13
NATIONAL DAM SAFETY PROGRAM, SAGAMORE LAKE DAM (INVENTORY NUMBE--ETC(U)
AUG 81 @ KOCH DACW51-79-C-0001
UNCLASSIFIED NL


40
410000


DATE _____

11-00000

DTIC

APPENDIX F
DRAWINGS AND
RELATED DOCUMENTS





TOPOGRAPHIC MAP
SAGAMORE LAKE DAM
NY-313

STATE OF NEW YORK



DEPARTMENT OF PUBLIC WORKS
DIVISION OF ENGINEERING

ALBANY

Received July 6, 1940 Dam No. _____
Disposition _____ Watershed _____
Foundation inspected _____
Structure inspected _____

Application for the Construction or Reconstruction of a Dam

Application is hereby made to the Superintendent of Public Works, Albany, N. Y., in compliance with the provisions of Section 948 of the Conservation Law (see last page of this application) for the approval of specifications and detailed drawings, marked _____

herewith submitted for the { construction } of a dam herein described. All provisions of law will be complied with in the erection of the proposed dam. It is intended to complete the work covered by the application about

Aug 15 30th
(Date)

1. The dam will be on West Branch of Croton flowing into Boyd's in the town of West County of Putnam and 100 ft west of old Forge dam
(give exact distance and direction from a well-known bridge, dam, village main cross-roads or mouth of a stream)

2. Location of dam is shown on the USGS quadrangle of the United States Geological Survey.

3. The name of the owner is Putnam Co. Ryder

4. The address of the owner is Carmel N.Y.

5. The dam will be used for Power

6. Will any part of the dam be built upon or its pond flood any State lands? No

7. The watershed above the proposed dam is 6 square miles.

8. The proposed dam will create a pond area at the spillcrest elevation of 30 acres and will impound _____ cubic feet of water.

9. The maximum height of the proposed dam above the bed of the stream is 9 feet _____ inches.
10. The lowest part of the natural shore of the pond is _____ feet vertically above the spillcrest, and everywhere else the shore will be at least _____ feet above the spillcrest.

11. State if any damage to life or to any buildings, roads or other property could be caused by any possible failure of the proposed dam. None

12. The natural material of the bed on which the proposed dam will rest is (clay, sand, gravel, boulders, granite, shale, slate, limestone, etc.) Clay + Boulders

13. Facing down stream, what is the nature of material composing the right bank? Hard Pan Clay, & Rocks

14. Facing down stream, what is the nature of the material composing the left bank? Hard Pan, Clay, & Rocks

15. State the character of the bed and the banks in respect to the hardness, perviousness, water bearing, effect of exposure to air and to water, uniformity, etc. Hard Pan Clay, & Rocks

16. Are there any porous seams or fissures beneath the foundation of the proposed dam? No

17. WASTES. The spillway of the above proposed dam will be 50 feet long in the clear; the waters will be held at the right end by a Retaining wall the top of which will be 3 feet above the spillcrest, and have a top width of 1 feet; and at the left end by a Retaining wall the top of which will be 3 feet above the spillcrest, and have a top width of 1 feet.

18. The spillway is designed to safely discharge _____ cubic feet per second.

19. Pipes, sluice gates, etc., for flood discharge will be provided through the dam as follows:

20" gate in pipe just on water side

20. What is the maximum height of flash boards which will be used on this dam? 1' 6"

21. APRON. Below the proposed dam there will be an apron built of Concrete feet long across the stream, 50 feet wide and 1 feet thick.

22. Does this dam constitute any part of a public water supply? No, -

and will impound.....4,400,000.....cubic feet of water.

9. The maximum height of the proposed dam above the bed of the stream is 21 feet 6 inches.
10. The lowest part of the natural shore of the pond is 4 feet vertically above the spillcrest, and everywhere else the shore will be at least 4 feet above the spillcrest.
11. State if any damage to life or to any buildings, roads or other property could be caused by any possible failure of the proposed dam. Yes. Downstream of town Road No. 1
Buildings destroyed
12. The natural material of the bed on which the proposed dam will rest is (clay, sand, gravel, boulders, granite, shale, slate, limestone, etc.) clay
13. Facing downstream, what is the nature of material composing the right bank? hard pan
14. Facing downstream, what is the nature of the material composing the left bank? hard pan
15. State the character of the bed and the banks in respect to the hardness, perviousness, water bearing effect of exposure to air and to water, uniformity, etc. Hard, uniform & impervious
16. Are there any porous seams or fissures beneath the foundation of the proposed dam? No
17. WASTES. The spillway of the above proposed dam will be 47.5' feet long in the clear; the waters will be held at the right end by a Concrete Retaining Wall the top of which will be 37.5' feet above the spillcrest, and have a top width of 2 feet; and at the left end by a Concrete Retaining Wall the top of which will be 37.5' feet above the spillcrest, and have a top width of 2 feet.
18. The spillway is designed to safely discharge 1000 cubic feet per second.
19. Pipes, sluice gates, etc., for flood discharge will be provided through the dam as follows:
20" dia steel pipe
20. What is the maximum height of flash boards which will be used on this dam? 2.0'
21. APRON. Below the proposed dam there will be an apron built of Concrete 97.5' feet long across the stream, 2.9 feet wide and 1 feet thick.
22. Does this dam constitute any part of a public water supply? Yes. In NYC watershed

ATE
LMED
- 8