

AD-A105 773

NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/G 13/13
NATIONAL DAM SAFETY PROGRAM. COBLESKILL UPPER RESERVOIR DAM NUM--ETC(U)
JUL 81 G KOCH

DACW51-79-C-0001

NL

UNCLASSIFIED

14
B-1

END
DATE
FILMED
11 R
DTIC

REPORT DOCUMENTATION PAGE

READ INSTRUCTIONS
BEFORE COMPLETING FORM

1. REPORT NUMBER

2. GOVT ACCESSION NO.

3. RECIPIENT'S CATALOG NUMBER

AD-A405 773

4. TITLE (and Subtitle)

Phase I Inspection Report
Cobleskill Reservoir Dam No. 1
Mohawk River Basin, Schoharie County, N.Y.
Inventory No. 656

5. TYPE OF REPORT & PERIOD COVERED
Phase I Inspection Report
National Dam Safety Program

6. PERFORMING ORG. REPORT NUMBER

7. AUTHOR(s)

GEORGE KOCH

8. CONTRACT OR GRANT NUMBER(s)

DACW51-79-C-0001

9. PERFORMING ORGANIZATION NAME AND ADDRESS

New York State Department of Environmental
Conservation 50 Wolf Road
Albany, New York 12233

10. PROGRAM ELEMENT, PROJECT, TASK
AREA & WORK UNIT NUMBERS

12 226

11. CONTROLLING OFFICE NAME AND ADDRESS

Department of the Army
26 Federal Plaza New York District, CoE
New York, New York 10287

12. REPORT DATE

29 July 1981

13. NUMBER OF PAGES

14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)

Department of the Army
26 Federal Plaza New York District, CoE
New York, NY 10287

15. SECURITY CLASS. (of this report)

UNCLASSIFIED

15a. DECLASSIFICATION/DOWNGRADING
SCHEDULE

16. DISTRIBUTION STATEMENT (of this Report)

Approved for public release; Distribution unlimited.

17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)

National Dam Safety Program. Cobleskill Upper
Reservoir Dam Number 1 (Inventory Number 656),
Mohawk River Basin, Schoharie County, New York.
Phase I Inspection Report.

18. SUPPLEMENTARY NOTES

19. KEY WORDS (Continue on reverse side if necessary and identify by block number)

Dam Safety
National Dam Safety Program
Visual Inspection
Hydrology, Structural Stability

Cobleskill Reservoir Dam No. 1
Schoharie County
Mohawk River Basin

20. ABSTRACT (Continue on reverse side if necessary and identify by block number)

This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization.

The examination of documents and visual inspection of the Cobleskill Upper Reservoir Dam and appurtenant structures did not reveal conditions which constitute a hazard to human life or property.

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

AD A105773

LEVEL

DTIC
SELECTED
OCT 19 1981

N.Y.

H

JMC FILE COPY

393970

The discharge capacity of the spillway is inadequate for all storms in excess of 57% of the Probable Maximum Flood. During the 1/2 PMF event, the maximum water surface elevation will be 0.33 feet below the top of dam. The dam will be overtopped by 0.28 feet during the full PMF; therefore, the spillway is assessed as "Inadequate".

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession For
 REG C-11
 REG T 3
 Unprocessed
 Application

By: _____
 Distribution/
 Availability Codes
 Available
 Dist 1/19/62

A

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
COBLESKILL UPPER RESERVOIR DAM
I.D. No. NY 656 DEC No. 174A-3138B
MOHAWK RIVER BASIN
SCHOHARIE COUNTY, NEW YORK

TABLE OF CONTENTS

	<u>PAGE NO.</u>
- ASSESSMENT	-
- OVERVIEW PHOTOGRAPH	-
1 PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	2
2 ENGINEERING DATA	4
2.1 GEOLOGY	4
2.2 SUBSURFACE INVESTIGATION	4
2.3 DAM AND APPURTENANT STRUCTURES	4
2.4 CONSTRUCTION RECORDS	4
2.5 OPERATION RECORDS	4
2.6 EVALUATION	4
3 VISUAL INSPECTION	5
3.1 FINDINGS	5
3.2 EVALUATION OF OBSERVATIONS	6
4 OPERATION AND MAINTENANCE PROCEDURES	7
4.1 PROCEDURES	7
4.2 MAINTENANCE OF THE DAM	7
4.3 WARNING SYSTEM	7
4.4 EVALUATION	7

	<u>PAGE NO.</u>
5 HYDRAULIC/HYDROLOGIC	8
5.1 DRAINAGE AREA CHARACTERISTICS	8
5.2 ANALYSIS CRITERIA	8
5.3 SPILLWAY CAPACITY	8
5.4 RESERVOIR CAPACITY	8
5.5 FLOODS OF RECORD	8
5.6 OVERTOPPING POTENTIAL	8
5.7 EVALUATION	8
6 STRUCTURAL STABILITY	9
6.1 EVALUATION OS STRUCTURAL STABILITY	9
7 ASSESSMENT/RECOMMENDATIONS	10
7.1 ASSESSMENT	10
7.2 RECOMMENDATIONS	10

APPENDIX

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS
- D. REFERENCES
- E. DRAWINGS

**PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**

Name of Dam: Cobleskill Upper Reservoir Dam
State Located: New York
County: Schoharie
Watershed: Mohawk River Basin
Stream: Smith Brook
(tributary of Cobleskill Creek
and Mohawk River)
Date of Inspection: October 30, 1980

ASSESSMENT

The examination of documents and visual inspection of the Cobleskill Upper Reservoir Dam and appurtenant structures did not reveal conditions which constitute a hazard to human life or property.

The discharge capacity of the spillway is inadequate for all storms in excess of 57% of the Probable Maximum Flood. During the 1/2 PMF event, the maximum water surface elevation will be 0.33 feet below the top of dam. The dam will be overtopped by 0.28 feet during the full PMF; therefore, the spillway is assessed as "Inadequate".

The following problems were observed which require remedial action within one year of notification to the owner:

1. Joints in the spillway must be cleaned and recaulked.
2. The voids under the riprap spillway channel must be investigated and backfilled or grouted.
3. Remove the trees and brush growth from the embankment and around the spillway. Provide a program of periodic cutting and mowing of these surfaces.
4. Provide a program of periodic inspection and maintenance of the dam and appurtenances. Document this information for future reference.
5. An emergency action plan must be developed.


See
File

George M.
Chief, San Francisco Section
New York State Department
of Environmental Conservation
NY License No. 45307

W. L. Smith

W. L. Smith
New York District Engineer

JUL 28 1981



VICINITY MAP




Photo # 1
Overview of Cobleskill Upper Reservoir Dam

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
COBLESKILL UPPER RESERVOIR DAM
I.D. No. NY 656 DEC No. 174A - 3138B
MOHAWK RIVER BASIN
SCHOHARIE COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the Nation Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

Evaluation of the existing conditions of the subject dam to identify deficiencies and hazardous conditions, determine if they constitute hazards to human life and property and recommend remedial measures where necessary.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances

The Cobleskill Uper Reservoir Dam consists of a 2200 feet long homogenous earth embankment, with a compacted core trench to an impervious layer. One leg of the embankment follows the shore line of the Cobleskill Lower Reservoir with 90° bend around a water supply intake the other leg stretches across Smith Brook. The upstream slope of the embankment is protected with stone. The spillway is a concrete overflow section discharging onto a sloped concrete apron and riprapped channel. There is a 12" drain located through the highest portion of the embankment across Smith Brook. It is a cast iron pipe with a concrete gate tower at the dam crest just west of the spillway. The embankment is approximately 30 feet high at its highest point across Smith Brook.

b. Location

→ The dam is located on Smith Brook, a tributary of Cobleskill Creek and Mohawk River approximately 2.0 miles southeast of Cobleskill, New York. →

c. Size

The dam is 30 feet high and impounds 239. acre feet at normal pool elevation. Therefore, it is classified as "small" in size (less than 40 feet in height.)

d. Hazard Classification

The dam is classified as high hazard due to its location above several homes in Mineral Springs, NY. The reservoir is also a major part of the Cobleskill, NY water supply system.

e. Ownership

The dam is owned and operated by the Village of Cobleskill, New York, 12093. Mr. John Barber, Water Supervisor, Village of Cobleskill, Cobleskill, New York, was the contact with the Village, he can be reached at (518) 234-2195.

f. Purpose of the Dam

The dam provides storage for the Cobleskill water supply. *to be*

g. Design and Construction History

The dam was constructed in 1967 according to the design of and under the direction of James S. Van Deusen, P.E. Cobleskill, New York. The original application for permit was filed in 1963 but funding held up start of construction 4 years.

h. Normal Operating Procedures

Water releases from the Cobleskill Upper Reservoir are normally through the intake and into the water supply either directly or through the lower reservoir. Any excess flow goes through the uncontrolled spillway.

1.3 PERTINENT DATA

a. Drainage Area (sq. mi.) 1.26

b. Height of Dam (ft.) 30.0

c. Discharge @ Dam Site (cfs.)
Spillway at Top of Dam. 1195.
Reservoir Drain (Normal) 20.
12" Cast Iron Overflow to Lower Reservoir (Normal) 12.

d. Elevations (ft. I.S. G.S.)
Top of Dam 1184.5
Spillway Crest 1180.6
Reservoir Drain 1150.6

e. Reservoir (acres)
Surface area of Top of Dam
Surface Area of Spillway Crest.

f. Storage (Acre feet)
Top of Dam 353.
Spillway Crest 239.

g. Dam

Type: Homogeneous earth embankment with core trench. Upstream slope protected with rockfill.

Length (ft): 2200'
Upstream Slope: 14: 1
Downstream Slope: 1: 3
Crest Width (ft): 15.

h. Spillway

Type: Concrete overflow section. Concrete apron and riprap discharge channel.

Weir length (ft): 41.0

1. Reservoir Drain

Type: 12" cast iron pipe, with gate tower at crest of dam.

Maximum Capacity (cfs). 20.00

SECTION 2: ENGINEERING DATA

2.1 GEOLOGY

The Cobleskill Upper Dam is located in the glaciated portion of the Appalachian Uplands (northern extreme of the Appalachian Plateau) physiographic province of New York State. These uplands were formed by the dissection of the uplifted but flat lying sandstones, siltstones and shales of the Lower and Middle Devonian Period (395 to 365 million years ago). The plateau surface is represented by flat-topped divides with drainage generally southward. Drainage in the vicinity of the dam is northward toward the Mohawk River.

Glacial cover is generally thin, the deposits of which have resulted from glaciations during the Wisconsin glaciation, approximately 11,000 years ago.

The "Preliminary Brittle Structures Map of New York" prepared by Yngvar W. Isochsen and William G. McKendree (dated 1977) indicates the presence of a subsurface fault, showing relative movement as inferred from drill hole data, and a topographic linear feature observed on one or more of the following: topographic map, Landsat (ERTS), Skylab, or U-2 photographic product, within the drainage area of the reservoir.

2.2 SUBSURFACE INVESTIGATION

Two borings were located for the design of the dam. These explorations indicate that the soils encountered are varying mixtures of clay, silt, sand, and gravel with boulders, of glacial till origin. No water table is indicated.

2.3 DAM AND APPURTENANT STRUCTURES

The dam was erected in 1967 under the supervision of James S. Van Deusen, P.E. Cobleskill, NY.

2.4 CONSTRUCTION RECORDS

No construction records are available.

2.5 OPERATION RECORDS

All operation records are maintained at the treatment plant below the Lower Dam.

2.6 EVALUATION

The data presented in this report has been compiled from information obtained from Mr. John Barber, Water Supervisor, Village of Cobleskill, NY, and the New York State DEC files. This information appears adequate and reliable for Phase I Inspection purposes.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

a. General

Visual inspection of the Cobleskill Upper Reservoir Dam and watershed was conducted on October 30, 1980. The weather was cloudy and the temperatures ranged in the thirties. The reservoir level at the time of inspection was approximately 5. feet below the spillway crest.

b. Embankment

The embankment shows no signs of distress and appears to be in good condition. All slopes seem to be stable with no erosion or depressions. However, the embankment is in need of maintenance, there is tree and brush growth on both slopes. The upstream riprap is generally in good shape but the trees and brush will begin to displace it, if left unattended to. The crest is in good condition. No evidence of seepage was found on the embankment or beyond the downstream toe. Low reservoir elevation at the time of inspection may have reduced the possibility of finding seepage, however, there were no other factors pointing to seepage problems. The discharge channel of the reservoir drain is in need of small tree and brush removal.

c. Spillway

The concrete spillway is in good condition but also in need of some minor maintenance. All joints in walls and floor slabs must be cleaned out and recaulked.

d. Downstream Channel

The riprapped channel is in need of further investigation, several voids were found under the grouted stone in the lower end of the channel. See photo # 6. There is also some brush and tree growth along the channel which must be cleared.

e. Reservoirs

No sediment or problems were reported within the reservoir area.

f. Appurtenant Structures

Both the reservoir drain and the lines to the water system are all reported to be operational. The concrete intake wells appeared to be in very good condition.

3.2 EVALUATION OF OBSERVATIONS

→ The problem areas observed during the inspection and the recommended remedial measures are as follows:

1. Joints in the concrete spillway are full of debris and vegetation is growing in them. They must be cleaned out and recaulked,
2. There are voids under the rip rapped spillway channel. This problem must be investigated further to determine the extent of undermining and backfilled or regouted,
3. Both the embankment and channel have tree and brush growth which must be removed. Provide a program of periodic cutting and mowing of the embankment and areas adjacent to the spillway,
4. Provide a program of periodic inspection and maintenance of the dam and appurtenances including yearly operation and lubrication of all gates and valves. Document this information for future reference, AOB
5. Develop an emergency action plan for notification of downstream residents and the proper governmental authorities. ←

SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

4.1 PROCEDURES

The normal water surface elevation is approximated by the crest of the spillway. Discharges can be to the treatment plant, lower reservoir, low level drain or over the spillway.

4.2 MAINTENANCE OF THE DAM

Maintenance of the dam is provided by the owner, the Village of Cobleskill, NY. Maintenance is not considered satisfactory as evidenced by the tree and brush growth on the embankment and deterioration of the spillway joints.

4.3 WARNING SYSTEM

There is no warning system in effect or in preparation.

4.4 EVALUATION

The dam and appurtenances are in need of maintenance. The areas sited are noted in "Section 3: Visual Inspection".

SECTION 5: HYDRAULIC/HYDROGOGIC

5.1 DRAINAGE AREA CHARACTERISTICS

The Cobleskill Upper Dam is located on Smith Brook, adjacent to the Lower Reservoir. Smith Brook has a drainage area of 1.26 square miles at the site and is a tributary of Cobleskill Creek and Mohawk River. The watershed is primarily wooded with some pasture in the lower, flatter portions. The cover is glacial till and generally thin.

5.2 ANALYSIS CRITERIA

The analysis of the spillway capacity of the dam and storage of the reservoir was performed using the Corps of Engineers HEC-1 computer model. The unit hydrograph was defined by the Snyder Synthetic Unit Hydrograph method, and the Modified Puls routing procedure was incorporated. The Probable Maximum Precipitation (PMP) was 19.5 inches (24 hrs., 200 sq. miles) from Hydrometeorological Report #33 in accordance with the recommended guidelines of the Corps of Engineers. Several floods (%s of the Probable Maximum Flood (PMF) were selected for analysis. The full PMF inflow of 2273 cfs was routed through the reservoir and found to produce an outflow of 2271 cfs.

5.3 SPILLWAY CAPACITY

The spillway is a 42.5 feet wide uncontrolled concrete section with a 1.5 feet thick pier leaving 41 feet of weir length. The crest elevation is 1180.55 U.S.G.S. with a maximum flow height of 4. feet before overtopping occurs. The maximum flow is 1195 cfs before overtopping.

5.4 RESERVOIR CAPACITY

The reservoir at the crest of the spillway, and at the top of the dam are 239 acre feet and 353 acre feet respectively. Surcharge, storage between spillway and top of dam is equivalent to 1.70 inches of runoff from the watershed area.

5.5 FLOODS OF RECORD

There are no gaging stations located on or near the dam site nor are there any accounts of high flows or levels.

5.6 OVERTOPPING POTENTIAL

The maximum capacity of the spillway before overtopping occurs is 1195 cfs, which is 57% of the routed PMF inflow of 2273 cfs. The dam is overtopped by 0.28 feet during the full PMF event.

5.7 EVALUATION

The spillway of the Cobleskill Upper Reservoir will handle 57% of the PMF. Based on the Corps of Engineers screening criteria it is considered inadequate.

SECTION 6: STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations

No signs of major distress were observed in connection with the earth embankment. The gate house and spillway both appeared to be in generally good condition.

b. Design and Construction Data

No information could be located concerning the structural stability of the embankment portion of the dam.

c. Post Construction Changes

No post construction changes have been initiated.

SECTION 7: ASSESSMENT/RECOMMENDATIONS

7.1 ASSESSMENT

a. Safety

The Phase I Inspection of the Cobleskill Upper Reservoir Dam revealed that the spillway is "Inadequate" based upon the Corps of Engineers screening criteria. The dam will be overtopped by all storms in excess of 57% of the PMF. The embankment appears stable with few minor maintenance problems.

b. Adequacy of Information

The information reviewed is considered adequate for Phase I Inspection purposes.

c. Need for Additional Investigation

The only additional investigation required is that of the voids under the spillway channel. Once the degree of undermining is determined the best solution can be applied.

d. Urgency

The areas listed below requiring remedial action should be initiated within 3 months and completed within 1 year of notification to the owner.

7.2 RECOMMENDATIONS

1. Clean out and recaulk the joints in the spillway.
2. The voids under the riprapped spillway channel must be investigated and repaired.
3. Remove the tree and brush growth from the embankment and around the spillway.
4. Provide a program of periodic inspection and maintenance of the dam and appurtenances. Document this information for future reference.
5. An emergency action plan must be developed.

APPENDIX A

PHOTOGRAPHS



Photo # 2.
View from upper end of reservoir.
Note: Spillway on left and water supply intake in corner
of reservoir, also tree growth.



Photo # 3.
Relative location of Cobleskill Upper and Lower Reservoirs.



Photo # 4.
Spillway Crest.




Photo #5
Spillway apron and downstream channel.




Photo # 6.
Opening to larger void under spillway channel.



Photo # 7.
Reservoir drain control. Note: trees and brush.




Photo # 8.
Reservoir drain outlet. Note: trees and brush.

APPENDIX B

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST1) Basic Data

a. General

Name of Dam Cobleskill Upper Reservoir Dam
 Fed. I.D. # NY 656 DEC Dam No. 174A - 313E B
 River Basin MOHAWIC RIVER BASIN
 Location: Town Cobleskill County SCHENECTADY
 Stream Name Smith Brook
 Tributary of Cobleskill Creek
 Latitude (N) 42°40.0' Longitude (W) 74°27.0'
 Type of Dam homogeneous earthfill
 Hazard Category high (C)
 Date(s) of Inspection Oct. 30, 1980
 Weather Conditions cloudy - 30's
 Reservoir Level at Time of Inspection 5 feet below spillcrest

b. Inspection Personnel E. McCarthy J. Vertich

c. Persons Contacted (Including Address & Phone No.)

John Barker
Water Supervisor
Village of Cobleskill
NY 12093 (518) 234-2125

d. History:

Date Constructed 1967 Date(s) Reconstructed

Designer James S. J. in Design

Constructed By

Owner Village of Cobleskill

93-15-3(9/80)

2) Embankment

a. Characteristics

- (1) Embankment Material homogeneous earth
- (2) Cutoff Type excavated earth trench
- (3) Impervious Core none
- (4) Internal Drainage System none
- (5) Miscellaneous —

b. Crest

- (1) Vertical Alignment good
- (2) Horizontal Alignment good
- (3) Surface Cracks none
- (4) Miscellaneous —

c. Upstream Slope

- (1) Slope (Estimate) (V:H) 1:3
- (2) Undesirable Growth or Debris, Animal Burrows trees and brush growth
- (3) Sloughing, Subsidence or Depressions none

(4) Slope Protection postponed - check after on good
condition

(5) Surface Cracks or Movement at Toe none

d. Downstream Slope

(1) Slope (Estimate - V:H) 1:3

(2) Undesirable Growth or Debris, Animal Burrows tree and brush
growth

(3) Sloughing, Subsidence or Depressions none

(4) Surface Cracks or Movement at Toe none

(5) Seepage none

(6) External Drainage System (Ditches, Trenches; Blanket) _____

(7) Condition Around Outlet Structure good - weeds under
spillway channel

(8) Seepage Beyond Toe none

e. Abutments - Embankment Contact

good

93-15-3(9/80)

(1) Erosion at Contact None

(2) Seepage Along Contact None

3) Drainage System

a. Description of System None

b. Condition of System +

c. Discharge from Drainage System -

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.)

None

5) Reservoir

- a. Slopes shallow - no problem
- b. Sedimentation little or no problem
- c. Unusual Conditions Which Affect Dam None

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) several
homes in Mineral Springs
- b. Seepage, Unusual Growth no seepage or associated
growth
- c. Evidence of Movement Beyond Toe of Dam None
- d. Condition of Downstream Channel trash & trees must be cleared

7) Spillway(s) (Including Discharge Conveyance Channel)

- good condition generally - joints need cleaning
& resurfacing
- a. General _____
- b. Condition of Service Spillway good

c. Condition of Auxiliary Spillway noned. Condition of Discharge Conveyance Channel 16105 inchgrated riprap - must be investigated
generally good8) Reservoir Drain/OutletType: Pipe ☒ Conduit _____ Other _____Material: Concrete _____ Metal P.I. Other _____Size: 12" Length _____

Invert Elevations: Entrance _____ Exit _____

Physical Condition (Describe): operable Unobservable _____Material: P.I.

Joints: _____ Alignment _____

Structural Integrity: assumed goodHydraulic Capability: 20 cfsMeans of Control: Gate _____ Valve ☒ Uncontrolled _____Operation: Operable ☒ Inoperable _____ Other _____Present Condition (Describe): good

9) Structural

- a. Concrete Surfaces very good
- b. Structural Cracking minor surface
- c. Movement - Horizontal & Vertical Alignment (Settlement) none
- d. Junctions with Abutments or Embankments good
- e. Drains - Foundation, Joint, Face none
- f. Water Passages, Conduits, Sluices —
- g. Seepage or Leakage none

h. Joints - Construction, etc.

Good condition

i. Foundation

apparently good

j. Abutments

good

k. Control Gates

good

l. Approach & Outlet Channels

good

m. Energy Dissipators (Plunge Pool, etc.)

—

n. Intake Structures

good condition

o. Stability

no problem

p. Miscellaneous

—

10) Appurtenant Structures (Power House, Lock, Gatehouse, Other)

a. Description and Condition gate tower & drain tower
good condition

11) Operation Procedures (Lake Level Regulation):

water supply - checked hourly

APPENDIX C

HYDROLOGIC / HYDRAULIC

ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>1184.55</u>	<u>32</u>	<u>353</u>
2) Design High Water (Max. Design Pool)	<u>—</u>	<u>—</u>	<u>—</u>
3) Auxiliary Spillway Crest	<u>—</u>	<u>—</u>	<u>—</u>
4) Pool Level with Flashboards	<u>—</u>	<u>—</u>	<u>—</u>
5) Service Spillway Crest	<u>1186.55</u>	<u>25</u>	<u>230</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u>1.</u>
2) Spillway @ Maximum High Water	<u>1125</u>
3) Spillway @ Design High Water	<u>—</u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u>—</u>
5) Low Level Outlet	<u>20</u>
6) Total (of all facilities) @ Maximum High Water	<u>1227</u>
7) Maximum Known Flood	<u>—</u>
8) At Time of Inspection	<u>0.</u>

CREST:

ELEVATION: 1134.55Type: Concrete with embankment on both sidesWidth: 15' Length: 2200'Spillover ~Location ~

SPILLWAY:

SERVICE

AUXILIARY

1180.55 Elevation —Concrete Weir overflow section Type —43.5' Width —Type of Control✓ Uncontrolled —

Controlled:

— Type —
(Flashboards; gate)— Number —— Size/Length —Invert Material —Anticipated Length
of operating service —30' Chute Length —1:3 slope Height Between Spillway Crest
& Approach Channel Invert
(Weir Flow) —

HYDROMETEROLOGICAL GAGES:

Type : NoneLocation: -

Records:

Date - -Max. Reading - -

FLOOD WATER CONTROL SYSTEM:

Warning System: None

Method of Controlled Releases (mechanisms):

12" C.I. reservoir drain to stream12" C.I. pipe to lower reservoir

DRAINAGE AREA: 1.26 square miles

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: primarily wooded, 3% agricultural

Terrain - Relief: moderately steep overall, steep terrain

Surface - Soil: thin fill overlying rock

Runoff Potential (existing or planned extensive alterations to existing (surface or subsurface conditions)

no alterations made or to be made to basin

Potential Sedimentation problem areas (natural or man-made; present or future)

none showing at time of inspection

Potential Backwater problem areas for levels at maximum storage capacity including surcharge storage:

secondary road, possibly

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the Reservoir perimeter:


Location: none

Elevation: _____

Reservoir:

Length @ Maximum Pool 1200 ft. (Miles)

Length of Shoreline @ Spillway Crest 2500 ft. (Miles)



Cobleskill (New Reservoir) No data obtained TRIB or Cobleskill Creek.

Planimetered Area: 8.80 sq. in. $\left(\frac{24000^2}{144(43560)} \right) = 808.1 \text{ ACRES}$
 { Smith Brook new }
 { Dow Brook old }

Reservoir Capacity / Spillway Capacity

41' long 4.0' d C=3.5

crest at 1180.55

Top of Dam 1184.55

Q_{DAM} = 966 + 1200 = 2166. C=3.0

STORAGE

CAPACITY

EL. as per plan	DSGS EL	AREA	AREA	Δ Vol. (K-Ft.)	Σ Vol.
1126	1156.55	0	0	0	0
1130	1160.55	22.	.11	.44	.44
1136	1166.55	4.2	2.21	13.3	13.7
1140	1170.55	6.6	5.40	21.6	35.3
1146	1176.55				122.
1150	1180.55	25.	14.4	149.0	267.

SPILLWAY CAP.

C = 41' 2% pier return.

EL.	H.	C	Q
1180.55	0.0	—	—
1181.00	0.45	3.2	39
1181.55	1.00	3.4	136
1182.00	1.45	3.5	244
1182.55	2.00	3.6	407
1183.55	3.00	3.8	790
1184.55	4.00	3.8	1216
1185.55	5.00	3.8	1700
1187.55	7.00	3.8	

PRECIP. $\Sigma PMP = 19.5''$

<u>6</u>	<u>12</u>	<u>24</u>	<u>48</u>
<u>X</u> 111	123	133	142

TOP OF DAM $C = 3. \quad L = 2166.'$

SCS UNIT HYDROGRAPH

$$A = 1.26 \text{ mi.}^2 \quad L = 8000' \quad \Delta H = 1840 - 1160 = 680'$$

$$T_c = \left(\frac{11.8 L^3}{H} \right)^{.385} = \left(\frac{11.8 (1.26)^3}{680} \right)^{.385} = .34 \text{ hr} = 20 \text{ MIN.}$$

$$\boxed{D = .25 \text{ hr}}$$

$$Q = 1.0''$$

$$T_p = \frac{D}{2} + 0.6 T_c = .125 + .6 (.34) = 0.33 \text{ hr} = 20 \text{ MIN.}$$

$$q_p = \frac{484 A Q}{T_p} = \frac{484 (1.26) 1.0}{.33} = 1898. \text{ cfs}$$

$$\boxed{D = .50 \text{ hr}}$$

$$T_p = .704 \text{ hr} = 42. \text{ MIN}$$

$$q_p = 871 \text{ cfs.}$$

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS
1
1
RUNOFF HYDROGRAPH AT
ROUTE HYDROGRAPH TO
END OF NETWORK

PL 3 HYDROGRAPH PACKAGE (HFC-1)
 LAST MODIFIED JULY 1975
 LAST MODIFICATION 26 FEB 76
 DESIGNED FOR NEWELL 204 79

PL DATE 02/04/81

COBLESKILL NEW RESERVOIR DAM
 SMITH BROOK
 3FEB1981

NEW YORK STATE
 DEPT OF ENVIRONMENTAL CONSERVATION
 FLOOD PROTECTION BUREAU

JCB SPECIFICATION
 AC NHR NPM IDAY JHR IMIN METRC JPLT JPRY NSTAN
 200 C 15 C 0 C 0 C 0
 JDEPR NWT LRPT TRACE C
 5 C 0 C

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 1 PARTID= 6 LRTOID= 1
 RTICS= 0.20 0.40 0.50 0.60 0.80 1.00

SUR-AREA RUNOFF COMPUTATION

INFLOW FROM SUB-BASIN
 ISTAQ ICOMP IECCN ITAPE JPLT JPRY INAME ISTAGE IAUTO
 1 0 0 C 2 C 1 0 0

HYDROGRAPH DATA
 IHDG IUNG TAREA SNAP TRSDA TRSPC RATIC ISNCH ISAME LOCAL
 1 1 1.26 0. 1.26 C. 0. C. C. C. C.

TRSPC COMPUTED BY THE PROGRAM IS 0.60
 PRECIP DATA
 SPFE PMS R6 R12 R24 R48 R96
 C. 19.50 111.00 123.00 133.00 142.00 C. C.

LOSS DATA
 LCRPT STRKR DLTVR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP
 0 C. 1.00 C. 0. 1.00 1.00 0.1C 0. C.

UNIT HYDROGRAPH DATA
 TP= 2.87 CP=0.63 NTA= C

RECESSION DATA
 STRTQ= -2.00 QPCSN= 2.00 RTICR= 1.00
 APPROXIMATE CLAPK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC=12.79 AND R=10.46 INTERVALS

UNIT HYDROGRAPH 63 END-OF-PERIOD ORDINATES, LAG= 2.85 HOURS, CP= C.63 VOL= 1.00	
5.	175.
10.	163.
15.	150.
20.	136.
25.	124.
30.	112.
35.	102.
40.	93.
45.	84.
50.	77.
55.	70.
60.	63.
65.	56.
70.	49.
75.	43.
80.	36.
85.	30.
90.	24.
95.	18.
100.	14.
105.	10.
110.	7.
115.	5.
120.	3.
125.	2.
130.	2.
135.	2.
140.	2.
145.	2.
150.	2.
155.	2.
160.	2.
165.	2.
170.	2.
175.	2.

END OF SUR-AREA RUNOFF COMPUTATION

[illegible]

[illegible]

0.15153.
0.39165.
0.67175.
1.05186.
1.15197.
1.25208.
1.55199.
2.00210.

• • • • •

•
•
•
•
•

•

•

•

•

•

•

•

•

•

•

•

.....

•

A 10x10 grid of dots forming a square shape. The dots are arranged in 10 rows and 10 columns, with the outermost dots forming the perimeter of the square.

.....

•

•

•

•

•

.....

•
•
•
•
•

.....

•

•

•

•

•

.....

.....

•

•

•

•

•

• • • • •

.....

...

[illegible]

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFS	397.	315.	110.	53.	1052.	1052.
CHS	11.	9.	3.	1.	30.	30.
INC-ES		2.32	3.24	3.26	3.26	3.26
MM		59.00	62.41	82.68	82.68	82.68
AC-FT		156.	218.	219.	219.	219.
TR-BLS CUM		192.	269.	270.	270.	270.

STAGE-ELEVATION DATA WILL BE EXTRAPOLATED ABOVE ELEVATION 1181.55

STATION 1, PLAN 1, RATIC 2
END-OF-PERIOD HYDROGRAPH CIRCINATES

0573104

[illegible]

SUMMARY OF CAN SAFETY ANALYSIS

PLAN 1	ELEVATION STORAGE	INITIAL VALUE	SPILLWAY CREST	TCP OF DAM
		1180.55	1180.60	1184.50
		218	325	

[illegible][illegible]

PEAK CUTOFF: IS 836. AT TIME 43.25 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFS	836.	651.	225.	169.	21760.	21760.
CHS	24.	18.	6.	3.	616.	616.
1-CFS		4.81	6.65	6.69	6.69	6.69
MW		122.13	168.98	170.02	170.02	170.02
2C-FT		323.	447.	456.	456.	450.
T-OLS		358.	551.	555.	555.	555.

***** TOP OF DAM, BOTTOM OF BREACH, OR LOW-LEVEL OUTLET IS NOT WITHIN RANGE OF GIVEN ELEVATIONS IN STORAGE-ELEVATION DATA
 BOTTOM OF RESERVOIR ASSUMED TO BE AT 1156.50
 STORAGE-ELEVATION DATA WILL BE EXTRAPOLATED ABOVE ELEVATION 1181.55

STATION: 1, PLAN 1, RAYIC 3

[illegible]

PEAK INTENSITY IS 1815. AT TIME 42.50 HOURS

WARNING *** TOP OF DAM, BOTTOM OF BREACH, OR LOW-LEVEL OUTLET IS NOT WITHIN RANGE OF GIVEN ELEVATIONS IN STORAGE-ELEVATION DATA
 BOTTOM OF RESERVOIR ASSUMED TO BE AT 1156.50
 STORAGE-ELEVATION DATA WILL BE EXTRAPOLATED ABOVE ELEVATION 1161.52

0000000000
0000000000
0000000000
0000000000
0000000000
OUTLET
0000000000
0000000000
0000000000
0000000000

TRULS C- P

1021.

1416.

1421.

1421.

.....

.....

.....

.....

.....

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FORMULTIPLE PLAN-RATIO ECCENTRIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE FEET (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS					
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6
				0.20	0.40	0.50	C.C.	0.80	1.00
HYDROGRAPH AT	1	1.26	1	435.	909.	1137.	1264.	1419.	2273.
	(5821.00)		(12.87)	(25.75)	(32.19)	(38.62)	(51.50)	(64.37)	(64.37)
ROUTED TO	1	1.26	1	397.	836.	1052.	1242.	1415.	2271.
	(5821.00)		(11.23)	(23.67)	(29.80)	(38.62)	(51.40)	(64.37)	(64.37)

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

RATIC CF P-F	ELEVATION STORAGE OUTFLCH	MAXIMUM RESERVOIR ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLCH CFS	DURATION OVER TCP HOURS	TIME OF DAM		TIME OF FAILURE HOURS
							MAX	TCP	
0.20	1182.51	1182.51	0.	253.	397.	C.	43.50	1184.50	C.
C.40	1163.06	1163.06	0.	328.	636.	C.	43.25	339.	C.
C.50	1184.17	1184.17	0.	343.	1052.	C.	43.25	1193.	C.
C.80	1184.57	1184.57	0.07	355.	1342.	1.25	42.75		C.
C.80	1184.69	1184.69	C.19	358.	1815.	3.25	42.50		C.
1.00	1184.78	1184.78	0.28	361.	2271.	4.50	42.50		C.

APPENDIX D

REFERENCES


APPENDIX D

REFERENCES

- 1) U.S. Department of Commerce, Technical Paper No. 40, Rainfall Frequency Atlas of the United States, May 1961.
- 2) U.S. Department of Commerce, Hydrometeorological Report No. 33, Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1,000 Square Miles and Durations of 6, 12, 24, and 48 Hours; April 1956.
- 3) Soil Conservation Service, National Engineering Handbook, Section 4, Hydrology, August 1972 (U.S. Department of Agriculture).
- 4) H.W. King and E.F. Brater, Handbook of Hydraulics, 5th edition, McGraw-Hill, 1963.
- 5) T.W. Lambe and R.V. Whitman, Soil Mechanics, John Wiley and Sons, 1965.
- 6) W.D. Thornbury, Principles of Geomorphology, John Wiley and Sons, 1969.
- 7) University of the State of New York, Geology of New York, Education Leaflet 20, Reprinted 1973.
- 8) Cornell University Agriculture Experiment Station (compiled by M.G. Cline and R.L. Marshall), General Soil Map of New York State and Soils of New York Landscapes, Information Bulletin 119, 1977.

APPENDIX E

DRAWINGS



TOPOGRAPHIC MAP

1 inch

1 mile

60

ASH STAMP
1055745
SPHE
3-BRILL
CLONE

Soil

STAIN
MAIL

STAIN
MAIL

STAIN

7+2828

7+80



conty

65,000 compacted only

11
50
1/2

stop into
Cut-off train
1' stop in
Ry Ry
Borrow

1140

1140

area 6" = 20,000 ±

trenchy looking = 5,000 ±


rock down =

~~EROSION~~

~~CHANNEL~~

= 65,000 ±

Top of hill



hold free

NOTE: IT WILL BE THE
CONTRACTOR'S OBLIGATION
TO DIVERT ALL WATER
FROM THE SITE OF THE
PROPOSED DAM DURING
CONSTRUCTION BY
THE USE OF THE
EXISTING AND OTHER
DIVERSION CHANNELS.

1150

ROAD



EXCAVATE STORAGE AREA
TO ELEV. 1140±
ESTIMATED VOLUME
27,000,000 GAL.

23,000

1140

TRANS. 1140


1140


1140

1140

1140

1140






NORMAL WATER ELEV.
NEW RESERVOIR
1150.0

5'-9"



TRASH BRIL
5'-10"

PLAN
5'-10"



PLAN, C. B.
Scale 1/4" = 1'-0"


1/4"
2" x 1 1/2" x 1/4" Clip



PLAN
Scale 1/4" = 1'-0"

ELEVATION, C.P.
Scale 1" = 1'-0"


Trim
Drain



SECTION A-A


PLAN
SC 10-1-10

INTAKE STRUCTURE



2

IRE Sta 0+60 DYKE 60 Rt.




3

PLAN

Scale $\frac{1}{4}'' = 1'-0''$

TOWER FOR DRAIN Sta. 7+65 DAM



ELEVATION SECTION

Scale $\frac{1}{4}'' = 1'-0''$

SECTION A-A

Scale 1" = 10'



KEYWAY DETAIL

Scale 1" = 10'

Notes:

1. Location of Intake Structure may have to be moved to the right due to foundation conditions.
2. Cat Walk, Wall Covers, and Trash Gullies for Intake will be paid for by AUSA.

By Arma ... 12-18-68

Approx. Ext. Ground

Item 7

9.0

ars 1' 6" dia

8

WATER SUPPLY SYSTEM
VILLAGE & COLEMAN
INTAKE and TRASH
Scale 1" = 10'
Drawn by ...
Check by ...




HEAD WA
S. 2. 0.


2
1.2



LL DETAIL
1'-0"




RUBBER WATER STOP
1'-0"



2
1.2
5' Pans 1'-0"

SECTION



TOP

METAL WATER ST
Scale 3'-1'-0"

8'-1'-4"

1/8" Bars 1'-0" ctrs.


3/8" Bars 1'-0" ctrs.

1'-5'-0"



TER STOP
1'-1'-0"

1'-6" of Rio Ref



1

SECTION C/C
1-0

2

5 Bars 1'-6" c'trs.

SECTION
Scale $\frac{1}{4}" = 1'$

3'-0" 1'-0"

5 Bars 1'-6" c'trs.

F

5 Bars 1'-6" c'trs.

5 Bars 1'-6" c'trs.

5 Bars 1'-6" c'trs.

SECTION
Scale $\frac{1}{4}" = 1'$

3
#4 Bars 1'-0" ctrs.


ON F-E
1'-0"

0'-6" of Bars Fill


TYP

1'-6" ctrs

0'




#4 Bars 1'-6"




ON D-D
1'-0"

7



TYPICAL SECTION OF DOWNSTREAM CHANNEL



WATER SUPPLY SYSTEM
VILLAGE OF COBLE SKILL
DETAIL OF SPILLWAY

SECTION 1

8

END

DATE
FILMED

11-8

DTIC