

AD-A146 330


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
COOK POND DAM (MA 001..(U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV AUG 78


1/2

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS 1963-A

AD-A146 330

BLACKSTONE RIVER BASIN
WORCESTER, MASSACHUSETTS

COOK POND DAM
MA 00123

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

DTIC FILE COPY



DTIC
ELECTE
OCT 03 1984
S E D

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

This document has been approved
for public release and its
distribution is unlimited.

AUGUST, 1978

This document has been approved
for public release and its
distribution is unlimited.

84 - 09 28 061

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER MA 00123	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Cook Pond Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE August 1978
		13. NUMBER OF PAGES 75
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Blackstone River Basin Worcester, Mass.		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Cook Pond Dam is an earthfill dam. The dam has a maximum height of 15 feet and is approximately 510 feet long. The dam is considered to be in fair to poor condition. It has been classified in the "high" hazard category. The test flood for the dam is one-half the PMF.		



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAFALGO ROAD
WALTHAM, MASSACHUSETTS 02154

AUG 31 1979

ATTENTION OF:
NEDED-E

Honorable Edward J. King
Governor of the Commonwealth of
Massachusetts
State House
Boston, Massachusetts

Dear Governor King:

Inclosed is a copy of the Cook Pond Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. The report is based upon a visual inspection, a review of past performance, and a preliminary hydrological analysis. A brief assessment is included at the beginning of the report.

The preliminary hydrologic analysis has indicated that the spillway capacity for the Cook Pond Dam would likely be exceeded by floods greater than 13 percent of the Probable Maximum Flood (PMF), the test flood for spillway adequacy. Our screening criteria specifies that a dam of this class which does not have sufficient spillway capacity to discharge fifty (50) percent of the PMF, should be adjudged as having a seriously inadequate spillway and the dam assessed as unsafe, non-emergency, until more detailed studies prove otherwise or corrective measures are completed.

The term "unsafe" applied to a dam because of an inadequate spillway does not indicate the same degree of emergency as that term would if applied because of structural deficiency. It does indicate, however, that a severe storm may cause overtopping and possible failure of the dam, with significant damage and potential loss of life downstream.

It is recommended that within twelve months from the date of this report the owner of the dam engage the services of a professional or consulting engineer to determine by more sophisticated methods and procedures the magnitude of the spillway deficiency. Based on this determination, appropriate remedial mitigating measures should be designed and completed within 24 months of this date of notification. In the interim a detailed emergency operation plan and warning system should be promptly developed. During periods of unusually heavy precipitation, the dam should be closely monitored.

NEDED-E

Honorable Edward J. King

I have approved the report and support the findings and recommendations described in Section 7, with qualifications as noted above. I request that you keep me informed of the actions taken to implement these recommendations since this follow-up is an important part of the non-Federal Dam Inspection Program.

A copy of this report has been forwarded to the Department of Environmental Quality Engineering, the cooperating agency for the Commonwealth of Massachusetts. This report has also been furnished to the owner of the project, Smith Pond, Inc., Mr. James Thurston, President, 14 Stark Road, Worcester, Massachusetts 01602.

Copies of this report will be made available to the public, upon request to this office, under the Freedom of Information Act, thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Environmental Quality Engineering for the cooperation extended in carrying out this program.

Sincerely,



MAX B. SCHEIDER
Colonel, Corps of Engineers
Division Engineer

COOK POND DAM

MA 00123

BLACKSTONE RIVER BASIN
WORCESTER, MASSACHUSETTS

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION
PROGRAM



Accession For	
NTIS GFA&I	☒
DTIC TAB	☐
Unannounced	☐
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A-1	

NATIONAL DAM INSPECTION
PROGRAM

PHASE I INSPECTION REPORT
BRIEF ASSESSMENT

Identification No.: MA00123

Name of Dam: Cook Pond

Town: Worcester

County and State: Worcester County, Massachusetts

Stream: Tributary of Blackstone River

Date of Inspection: July 10, 1978

Cook Pond Dam is an earthfill dam built about 1830. The dam has a maximum height of 15 feet and is approximately 510 feet long. The main spillway is located near the west abutment and is made of dry stone masonry and concrete. The weir is 37.7 feet long and the crest of the weir is 11.6 feet wide. Normal discharge flows over the weir, down a dry-stone cascade, and into the stream bed. There is an emergency spillway excavated in natural ground and located about 100 feet east of the left dam abutment. The emergency spillway is 470 feet long, with a trapezoidal section having a bottom width of 13 feet, and a height of 5 to 8 feet. It joins the stream 100 feet below the main spillway. There is also an outlet conduit beneath the dam embankment, 4 feet east of the spillway. The conduit is a 12-inch-diameter, cast-iron pipe and is about 45 feet long. Flow is controlled by a gate valve operated by a hand wheel and enclosed in a corrugated metal housing just upstream of the spillway. The only plans, specifications, or computations available from the Owner, State, or County offices on the design, construction, or repairs to this dam are an undated sketch of the spillway and a drawing dated 1958 of the reconstruction of the gate valve housing.

Due to its age, Cook Pond Dam was neither designed nor constructed by current approved state-of-art procedures. Based upon the visual inspection at the site, the lack of engineering data available, and limited operational or maintenance evidence, there are areas of concern which must be corrected to assure the continued performance of this dam. Generally, the dam is considered to be in fair to poor condition. Cook Pond Dam has been classified in the "high" hazard category.

There are several visible signs of distress which indicate a potential hazard at the site: seepage at the toe of the dam, buried outlet of the outlet conduit, steep embankment slopes near the spillway, severe erosion of the spillway weir and pier, heavy growth of trees and brush on the dam embankment and downstream areas, erosion and lack of riprap on the upstream face of the dam, stonework missing from the west spillway sidewall and cascade, and wood/trash debris in the downstream stream bed.

Hydraulic analyses indicate that the main spillway can discharge a flow of 693 cubic feet per second (cfs) and the emergency spillway can discharge a flow of 144 cfs at Elevation (El) 609.5 which is the approximate average dam crest. The lowest point on the dam crest is El 608.6 which is a localized erosion area near the spillway. Based on size and hazard classification, in accordance with Corps guidelines, a test flood of one-half Probable Maximum Flood (1/2 PMF) was utilized. An inflow test flood of 6,390 cfs will overtop the main dam by about 2.3 feet. The two spillways are considered inadequate because combined they discharge only 13 percent of the adjusted outflow test flood of 6,230 cfs. In the event of overtopping, complete failure of the dam could occur. Due to the potential for overtopping, it is recommended that a definite plan for surveillance and a warning system be developed for use during periods of unusually heavy rains and/or runoff. This system should be coordinated with the Owner of the dam.

It is recommended that the Owner employ a qualified consultant to evaluate the stability of the dam and seepage at the toe of the dam and to conduct a more detailed hydrologic and hydraulic investigation in order to evaluate the spillway and outlet capacities. It is also recommended that the Owner repair the concrete on the spillway weir and pier,

remove the blockage at the outlet pipe, clear trees and brush from the embankment and downstream areas, repair erosion on the upstream face of the dam and protect the slope with riprap, replace missing stonework from the west spillway wall and cascade, and clear debris from the stream bed below the main spillway. The Owner should also implement a systematic program of inspection and maintenance.

The above recommendations should be implemented within a period of 1 year after receipt of the Phase I Inspection Report. An alternative to these recommendations would be draining the reservoir and breaching or removing the dam.



A handwritten signature in cursive script, reading "Edward M. Greco".

Edward M. Greco, P.E.
Project Manager
Metcalf & Eddy, Inc.

Connecticut Registration
No. 08365

Approved by:

A handwritten signature in cursive script, reading "Stephen L. Bishop".

Stephen L. Bishop, P.E.
Vice President
Metcalf & Eddy, Inc.

Massachusetts Registration
No. 19703



This Phase I Inspection Report on Cook Pond Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.



CHARLES G. TIERSCH, Chairman
Chief, Foundation and Materials Branch
Engineering Division




FRED J. RAVENS, Jr., Member
Chief, Design Branch
Engineering Division



SAUL COOPER, Member
Chief, Water Control Branch
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in Recommended Guidelines for Safety Inspection of Dams, for a Phase I Investigation. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D. C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general conditions and the downstream damage potential.

TABLE OF CONTENTS

	<u>Page</u>
BRIEF ASSESSMENT	
PREFACE	
OVERVIEW PHOTO	iii
LOCATION MAP	iv
REPORT	
SECTION 1 - PROJECT INFORMATION	1
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	2
SECTION 2 - ENGINEERING DATA	10
2.1 General	10
2.2 Construction Records	10
2.3 Operation Records	10
2.4 Evaluation of Data	11
SECTION 3 - VISUAL INSPECTION	12
3.1 Findings	12
3.2 Evaluation	14
SECTION 4 - OPERATION PROCEDURES	15
4.1 Procedures	15
4.2 Maintenance of Dam	15
4.3 Maintenance of Operating Facilities	15
4.4 Description of Any Warning System in Effect	15
4.5 Evaluation	15
SECTION 5 - HYDRAULIC/HYDROLOGIC	17
5.1 Evaluation of Features	17

TABLE OF CONTENTS (Continued)

	<u>Page</u>
SECTION 6 - STRUCTURAL STABILITY	20
6.1 Evaluation of Structural Stability	20
SECTION 7 - ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES	22
7.1 Dam Assessment	22
7.2 Recommendations	23
7.3 Remedial Measures	23
APPENDIXES	
APPENDIX A - PERIODIC INSPECTION CHECKLIST	
APPENDIX B - PLAN OF DAM, AND PREVIOUS INSPECTION REPORTS	
APPENDIX C - PHOTOGRAPHS	
APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS	
APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	

OVERVIEW
COOK POND DAM
WORCESTER, MASSACHUSETTS



DAM CREST AND SPILLWAY

LOCATION AND DIRECTION OF
PHOTOGRAPHS SHOWN ON
FIGURE D-1 OF APPENDIX B

NATIONAL DAM INSPECTION
PROGRAM

PHASE I INSPECTION REPORT

COOK POND

SECTION 1

PROJECT INFORMATION

1.1 General

- a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Metcalf & Eddy, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Massachusetts. Authorization and notice to proceed was issued to Metcalf & Eddy, Inc. under a letter of May 3, 1978, from Ralph T. Garver, Colonel, Corps of Engineers. Contract No. DACW 33-78-C-0306 has been assigned by the Corps of Engineers for this work.
- b. Purpose:
 - (1) Perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.
 - (2) Encourage and assist the States to initiate quickly effective dam safety programs for non-Federal dams.
 - (3) Update, verify and complete the National Inventory of Dams.

1.2 Description of Project

- a. Location. The dam is located in the City of Worcester, Worcester County, Massachusetts, on Tatnuck Brook, a tributary of the Blackstone River. See Location Map, Map of Drainage Area Figure D-2, and Watershed Plan Figure D-1.
- b. Description of Dam and Appurtenances. Cook Pond Dam is an earthfill dam, 510 feet long and 15 feet high (see Plan of Dam and Sections in Appendix B). The dam crest, which is a foot-path, is generally 7 to 12 feet wide except in a fill area west of the main spillway, where the width is 86 feet. The elevation of the crest varies from 608.6 to 609.7. The upstream and downstream slopes vary from 1:1 to 4:1. The slopes are covered with grass, brush, and trees. There is an 8-foot long, dry-stone masonry wall along the downstream edge of the dam crest adjacent to the east wall of the spillway.

The main spillway is located 200 feet east of the west abutment. It is a flat broad-crested weir constructed of dry-stone masonry that has been covered with reinforced concrete. The crest is 37.7 feet long. There is a raised edge 1.1-foot wide along the upstream weir. It has a top elevation of 606. There is a wooden walkway over the crest which is supported by a 3.7-foot thick concrete pier located near the middle of the weir (see photograph in Appendix C). The sidewalls are about 17 feet long and 2.0 (west side) to 2.8 (east side) feet thick. Discharge flows over the weir, down a stone cascade and into a stream bed.

There is an emergency spillway located about 100 feet east of the east abutment. The spillway is an unlined trapezoidal section excavated in natural ground. It is about 470 feet long and curves around to the south and west to intersect the stream bed at about 100 feet

downstream of the spillway cascade. The invert elevation varies from 606.2 near the upstream end to 592.2 at the downstream end. The average bottom width is 13 feet, with side slopes of 1.3:1 to 1.4:1.

There is an outlet conduit located just east of the main spillway. The gate valve to the conduit was not operated during the inspection, and the conduit was not visible. A 1958 drawing (see Figure B-2 in Appendix B) indicates that it is a 12-inch diameter cast-iron pipe located 4 feet east of the main spillway. The invert of the conduit is estimated from the drawing to be 595.3 feet. The drawing shows a gate valve which is operated by a hand wheel and controls the flow into the conduit. The valve and wheel mechanism are enclosed in a circular, corrugated metal housing which is 4 feet in diameter. A metal cover is welded to the top of the housing and is secured by padlocks. The housing is located 8.5 feet upstream of the east wall of the spillway. A 6-inch wide metal plank provides access out to the housing from the spillway wall.

The downstream end of the conduit which is at the toe of the dam was not visible.

- c. Size Classification. Cook Pond Dam is classified in the "small" category, since it has a maximum height of 15 feet and a maximum storage capacity of 150 acre-feet.
- d. Hazard Classification. Highly developed residential areas of Worcester are located 0.2 miles downstream of the dam. Two well-traveled roadways also cross the stream at 0.3 and 0.4 miles below the dam. In the event of dam failure, numerous lives could be lost, and appreciable property damage could occur. Accordingly, the dam has been placed in the "high" hazard category.

- e. Ownership. The dam is presently owned by Smith Pond, Inc., which is an association of local property owners. The association president, Mr. James Thurston (617-752-4505) granted permission to enter the dam and to inspect the property.
- f. Operator. The Owner is the only operator of the dam, and has possession of keys to open the gate valve housing.
- g. Purpose of Dam. The dam was originally built as a storage pond for a grist mill. There is no available information as to the length of time it was used for that purpose. The dam was purchased by Smith Pond, Inc. in the early 1930's. Since that time it has been used for recreational purposes.
- h. Design and Construction History. Mr. Wallace Lindquist, retired engineer of the Worcester County Engineer's office, stated that Cook Pond dam was built around 1830 and was used as a storage reservoir for a grist mill. The Owner, however, believes the dam was built about 1900 and used as a water supply for Smith Woolen Mill which used to be located near Tatnuck Square. The dam was purchased from Frank Smith in the early 1930's by Smith Pond, Inc., an association of local property owners.

It was reported by the Owner and reports from the Worcester County Engineer's office that during the flood of 1938, overtopping of the dam occurred causing damage to the embankment. Subsequently, repairs were made to the embankment and the section west of the main spillway was partially removed, refilled, and widened. Also, the emergency spillway was constructed at that time. In 1958, the wooden gatehouse located upstream of the spillway was burned down, and the present corrugated metal housing was built at the same location. About three years ago, the Owner cleared the brush from the emergency spillway.

The only plans, specifications, or computations available from the Owner, State, or County offices on the design and construction of this dam are: an undated sketch of the spillway plan and sections showing no measurements or elevations, and a drawing dated 1958 showing the proposed reconstruction of the gate valve housing (copies included in Appendix B). A note on the list of past inspections at the Worcester County Engineer's office (see page B-5 in Appendix B) reports the 1938 flood elevation was 610.2.

1. Normal Operational Procedure. There are no normal operating procedures at this dam. The only apparent outlet control is a 12-inch diameter cast-iron pipe located just east of the main spillway. Flow is controlled by a gate valve located in a corrugated metal housing just upstream of the dam. The Owner stated that the gate is operated periodically, although the last time was about four years ago.

The main spillway and emergency spillway are ungated and flows are unrestricted.

1.3 Pertinent Data

- a. Drainage Area. The approximately 4,531-acre (7.1 square mile) drainage area above the dam consists of sparsely developed, heavily wooded, and gently rolling land. The drainage area includes the watersheds for two Worcester County water supply reservoirs, Holden No. 1 and Holden No. 2. Discharge (see Figure D-2 in Appendix D) is to Tatnuck Brook which flows past Tatnuck Square about 2,200 feet downstream and into Patch Reservoir about 5,000 feet downstream. Cook Pond is one of a series of six dams located on Tatnuck Brook which eventually joins other tributaries of the Blackstone River at Webster Square in Worcester. (See Figure D-1 in Appendix D.)

- b. Discharge at the Dam Site. Normal discharge at the dam site is through the main spillway which is 37.7 feet long. It has a maximum crest elevation of 606.0, although flow is currently passing over eroded areas of the weir at El 605.5. The discharge flows down a stonework cascade into a stream bed about 35-feet wide. The elevation of the stream bed below the dam is about 594 and slopes very gently downstream. The bed is naturally lined with boulders and cobbles.

For pond elevations above El 606.2, discharge also flows through the emergency spillway located about 100 feet east of the left abutment. The spillway is a trapezoidal section with a bottom width of 13 feet, a height of 5 to 8 feet, and side slopes of about 1:1. The invert elevation ranges from 606.2 near the upstream end to 592.2 at the downstream end. The emergency spillway channel is 470 feet long and joins the stream below the dam about 100 feet from the spillway cascade. Water flows regularly through the emergency spillway, especially during periods of high runoff and when the reservoirs upstream are discharging surplus water.

Hydraulic analyses indicate that the main spillway can discharge an estimated 693 cfs and the emergency spillway an estimated 144 cfs at El 609.5 which is the approximate average dam crest. The lowest point on the dam crest is El 608.6 which is a localized erosion area near the spillway. An inflow test flood of 6,390 cfs (half of the probable maximum flood) will overtop the main dam by about 2.3 feet. There are no records of overtopping at the dam since the emergency spillway was constructed. The list of past inspections from the Worcester County Engineer's office notes that the flood elevation in 1938 was 610.2 (approximately 940 cfs), which is 0.7 to 1.6 feet above the dam crest.

Controlled discharge from the dam is through a 12-inch diameter outlet conduit located 4 feet east of the main spillway. The upstream invert is estimated to be 595.3 feet. The flow is controlled by a gate valve operated by a hand wheel. The conduit is about 45 feet long and outlets at the toe of the dam.

c. Elevation (feet above Mean Sea Level (MSL)). A benchmark elevation of 606.0 at the spillway crest was estimated from a U.S.G.S. topographic map.

- (1) Top dam 608.6 to 609.7
- (2) Test flood pool: 611.8
- (3) Design surcharge (original design):
unknown
- (4) Full flood control pool: Not Applicable
(N/A)
- (5) Recreation pool: 606.0
- (6) Main spillway crest (ungated): 606.0
Emergency spillway crest (ungated): 606.2
- (7) Upstream portal invert diversion tunnel:
N/A
- (8) Stream bed at centerline of dam: 594.0
- (9) Maximum tailwater: None

d. Reservoir

- (1) Length of maximum pool: 1,200 feet
- (2) Length of recreation pool: 1,200 feet
- (3) Length of flood control pool: N/A

e. Storage (acre-feet)

- (1) Test flood surcharge: 90 at 611.8
- (2) Top of dam: 150
- (3) Flood control pool: N/A
- (4) Recreation pool: 100 (Approximate)

(5) Spillway crest: 100

f. Reservoir Surface (acres)

*(1) Top dam: 15

*(2) Maximum pool: 15

(3) Flood-control pool: N/A

(4) Recreation pool: 15

(5) Spillway crest: 15

g. Dam

(1) Type: earthfill

(2) Length: 510 feet

(3) Height: 15 feet

(4) Top width: Crest varies from 7 to 15 feet

(5) Side slopes: 1:1 to 4:1

(6) Zoning: Unknown

(7) Impervious core: Unknown

(8) Cutoff: Unknown

(9) Grout curtain: Unknown

1. Spillway

(1) Type: Broad crest

(2) Length of weir: 37.7 feet

*Based on the assumption that the surface area will not significantly increase with changes in reservoir elevation from 606 to 609.5.

- 1
- (3) Crest elevation: 606 MSL (assumed benchmark)
 - (4) Gates: None
 - (5) Upstream Channel: None
 - (6) Downstream Channel: Stone cascade to 35-foot wide stream bed
 - (7) General: Emergency spillway (ungated) - crest El 606.2, bottom width 13 feet, top width 33 feet, height 5 to 8 feet, length 470 feet.

J. Regulating Outlets. The only apparent regulating outlet is a 12-inch diameter, 45-foot long cast-iron conduit. The outlet has a capacity of 8 cfs (1.1 cfs per square mile). It is controlled by a gate valve operated by a hand wheel. The downstream end of the conduit is located at the toe of the dam. According to the Owner, the outlet was last operated four years ago, and is still operable. It was not opened at the time of inspection.

SECTION 2
ENGINEERING DATA

- 2.1 General. The only plans, specifications, or computations available from the Owner, State, or County offices relative to the design, construction, or repairs of this dam are: an undated sketch of the spillway plan and sections showing no measurements or elevations, and a drawing dated 1958 showing the proposed reconstruction of the gate valve housing (copies in Appendix B). The only other data available for this evaluation were visual observations during inspection, review of previous inspection reports, and conversations with the Owner and with personnel from the State and County agencies.

We acknowledge the assistance and cooperation of personnel of the Massachusetts Department of Public Works: Messrs. Willis Regan and Raymond Rochford, and of the Massachusetts Department of Environmental Quality Engineering, Division of Waterways: Messrs. John J. Hannon and Joseph Iagallo.

Also, we acknowledge the cooperation and assistance of personnel from the Worcester County Engineer's Office: Messrs. John O'Toole, Joseph Brazauskas, and Mr. Wallace Lindquist - recently retired from county service.

In addition, we thank Mr. James Thurston, President of Smith Pond, Inc., Owners of the dam, who allowed us to inspect the dam and who provided us with information on the history and operating characteristics of the dam.

- 2.2 Construction Records. There are no detailed construction records available.
- 2.3 Operation Records. No operation records are available, and there is no daily record kept of pool elevation or rainfall at the dam site.
- 2.4 Evaluation.
- a. Availability. Due to its age, there is limited engineering data available.

- b. Adequacy. The lack of indepth engineering data did not allow for a definitive review. Therefore the adequacy of this dam could not be assessed from the standpoint of reviewing design and construction data, but is based primarily on visual inspection, past performance history and sound engineering judgment.
- c. Validity. The limited data available is considered valid.

SECTION 3
VISUAL INSPECTION

3.1 Findings

- a. General. The Phase I Inspection of the dam at Cook Pond was performed on July 10, 1978. A copy of the inspection check list is included in Appendix A. Periodic inspections of this dam by others have been made since 1925. A listing of these inspections is in Appendix B. An inspection was made in 1973 by personnel from the Massachusetts Department of Public Works. A copy of their report is included in Appendix B.
- b. Dam. Cook Pond Dam is an earthfill dam. There is no information on the zoning or core, since it was probably constructed about 150 years ago. Several signs of distress are visible, the most severe being seepage along the downstream toe 30 feet east of the spillway. The seepage forms a pool of water which flows downstream and into the main stream channel just upstream of the emergency spillway. Several other smaller seeps flow into the main stream of seepage. Some of these smaller seeps are bright orange in color.

The upstream and downstream slopes on both sides of the main spillway are steep, sloping at 1:1. Trees along the downstream face of the embankment to the east are tilted downstream which could indicate creep of the slope. In addition, footpaths have been worn adjacent to the sides of the spillway, leaving unprotected earth slopes. The crest on both sides of the spillway is eroded, forming the lowest elevations of the top of the dam. The upstream face of the embankment is not protected with riprap, and local sloughing occurs east and west of the main spillway. Outcrops of granite bedrock were noted in the left abutment area.

There is extensive tree and brush growth on both upstream and downstream slopes of the entire embankment. The footpath along the crest is worn and irregular.

- c. Appurtenant Structures. The main spillway is a 37.7-foot long reinforced concrete weir with dry-stone masonry sidewalls and a downstream stonework cascade. A reinforced concrete pier is located in about the center of the weir to support an overhead footbridge. The concrete forming the weir is in poor condition, especially downstream of the pier where erosion has exposed the reinforcing bars. The lower 1 foot of the concrete pier is also severely eroded, exposing the reinforcing, and the remaining portion of the pier is cracked. Two sections of the upstream edge of the weir are missing and eroded. The eroded areas are 3.7 feet wide along the west wall, and 7.2 feet wide along the east wall, and water is flowing over the spillway at these points. Local cracking and minor spalling occurs at other locations on the weir. Stonework is missing from the downstream edge of the west sidewall and from various steps in the cascade. Wood and trash debris is lying at the foot of the cascade and in the downstream stream bed. Trees overhang the cascade and stream bed areas.

The outlet of the outlet conduit was not visible. At the reported location of the outlet, the area was overgrown with brush and covered with soil and pieces of rock.

The unlined emergency spillway is excavated in till-like overburden. The slopes are steep, about 1:1, but do not appear to be significantly eroded. The channel contains slight to moderate brush growth, except at the downstream end where there are several large trees.

- d. Reservoir Area. The drainage area is generally sparsely populated, but areas of development occur, mainly north of Cook Pond and in the southwest corner of the drainage area. About 300 residences are in the drainage area. The area is generally heavily wooded, and slopes range from about 5 to 25 percent.
 - e. Downstream Channel. The discharge from the spillway flows down a boulder and cobble stream bed with earth banks to Patch Reservoir situated about 5,000 feet downstream. The slope of the stream bed is about 1 percent.
- 3.2 Evaluation. The above findings indicate that the dam has several signs of distress which require attention. It is evident that the dam is not adequately maintained and that deterioration will continue unless action is taken. Recommended measures to improve these conditions are stated in Section 7.

SECTION 4
OPERATING PROCEDURES

- 4.1 Procedures. There are no operating procedures at Cook Pond Dam.
- 4.2 Maintenance of Dam. The dam is not adequately maintained, although the Owner visits the dam several times a year. It was reported that brush was cleared from the emergency spillway about three years ago. Mr. James Thurston of Smith Pond, Inc. stated that the association is planning to fill in eroded areas of the embankment and repair the concrete in the main spillway this summer.

The 1973 inspection report by the Massachusetts Department of Public Works (copy in Appendix B) stated that repairs were needed to the concrete and stonework in the main spillway and that trees and brush should be cleared from the dam embankment. There was no evidence during the inspection that these repairs had been made. Numerous past inspection reports by the Worcester County Engineer's Office stated that the steep embankment slopes should be flattened. However, portions of the embankment are presently sloping at 1:1 to 2:1.

- 4.3 Maintenance of Operating Facilities. The Owner stated that the outlet gate is operated periodically, although the last time was four years ago. Also the Owner said the gate is operable, although it was not opened at the time of inspection. The outlet end of the conduit is supposed to be located at the toe of the dam. However, that area is heavily overgrown with brush and trees, so the outlet was not visible.
- 4.4 Description of Any Warning Systems in Effect. There are no warning systems in effect at this dam.
- 4.5 Evaluation. There are no adequate operational, maintenance, or warning systems in effect at Cook Pond dam. This is extremely undesirable considering the fact that it is in the "high" hazard

category. A program of operation and maintenance for this dam should be implemented as recommended in Section 7.

SECTION 5

HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

- a. Design Data. The Probable Maximum Flood (PMF) rate was determined to be 1,800 cfs per square mile. This calculation is based on the average drainage area slope of 6.0 percent, the pond-plus-swamp area to drainage area ratio of 6.5 percent, and the U. S. Army Corps of Engineers' guide curves for Maximum Probable Flood Peak Flow Rates (dated December 1977). Applying one-half the PMF to the 7.1 square miles of drainage area results in a calculated peak flood flow of 6,390 cfs as the inflow test flood. By adjusting the inflow test flood for surcharge storage, the maximum discharge rate was established as 6,230 cfs (877 cfs per square mile), with a water surface at El 611.8.

Flow over the dam crest is predicted to be 4,442 cfs. Flow through the main spillway (assuming the footbridge had been washed away) would be 1,388 cfs and flow through the emergency spillway would be 390 cfs. The maximum head on the dam would be 2.3 feet with a discharge of 8.61 cfs per foot of width. Depth at critical flow would be at 1.3-foot with a velocity of 6.2 feet per second.

The inflow from a 100-year frequency storm was estimated to be 2,690 cfs. After adjustment for surcharge storage, the outflow from the 100-year storm was calculated to be 2,566 cfs which would result in a water surface at El 610.6 or about 0.9 feet over the dam crest.

Hydraulic analyses indicate that the existing main spillway and emergency spillway can discharge flows of 693 cfs and 144 cfs at water surface El 609.5 which is the approximate average dam crest. The combined discharge of 837 cfs is equivalent to 13 percent of the test flood outflow.

- b. Experience Data. Hydraulic records are not generally available for this dam. However, past inspection reports indicate that the dam was overtopped in 1938. The maximum pond level during the flood was El 610.2. It was reported that the emergency spillway was constructed in 1939 after the 1938 floods. Since that time there are no records of dam overtopping, although the emergency spillway has been frequently used.
- c. Visual Observations. Discharge from Cook Pond is through the main spillway and the emergency spillway located east of the left abutment (see Figure B-1). Since the emergency spillway is only 0.2 feet above the crest of the main spillway, the emergency spillway would be expected to discharge flow on a regular basis and not just during severe storm flows. This has been corroborated by verbal information supplied by the Owner.

The visual inspection on July 10, 1978 showed that brush and trees had been recently cleared from the emergency spillway. This indicates that some maintenance has been done to insure unrestricted flow through the emergency spillway.

The concrete weir at the main spillway shows signs of severe erosion. The erosion downstream of the footbridge pier was probably caused by cavitation during supercritical flow due to the poor hydraulic design of the pier.

- d. Overtopping Potential. Overtopping of the dam is expected under the test flood of 6,390 cfs (inflow) as well as the 100-year frequency flood; as noted previously, however, the only available records on overtopping indicate that the dam has not been overtopped since 1938, when the outflow was approximately 940 cfs. The emergency spillway was constructed in 1939. In the event of overtopping, complete failure of the dam could occur. A flood wave resulting from dam failure could cause appreciable property damage and numerous loss of life.

Failure of the dam would produce a peak discharge of 4,210 cfs, as estimated using Corps of Engineers criteria, with a flood wave in the order of 9 feet. The volume from Cook Pond would raise the level of Patch Reservoir by 6 feet.

- e. Additional Hydraulic Considerations. As shown in Figures D-1 and D-2 in Appendix D, Cook Pond is located downstream of Holden Reservoirs No. 1 and No. 2. However, the hydrologic and hydraulic calculations for this Phase I Investigation have been based on U. S. Army Corps of Engineers guide curves which do not fully consider the storage-discharge characteristics of upstream reservoirs. Therefore, the conclusions on peak flood flows and dam overtopping should be considered as preliminary only. A more detailed hydraulic and hydrologic investigation should be based on the storage effects of upstream reservoirs.

SECTION 6

STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

- a. Visual Observations. The evaluation of the structural stability of Cook Pond Dam is mainly based on the visual inspection conducted on July 10, 1978. Based on the observations as discussed in Section 3, Visual Inspection, Cook Pond Dam is considered a hazard. Conditions at the dam are unsatisfactory and conventional factors of safety may not exist.

It is recommended that a more detailed investigation be initiated to evaluate the dam stability and seepage at the downstream toe of the dam.

- b. Design and Construction Data. Discussions with the Owner, County, and State personnel indicate that there are no detailed plans, specifications, or computations relative to the design or construction of this dam. Furthermore, information on the type, shear strength, and permeability of the soil and/or rock materials of the dam embankment does not appear to exist.

Cook Pond Dam was probably built about 1830, presumably of local soil or rock materials. There is no data, however, on the type of the impervious core wall.

- c. Operating Records. There is no evidence of instrumentation of any type in Cook Pond Dam, and there is nothing to indicate that any instrumentation was ever installed in this dam. The performance of this dam under prior loading can only be inferred by physical evidence at the site.

- d. Post-Construction Changes. There are no as-built drawings for Cook Pond Dam. The Owner indicates that the embankment was repaired and the section west of the main spillway was partially refilled and widened about 1939. The emergency spillway was also excavated at about the same time. In 1958, the original wooden gate house for the outlet conduit burned down, and the present metal corrugated housing was installed. In 1974, trees and brush were cleared from the emergency spillway channel.
- e. Seismic Stability. The dam is located in Seismic Zone No. 2 and in accordance with Phase I "Recommended Guidelines" does not warrant seismic analyses.

SECTION 7
ASSESSMENT, RECOMMENDATIONS,
AND REMEDIAL MEASURES

7.1 Dam Assessment

- a. Condition. Due to its age, Cook Pond Dam was neither designed nor constructed according to current approved state-of-art procedures. Based upon the visual inspection at the site, the lack of engineering data available, and limited operational or maintenance information, there are areas of concern which must be corrected to assure the continued performance of this dam. Generally, the dam is considered to be in fair to poor condition. There were several signs of distress observed at the site: seepage at the downstream toe of the dam, buried outlet of the outlet conduit, steep embankment slopes near the spillway, severe erosion of the spillway weir and pier, heavy growth of trees and brush on the dam embankment and downstream areas, erosion and lack of riprap on the upstream face of the dam, stonework missing from the west spillway sidewall and cascade, and wood/trash debris in the downstream stream bed.

Hydraulic analyses indicate that the main spillway can discharge a flow of 693 cfs and the emergency spillway a flow of 144 cfs at El 609.5 which is the approximate average dam crest. The lowest point on the dam crest is El 608.6 which is a localized area of erosion near the spillway. An inflow test flood of 6,390 cfs (one-half the probable maximum flood) will overtop the main dam by about 2.3 feet. The combined spillways will discharge only 13 percent of the adjusted test flood outflow (877 cfs per square mile) before the dam is overtopped. The inflow from a 100-year-frequency storm would result in a water surface at El 610.6 or about 0.9 feet above the crest of the dam. Previous records at this site indicate the dam was not overtopped in the 1955 floods due to the regulating effects of upstream

reservoirs. However, future development in the watershed could increase the runoff and alter conditions.

- b. Adequacy of Information. The lack of in-depth engineering data did not allow for a definitive review. Therefore the adequacy of this dam could not be assessed from the standpoint of reviewing design and construction data, but is based primarily on visual inspection, past performance history and sound engineering judgment.
- c. Urgency. The recommendations outlined below should be implemented within 1 year after receipt of the Phase I Inspection Report.
- d. Need for Additional Information. Additional investigations to further assess the adequacy of the dam and appurtenant structures are outlined below in Section 7.2 Recommendations.

7.2 Recommendations. In view of the concerns over the continued performance of this dam, it is recommended that the Owner employ a qualified consultant to:

- a. evaluate the stability of the dam
- b. evaluate the seepage at the toe of the dam
- c. conduct a more detailed hydrologic and hydraulic investigation for the entire drainage area. The purpose of the investigation is to design a means of increasing the discharge capabilities at the dam and to evaluate the outlet capacity.

The recommendations on repairs and maintenance procedures are stated below under Section 7.3 Remedial Measures.

7.3 Remedial Measures

- a. Alternatives. An alternative to the recommendations above and maintenance procedures itemized below would be draining the reservoir and breaching or removing the dam.

b. Operation and Maintenance Procedures. The dam and appurtenant structures are not adequately maintained. It is recommended that the Owner accomplish the following items:

- (1) remove the blockage at the outlet pipe
- (2) repair the concrete on the spillway weir and pier
- (3) cut down trees and clear brush from the embankment to 20 feet downstream of the toe, from the sides of the downstream stream channel, and from the emergency spillway channel
- (4) repair eroded areas of the upstream face of the dam face and protect with riprap or other suitable material
- (5) replace missing stonework from west wall of spillway and cascade
- (6) clear wood and trash debris from stream bed below spillway cascade
- (7) provide around the clock surveillance during periods of unusually heavy precipitation. The Owner should develop a formal warning system with local officials for alerting downstream residents in case of emergency.
- (8) implement a systematic program of inspection and maintenance. As a minimum, the inspection program should consist of a monthly inspection of the dam and appurtenances, supplemented by additional inspections during and after severe storms. All repairs and maintenance should be undertaken in accordance with all applicable State regulations.

APPENDIX A
PERIODIC INSPECTION CHECKLIST

PERIODIC INSPECTION

PARTY ORGANIZATION

PROJECT Cook Pond

DATE 7/10/78

TIME 9:00 AM

WEATHER cloudy - 45°F

W.S. ELEV. 505.4 * U.S. 505 B.N.C.

* 606 top of raised lip, west end spillway, crest

PARTY:

1. Ed Greco

6. David Cole

2. Lyle Branagan

7. Frank Sviokla

3. Richard Kleber

8. _____

4. Carol Sweet

9. _____

5. Susan Pierce

10. _____

PROJECT FEATURE

INSPECTED BY

REMARKS

1. dam embankment

Ed Greco

2. spillway/emergency spillway

Lyle Branagan

3. intake of outlet conduit

Ed Greco

4. _____

5. _____

6. _____

7. _____

8. _____

9. _____

10. _____

PERIODIC INSPECTION CHECK LIST

PROJECT Cock Pond Dam DATE July 10, 1975
 PROJECT FEATURE dam embankment NAME Ed Gress
 DISCIPLINE geotechnical NAME Richard Weber

AREA EVALUATED	CONDITIONS
<u>DAM EMBANKMENT</u>	
Crest Elevation	658.6 to 659.7
Current Pool Elevation	605.9
Maximum Impoundment to Date	unknown
Surface Cracks	none visible
Pavement Condition	none - crest is earth finish
Movement or Settlement of Crest	crest irregular
Lateral Movement	steep ds slope at left abutment -
Vertical Alignment	crest elevation varies
Horizontal Alignment	irregular
Condition at Abutment and at Concrete Structures	fill in right abutment, ledge at left abutment, steep slopes at spillway abutments
Indications of Movement of Structural Items on Slopes	numerous trees growing on dam - sloping trunks on slopes near spillway
Trespassing on Slopes	path on ls face left abutment - of spillway - chipmunk holes
Sloughing or Erosion of Slopes or Abutments	erosion left + right of spillway
Rock Slope Protection - Riprap Failures	none - scattered stones
Unusual Movement or Cracking at or near Toes	none visible
Unusual Embankment or Downstream Seepage	slight seep at ds toe 30ft. left of spillway - smaller seeps ds along outlet channel
Piping or Boils	none visible
Foundation Drainage Features	none visible
Toe Drains	none visible
Instrumentation System	none visible

PERIODIC INSPECTION CHECK LIST

PROJECT Cook Pond Dam DATE July 10, 1975
 PROJECT FEATURE main spillway NAME Lyle Brainerd
 DISCIPLINE geotechnical NAME Ed Groce

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR,*</u> <u>APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	<i>None</i>
General Condition	<i>NA</i>
Loose Rock Overhanging Channel	<i>NA</i>
Trees Overhanging Channel	<i>NA</i>
Floor of Approach Channel	<i>NA</i>
b. Weir and Training Walls	<i>weir slab - reinforced concrete</i> <i>training walls - mortared masonry</i>
General Condition of Concrete	<i>poor</i>
Rust or Staining	<i>reinforcing mesh exposed on concrete pier + abut</i>
Spalling	<i>along right + left sides of weir</i>
Any Visible Reinforcing	<i>at base of pier + ds on weir</i>
Any Seepage or Efflorescence	<i>none visible</i>
Drain Holes	<i>none</i>
c. Discharge Channel	<i>stone cascade steps</i>
General Condition	<i>poor to fair - some dislodged stones</i>
Loose Rock Overhanging Channel	<i>none</i>
Trees Overhanging Channel	<i>right abutment</i>
Floor of Channel	<i>small stone - 1.5:1 - logs</i>
Other Obstructions	<i>none</i>

* emergency spillway 370' east from spillway

a) earthen channel - trapezoidal - 15 ft wide at bottom, side slopes 1.5:1 ±

b) small brush - recently cleared

c) 400 ft long - connects to discharge channel 100' ds to dam

PERIODIC INSPECTION CHECK LIST



PROJECT Cook Pond Dam DATE July 10, 1978
 PROJECT FEATURE intake of outlet conduit NAME Ed Greco
 DISCIPLINE geotechnical NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u>	
a. Approach Channel	<i>None</i>
Slope Conditions	<i>NA</i>
Bottom Conditions	<i>NA</i>
Rock Slides or Falls	<i>NA</i>
Log Boom	<i>NA</i>
Debris	<i>NA</i>
Condition of Concrete Lining	<i>NA</i>
Drains or Weep Holes	<i>NA</i>
b. * Intake Structure	<i>4'diameter x 7'high-corrugated metal</i>
Condition of Concrete	<i>None</i>
Stop Logs and Slots	<i>None visible</i>


* apparent outlet control:

6 ft. walkway from left us corner of spillway training wall
 2 ft. wide steel plate - 1/4" on steel channel
 steel plate to corrugated metal pipe - locked
 no outlet conduit visible - us or ds
 outlet of pipe - unknown

1





2



WATER LEVEL


3




4

WATER LEVEL


5



SECTION AT SOUTHWEST
END OF SPILLWAY



AT SOUTHWEST
OF SPILLWAY



SECTION AT NORTHEAST
END OF SPILLWAY

WORCESTER
COOKS POND SPILLWAY

WATER LEVEL

8

NORTHEAST
SPILLWAY

ER
SPILLWAY

WORCESTER
WORCESTER

CO

AS FI
COUNT

TRACED BY: *4*
TRACING CHECK

9

6


WORCESTER COUNTY COMMISSIONERS
WORCESTER COUNTY ENGINEERING DEPARTMENT
PLAN OF
DAM
COOKS POND SPILLWAY
WORCESTER
AS FILED AND APPROVED BY THE
COUNTY COMMISSIONERS

SCALES AS NOTED

TRACED BY: J. J. Callahan 3-A-61
TRACING CHECKED BY: _____

DAM NO. 61-13

COUNTY ENGINEER




LOCATION PLAN
1958 THAYER POND
IMPROVEMENTS
GATE PROTECTION
MANHOLE


ACB

PREVIOUS PAGE
IS BLANK

THAYER ²
POND



PLAN
POND
EMENTS
TECTION
LE
H.C.B.



PLAN
1/2" = 1'-0"

3




EXISTING 12" GATE

EXISTING 12"
CAST IRON DRAIN

6'-0"

EXISTING CEM.
STONE MASONRY




EXISTING

THAYER POND
1958 IMPROVEMENTS

H.C.B.

AN
0"


4



SECTION
1/2" = 1'-0"

5

THAYER POND
NEW CONSTRUCTION
1958



6

R. H. WHITE CONSTR
41 CENTR
AUE

VA IO
COVER
1/8" R
WELD

48" ACCM. PIPE

14' ±

4"

2'-0"

15'

BL 592.3

606.6

13.7 H. 1.00

7

WHITE CONSTRUCTION COMPANY, INC.
41 CENTRAL ST.
AUBURN, MASS.

WORCESTER COUNTY COMMISSIONERS
WORCESTER COUNTY ENGINEERING DEPARTMENT
PLAN OF
GATE IMPROVEMENTS
THAYER POND
WORCESTER, MASS.
COUNTY COMMISSIONERS


SCALES AS NOTED

TRACED BY: W. J. Callahan 2-13-67 DAM NO. 61-13
TRACING CHECKED BY: W. O. L. 2-13-67

COUNTY ENGINEER

APPENDIX B
PLAN OF DAM, AND PREVIOUS
INSPECTION REPORTS

	<u>Page</u>
Figure B-1, Plan of Dam	B-1
Figure B-2, Sections	B-2
Figure B-3, Sketch of Spillway, undated	in pocket
Figure B-4, Drawing of Gate House Improvements, dated 1958	in pocket
Previous Inspections (Partial Listing)	B-5
Inspection Report by Massachusetts Department of Public Works January, 1973	B-6



NOTES

1. ELEVATIONS ARE REFERENCED TO ASSUMED BENCHMARK ELEVATION 606.0 (MSL) AT SPILLWAY CREST.
2. INFORMATION SHOWN BASED ON FIELD SURVEY OF JULY, 10, 1978
3. FIELDSTONE SPILLWAY CASCADE NOT INTENDED TO SHOW ACTUAL CONSTRUCTION OR CONFIGURATION.
4. SEE FIGURE 8-2 FOR SECTIONS
5. $\frac{1}{2}$ DENOTES MARSH
6. $\frac{1}{2}$ INDICATES LOCATION AND DIRECTION OF VIEW FOR PHOTO STATIONS

Metcalf & Eddy, Inc.

Cook Pond

EROSION TRENCHES IN CONCRETE SPILLWAY

OUTLET STRUCTURE

MODERATE TO HEAVY VEGETATION

FOOT PATH

DAM CREST

HEAVY VEGETATION ALONG ENTIRE SLOPE


MODERATE VEGETATION ALONG INTERCEPT

ALL ELEVATIONS ARE REFERENCED TO BENCHMARK 606.0 (MSL) AT CREST. INFORMATION SHOWN BASED ON SURVEY OF 1978


NOT SHOWN BASED
SURVEY OF
1978

8-2 FOR SECTIONS
ES MARSH

TES LOCATION AND DIRECTION
FOR PHOTOGRAPHS



3



Figure







Figure B-1 PLAN OF DAM




DAM SECTION 1-1
WS. ELEV. 605.9




DAM SECTION 2-2




SPILLWAY SECTION 3-3



DAM SECTION 4-4



DAM SECTION 5-5



EMERGENCY SPIRWAY SECTION 6-6

SEE PAGE 10

PREVIOUS PAGE IS BLANK

ASCE 1988

Figure B-2 DAM SECTIONS

PREVIOUS INSPECTIONS (PARTIAL LISTING)

INSPECTION REPORT - DAMS AND RESERVOIRS

1. Location: City/Town WORCESTER Dam No. 314-348-13

Name of Dam COOK POND DAM Inspected by MULCAHY DANAHUE

Date of Inspection 1/11/73

2. Owner/s: per: Assessors _____ Prev. Inspection /

Reg. of Deeds _____ Pers. Contact _____

1. SMITH POND, INC. % PHILIP D. THURSTON, 43 TORY FORT LANE, WORC.
Name _____ St. & No. _____ City/Town State Tel. No. _____

2. _____
Name _____ St. & No. _____ City/Town State Tel. No. _____

3. _____
Name _____ St. & No. _____ City/Town State Tel. No. _____

3. Caretaker (if any) e.g. superintendent, plant manager, appointed by absentee owner, appointed by multi owners.

Name: _____ St. & No.: _____

City/Town: _____ State: _____ Tel. No.: _____

4. No. of Pictures taken NONE

5. Degree of Hazard: (if dam should fail completely)*

1. Minor _____ 2. Moderate /

3. Severe _____ 4. Disastrous _____

* This rating may change as land use changes (future development)

6. Outlet Control: Automatic _____ Manual /

Operative _____ yes; _____ No.

Comments: _____

7. Upstream Face of Dam: Condition:

1. Good / 2. Minor Repairs _____

3. Major Repairs _____ 4. Urgent Repairs _____

Comments: _____

DAM NO. 3-14-2411-12

8. Downstream Face of Dam:

Condition: 1. Good 2. Minor Repairs
3. Major Repairs 4. Urgent Repairs

Comments:

9. Emergency Spillway: NONE

Condition: 1. Good 2. Minor Repairs
3. Major Repairs 4. Urgent Repairs

Comments:

10. Water Level at time of inspection: 4.4 ft. above below
top of dam principal spillway
other

11. Summary of Deficiencies Noted:

- Growth (Trees and Brush) on Embankment YES
- Animal Burrows and Washouts NONE
Damage to slopes or top of dam NONE
Cracked or Damaged Masonry RETAINING WALL IN RIGHT HAND CORNER
Evidence of Seepage NONE
Evidence of Piping NONE
Erosion CENTER PIER OF DAM - PART OF THE RIGHT HAND CORNER OF SPILLWAY
Leaks NONE
Trash and/or debris impeding flow NONE
Clogged or blocked spillway NO
Other

12. Remarks & Recommendations: (Fully Explain)

THE CEMENT CONCRETE SPILLWAY SHOWS SIGNS OF EROSION IN THE RIGHT HAND CORNER OF THE SPILLWAY. THIS CONDITION WILL CONTINUE TO EXIST UNTIL REPAIRS ARE MADE TO THE SPILLWAY AND TO THE FIELDSTONE RETAINING WALL WHERE SOME SEEPAGE IS TAKING PLACE AND WATER COMING ONTO THE SPILLWAY IN THIS AREA IS CAUSING THE EROSION. THERE IS ALSO EROSION TAKING PLACE AROUND THE CONCRETE-CENTER PIER THE PURPOSE OF THIS PIER IS TO SUPPORT PEDESTRIAN WALK. SOME OF THE FIELDSTONE IN THE STEPPING AT THE SPILLWAY HAVE FALLEN OUT OF PLACE AND SOME MINOR REPAIRS TO CORRECT THIS CONDITION SHOULD BE MADE. THE FIELDSTONE RETAINING WALLS ALSO NEED MINOR REPAIRS GROWTH OF BRUSH AND TREES ON EARTH EMBANKMENT SECTION OF DAM SHOULD BE REMOVED TO ELIMINATE ANY HAZARD THEY MIGHT POSE TO THE DAM

13. Overall Conditions

1. Safe ✓
2. Minor repairs needed ✓
3. Conditionally safe - major repairs needed _____
4. Unsafe _____
5. Reservoir impoundment no longer exists (explain)
Recommend removal from inspection list _____

DESCRIPTION OF DAM

DISTRICT 3

Submitted by MURPHY - CONCRETE Dam No. 3-14-340-13
 Date 1/11/73 City/Town WILCOX, AR
 Name of Dam COOK POND DAM

1. Location: Topo Sheet No. 20 D

Provide 8 1/2" x 11" in clear copy of topo map with location of Dam clearly indicated.

2. Year built: _____ Year/s of subsequent repairs _____

3. Purpose of Dam: Water Supply _____ Recreational ☒
 Irrigation _____ Other _____

4. Drainage Area: 7.33 sq. mi. _____ acres

5. Normal Ponding Area: 13 ± acres; Ave. depth _____

Impoundment: _____ gals.; _____ acre ft.

6. No. and type of dwellings located adjacent to pond or reservoir

10 WOOD FRAME i.e. summer homes, etc. _____

7. Dimensions of Dam: Length 520' Max. Height 15'

Slopes: Upstream Face 1 1/2:1

Downstream Face 1 1/2:1

Width across top VARIES 12-15'

8. Classification of Dam by Material:

Earth ☒ Conc. Masonry ☒ Stone Masonry ☒

Timber _____ Rockfill _____ Other _____

9. A. Description of present land usage downstream of dam:

_____ % rural; 100 % urban.

B. Is there a storage area or flood plain downstream of dam which could accommodate the impoundment in the event of a complete dam failure? yes ☒ no _____

DAM NO. 3-14-348-13

C 10. Risk to life and property in event of complete failure.

No. of people 40.

No. of homes 8.

No. of Businesses NONE.

No. of industries NONE. Type _____

No. of utilities NONE. Type _____

Railroads NONE.



Other dams SMITH MILL POND

Other _____.

11. Attach Sketch of dam to this form showing section and plan.
on 8½" x 11" sheet.

12. HOW TO LOCATE: FROM INTERSECTION OF CHANDLER AND
PLEASANT STS. GO UP PLEASANT ST. (OPPOSITE)
CHANDLER) STRAIGHT
UP PLEASANT ST. 0.2 MI. TO TATUMS GARDENS TRAIL RT.
DAM OPPOSITE HOUSE # 11.

WORCESTER
COOK POND DAM
DAM NO 3-14-348-13




SECT A-A

APPENDIX C
PHOTOGRAPHS




NO. 1 SPILLWAY WEIR



NO. 2 GATE HOUSE FOR OUTLET CONDUIT




NO. 3 WEST ABUTMENT OF SPILLWAY, DOWNSTREAM SLOPE



NO. 4 CHANNEL DOWNSTREAM OF SPILLWAY



NO. 5 DAM CREST EAST OF SPILLWAY



NO. 6 EMERGENCY SPILLWAY, VIEW LOOKING UPSTREAM

APPENDIX D
HYDROLOGIC AND HYDRAULIC
COMPUTATIONS

	<u>Page</u>
Hydrologic and Hydraulic Computations	D-1
Figure D-1 - Watershed Plan	In pocket
Figure D-2 - Map of Drainage Area.	D-7

Project Nat Review of Non-F. Dams Acct. No. 5864 Page 1 of 6
 Subject Worcester, Ma. Area Comptd. By LEB Date 6/6/78
 Detail COOK POND DAM Ck'd. By EMG Date 7/28/78
 [Gen. Reference: "Open Channel Hydraulics" - Ven Te Chow]

(I) Broad Crested Spillway - $Q_s = CLH^{1.5}$ [Ref. pp 360-362]

$$C = 3.27 + 0.4 \frac{H}{h} ; L = L' - 0.1NH$$

H = Physical Water Head on CREST (h_v not included)

h = Weir Height, L' = Measured Crest Length

Assumptions

For Floods or Peak Flows, $\frac{H}{h} \approx 0.5 \therefore C = 3.47$

$$L = 90\% L' ; L = 37.7' \therefore L' = 33.13$$

$$\therefore Q_s = 3.12 L' H^{3/2}$$

$$\& Q_s = 105.9 (H)^{3/2} \quad \begin{matrix} \text{with } H \text{ meas.} \\ \text{above el. 606} \end{matrix}$$



(II) Flow over Crest of Dam - $q_c = 3.475 \left[\frac{y}{y+h'} \right]^{1/2} (H')^{3/2}$ [Ref. pp 52-3]

q_c = Disch. / ft. of width

H' & h' as defined above; $y = h' + H'$

Assumptions

For Floods (flow over dam crest)

$$H' = \frac{1}{6} h' \quad [\text{note } h' \approx h + H \text{ in Item (I) above}]$$

$$\therefore y = \frac{7}{6} h' \& \left[\frac{y}{y+h'} \right]^{1/2} = \left[\frac{7/6 h'}{13/6 h'} \right]^{1/2} = 0.734$$

$$\therefore q_c = 2.55 (H')^{3/2}$$

Apply to Crest in steps where levels are roughly const.


Dam crest roughly const @ elev. 609.5 & 516' long


$$\therefore Q_c = 1316 (H')^{3/2} \quad \text{with } H' \text{ measured above elev. 609.5}$$


LEGEND

-  WATER SHED
-  PRIMARY ROADS
-  SECONDARY ROADS
-  THICKLY SETTLED
-  RAILROADS
-  TOWN LINES
-  BODY OF WATER, DAM, ELEVATION
-  AREA OF WATER - SHED IN ACRES
-  WATER SHEDS HAVING RUN OFF IMPONDED BY WORC. RES.

TRUE NORTH








EET

5




SCALE IN MILES

WORCESTER COUNTY COMMISSIONERS
WORCESTER COUNTY ENGINEERING DEPARTMENT
PLAN OF
DAMS
FOR
AMERICAN STEEL & WIRE CO.


W. TY. COMMISSIONERS

6



PAXTON
YEAR BUILT
ORIGINAL DAM PREVIOUS DAM

	POND NAME		CAPACITY OF POND IN MILLIONS OF GAL.	AREA OF POND IN ACRES	INDIVIDUAL WATERSHED IN ACRES	TOTAL WATERSHED IN ACRES	ELEV. OF TOP OF DAM SPILLWAY	ELEV. OF TOP OF FLASHBOS- TO SPENCER		
61-02	CENTRAL WORKS *		5.3	5.3			443.40		1814	181
61-08	COES RESERVOIR *			119		4229				
61-05	CURTIS POND *		160	62	883	16663				
03-03	HILTON POND		40	26.4	1347	6792	96.56	98.38		19
61-15	LEESVILL POND		125		1522	15780				
03-05	MOSS RESERVOIR		256	158	699	699	110.79	112.17	CONCRETE	19
03-04	PONDVILLE POND		125	45	2639	4746				
30-21	RAMSHORN POND		720	145	1527	1527	22.0	24.0	PREVIOUS TO 1831	187
30-21	RAMSHORN MEADOW POND		22	38	580	2107				191
61-03	STILL WATER POND *		35	30	605	24319				
03-21	STONEVILLE POND			45	4870	7466				
03-02	STONEVILLE RESERVOIR		185	68	1772	1772				
			1.5	1.5	83	302				



PAXTON


YEAR BUILT

TYPE OF DAM


ORIGINAL DAM PRESENT DAM

HIGH WATER

	1814	1899	EARTH MASONARY TIMBER CORE PLAN B 177 1899 REPAIRS 1936 PLAN 12718	ELEV 443.47 COR SOUTH OF AND IS 3646 - BOUND IS WAY PROP. PL
98.38		1939	GATE IS SCREW STEM 24" PIPE EARTH WITH CONCRETE CORE WALL PLAN FOR CORE - WALL 9642 - CONCRETE SPILLWAY PLAN 13530 - 31 10591 REPAIRS	ELEV 473.51 TWO OF SPILLWAY WORK WATER RIGHTS P PAGE 293 PROPERTY PLAN
112.17	1921	1928	CONCRETE GRAVITY SECTION COVERED WITH EARTH GATE SCREW STEM, 30" x 30" BOX OUTLET STONE MASONARY	ELEV. 112.05 BRASS SOUTH OF SPILLWAY 8044 A FOR PARC
24.0	PREVIOUS TO 1831	1872-3	GATE SCREW STEM, 24" x OUTLET PIPE (POSSIBLY) 30" EARTH PUDDLED TO EITHER SIDE CHESTNUT CUTOFF WALL ALONG DAM & (1873) PLAN 13515 A & B.	ELEV. 24.29 IRON PI OF N.W. COR. OF N.Y
		1916	GATE 36" x OUTLET EARTH WITH CONCRETE CORE WALL, CONCRETE SPILLWAY PLAN 7171	PROPERTY MAP
			RACK, PINON & CONCRETE &	PROPERTY MAP
			GATE 30" x OUTLET EARTH & STONE WALL	PROPERTY MAP
			FLOOD GATE - RACK & PINON, INTAKE GATE - SCREW	ELEV. 443.47 SA



HIGH WATER MARK & WATER RIGHTS	YEAR ESTABLISHED
ELEV 443.47 COPPER BOLT TOP OF STONE BOUND 11.5 SOUTH OF AND 153' W FROM S.E. COR. OF MILL FROM PLAN 3846 - BOUND IS SHOWN AS 60' UP STREAM FROM SPILL - WAY. PROP. PLAN - 8038	1873 BY SUPERIOR COURT DECREE P. 127. WASHBURN MOEN MFG. CO. CROMPTON CARPET CO. DEFENDANT
ELEV. 473.51 TWO FEET BELOW BOLT IN EAST CONCRETE WALL OF SPILLWAY. WORCESTER ELECTRIC LIGHT PLAN 1336 WATER RIGHTS PURCHASED 1917 FROM HILTON HEIRS BK 2123 PAGE 293 PROPERTY PLAN 8034 HIGH WATER MARK	JAN 30, 1914 BY H.A. PRATT PRIVATE
ELEV. 112.05 BRASS PLUG IN LEDGE, EAST SIDE OF POND, 208' SOUTH OF SPILLWAY CREST PLANS 14628 - SEE PLAN 8044 A FOR PARCIS PURCHASE - ALSO 8771 - 8777	OCT. 21, 1924 BY COUNTY COMMISSION
ELEV. 24.29 IRON PIN IN LEDGE ON WESTERLY SHORE. ELEV. OF N.W. COR. OF N.W. BRIDGE WING WALL - 30.00 PROPERTY MAP 8033	1872 REG OF DEEDS, BK. 875, P. 68 PURCHASED BY A CURTIS AS TRUSTEE OF RAMSHORN POND CO. PREVIOUS
PROPERTY MAP 8769 (1904)	
PROPERTY MAP 8769 (1904)	
FROM M. BONZEY 1917 BK. 2123, P. 290	
ELEV. 443.47 SAME AS (CENTRAL WORKS) ESTABLISHED IN EXCHANGE OF TITLES BETWEEN HOLY CROSS, AM. S. & W. CO. CITY OF WORCESTER AND P.F. & F.W. TAYLOR PROP. PLAN 8041.	AP. 29, 1909 BK. 1904, P. 68 (TAYLOR DEED)



YEAR ESTABLISHED	FLOW CONTROLLED BY	MISC INFORMATION
BY SUPERIOR COURT DEGREE VOL. 22 WASHBURN MOEN MFG. CO. VERSUS ON CARPET CO. DEFENDANT	AMERICAN STEEL & WIRE CO	
	NO AGREEMENT - COES CO.	
1914 BY H.A. PRATT PRIV. ENG.	NEW ENG. POWER ASSOCIATES AM. S & W. CO. CAN OBTAIN WATER IN EMERG.	OLDEST WATER PRIVILEGE ELEC. LIGHT CO USES 2 FOR CONDENSING, POND
	AMERICAN STEEL & WIRE CO.	
	CONSOLIDATED RENDERING CO.	NECESSARY TO KEEP P OF THEIR PUMPS
1. 1924 BY COUNTY COMM.	AMERICAN STEEL & WIRE CO.	DURING SUMMER MONTH OF WATER WITHOUT
	LAREE FABRICS MILLS INC WE HAVE NO AGREEMENT	USED FOR CLEANING & NO POWER USE
REG. OF DEEDS, BK. 875, P. 132-149 USED BY A. CURTIS AS TRUSTEE FOR HORN POND CO. PREVIOUS TO RAISING DAM	RAMSHORN POND ASS. - A. S. & W. CO. WORC. COUNTY ELEC. HOPEVILL MFG. CO. CONSOL. RENDERING. WHITTALL EL. ON BLACKSTONE RIVER (AM. S. & W. CO. DAY. CLOVER, W. WINDLE	MIN. FLOW REQ BY SMALL WEIR - 2,500,000 GAL. 1939 NEVER HAS EXCEEDED USED FOR IMPONDING DU IN WINTER TO ENABLE C HORN POND GATE USED FOR POWER WHEN WATER OTHER USE IS FOR
	WHITTALL ASSOCIATES CALL ENG. RM FOR FLASH BD. CHANGE	
	(QUEENSBURY COMBING CO. NEW ENGLAND POWER ASSOCIATES PURCHASED IN 1945	THE AGREEMENT IS THAT COMBING CO. CAN DRAW WATER TO RUN PLANT. W WATER BY CONSULTING N
	AMERICAN STEEL & WIRE CO.	DAM WASHED OUT
1902 BK. 1204, P. 68 THIS IS (DEED)	AMERICAN STEEL & WIRE CO.	18,700,000 GAL. PER. FOR SOUTH WORKS & W AS MEASURED IN 1942 TO INTAKE CHANGES

COUNTY COMMISSIONERS

JAN. 1, 1947.

MEETING DOCKET
SCALES AS NOTED

TRACED BY: P.P.P.

TRACING CHECKED BY: W.O.L.

DAM NO. 10

MISC INFORMATION

COUNTY ENGINEER

OLDEST WATER PRIVILEGE IN SYSTEM, WORC. COUNTY
ELEC. LIGHT CO USES 2 MIL. GAL. 24 HRS. (1921)
FOR CONDENSING, POND KEPT FULL

NECESSARY TO KEEP POND FULL FOR SUCTION
OF THEIR PUMPS

DURING SUMMER MONTHS RESERVOIR LOSES 2"
OF WATER WITHOUT DRAW DOWN

USED FOR CLEANING & CONDENSING PURPOSES
NO POWER USE

MIN. FLOW REQ BY SMALL MILLS WHEN IN OPERATION IS 6" THRU 36" WIDE
WEIR - 2,500,000 GAL. DAY FROM H.W. CLOVER, FLOW FROM 1904 TO
1939 NEVER HAS EXCEEDED 10" OVER SPILLWAY

USED FOR IMPONDING DURING RAINS &
IN WINTER TO ENABLE CLOSING OF RAMS
HORN POND GATE

USED FOR POWER WHEN PLENTY OF
WATER OTHER USE IS FOR CLEANING

THE AGREEMENT IS THAT GUENSBURY
COMBING CO. CAN DRAW SUFFICIENT
WATER TO RUN PLANT. WE CAN OBTAIN
WATER BY CONSULTING N.E. POWER CO

DAM WASHED OUT

18,700,000 GAL. PER DAY REG.
FOR SOUTH WORKS & WIRE MILL
AS MEASURED IN 1942 PREPARATORY
TO INTAKE CHANGES

Y OF THE AMERICAN STEEL & WIRE COMPANY
ED UNLESS AUTHORIZED BY THEM

AMERICAN STEEL & WIRE CO
SUBSIDIARY OF
UNITED STATES STEEL CORPORATION

ENGINEERING
DEPARTMENT

WORCESTER
MASS

USS

DRAWN BY JAN. 1, 1947, BROUGHT
SCALE 1" = 1/2 MILE

17720

WATER SHED OF
SOUTHWORKS POND

DAM NOS. AS NOTED IN PLAN

WATER SHED PLAN
FIGURE D-1

30-21	RANSHAW POND	720	146	1527	1527	22.0	24.0	10185	187
30-21	RANSHAW MEADOW POND	22	38	580	2107				191
01-05	STILL WATER POND *	3.5	30	605	24319				
01-01	STONEVILLE POND		45	4870	7466				
01-02	STONEVILLE RESERVOIR	185	68	1772	1772				
01-07	SOUTHGATE POND	1.5	1.5	83	782				
01-01	SOUTH WORKS POND *	20.0	130	381	24700	438.04	440.04		189

* RUN OFF FROM WATERSHED EFFECTED BY CITY STREETS AND STORM SEWERS (PLANS 6)

NOTE: THE INFORMATION SHOWN ON THIS PLAN WAS DRAWN FROM EXISTING PLANS, & FROM
SPECIALLY THE G.E. GOODWIN REPORT NOV. 14, 1921 AND MOSS RESERVOIR

CROSS, AM. S. & W. T.
P. F. & F. W. TAYLOR

SEWERS (PLANS FOR MOSS RES. DAM: CONCRETE, ORIGINAL DAM 8510 TO 12, PRES. CONST. 10584, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 101, 102, 103, 104, 105, 106, 107, 108, 109, 110, 111, 112, 113, 114, 115, 116, 117, 118, 119, 120, 121, 122, 123, 124, 125, 126, 127, 128, 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 8

SOUTH OF BRIDGE CHURCH PLANS 14628 - SEE PLAN
8044 A FOR PARCELS PURCHASE - ALSO 8771 - 8777

ELEV. 24.29 IRON PIN IN LEDGE ON WESTERLY SHORE. ELEV.
OF N.W. COR. OF N.W. BRIDGE WING WALL - 30.00

1872 REG OF DEEDS, BK. 875, P.132 -
PURCHASED BY A. CURTIS AS TRUSTEE
RAMSHORN POND CO. PREVIOUS TO RA

PROPERTY MAP 8033

PROPERTY MAP 8769 (1904)

PROPERTY MAP 8769 (1904)

FROM M. BONZEY 1917 BK. 2123, P.290

ELEV. 443.47 SAME AS (CENTRAL WORKS)
ESTABLISHED IN EXCHANGE OF TITLES BETWEEN HOLY
CROSS, AM. S. & W. CO. CITY OF WORCESTER AND
P.F. & F.W. TAYLOR PROP. PLAN 8041.

AP. 29, 1909, BK. 1904, P.68 THIS
(TAYLOR DEED)

REG. CONST. 10584, 10582-3, 10507 & S10400, S14628)
ED. IN CEDAR SWAMP 8771

THIS DRAWING AND
AND IS CONFIDENTIAL
AND IS SUBJECT TO

13

OCT. 21, 1924 BY COUNTY COMM.	AMERICAN STEEL & WIRE CO.	DURING SUMMER OF WATER W
	LAREE FABRICS MILLS INC	
	WE HAVE NO AGREEMENT	USED FOR CLEA NO POWER USE
1872 REG OF DEEDS, BK. 875, P132-149	RAMSHORN POND ASS. - A, S & W, CO.	MIN. FLOW REQ
PURCHASED BY A. CURTIS AS TRUSTEE FOR	WORC. COUNTY ELEC. HOPEVILL MFG.	WEIR - 2,500,00
RAMSHORN POND CO. PREVIOUS TO RAISING DAM	CO. CONSOL. RENDING, WHITTALL	1939 NEVER HA
	EL. ON BLACKSTONE RIVER	USED FOR IMPOR
	(AM. S. & W. CO. DAY CLOVER,	IN WINTER TO EN
	W. WINDLE	HORN POND GA
	WHITTALL ASSOCIATES	USED FOR POWER
	CALL ENG. RM FOR FLASH BD. CHANGE	WATER OTHER US
	(QUEENSBURY COMBING CO.	THE AGREEMENT
	NEW ENGLAND POWER ASSOCIATES	COMBING CO. CAN
	PURCHASED IN 1945	WATER TO RUN P
		WATER BY CONSU
	AMERICAN STEEL & WIRE CO.	DAM WASHED
AP. 29, 1909, BK. 1904, P. 68 THIS IS		
(TAYLOR DEED)	AMERICAN STEEL & WIRE CO.	18,700,000 GA
		FOR SOUTH WORK
		AS MEASURED IN
		TO INTAKE CHA

THIS DRAWING AND ALL INFORMATION THEREON IS THE PROPERTY OF THE AMERICAN S
AND IS CONFIDENTIAL AND MUST NOT BE MADE PUBLIC OR COPIED UNLESS AUTHORIZ
AND IS SUBJECT TO RETURN UPON DEMAND.

14

DAM NO

OF THEIR PUMPS

DURING SUMMER MONTHS RESERVOIR LOSES 2"
OF WATER WITHOUT DRAW DOWN

USED FOR CLEANING & CONDENSING PURPOSES
NO POWER USE

CO.
MFG.
ALL

MIN. FLOW REQ BY SMALL MILLS WHEN IN OPERATION IS 6" THRU 36" WIDE
WEIR - 2,500,000 GAL. DAY FROM H.W. CLOVER. FLOW FROM 1904 TO
1939 NEVER HAS EXCEEDED 10" OVER SPILLWAY

USED FOR IMPONDING DURING RAINS &
IN WINTER TO ENABLE CLOSING OF RAMS
HORN POND GATE

ANGE

USED FOR POWER WHEN PLENTY OF
WATER OTHER USE IS FOR CLEANING

ATES

THE AGREEMENT IS THAT GUENSBURY
COMBING CO. CAN DRAW SUFFICIENT
WATER TO RUN PLANT. WE CAN OBTAIN
WATER BY CONSULTING N.E. POWER CO

DAM WASHED OUT

18,700,000 GAL. PER DAY REG.
FOR SOUTH WORKS & WIRE MILL
AS MEASURED IN 1942 PREPARITORY
TO INTAKE CHANGES

TY OF THE AMERICAN STEEL & WIRE COMPANY
PIED UNLESS AUTHORIZED BY THEM

AMERICAN STEEL & WIRE CO
SUBSIDIARY OF
UNITED STATES STEEL CORPORATION

ENGINEERING
DEPARTMENT

WORCESTER
MASS

USS

DRAWN BY JAN. 1, 1947, BROUGHT
SCALE 1" = 1/2 MILE

17720

WATER SHED OF
SOUTHWORKS POND



DAM NOS. AS NOTED IN PLAN

WATERSHED PLAN
FIGURE D-1

15

Project NAT. REV. OF NONFED. DAMS Acct. No. 5864 Page 2 of 6
 Subject WORCESTER MASS. AREA Comptd By LEB Date 7/17/78
 Detail COOK POND Ck d. By EMG Date 7/17/78

III DISCHARGE OF EMERGENCY SPILLWAY



Nominal Channel Section

Control Section

$$S = .0035 ; n = 0.06$$

$$A = y(13 + 1.38y) ; P = 13 + 3.41y$$

$$Q_{ES} = A \frac{1.49}{n} R^{2/3} S^{1/2} = 1.47 A R^{2/3}$$

Loss @ Ent. = one vel. head

y	A	P	$R^{2/3}$	Q_{ES}	V	h_v	Pond Elev.
1	14.4	16.4	.917	19	1.35	0.03	607.2
2	31.52	19.82	1.362	63	2.00	0.06	608.3
3	51.42	23.23	1.698	128	2.497	0.10	609.3
4	74.08	26.64	1.977	215	2.907	0.13	610.3
5	99.5	30.05	2.222	325	3.266	0.17	611.4
0.8	11.29	15.73	0.801	13.3	1.178	0.02	607.0
3.2	55.73	23.91	1.758	144	2.584	0.10	609.5
6	127.68	33.46	2.442	458	3.59	0.20	612.4

IV PEAK INFLOW TEST FLOOD

- For total Drainage Area = 7.1 sq miles

1- Pond & Swamp Areas:

0.024	- Cook P.
0.076	- " " #2
0.240	- " " #1
0.060	- Southern Swamp #2
0.060	- Northern Swamp #1
<u>0.460</u>	<u>mi² - S&P -</u>

$$\frac{0.46}{7.1} = \underline{\underline{6.5\% \text{ Ponds \& Swamps}}}$$

2- Slopes: Tattuck Brook - 4% ± } Northern End
 Scott Brook - 7% ± }

Essentially rest of D.A. is lower peaks

Use 6% ± as average slope.

3- "Rolling": - $\Delta_1 = 5\%$ (2.5% slope 70% Pts)
 $\Delta_2 = 5\%$ (7.5% " 10% Pts)

For 6% slope, $\Delta_1 = 3.5\%$, $\Delta_2 = 2(3.5) = 7.0\%$ Pts.
 This D.A. has 6.5% Pts. thus we are
 slightly higher than "Rolling"

Say 1800 c.f.s. / mi² (Full R.M.P. storm)

$$\therefore \text{Inflow Test Flood: } 1800 \times 7.1 \times \frac{1}{2} = \underline{\underline{6390 \text{ cfs.} = Q_1}}$$

V OUTFLOW RELATION

Adjust Q_1 by storage considerations to obtain final outflow Q_F . S_F = Final Storage @ Pond, related to Q_F , but in terms of inches of rain on the Drainage Area

$$Q_F = 6390 \left(1 - \frac{S_F}{9.5}\right) = 6390 - 672.6(S_F)$$

Project NAT. REV. OF NON FED DAMS Acct No. 5864 Page 4 of 6
 Subject WORCESTER MASS AREA Comptd By LEB Date 7/17/78
 Detail COOK POND DAM Ckd By EMG Date 7/27/78

(VI) DISCHARGE, STORAGE & ADJUSTMENT SUMMARY

Pond Elev.	Q_s	Q_{ES}	Q_C	Q_{TOT}	Storage Above Spill		For $Q_F =$ 6390 - 672.6 (S)	$Q_{F100} =$ 2690 - 572 S
					in. - mi ²	in. on D.A. (S)		
606.0	—	—	—	0	0	0		
607.0	106	13	—	119	0.29	0.04	6363	
607.2	139	19	—	158	0.35	0.05	6356	
608.3	369	63	—	432	0.66	0.09		
609.3	635	120	—	763	0.95	0.13		
609.5	693	144	—	837	1.01	0.14	6296	
610.3	944	215	942	2101	1.24	0.17	6275	2573
611.4	1329	325	3447	5101	1.56	0.22	6242	2564
612.4	1715	458	6499	8672	1.84	0.26	6215	

From Discharge Curves Outflow for Test Flood = 6230 cfs.

(VII) 100 YEAR STORM

100 yr. 6 hour storm equals 4.7 inches.

MIN INFILTRATION FOR $\frac{B+C}{B+C}$ soils = $(0.18"/hr)(6.0 \text{ hours}) = 1.1 \text{ inches}$

$$Q_{100} = 12780 \left(\frac{4.7 - 1.1}{19 - 1.1} \right) = 2690 \text{ cfs. (inflow)}$$

$Q_{F100} = 2690 - 572 S_{F100}$; From Disch. Curves Outflow = 2560 cfs for 100 yr storm

(VIII) Flow over Dam Crest

Pond Elev. 611.75, $Q_C = 1316(2.25)^{3/2} = 4441.5 \text{ cfs}$
 Ave Over Crest = 8.61 cfs/ft.

$$y_c = 1.32', V_c = 6.2 \text{ fps.}$$

Low Level Outlet [Ref. Chow "Open Chan. Hydr." - pg 498, Fig 17-3c]

Outlet consists of one- 12" ϕ pipe line, assumed invert elev. 598
 Nom. Pond Elev. 606; $H = 7'$, $d = 7$, $Q = 8 \text{ cfs. on 1.1 c.s.m.}$

AD-A146 330

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
COOK POND DAM (MA 001..(U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV AUG 78


2/2

UNCLASSIFIED

F/G 13/13

NL


						END
						DATE
						FORMED
						10-84
						DTIC



Project NAT. REV. OF NONFED DAMS Acct No. 5864 Page 6 of 6
 Subject WORCESTER MASS AREA Comptd By LEB Date 7/17/53
 Detail COOK POND DAM Ckd By ENR Date 7/22/53

(IX) Discharge & Storage Function vs Pond Elev.

METCALF & EDDY, ENGINEERS



Project Nat Review of Non Fed Dams Acct No 5864 Page 6 of 6
 Subject Worcester Mass. Area Comptd By LEB Date 7/20/78
 Detail Cook Pond Dam Ckd. By EMG Date 7/20/78



Failure of Dam

Peak Failure Flow:

Pond Elevation - 611.75

Toe Elevation - 598.70

$$Y_0 = 13.05$$

Dam Length Subject to Breaching = 157'*

*157' = Mid Ht. Length of
Easterly Sect. of Dike

$$W_0 = 40\% (157) = 63$$

$$Q_P = 1.68 W_0 (Y_0)^{1.5} = 1.68 (63) (13.05)^{1.5} = \underline{4990 \text{ c.f.s}}$$


Storage Volume Released:

Storage Above Spillway = 0.024 (640) (5.75) = 88 Ac. ft

Storage Below Spillway = 105 "

S = Total Storage = 193 "


Channel Hydraulics:



$$S = \frac{10}{1190} = .0084, n \approx .06, A = \frac{1}{2} (58.8) y^2 = 29.4 y^2$$

$$P \approx \text{Width} = 58.8 y, R = \frac{y}{2}; Q = AR^{2/3} = 2.28 AR^{2/3}$$

y	A	R ^{2/3}	V	Q
3'	265	1.31	2.99	791 c.f.s.
4'	470		3.62	1701
5'	735	1.84	4.20	3087
6'	1058	2.08	4.74	5017



Reach = 2540

$$Q_1 = 4990; y_1 = 5.95'; A_1 = 1030; Vol_1 = \frac{1}{2} (1030) (2540) = 30 \text{ Ac. ft}$$

$$Q_2 = 4990 \left(1 - \frac{30}{193}\right) = 4210 \text{ c.f.s.}; \text{Wave Ht.} \approx 5.6'; \text{Vel.} = 4.6 \text{ fps}$$

Time to Drain:

$$\frac{43560 (193 \text{ Ac. ft})}{3600 (\frac{1}{2}) (4210)} = \underline{1.1 \text{ Hours or 67 Minutes}}$$

Effect on Patch Res:

$$\text{Raise Level by } \frac{193}{640 (.05)} = \underline{6 \text{ feet}}$$

D-6




FIG. D-2 COOK POND DRAINAGE AREA

APPENDIX E
INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

INVENTORY OF DAMS IN THE UNITED STATES

STATE	IDENTITY NUMBER	SPONSOR	AGENCY	DATE	COUNTY	NAME	REPORT DATE
MA	123	NED	MA	027	03	COOK POND DAM	15AUG78

POPULAR NAME	NAME OF IMPROVEMENT

RECORD NO.	RIVER OR STREAM	NEAREST DOWNSTREAM CITY-TOWN-VILLAGE	POPULATION
01 06	TR-BLACKSTONE RIVER	MORCESTER	172300

TYPE OF DAM	YEAR COMPLETED	PURPOSES	HYDRO-P. CAP.	HYDRO-P. HEIGHT	HYDRO-P. AREA	HYDRO-P. CAP.	HYDRO-P. HEIGHT	HYDRO-P. AREA
REPG	1830	R	15	15	150	100	NED	N

REMARKS

IDB	SPILLWAY	MAXIMUM DISCHARGE (CFS)	VOLUME OF DAM (CU FT)	POWER CAPACITY (KW)	NAVIGATION LOCKS
1	U	510	693	16000	

OWNER	ENGINEERING BY	CONSTRUCTION BY
SMITH POND INC.	UNKNOWN	UNKNOWN

DESIGN	CONSTRUCTION	OPERATION	MAINTENANCE
NONE	NONE	NONE	NONE

INSPECTION BY	INSPECTION DATE	AUTHORITY FOR INSPECTION
METCALF AND EDDY INC.	10JUL78	PL 92-367

REMARKS

VER/DATE

10AUG78

ATE
LME