


AD-A146 332


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  
TOWNSEND HARBOR DAM (..(U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV JUN 79

1/1

UNCLASSIFIED

F/G 13/13 NL





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A146 332

MERRIMACK RIVER BASIN  
TOWNSEND, MASSACHUSETTS

TOWNSEND HARBOR DAM  
MA 00138

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

DTIC FILE COPY



DTIC  
ELECTE  
OCT 03 1984  
S D

DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

JUNE 1979

84 09 28 063

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                   | READ INSTRUCTIONS<br>BEFORE COMPLETING FORM                 |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------|-------------------------------------------------------------|
| 1. REPORT NUMBER<br>MA 00138                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 2. GOVT ACCESSION NO.<br>A146 332 | 3. RECIPIENT'S CATALOG NUMBER                               |
| 4. TITLE (and Subtitle)<br>Townsend Harbor Dam<br>NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS                                                                                                                                                                                                                                                                                                                                                                                       |                                   | 5. TYPE OF REPORT & PERIOD COVERED<br>INSPECTION REPORT     |
| 7. AUTHOR(s)<br>U.S. ARMY CORPS OF ENGINEERS<br>NEW ENGLAND DIVISION                                                                                                                                                                                                                                                                                                                                                                                                                        |                                   | 6. PERFORMING ORG. REPORT NUMBER                            |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                   | 8. CONTRACT OR GRANT NUMBER(s)                              |
| 11. CONTROLLING OFFICE NAME AND ADDRESS<br>DEPT. OF THE ARMY, CORPS OF ENGINEERS<br>NEW ENGLAND DIVISION, NEDED<br>424 TRAPELO ROAD, WALTHAM, MA. 02254                                                                                                                                                                                                                                                                                                                                     |                                   | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)                                                                                                                                                                                                                                                                                                                                                                                                                 |                                   | 12. REPORT DATE<br>June 1979                                |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                   | 13. NUMBER OF PAGES<br>65                                   |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                   | 15. SECURITY CLASS. (of this report)<br>UNCLASSIFIED        |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                   | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE                  |
| 16. DISTRIBUTION STATEMENT (of this Report)<br>APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED                                                                                                                                                                                                                                                                                                                                                                                          |                                   |                                                             |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)                                                                                                                                                                                                                                                                                                                                                                                                  |                                   |                                                             |
| 18. SUPPLEMENTARY NOTES<br>Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.                                                                                                                                                                                                                                          |                                   |                                                             |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number)<br>DAMS, INSPECTION, DAM SAFETY,<br>Merrimack River Basin<br>Townsend, Mass.                                                                                                                                                                                                                                                                                                                             |                                   |                                                             |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number)<br>Townsend Harbor Dam consists of a 100 foot long earth embankment 11 feet high at the right, a 92 foot long stone masonry spillway 8 feet high at the center and 57 foot long stone masonry wall retaining apparent fill at the left side of the dam. The dam is in fair condition. Based on the size, small, and hazard classification, significant, the spillway test flood is the $\frac{1}{4}$ PMF. |                                   |                                                             |



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
424 TRAPELO ROAD  
WALTHAM, MASSACHUSETTS 02154

REPLY TO  
ATTENTION OF:

NEDED

SEP 17 1979

Honorable Edward J. King  
Governor of the Commonwealth of  
Massachusetts  
State House  
Boston, Massachusetts 02133

Dear Governor King:

I am forwarding to you a copy of the Townsend Harbor Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Department of Environmental Quality Engineering, the cooperating agency for the Commonwealth of Massachusetts. In addition, a copy of the report has also been furnished the owner, Hollingsworth & Vose Co., Townsend Road, West Groton, Massachusetts 01472.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Environmental Quality Engineering for your cooperation in carrying out this program.

Sincerely yours,

  
MAX B. SCHEIDER

Colonel, Corps of Engineers  
Division Engineer

Incl  
As stated

MERRIMACK RIVER BASIN  
TOWNSEND, MASSACHUSETTS

TOWNSEND HARBOR DAM  
MA 00138

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

JUNE 1979

TOWNSEND HARBOR DAM  
MA 00138

MERRIMACK RIVER BASIN  
TOWNSEND, MASSACHUSETTS

|                    |                                     |  |
|--------------------|-------------------------------------|--|
| Accession For      |                                     |  |
| NTIS GRA&I         | <input checked="" type="checkbox"/> |  |
| DTIC TAB           | <input type="checkbox"/>            |  |
| Unannounced        | <input type="checkbox"/>            |  |
| Justification      |                                     |  |
| By                 |                                     |  |
| Distribution/      |                                     |  |
| Availability Codes |                                     |  |
| Avail and/or       |                                     |  |
| Special            |                                     |  |
| A-1                |                                     |  |



PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

Identification No. : MA 00138  
Name of Dam: TOWNSEND HARBOR DAM  
Town: TOWNSEND  
County and State: MIDDLESEX, MA  
Stream: SQUANNACOOK  
Date of Inspection: 15 NOVEMBER 1978

BRIEF ASSESSMENT

Townsend Harbor Dam consists of a 100 foot long earth embankment 11 feet high at the right, a 92 foot long stone masonry spillway 8 feet high at the center and 57 foot long stone masonry wall retaining apparent fill at the left side of the dam. The outlet works of the reservoir, a millrace, is to the left of the stone masonry wall. The millrace has an abandoned concrete control structure near its mid-length, a concrete overflow near the three-quarter point and a concrete control structure with stop logs at the discharge end which is approximately 200 feet downstream of the spillway.

The dam is in fair condition. Slight seepage was observed at the right end of the spillway and from under the old grist mill building. Brush, trees and debris are present on the dam and dike embankments and in the downstream channel.


Based on the size, small, and hazard classification, significant, in accordance with the Corps of Engineers Guidelines, the spillway test flood is the 1/4 Probable Maximum Flood (1/4 PMF). The test flood peak outflow was estimated to be 14,610 cfs and would result in overtopping the dam by approximately 7.5 feet; however, under such a flooding condition the dam would be essentially submerged by tailwater. Hydraulic analysis indicates that the spillway will only pass 43 percent of the test flood.

Recommended additional investigations by the Owner include a detailed hydrologic-hydraulic study of spillway capacity, an investigation of the protection of the millrace dike and an investigation of seepage at the grist mill foundation and at the right end of the spillway. Recommended remedial measures include the cutting of brush and trees at the dam, dike and discharge channel, the repair of locally eroded areas and spillway apron and the establishment of formal maintenance program, operational procedures and emergency preparedness plan and warning system. These recommendations and remedial measures as delineated in Section 7 of the report should be undertaken within one year of receipt of the report by the Owner.


CAMP DRESSER & MCKEE INC.


*Roger H. Wood*


Roger H. Wood  
Vice President




This Phase I Inspection Report on Townsend Harbor Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgement and practice, and is hereby submitted for approval.

  
JOSEPH W. FINEGAN, JR., MEMBER  
Water Control Branch  
Engineering Division

  
JOSEPH A. MCELROY, MEMBER  
Foundation & Materials Branch  
Engineering Division

  
CARNEY M. TERZIAN, CHAIRMAN  
Chief, Structural Section  
Design Branch  
Engineering Division

APPROVAL RECOMMENDED:

  
JOE B. FRYAR  
Chief, Engineering Division

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I Investigations are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the test flood is based on the estimated "probable maximum flood" for the region (greatest reasonably possible storm runoff), or a fraction thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

## TABLE OF CONTENTS

| <u>Section</u>        | <u>Page</u> |
|-----------------------|-------------|
| Letter of Transmittal |             |
| Brief Assessment      |             |
| Review Board Page     |             |
| Preface               | i           |
| Table of Contents     | ii & iii    |
| Overview Photo        | iv          |
| Location Map          | v           |

## REPORT

### 1. PROJECT INFORMATION

|                                         |     |
|-----------------------------------------|-----|
| 1.1 General                             |     |
| a. Authority                            | 1-1 |
| b. Purpose of Inspection                | 1-1 |
| 1.2 Description of Project              |     |
| a. Location                             | 1-2 |
| b. Description of Dam and Appurtenances | 1-2 |
| c. Size Classification                  | 1-3 |
| d. Hazard Classification                | 1-3 |
| e. Ownership                            | 1-3 |
| f. Operator                             | 1-3 |
| g. Purpose of Dam                       | 1-3 |
| h. Design and Construction History      | 1-3 |
| i. Normal Operational Procedures        | 1-3 |
| 1.3 Pertinent Data                      | 1-3 |

### 2. ENGINEERING DATA

|                  |     |
|------------------|-----|
| 2.1 Design       | 2-1 |
| 2.2 Construction | 2-1 |
| 2.3 Operation    | 2-1 |
| 2.4 Evaluation   | 2-1 |

### 3. VISUAL INSPECTION

|                           |     |
|---------------------------|-----|
| 3.1 Findings              |     |
| a. General                | 3-1 |
| b. Dam                    | 3-1 |
| c. Appurtenant Structures | 3-2 |
| d. Reservoir Area         | 3-2 |
| e. Downstream Channel     | 3-3 |
| 3.2 Evaluation            | 3-3 |

### 4. OPERATIONAL PROCEDURES

|                                                 |     |
|-------------------------------------------------|-----|
| 4.1 Procedures                                  | 4-1 |
| 4.2 Maintenance of Dam                          | 4-1 |
| 4.3 Maintenance of Operating Facilities         | 4-1 |
| 4.4 Description of any Warning System in Effect | 4-1 |
| 4.5 Evaluation                                  | 4-1 |

## TABLE OF CONTENTS (Cont'd)


|                                                      | <u>Page</u> |
|------------------------------------------------------|-------------|
| 5. HYDRAULIC/HYDROLOGIC                              |             |
| 5.1 Evaluation of Features                           | 5-1         |
| a. General                                           | 5-1         |
| b. Design Data                                       | 5-1         |
| c. Experience Data                                   | 5-1         |
| d. Visual Observations                               | 5-1         |
| e. Test Flood Analysis                               | 5-2         |
| f. Dam Failure Analysis                              | 5-2         |
| 6. STRUCTURAL STABILITY                              |             |
| 6.1 Evaluation of Structural Stability               | 6-1         |
| a. Visual Observation                                | 6-1         |
| b. Design and Construction Data                      | 6-1         |
| c. Operating Records                                 | 6-1         |
| d. Post-Construction Changes                         | 6-1         |
| e. Seismic Stability                                 | 6-1         |
| 7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES |             |
| 7.1 Dam Assessment                                   | 7-1         |
| a. Condition                                         | 7-1         |
| b. Adequacy of Information                           | 7-1         |
| c. Urgency                                           | 7-1         |
| d. Need for Additional Investigation                 | 7-1         |
| 7.2 Recommendations                                  | 7-1         |
| 7.3 Remedial Measures                                | 7-1         |
| a. Operation and Maintenance Procedures              | 7-1         |
| 7.4 Alternatives                                     | 7-2         |

## APPENDIXES

|                                                                            |     |
|----------------------------------------------------------------------------|-----|
| APPENDIX A - INSPECTION CHECKLIST                                          | A-1 |
| APPENDIX B - ENGINEERING DATA                                              | B-1 |
| APPENDIX C - PHOTOGRAPHS                                                   | C-1 |
| APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS                         | D-1 |
| APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL<br>INVENTORY OF DAMS | E-1 |



1. OVERVIEW OF DAM FROM SOUTH HARBOR ROAD BRIDGE.



DAM TOWNSEND HARBOR DAM

IDENTIFICATION NO. MA 00138



LOCATION MAP  
USGS QUADRANGLE  
TOWNSEND, MASS. - N.H.

APPROX. SCALE: 1" = 2000'

PHASE 1 INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

TOWNSEND HARBOR DAM  
MA 00138

SECTION 1: PROJECT INFORMATION

1.1 General

- a. Authority - Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England region.

Camp Dresser & McKee Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Massachusetts. Authorization and notice to proceed was issued to Camp Dresser & McKee Inc. under letters of 12 July 1978 and 23 October 1978 from Colonel John P. Chandler, Corps of Engineers. Contract No. DACW 33-78-C-0354 has been assigned by the Corps of Engineers for this work. Haley and Aldrich, Inc. has been retained by Camp Dresser & Inc. for soils and geological portions of the work.

- b. Purpose - The primary purpose of the investigation is to:
- (1) Perform technical inspection and evaluation of non-federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-federal interests.
  - (2) Encourage and assist the states to initiate quickly effective dam safety programs for non-federal dams.
  - (3) Update, verify and complete the National Inventory of Dams.

PHASE 1 INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

TOWNSEND HARBOR DAM  
MA 00138

SECTION 1: PROJECT INFORMATION

1.1 General

- a. Authority - Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England region.

Camp Dresser & McKee Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Massachusetts. Authorization and notice to proceed was issued to Camp Dresser & McKee Inc. under letters of 12 July 1978 and 23 October 1978 from Colonel John P. Chandler, Corps of Engineers. Contract No. DACW 33-78-C-0354 has been assigned by the Corps of Engineers for this work. Haley and Aldrich, Inc. has been retained by Camp Dresser & Inc. for soils and geological portions of the work.

- b. Purpose - The primary purpose of the investigation is to:
- (1) Perform technical inspection and evaluation of non-federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-federal interests.
  - (2) Encourage and assist the states to initiate quickly effective dam safety programs for non-federal dams.
  - (3) Update, verify and complete the National Inventory of Dams.

## 1.2 Description of Project

- a. Location - Townsend Harbor Dam is located on the Squannacook River, approximately 95 feet upstream of South Harbor Road and adjacent to Main Street in the Town of Townsend, Massachusetts, as shown on the report's location map. Water impounded by the dam is called Harbor Pond.
- b. Description of Dam and Appurtenances - Townsend Harbor Dam consists of a 92.2-ft. long, 8.3-ft. high stone-masonry overflow spillway flanked on the right by a 100 foot long low earth embankment and on the left by an area of apparent fill retained by a 57-ft. long stone-masonry wall.

A 17.6-ft. wide millrace runs parallel to the Squannacook River around the left abutment area past old mill buildings and rejoins the downstream channel over 200 feet below the dam. A 16.3-ft. long railroad bridge forms the entrance to the millrace, which is a stone-masonry-walled channel upstream of South Harbor Road and is a concrete channel downstream. A 3.9-foot-wide, stop-log controlled concrete outlet at the end of the millrace allows the flow to return to the Squannacook River.

Short stone masonry walls extend about 8 feet from the right spillway training wall along the upstream and downstream faces of the right dam embankment. Beyond these walls, extending to a total length of approximately 100 feet from the spillway, there is an irregularly-shaped grass and brush-covered earth embankment. The embankment height varies from a maximum of approximately 13 ft. at the spillway to a junction with natural ground in a private yard. The embankment crest is about 2.7 feet above the level of the spillway crest.

To the left of the spillway, the apparent filled area is relatively level at 2.8 feet above the spillway crest and is bounded by the left spillway and channel walls to the south, a stone-masonry upstream wall to the west, the millrace to the north, and South Harbor Road to the east. Most of the surface is grass and weeds, but there is one large wood-frame building called "The Cooperage" that projects over the downstream river channel.

Downstream of South Harbor Road the millrace generally parallels the river channel, with its river-side bank about 12 feet above the river channel. An 80-ft. long section of this bank, between an old wood frame grist mill near South Harbor Road and the concrete millrace outlet structure near another mill building, functions as an earth dike. The dike has a crest width that varies from 10 to 20 feet, an upstream concrete wall, and a partial downstream stone-masonry wall. Most of the millrace dike crest has a cover of grass and weeds with some trees and brush, while the gradual slope from the downstream wall to the river channel has more trees and brush.

- c. Size Classification - Townsend Harbor Dam has a height of approximately 11 feet and a storage capacity of 273 acre-feet at the top of the dam. According to guidelines established by the Corps of Engineers, the dam is classified in the small category.
- d. Hazard Classification - Based on the results of the dam failure analysis included in Section 5 of this report, failure of the dam could jeopardize a few lives due to the presence of a building on the left side of the downstream channel. The dam is, therefore, classified in the significant hazard category.
- e. Ownership -The dam and millrace have been owned by Hollingsworth & Vose Company for the past 18 years. The previous owner is reported to be Townsend Harbor Investments Inc., from which Hollingsworth & Vose Co. purchased the property. The address of the present owner is: Hollingsworth & Vose Company, Townsend Road, West Groton, Massachusetts, 01472. Mr. A.E. Irean at the above address is the owner's representative.
- f. Operator - Operation of the dam is the responsibility of Mr. A.E. Irean of Hollingsworth & Vose Co. His address is Hollingsworth & Vose Co., Townsend Road, West Groton, Massachusetts, 01472 (phone 617/448-3311).
- g. Purpose of Dam - A dam was originally constructed at this general area in 1733 as a water supply for a saw mill which eventually became a grist mill. In 1870, the present dam was constructed to provide additional power for the Spaulding Leatherboard Company. The present owner utilizes the dam as a water reservoir to supplement extreme dry-weather river flow.
- h. Design and Construction History - There are no records of the design or construction of this dam. A newspaper account and plaque at the site indicate that a dam was originally built in 1733 in this area. The present dam was constructed in 1870 and rebuilt or repaired after being damaged in 1936 and 1938.
- i. Normal Operational Procedures - There is no formally-established routine for operation of the dam. Mr. Irean stated that Harbor Pond is maintained at approximate spillway crest elevation year-round with stop logs located at the millrace outlet. During very dry periods, the operator increases the flow through the millrace by removing the stop logs.

j.3 Pertinent Data - Elevations used in this report are on National Geodetic Vertical Datum (NGVD), formerly referred to as Mean Sea Level Datum (MSL). The elevations previously established at the dam site and shown on the plan included in Appendix B are on NGVD and agree with those shown on the USGS Quadrangle, Townsend, Mass., 1965.

- a. Drainage Area - The drainage area tributary to the dam site is 58.3 square miles and is characterized by moderately-forested, lightly-developed rolling terrain. In the vicinity of Harbor Pond, the terrain is flat and swampy. Harbor Pond accounts for approximately 0.1 percent of the total drainage area.
- b. Discharge at Dam Site - There are no records of discharges at the dam site, but Squannacook River discharges are recorded at USGS Gage Number 01096000 located approximately 2 miles downstream of the dam site.
  - (1) Outlet works size-----3.9 ft. wide by 2.8 ft. high  
box outlet
  - (2) Maximum known flood at damsite-----Unknown
  - (3) Ungated spillway capacity at top of dam  
1,430 cfs @ 270.0 elev.
  - (4) Ungated spillway capacity at test flood elevation  
6,320 cfs @ 277.5 elev.
  - (5) Gated spillway capacity at normal pool elevation-----N/A
  - (6) Gated spillway capacity at test flood elevation-----N/A
  - (7) Total spillway capacity at test flood elevation  
6,320 cfs @ 277.5 elev.
  - (8) Total project discharge at test flood elevation  
14,610 cfs @ 277.5 elev.
- c. Elevation (NGVD)
  - (1) Streambed at centerline of dam-----259.0 (Est)
  - (2) Test flood tailwater-----275.0
  - (3) Upstream portal invert diversion tunnel-----N/A
  - (4) Normal pool-----267.3
  - (5) Full flood control pool-----N/A
  - (6) Spillway crest-----267.3
  - (7) Design surcharge (Original Design)-----Unknown
  - (8) Top of dam-----Varies, low point at 270.0
  - (9) Test flood design surcharge-----277.5

d. Reservoir

- (1) Length of test flood pool-----8,400 ft.
- (2) Length of normal pool-----3,500 ft.
- (3) Length of flood control pool-----N/A

e. Storage (acre-feet)

- (1) Normal pool-----116.0
- (2) Flood control pool-----N/A
- (3) Spillway crest pool-----116.0
- (4) Top of dam-----273.0
- (5) Test flood pool-----2,646

f. Reservoir Surface (acres)

- (1) Normal pool-----43.5
- (2) Flood-control pool-----N/A
- (3) Spillway crest-----43.5
- (4) Test flood pool-----374.4
- (5) Top of dam-----197.4

g. Embankments

|                             | <u>Right Embankment</u> | <u>Millrace Dike</u>                                                                                   |
|-----------------------------|-------------------------|--------------------------------------------------------------------------------------------------------|
| (1) Type                    | Earth fill              | Earth fill with concrete upstream face and partial stone-masonry downstream face                       |
| (2) Length                  | Approx. 100 ft.         | Approx. 80 ft.                                                                                         |
| (3) Height                  | Approx. 11 ft. max      | Approx. 12 ft.                                                                                         |
| (4) Top width and elevation | 20 ft. max at elev. 270 | 10 to 20 ft. at elev. 270.2                                                                            |
| (5) Side slopes             | Irregular U/S & D/S     | Vertical walls with irregular base slopes which are flatter than 3H to 1V slope below downstream wall. |

|                     |               |               |
|---------------------|---------------|---------------|
| (6) Zoning          | Unknown       | Unknown       |
| (7) Impervious core | Unknown       | Unknown       |
| (8) Cutoff          | Unknown       | Unknown       |
| (9) Grout curtain   | Probably none | Probably none |

h. Diversion and Regulating Tunnel-----None

i. Spillway

|                          |                                   |
|--------------------------|-----------------------------------|
| (1) Type-----            | Stone masonry                     |
| (2) Length of weir-----  | 92.2 ft.                          |
| (3) Crest elevation----- | 267.3 MSL                         |
| (4) Gates-----           | None                              |
| (5) U/S Channel-----     | None                              |
| (6) D/S Channel-----     | 85-ft. wide river at 0.0015 slope |

j. Regulating Outlets - Flow at the dam can be regulated by insertion or removal of stop logs at the control structure at the downstream end of the millrace. The discharge opening is 3.9 feet wide and, without stop logs, is 6.1 feet high, with an estimated invert elevation of 263.1. Normally, there are 3.3 feet of stop logs at the outlet, setting the normal weir crest at elevation 266.4. There is an uncontrolled overflow spillway from the millrace to the Squannacook River located approximately 23 feet upstream from the downstream millrace control structure. The overflow spillway crest is at elevation 268.3 and is approximately 18 feet long.

## SECTION 2. ENGINEERING DATA

- 2.1 Design Records - No design records were located for the Townsend Harbor Dam.
- 2.2 Construction Records - No records of the original construction were located.
- 2.3 Operation Records - No operational records were located for the dam.
- 2.4 Evaluation
  - a. Availability - No records for the dam other than prior inspection reports were located.
  - b. Validity - There are no known design, construction or operating records.
  - c. Adequacy - The absence of known records requires that the evaluation of the dam during this investigation be based on the visual examination described in the following section.

## SECTION 3: VISUAL INSPECTION

### 3.1 Findings

- a. General - The Phase I visual examination of Townsend Harbor Dam was conducted on 15 November 1978. In general, the structures were observed to be in fair condition. It should be noted that the only pond drain for this structure is the millrace channel.

Visual inspection checklists for the dam are included in Appendix A, and selected photographs are given in Appendix C.

- b. Dam and Spillway - The spillway, and the earth embankments on each side of it, show no visual evidence of major lateral movement or settlement. The open-joint stone-masonry spillway and the left wall between the dam and South Harbor Road appear to be stable. The walls to the right of the spillway are in fair condition. Minor seepage is present at the juncture of the spillway and downstream wall parallel to the crest of the embankment, while portions of the flared downstream wall are displaced. The earth embankment located to the right of the spillway is generally in fair condition, with no visual evidence of major erosion or seepage.

The following specific items were noted:

1. Quarry stone debris just downstream of the spillway on the left side appears to be apron stone which may have been broken or dislodged from the apron and moved downstream. It appears that some of the pieces from the apron have been used as protection for the right wing wall of the South Harbor Road bridge.
2. Much of the right embankment surface is mowed lawn, but there is considerable growth of brush and trees on the downstream face and near the spillway. Leaves and branches have been dumped on part of the downstream face.
3. There is local slight erosion of the right embankment at the end of the short downstream masonry wall.
4. There is slight water flow through joints, as shown in Photo 12, in the right downstream masonry wall which is parallel to the embankment crest.
5. The crest of the right dam embankment is irregular, and is slightly low immediately behind the masonry wall at the spillway.
6. There is some brush growth in the channel downstream of the spillway.
7. The right downstream flared stone masonry wall has areas of displaced stones.

- c. Appurtenant Structures - The stone-masonry wall just upstream of the millrace entrance at the railroad bridge is in good condition. Heavy brush, however, was observed along both sides. The millrace dike is in poor condition, due to extensive erosion and other deficiencies. The upstream millrace control structure was in good condition, but the stop-log guides were in poor condition. No stop logs were observed. The millrace downstream of South Harbor Road and the downstream control structure are of concrete and are in good condition. Submerged stop logs were observed at this structure during the site visit. The overflow spillway on the right side of the millrace is in good condition with minor vegetation at the crest. On the left side of the channel just upstream of the downstream control structure there is evidence of a former continuation of the millrace through the buildings located downstream along the left river bank.

The following additional specific items were noted:

1. The millrace dike has major erosion loss near the corner of the old grist mill and behind about half the length of the upstream stone-masonry wall. The erosion appears to have been at least partly the result of overtopping.
  2. Part of the millrace dike crest has brush and tree growth, as shown in Photos 7, 8, and 9, while the eroded portions are bare of any vegetation.
  3. There is a large, partly stone-filled, depression immediately below the millrace dike overflow spillway, apparently the result of scour from past spillway flows.
  4. Slight seepage flow is emerging from under the grist mill building next to the downstream river channel. This flow may originate at the other end of the building basement, where there would have been a gated waterway connection to the millrace.
- d. Reservoir Area - The area around Harbor Pond is moderately developed. There appear to be no structures below elevation 270, but there are approximately 35 structures below elevation 280. The side slopes of the pond are generally flat and swampy. There is no apparent potential for significant landslides into the pond which could create waves that might overtop the dam. No conditions were noted which could result in a sudden increase in sediment load in the pond.

The Squannacook River enters Harbor Pond approximately 3,500 feet upstream (west) of the dam. The channel meanders slightly, and its slope varies from 0.05 percent near the pond to 0.13 percent near the center of the Town of Townsend.

- e. Downstream Channel - The Squannacook River downstream of the dam is approximately 85 to 100 feet wide, appears to be unobstructed, and has very little development along its banks. The slope is approximately 0.13 percent. There appear to be two other dams on the Squannacook River before its confluence with the Nashua River, approximately 7 miles downstream.

### 3.2 Evaluation

The masonry spillway, side embankments and appurtenances appear to be performing satisfactorily at the present time. The seepage observed at the right masonry wing wall adjacent to the spillway, however, could cause future problems if allowed to continue. Furthermore, the limited millrace dike freeboard and partially-unprotected dike embankment appear to provide potential for failure under conditions of water levels which overtop the embankments.

#### SECTION 4: OPERATIONAL PROCEDURES

- 4.1 Procedures - There is no formal procedure for operation of the dam. On an informal basis, the Owner attempts to control flow over the spillway by removing stop logs at the downstream end of the millrace. During extreme low flow, the Owner removes additional stop logs, releasing water impounded by the dam and spillway for his use as process water at a downstream mill.
- 4.2 Maintenance of Dam - There is no established formal maintenance program for this dam. The operator indicated that the dam is inspected twice a year and maintenance is performed on a demand basis.
- 4.3 Maintenance of Operating Facilities - There is no formal procedure for maintenance of operating facilities (millrace control structures).
- 4.4 Description of Any Warning System in Effect - There is no established warning system or emergency preparedness plan in effect for the dam. The operator indicated that the dam is observed during periods of high water.
- 4.5 Evaluation - Formal operational procedures should be established for high-flow conditions at the dam. Formal maintenance programs, warning systems and emergency preparedness plans should also be established. Periodic observation should be made, and the tree and brush growth at the embankments should be brought under control. Maintenance of the dam should be performed at regular intervals.

## SECTION 5: HYDRAULIC/HYDROLOGIC

### 5.1 Evaluation of Features

- a. General - Harbor Pond is formed by the Townsend Harbor Dam on the Squannacook River, which is a tributary of the Nashua River approximately 7 miles downstream of the dam. The surface area of the pond is approximately 44 acres at spillway crest and approximately 197 acres at the top of the dam. The dam impounds approximately 116 acre-feet of water at spillway crest and approximately 273 acre-feet at the top of the dam.

The stone masonry spillway, at crest elevation 267.3, is 92.2 feet long. The low point of the right embankment of the dam is at elevation 270. The left embankment, at elevation 270.1, extends 57 feet from the dam to the railroad bridge at the entrance to the millrace. The millrace entrance consists of a box culvert 16.3 feet wide, 6.6 feet high and 11.5 feet long, with an invert elevation of 263.1.

There are several means of discharge from the millrace, depending on the water surface elevation. The invert of the normal discharge opening, 3.9 feet wide and 6.1 feet high, is 263.1. However, the 3.3 feet of stop logs normally maintained in this opening sets the normal operating weir at 266.4. The overflow spillway upstream of the normal discharge opening is at elevation 268.1 and is 18 feet long. The walls on both sides of the overflow spillway form an additional 44.4 feet of weir at elevation 269.2. The top of the wall above the normal discharge opening forms an additional 15-foot weir at elevation 270.2. The side wall of the remainder of the millrace, upstream of South Harbor Road, is at elevation 272.1.

- b. Design Data - No hydraulic/hydrologic design data are available for the dam.
- c. Experience Data - A newspaper report indicates that the dam and South Harbor Road bridge were "washed out" during the 1936 flood and were rebuilt in 1937. The report further states that the dam was repaired after the 1938 hurricane.

USGS Gaging Station 01096000 has recorded Squannacook River flows approximately 2 miles downstream of the dam since October 1949. The drainage area tributary to the gage is 62.8 square miles, which is only 4.6 square miles more than that tributary to the dam site. Flows recorded at the gage, therefore, should be only slightly greater than flows at the dam site. Some of the larger flows recorded at the gage have been: 4,010 cfs (October 16, 1955); 2,760 cfs (March 14, 1977); 2,340 cfs (April 2, 1962); and 2,260 cfs (March 19, 1968).

- d. Visual Observations - The pond level was at spillway crest at the time of inspection. The millrace and downstream channel appeared to be in good hydraulic condition, with the exception of some vegetation in the river bed.

- e. Test Flood Analysis - Based on the Corps of Engineers guidelines, the recommended test flood for the size (small) and hazard potential (significant) is between the 100-year flood and one-half of the Probable Maximum Flood (PMF). The 1/4 PMF was adopted as the test flood and was determined using Corps of Engineers guidelines for "Estimating Maximum Probable Discharge" in Phase I Dam Safety Investigations. The watershed terrain is characterized as rolling, and a PMF inflow rate of 1,100 cubic feet per second (cfs) per square mile was adopted for the 58.3-square-mile drainage area. The resulting test-flood inflow is 16,000 cfs.

Initial surcharge-storage routing of the test-flood inflow through Harbor Pond resulted in a peak test-flood outflow of 14,840 cfs at a surcharge pond stage of 275.9 feet above NGVD. Stage discharge relationships, presented in Appendix D, include the discharge capacity of the millrace. Due to the indicated tailwater elevation of 275.7, further analysis was performed to account for submergence. The subsequent surcharge-storage routing resulted in a peak test-flood outflow of 14,610 cfs at a surcharge pond stage of 277.5 feet above NGVD. At this stage, which is 10.2 feet above the spillway crest, the dam will be overtopped by 7.5 feet. The spillway capacity at test flood is approximately 6,320 cfs, and the tailwater elevation is approximately 275.0.

- f. Dam Failure Analysis - Dam failure analysis was performed in order to assess the downstream hazards in the event of dam failure. A peak failure outflow of approximately 3,130 cfs was estimated based on a breach width of approximately 37 feet and with the pond at the top of the dam (270.0 feet above NGVD), which is 2.7 feet above the spillway crest. Water flowing 2.7 feet deep over the spillway is equivalent to a flow of 1,430 cfs. Such a wet-weather flow would produce flooding conditions downstream prior to dam failure. While this flooding would not be expected to endanger lives downstream, it is estimated that the sudden release of an additional 1,700 cfs in a dam failure would severely damage the building on the left bank just downstream of the South Harbor Road bridge with potential loss of a few lives. Approximately 1.6 miles downstream, a building on Trout Brook in the right flood plain of the Squannacook River would also be flooded by the dam-failure flow. Accordingly, Townsend Harbor Dam is classified as having a "significant" hazard potential.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

- a. Visual Observation - There was no visible evidence of spillway or dam embankment instability during the site examination of 15 November 1978. The observed locations of slight seepage at the right end of the spillway and under the old grist mill building showed no evidence of soil movement, and are not considered to pose an immediate hazard to the stability of the downstream faces of the embankments.
- b. Design and Construction - There are neither design drawings nor construction data which would show the embankment cross sections or the physical properties of the materials in the embankments. Thus, theoretical analyses of the structural stability of the dam embankments are not possible.

The embankments have had a long period of service, and, in the absence of seepage or erosion problems, would be expected to be adequately stable under static loading conditions.

- c. Operating Records - No operating records, other than state and county inspection reports, were located.
- d. Post-Construction Changes - The dam was constructed in 1870 (the date inscribed on the face of the spillway) to provide additional power for the Spaulding Leatherboard Company. The presence of a concrete millrace, concrete control structures and grouted stone-masonry walls upstream of the spillway further indicate that post-construction changes have been made to the dam.
- e. Seismic Stability - The dam is located in seismic zone No. 2 and, in accordance with recommended Phase I Guidelines, does not warrant seismic analysis.

## SECTION 7: ASSESSMENTS, RECOMMENDATIONS AND REMEDIAL MEASURES

### 7.1 Dam Assessment

- a. Condition - The visual examination of the Townsend Harbor Dam and dike embankments did not reveal any evidence of failure or conditions which would warrant urgent remedial treatment. However, because of the need for maintenance and additional investigations that are outlined hereinafter and the limited capacity of the spillway, the project is considered to be in only fair condition.
- b. Adequacy of Information - All of the information for the Phase I Investigation had to be obtained from visual examination and limited measurements at the site. This information has been sufficient for the purpose of this investigation, but it does not permit detailed evaluation of stability or seepage.
- c. Urgency - The recommended additional investigations and remedial measures outlined in Sections 7.2 and 7.3, respectively, should be undertaken within one year of receipt of the report by the Owner.
- d. Need for Additional Investigations - Additional investigations should be performed by the Owner as outlined in the following section.

### 7.2 Recommendations - It is recommended that the Owner engage a registered professional engineer to perform the following additional investigations:

1. A detailed hydrologic-hydraulic investigation to determine the adequacy of the spillway and any necessary modifications to the facility to provide adequate capacity, taking into account the surmergence of the dam.
2. An investigation of the millrace geometry, controls and operation to determine a practicable means of protection against overtopping and subsequent erosion damage to the millrace dike.
3. An investigation of the seepage that is emerging from under the old grist mill building and at the masonry wall to the right of the spillway, to determine what corrective or control measures may be necessary.

### 7.3 Remedial Measures

- a. Operation and Maintenance Procedures - It is recommended that the following remedial work be undertaken by the Owner, in addition to the investigations outlined in Section 7.2, to correct deficiencies noted during the visual examination:
  - (1) Clear brush, trees and debris from the dam and dike embankments including stump removal and backfilling, and cut grass

and weeds on the embankments at least once a year. Clearing of the gradual slope below the millrace dike downstream wall is not necessary beyond 10 ft. from the wall.

- (2) Restore displaced apron stones at the downstream face of the spillway.
- (3) Fill area of local erosion in the right embankment at the end of the short downstream masonry wall and bring crest of embankment behind the wall to grade.
- (4) Reset displaced stones in right downstream flared stone masonry wall.
- (5) Restore low and eroded areas in the millrace dike embankment and re-establish vegetative cover. Work on the millrace dike would be subject to the results of the millrace investigation under Section 7.2.
- (6) Clear brush from channel immediately downstream of spillway.
- (7) Place additional stone protection or dumped riprap in depression at discharge end of millrace overflow spillway.
- (8) Establish a formal maintenance program, operational procedures and emergency preparedness plan and warning system.

The Owner should continue his program of technical inspections. These inspections should be made at least at yearly intervals.

7.4 Alternatives - There are no practical alternatives recommended.

APPENDIX A  
INSPECTION TEAM ORGANIZATION AND CHECK LIST

|                                                | <u>Page No.</u> |
|------------------------------------------------|-----------------|
| <u>VISUAL INSPECTION PARTY ORGANIZATION</u>    | A-1             |
| <u>VISUAL INSPECTION CHECK LIST</u>            |                 |
| Embankment: Right of Spillway                  | A-2             |
| Embankment: Dike between Millrace and Spillway | A-3             |
| Spillway                                       | A-4             |
| Spillway (cont'd)                              | A-5             |
| Outlet Works                                   | A-6             |

VISUAL INSPECTION PARTY ORGANIZATION  
NATIONAL DAM INSPECTION PROGRAM

DAM: Townsend Harbor

DATE: 15 November, 1978

TIME: 3:30 PM

WEATHER: Clear and cool-- 40 to 45 F..

WATER SURFACE ELEVATION UPSTREAM: 267.3 (at spillway crest)

STREAM FLOW:  $(3.33)(3.9')(0.75')^{3/2} = 8.4 \text{ cfs}$

INSPECTION PARTY:

1. Robert P. Howard - Structural & Operation
2. Charles E. Fuller - Hydraulics & Hydrology
3. Joseph E. Downing - Ass't. Hydraulics & Hydrology
4. A. Ulvi Gulbey - Ass't. Hydraulics & Hydrology
5. Peter L. LeCount (H & A) - Soils
6. \_\_\_\_\_

PRESENT DURING INSPECTION:

1. A. E. Irelan - Project Engineer, Hollingsworth & Vose Co.
2. \_\_\_\_\_
3. \_\_\_\_\_
4. \_\_\_\_\_

VISUAL INSPECTION CHECK LIST  
NATIONAL DAM INSPECTION PROGRAM

DAM: Townsend Harbor

DATE: 11/15/78

EMBANKMENT: (Rt. of Spillway)

| CHECK LIST                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | CONDITION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <ol style="list-style-type: none"> <li>1. Upstream Slope               <ol style="list-style-type: none"> <li>a. Vegetation</li> <li>b. Sloughing or Erosion</li> <li>c. Rock Slope Protection - Riprap Failures</li> <li>d. Animal Burrows</li> </ol> </li> <li>2. Crest               <ol style="list-style-type: none"> <li>a. Vegetation</li> <li>b. Sloughing or Erosion</li> <li>c. Surface cracks</li> <li>d. Movement or Settlement</li> </ol> </li> <li>3. Downstream Slope               <ol style="list-style-type: none"> <li>a. Vegetation</li> <li>b. Sloughing or Erosion</li> <li>c. Surface cracks</li> <li>d. Animal Burrows</li> <li>e. Movement or Cracking near toe</li> <li>f. Unusual Embankment or Downstream Seepage</li> <li>g. Piping or Boils</li> <li>h. Foundation Drainage Features</li> <li>i. Toe Drains</li> </ol> </li> <li>4. General               <ol style="list-style-type: none"> <li>a. Lateral Movement</li> <li>b. Vertical Alignment</li> <li>c. Horizontal Alignment</li> <li>d. Condition at Abutments and at Structures</li> <li>e. Indications of Movement of Structural Items</li> <li>f. Trespassing</li> <li>g. Instrumentation Systems</li> </ol> </li> </ol> | <ol style="list-style-type: none"> <li>1.               <ol style="list-style-type: none"> <li>a. Grass (lawn)</li> <li>b. None evident</li> <li>c. None</li> <li>d. None observed</li> </ol> </li> <li>2.               <ol style="list-style-type: none"> <li>a. Grass, scattered brush, tree, two stumps.</li> <li>b. Grass intact, but irregular shape</li> <li>c. None evident</li> <li>d. Not evident-irregular shape</li> </ol> </li> <li>3.               <ol style="list-style-type: none"> <li>a. Mostly brush &amp; trees, some dumped leaves, branches, etc.</li> <li>b. Irregular shape, local slight eros. from runoff at end of masonry wingwall.</li> <li>c. None evident</li> <li>d. None evident</li> <li>e. None evident</li> <li>f. Slight flow thru masonry wall joints close to spillway.</li> <li>g. None evident</li> <li>h. None evident</li> <li>i. None</li> </ol> </li> <li>4.               <ol style="list-style-type: none"> <li>a., b., c. Irregular shape w/o defined alignment or indication of movement.</li> <li>d. Embank. sl. low immed. behind masonry wall, but no indication of recent movement.</li> <li>e. None evident</li> <li>f. None evident</li> <li>g. None</li> </ol> </li> </ol> |

VISUAL INSPECTION CHECK LIST  
NATIONAL DAM INSPECTION PROGRAM

DAM: Townsend Harbor

DATE: 11/15/78

EMBANKMENT: Dike between Millrace and Spillway

| CHECK LIST                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | CONDITION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <ol style="list-style-type: none"> <li>1. Upstream Slope               <ol style="list-style-type: none"> <li>a. Vegetation</li> <li>b. Sloughing or Erosion</li> <li>c. Rock Slope Protection - Riprap Failures</li> <li>d. Animal Burrows</li> </ol> </li> <li>2. Crest               <ol style="list-style-type: none"> <li>a. Vegetation</li> <li>b. Sloughing or Erosion</li> <li>c. Surface cracks</li> <li>d. Movement or Settlement</li> </ol> </li> <li>3. Downstream Slope               <ol style="list-style-type: none"> <li>a. Vegetation</li> <li>b. Sloughing or Erosion</li> <li>c. Surface cracks</li> <li>d. Animal Burrows</li> <li>e. Movement or Cracking near toe</li> <li>f. Unusual Embankment or Downstream Seepage</li> <li>g. Piping or Boils</li> <li>h. Foundation Drainage Features</li> <li>i. Toe Drains</li> </ol> </li> <li>4. General               <ol style="list-style-type: none"> <li>a. Lateral Movement</li> <li>b. Vertical Alignment</li> <li>c. Horizontal Alignment</li> <li>d. Condition at Abutments and at Structures</li> <li>e. Indications of Movement of Structural Items</li> <li>f. Respassing</li> <li>g. Instrumentation Systems</li> </ol> </li> </ol> | <ol style="list-style-type: none"> <li>1.               <ol style="list-style-type: none"> <li>a., b., c., d. N.A.-Concrete canal wall</li> </ol> </li> <li>2.               <ol style="list-style-type: none"> <li>a. Grass &amp; weeds, few trees.</li> <li>b. Erosion behind downstream end of canal wall-apparently has been overtopped</li> <li>d. Only in concrete canal overflow spillway slab.</li> </ol> </li> <li>3.               <ol style="list-style-type: none"> <li>a. Some grass, weeds, brush &amp; trees - mostly stone masonry wall or bare earth.</li> <li>b. Erosion due to surface runoff at corner of bldg., possibly due to overtopping.</li> <li>c. Not evident</li> <li>d. None observed</li> <li>e. None observed</li> <li>f. Ponded seepage in rear of old building - formerly for canal.</li> <li>g. None observed</li> <li>h. None observed</li> <li>i. None</li> </ol> </li> <li>4.               <ol style="list-style-type: none"> <li>a. Not evident</li> <li>b., c. Irregular shape</li> <li>d. Local erosion from overtopping.</li> <li>e. Slight settlement toward end of overflow spillway slab.</li> <li>f. Scattered trash &amp; cans</li> <li>g. None</li> </ol> </li> </ol> |

VISUAL INSPECTION CHECK LIST  
NATIONAL DAM INSPECTION PROGRAM

DAM: Townsend Harbor

DATE: 11/15/78

EMBANKMENT: Dike between Millrace and Spillway

| CHECK LIST                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | CONDITION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1. Upstream Slope<br>a. Vegetation<br>b. Sloughing or Erosion<br>c. Rock Slope Protection -<br>Riprap Failures<br>d. Animal Burrows<br>2. Crest<br>a. Vegetation<br>b. Sloughing or Erosion<br>c. Surface cracks<br>d. Movement or Settlement<br>3. Downstream Slope<br>a. Vegetation<br>b. Sloughing or Erosion<br>c. Surface cracks<br>d. Animal Burrows<br>e. Movement or Cracking near<br>toe<br>f. Unusual Embankment or<br>Downstream Seepage<br>g. Piping or Boils<br>h. Foundation Drainage Features<br>i. Toe Drains<br>4. General<br>a. Lateral Movement<br>b. Vertical Alignment<br>c. Horizontal Alignment<br>d. Condition at Abutments and<br>at Structures<br>e. Indications of Movement of<br>Structural Items<br>f. Trespassing<br>g. Instrumentation Systems | 1.<br>a., b., c., d. N.A.-Concrete canal wall<br>2.<br>a. Grass & weeds, few trees.<br>b. Erosion behind downstream end of<br>canal wall-apparently has been<br>overtopped<br>d. Only in concrete canal overflow<br>spillway slab.<br>3.<br>a. Some grass, weeds, brush & trees -<br>mostly stone masonry wall or bare<br>earth.<br>b. Erosion due to surface runoff at<br>corner of bldg., possibly due to<br>overtopping.<br>c. Not evident<br>d. None observed<br>e. None observed<br>f. Ponded seepage in rear of old<br>building - formerly fed by<br>canal.<br>g. None observed<br>h. None observed<br>i. None<br>4.<br>a. Not evident<br>b., c. Irregular shape<br>d. Local erosion from overtopping.<br>e. Slight settlement toward end of<br>overflow spillway slab.<br>f. Scattered trash & cans<br>g. None |

VISUAL INSPECTION CHECK LIST  
NATIONAL DAM INSPECTION PROGRAM

DAM: TOWNSEND HARBOR

DATE: 15 NOVEMBER 1978

SPILLWAY: \_\_\_\_\_

| CHECK LIST                                                                                                                                                                                                                                                       | CONDITION                                                                                                                                                                                                                                                                                                                                                                                                |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1. Approach Channel<br>a. General Condition<br>b. Obstructions<br>c. Log Boom etc.                                                                                                                                                                               | 1.<br>a. Good.<br>b. None.<br>c. None.                                                                                                                                                                                                                                                                                                                                                                   |
| 2. Weir<br>a. Flashboards<br>b. Weir Elev. Control (Gate)<br>c. Vegetation<br>d. Seepage or Efflorescence<br>e. Rust or Stains<br>f. Cracks<br>g. Condition of Joints<br>h. Spalls, Voids or Erosion<br>i. Visible Reinforcement<br>j. General Struct. Condition | 2.<br>a. None.<br>b. N/A see Outlet Works.<br>c. Minor growth in joints of cut quarry stone face.<br>d. None observed.<br>e. None observed.<br>f. None observed.<br>g. Wall is ungrouted cut quarry stone, one stone has an 1870 date inscribed.<br>h. N/A.<br>i. N/A.<br>j. Good.                                                                                                                       |
| 3. Discharge Channel<br>a. Apron<br>b. Stilling Basin<br>c. Channel Floor<br>d. Vegetation<br>e. Seepage<br>f. Obstructions<br>g. General Struct. Condition                                                                                                      | 3.<br>a. Two courses of cut quarry stone slabs near face of dam stepping down to one course. These quarry stones appear to have been broken and washed downstream. Some pieces have been used as protection of bridge wing wall.<br>b. N/A.<br>c. Earth.<br>d. Heavy brush growth in channel downstream.<br>e. None observed.<br>f. Quarry stone debris left side appears to be apron stone.<br>g. Good. |
| 4. Walls<br>a. Wall Location <u>Lt. &amp; Rt.</u><br>(1) Vegetation<br>(2) Seepage or Efflorescence<br>(3) Rust or Stains<br>(4) Cracks<br>(5) Condition of Joints<br>(6) Spalls, Voids or Erosion<br>(7) Visible Reinforcement<br>(8) General Struct. Condition | 4.<br>a. (1) None observed.<br>(2) Seepage at base of rt. wall that runs parallel with spillway.<br>(3) None observed.<br>(4) None observed.<br>(5) Grouted cut stone block walls upstream of spillway need re-grouting. Downstream walls are ungrouted cut stone block walls. Conditions of joints are good.<br>(6) None observed.                                                                      |

VISUAL INSPECTION CHECK LIST  
NATIONAL DAM INSPECTION PROGRAM

DAM: TOWNSEND HARBOR

DATE: 15 NOVEMBER 1978

SPILLWAY: (cont'd)

CHECK LIST

CONDITION

4. (7) N/A.  
(8) Good except rt. wall downstream  
of spillway is in poor condition.

VISUAL INSPECTION CHECK LIST  
NATIONAL DAM INSPECTION PROGRAM

DAM: TOWNSEND HARBOR

DATE: 15 NOVEMBER 1978

OUTLET WORKS: MILLRACE

| CHECK LIST                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | CONDITION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <ol style="list-style-type: none"> <li>1. Inlet               <ol style="list-style-type: none"> <li>a. Obstructions</li> <li>b. Channel</li> <li>c. Structure</li> <li>d. Screens</li> <li>e. Stop Logs</li> <li>f. Gates</li> </ol> </li> <li>2. Control Facility               <ol style="list-style-type: none"> <li>a. Structure</li> <li>b. Screens</li> <li>c. Stop Logs</li> <li>d. Gates</li> <li>e. Conduit</li> <li>f. Seepage or Leaks</li> </ol> </li> <li>3. Outlet               <ol style="list-style-type: none"> <li>a. Structure</li> <li>b. Erosion or Cavitation</li> <li>c. Obstructions</li> <li>d. Seepage or Leaks</li> </ol> </li> <li>4. Mechanical and Electrical               <ol style="list-style-type: none"> <li>a. Crane Hoist</li> <li>b. Hydraulic System</li> <li>c. Service Power</li> <li>d. Emergency Power</li> <li>e. Lighting</li> <li>f. Lightning Protection</li> </ol> </li> <li>5. Others</li> </ol> | <ol style="list-style-type: none"> <li>1.               <ol style="list-style-type: none"> <li>a. None.</li> <li>b. Submerged.</li> <li>c. Railroad bridge abutments show repairs and modifications. Upstream edge of concrete seat on rt. abutment is badly cracked and separating from abutment.</li> <li>d. None.</li> <li>e. None.</li> <li>f. None.</li> </ol> </li> <li>2.               <ol style="list-style-type: none"> <li>a. Upstream Control Facility                   <ol style="list-style-type: none"> <li>a. Good condition.</li> <li>b. None.</li> <li>c. Submerged, guides in poor condition.</li> <li>d. None.</li> <li>e. None.</li> <li>f. N/A.</li> </ol> </li> </ol> </li> <li>2.               <ol style="list-style-type: none"> <li>b. Downstream Control Facility                   <ol style="list-style-type: none"> <li>a. Good condition, some minor erosion of concrete.</li> <li>b. None.</li> <li>c. Submerged.</li> <li>d. None.</li> <li>e. None.</li> <li>f. None observed.</li> </ol> </li> </ol> </li> <li>3.               <ol style="list-style-type: none"> <li>a. Good condition.</li> <li>b. None observed.</li> <li>c. None observed.</li> <li>d. None observed.</li> </ol> </li> <li>4. N/A.</li> <li>5. Spillway on right side of channel in good condition with some minor growth. Spillway on left side of channel has been abandoned.</li> </ol> |

APPENDIX B

LIST OF AVAILABLE DOCUMENTS AND  
PRIOR INSPECTION REPORTS

Page No.

LIST OF AVAILABLE DOCUMENTS

B-1

PRIOR INSPECTION REPORTS

DATE

BY

July 18, 1961

Middlesex County Engineering  
Department

B-2 to B-10

September 6, 1973

Mass. Dept. of Public Works,  
includes Description of Dam

B-11 to B-16

DRAWINGS

Plan and Sections of Townsend Harbor Dam and  
Millrace

B-17

LIST OF AVAILABLE DOCUMENTS

Survey plan No. 3048, at 1" = 40 ft. scale, prepared for Hollingsworth & Vose Company by Charles A. Perkins Co., Engineers & Surveyors, Littleton, Mass., November 1961.

TOWN Townsend, Mass DAM NO. E-1  
LOCATION Int. Main St. & Harbor Rd. STREAM Squannacook River

MIDDLESEX COUNTY ENGINEERING DEPARTMENT  
CAMBRIDGE, MASSACHUSETTS

D A M I N S P E C T I O N R E P O R T

Owned by Mr. Aksila Place Townsend Harbor, Mass. Use None at Present  
Inspected by Richard D. Howard Date 7-18-61  
Type of Dam Stone Overflow Condition Good

SPILLWAY Length 92' Ht. to Top Emb. Section 4.5'  
Flashboards in Place None Ht. of          Recent Repairs None  
Condition Excellent  
Repairs Needed None

EMBANKMENT Length None Height          Type           
Recent Repairs           
Condition           
Repairs Needed         

GATES Number 2 (In Canal) Size 5'-6" x 5'-5" Types Stop log  
Recent Repairs None  
Condition Not operating -- remain open  
Repairs Needed None

LEAKS Detailed Description and Location on Back of Sheet  
How Serious         

DATE: 7-18-61 Richard D. Howard  
Signature Inspecting Engineer

Rec. Action - See Back of Sheet Engineer, Metcalf & Eddy  
Title

Special Remarks and Characteristics on Back of Sheet

LEAKS: None

RECOMMENDED ACTION: None

SPECIAL REMARKS: None

METCALF & EDDY  
ENGINEERS  
BOSTON MASS

E-1

J-Mec Dams  
GET/cv  
8/31/61

REPORT  
UPON  
TOWNSEND HARBOR DAM  
TOWNSEND HARBOR, MASSACHUSETTS

General

The Townsend Harbor Dam across the Squannacook River is located at Townsend Harbor about 200 feet southwest of the intersection of Main Street and Harbor Road. The dam is an over-flow type structure of stone masonry construction. The dam is not used for any purpose. A canal, about 100 feet from the left abutment of the dam, runs parallel to the river. The entrance to the canal is just upstream from the left dam abutment. A Boston and Maine Railroad track runs parallel to the canal about 70 feet from the left end of the dam.

The spillway is about 6.2 feet high and 92 feet long. The depth of the spillway at the crest is 4.5 feet. Due to the elevation of the top of the left upstream abutment wall being 1.7 feet lower, the effective depth at the spillway crest is 2.8 feet. The structure is a triangular crested type with the upstream face sloping downward and upstream at the rate of 0.09 feet to the foot. The downstream face is vertical.

The abutment walls are of stone masonry, 2 feet thick. The left abutment wall forms a right angle about 20 feet upstream from the dam, runs parallel to the intake of the canal and connects to an abutment of a railroad bridge over the canal intake.

FORM 121

The right abutment is U shaped. Training walls lead downstream from the abutments.

A frame building, named "The Cooperage" and used as a gift shop, is located about 12 feet downstream from the dam on the left bank. The structure extends over the stream from the top of the training wall for a distance of about 9 feet.

Conclusions and Recommendations.

1. The present spillway capacity of the dam is about one-seventh the Rare Flood Flow as determined by the Kinnison-Colby Formula.
2. The dam may be protected by the following method:
  - a. Raise the tops of all abutment walls at and upstream from the dam to El. 272.1.
  - b. Extend the right abutment to meet the ground at El. 272.1.
  - c. Protect the abutments with stone riprap.

Spillway Capacity and Flood Flows

The capacity of the 92 ft. long spillway is estimated to be 1290 c.f.s. without provision for freeboard. The canal can divert a flow of about 130 c.f.s. making a total of 1420 c.f.s. The tributary drainage area is 60.6 square miles. The maximum flood flow as estimated from the Kinnison-Colby Formula (Rare Floods) is about 9000 c.f.s. This rate of flow is about 7 times the discharge capacity of the spillway and about 6-1/2 times the combined discharge capacities of the spillway and canal.

It is possible that during a flood, the waterways between the trestlebeds of the railroad bridge over the entrance to the canal would become blocked with debris so that diversion of water by the canal would become negligible.

In order for the spillway to discharge the entire estimated rare flood flow of 9000 c.f.s., the head on the spillway crest would have to be increased to 10.4 feet. Due to the location and grade of the railroad trestle bridge there appears to be no practical way to accomplish this by raising the height of the walls on the left abutment. The right abutment wall would have to be increased 5.9 feet in height and extended to Harbor Road.

If the tops of all the abutment walls were raised to El. 272.1, or the elevation of the top of the railroad bridge abutments, the capacity of the spillway could be increased to about 2900 c.f.s. or about 2-1/4 times the present capacity. The right abutment walls could either be extended into the hillside slope or a short earth embankment could be constructed in place of the wall extension.

#### Stability and Repairs

The stability of the structure is adequate. The condition of the dam is good.

In order to obtain a substantial increase in spillway capacity, the tops of all abutment walls upstream from the dam should be raised to El. 272.1. These walls would be raised 0.3 feet except the upstream left abutment wall which would be raised 2.0 feet. On the right abutment the raised wall should

either be extended a few feet into the hillside slope or connected to the slope with an earth dike. The abutments on both sides of the dam should be protected with stone riprap. On the left abutment this stone protection may be in the form of stone paving on the ground behind the walls for a distance of at least 10 feet from the backface of the wall. On the right abutment the junction of the ground with the end of the extended wall together with the ground on the downstream face of the wall should be protected with dumped stone riprap. If a connecting earth dike is used, it should be completely covered with stone.

By: Gordon E. Thomas  
Gordon E. Thomas  
Project Engineer

*TOWNSEND HARBOR DAM E-1 TOWNSEND HARBOR, MASS.*

*PICTURES TAKEN JULY 18, 1961*



*STOPLOG GATES IN BY-PASS CHANNEL*




*HIGHWAY BRIDGE DOWNSTREAM*

*TOWNSEND HARBOR DAM E-1 (CONTINUED)*



*RAILROAD BRIDGE AND NORTH UPSTREAM ABUTMENT*



*RAILROAD BRIDGE AND POND BEYOND*

*TOWNSEND HARBOR DAM E-1 (CONTINUED)*



*SPILLWAY*

OF  
FILE 821

INSPECTION REPORT - DAMS AND RESERVOIRS

(1.) Location: ~~City/Town~~ TOWNSEND

Dam No. 4-9-299-1

Name of Dam TOWNSEND HARBOR DAM

Inspected by A. Z. PIZAN

F. H. PARE  
Date of Inspection 9-6-'73

| (2) Owners:                            | per:                   | Assessors           | Prev. Inspection | Reg. of Deeds   | Pers. Contact |
|----------------------------------------|------------------------|---------------------|------------------|-----------------|---------------|
| 1. <u>HOLLINGSWORTH &amp; VASE CO.</u> | <u>TOWNSEND ST. W.</u> | <u>GROTON MASS.</u> | <u>01450</u>     | <u>448-3311</u> |               |
| Name                                   | St. & No.              | City/Town           | State            | Tel. No.        |               |
| 2. _____                               | _____                  | _____               | _____            | _____           | _____         |
| Name                                   | St. & No.              | City/Town           | State            | Tel. No.        |               |
| 3. _____                               | _____                  | _____               | _____            | _____           | _____         |
| Name                                   | St. & No.              | City/Town           | State            | Tel. No.        |               |

(3) Caretaker: (if any) e.g. superintendent, plant manager, appointed by absentee owner, appointed by multi owners.

SAME  
Name \_\_\_\_\_ St. & No. \_\_\_\_\_ City/Town \_\_\_\_\_ State \_\_\_\_\_ Tel. No. \_\_\_\_\_

(4) No. of Pictures taken 2

(5) Degree of Hazard: (if dam should fail completely)\*

1. Minor \_\_\_\_\_ 2. Moderate ✓  
3. Severe \_\_\_\_\_ 4. Disastrous \_\_\_\_\_

\*This rating may change as land use changes (future development)

(6) Outlet Control: Automatic \_\_\_\_\_ Manual ✓  
Operative ✓ yes: \_\_\_\_\_ no: \_\_\_\_\_

Comments: FLASHBOARDS IN EMERGENCY SPILLWAY CONTROL

FLOW OF WATER OVER PRINCIPAL SPILLWAY.

(7) Upstream Face of Dam: Condition:

1. Good ✓ 2. Minor Repairs \_\_\_\_\_  
3. Major Repairs \_\_\_\_\_ 4. Urgent Repairs \_\_\_\_\_

Comments: \_\_\_\_\_

2-  
3) Downstream Face of Dam: Condition: 1. Good ☒ 2. Minor Repairs 2  
3. Major Repairs 0 4. Urgent Repairs 0

Comments: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

9) Emergency Spillway: Condition: 1. Good ☒ 2. Minor Repairs 0  
3. Major Repairs 0 4. Urgent Repairs 0

Comments: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

3) Water level @ time of inspection 0.5' above 0.5' below  
top of dam 0 Principal spillway 1  
other 0

11) Summary of Deficiencies Noted:

Growth (Trees and Brush) on Embankment ☒  
Animal Burrows and Washouts \_\_\_\_\_  
Damage to slopes or top of dam \_\_\_\_\_  
Cracked or Damaged Masonry \_\_\_\_\_  
Evidence of Seepage \_\_\_\_\_  
Evidence of Piping \_\_\_\_\_  
Erosion \_\_\_\_\_  
Leaks \_\_\_\_\_  
Trash and/or debris impeding flow \_\_\_\_\_  
Clogged or blocked spillway \_\_\_\_\_  
Other \_\_\_\_\_

4-9-299-1

-3-

(12) Remarks & Recommendations: (Fully Explain)

DAM IS IN GOOD CONDITION.

(13) Overall Condition:

1. Safe ☒
  2. Minor repairs needed ☐
  3. Conditionally safe - major repairs needed ☐
  4. Unsafe ☐
  5. Reservoir impounded no longer within design ☐
- Recommend removal from service ☐

DESCRIPTION OF DAM  
DISTRICT #4

Submitted by FRANCIS H. PARE & ADAM Z PIZAN  
Date 9-6-75

Dam No. 4-9-299-1  
City/Town TOWNSEND, 01469  
Name of Dam TOWNSEND HARBOUR  
DAM

1. Location: Topo Sheet No. 22A  
Provide 8 1/2" x 11" in clear copy of topo map with location of Dam clearly indicated.
2. Year built: UNKNOWN Year/s of subsequent repairs NONE VISIBLE
3. Purpose of Dam: Water Supply \_\_\_\_\_, Recreational ✓  
Irrigation \_\_\_\_\_, Other \_\_\_\_\_
4. Drainage Area: 60.6 SQ. MI. 38,400 ACRES.
5. Approx Ponding Area: 80 acres; Ave Depth 9'  
impoundment: 213 MIL gals: 640 acre ft.
6. No. and type of dwellings located adjacent to pond or reservoir  
i.e. summer homes etc. 3 HOMES ADJ. TO DAM
7. Dimensions of Dam: Length 20' Max. Height 10'  
Slopes: Upstream Face VERT  
Downstream Face "  
Width across top 5'
8. Classifications of Dam by Materials:  
Earth \_\_\_\_\_, Conc. Masonary \_\_\_\_\_, Stone Masonary ✓  
Timber \_\_\_\_\_, Rockfill \_\_\_\_\_, Other \_\_\_\_\_
9. a. Description of present land usage downstream of dam: 80% rural;  
20% urban  
b. Is there a storage area or flood plain downstream of dam: which could  
accommodate the impoundment in the event of a complete dam failure  
no ✓ yes \_\_\_\_\_



DAM NO. 4-9-299-1


10.

Risk to life and property in event of complete failure.

No. of people 21 EST. 3 PER. HOME  
No. of homes 7  
No. of businesses NONE  
No. of industries 11 Type \_\_\_\_\_  
No. of utilities 1 WATER SYSTEM PLANT EMER. SPILLWAY  
Railroads 1 OPERATING RR, PARALLEL TO DAM  
Other dams NONE  
Other \_\_\_\_\_


11.

Attach sketch of dam to this form showing section and plan 8 1/2" X 11" She



X SECTION AA

SKETCH NOT TO SCALE



# TOWNSEND

## DAM NO. E-1

NAME Townsend Harbor Dam

STREAM Squannacook River

LOCATION Townsend Harbor, Mass  
Longitude 71°00'25" Latitude 42°39'09"

DRAINAGE AREA 606 Square Miles

TYPE Stone Masonry Overflow

GENERAL DIMENSIONS Length 92 ft, Height 62 ft

SPILLWAY Capacity 1290 cfs


OUTLET WORKS None

POND AREA 48 Acres


POND CAPACITY 932 Million Gallons

BENCH MARK USGS disc on southeast abutment  
of RR bridge as shown on plan

SECTION A-A  
SCALE VERT 1" = 10'  
HORIZ 1" = 20'




SECTION B-B  
SCALE 1/4" = 1'-0"



SECTION C-C

SCALE 1/4" = 1'-0"



SECTION D-D

APPENDIX C  
SELECTED PHOTOGRAPHS OF PROJECT

LOCATION PLAN

Page No.

Location of Photographs

C-1


PHOTOGRAPHS

No.

Title

Page No.

|     |                                                                            |     |
|-----|----------------------------------------------------------------------------|-----|
| 1.  | Overview of Dam from South Harbor Road Bridge                              | iv  |
| 2.  | View of Dam from Right Downstream Abutment                                 | C-2 |
| 3.  | Keystone in Downstream Face of Dam                                         | C-2 |
| 4.  | View of the "Cooperage" from Downstream Right Bank of Squannacook River    | C-3 |
| 5.  | View of South Harbor Road Bridge and Downstream Channel from Left Abutment | C-3 |
| 6.  | View of Left Abutment and Millrace Inlet with Railroad Crossing            | C-4 |
| 7.  | View of Millrace Control Structure Looking East from South Harbor Road     | C-4 |
| 8.  | Downstream Face of South Harbor Road over Millrace                         | C-5 |
| 9.  | View of Downstream End of Millrace from South Harbor Road                  | C-5 |
| 10. | Downstream Face of Millrace Overflow Spillway                              | C-6 |
| 11. | Downstream Face of Millrace Outlet                                         | C-6 |





2. VIEW OF DAM FROM RIGHT DOWNSTREAM ABUTMENT.



3. KEY STONE IN DOWNSTREAM FACE OF DAM.



4. VIEW OF THE "COOPERAGE" FROM DOWNSTREAM RIGHT BANK OF SQUANNACOOK RIVER.




5. VIEW OF SOUTH HARBOR ROAD BRIDGE AND DOWNSTREAM CHANNEL FROM LEFT ABUTMENT.



6. VIEW OF LEFT ABUTMENT AND MILLRACE INLET WITH  
RAILROAD CROSSING.



7. VIEW OF MILLRACE CONTROL STRUCTURE LOOKING EAST  
FROM SOUTH HARBOR ROAD.



8. DOWNSTREAM FACE OF SOUTH HARBOR ROAD OVER MILLRACE.



9. VIEW OF DOWNSTREAM END OF MILLRACE FROM SOUTH HARBOR ROAD. SECOND RAILROAD CROSSING IS IN FOREGROUND, MILLRACE OUTLET IN THE CENTER AND OVERFLOW SPILLWAY ALONG RIGHT CHANNEL WALL.



10. DOWNSTREAM FACE OF MILLRACE OVERFLOW SPILLWAY.



11. DOWNSTREAM FACE OF MILLRACE OUTLET.



12. SEEPAGE AT BOTTOM OF RIGHT WING WALL ADJACENT  
TO SPILLWAY.

APPENDIX D  
OUTLINE OF DRAINAGE AREA AND  
HYDRAULIC COMPUTATIONS

Page No.


MAPS


|                             |     |
|-----------------------------|-----|
| Drainage Area Map           | D-1 |
| Dam Failure Impact Area Map | D-2 |

COMPUTATIONS

|                                                                                |      |
|--------------------------------------------------------------------------------|------|
| Size Classification, Elevations, Storage Volumes,<br>Dam Failure Analysis      | D-3  |
| Test Flood                                                                     | D-9  |
| Millrace Discharges                                                            | D-10 |
| Stage-Discharge and Stage-Storage-Area Characteristics<br>and Stage-Area Curve | D-13 |
| Stage-Discharge-Storage Curve                                                  | D-14 |
| Surcharge-Storage Routing and Tailwater Analysis<br>For Free-Flow Conditions   | D-15 |
| Surcharge-Storage Routing and Tailwater Analysis<br>For Submerged Conditions   | D-17 |

MATCH LINE





DRAINAGE AREA MAP

APPROX. SCALE: 1" = 5200'




DAM TOWNSEND HARBOR DAM

IDENTIFICATION NO. MA 00138

Location of Dam





DAM TOWNSEND HARBOR DAM

IDENTIFICATION NO. MA 00138



DAM FAILURE IMPACT  
AREA MAP  
USGS QUADRANGLE  
TOWNSEND, MASS. - N.H.

APPROX. SCALE: 1" = 2000'

APPENDIX D-2

CAMP DRESSER & McKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Townsend Harbor Dam

JOB NO 380-S-11  
DATE CHECKED 6-6-79  
CHECKED BY JED

PAGE 1 of 14  
DATE 5/22/79  
COMPUTED BY PFH

### SIZE CLASSIFICATION

Height :      Top of dam      El. 270.0  
                    Toe of dam      El. 259.0  
                                                 11.0

Storage at top of dam :

Dead Storage (below spillway)      116 acre-feet  
Surcharge Storage (to top of dam)      157 acre-feet  
                                                 273 acre-feet

∴ Size Classification is SMALL

### DAM FAILURE ANALYSIS

$$Q_{p1} = \left[ \left( \frac{8}{27} \right) W_b \sqrt{g} Y_o^{3/2} \right] + \left[ 0.6 C L H^{3/2} \right]$$

$$W_b = 37', Y_o = 11', C = 3.5, L = 92.2', H = 2.7'$$

$$Q_{p1} = \left[ \left( \frac{8}{27} \right) (37') (32.2')^{3/2} (11')^{3/2} \right] + \left[ 0.6 (3.5) (92.2') (2.7')^{3/2} \right] = 3,130 \text{ cfs}$$

First downstream reach: From dam to South Harbor Reach

| Elevation | Discharge (cfs) | Storage (ac.-ft) |
|-----------|-----------------|------------------|
| 260       | 0               | 0                |
| 262       | 295             | 1.5              |
| 264       | 905             | 3.0              |
| 266       | 1,730           | 4.4              |
| 268       | 2,715           | 5.9              |
| 270       | 3,850           | 7.4              |

Stage in 1<sup>st</sup> reach when outflow is 3,130 cfs is :

$$268 + \left[ \frac{3,130 - 2,715}{3,850 - 2,715} \right] [270 - 268] = 268.7$$

Storage in 1<sup>st</sup> reach at El. 268.7 is :

$$5.9 + \left[ \frac{268.7 - 268.0}{270.0 - 268.0} \right] [7.4 - 5.9] = 6.4 \text{ ac.-ft} = V_1$$

$$Q_{p2} = Q_{p1} \left( 1 - \frac{V_1}{S} \right) = 3,130 \left( 1 - \frac{6.4}{273} \right) = 3,060 \text{ cfs}$$

Stage in 1<sup>st</sup> reach when outflow is 3,060 cfs is :


$$268 + \left[ \frac{3,060 - 2,715}{3,850 - 2,715} \right] [270 - 268] = 268.6$$

CAMP DRESSER & MOORE INC.

CLIENT COE  
PROJECT Dam Inspections  
DETAIL Townsend Harbor Dam

JOB NO 380-5-11  
DATE CHECKED 6-6-79  
CHECKED BY PFH

PAGE 1a.1  
DATE 6-6-79  
COMPUTED BY JE



Location Cross Sections defining downstream reaches for the dam failure analysis

|             |                                                          |
|-------------|----------------------------------------------------------|
| REACH No. 1 | Dam to South Harbor Rd. Bridge                           |
| REACH No. 2 | South Harbor Rd. Bridge to Millrace Outlet (X-Section 5) |
| REACH No. 3 | Millrace Outlet (X-Section 5) to X-Section 4             |
| REACH No. 4 | X-Section 4 to X-Section 3                               |
| REACH No. 5 | X-Section 3 to X-Section 2                               |
| REACH No. 6 | X-Section 2 to USGS Gage No. 30270 (X-Section 1)         |

CAMP DRESSER & MCKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Townsend Harbor Dam

JOB NO 380-5-11  
DATE CHECKED 6-6-79  
CHECKED BY JED

PAGE 2 of 14  
DATE 5/22/79  
COMPUTED BY PEH

Storage in 1<sup>st</sup> reach at El. 268.6 is:

$$5.9 + \frac{[268.6 - 268.0]}{[270.0 - 268.0]} [7.4 - 5.9] = 6.4 \text{ ac-ft} = V_2$$

$$V_3 = \frac{V_1 + V_2}{2} = 6.4 \text{ ac-ft.}$$

$$Q_{P3} = Q_{P2} = 3,060 \text{ cfs} = \text{Outflow from 1<sup>st</sup> reach}$$

Stage in 1<sup>st</sup> reach when outflow is 3,060 cfs is 268.6.  
No buildings in the 1<sup>st</sup> reach would be affected by the dam-failure flood, but a building on the left bank just downstream of the bridge would be severely damaged and its occupants could be killed.

Second downstream reach: From South Harbor Rd. to Millrace Outlet

Discharge from millrace at dam failure (El. 270):

$$Q = [C_1 A_1 \sqrt{2g H_1}] + [C_2 L_2 H_2^{3/2}] + [C_3 L_3 H_3^{3/2}]$$

$$\text{Outlet orifice: } C_1 = \left[ 1 + 0.4 R^{0.3} + \frac{0.0045 L}{R^{1.15}} \right]^{-1/2}$$

$$C_1 = \left[ 1 + (0.4) \left( \frac{3.9' \times 2.8'}{(2)(3.9' + 2.8')} \right)^{0.3} + \left( \frac{0.0045 \times 2'}{0.82^{1.15}} \right) \right]^{-1/2} = 0.85$$

$$A_1 = 3.9' \times 2.8' = 10.92 \text{ ft}^2$$

$$H_1 = 270.0 - 266.4 = 3.6'$$

$$\text{Emergency spillway: } C_2 = 2.8, L_2 = 18', H_2 = 1.9'$$

$$\text{Right bank: } C_3 = 2.6, L_3 = 44.4', H_3 = 0.8'$$

$$Q = [(0.85)(10.92)^{3/2}(3.6)^{1/2}] + [(2.8)(18')(1.9')^{3/2}] + [(2.6)(44.4')(0.8')^{3/2}] = 360 \text{ cfs}$$

$$Q_{P1} = [Q_{P3} \text{ From 1<sup>st</sup> reach}] + [360 \text{ cfs}] = 3,060 + 360 = 3,420 \text{ cfs}$$

| Elevation | Discharge(cfs) | Storage(ac-ft) |
|-----------|----------------|----------------|
| 260       | 0              | 0              |
| 262       | 500            | 1.1            |
| 264       | 1,700          | 2.2            |
| 266       | 3,560          | 3.3            |

Stage-Discharge-Storage Relationships at Channel Cross Section at Millrace Outlet

Stage in 2<sup>nd</sup> reach when outflow is 3,420 cfs is:

$$264 + \frac{[3,420 - 1,700]}{[3,560 - 1,700]} [266 - 264] = 265.8$$

Storage in 2<sup>nd</sup> reach at El. 265.8 is:

$$2.2 + \frac{[265.8 - 264]}{[266 - 264]} [3.3 - 2.2] = 3.2 \text{ ac-ft} = V_1$$

CAMP DRESSER & McKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Townsend Harbor Dam

JOB NO. 380-5-11  
DATE CHECKED 6-6-79  
CHECKED BY JED

PAGE 3 of 14  
DATE 5/23/79  
COMPUTED BY PFH

$$Q_{p2} = Q_{p1} \left(1 - \frac{V}{S}\right) = 3,420 \left(1 - \frac{3.2}{273}\right) = 3,380 \text{ cfs}$$

Stage in 2<sup>nd</sup> reach when outflow is 3,380 cfs is:

$$264 + \left[ \frac{3,380 - 1,700}{3,560 - 1,700} \right] [266 - 264] = 265.8$$

Storage in 2<sup>nd</sup> reach at El. 265.8 = 3.2 ac.-ft. =  $V_2$

$$\therefore V_1 = V_2 = V_3 \implies Q_{p3} = Q_{p2} = 3,380 \text{ cfs} = \text{Outflow from 2<sup>nd</sup> reach}$$

No buildings in 2<sup>nd</sup> reach, except for the one just downstream of South Harbor Road referred to above, would be affected by dam-failure flood.

Third downstream reach: From Millrace Outlet to Cross Section 4

$$Q_{p1} = 3,380 \text{ cfs (From 2<sup>nd</sup> reach)}$$

| Elevation | Discharge (cfs) | Storage (ac.-ft.) |
|-----------|-----------------|-------------------|
| 256.4     | 0               | 0                 |
| 260.0     | 920             | 16.5              |
| 261.0     | 1,640           | 39.9              |
| 262.0     | 3,010           | 63.3              |
| 263.0     | 5,635           | 86.8              |

Stage in 3<sup>rd</sup> reach when outflow is 3,380 cfs is:

$$262 + \left[ \frac{3,380 - 3,010}{5,635 - 3,010} \right] [263 - 262] = 262.1$$

Storage in 3<sup>rd</sup> reach at El. 262.1 is:

$$63.3 + \left[ \frac{262.1 - 262.0}{263.0 - 262.0} \right] [86.8 - 63.3] = 65.6 \text{ ac.-ft.} = V_1$$

$$Q_{p2} = Q_{p1} \left(1 - \frac{V}{S}\right) = 3,380 \left(1 - \frac{65.6}{273}\right) = 2,570 \text{ cfs}$$

Stage in 3<sup>rd</sup> reach when outflow is 2,570 cfs is:

$$261 + \left[ \frac{2,570 - 1,640}{3,010 - 1,640} \right] [262 - 261] = 261.7$$

Storage in 3<sup>rd</sup> reach at El. 261.7 is:

$$39.9 + \left[ \frac{261.7 - 261.0}{262.0 - 261.0} \right] [63.3 - 39.9] = 56.3 \text{ ac.-ft.} = V_2$$

$$V_3 = \frac{V_1 + V_2}{2} = \frac{65.6 + 56.3}{2} = 61.0 \text{ ac.-ft.}$$

$$Q_{p3} = 3,380 \left(1 - \frac{61}{273}\right) = 2,625 \text{ cfs} = \text{Outflow from 3<sup>rd</sup> reach}$$

CAMP DRESSER & McKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Townsend Harbor Dam

JOB NO 380-5-11  
DATE CHECKED 6-6-79  
CHECKED BY JED

PAGE 4 of 14  
DATE 5/23/79  
COMPUTED BY PFH

Stage in 3<sup>rd</sup> reach when outflow is 2,625 cfs is:

$$261 + \frac{2,625 - 1,640}{3,010 - 1,640} [262 - 261] = 261.7$$

No buildings in 3<sup>rd</sup> reach affected by dam-failure flood.

Fourth downstream reach: From Cross Section 4 to Cross Section 3

$Q_{p1} = 2,625$  cfs (From 3<sup>rd</sup> reach)

| Elevation | Discharge (cfs) | Storage (ac.-ft.) |
|-----------|-----------------|-------------------|
| 252       | 0               | 0                 |
| 254       | 310             | 48.7              |
| 255       | 910             | 73.0              |
| 256       | 1,960           | 97.4              |
| 257       | 3,540           | 121.7             |

Stage in 4<sup>th</sup> reach when outflow is 2,625 cfs is:

$$256 + \frac{2,625 - 1,960}{3,540 - 1,960} [257 - 256] = 256.4$$

Storage in 4<sup>th</sup> reach at El. 256.4 is:

$$97.4 + \frac{256.4 - 256.0}{257.0 - 256.0} [121.7 - 97.4] = 107.1 \text{ ac.-ft.} = V_1$$

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_1}{S}\right) = 2,625 \left(1 - \frac{107.1}{273}\right) = 1,595 \text{ cfs}$$

Stage in 4<sup>th</sup> reach when outflow is 1,595 cfs is:

$$255 + \frac{1,595 - 910}{1,960 - 910} [256 - 255] = 255.6$$

Storage in 4<sup>th</sup> reach at El. 255.6 is:

$$73.0 + \frac{255.6 - 255.0}{256.0 - 255.0} [97.4 - 73.0] = 87.6 \text{ ac.-ft.} = V_2$$

$$V_3 = \frac{V_1 + V_2}{2} = \frac{107.1 + 87.6}{2} = 97.4 \text{ ac.-ft.}$$

$$Q_{p3} = 2,625 \left(1 - \frac{97.4}{273}\right) = 1,690 \text{ cfs} = \text{Outflow from 4<sup>th</sup> reach}$$

Stage in 4<sup>th</sup> reach when outflow is 1,690 cfs is:

$$255 + \frac{1,690 - 910}{1,960 - 910} [256 - 255] = 255.7$$

No buildings in 4<sup>th</sup> reach affected by dam-failure flood.

CAMP DRESSER & McKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Townsend Harbor Dam

JOB NO 380-5-11  
DATE CHECKED 6-6-79  
CHECKED BY JED

PAGE 5 of 14  
DATE 5/24/79  
COMPUTED BY PFH

Fifth downstream reach: From Cross Section 3 to Cross Section 2

$Q_p = 1,690$  cfs (From 4th reach)

| Elevation | Discharge (cfs) | Storage (ac.-ft.) |
|-----------|-----------------|-------------------|
| 247.7     | 0               | 0                 |
| 250.0     | 250             | 5.8               |
| 251.0     | 635             | 49.6              |
| 252.0     | 1,460           | 93.5              |
| 253.0     | 2,995           | 137.4             |

Stage in 5th reach when outflow is 1,690 cfs is:  
 $252 + \left[ \frac{1,690 - 1,460}{2,995 - 1,460} \right] [253 - 252] = 252.2$

Storage in 5th reach at El. 252.2 is:  
 $93.5 + \left[ \frac{252.2 - 252.0}{253.0 - 252.0} \right] [137.4 - 93.5] = 102.3 \text{ ac.-ft} = V_1$

$Q_p = Q_p \left( 1 - \frac{V_1}{S} \right) = 1,690 \left( 1 - \frac{102.3}{273} \right) = 1,055$  cfs

Stage in 5th reach when outflow is 1,055 cfs is:  
 $251 + \left[ \frac{1,055 - 635}{1,460 - 635} \right] [252 - 251] = 251.5$

Storage in 5th reach at El. 251.5 is:  
 $49.6 + \left[ \frac{251.5 - 251.0}{252.0 - 251.0} \right] [93.5 - 49.6] = 71.6 \text{ ac.-ft.} = V_2$

$V_3 = \frac{V_1 + V_2}{2} = \frac{102.3 + 71.6}{2} = 87.0 \text{ ac.-ft.}$

$Q_{p3} = 1,690 \left( 1 - \frac{87}{273} \right) = 1,150$  cfs = Outflow from 5th reach

Stage in 5th reach when outflow is 1,150 cfs is:  
 $251 + \left[ \frac{1,150 - 635}{1,460 - 635} \right] [252 - 251] = 251.6$

A building on Trout Brook in the right flood plain of the Squannacook River would probably be affected by a dam failure flood stage at El. 251.6.

Sixth downstream reach: At USGS Gage No. 01096000

$Q_p = 1,150$  cfs (From 5th reach)

| Elevation | Discharge (cfs) | Storage (ac.-ft.) |
|-----------|-----------------|-------------------|
| 244.3     | 0               | 0                 |
| 249.0     | 640             | 19.5              |
| 250.0     | 1,220           | 23.6              |

Elevation-Discharge Relationships From Annual USGS Publications of Surface Water Records

CAMP DRESSER & MCKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Townsend Harbor Dam

JOB NO 380-5-11  
DATE CHECKED 6-6-79  
CHECKED BY JED

PAGE 6 of 14  
DATE 5/24/79  
COMPUTED BY PFH

Stage in 6<sup>th</sup> reach when outflow is 1,150 cfs is:

$$249 + \left[ \frac{1,150 - 640}{1,220 - 640} \right] [250 - 249] = 249.9$$

Storage in 6<sup>th</sup> reach at El. 249.9 is:

$$19.5 + \left[ \frac{249.9 - 249.0}{250.0 - 249.0} \right] [23.6 - 19.5] = 23.2 \text{ ac.-ft.} = V_1$$

$$Q_{P2} = Q_P \left( 1 - \frac{V_1}{S} \right) = 1,150 \left( 1 - \frac{23.2}{273} \right) = 1,050 \text{ cfs}$$

Stage in 6<sup>th</sup> reach when outflow is 1,050 cfs is:

$$249 + \left[ \frac{1,050 - 640}{1,220 - 640} \right] [250 - 249] = 249.7$$

Storage in 6<sup>th</sup> reach at El. 249.7 is:

$$19.5 + \left[ \frac{249.7 - 249.0}{250.0 - 249.0} \right] [23.6 - 19.5] = 22.4 \text{ ac.-ft.} = V_2$$

$$V_3 = \frac{V_1 + V_2}{2} = \frac{23.2 + 22.4}{2} = 22.8 \text{ ac.-ft.}$$

$$Q_{P3} = 1,150 \left( 1 - \frac{22.8}{273} \right) = 1,055 \text{ cfs} = \text{Outflow from 6<sup>th</sup> reach}$$

Stage in 6<sup>th</sup> reach when outflow = 1,055 cfs is:

$$249 + \left[ \frac{1,055 - 640}{1,220 - 640} \right] [250 - 249] = 249.7$$

No buildings in 6<sup>th</sup> reach affected by dam-failure flood.

A flow of 1,055 cfs is expected to be equaled or exceeded at the gage an average of once every 17 months. There is a 70 percent chance that it will be equaled or exceeded in any given year. This flow is not expected to cause any damage downstream of the gage.

The dam failure analysis indicates that 2 buildings may be affected by the dam failure flood. The estimated potential loss of life is a few persons.

∴ SIGNIFICANT HAZARD

TEST FLOOD: 100-yr. to 1/2 PMF Range; Use 1/4 PMF

From COE Guideline Curves for Rolling Terrain use 1,100 cfs/mi<sup>2</sup>

$$\text{Test Flood} = (1/4) \times 1,100 \text{ cfs/mi}^2 \times (58.3 \text{ mi}^2) = \underline{16,000 \text{ cfs}}$$

CAMP DRESSER & McKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Townsend Harbor Dam

JOB NO 380-5-11  
DATE CHECKED 6-6-79  
CHECKED BY 160

PAGE 7 of 14  
DATE 5/31/79  
COMPUTED BY PFH

### Millrace Discharges

1. Outlet below El. 269.2

Weir with end contractions  $Q = C_e L_e H_e^{3/2}$

Length = 3.9'

b = millrace width = 12' ±

P = 266.4 - 263.1 = height from millrace invert to weir crest

$K_H = 0.003$

$L_b = (3.9') \div (12') = 0.3 \therefore K_L = 0.009 \Rightarrow L_e = 3.909$

| Elev. | H   | $H/P$ | $C_e$ | $H_e$ | Q  |
|-------|-----|-------|-------|-------|----|
| 266.4 | 0   | 0     | 0     | 0     | 0  |
| 267.3 | 0.9 | 0.27  | 3.15  | 0.903 | 11 |
| 268.1 | 1.7 | 0.52  | 3.18  | 1.703 | 28 |

2. Outlet above El. 269.2

Orifice operating under inlet control  $Q = CA\sqrt{2gH}$

From page 2 of 14, above,  $Q = (0.85)(10.92)(8.02)(H)^{3/2}$

| Elev  | H   | Q   |
|-------|-----|-----|
| 269.2 | 2.8 | 125 |
| 270.1 | 3.7 | 143 |
| 270.2 | 3.8 | 145 |
| 271.0 | 4.6 | 160 |
| 272.0 | 5.6 | 175 |
| 273.0 | 6.6 | 190 |

3. Overflows above El. 268.1

|                 |       | Overflow<br>Spillway |     | Side Walls<br>at Overflow<br>Spillway |     | Weir Above<br>Millrace<br>Outlet |     | Total<br>Flow |
|-----------------|-------|----------------------|-----|---------------------------------------|-----|----------------------------------|-----|---------------|
| Weir length     |       | 18'                  |     | 44.4'                                 |     | 15'                              |     |               |
| Weir crest elev |       | 268.1                |     | 269.2                                 |     | 270.2                            |     |               |
| Weir "C"        |       | 2.8                  |     | 2.6                                   |     | 3.5                              |     |               |
|                 | Elev. | H                    | Q   | H                                     | Q   | H                                | Q   |               |
|                 | 268.1 | 0                    | 0   | 0                                     | 0   | 0                                | 0   | 0             |
|                 | 269.2 | 1.1                  | 60  | 0                                     | 0   | 0                                | 0   | 60            |
|                 | 270.1 | 2.0                  | 145 | 0.9                                   | 100 | 0                                | 0   | 245           |
|                 | 270.2 | 2.1                  | 155 | 1.0                                   | 115 | 0                                | 0   | 270           |
|                 | 271.0 | 2.9                  | 250 | 1.8                                   | 280 | 0.8                              | 40  | 570           |
|                 | 272.0 | 3.9                  | 390 | 2.8                                   | 540 | 1.8                              | 125 | 1,055         |
|                 | 273.0 | 4.9                  | 545 | 3.8                                   | 855 | 2.8                              | 245 | 1,645         |

## Discharges at Millrace Entrance (Railroad Bridge)

### 1. Open-channel flow below El. 269.7

The discharge is equal to that at the downstream end of the millrace, but the pond water surface elevation equals the water surface elevation at the downstream end of the millrace plus the millrace head loss.

### 2. Orifice flow above El. 269.7, operating under outlet control.

$$\text{Area} = 16.3' \times 6.6' = 107.6'$$

$$\text{Wetted Perimeter} = (2 \times 16.3' + 6.6') = 45.8'$$

$$R = (107.6) \div (45.8) = 2.35$$

$$K = 1.5 + \frac{29 n^2 L}{R^{4/3}} = 1.5 + \frac{(29)(0.020)^2 (11.5')}{(2.35)^{4/3}} = 1.54$$

$$Q_0 = A \sqrt{\frac{2gH}{K}} = (107.6) \sqrt{\frac{(64.4)(H)}{(1.54)}} = 695.8 \sqrt{H}$$

H is the difference between water surface elevation, upstream and downstream of the railroad bridge.

| ①                                                     | ②                  | ③                  | ④                                               | ⑤                       | ⑥ *                                           |
|-------------------------------------------------------|--------------------|--------------------|-------------------------------------------------|-------------------------|-----------------------------------------------|
| Water Surface Elevation at Downstream End of Millrace | Millrace Discharge | Millrace Head Loss | Water Surface Elevation Downstream of RR Bridge | "H" in Orifice Equation | Water Surface Elevation Upstream of RR Bridge |
|                                                       | (Previous Page)    | (Estimated)        | ① + ③                                           | ② ÷ 695.8               | ④ + ⑤                                         |
| 266.4                                                 | 0                  | 0                  | 266.4                                           |                         | 266.4                                         |
| 267.3                                                 | 11                 | 0.2                | 267.5                                           | Open-Channel Flow       | 267.5                                         |
| 268.1                                                 | 28                 | 0.2                | 268.3                                           |                         | 268.3                                         |
| 269.2                                                 | 185                | 0.2                | 269.4                                           |                         | 269.4                                         |
| 270.1                                                 | 390                | 0.5                | 270.6                                           | 0.31                    | 270.9                                         |
| 270.2                                                 | 415                | 0.5                | 270.7                                           | 0.36                    | 271.1                                         |
| 271.0                                                 | 730                | 0.8                | 271.8                                           | ** 1.10                 | 272.9                                         |
| 272.0                                                 | 1,230              | 1.0                | 273.0                                           | ** 1.80                 | 274.8                                         |
| 273.0                                                 | 1,835              | 1.2                | 274.2                                           | ** 2.50                 | 276.7                                         |

\* Water surface elevation of Harbor Pond.

\*\* Value of "H" determined by balancing orifice and weir flow. See next page.

### 3. Weir flow above El. 272.6 (railroad track)

$$\text{Weir length} = 35'$$

$$\text{Weir 'C' } = 2.6$$

$$Q_w = C L H^{3/2}$$

H, is the difference between the pond elevation and the weir crest (El. 272.6).

CAMP DRESSER & MCKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Leicester Harbor Dam

JOB NO 380-S-11  
DATE CHECKED 6-6-79  
CHECKED BY JED

PAGE 9 of 14  
DATE 5/31/79  
COMPUTED BY PFH

Balance orifice and weir flow at railroad bridge:


$$Q_T = Q_o + Q_w = 695.8\sqrt{H} + 91(H)^{3/2}$$

DSEL = water surface elevation downstream of railroad bridge

USEL = pond water surface elevation (upstream of RR bridge)

| ①              | ②     | ③   | ④     | ⑤   | ⑥              | ⑦              | ⑧          | ⑨         |
|----------------|-------|-----|-------|-----|----------------|----------------|------------|-----------|
| Q <sub>T</sub> | DSEL  | H   | USEL  | H   | Q <sub>o</sub> | Q <sub>w</sub> | Computed H | Try New H |
|                |       | ①-② | ④-⑤   | ⑤-⑥ | ⑥-⑦            | ⑦-⑧            | ⑧-⑨        |           |
| 730            | 276.0 | 1.1 | 272.9 | 0.3 | 15             | 715            | 1.1        | OK        |
| 1230           | 273.0 | 3.1 | 276.1 | 3.5 | 595            | 635            | 0.8        | 1.8       |
|                |       | 1.8 | 274.8 | 2.2 | 295            | 935            | 1.8        | OK        |
| 1835           | 274.2 | 2.0 | 276.2 | 3.6 | 620            | 1,215          | 3.1        | 2.5       |
|                |       | 2.5 | 276.7 | 4.1 | 755            | 1,080          | 2.4        | OK        |

Discharge at Railroad Bridge



CAMP DRESSER & McKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Townsend Harbor Dam

JOB NO 380-5-11  
DATE CHECKED 6-6-79  
CHECKED BY JED


PAGE 10 of 14  
DATE 6/1/79  
COMPUTED BY PFH

### Stage-Discharge Characteristics of Harbor Pond

| Weir C<br>Weir Length<br>Weir Crest Elev. | Spillway |        | Right Embankment |       |       | Left Embankment |       | Railroad Bridge      | Total Discharge |
|-------------------------------------------|----------|--------|------------------|-------|-------|-----------------|-------|----------------------|-----------------|
|                                           | 3.5      |        | 2.3              |       |       | 2.6             |       | See graph on page 9. |                 |
|                                           | 92.2'    |        | Varies           |       |       | 57'             |       |                      |                 |
| Elev.                                     | H        | Q      | H                | L     | Q     | H               | Q     | (cfs)                | (cfs)           |
| (ft)                                      | (ft)     | (cfs)  | (ft)             | (ft)  | (cfs) | (ft)            | (cfs) |                      |                 |
| 266.4                                     | 0        | 0      | 0                | 0     | 0     | 0               | 0     | 0                    | 0               |
| 267.0                                     | 0        | 0      | 0                | 0     | 0     | 0               | 0     | 5                    | 5               |
| 268.0                                     | 0.7      | 190    | 0                | 0     | 0     | 0               | 0     | 20                   | 210             |
| 269.0                                     | 1.7      | 715    | 0                | 0     | 0     | 0               | 0     | 150                  | 865             |
| 270.0                                     | 2.7      | 1,430  | 0                | 0     | 0     | 0               | 0     | 225                  | 1,655           |
| 271.0                                     | 3.7      | 2,300  | 1.0              | 33.5  | 55    | 0.9             | 125   | 410                  | 2,890           |
| 272.0                                     | 4.7      | 3,290  | 2.0              | 43.0  | 280   | 1.9             | 390   | 500                  | 4,460           |
| 273.0                                     | 5.7      | 4,390  | 3.0              | 56.0  | 670   | 2.9             | 730   | 750                  | 6,540           |
| 274.0                                     | 6.7      | 5,595  | 4.0              | 68.0  | 1,250 | 3.9             | 1,140 | 1,000                | 8,985           |
| 275.0                                     | 7.7      | 6,895  | 5.0              | 81.0  | 2,085 | 4.9             | 1,605 | 1,300                | 11,885          |
| 276.0                                     | 8.7      | 8,280  | 6.0              | 93.5  | 3,160 | 5.9             | 2,120 | 1,610                | 15,170          |
| 277.0                                     | 9.7      | 9,750  | 7.0              | 106.0 | 4,515 | 6.9             | 2,680 | 1,940                | 18,885          |
| 278.0                                     | 10.7     | 11,295 | 8.0              | 119.0 | 6,195 | 7.9             | 3,290 | 2,250                | 23,030          |

### Stage - Storage - Area Characteristics of Harbor Pond

| Elev. | Area    | Avg. Area | H    | Storage Above Spillway |
|-------|---------|-----------|------|------------------------|
| (ft)  | (acres) | (acres)   | (ft) | (acre-ft)              |
| 267.3 | 43.5    |           |      | 0                      |
| 270.0 | 197.4   | 120.4     | 2.7  | 325                    |
| 280.0 | 421.5   | 309.4     | 10.0 | 3,419                  |




CAMP DRESSER & McKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Townsend Harbor Dam

JOB NO 380-5-11  
DATE CHECKED 6-16-79  
CHECKED BY ABD

PAGE 11 of 14  
DATE 6/1/79  
COMPUTED BY PEH



### Surcharge - Storage Routing Through Harbor Pond

$Q_p$  = Test flood inflow = 16,000 cfs (From page 6)

Stage when outflow is 16,000 cfs is El. 276.2

Storage at El. 276.2 is 2,243 ac.-ft.

$$\text{Runoff Volume} = \frac{2,243 \text{ ac.-ft.}}{(58.25 \text{ mi}^2)(53.3 \frac{\text{ac.-ft.}}{\text{inch.-ft.}})} = 0.72" \text{ runoff}$$

1/4 PMF runoff volume = 5" ±

$$Q_R = Q_p \left(1 - \frac{V_i}{S}\right) = 16,000 \left(1 - \frac{0.72"}{5"}\right) = 13,700 \text{ cfs}$$

Stage when outflow is 13,700 cfs is El. 275.6

Storage at El. 275.6 is 2,058 ac.-ft.

$$\text{Avg. Storage} = \frac{2,243 + 2,058}{2} = 2,150 \text{ ac.-ft.}$$

Stage when storage is 2,150 ac.-ft is 275.9

Outflow at El. 275.9 is 14,840 cfs

### Tailwater Analysis

Determine tailwater elevation at upstream face of South Harbor Road bridge. The river channel discharge between the dam and the bridge comes principally from the spillway and right embankment.

$$Q = [(3.5)(92.2')(275.9 - 267.3)^{3/2}] + [(2.3)(92.2')(275.9 - 270.0)^{3/2}] = 11,180 \text{ cfs}$$

Water surface elevation at downstream face of South Harbor Road bridge is approximately the same as that at the confluence of the millrace discharge channel with the river channel, at which point the river flow is the entire test flood outflow, 14,840 cfs.

At millrace outlet:

| Elevation | Discharge (cfs) |
|-----------|-----------------|
| 270       | 9,535           |
| 271       | 10,070          |
| 272       | 11,485          |
| 273       | 13,670          |
| 274       | 16,600          |

Stage when discharge is 14,840 cfs is:

$$273 + \frac{[14,840 - 13,670]}{[16,600 - 13,670]} [274 - 273] = 273.4$$

Balance orifice and weir flow at South Harbor Road bridge

1. Orifice under outlet control (Crown El. 270.4)

$$\begin{aligned} \text{Area} &= (10.4' \times 83') = 863.2' \\ \text{Wetted Perimeter} &= (2 \times 10.4' + 83') = 186.8' \\ R &= (863.2) / (186.8) = 4.62' \\ \text{Length} &= 30' \\ n &= 0.050 \\ K &= 1.5 + \frac{29n^2L}{R^{4/3}} = 1.5 + \frac{(29)(0.050)^2(30')}{(4.62)^{4/3}} = 1.78 \end{aligned}$$

$$Q_o = A \sqrt{\frac{2gH_o}{K}} = 863.2' \sqrt{\frac{(64.4)H_o}{1.78}} = 5,192 \sqrt{H_o}$$

2. Weir at El. 274: Length = 200', C = 3.0,  $Q_w = CLH_w^{3/2}$

Stage - Area Relationships:

| Elevation   | Area (sq ft) |
|-------------|--------------|
| 270.4 - 274 | 863.2        |
| 275         | 1,063.2      |
| 276         | 1,263.2      |
| 277         | 1,463.2      |

| ①                                         | ②       | ③     | ④                  | ⑤        | ⑥                | ⑦                       | ⑧       | ⑨       | ⑩                 | ⑪                      |
|-------------------------------------------|---------|-------|--------------------|----------|------------------|-------------------------|---------|---------|-------------------|------------------------|
| Assumed<br>$Q_w$                          | $H_w$   | USEL  | Area<br>at<br>USEL | Velocity | Velocity<br>Head | Energy<br>Grade<br>Line | $H_o$   | $Q_o$   | Computed<br>$Q_w$ | Assume<br>New<br>$Q_w$ |
|                                           | ①/600/4 | 274+② | From Table Above   | 11,180/④ | ⑤/29             | ③+⑥                     | ⑦-273.4 | 5,192-⑧ | 11,180-⑨          |                        |
| 1,330                                     | 1.7     | 275.7 | 1,203.2            | 9.3      | 1.3              | 277.0                   | 3.6     | 9,850   | 1,330             | OK                     |
| For Submerged Conditions: (See next page) |         |       |                    |          |                  |                         |         |         |                   |                        |
|                                           |         |       |                    | 9,530/④  |                  |                         | ⑦-273.3 |         | 9,530-⑨           |                        |
| 540                                       | 0.9     | 274.9 | 1,043.2            | 9.1      | 1.3              | 276.2                   | 2.9     | 8,840   | 690               | 560                    |
| 560                                       | 1.0     | 275.0 | 1,063.2            | 9.0      | 1.3              | 276.3                   | 3.0     | 8,990   | 540               | OK                     |

Tailwater El. 275.7 indicates that the dam is submerged. In order to account for submergence at the dam, reduce the discharges at the spillway and right embankment. Assume submergence ratio = 0.75. Reduce free-flow discharges 40%.

| Elev. | Spillway       |                     | Right Embankment |                     | Total Submerged Discharge | Left Embankment | Railroad Bridge | Total Discharge |
|-------|----------------|---------------------|------------------|---------------------|---------------------------|-----------------|-----------------|-----------------|
|       | Free Discharge | Submerged Discharge | Free Discharge   | Submerged Discharge |                           |                 |                 |                 |
| 273   | 4,390          | 2,635               | 670              | 400                 | 3,035                     | 730             | 750             | 4,515           |
| 274   | 5,595          | 3,355               | 1,250            | 750                 | 4,105                     | 1,140           | 1,000           | 6,245           |
| 275   | 6,895          | 4,135               | 2,085            | 1,250               | 5,385                     | 1,605           | 1,300           | 8,290           |
| 276   | 8,280          | 4,970               | 3,160            | 1,895               | 6,865                     | 2,120           | 1,610           | 10,595          |
| 277   | 9,750          | 5,850               | 4,515            | 2,710               | 8,560                     | 2,680           | 1,940           | 13,180          |
| 278   | 11,295         | 6,780               | 6,195            | 3,720               | 10,500                    | 3,290           | 2,250           | 16,040          |

CAMP DRESSER & McKEE  
Environmental Engineers  
Boston, Mass.

CLIENT COE  
PROJECT Dam Inspection  
DETAIL Townsend Harbor Dam

JOB NO. 380-5-11  
DATE CHECKED 6-16-79  
CHECKED BY JED

PAGE 14 of 14  
DATE 6/5/79  
COMPUTED BY PFH

### Surcharge - Storage Routing With Submergence

Stage when outflow is 16,000 cfs is El. 278

Storage at El. 277.8 is 2,800 ac.-ft.

$$\text{Runoff Volume} = \frac{2,800}{(58.25)(53.3)} = 0.9" \text{ runoff}$$

$$Q_{p2} = 16,000 \left(1 - \frac{0.9}{5}\right) = 13,120 \text{ cfs}$$

Stage when outflow is 13,120 cfs is El. 277

Storage at El. 277 is 2,491 ac.-ft.

$$\text{Avg. Storage} = \frac{2,800 + 2,491}{2} = 2,646 \text{ ac.-ft.}$$

Stage when storage is 2,646 ac.-ft. is 277.5

Outflow at El. 277.5 is 14,610 cfs

### Tailwater Analysis With Submergence

Stage at downstream face of South Harbor Road bridge when discharge at confluence with millrace outlet is 14,710 cfs is:

$$273 + \frac{14,610 - 13,670}{16,600 - 13,670} [274 - 273] = 273.3$$

Discharge at spillway and right embankment:

$$Q = 8,560 + \frac{277.5 - 277.0}{278.0 - 277.0} [10,500 - 8,560] = 9,530 \text{ cfs}$$

Tailwater elevation for submerged conditions is El. 275.0. (See tabular balance of orifice and weir flow on previous page)

$$\text{Check submergence ratio: } \frac{(275.0 - 267.3)}{(277.5 - 267.3)} = 0.76 \text{ OK}$$

Test-Flood Outflow = 14,610 cfs at El. 277.5

The test flood overtops the dam by 7.5' and the spillway by 10.2'.

Tailwater Elevation is 275.0

Spillway capacity at test flood elevation:

$$5,850 + \frac{277.5 - 277.0}{278.0 - 277.0} [6,780 - 5,850] = 6,320 \text{ cfs}$$

APPENDIX E  
INFORMATION AS CONTAINED IN  
THE NATIONAL INVENTORY OF DAMS

# INVENTORY OF DAMS IN THE UNITED STATES

|                 |        |       |        |                     |                  |                  |                             |
|-----------------|--------|-------|--------|---------------------|------------------|------------------|-----------------------------|
| IDENTITY NUMBER | OWNER  | STATE | COUNTY | NAME                | LATITUDE (NORTH) | LONGITUDE (WEST) | REPORT DATE (DAY / MO / YR) |
| 140025          | 425705 |       |        | TOWNSEND HARBOR DAM | 4259.2           | 7140.4           | 22JUN79                     |

|                |                                        |
|----------------|----------------------------------------|
| POPULAR NAME   | NAME OF CONSTRUCTION                   |
| SPALDING DAM   | HARBOR POND                            |
| TYPE OF DAM    | NEAREST POPULATED CITY (TOWN, VILLAGE) |
| CONCRETE       | TOWNSEND                               |
| YEAR COMPLETED | POPULATION                             |
| 1970           | 5125                                   |

|          |        |          |             |             |                    |                 |                  |                |
|----------|--------|----------|-------------|-------------|--------------------|-----------------|------------------|----------------|
| PURPOSES | DESIGN | DESIGNER | DESIGN DATE | DESIGN TYPE | DESIGNER'S ADDRESS | DESIGNER'S CITY | DESIGNER'S STATE | DESIGNER'S ZIP |
|          |        |          |             |             |                    |                 |                  |                |


## REMARKS

|              |           |             |
|--------------|-----------|-------------|
| CONSTRUCTION | OPERATION | MAINTENANCE |
|              |           |             |

|              |           |             |
|--------------|-----------|-------------|
| CONSTRUCTION | OPERATION | MAINTENANCE |
|              |           |             |

## REMARKS

|              |           |             |
|--------------|-----------|-------------|
| CONSTRUCTION | OPERATION | MAINTENANCE |
|              |           |             |



1

# TOWNSEND

## DAM NO. E-1

NAME Townsend Harbor Dam

STREAM Squamacook River

LOCATION Townsend Harbor, Mass  
Longitude 71°40'25" Latitude 42°39'09"

DRAINAGE AREA 60.6 Square Miles

TYPE Stone Masonry Overflow

GENERAL DIMENSIONS Length 92 ft, Height 62 ft


SPILLWAY Capacity 1290 cfs

OUTLET WORKS None

POND AREA 48+ Acres

POND CAPACITY 33+ Million Gallons

BENCH MARK USGS disc on southeast abutment  
of R.R. bridge as shown on plan



APPENDIX B-17

(2)

