

MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A156 109

CONNECTICUT RIVER BASIN
HARRISVILLE, NEW HAMPSHIRE

CHESHAM POND DAM
NH 00063

STATE NO 109.02

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DTIC
SELECTED
JUL 08 1985
S D G

DTIC FILE COPY

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

MARCH 1980

DISTRIBUTION STATEMENT A
Approved for public release
Distribution Unlimited *

85 06 13 058

DISCLAIMER NOTICE

THIS DOCUMENT IS BEST QUALITY PRACTICABLE. THE COPY FURNISHED TO DTIC CONTAINED A SIGNIFICANT NUMBER OF PAGES WHICH DO NOT REPRODUCE LEGIBLY.

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00063	2. GOVT ACCESSION NO. AD-A156 109	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Chesham Pond Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		12. REPORT DATE March 1980
		13. NUMBER OF PAGES 40
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Connecticut River Basin Harrisville, New Hampshire Minnewawa Brook		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is a concrete gravity dam and earthen embankment 125 ft. long and 16 ft. high. The dam is in fair condition. It is small in size with a significant hazard classification. A breach in the dam could cause potential for loss of 1-2 lives and appreciable property damage. There are various major concerns which must be corrected to assure the continued performance of the dam.		



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF:
NEDED

JUN 19 1980

Honorable Hugh J. Gallen
Governor of the State of New Hampshire
State House
Concord, New Hampshire 03301

Dear Governor Gallen:


Inclosed is a copy of the Chesham Pond Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire. In addition, a copy of the report has also been furnished the owner, the State of New Hampshire.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely,


MAX B. SCHEIDER

Colonel, Corps of Engineers
Division Engineer

Incl
As stated

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT

Identification No.: NH00063
Name of Dam: Chesham Pond Dam
Town: Harrisville
County and State: Cheshire County, New Hampshire
Stream: Minnewawa Brook
Date of Inspection: September 13, 1979

BRIEF ASSESSMENT

Chesham Pond Dam is a concrete gravity dam and earthen embankment 125 feet in length with a hydraulic height of 16 feet. The spillway consists of a concrete ogee spillway 41 feet in length. A concrete sluiceway structure is adjacent to the northwest end of the spillway and contains a gate-operated low-level outlet 2'H x 3.5'W. The gate is operated by a hand operated mechanism located directly above the gate. A highway crossing is located just downstream of the dam. Stone masonry training walls are located on either side of the spillway discharge channel and terminate against the highway embankment. The dam spans Minnewawa Brook and is located in southwest New Hampshire. The drainage area above the dam is 8.2 square miles and contains Silver Lake, Childs Bog, and Seaver Reservoirs. Maximum storage capacity is approximately 630 acre-feet. Normal pool is approximately 0.55 miles in length with a surface area of 70 acres. Chesham Pond is currently used for recreational purposes.

The dam is in fair condition. Major concerns are: inadequate spillway capacity, deterioration of the mortar in the stone masonry training walls on both sides of the discharge channel between the dam and the highway embankment, lack of vegetation and erosion resistance on the upstream slope of the embankment section near the southeast end of the dam, and trees growing on the upstream and downstream slopes of the dam.

The dam is of small size and significant hazard classification based on storage volume and potential for loss of 1-2 lives and appreciable property damage in event of a breach. In accordance with the Recommended Guidelines for Safety Inspection of Dams, the test flood may range from the 100-year to $\frac{1}{2}$ the Probable Maximum Flood (PMF). A test flood equal to $\frac{1}{2}$ PMF was selected because of the potential for loss of 1-2 lives in the event of a breach. To determine the test flood outflow, the Seaver Reservoir Dam Phase I Inspection Report was consulted. The drainage area to Seaver Dam is 4.4 square miles and the resulting test flood outflow ($\frac{1}{2}$ PMF) was determined to be 2,660 cfs. The subdrainage area to Chesham Pond Dam is 3.8 square miles of steeply sloping terrain (166 ft/mile). Using the PMF Peak Flow Rates graph, the peak discharge for a 'mountainous' watershed, having a drainage area of 3.8 square miles, was determined to be 8,740 cfs. Therefore, the test flood inflow from the subdrainage area would be 4,370 cfs. Using the $\frac{1}{2}$ PMF discharge from Seaver Reservoir Dam of 2,660 cfs and the test flood inflow from the subdrainage area of 4,370 cfs, the total test flood inflow to Chesham

Pond Dam was determined to be approximately 7,000 cfs (854 csm). It should be noted that the peaks for the test flood outflow from Seaver Reservoir Dam and the inflow from the subdrainage area would probably not occur at the same time. However, for the purposes of this Phase I investigation, the test flood inflow will be assumed to equal the summation of these two values. Using the procedure outlined in Estimating Effect of Surcharge Storage on Maximum Probable Discharges issued by the Corps, to determine the modifying effect of surcharge storage on the test flood inflow, the routed test flood outflow was determined to be 6,000 cfs (732 csm) at elevation 1161.2' NGVD. The test flood analysis indicates that the dam would be overtopped by 4.8 feet during the test flood. Maximum spillway capacity at top of dam is 535 cfs which is 9 percent of the routed test flood outflow.

The owner, the New Hampshire Water Resources Board, should implement the results of the recommendations and remedial measures given in Sections 7.2 and 7.3 within one year after receipt of this Phase I Inspection Report.

Warren A. Guinan

Warren A. Guinan
 Project Manager
 N.H. P.E. 2339

DTIC
 ELECTE
 S JUL 08 1985 D
 G

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/1	23 CW

This Phase I Inspection Report on Chesham Pond Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

Richard J. Di Bruno

RICHARD DIBUONO, MEMBER
Water Control Branch
Engineering Division

Aramast Mahtesian

ARAMAST MAHTESIAN, MEMBER
Foundation & Materials Branch
Engineering Division

Carney M. Terzian

CARNEY M. TERZIAN, CHAIRMAN
Design Branch
Engineering Division

APPROVAL RECOMMENDED:

Joe B. Fryar
JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

Title	Page
LETTER OF TRANSMITTAL.....	
BRIEF ASSESSMENT.....	
REVIEW BOARD PAGE.....	
PREFACE.....	v
TABLE OF CONTENTS.....	vi
OVERVIEW PHOTO.....	vii
LOCATION MAP.....	viii

REPORT

SECTION

1	PROJECT INFORMATION.....	1-1
	1.1 General.....	1-1
	1.2 Description of Project.....	1-1
	1.3 Pertinent Data.....	1-3
2	ENGINEERING DATA.....	2-1
	2.1 Design.....	2-1
	2.2 Construction.....	2-1
	2.3 Operation.....	2-1
	2.4 Evaluation.....	2-1
3	VISUAL INSPECTION.....	3-1
	3.1 Findings.....	3-1
	3.2 Evaluation.....	3-2
4	OPERATIONAL PROCEDURES.....	4-1
	4.1 Procedures.....	4-1
	4.2 Maintenance of Dam.....	4-1
	4.3 Maintenance of Operating Facilities.....	4-1
	4.4 Description of Any Warning System in Effect.....	4-1
	4.5 Evaluation.....	4-1
5	HYDROLOGY AND HYDRAULIC ANALYSIS.....	5-1
	5.1 Evaluation of Features.....	5-1
6	STRUCTURAL STABILITY.....	6-1
	6.1 Evaluation of Structural Stability.....	6-1
7	ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES.....	7-1
	7.1 Dam Assessment.....	7-1
	7.2 Recommendations.....	7-1
	7.3 Remedial Measures.....	7-2
	7.4 Alternatives.....	7-2

APPENDICES

	<u>Designation</u>
VISUAL INSPECTION CHECK LISTS.....	A
ENGINEERING DATA.....	B
PHOTOGRAPHS.....	C
HYDROLOGY AND HYDRAULIC COMPUTATIONS.....	D
INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS.....	E




Figure 1 - Overview of Chesham Pond Dam. June 1979



Reprinted by permission of the Department of Resources and Economic Development, Concord, N.H. 03301, and the copyright owners, The National Survey, Concord, VT. 0-17-78.

Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.	
CONCORD	NEW HAMPSHIRE		
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
CHESIAM POND DAM LOCATION MAP			
MINNEWAWA BROOK		NEW HAMPSHIRE	
		SCALE: SEE BAR SCALE	
		DATE: MARCH 1980	

SCALE IN MILES



MAP BASED ON STATE OF NEW HAMPSHIRE
OFFICIAL HIGHWAY MAP.

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT
CHESHAM POND DAM

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Anderson-Nichols & Company, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire. Authorization and notice to proceed were issued to Anderson-Nichols under a letter of March 22, 1979 from John P. Chandler, Colonel, Corps of Engineers. Contract No. DACW33-79-C-0050, as changed, has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the States to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location. Chesham Pond Dam is located in the Town of Harrisville, New Hampshire and impounds a reservoir of small size. Chesham Dam is the downstream dam in a series of four dams which impound the headwaters of Minnewawa Brook. After discharging at damsite, Minnewawa Brook flows southwesterly approximately 7 miles to its confluence with Otter Brook to form The Branch. The Branch then continues another 2.5 miles to Keene, New Hampshire where it joins the Ashuelot River. The Ashuelot River is a major tributary in the Connecticut River Basin. Chesham Pond Dam is shown on U.S.G.S. Quadrangle, Monadnock, New Hampshire with coordinates approximately at N42°56'15", W72°08'23", Cheshire County, New Hampshire. (See Location Map page viii.)

b. Description of Dam and Appurtenance. Chesham Pond dam is a concrete gravity dam and earthen embankment 125 feet in length with a hydraulic height of 16 feet. Beginning at the southeast end of the dam and going northwest the dam consists

APPENDIX A
VISUAL INSPECTION CHECKLIST

(5) Inspect the spillway when no water is flowing over it for evidence of leakage or undermining.

The owner should carry out the recommendations made by the engineer.

.3 Remedial Measures

a. Operating and Maintenance Procedures. The owner should:

(1) Clear trees for a distance of 25 feet on either side of the discharge channel between the dam and the highway that crosses the channel downstream of the dam.

(2) Remove trees from the shore of the pond for a distance of 100 feet upstream from the intake to the low-level outlet at the east end of the dam.

(3) Repair the spalled concrete at the southeast abutment all.

(4) Visually inspect the dam and appurtenant structures once a month.

(5) Engage a professional engineer qualified in the design and construction of dams to make a comprehensive technical inspection of the dam once every year.

(6) Establish a surveillance program for use during and immediately after heavy rainfall and also a downstream warning program to follow in case of emergency conditions.

(7) Establish trespassing control.

(8) Ensure operation of low-level outlet.

.4 Alternatives

one.

SECTION 7
ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual examination indicates that Chesham Pond Dam is in fair condition. The major concerns with respect to the integrity of the dam are:

- (1) Inadequate spillway capacity.
- (2) Deterioration of the mortar in the stone masonry training walls on both sides of the discharge channel between the dam and the highway embankment which crosses the channel downstream of the dam.
- (3) Lack of vegetation and erosion resistance on the upstream slope of the embankment section near the southeast end of the dam.

(4) Trees growing on the upstream and downstream slopes of the dam.

b. Adequacy of Information. The information from the visual inspection and hydraulic analyses is adequate to identify the problems listed in 7.2. These problems will require the attention of a professional engineer who will have to make additional engineering studies to design or specify remedial measures. No additional information is needed for the purposes of this Phase I investigation.

c. Urgency. The owner should implement the recommendations in 7.2 and 7.3 within one year after receipt of this Phase I report.

7.2 Recommendations

The owner should retain a professional engineer qualified in the design and construction of dams to:

- (1) Perform a more detailed investigation to evaluate spillway adequacy and overtopping potential.
- (2) Specify procedures for repair of the stone masonry training walls on both sides of the discharge channel between the dam and the highway embankment that crosses the channel downstream of the dam.
- (3) Specify procedures for providing adequate erosion resistance on the upstream slope of the embankment section of the dam.
- (4) Specify and oversee procedures for removing trees and their root systems from the embankment section of the dam. Also specify and oversee the filling of the voids remaining from the root system removal.

SECTION 6
STRUCTURAL STABILITY

6.1 Visual Observations

The visual examination indicates the following potential structural problems:

(1) Deterioration of the mortar in the stone masonry training walls on both sides of the discharge channel between the dam and the highway embankment which crosses the channel downstream of the dam.

(2) Lack of vegetation and erosion resistance on the upstream slope of the embankment section near the southeast end of the dam.

(3) Trees growing on the upstream and downstream slopes of the embankment section which could cause seepage or erosion problems if a tree blows over and pulls out its roots or if a tree dies or is cut and its roots rot.

6.2 Design and Construction Data

In a letter dated June 30, 1949, it is stated that the contractor who built the original dam in 1921 stated "that most of this dam is built of very large boulders... (and) the bottom of this dam was planked and there was some decay there."

6.3 Post-Construction Changes

A letter dated April 20, 1949 states that the dam "appears to be in a weak state and is in need of immediate repairs or reconstruction." A petition for repair dated September 6, 1949 states that the reconstruction will consist of "cement" {sic!}.

6.4 Seismic Stability

This dam is located in Seismic Zone 2 and, in accordance with the Phase I guidelines, does not warrant seismic analysis.

by the Corps, to determine the modifying effect of surcharge storage on the test flood inflow, the routed test flood outflow was determined to be 6,000 cfs (732 csm) at elevation 1161.2' NGVD. The test flood analysis indicates the dam would be overtopped by 4.8 feet during the test flood. Maximum spillway capacity at top of dam is 535 cfs which is 9 percent of the routed test flood outflow.

f. Dam Failure Analysis. The impact of failure of the dam with pool level at top of dam was assessed. Because of the tandem relationship of Childs Bog, Seaver and Chesham Dams, the three dams were analyzed through the use of the Corps of Engineers HEC-1DB computer program. With this analysis, it could be determined how much overtopping would occur at each dam under various breach conditions. Since Chesham Pond Dam is the most downstream, the analysis of all these results is not necessary to determine the appropriate hazard classification for Chesham. Therefore, only the breach of Chesham will be discussed in this report.

A breach of Chesham Pond Dam was analyzed from the dam to a point about 1 mile downstream. The breach was assumed to occur at the top of dam and develop to the toe of the dam. The time for a breach to develop with a bottom width of 50 feet and side-slopes 1H:1V was estimated to be one hour. A breach of this magnitude resulted in a discharge of 6,960 cfs. One trailer located about 200 feet downstream of the dam could be inundated by 3.2 feet of water. This could cause damage to the structure and possibly cause loss of 1-2 lives. The road crossing, one-half mile downstream of the dam, could be overtopped by about 5.1 feet of water with a breach discharge of 6,470 cfs. Damage to the roadway and culvert could occur. Two houses located about 8 and 10 feet above streambed, just upstream from the road crossing, could be subjected to property damage. (See Appendix C - Figure 12.) The next road crossing, one mile downstream of the dam, could be overtopped by 3 feet with a breach discharge of 5,500 cfs. (See Appendix C - Figure 13.) This amount of overtopping could possibly damage the gravel roadway and culvert. The reach between these two road crossings provides a large storage area for attenuation of the breach wave. (See Appendix C - Figure 14.) One house in this reach, located about ten feet above the streambed, may be subjected to basement flooding.

A breach of Chesham Pond Dam could result in the possible loss of 1-2 lives and cause appreciable property damage. Based on this analysis, Chesham Pond Dam was classified Significant Hazard.

SECTION 5
HYDROLOGIC/HYDRAULIC

5.1 Evaluation of Features

a. General. Chesham Pond Dam is a concrete gravity dam which impounds a reservoir of small size. The drainage area to the damsite consists of 8.2 square miles of moderately to steeply sloping terrain. Silver Lake, Childs Bog, and Seaver Reservoir are storage areas in the upstream watershed. The total length of the dam is 125 feet with a hydraulic height of 16 feet. The concrete ogee spillway is 41 feet in length. A low-level outlet structure is located in the northwest abutment. A roadway is located immediately downstream of the dam. Discharge from the dam passes through the roadway in a corrugated metal pipe arch with a span of 14' 11" and rise of 10' 2".

b. Design Data. No design data were disclosed.

c. Experience Data. According to a letter dated October 13, 1938, Chesham Pond Dam had a flow of about 4 feet over the spillway crest during the flood of September 21-24, 1938. No other experience data was found.

d. Visual Observations. At the time of inspection, no visual evidence was noted of damage to any portions of the dam caused by excessive discharges.

e. Test Flood Analysis. Chesham Pond Dam is classified as being small in size, having a hydraulic height of 16 feet and a maximum storage capacity of 630 acre-feet. The dam was determined to have a significant hazard classification. Using the Recommended Guidelines for Safety Inspection of Dams, the test flood may range from the 100-year to $\frac{1}{2}$ the Probable Maximum Flood (PMF). A test flood equal to $\frac{1}{2}$ PMF was selected because of the potential for loss of 1-2 lives in the event of a breach. To determine the test flood inflow, the Seaver Reservoir Dam Phase I Inspection Report was consulted. The drainage area to Seaver Dam is 4.4 square miles and the resulting test flood outflow ($\frac{1}{2}$ PMF) was determined to be 2,660 cfs. The subdrainage area to Chesham Pond Dam is 3.8 square miles of steeply sloping terrain (166 ft/mile). Using the PMF Peak Flow Rates graph, the peak discharge for a 'mountainous' watershed, having a drainage area of 3.8 square miles, was determined to be 8,640 cfs. Therefore, the test flood inflow from the subdrainage area would be 4,370 cfs. Using the $\frac{1}{2}$ PMF discharge from Seaver Reservoir Dam of 2,660 cfs and the test flood inflow from subdrainage area of 4,370 cfs, the total test flood inflow to Chesham Pond Dam was determined to be approximately 7,000 cfs (854 csm.) Using the procedure outlined in Estimating Effect of Surcharge Storage on Maximum Probable Discharges issued

SECTION 4
OPERATIONAL PROCEDURES

4.1 Procedures

Chesham Pond Dam is owned and operated by the New Hampshire Water Resources Board (NHWRB). The normal recreational lake level is maintained at the permanent spillway crest during the summer season. The lake level is lowered in the fall by use of the low-level outlet to provide storage for spring runoff and to enable property owners to make shoreline improvements.

4.2 Maintenance of Dam

NHWRB is responsible for the maintenance of the dam.

4.3 Maintenance of Operating Facilities

Throughout the year, the dam is visited on a weekly basis by a maintenance staff member of the NHWRB. A weekly log is kept on conditions at the dam site. The gate was not operated during the inspection; however, the mechanism appeared to be in satisfactory condition but has surface rust.

4.4 Description of Any Warning System in Effect

No written warning system was disclosed.

4.5 Evaluation

The current operation and maintenance procedures, consisting of a weekly program of inspection, should ensure that all minor problems encountered can be remedied within a reasonable period of time.

Some trees have grown on the upstream slope of the embankment section near the abutment and also on the downstream slope near the training wall on the east side of the channel. (See Appendix C - Figure 6.) No seepage was observed on the downstream embankment section of the dam.

c. Appurtenant Structures. The concrete low-level outlet structure at the northwest end of the spillway is approximately 4.5' wide and supports the sluice gate operating mechanism and wooden racks. (See Appendix C - Figure 7.) The concrete was observed to be in good condition with only a minor hair line crack in the concrete wall at one corner and only minor surface erosion of the concrete at the water line. The wooden decking over the sluice way channel was observed to be in good condition with only minor evidence of weathering and warping. The gate operating mechanism, which is a hand operated racket type, was observed to be in fair condition with some surface rust. (See Appendix C - Figure 8.) There was no indication of recent lubrication or operation. The trash racks which have been constructed of 2x4 wood members, were observed to be weathered.

d. Reservoir. The watershed above the reservoir is moderately to steeply sloping and heavily wooded. (See Appendix C - Figure 9.) The slopes of the reservoir appear stable. No evidence of significant sedimentation was observed. There are some trees overhanging the edge of the pond immediately upstream from the intake to the low-level outlet.

e. Downstream Channel. A roadway is located 20 feet downstream of the dam. (See Appendix C - Figure 10.) The channel downstream of the culvert is tree lined on both banks. (See Appendix C - Figure 11.)

3.2 Evaluation

On the basis of the results of the visual inspection, Chesham Pond Dam is considered to be in fair condition.

Deterioration of the mortar between the stone blocks in the stone masonry training walls on both sides of the discharge channel between the dam and highway immediately downstream could lead to failure of the walls and subsequent failure of the soil abutments of the dam.

The lack of vegetation on the upstream slope of the embankment section near the east end of the dam has led to some erosion, if allowed to continue, could result in breaching of the dam.

Trees growing on the upstream and downstream slopes of the embankment section of the dam could cause seepage or erosion problems if a tree blows over and pulls out its roots or if a tree dies or is cut and its roots rot.

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. General. Chesham Pond Dam is a low dam which impounds a reservoir of small size. The watershed above the reservoir is moderately to steeply sloping and heavily wooded. The downstream area is moderately sloping. From the southeast end of the concrete gravity section to the southeast abutment (which is not clearly defined) there is an embankment section about 65 feet long.

b. Dam. Chesham Pond Dam is a concrete gravity dam with a hydraulic height of 16 feet and totaling 125 feet in length. (See Appendix C-Figures 2 and 3.) The downstream face of the spillway is inclined at 1H:1V.

Both abutments of the dam consist of soil. There are many large boulders at the downstream toe of the dam, but no evidence near the dam of anything that appears to be bedrock. No information was found in the available records as to whether the dam is founded on bedrock or soil. Therefore, it is not possible to conclude what material the dam is founded on.

Water was flowing over the dam at the time of the inspection. As a result it is not possible to determine whether any leakage is taking place under the dam.

Stone masonry training walls are located on either side of the discharge channel between the dam and the roadway culvert about 20 feet downstream. The mortar between the stone blocks in these training walls is badly deteriorated. No water was leaking through these walls above tailwater except for one leak at an elevation 0.6 foot below pond level where the training wall on the east side of the channel meets the stone masonry wall which retains the highway fill. (See Appendix C-Figure 4.) It is considered unlikely that this leakage is coming from the pond.

The concrete weir was observed to be in good condition with minor surface erosion of the concrete at the water line. The training wall (abutment) at the southeast end of the weir was eroded and spalled up to 2" deep. (See Appendix C-Figure 5.)

The upstream slope of the embankment section has very little vegetation near the southeast end of the dam (apparently this is due to trespassing) and has experienced some erosion.

SECTION 2
ENGINEERING DATA

2.1 Design

No original design plans were found for Chesham Pond Dam. Plans for repairs in 1949 were found in the files of the New Hampshire Water Resources Board (NHWRB).

2.2 Construction Records

No construction records were revealed.

2.3 Operation

No engineering operational data were found.

2.4 Evaluation

a. Availability. A search of the files of the NHWRB revealed the plans of repairs in 1949 and other general historical information which was utilized in the preparation of this report.

b. Adequacy. The information obtained from the files of the NHWRB was used in conjunction with the visual inspection and the hydrologic and hydraulic computations to make the final assessments and recommendations of this investigation.

c. Validity. The structure as seen on the visual inspection is in close conformity to the disclosed plans and information.

(7) Impervious core - unknown

(8) Cutoff - unknown

(9) Grout curtain - unknown

h. Diversion and Regulating Tunnel - not applicable
(See j. below.)

i. Spillway

(1) Type - concrete gravity ogee spillway with a sloping downstream face (1H:1V).

(2) Length of weir - 41'

(3) Crest elevation - 1154' NGVD (See 1.3 c (6) above)

(4) Gates - none

(5) U/S Channel - Numerous cottages and homes are located around the reservoir. The reservoir slopes are wooded. No significant sedimentation at the damsite was observed.

(6) D/S Channel - About 20 feet downstream from the spillway apron is a roadway crossing. Discharge over the spillway passes through the roadway in a corrugated metal pipe arch with a span of 14' 11" and rise of 10'2".

j. Regulating Outlets. There is one 2.0'H x 3.5'W low-level opening located in the sluiceway structure adjacent to the northwest end of the spillway. This opening is controlled by a CI sluice gate. The invert of the opening is at elevation 1146.6' NGVD.

(6) Spillway crest - 1154 (Shown on USGS Quad-range Sheet and assumed to be spillway crest elevation.)

(7) Original design surcharge - unknown

(8) Top of dam - 1156.4

(9) Test flood pool - 1161.2

d. Reservoir Length (miles)

(1) Maximum pool - 0.57

(2) Spillway crest pool - 0.55

(3) Flood control pool - not applicable

e. Storage (acre-feet)

(1) Recreation pool - 460

(2) Flood control pool - not applicable

(3) Spillway crest pool - 460

(4) Top of dam - 630

(5) Test flood pool - 1140

f. Reservoir Surface Area (acres)

(1) Recreation pool - 70

(2) Flood control pool - not applicable

(3) Spillway crest - 70

(4) Test flood pool - 115

(5) Top of dam - 84

g. Dam

(1) Type- concrete gravity dam with earth embankment

(2) Length - 125'

(3) Height - 16' (structural and hydraulic)

(4) Topwidth - varied

(5) Side slopes - varied

(6) Zoning - unknown

The lake level is lowered in the fall by use of the low-level outlet. Throughout the year, the dam is visited on a weekly basis by a maintenance staff member of the NHWRB. A weekly log is kept on conditions at the damsite.

1.3 Pertinent Data

a. Drainage Area. The drainage area consists of 8.2 square miles (5,248 acres) of moderately to steeply sloping terrain. Silver Lake, Childs Bog and Seaver Reservoir are located in the upstream watershed. The normal pool of Chesham Pond has a surface area of 70 acres which constitutes 1 percent of the watershed.

b. Discharge at Damsite

(1) Outlet works - one 2.0'H x 3.5'W low-level opening controlled by CI sluice gate at invert elevation 1146.6' NGVD. Approximate capacity at top of dam - 120 cfs at 1156.4' NGVD.

(2) The maximum discharge at the damsite is unknown. However, a flow of 48 inches over spillway crest was reported during the flood of September 21-24, 1938. If this depth of flow over the spillway were to occur today, the approximate discharge would be 1,270 cfs with 1.6 feet of overtopping.

(3) Ungated spillway capacity at top of dam - 535 cfs @ 1156.4' NGVD

(4) Ungated spillway capacity at test flood elevation - 2,770 cfs @ 1161.2' NGVD

(5) Gated spillway capacity at top of dam - not applicable

(6) Gated spillway capacity at test flood elevation - not applicable

(7) Total spillway capacity at test flood elevation - 2,770 cfs @ 1161.2' NGVD

(8) Total project discharge at test flood elevation - 6,000 cfs @ 1161.2' NGVD

c. Elevation (ft. above NGVD of 1929; formerly called Mean Sea Level (MSL); see (6) below).

(1) Streambed at centerline of dam - 1140.8 (downstream invert pipe arch)

(2) Maximum tailwater - unknown

(3) Upstream gate invert - 1146.6

(4) Recreation pool - 1154

(5) Full flood control pool - not applicable

of the following sections: an earthen embankment 65 feet in length, a concrete spillway abutment, a concrete ogee spillway 41 feet long, and a concrete low-level sluiceway. The sluiceway structure contains a gate-operated mechanism located directly above the gate. The sluiceway intake is protected with a trash rack. A highway crossing is located just downstream of the dam. Discharge over the spillway passes through the roadway in a corrugated metal pipe arch with a span of 14'-11" and a rise of 10'2". Stone masonry training walls are located on either side of the spillway discharge channel and terminate against the highway embankment. The dam was originally constructed integrally with a railroad embankment long since abandoned, but the bridge seats remain in the downstream training walls mentioned above.

c. Size Classification. Small (hydraulic height-16 feet; storage-630 acre - feet) based on storage (≥ 50 to < 1000 acre - feet) as given in the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. Significant hazard. A breach with pool at top of dam could result in the loss of 1-2 lives and cause appreciable property damage. For details see Section 5.1 f.

e. Ownership. Chesham Pond Dam was reported to have been built in 1921. The name of the original owner was not found. Ownership in 1930 was recorded to have been Breed Pond Company, in Marlborough, New Hampshire, formerly owned by Whitney. It is possible that Whitney was the original owner. Files from the New Hampshire Water Resources Board (NHWRB) indicate that the NHWRB took over ownership sometime between 1949 and 1968.

f. Operator. The current owner and operator of Chesham Pond Dam is the NHWRB. Mr. Vernon Knowlton, Chief Engineer, 37 Pleasant Street, Concord, New Hampshire 03301. Phone (603) 271-3406.

g. Purpose of Dam. The dam was previously used for storage purposes and is currently utilized for recreation.

h. Design and Construction History. According to the files at the NHWRB, the dam was originally built in 1921. No design or construction information was found regarding the original construction. The files also indicate the concrete spillway apron was constructed October 6, 1937. Plans of repairs made in 1949 were found. These plans were engineered and drawn by the Public Service Company of New Hampshire and dated August 9, 1949. Repairs included construction of the present sluiceway structure.

i. Normal Operating Procedures. The normal recreational level is maintained at the crest of the permanent spillway.

VISUAL INSPECTION CHECKLIST
PARTY ORGANIZATION

PROJECT CHESHAM POND DAM, N.H.

DATE September 13, 1979

TIME 9:30 AM

WEATHER Sunny, warm

W.S. ELEV.	U.S.	DN.S.
	<u>1154'</u>	<u>1142.1'</u>
	NGVD	NGVD

PARTY:

- | | |
|-----------------------------------|-----------|
| 1. <u>Warren Guinan (ANCo)</u> | 6. _____ |
| 2. <u>Stephen Gilman (ANCo)</u> | 7. _____ |
| 3. <u>David Deane (ANCo)</u> | 8. _____ |
| 4. <u>Ronald Hirschfeld (GEI)</u> | 9. _____ |
| 5. _____ | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Hydrology/Hydraulics</u>	<u>D. Deane/W. Guinan</u>	
2. <u>Structural Stability</u>	<u>S. Gilman</u>	
3. <u>Soils and Geology</u>	<u>R. Hirschfeld</u>	
4. _____		
5. _____		
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		

PERIODIC INSPECTION CHECKLIST

PROJECT CHESHAM POND DAM, N.H. DATE Sept. 13, 1979
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	
Current Pool Elevation	
Maximum Impoundment to Date	
Surface Cracks	None observed.
Pavement Condition	Not paved
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	Good
Horizontal Alignment	Good
Condition at Abutment and at Concrete Structures	Trespassing and bare soil on upstream slope next to left end of spillway
Indications of Movement of Structural Items on Slopes	None observed
Trespassing on Slopes	See "Condition at Abutment..." above
Sloughing or Erosion of Slopes or Abutments	See "Condition at Abutment..." above
Rock Slope Protection - Riprap Failures	No riprap
Unusual Movement or Cracking at or Near Toe	None observed
Unusual Embankment or Downstream Seepage	None observed
Piping or Boils	None observed
Foundation Drainage Features	None observed
Toe Drains	None observed
Instrumentation System	None observed
Vegetation	Trees on upstream slope near left end of spillway

PERIODIC INSPECTION CHECKLIST

PROJECT CHESHAM POND DAM, N.H. DATE Sept. 13, 1979

PROJECT FEATURE _____ NAME _____

DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p>a. Approach Channel</p> <p>Slope Conditions</p> <p>Bottom Conditions</p> <p>Rock Slides or Falls</p> <p>Log Boom</p> <p>Debris</p> <p>Condition of Concrete Lining</p> <p>Drains or Weep Holes</p> <p>b. Intake Structure</p> <p>Condition of Concrete</p> <p>Stop Logs and Slots - Trashrack</p>	<p>Not applicable</p> <p>Not visible beneath pond surface</p> <p>Not applicable</p> <p>None</p> <p>None</p> <p>Not visible</p> <p>None</p> <p>Good; a little surface erosion of concrete at waterline</p> <p>Weathered wood</p>

PERIODIC INSPECTION CHECKLIST

PROJECT CHESHAM POND DAM DATE Sept. 13, 1979
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - CONTROL TOWER</u></p> <p>a. Concrete and Structural</p> <p> General Condition</p> <p> Condition of Joints</p> <p> Spalling</p> <p> Visible Reinforcing</p> <p> Rusting or Staining of Concrete</p> <p> Any Seepage or Efflorescence</p> <p> Joint Alignment</p> <p> Unusual Seepage or Leaks in Gate Chamber</p> <p> Cracks</p> <p> Rusting or Corrosion of Steel</p> <p>b. Mechanical and Electrical</p> <p> Gate Operating Mechanism</p>	<p>Good</p> <p>Good—one hairline crack at change in direction of wall</p> <p>Minor erosion of concrete at water surface</p> <p>None</p> <p>Only at embedded items</p> <p>None visible</p> <p>Not applicable</p> <p>None visible</p> <p>See "condition of joints" above</p> <p>Railings are painted—good</p> <p>Other items are surface eroded</p> <p>Hand operated ratchet type, good condition—surface rust only. No indication of recent operation.</p> <p>Note: Wood decking over control tower is treated wood planking in fair condition; some evidence of weathering and warping.</p>

PERIODIC INSPECTION CHECKLIST

PROJECT CHESHAM POND DAM DATE SEPTEMBER 13, 1979

PROJECT FEATURE _____ NAME _____

DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u></p>	
<p>a. Approach Channel</p> <p> General Condition</p> <p> Loose Rock Overhanging Channel</p> <p> Trees Overhanging Channel</p> <p> Floor of Approach Channel</p>	<p>Good.</p> <p>None</p> <p>Some trees at edge of pond immediately upstream of low-level outlet</p> <p>Not visible beneath pond surface</p>
<p>b. Weir and Training Walls</p> <p> General Condition of Concrete</p> <p> Rust or Staining</p> <p> Spalling</p> <p> Any Visible Reinforcing</p> <p> Any Seepage or Efflorescence</p> <p> Drain Holes</p>	<p>Good</p> <p>Only at embedded steel items</p> <p>Minor surface erosion of concrete of training walls at water surface. Left training wall-old concrete portion spalled and eroded.</p> <p>None</p> <p>None</p> <p>None</p>
<p>c. Discharge Channel</p> <p> General Condition</p> <p> Loose Rock Overhanging Channel</p> <p> Trees Overhanging Channel</p> <p> Floor of Channel</p> <p> Other Obstructions</p>	<p>Fair</p> <p>None</p> <p>Trees overhanging channel between spillway and roadway and downstream of roadway. Boulders</p> <p>Culvert under roadway immediately downstream of spillway</p>

APPENDIX B
ENGINEERING DATA

BREED POND COMPANY

Marlboro N. H.
June 30 1949

State of New Hampshire
Water Resources Board
Concord, N. H.

Attention Mr. Walter G. White

Dear Mr. White:

Supplimenting our letter of June 3rd. we wish to say that we have contacted the Contractor who built this dam in 1921 and he has gone over it very carfully and states that most of this dam is built of very large boulders and could not possibly give way only on the top. The cause of the small leaks which were evident at the time of our last letter were in his estimation due to the fact that the bottom of this dam was planked and there was so me decay there.

This contractor is figuring out the best thing to do and will submit his report very soon.

In the mean time the water in this pond is down to a safe level due to the dry weather and the drawing from it for power purposes.

We will report more as soon as possible.

Very Truly yours,

Breed Pond Company



Robert C. Derby Clerk.

NEW HAMPSHIRE WATER CONTROL COMMISSION
DATA ON RESERVOIRS & PONDS IN NEW HAMPSHIRE

LOCATION AT DAM NO. 109.02
Town Harrisville: County Cheshire
Stream Chesham Pond
Basin—Primary Connecticut: Secondary Minnewawa Brook
Local Name Symonds Reservoir

DRAINAGE AREA

Controlled Sq. Mi.: Uncontrolled Sq. Mi.: Total 8.15 Sq. Mi.

ELEVATION vs. WATER SURFACE AREA vs. VOLUME

Point	Head Feet	Surface Area Acres	Volume Acre Ft.
(1) Max. Flood Height
(2) Top of Flashboards
(3) Permanent Crest
(4) Normal Drawdown	<u>8</u>	<u>74.20</u>
(5) Max. Drawdown
(6) Original Pond	<u>1154</u> U.S.G.S

Base Used: Coef. to change to U.S.G.S. Base

RESERVOIR CAPACITY

	Total Volume	Useable Volume
Drawdownft.ft.
Volumeac. ft.ac. ft.
Acre ft. per sq. mi.
Inches per sq. mi.


USE OF WATER Storage

OWNER Breed Pond Reservoir Co. Harrisville N.H.


REMARKS Condition Good Wing Wall Badly Cracked

CHESTER POND DAM - HARRIS, ILL.

109.02




PLAN



PROFILE

B-3



X-SECTION

**NEW HAMPSHIRE WATER CONTROL COMMISSION
DATA ON DAMS IN NEW HAMPSHIRE**

LOCATION STATE NO. 109.02
 Town Harrisville : County Cheshire
 Stream Chesham Pond
 Basin-Primary Connecticut : Secondary Minnewawa Brook
 Local Name Symonds Reservoir
 Coordinates—Lat. 42° 55' + 3,600 : Long. 72° 10' - 9,600

GENERAL DATA

Drainage area: Controlled.....Sq. Mi.: Uncontrolled Sq. Mi.: Total 8.15 Sq. Mi.
 Overall length of dam 86 ft.: Date of Construction 1921
 Height: Stream bed to highest elev. 13 ft.: Max. Structure 10.75 ft.
 Cost—Dam : Reservoir

DESCRIPTION

Waste Gates

Type
 Number 1 : Size 2.25 ft. high x 3.5 ft. wide
 Elevation Invert 8' : Total Area 7.875 sq. ft.
 Hoist

Waste Gates Conduit

Number : Materials
 Sizeft.: Length.....ft.: Area sq. ft.

Embankment

Type
 Height—Max. ft.: Min. ft.
 Top—Width : Elev. ft.
 Slopes—Upstream on : Downstream on
 Length—Right of Spillway : Left of Spillway

Spillway

Materials of Construction
 Length—Total 46.5 ft.: Net ft.
 Height of permanent section—Max. 10.2 ft.: Min. 10.75 ft.
 Flashboards—Type : Height 19" ft.
 Elevation—Permanent Crest : Top of Flashboard
 Flood Capacity 605 cfs.: 75 cfs/sq. mi.

Abutments

Materials:
 Freeboard: Max. 2.25 ft.: Min. 2.15 ft.

Headworks to Power Level.—(See "Data on Power Development")

OWNER Breed Pond Reservoir Co. Harrisville N.H.

REMARKS

Storage

Publication By A. A. N. & R. L. T Date December 9, 1938.

Rec'd 10/15/38

WATER CONTROL COMMISSION
STATE OF NEW HAMPSHIRE

Concord, New Hampshire

October 13, 1938.

Jacobson	
Holmgren	✓
<i>Edson</i>	
Received	
Date	
File No.	

Breed Pond Reservoir Co.,
Marlboro, N H

Known as Symonds Pond

RE: Chesham Pond Dam. N. C. C. No. 109.02

Gentlemen:

In order that we may determine the magnitude and extent of the flood of September 21-24 just passed, we are requesting the various dam owners in the State to supply us with the following information:

1. Was this dam injured? Ans. no
2. If so, to what extent? Ans. _____
3. Did all flashboards go out? Ans. _____
4. What was the maximum height of water over the permanent crest of spillway? Ans. Est. 48"
5. At what day and hour did the maximum flood height reach your dam? Ans. _____

6. Any other interesting information regarding the flood or rain fall may be given on the back of this sheet, or attach sheets.

Will you please return this letter with as much information as you can give us as promptly as possible. A self-addressed envelope is attached hereto.

We thank you for your cooperation.

Very truly yours,

Richard S. Holmgren

Richard S. Holmgren
Chief Engineer

CDC:GMB
Enc.

B-5


Harrisville

Inspected June 13, 1930.

Simmonds Pond, also known as Chesham Pond, owned by Breeds Pond Association formerly owned by Whitney.

Small concrete dam built in 1921 near railroad and highway. The main dam seemed dry and in good condition. There were some small cracks on the west wing wall just east of the gate outlet. The west wing wall was quite badly cracked about sixteen feet from the gage board. No serious results however, as the earth back of the wing walls is in quite good condition.

No picture.



PLAN


NOTE ALL ELEVATIONS ARE BASED ON SPILLWAY CREST ASSUMED ELEVATION OF 1154 N.G.D.

ANDERSON-NICHOLS & Co, Inc
CONCORD NEW HAMPSHIRE
U.S. ARMY ENGINEER DIVISION, ENGLAND
CORPS OF ENGINEERS
WALTHAM, MA

NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS


CHESHAM POND DAM

DATE: 11/15/64
BY: J. H. [unclear]




SECTION A-A

SECTION B-B



ELEVATION

CHESTNUT POND - TOP OF DAILY WEIR SECTION



1160

D-4

1150

1140

-100

0

100


200

300

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

- FREE OVERFLOW OGEE CREST
- CONTRACTED WINGWALL D/S ON EASTERLY SIDE
- PIPE ARCH BENEATH ROAD IMMEDIATELY D/S WILL CONTROL AT HIGH DISCHARGE

Plan of Spillway




Normal Pool = Spillway Crest = 1154 msl from quad
 $L = 41'$ Take $C = 3.5$ Top of Dam = 1156.4 (low point)

$$Q = CLH^{3/2} = (3.5)(41)H^{3/2} = 143.5 H^{3/2}$$

Dam Embankment - see attached sketch.

$$Q = CLH^{3/2} \quad L \text{ varies with } H \text{ take } C = 2.5$$

- Determine when (or if) pipe arch capacity controls
 Assume 31 concrete radius for pipe arch



**NATIONAL PROGRAM OF INSPECTION OF
NON-FED. DAMS**

**CHESHAM POND DAM
HARRISVILLE, NEW HAMPSHIRE**

REGIONAL VICINITY MAP


MARCH 1980

**DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS**

ANDERSON-NICHOLS & CO., INC.


CONCORD, NH

SCALE IN MILES




**MAP BASED ON U.S.G.S. 7.5 MINUTE QUADRANGLE
SHEET. MONADNOCK, N.H. 1949.**

APPENDIX D
HYDROLOGIC AND HYDRAULIC COMPUTATIONS




October 1979


Figure 14 - Overview of the reach between the two road crossings shown in Figures 11 and 12 above.



October 1979
Figure 12 - Overview of the road crossing located
 $\frac{1}{2}$ mile downstream of the dam.




October 1979
Figure 13 - Overview of the road crossing located
one mile downstream of the dam.



September 13, 1979
Figure 10 - Looking downstream at pipe arch from
low-level outlet structure.



September 13, 1979
Figure 11 - View of the discharge channel downstream
of the pipe arch.



September 13, 1979
Figure 8 - Looking at the control mechanism for the
low-level gated outlet.



September 13, 1979
Figure 9 - Looking into the upstream reservoir from
the dam.



September 13, 1979

Figure 6 - Looking southeasterly across the crest of the embankment.




September 13, 1979


Figure 7 - View of downstream face of northwest end of spillway and low-level outlet structure.



September 13, 1979
Figure 4 - Seepage at intersection of highway culvert
headwall and training wall on southeast
side of spillway discharge channel.



September 13, 1979
Figure 5 - Close-up of spalled area on training wall
at southeast abutment.




September 13, 1979
Figure 2 - Looking southeast across crest of the dam.



September 13, 1979
Figure 3 - Looking northwest across the crest of dam.

1



Anderson-Nichols & Co., Inc. CONCORD NEW HAMPSHIRE		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MA.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
PHOTO INDEX			
MINNEWAWA BROOK		NEW HAMPSHIRE	
		SCALE: NOT TO SCALE	
		DATE: MARCH 1980	

APPENDIX C
PHOTOGRAPHS

JOB NO.

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

DESIGN FOR CHANNEL DESIGN

Minimum elevation 1156.4 $Q = 0$ - @ elev. 1156.7 $L = 25$ avg $H = .2$ TAKE $C = 2.5$

$$Q = CLH^{3/2} = (2.5)(25)(.2)^{3/2} = 6 \text{ cfs}$$

- @ elev. 1157.0 $L = 32$ avg $H = .4$ $Q = (2.5)(32)(.4)^{3/2} = 20$ - @ elev. 1157.2 $L = 40$ avg $H = .5$ $Q = (2.5)(40)(.5)^{3/2} = 35$ - @ elev. 1157.5 $L = 54$ avg $H = .7$ and $L = 45$ avg $H = .3$

$$Q = (2.5)(54)(.7)^{3/2} + (2.5)(45)(.3)^{3/2} = 98$$

- @ elev. 1158.0 $L = 60$ avg $H = .9$ and $L = 55$ avg $H = .7$ and
 $L = 24$ avg $H = .3$

$$Q = (2.5)(60)(.9)^{3/2} + (2.5)(55)(.7)^{3/2} + (2.5)(24)(.3)^{3/2} = 218$$

- @ elev. 1158.5 $L = 60$ avg $H = 1.1$ and $L = 45$ avg $H = .7$
 $L = 30$ avg $H = .3$

$$Q = (2.5)(60)(1.1)^{3/2} + (2.5)(45)(.7)^{3/2} + (2.5)(30)(.3)^{3/2} = 480$$

- @ elev. 1159.0 $L = 60$ avg $H = 1.5$ and $L = 72$ avg $H = 1.5$
 $L = 36$ avg $H = 1.0$

$$Q = (2.5)(60)(1.5)^{3/2} + (2.5)(72)(1.5)^{3/2} + (2.5)(36)(1.0)^{3/2} = 814$$

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
 4 IN. SCALE

1
 2 - @ elev. 1159.5 $L=60$ $H=2.4$ and $L=85$ $H=1.9$
 3 and $L=41$ $H=1.2$

$$4 \quad Q = (2.5)(60)(2.4)^{3/2} + (2.5)(85)(1.9)^{3/2} + (2.5)(41)(1.2)^{3/2} = 1249$$

5
 6
 7 - @ elev. 1166.0 $L=60$ $H=2.9$ and $L=96$ $H=2.2$
 8 and $L=48$ $H=1.6$

$$9 \quad Q = (2.5)(60)(2.9)^{3/2} + (2.5)(96)(2.2)^{3/2} + (2.5)(48)(1.6)^{3/2} = 1767$$

10
 11
 12 - @ elev. 1161.0 $L=60$ $H=3.9$ and $L=180$ $H=2.5$
 13 and $L=70$ $H=2.2$

$$14 \quad Q = (2.5)(60)(3.9)^{3/2} + (2.5)(180)(2.5)^{3/2} + (2.5)(70)(2.2)^{3/2} = 3505$$

15
 16
 17 - @ elev. 1162.0 $L=60$ $H=4.9$ and $L=140$ $H=2.8$
 18 and $L=97$ $H=2.7$

$$19 \quad Q = (2.5)(60)(4.9)^{3/2} + (2.5)(140)(2.8)^{3/2} + (2.5)(97)(2.7)^{3/2} = 4343$$

20
 21
 22 - @ elev. 1163.2 $L=60$ $H=6.1$ and $L=160$ $H=3.5$
 23 and $L=132$ $H=3.5$

$$24 \quad Q = (2.5)(60)(6.1)^{3/2} + (2.5)(160)(3.5)^{3/2} + (2.5)(132)(3.5)^{3/2} = 7040$$

25
 26
 27 @ elev. 1164.0 $L=60$ $H=6.9$ and $L=190$ $H=4.1$
 28 and $L=155$ $H=4.1$

$$29 \quad Q = (2.5)(60)(6.9)^{3/2} + (2.5)(190)(4.1)^{3/2} + (2.5)(155)(4.1)^{3/2} = 9879$$

30
 31
 32
 33 @ elev. 1165.0 $L=60$ $H=7.9$ and $L=210$ $H=4.8$
 34 and $L=185$ $H=4.8$

$$35 \quad Q = (2.5)(60)(7.9)^{3/2} + (2.5)(210)(4.8)^{3/2} + (2.5)(185)(4.8)^{3/2} = 13715$$

JOB NO.

CHESAPEE POND


SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
 1/4 IN. SCALE

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39

ELEVATION (FT)	SPILLWAY			SLUICeway		PIPE ARCH			DAM CREST Q	COMBINED Q
	L	H	Q	H	Q	Q	H	ELEV.		
1154.0	41	0	0							0
1154.2	41	.2	13							13
1154.5	41	.5	51							51
1155.0	41	1.0	144							144
1155.7	41	1.7	318							318
1156.4	41	2.4	534						0	534
1156.7	40	2.7	621						4	627
1157.0	39	3.0	709						20	729
1157.2	39	3.2	781	0	0	781	7.3	1148.1	35	816
1157.5	38	3.5	871	.3	4	875	7.9	1148.7	98	873
1158.0	37	4.0	1036	.8	19	1055	8.9	1149.7	218	1273
1158.5	36	4.5	1203	1.3	39	1242	10.2	1151.0	480	1722
1159.0	35	5.0	1409	1.8	63	1472	11.3	1152.1	814	2286
1159.5	34	5.5	1535	2.3	91	1626	12.3	1153.1	1249	2875
1160.0	33	6.0	1697	2.8	123	1820	13.8	1154.6	1767	3587
1161.0	32	7.0	2074	3.8	194	2168	16.3	1157.1	3505	5673
1163.2*						2809	22.4	1163.2*	7040	9849
1164.0						3100	23.2	1164.0	9879	12979
1165.0						3300	24.2	1165.0	13715	17015

* PIPE ARCH CONTROLS AT AND ABOVE THIS ELEVATION

Using the above trials establish a discharge rating curve for the dam.



JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
SCALE 1/4

$$Q_{p1} = 7,000 \text{ cfs} \Rightarrow \text{elevation } 1161.6' \text{ MSL}$$

STEP # 2b Determine the volume of surcharge in inches of runoff. To do this a storage vs elevation curve must be determined. (See pages _____).

$$Q_{p1} \Rightarrow 7,000 \text{ cfs} \Rightarrow 1161.6' \text{ MSL} \Rightarrow 1200 \text{ AC-FT}$$

$$\text{Normal Storage (spillway crest)} \Rightarrow 460 \text{ AC-FT}$$

$$740 \text{ AC-FT} \times \frac{1}{8.2 \text{ mi}^2} \times \frac{1 \text{ mi}^2}{640 \text{ AC}} \times \frac{12 \text{ in}}{\text{ft}} = 1.69'' \text{ runoff (STOR}_1)$$

STEP # 2c

$$Q_{p2} = Q_{p1} \left(1 - \frac{\text{STOR}_1}{9.5}\right) = 7,000 \left(1 - \frac{1.69''}{9.5''}\right) = 5,750 \text{ cfs}$$

STEP # 3a Determine surcharge height and

STOR₂ to pass Q_{p2}

$$5,750 \text{ cfs} \Rightarrow 1161' \text{ MSL} \Rightarrow 1110 \text{ AC-FT}$$

$$650 \text{ AC-FT} \times \frac{1}{8.2 \text{ mi}^2} \times \frac{1 \text{ mi}^2}{640 \text{ AC}} \times \frac{12 \text{ in}}{\text{ft}} = 1.49'' \text{ runoff (STOR}_2)$$

STEP # 3b Average STOR₁ & STOR₂ and determineQ_{p3}

$$\frac{1.69'' + 1.49''}{2} = 3.18 \div 2 = 1.59'' \text{ runoff} \approx 0.13'$$

$$0.13' \times \frac{1}{8.2 \text{ mi}^2} \times \frac{1 \text{ mi}^2}{640 \text{ AC}} \times \frac{12 \text{ in}}{\text{ft}} = 682 \text{ AC-FT}$$

$$682 \text{ AC-FT} + 460 \text{ AC-FT} = 1142 \text{ AC-FT} \Rightarrow 1161.2' \text{ MSL}$$

$$1161.2' \text{ MSL} \Rightarrow 6,000 \text{ cfs} \Rightarrow \text{Routed test flood outflow}$$

Top of dam = 1156.4' MSL therefore dam will be overtopped by 4.8 feet during test flood. Maximum spillway capacity at top of dam is 535 cfs which is only 9 percent of the routed test flood outflow.

JOB NO.

RES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
I. SCALE

STORAGE - ELEVATION

- FROM KEENE GAS-ELECTRIC DATA

@ Normal Pool el. 1154 A = 70 ac Vol = 20 mil/ft³
= 460 ac-ft

- Total draw 14' - Take invert of dam @ 1140.0

- FROM PLANIMETER


@ contour 1160 A = 105 ac.

$$\Delta S = \frac{105 + 70}{2} \times 6 = 525 \text{ ac ft}$$

$$\text{Total} = 525 + 460 = 985$$

Storage-Elevation Points

el.	Storage
1140	0
1154	460
1160	985



1170

1160

D-11

1150

1140

0 200 400 600 800 1000 1200 1400

JOB NO. **HEC-1**
SUMMARY

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30


CASE 5 CHESAM POND FAILS

STA A2

CHILDS BOG DAM

$Q_p = 183$

EL. = 1376.5



INITIAL WSEL
@ TOP OF DAM 1376.5

STA A4

INLET TO SEAWATER RESERVOIR

$Q_p = 176$

EL. = 1201.2

STA A6


SEAWATER RESERVOIR DAM

INITIAL WSEL @ TOP OF

DAM 1204.3

$Q_p = 790$

EL. = 1204.3



Min el. 1200

STA A8

INLET TO CHESAM POND

$Q_p = 790$

EL. = 1162.5

STA A10

CHESAM POND DAM

INITIAL WSEL @

TOP OF DAM 1156.4

$Q_b = 6963$

6 houses at or below 1162.0



Min el. 1158

STA A11


$Q_p = 6466$

EL. = 1142.2

STA A12

$Q_p = 5508$

EL. = 1140.1



1 House @ 1140

Min el. 1130

1 House @ 1144
1 House @ 1142
1 TRAILER @ 1139
(located 200 ft. up of dam)

1/2 MI

Min el. 1134

D-12

CHESHAM FAILS

.....
 IUCD HYDROGRAPH PACKAGE (IHC-1)
 DAM SAFETY DESIGN JULY 1978
 LAST MODIFICATION 26 FEB 79

1 A1 CHILDS BOG - SEAWER RESERVOIR - CHESAP POND DOWNSTREAM HAZARD EVALUATION
 2 A2 NEW HAMPSHIRE DAM NUMBERS 00096,
 3 A3 SEGMENT 3 ROUTE [REDACTED] INFLOW HYDROGRAPH FROM SEAWER [REDACTED] THROUGH CHESAP

	0	100	0	5	0	0	0	0	0
4	U	100	0	5	0	0	0	0	0
5	B1	5							
6	J	2	1	1					
7	J1	1							
8	P	0	AP						
9	V1	ROUTED [REDACTED]	HYDROGRAPH FROM SEAWER USED AS INFLOW TO CHESAM						
10	P	-1							
11	N	540.	562.	840.	710.	638.	639.	603.	568.
12	N	545.	525.	506.	471.	454.	438.	423.	408.
13	N	381.	360.	356.	344.	321.	311.	301.	291.
14	N	273.	264.	256.	248.	240.	233.	226.	219.
15	N	213.	209.	206.	200.	197.	194.	191.	188.
16	N	182.	179.	177.	174.	169.	166.	164.	161.
17	N	156.	154.	151.	149.	144.	142.	140.	138.
18	N	134.	132.	130.	128.	124.	122.	120.	118.
19	N	115.	113.	111.	108.	106.	105.	103.	101.
20	N	98.	97.	95.	94.	91.	90.	88.	87.
21	K1	1	A10						
22	K1	ROUTE COMBINED HYDROGRAPH THROUGH CHESAP POND							
23	V								
24	V4	1154.	1154.2	1154.5	1155.	1155.7	1156.4	1156.7	1157.2
25	V4	1158.	1158.5	1159.	1159.5	1160.	1161.	1163.2	1164.
26	V5	0.	13.	51.	144.	318.	534.	627.	729.
27	V5	1273.	1722.	2266.	2875.	3587.	5673.	9849.	12979.
28	SE	0.	180.	300.	460.	630.	700.	985.	1320.
29	SE	1140.	1148.	1151.	1155.	1156.4	1157.2	1160.	1162.5
30	SE	1154.							
31	SE	1154.							
32	IR	50.	0.	1140.	1.0	1156.4	1156.4		
33	IR	50.	0.	1140.	1.0	1156.4	1170.		
34	K1	ROUTE HYDROGRAPH DOWN MINNEVAVA BROOK FOR 1/2 MILE							
35	V								
36	V1	1							
37	V6	.1	.04	.1	1139.	1155.	2500.	.0024	
38	V7	550.	1153.	700.	1140.	880.	1138.	1000.	1139.
39	V7	1050.	1140.	1200.	1150.	1280.	1155.		
40	K1	ROUTE HYDROGRAPH DOWN MINNEVAVA BROOK FOR ANOTHER 1/2 MILE							
41	V								
42	V1	1							
43	V6	.03	.03	.03	1130.	1145.	2500.	.0016	
44	V7	950.	1145.	1000.	1140.	1900.	1138.	1980.	1134.
45	V7	2020.	1139.	2080.	1140.	2105.	1145.		
46	K1	ROUTE HYDROGRAPH ANOTHER 7000 FT DOWN MINNEVAVA BROOK							
47	V								
48	V1	1							
49	V6	.1	.03	.03	1130.	1145.	2500.	.0016	
50	V7	950.	1145.	1000.	1140.	1900.	1138.	1980.	1134.
51	V7	2020.	1139.	2080.	1140.	2105.	1145.		

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 INITIAL VALUE SPILLWAY CREST TOP OF DAM
 ELEVATION 1156.40 1154.00 1156.40
 STORAGE 630. 420. 630.
 OUTFLOW 534. 0. 534.

RATIO OF PHF 1.00
 MAXIMUM RESERVOIR DEPTH OVER DAM 0.00
 MAXIMUM STORAGE AC-FT 630.
 MAXIMUM OUTFLOW CFS 6963.
 DURATION OVER TCP HOURS 0.00
 TIME OF MAX OUTFLOW HOURS 1.00
 TIME OF FAILURE HOURS 0.00

PLAN 2 INITIAL VALUE SPILLWAY CREST TOP OF DAM
 ELEVATION 1156.40 1154.00 1156.40
 STORAGE 630. 420. 630.
 OUTFLOW 534. 0. 534.

RATIO OF PHF 1.00
 MAXIMUM RESERVOIR DEPTH OVER DAM 0.07
 MAXIMUM STORAGE AC-FT 636.
 MAXIMUM OUTFLOW CFS 555.
 DURATION OVER TCP HOURS 1.67
 TIME OF MAX OUTFLOW HOURS 0.83
 TIME OF FAILURE HOURS 0.00

D-11

PLAN 1 STATION A11
 RATIO 1.00
 MAXIMUM FLOW,CFS 6466.
 MAXIMUM STAGE,FT 1142.2
 TIME HOURS 1.08

PLAN 2 STATION A11
 RATIO 1.00
 MAXIMUM FLOW,CFS 542.
 MAXIMUM STAGE,FT 1137.4
 TIME HOURS 1.17

PLAN 1 STATION A12
 RATIO 1.00
 MAXIMUM FLOW,CFS 550.
 MAXIMUM STAGE,FT 1140.1
 TIME HOURS 1.25

PLAN 2 STATION A12
 RATIO 1.00
 MAXIMUM FLOW,CFS 550.
 MAXIMUM STAGE,FT 1140.1
 TIME HOURS 1.25

bl.

PLAN 1 STATION A13

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
1.00	5160	1086.0	1.50

PLAN 2 STATION A13


RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
1.00	590	1070.6	1.92

NO. 3273-23 Chesham Pond Dam

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29

Evaluate capacity of box culvert located about 1/2 mile downstream of Chesham Dam.

Road width = 35'



Use the orifice equation to determine the capacity of the culvert at top of road.

$$Q = CA \sqrt{2gh}$$

$$Q = (0.8)(101.5) \sqrt{64.4 \times 3.2} = 1,165 \text{ cfs}$$

Breach Q through reach ≈ 6470 cfs. Therefore, the culvert will not carry the breach Q . Weir flow will occur over the road along with pressure flow through the culvert. Develop a rating curve for the weir cross section shown on Sheet 3. Use weir equation $Q = CLH^{3/2}$, where $c \approx 2.7$.

Stage (ft. above invert)	Discharge (cfs)
0	0
6.4 (top road)	$Q_{\text{ORIFICE}} = 1,165$
7.4	$Q_{\text{ORIFICE}} = (0.8)(101.5) \sqrt{64.4 \times 4.2}$ $Q_{\text{ORIFICE}} = 1,335$ $Q_{\text{WEIR}} = 2.7(100)(1.0)^{3/2} +$ $2.7(10)(1.0)^{3/2}$ $= 297$ $Q_{\text{TOTAL}} = 1,632$

0

Discharge (cfs)

0

6.4 (top road)

$$Q_{\text{ORIFICE}} = 1,165$$

7.4

$$Q_{\text{ORIFICE}} = (0.8)(101.5) \sqrt{64.4 \times 4.2}$$

$$Q_{\text{ORIFICE}} = 1,335$$

$$Q_{\text{WEIR}} = 2.7(100)(1.0)^{3/2} +$$

$$2.7(10)(1.0)^{3/2}$$

$$= 297$$

$$Q_{\text{TOTAL}} = 1,632$$

2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Stage

Discharge (cfs)

8.4

$$Q_{ORIFICE} = (0.8)(101.5)\sqrt{6.4 \times 5.2} = 1485$$

$$Q_{WEIR} = 2.7(100)(2.0)^{3/2} + 2.7(\frac{1}{2}16)(2.0)^{3/2} + 2.7(\frac{1}{2}20)(2.0)^{3/2}$$

$$= 901$$

$$Q_{TOTAL} = 2,386$$

9.4

$$Q_{ORIFICE} = (0.8)(101.5)\sqrt{6.4 \times 6.2} = 1,623$$

$$Q_{WEIR} = 2.7(100)(3.0)^{3/2} + 2.7(\frac{1}{2}25)(3.0)^{3/2} + 2.7(\frac{1}{2}30)(3.0)^{3/2} = 1,789$$

$$Q_{TOTAL} = 3,412$$

11.4

$$Q_{ORIFICE} = (0.8)(101.5)\sqrt{6.4 \times 8.2} = 1,866$$

$$Q_{WEIR} = 2.7(100)(5.0)^{3/2} + 2.7(\frac{1}{2}41)(5.0)^{3/2} + 2.7(\frac{1}{2}50)(5.0)^{3/2} = 4,392$$

$$Q_{TOTAL} = 6,258$$

12.4

$$Q_{ORIFICE} = (0.8)(101.5)\sqrt{6.4 \times 9.2} = 1,976$$

$$Q_{WEIR} = 2.7(100)(6.0)^{3/2} + 2.7(\frac{1}{2}50)(6.0)^{3/2} + 2.7(\frac{1}{2}60)(6.0)^{3/2} = 6,151$$

$$Q_{TOTAL} = 8,127$$


Using the above trials, establish a stage/discharge curve. (See Sheet 4.)

Breach $Q = 6,470$ cfs Stage = 11.5 feet

Precedent $Q = 535$ cfs Stage = 4.2 feet

Increase due to breach would be 7.3 feet. This increase could cause property damage to two houses located on the right bank of the channel. Loss of life would probably not occur. Damage to roadway and the structure could occur. Road would be overtopped by about 5.1 feet of water. One trailer/shack located 200 feet d/s the dam could be inundated by 3.2 feet of water. Loss of 1 or 2 lives is possible. (See HEC-1 summary Schematic)

Sheet 3/8
L. Williams
1930




FEET ABOVE TOP OF ROAD

STATIONING IN FEET

61-D

Sheet 4/8
L. Williams
4/10/20



CHESHAM POND DAM
DIS HAZARD ANALYSIS
1st Culvert d/s of Chesham
RATING CURVE

DISCHARGE (cfs)

STAGE HEIGHT IN FEET
D-20


JOB NO. _____

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1 IN. SCALE

1 Evaluate capacity of box culvert located about
2 one mile downstream of Chesham Pond Dam.
3

4 Road width = 18'

5 Gravel Road on left side



6 Use the orifice equation to determine the
7 capacity of the culvert at top of road.
8

$$Q = CA\sqrt{2gh}$$

$$Q = (0.8)(10.5)\sqrt{64.4 \times 5.25} = 1493 \text{ cfs}$$

9 Breach Q through reach $\approx 5,500$ cfs. Therefore,
10 culvert will not carry breach Q . Weir flow
11 will occur over the road along with pressure
12 flow through the culvert. Develop a rating curve
13 for the weir cross section shown on Sheet 7.

14 Use weir equation $Q = CLH^{3/2}$ to rate flow over
15 roadway. Assume 'c' is ≈ 2.7 .

16 Stage (ft. above invert)

16 Discharge (cfs)

17 0

17 0

18 10.5 (top of road)

$$Q_{\text{ORIFICE}} = 1493$$

19 11.5

$$Q_{\text{ORIFICE}} = (0.8)(10.5)\sqrt{64.4 \times 6.25} = 1629$$

$$Q_{\text{WEIR}} = 2.7(211)(1.0)^{3/2} + 2.7(1/2 \times 20)(1.0)^{3/2} + 2.7(25)(1.0)^{3/2} = 603$$

$$Q_{\text{TOTAL}} = 2096 \text{ cfs}$$

20 D-21

JOB NO.

AREAS
IN. SCALE 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 301 Stage (ft. above invert) Discharge (cfs)
2

3 12.5

$$Q_{ORIFICE} = (0.8)(101.5)\sqrt{64.4 \times 7.25} = 1,755$$

$$Q_{WEIR} = 2.7(211)(2.0)^{3/2} + 2.7(24)(2.0)^{3/2} + 2.7(210)(2.0)^{3/2} = 1,806$$

$$Q_{TOTAL} = 3,561 \text{ cfs}$$

8 14.0

$$Q_{ORIFICE} = (0.8)(101.5)\sqrt{64.4 \times 8.75} = 1,928$$

$$Q_{WEIR} = 2.7(211)(3.5)^{3/2} + 2.7(275)(3.5)^{3/2} + 2.7(216)(3.5)^{3/2} = 4,535$$

$$Q_{TOTAL} = 6,463$$


13 Using the above trials, establish a stage/discharge
14 relationship. See curve on sheet 8.
1516 Breach $Q = 5,500$ cfs Stage = 13.5 feet17 Antecedent $Q = 535$ cfs Stage = 5.2 feet

18 Increase due to breach would be = 8.3 feet. This

19 would result in the gravel roadway being
20 overtopped by 3 feet. One house located
21 in this reach may suffer some property
22 damage. Loss of life is unlikely. A large storage
23 area exists in this reach; the wave would be
24 attenuated in this area. The 2nd road crossing
25 would act as a dam and would fill up this
26 area. After overtopping of the roadway, the
27 lessened breach discharge would continue
28 downstream.
2930 This analysis, in conjunction with the HEC-1
31 analysis, supports the appropriate hazard
32 classification of Chesham as Significant. A
33 breach could possibly result in the loss
34 of 1-2 lives and could cause appreciable
35 property damage.
36
37
38
39

Sheet 7/8
L. Williams
-10/80

CHESHAM POND DAM
WEIR SECTION - 2ND d/s culvert - D/s HAZARD ANALYSIS




HEIGHT ABOVE ROAD (FEET)

DISTANCE IN FEET

D-23

Sheet 8/8
L. Williams
4/10/30.

CHESHAM POND DAM
RATING CURVE - 2ND d/s culvert - D/S HAZARD ANALYSIS



D-24

APPENDIX E
INFORMATION AS
CONTAINED IN THE NATIONAL
INVENTORY OF DAMS

NOT AVAILABLE AT THIS TIME

END

FILMED

8-85

DTIC