

AD-A169 440

Installation Restoration General Environmental Technology Development

REPORT NO. AMXTH-TE-CR-86074

Task 11. Pilot Investigation of Low Temperature Thermal Stripping of Volatile Organic Compounds (VOC's) From Soil

Volume 2 - Appendices

June 1986

Distribution unlimited approved for public release

Prepared for:
U.S. ARMY TOXIC AND HAZARDOUS MATERIALS AGENCY
Aberdeen Proving Ground (Edgewood Area), Maryland 21010

WESTON
DESIGNERS CONSULTANTS

Ray F. Weston Inc.
West Chester
Pennsylvania

DTIC FILE COPY

86 7 2 040

20030122122

DTIC
ELECTE
JUL 03 1986
S D

TABLE OF CONTENTS

	<u>Page</u>
APPENDIX A - ORGANIC WASTE CHARACTERISTICS OF SITE SOILS AT LEAD (DETERMINED DURING PRELIMINARY INVESTIGATIONS)	A-1
APPENDIX B - GRAIN SIZE GRADATION CURVES CORRESPONDING TO FILL SOIL AND NATIVE SOIL	B-1
APPENDIX C - AIR SAMPLING TECHNIQUES	C-1
APPENDIX D - FEDERAL REGULATIONS	D-1
APPENDIX E - ANALYTICAL METHODS	E-1
APPENDIX F - FIELD/ANALYTICAL DATA	F-1
APPENDIX G - MASS/ENERGY BALANCES	G-1
APPENDIX H - SUPPLEMENTAL DATA	H-1
APPENDIX I - STATISTICAL ANALYTICAL APPROACH	I-1

Accession For	
NTIS CRA&I	☒
DTIC TAB	☐
Unannounced	☐
Justification	
By	
Distribution	
Availability Codes	
Dist	Availability Codes
A-1	

WESTON

APPENDIX A

ORGANIC WASTE CHARACTERISTICS OF SITE SOILS AT LEAD
(DETERMINED DURING PRELIMINARY INVESTIGATIONS)

0000A

TABLE A-1. CONCENTRATION RANGE OF ORGANIC COMPOUNDS DETERMINED TO BE PRESENT AT THE EAST PATROL ROAD DISPOSAL AREA*

Compound	Area A	Area B	Concentration (ug/L)			
			Area E	Area K-1	Area K-2	Area K-3 K-4
Acetone						
Benzene		0.1-4		0.1-0.7	0.2-0.7	0-0.1
Bromomethane						
Bromotoluene						
2-Butanone						
Carbon disulfide						
Carbon tetrachloride	0-20			0-0.6		
Chlorobenzene						
Chlorobromomethane						
Chloroethane						
2-Chloroethylvinyl ether						
Chloroform				0-0.2	0.4-0.7	
Chloromethane						
Dichlorobromomethane						
1,1-Dichloroethane						
1,2-Dichloroethane						
1,1-Dichloroethylene				0-1		10-20
1,2-Dichloropropane				0-10		
1,3-Dichloropropene				9-10	0-20	
1,1,2,2-Tetrachloroethane	200-1000	2-8		0.8-10	0.7-4	
Ethylbenzene						
2-Hexanone	0.6-7					
Methylene chloride						
4-Methyl-2-pentanone						
Styrene						
1,1,2,2-Tetrachloroethane				0.2-800	0-0.2	0-1
Tetrachloroethylene						
Toluene	1-10	0-2		1-100	0.9-7	
1,2-Dichloroethylene	0-200	0-1		50-2000		
1,1,2,2-Tetrachloroethane						
1,1,1-Trichloroethane	0-0.9					0-0.4
Trichloroethylene	0-0.8			1-500		0.8-40 0-2

*Source: Lettering Army Depot Remedial Investigation and Feasibility Study, WESTON Report No. DRXTH-AS-8-8-17, February 1981.

TABLE A-1. (CONTINUED)

Compound	Concentration (ug/L)				
	Area A	Area B	Area E	Area K-1	Area K-2 K-3 K-4
1. Volatiles as Hazardous Substance List (HSL) (continued)					
Vinyl Acetate	0-30			5 200	
Vinyl Chloride	0-7000	3-100		1-700	0-40
Xylene					
Total Volatiles	201.6- 8298.7	5.1-115		70.1- 4334.5	2.2- 72.6 10.8- 61.4 0-3.1
2. Others					
Ethyl Methyl Benzene		0-10		0-3	
Methyl Cyclohexane	0-7				
Trichlorofluoromethane	0-0.5	1-7		2-30	
Trimethyl Benzene	0-20				
Trimethyl Pentane	2-100	4-7000		2-400	0-8
Various Hydrocarbon					
Total Others	2-127.5	5-7017		4-433	0-8
TOTAL	203.6- 8426.2	10.1- 7132		74.1- 4767.5	2.2- 80.6 10.8- 61.4 0-3.1

TABLE A-2. VOLATILE ORGANIC COMPOUNDS (VOC'S) INCLUDED ON THE HAZARDOUS SUBSTANCE LIST (HSL)

Volatile organic compounds	Detection limits*	
	Low water ^a ug/L	Low soil/ sediment ^b ug/Kg
1. Chloromethane	10	10
2. Bromomethane	10	10
3. Vinyl Chloride	10	10
4. Chloroethane	10	10
5. Methylene Chloride	5	5
6. Acetone	10	10
7. Carbon Disulfide	5	5
8. 1,1-Dichloroethene	5	5
9. 1,1-Dichloroethane	5	5
10. Trans-1,2-Dichloroethene	5	5
11. Chloroform	5	5
12. 1,2-Dichloroethane	5	5
13. 2-Butanone	10	10
14. 1,1,1-Trichloroethane	5	5
15. Carbon Tetrachloride	5	5
16. Vinyl Acetate	10	10
17. Bromodichloromethane	5	5
18. 1,1,2,2-Tetrachloroethane	5	5
19. 1,2-Dichloropropane	5	5
20. Trans-1,3-Dichloropropene	5	5
21. Trichloroethene	5	5
22. Dibromochloromethane	5	5
23. 1,1,2-Trichloroethane	5	5
24. Benzene	5	5
25. Cis-1,3-Dichloropropene	5	5

*Medium Water Contract Required Detection Limits (CRDL) for Volatile HSL Compounds are 100 times the individual Low Water CRDL.

*Medium Soil/Sediment Contract Required Detection Limits (CRDL) for Volatile HSL Compounds are 100 times the individual Low Soil/Sediment CRDL.

*Detection limits listed for soil/sediment are based on wet weight.

TABLE A-2. (CONTINUED)

Volatile organic compounds	Detection limits*	
	Low water ^a ug/L	Low soil/ sediment ^b ug/Kg
26. 2-Chloroethyl Vinyl Ether	10	10
27. Bromoform	5	5
28. 2-Hexanone	10	10
29. 4-Methyl-2-pentanone	10	10
30. Tetrachloroethene	5	5
31. Toluene	5	5
32. Chlorobenzene	5	5
33. Ethyl Benzene	5	5
34. Styrene	5	5
35. Total Xylenes	5	5

^aMedium Water Contract Required Detection Limits (CRDL) for Volatile HSL Compounds are 100 times the individual Low Water CRDL.

^bMedium Soil/Sediment Contract Required Detection Limits (CRDL) for Volatile HSL Compounds are 100 times the individual Low Soil/Sediment CRDL.

*Detection limits listed for soil/sediment are based on wet weight.

TABLE A-3. CONCENTRATION RANGE OF VOLATILE ORGANIC COMPOUNDS (VOC'S) DETERMINED
TO BE PRESENT IN AREA K-1 (BASED ON TESTING PERFORMED ON 10-12 JUNE 1985)*

Compound	Concentration (ug/g)**			
	Borehole 1	Borehole 2	Borehole 3	Borehole 4
<u>1. Volatiles on Hazardous Substance List (HSL)</u>				
Acetone				
Benzene				
Bromomethane				
Bromoform				
2-Butanone				
Carbon Disulfide				
Carbon Tetrachloride				
Chlorobenzene	0.33-240			
Chlorodibromomethane				
Chloroethane				
2-Chloroethylvinyl Ether				
Chloroform				
Chloromethane				
Dichlorobromomethane				
1,1-Dichloroethane				
1,2-Dichloroethane				
1,1-Dichloroethylene				
1,2-Dichloropropane				
1,3-Trans Dichloropropene				
1,3-Cis Dichloropropene				
Ethylbenzene	3.5-4.8	0-3.7	0.73-5.9	0-0.002
2-Hexanone				
Methylene Chloride	0-4.3			
4-Methyl-2-Pentanone				
Styrene				
1,1,2,2-Tetrachloroethane				
Tetrachloroethylene	0.39-28	0.012-0.6	0.008-29	0-0.047
Toluene	0-16			0-0.002
1,2-cis/trans Dichloroethylene	5.8-1300	0.03-76	13-390	0.07-4.8

*For reference, the locations of soil borings drilled in Area K-1 during the waste characterization phase of the pilot study are shown in Figure A-1.

**Concentration ranges correspond to the minimum and maximum concentrations observed for all discrete samples (i.e., 1.5'-3.5', 3.5'-5.0', 5.0'-6.5', 6.5'-8.0', 8.0'-10.0').

TABLE A-3. (CONTINUED)

Compound	Concentration (ug/g)**			
	Borehole 1	Borehole 2	Borehole 3	Borehole 4
11. Volatiles on Hazardous Substance List (HSL) (continued)				
1,1,2-Trichloroethane			0-14	
1,1,1-Trichloroethane				
Trichloroethylene	0.84-16	0.03-27	0.078-300	0.02-1.1
Vinyl Acetate				
Vinyl Chloride	0-2.1		0-2.6	
Xylene	25-32	0.006-25	4-31	0-0.006
Total Volatiles	35.86- 1643.2	0.078- 132.3	17.816 772.5	0.09-5.957
2. Others				
Cis-Allyl Benzene	20-30			
Dichlorobenzene	3-600	0.03-10	0.009-100	0-0.07
Methyl Ethyl Benzene	0.07-30	0-10	2.3-9	
n-Propylbenzene	4-7	0-3	0-2.9	
Trimethyl Benzene	30-110	0.13-60	8.4-37	
Total Others	57.07-777	0.16-83	10.709-148.9	0-0.07
TOTAL	92.93- 2420.2	0.238-215.3	28.525-921.4	0.09-6.027

*For reference, the locations of soil borings drilled in Area K-1 during the waste characterization phase of the pilot study are shown in Figure A-1.

**Concentration ranges correspond to the minimum and maximum concentrations observed for all discreet samples (i.e., 1.5'-3.5', 3.5'-5.0', 5.0'-6.5', 6.5'-8.0', 8.0'-10.0').

TABLE A-3. (CONTINUED)

Compound	Concentration (ug/q)**			
	Borehole 5	Borehole 6	Borehole 7	Borehole 8
<u>1. Volatiles on Hazardous Substance List (HSL)</u>				
Acetone		0-0.28		
Benzene				
Bromomethane				
Bromoform				
2-Butanone				
Carbon Disulfide				
Carbon Tetrachloride				
Chlorobenzene		0-0.44		
Chlorodibromomethane				
Chloroethane				
2-Chloroethylvinyl Ether				
Chloroform				
Chloromethane				
Dichlorobromomethane				
1,1-Dichloroethane		0-0.26		
1,2-Dichloroethane				
1,1-Dichloroethylene		0.3-2.7		0-1.8
1,2-Dichloropropane				
1,3-Trans Dichloropropene				
1,3-Cis Dichloropropene				
Ethylbenzene		0.97-4.3	0-4.9	0.15-11
2-Hexanone				
Methylene Chloride	0-1.7	0-0.6		
4-Methyl-2-Pentanone				
Styrene				
1,1,2,2-Tetrachloroethane		0.07-0.76		
Tetrachloroethylene	0.012-0.064	0.009-4.2	210-3800	0.058-17
Toluene		4.9-8.2		
1,2-cis/trans Dichloroethylene	0.46-5.2	0.098-990	10-130	0.9-920

*For reference, the locations of soil borings drilled in Area K-1 during the waste characterization phase of the pilot study are shown in Figure A-1.

**Concentration ranges correspond to the minimum and maximum concentrations observed for all discrete samples (i.e., 1.5'-3.5', 3.5'-5.0', 5.0'-6.5', 6.5'-8.0', 8.0'-10.0').



TABLE A-3. (CONTINUED)

Compound	Concentration (ug/g)**			
	Borehole 5	Borehole 6	Borehole 7	Borehole 8
1. <u>Volatiles on Hazardous Substance List (HSL)</u> (continued)				
1,1,2-Trichloroethane				
1,1,1-Trichloroethane			34-48	
Trichloroethylene	0.047-1.2	0.056-330	25-3500	1.2-3000
Vinyl Acetate				
Vinyl Chloride		0-4.3		4.4-4.8
Xylene		0.049-25	5.1-24	0.82-47
Total Volatiles	0.519-8.164	6.452 1371.04	284.1- 7506.9	7.528 4001.6
2. <u>Others</u>				
Cis-Allyl Benzene		2-20		0-5
Dichlorobenzene	0-0.4	7-200	0.9-2.4	0.5-20
Methyl Ethyl Benzene		0.5-24	0-10	0.4-11
n-Propylbenzene		0.72-5.6		0-4
Trimethyl Benzene		3.7-66	0-43	2.5-50
Total Others	0-0.4	13.92- 315.6	0.9-55.4	3.4-90
TOTAL	0.519-8.564	20.372 1686.64	285- 7562.3	10.928 4091.6

*For reference, the locations of soil borings drilled in Area K-1 during the waste characterization phase of the pilot study are shown in Figure A-1.

**Concentration ranges correspond to the minimum and maximum concentrations observed for all discrete samples (i.e., 1.5'-3.5', 3.5'-5.0', 5.0'-6.5', 6.5'-8.0', 8.0'-10.0').

TABLE A-3. (CONTINUED)

Compound	Concentration (ug/g)**		
	Borehole 9	Borehole 10	Borehole 11
1. <u>Volatiles on Hazardous Substance List (HSL)</u>			
Acetone			
Benzene			
Bromomethane			
Bromoform			
2-Butanone			
Carbon Disulfide			
Carbon Tetrachloride			
Chlorobenzene			
Chlorodibromomethane			
Chloroethane			
2-Chloroethylvinyl Ether			
Chloroform			
Chloromethane		0-0.1	
Dichlorobromomethane			
1,1-Dichloroethane			
1,2-Dichloroethane			
1,1-Dichloroethylene	0-0.01		
1,2-Dichloropropane			
1,3-Trans Dichloropropene			
1,3-Cis Dichloropropene			
Ethylbenzene			
2-Hexanone			
Methylene Chloride			
4-Methyl-2-Pentanone			
Styrene			
1,1,2,2-Tetrachloroethane			
Tetrachloroethylene	0.006-170	0.016-0.83	0-0.007
Toluene			0-0.006
1,2-cis/trans Dichloroethylene	4.5-74	0.05-0.08	0.007-0.023

*For reference, the locations of soil borings drilled in Area K-1 during the waste characterization phase of the pilot study are shown in Figure A-1.

**Concentration ranges correspond to the minimum and maximum concentrations observed for all discrete samples (i.e., 1.5'-3.5', 3.5'-5.0', 5.0'-6.5', 6.5'-8.0', 8.0'-10.0').

TABLE A-1. (CONTINUED)

Compound	Concentration (ug/l)**		
	Borehole 9	Borehole 10	Borehole 11
1. Volatile Organic Hazardous Substance List (VHSL) (continued)			
1,1,1-Trichloroethane			
1,1,2-Trichloroethane	2-31		
1,2-Dichloroethane	2.14-17.00	0.01-2.5	0.012-0.037
1,2-Dichloropropane			
1,2-Dichloroethane		0.05-0.24	
Xylene	3-11	0.012-0.06	
Total Volatiles	12.945 1985.01	0.168-3.81	0.019-0.073
2. Other			
Di-Allyl Benzene		0-0.03	
Dinitrobenzene	2-11	0.02-0.1	
Methyl Ethyl Benzene	0-4	0.02-0.13	
n-Propylbenzene		0-0.02	
Triethyl Benzene	0-23	0.15-0.64	
Total Others	2-15	0.17-0.77	
TOTAL	14.945 2021.01	0.708-4.58	0.019-0.073

*For reference, the locations of soil borings drilled in Area K-1 during the waste characterization phase of the pilot study are shown in Figure A-1.

**Concentration ranges correspond to the minimum and maximum concentrations observed for all samples sampled (i.e., 1.0-1.5, 1.5-2.0, 2.0-2.5, 2.5-3.0, 3.0-3.5, 3.5-4.0, 4.0-4.5, 4.5-5.0, 5.0-5.5, 5.5-6.0, 6.0-6.5, 6.5-7.0, 7.0-7.5, 7.5-8.0, 8.0-8.5, 8.5-9.0, 9.0-9.5, 9.5-10.0).





FIGURE A-1 LOCATION OF SOIL BORINGS DRILLED IN AREA K-1 DURING THE WASTE CHARACTERIZATION PHASE OF THE PILOT STUDY

WESTON

APPENDIX B.

GRAIN SIZE GRADATION CURVES CORRESPONDING TO FILL
SOIL AND NATIVE SOIL

6060A



Symbol Sample Specific Gravity D60		Description of Sample FILL - GRAVELLY SAND Gradation Curves	
Symbol Sample Specific Gravity D60		Description of Sample FILL - GRAVELLY SAND Gradation Curves	

WESTON

APPENDIX C
AIR SAMPLING TECHNIQUES

6060A

C. AIR SAMPLING TECHNIQUES

C.1 Description of test locations. An instrumentation diagram showing the location of measuring devices is included in Figure C-1. A brief description of each location is discussed in the following subsections.

C.1.1 Process air inlet. A single 2-inch inner diameter (ID) test port was installed in a horizontal straight section of pipe downstream from the air preheater outlet, i.e., 32 inches (8 diameters) downstream of a pipe bend and 25 inches (greater than 2 diameters) upstream of the thermal processor air inlet (Figure C-2). Traverse point selection criteria dictated by EPA Method 1 for this "ideal" test location required a minimum of 8 points, 4 per port axis. For this duct configuration, only one port axis was traversed to obtain preliminary velocity profiles. During formal testing, flow rates were measured from a center point location. Figure C-1 illustrates test port placement and sampling point locations.

C.1.2 Process off-gas manifolds. A single 2-inch ID test port was installed on each of the three identical and parallel air lines discharging gases from the thermal processor. Each test port was located in a 3-inch ID horizontal straight section >8 diameters downstream of the processor dome and >2 diameters upstream of a 4-inch ID header that combined the three off-gas manifolds. Traverse point selection criteria dictated by EPA Method 1 for this "ideal" location required a minimum of 8 points, 4 per port axis. For this duct configuration, only one port axis was traversed to obtain preliminary velocity profiles. During formal testing, flow rates were measured from a center point location. Figure C-3 illustrates test port placement and sampling point locations.

C.1.3 Afterburner inlet. A single 2-inch ID test port was installed in a 4-inch horizontal straight section of pipe downstream of the off-gas manifold main header >8 diameters downstream of a pipe bend and >2 diameters upstream of the induced draft fan. Traverse point selection criteria dictated by EPA Method 1 for this "ideal" location required a minimum of 8 points, 4 per port axis. For this duct configuration, only one port axis was traversed to obtain preliminary velocity profiles. During formal testing, flow rates were measured at center point locations. Figure C-4 illustrates test port placement and sampling point locations.

Code of Federal Regulations, Title 40, Part 60, Appendix A,
"Standards of Performance for New Stationary Sources," 13
August 1977.




FIGURE C-1 THERMAL PROCESSING SYSTEM INSTRUMENTATION AND SAMPLING/ANALYSIS DIAGRAM




FIGURE C-2 PROCESS AIR INLET PORT AND TRAVERSE POINT LOCATIONS




FIGURE C-3 PROCESS OFF-GAS MANIFOLDS PORT AND TRAVERSE POINT LOCATIONS




FIGURE C-4 AFTERBURNER INLET PORT AND TRAVERSE POINT LOCATION

C.1.4 Discharge stack. Two test ports were installed 90° apart in a straight section of the vertical stack 102 inches (>8 diameters) downstream of the afterburner chamber and 72 inches (>2 diameters) upstream of the stack outlet. Five inches of refractory brick lined the inside of the 9.625-inch ID stack. Traverse point selection criteria dictated by EPA Method 1 for this "ideal" test location required a minimum of 8 points, 4 per port axis. Figure C-5 illustrates test port placement and sample point locations.

C.2 Description of test equipment.

C.2.1 Flow. Air flow at the processor inlet and afterburner inlet was measured using 12-inch standard pitot tubes connected to inclined manometers (velocity pressure indicators). Air flow in the process off-gas manifolds was measured by orifice plates. Magnahelics monitored the orifice plate pressure differentials. Flow at the discharge stack was determined using S-type pitot tubes incorporated with a modified EPA Method 5 train (described in Section C.2.4.2).

C.2.2 Temperature was monitored using chromel/alumel thermocouples placed alongside the pitot tubes or orifice plates and wired to a switchable calibrated digital pyrometer.

C.2.3 Moisture. The moisture contents of the process inlet air and infiltration air were assumed to be the same as ambient air and were measured using a sling psychrometer and associated psychrometric chart.

The moisture content at the afterburner inlet was measured by an EPA Method 4 sampling train. Moisture was determined at the discharge stack using a modified EPA Method 5 train described in subsection C.2.4.2.

C.2.4 VOC's.

C.2.4.1 Total VOC's by continuous emissions monitoring (CEM) system. The CEM system was used to measure total VOC concentrations at the process off-gas manifolds for Test Runs 1 through 18, at the afterburner inlet for Test Runs 19 through 23, and at manifold 2 for Test Runs 25 through 28. This system measured gross VOC concentrations in the linear range from 1 to 600 ppm by volume dry air relative to the calibration gas (benzene). The CEM system (see Figure C-6) consisted of the following components connected in series:




FIGURE C-5 DISCHARGE STACK TEST PORT AND TRAVERSE POINT LOCATIONS




FIGURE C-6 CONTINUOUS EMISSIONS MONITORING SYSTEM

- (a) A glass wool thimble (to remove particulate) connected to 8 feet of 1/4-inch heated (approximately 170°F) teflon tubing (to transport sample gas).
- (b) A stainless steel four-way switch valve that connected sample gas lines (manifolds 1, 2, and 3 or afterburner inlet) and calibration gas to a common 1/4-inch teflon tube (to select individual gas source).
- (c) From the common line, an ice water-cooled glass condenser and condensate trap (to cool and dry the sample gas).
- (d) An AID Model 590 volatile organics monitor/GC (photoionization detector with 10.0 eV lamp) for Test Runs 1 through 11.
- (e) A century model 128 volatile organics monitor/GC (flame ionization detector) for Test Runs 12 through 23 and 24 through 28.
- (f) Monitor output recorded on Molytek single channel recorder.

Both monitors were used in the total VOC survey mode and were calibrated on benzene (or styrene referenced to benzene) standards in air.

C.2.4.2 Specific VOC's by Modified Volatile Organic Sampling Train (MOD VOST). Specific VOC concentrations were measured at the afterburner inlet for Test Runs 1 through 18 and at the process off-gas manifolds for Test Runs 19 through 23, using a MOD VOST. This sampling train was applicable to the higher VOC concentrations (i.e., greater than 500 ppm/volume) encountered at these test locations. The sampling train (see Figure C-7) consisted of the following components connected in series:

- (a) A glass wool thimble (to remove particulate) connected to 8 feet of 1/4-inch heated (approximately 170°F) teflon tubing (to transport sample gas).
- (b) An ice water-cooled glass condensor and condensate trap (to collect VOC condensable at 68°F).
- (c) A section of 1/4-inch teflon tubing connecting the condensate trap to a 2-section, 3-gram and 4-gram activated charcoal tube (to adsorb VOC's) and a silica gel tube (to remove residual moisture before entering the pump).
- (d) The silica gel tube was connected via an umbilical cable to a control console containing flow controllers, a calibrated 1 liter per minute (lpm) dry gas meter, a sample pump, valves and vacuum gauges, a water coolant pump, and temperature indicators.





FIGURE C-7 MODIFIED VOLATILE ORGANICS SAMPLING TRAIN (MOD VOST)

C.2.4.3 Specific VOC's by VOST. Specific VOC concentrations in the discharge stack gas emission stream were determined using a volatile organics sampling train. This sampling train (see Figure C-8) consisted of the following components connected in series:

- (a) A heated borosilicate probe, 3-ft in length, containing a glass wool particulate filter.
- (b) The probe was connected to an ice water-cooled condenser followed by an adsorption cartridge containing 1.6 grams of Tenax (35/60 mesh) and a condensate trap.
- (c) A section of teflon tubing was used to connect the outlet of the condensate trap to a second condenser which is followed by a back-up sorbent trap (containing 1 gram of Tenax and 1 gram of SKC petroleum-based charcoal), a condensate collector, and a tube containing a measured amount of silica gel.
- (d) The tube of silica gel was connected via an umbilical cable to a control console containing flow controllers, a calibrated 1 lpm dry gas meter, a sample pump, a coolant pump, a temperature indicator, and other components.

C.2.5 Particulate and hydrochloric acid sampling equipment. Particulate, hydrochloric acid (HCl), and moisture present in the stack gases were collected simultaneously using a modified EPA Method 5 sampling train (see Figure C-9). This sampling train consisted of the following components:

- (a) A 316 stainless steel nozzle with an inside diameter sized to sample isokinetically.
- (b) A heated, hastalloy-C probe, approximately 3 ft long, equipped with thermocouple to measure flue gas temperature and an S-type pitot tube to measure flue gas velocity pressure.
- (c) A heated oven containing a borosilicate filter holder with a weighed 90-millimeter Reeve Angle 934 AH glass fiber filter.
- (d) A section of borosilicate tubing to connect the outlet of the filter hold to the inlet of the impinger train.
- (e) An impinger train containing 4 impingers (No. 1 -- 100 ml 0.1 N NaOH; No. 2 -- 100 milliliter 0.1 N NaOH; No. 3 -- dry; No. 4 -- 200 gram silica gel). The first 3 impingers were of the standard Greenburg-Smith design; the final impinger was modified by replacing the impaction tip with straight tubing.



NOTE
Both traps were replaced every
20 minutes over 2-hour period

FIGURE C-8 VOLATILE ORGANICS SAMPLING TRAIN (VOST)




FIGURE C-9 PARTICULATE/HCl SAMPLING TRAIN - MODIFIED EPA METHOD 5

- (f) A vacuum hose to connect the outlet of the impinger train to a control module.
- (g) A control module containing a 3 cubic foot per minute carbon vane vacuum pump (sample gas mover), a calibrated dry gas meter (sample gas volume measurement device), a calibrated orifice (sample gas flow rate indicator), and inclined manometers (orifice and gas stream pressure indicators).
- (h) A switchable calibrated digital pyrometer to monitor flue and sample gas temperatures.

The material collected in the nozzle, probe, front-half of the filter holder, and on the glass fiber filter were analyzed gravimetrically for particulate. The liquid from the NaOH-containing impingers was analyzed for HCl.

C.2.6 Fixed gases (CO_2 , O_2 , CO) sampling equipment. The fixed gas sampling train (Figure C-10) was assembled in accordance with EPA Method 3 and consisted of the following components:

- (a) A stainless steel probe with a plug of glass wool to remove particulate.
- (b) An air or water-cooled condenser to remove moisture from the sampled gases.
- (c) A diaphragm pump to draw a continuous sample of the gases.
- (d) A Tedlar or plastic-coated aluminum barrier bag to contain the sample of flue gases.

An Orsat analyzer was used to analyze the contents of the bag for CO_2 , O_2 , and CO .

C.3 Testing, monitoring, and analytical procedures. Following equipment set-up, technicians compiled preliminary test data at the process air inlet, process off-gas manifolds, afterburner inlet, and discharge stack. Geometric flue measurements were recorded and pitot tube traverses were performed to determine the presence/absence of cyclonic flow.

Formal tests generally ran two to three hours in duration, depending on process upsets, available quantities of feed soil, and weather conditions. The test period was defined by the VOC sampling time at the afterburner inlet. Simultaneous testing was performed on all source locations (excluding the discharge stack) during the 23 test runs. Concurrent compliance tests were performed at the discharge stack during selected low, medium, and high VOC-inlet loading conditions (Test Runs 8, 9, and 10, respectively). Table C-1 presents the parameters measured at each source location for each test run.




FIGURE C-10 INTEGRATED GAS SAMPLING TRAIN - EPA METHOD 3

TABLE C-1. TEST PARAMETERS MEASURED FOR EACH LOCATION
BY TEST RUN

Test run	Process air inlet	Process off-gas manifolds	Afterburner inlet	Discharge stack
1-7	Flow Temperature Moisture Total VOC Fixed Gases	Flow Temperature --- Total VOC Fixed Gases	Flow Temperature Moisture Specific VOC Fixed Gases	--- --- --- --- ---
8-10	Flow Temperature Moisture Total VOC Fixed Gases	Flow Temperature --- Total VOC Fixed Gases	Flow Temperature Moisture Specific VOC Fixed Gases	Flow Temperature Moisture Specific VOC Fixed Gases Particulate Hydrogen Chloride
11-18	Flow Temperature Moisture Total VOC Fixed Gases	Flow Temperature --- Total VOC Fixed Gases	Flow Temperature Moisture Specific VOC Fixed Gases	Flow Temperature --- --- ---
19-23	Flow Temperature Moisture Total VOC Fixed Gases	Flow Temperature --- Specific VOC Fixed Gases	Flow Temperature Moisture Total VOC Fixed Gases	Flow Temperature --- --- ---
24	Flow Temperature Moisture	Flow Temperature ---	Flow Temperature Moisture	Flow Temperature ---
25-28	Flow Temperature Moisture	Flow Temperature Total VOC at Manifold 2	Flow Temperature Moisture	Flow Temperature ---

WESTON

Testing and analysis protocols followed for each parameter measured are summarized in Table C-2. The following paragraphs and flow charts summarize the sample train preparation, testing procedures, sample recovery, and analytical techniques. Copies of the EPA Reference methods are included in the draft version of the Work Plan.²

C.3.1 Flow. Process air flows were measured every thirty minutes for each test run. Pitot tube orifice pressure differentials were recorded for all test locations within a ten-minute period in the following order: process air inlet, process off-gas manifolds, afterburner inlet, and stack.

C.3.2 Temperature. Processor air temperatures were recorded at each test location simultaneously with the air flow measurements.

C.3.3 Moisture. The moisture content of ambient air (process inlet air and infiltration air) was measured simultaneously with the process air flow and temperature measurements. Average moisture content of the afterburner inlet air was measured by an EPA Method 4 sampling train ran concurrently with the VOC sampling for each test run. Average moisture content of the stack gas stream was measured concurrently with the afterburner inlet VOC sampling by an EPA Method 4 sampling train for Test Runs 6 and 7 and incorporated with the Modified EPA Method 5 sampling train for Test Runs 8, 9, 10.

Test Plan for a Pilot Investigation of Low Temperature Thermal Stripping of Volatile Organic Compounds From Soil at Letterkenny Army Depot (LEAD), Draft Version, June 1985.



TABLE C-2. TESTING PROTOCOLS FOR AIR SAMPLING

Parameters measured	EPA reference methods ¹
Air Temperature, Volumetric Flow, and Mass Rate	EPA 1, 2 (modified by using centerpoint velocities)
Fixed Gases (CO ₂ , O ₂ , and CO) Concentration	EPA 3 (stack only)
Moisture Concentration	EPA 4 (sling psychrometer at process inlet)
Volatile Organic Compounds Concentration	
Total VOC by CEM	EPA 25A (modified by using PID monitor for runs 1-11)
Specific VOC by MOD VOST	WESTON designed
Specific VOC by VOST	EPA 600/8-84-007, March 1984
Particulate and Hydrogen Chloride Concentration and Mass Rate	EPA 5 (modified by replacing impinger solutions with 0.1 N NaOH; analyzed for hydrochloric acid by standard methods)

¹Code of Federal Regulations, Title 40, Part 60, Appendix A, "Standards of Performance For New Stationary Sources," 18 August 1977.

C.3.4 VOC's

C.3.4.1 Total VOC's by CEM system. A portable organic vapor analyzer was used to monitor the total VOC concentrations (ppm/volume) at the following locations: (1) each leg of the off-gas manifold system (Test Runs 1 through 18), (2) at the afterburner inlet (Test Runs 19 through 23), and (3) at manifold 2 (Test Runs 25 through 28). No monitoring was conducted during Run 24 due to a faulty analyzer.

C.3.4.1.1 Calibration of instrument. A three-point calibration was completed before and after each test run. The calibrations were completed using an ambient air source and calibration gases (i.e., 10 ppm, 100 ppm, and/or 1000 ppm benzene in air standard). A single mid-test span check was also performed during each test run.

C.3.4.1.2 Monitoring. During Test Runs 1 through 18, total VOC concentrations in each manifold leg were monitored and recorded every 15 minutes. A stainless steel 4-way switch valve assembly was used to sample manifolds 1, 2, and 3 and ambient air/calibrating gas. Total VOC concentrations were monitored for 5 minutes per leg.

During Test Runs 19 through 23 the instrument was drawing a continuous sample from the gases entering the afterburner. Total VOC concentrations were recorded every 15 minutes.

The pump suction on the OVA instrument used during Test Runs 25 through 28 was not strong enough to overcome the 23 inches of water column negative pressure present at the afterburner inlet test port. Therefore, the instrument was connected to the test port at manifold 2. Total VOC concentrations were recorded every 15 minutes.

C.3.4.2 Specific VOC's by the MOD VOST. A modified VOST train was used to measure the specific VOC concentrations at the afterburner inlet (Test Runs 1 through 18) and in each of the three legs of the manifold (Test Runs 19 through 23). The sample train preparation, testing, and sample recovery procedures are depicted in the flowcharts in Figures C-11, C-12, and C-13, respectively.

C.3.4.3 Specific VOC's by VOST. A VOST train was used at the discharge stack to measure the specific VOC concentrations in the gases. The sample train preparation, sampling, and sample recovery procedures are shown in the flowcharts in Figures C-14, C-15, and C-16, respectively. The integrated gas sample flow rate was less than or equal to 1 lpm for each two-to three-hour test. The VOST trap pairs were replaced with fresh traps every 20 minutes.




FIGURE C-11 PREPARATION PROCEDURES FOR MODIFIED VOLATILE ORGANICS SAMPLING TRAIN




FIGURE C-12 SAMPLING PROCEDURES FOR VOLATILE ORGANICS USING MODIFIED VOST




FIGURE C-13 SAMPLE RECOVERY PROCEDURES FOR VOLATILE ORGANICS USING MODIFIED VOST




FIGURE C-14 PREPARATION PROCEDURES FOR VOLATILE ORGANICS SAMPLING TRAIN




FIGURE C-15 SAMPLING PROCEDURES FOR VOLATILE ORGANICS




FIGURE C-16 SAMPLE RECOVERY PROCEDURES FOR VOLATILE ORGANICS

C.3.5 Particulate and HCl. Figures C-17, C-18, and C-19 illustrate the procedures that were used to prepare the particulate/HCl sampling train prior to each test, the procedures used to sample the stack gases, and the procedures used to recover the samples from the train. Procedures were in accordance with EPA Method 5 except for minor modifications in train configuration and sample recovery procedures for HCl. Immediately following sample recovery, the sampling train was recharged, components reassembled, and the openings sealed to prevent contamination. Tests were generally two to three hours in duration, 30 dscf in size, and isokinetic ± 10 percent.

C.3.6 Fixed gases (CO, CO₂, O₂). Figure C-20 illustrates the procedure used to measure the CO, CO₂, and O₂ content of the stack gases. No special preparations were required apart from making certain the gas sampling bag, train, and Orsat were leak-free and the Orsat contained fresh reagents.




FIGURE C-17 PREPARATION PROCEDURES FOR PARTICULATE AND HCl SAMPLING TRAIN




FIGURE C-18 SAMPLING PROCEDURES FOR PARTICULATE AND HCl SAMPLING TRAIN




FIGURE C-19 SAMPLE RECOVERY PROCEDURES FOR PARTICULATE AND HCl




FIGURE C-20 SAMPLING PROCEDURES FOR CO₂, O₂, AND CO



APPENDIX D

FEDERAL REGULATIONS

A. Asbestos

- Chapter 27
Occupational Safety and Health
Administration (OSHA) 29 CFR 1910.1001
- Chapter 1
Environmental Protection Agency (EPA)
40 CFR Part 61, Subpart B

B. Hazardous Waste

- Part 260
Hazardous Waste Management
System: General
40 CFR 260
- Part 261
Identification and Listing
of Hazardous Waste
40 CFR 261
- Part 234
Subpart O
Incinerators
40 CFR 264.340 - 264.347



A. ASBESTOS
CHAPTER 27
OSHA REGULATIONS
29 CFR 1910.1001

6060A

Chapter XVII—Occupational Safety and Health Administration § 1910.1001

NOTE: Conversion factors—
 $\text{mgpd} \times 35.3 = \text{million particles per cubic meter}$
 $= \text{particles per c.c.}$

* Millions of particles per cubic foot of air, based on impinger samples counted by light-bead techniques.

† The percentage of crystalline silica in the formula is the amount determined from air-borne samples, except in those instances in which other methods have been shown to be applicable.

* Both concentration and percent quartz for the application of this limit are to be determined from the fraction passing a size-selector with the following characteristics:

* Containing <1% quartz; if 1% quartz, use quartz limit.

Aerodynamic diameter (unit density sphere)	Percent passing selector
2	90
2.5	75
3.5	50
5.0	25
10	0

The measurements under this note refer to the use of an AEC instrument. The respirable fraction of coal dust is determined with a MRE, the figure corresponding to that of 2.4 Mg/M^3 in the table for coal dust is 4.5 Mg/M^3 .

(Secretary of Labor's Order No. 8-78 (41 CFR Part 25059); 29 CFR Part 1911)

(39 FR 23502, June 27, 1974. Redesignated and amended at 40 FR 23073, May 28, 1975; 42 FR 22525, May 3, 1977; 43 FR 2600, Jan. 17, 1978; 43 FR 5963, Feb. 10, 1978; 43 FR 13563, Mar. 31, 1978; 43 FR 19624, May 5, 1978; 43 FR 27394, June 23, 1978; 43 FR 45809, Oct. 3, 1978; 43 FR 53007, Nov. 14, 1978; 43 FR 57602, Dec. 8, 1978)

§ 1910.1001 Asbestos.

(a) *Definitions.* For the purpose of this section, (1) "Asbestos" includes chrysotile, amosite, crocidolite, tremolite, anthophyllite, and actinolite.

(2) "Asbestos fibers" means asbestos fibers longer than 5 micrometers.

(b) *Permissible exposure to airborne concentrations of asbestos fibers—*(1) *Standard effective July 7, 1972.* The 8-hour time-weighted average airborne concentrations of asbestos fibers to which any employee may be exposed shall not exceed five fibers, longer than 5 micrometers, per cubic centimeter of air, as determined by the method prescribed in paragraph (e) of this section.

(2) *Standard effective July 1, 1978.* The 8-hour time-weighted average airborne concentrations of asbestos fibers to which any employee may be exposed shall not exceed two fibers, longer than 5 micrometers, per cubic

centimeter of air, as determined by the method prescribed in paragraph (e) of this section.

(3) *Ceiling concentration.* No employee shall be exposed at any time to airborne concentrations of asbestos fibers in excess of 10 fibers, longer than 5 micrometers, per cubic centimeter of air, as determined by the method prescribed in paragraph (e) of this section.

(c) *Methods of compliance—*(1) *Engineering methods.* (i) *Engineering controls.* Engineering controls, such as, but not limited to, isolation, enclosure, exhaust ventilation, and dust collection, shall be used to meet the exposure limits prescribed in paragraph (b) of this section.

(ii) *Local exhaust ventilation.* (a) Local exhaust ventilation and dust collection systems shall be designed, constructed, installed, and maintained in accordance with the American National Standard Fundamentals Governing the Design and Operation of Local Exhaust Systems, ANSI Z9.2-1971, which is incorporated by reference herein.

(b) See § 1910.6 concerning the availability of ANSI Z9.2-1971, and the maintenance of a historic file in connection therewith. The address of the American National Standards Institute is given in § 1910.100.

(iii) *Particular tools.* All hand-operated and power-operated tools which may produce or release asbestos fibers in excess of the exposure limits prescribed in paragraph (b) of this section, such as, but not limited to, saws, scorers, abrasive wheels, and drills, shall be provided with local exhaust ventilation systems in accordance with subdivision (ii) of this subparagraph.

(2) *Work practices—*(i) *Wet methods.* Insofar as practicable, asbestos shall be handled, mixed, applied, removed, cut, scored, or otherwise worked in a wet state sufficient to prevent the emission of airborne fibers in excess of the exposure limits prescribed in paragraph (b) of this section, unless the usefulness of the product would be diminished thereby.

(ii) *Particular products and operations.* No asbestos cement, mortar, coating, grout, plaster, or similar material containing asbestos shall be removed from bags, cartons, or other

containers in which they are shipped, without being either wetted, or enclosed, or ventilated so as to prevent effectively the release of airborne asbestos fibers in excess of the limits prescribed in paragraph (b) of this section.

(iii) *Spraying, demolition, or removal.* Employees engaged in the spraying of asbestos, the removal, or demolition of pipes, structures, or equipment covered or insulated with asbestos, and in the removal or demolition of asbestos insulation or coverings shall be provided with respiratory equipment in accordance with paragraph (d)(2)(iii) of this section and with special clothing in accordance with paragraph (d)(3) of this section.

(d) *Personal protective equipment—*

(1) Compliance with the exposure limits prescribed by paragraph (b) of this section may not be achieved by the use of respirators or shift rotation of employees, except:

(i) During the time period necessary to install the engineering controls and to institute the work practices required by paragraph (c) of this section;

(ii) In work situations in which the methods prescribed in paragraph (c) of this section are either technically not feasible or feasible to an extent insufficient to reduce the airborne concentrations of asbestos fibers below the limits prescribed by paragraph (b) of this section; or

(iii) In emergencies.

(iv) Where both respirators and personnel rotation are allowed by paragraphs (d)(1) (i), (ii), or (iii) of this section, and both are practicable, personnel rotation shall be preferred and used.

(2) Where a respirator is permitted by paragraph (d)(1) of this section, it shall be selected from among those approved by the Bureau of Mines, Department of the Interior, or the National Institute for Occupational Safety and Health, Department of Health, Education, and Welfare, under the provisions of 30 CFR Part 11 (37 P.R. 6244, Mar. 25, 1972), and shall be used in accordance with subdivisions (i), (ii), (iii), and (iv) of this subparagraph.

(i) *Air purifying respirators.* A reusable or single use air purifying respirator, or a respirator described in paragraphs (d)(2) (ii) or (iii) of this section, shall be used to reduce the concentrations of airborne asbestos fibers in the respirator below the exposure limits prescribed in paragraph (b) of this section, when the ceiling or the 8-hour time-weighted average airborne concentrations of asbestos fibers are reasonably expected to exceed no more than 10 times those limits.

(ii) *Powered air purifying respirators.* A full facepiece powered air purifying respirator, or a powered air purifying respirator, or a respirator described in paragraph (d)(2)(iii) of this section, shall be used to reduce the concentrations of airborne asbestos fibers in the respirator below the exposure limits prescribed in paragraph (b) of this section, when the ceiling or the 8-hour time-weighted average concentrations of asbestos fibers are reasonably expected to exceed 10 times, but not 100 times, those limits.

(iii) *Type "C" supplied-air respirators, continuous flow or pressure-demand class.* A type "C" continuous flow or pressure-demand, supplied-air respirator shall be used to reduce the concentrations of airborne asbestos fibers in the respirator below the exposure limits prescribed in paragraph (b) of this section, when the ceiling or the 8-hour time-weighted average airborne concentrations of asbestos fibers are reasonably expected to exceed 100 times those limits.

(iv) *Establishment of a respirator program.* (a) The employer shall establish a respirator program in accordance with the requirements of the American National Standards Practices for Respiratory Protection, ANSI Z88.2-1969, which is incorporated by reference herein.

(b) See § 1910.6 concerning the availability of ANSI Z88.2-1969 and the maintenance of a historic file in connection therewith. The address of the American National Standards Institute is given in § 1910.100.

(c) No employee shall be assigned to tasks requiring the use of respirators if, based upon his most recent examination, an examining physician determines that the employee will be

unable to function normally wearing a respirator, or that the safety or health of the employee or other employee could be impaired by his use of a respirator. Such employee shall be rotated to another job or given the opportunity to transfer to a different position where duties he is able to perform with the same employer, in the same geographical area and with the same seniority, status, and rate of pay he had just prior to such transfer, if such a different position is available.

(3) **Special clothing:** The employer shall provide, and require the use of, special clothing, such as coveralls or similar whole body clothing, head coverings, gloves, and foot coverings for any employee exposed to airborne concentrations of asbestos fibers, which exceed the ceiling level prescribed in paragraph (b) of this section.

(4) **Change rooms:** (i) At any fixed place of employment exposed to airborne concentrations of asbestos fibers in excess of the exposure limits prescribed in paragraph (b) of this section, the employer shall provide change rooms for employees working regularly at the place.

(ii) **Clothes lockers:** The employer shall provide for separate lockers or containers for each employee, so separated or isolated as to prevent contamination of the employee's street clothes from his work clothes.

(iii) **Laundering:** (a) Laundering of asbestos-contaminated clothing shall be done so as to prevent the release of airborne asbestos fibers in excess of the exposure limits prescribed in paragraph (b) of this section.

(b) Any employer who gives asbestos-contaminated clothing to another person for laundering shall inform such person of the requirement in paragraph (d)(4)(iii)(a) of this section to effectively prevent the release of airborne asbestos fibers in excess of the exposure limits prescribed in paragraph (b) of this section.

(c) Contaminated clothing shall be transported in sealed impermeable bags, or other closed, impermeable containers, and labeled in accordance with paragraph (g) of this section.

(d) **Method of measurement:** All determinations of airborne concentrations of asbestos fibers shall be made

by the membrane filter method, 990-450, magnification of 4 milimeter objective with phase contrast illumination.

(f) **Monitoring:** (i) **Initial determinations:** Within 6 months of the implementation of this section, the employer shall cause every place of employment where asbestos fibers are known to be monitored in such a way as to determine whether exposure levels are above to asbestos fibers in excess of the limits prescribed in paragraph (b) of this section. If the limit is exceeded, the employer shall immediately institute measures to reduce exposure to the level prescribed in paragraph (b) of this section.

porosity mounted in an open-face filter holder. Samples shall be taken for the determination of the 8-hour time-weighted average airborne concentrations and of the ceiling concentrations of asbestos fibers.

(ii) **Sampling frequency and patterns:** After the initial determinations required by paragraph (f)(i) of this section, samples shall be of such frequency and pattern as to represent with reasonable accuracy the levels of exposure of employees. In no case shall the sampling be done at intervals greater than 6 months for employees whose exposure to asbestos may reasonably be foreseen to exceed the limits prescribed by paragraph (b) of this section.

(3) **Environmental monitoring.** (i) Samples shall be collected from areas of a work environment which are representative of the airborne concentrations of asbestos fibers which may reach the breathing zone of employees. Samples shall be collected on a membrane filter of 0.8 micrometer porosity mounted in an open-face filter holder. Samples shall be taken for the determination of the 8-hour time-weighted average airborne concentrations and of the ceiling concentrations of asbestos fibers.

(ii) **Sampling frequency and patterns:** After the initial determinations required by paragraph (f)(i) of this section, samples shall be of such frequency and pattern as to represent with reasonable accuracy the levels of exposure of employees.

quency and pattern as to represent with reasonable accuracy the levels of exposure of the employees. In no case shall sampling be at intervals greater than 6 months for employees whose exposures to asbestos may reasonably be foreseen to exceed the exposure limits prescribed in paragraph (b) of this section.

(4) *Employee observation of monitoring.* Affected employees, or their representatives, shall be given a reasonable opportunity to observe any monitoring required by this paragraph and shall have access to the records thereof.

(g) *Caution signs and labels.* (1) *Caution signs.* (i) *Posting.* Caution signs shall be provided and displayed at each location where airborne concentrations of asbestos fibers may be in excess of the exposure limits prescribed in paragraph (b) of this section. Signs shall be posted at such a distance from such a location so that an employee may read the signs and take necessary protective steps before entering the area marked by the signs. Signs shall be posted at all approaches to areas containing excessive concentrations of airborne asbestos fibers.

(ii) *Sign specifications.* The warning signs required by paragraph (g)(1)(i) of this section shall conform to the requirements of 20" x 14" vertical format signs specified in § 1910.145(d)(4), and to this subdivision. The signs shall display the following legend in the lower panel, with letter sizes and styles of a visibility at least equal to that specified in this subdivision.

Legend	Notation
Asbestos	1" Sans Serif, Gothic or Block
Dust Hazard	½" Sans Serif, Gothic or Block
Avoid Breathing Dust	¼" Gothic
Wear Assigned Protective Equipment	¼" Gothic
Do Not Remain in Area Unless Your Work Requires It	¼" Gothic
Breathing Asbestos Dust May Be Hazardous To Your Health	14 point Gothic

Spacing between lines shall be at least equal to the height of the upper of any two lines.

(2) *Caution labels.*—(i) *Labeling.* Caution labels shall be affixed to all raw materials, mixtures, scrap, waste, debris, and other products containing

asbestos fibers, or to their containers, except that no label is required where asbestos fibers have been modified by a bonding agent, coating, binder, or other material so that during any reasonably foreseeable use, handling, storage, disposal, processing, or transportation, no airborne concentrations of asbestos fibers in excess of the exposure limits prescribed in paragraph (b) of this section will be released.

(ii) *Label specifications.* The caution labels required by paragraph (g)(2)(i) of this section, shall be printed in letters of sufficient size and contrast as to be readily visible and legible. The label shall state:

CAUTION

Contains Asbestos Fibers

Avoid Creating Dust

Breathing Asbestos Dust May Cause Serious Bodily Harm

(h) *Housekeeping.*—(1) *Cleaning.* All external surfaces in any place of employment shall be maintained free of accumulations of asbestos fibers if, with their dispersion, there would be an excessive concentration.

(2) *Waste disposal.* Asbestos waste, scrap, debris, bags, containers, equipment, and asbestos-contaminated clothing, consigned for disposal, which may produce in any reasonably foreseeable use, handling, storage, processing, disposal, or transportation airborne concentrations of asbestos fibers in excess of the exposure limits prescribed in paragraph (b) of this section shall be collected and disposed of in sealed impermeable bags, or other closed, impermeable containers.

(i) *Recordkeeping.*—(1) *Exposure records.* Every employer shall maintain records of any personal or environmental monitoring required by this section. Records shall be maintained for a period of at least 20 years and shall be made available upon request to the Assistant Secretary of Labor for Occupational Safety and Health, the Director of the National Institute for Occupational Safety and Health, and to authorized representatives of either.

(2) *Access.* Employee exposure records required by this paragraph shall be provided upon request to employ-

ees, designated representatives, and the Assistant Secretary in accordance with 29 CFR 1910.20 (a)-(e) and (g)-(i).

(3) *Employee notification.* Any employee found to have been exposed at any time to airborne concentrations of asbestos fibers in excess of the limits prescribed in paragraph (b) of this section shall be notified in writing of the exposure as soon as practicable but not later than 5 days of the finding. The employee shall also be timely notified of the corrective action being taken.

(j) *Medical examinations—(1) General.* The employer shall provide or make available at his cost, medical examinations relative to exposure to asbestos required by this paragraph.

(2) *Preplacement.* The employer shall provide or make available to each of his employees, within 30 calendar days following his first employment in an occupation exposed to airborne concentrations of asbestos fibers, a comprehensive medical examination, which shall include, as a minimum, a chest roentgenogram (posterior-anterior 14 × 17 inches), a history to elicit symptomatology of respiratory disease, and pulmonary function tests to include forced vital capacity (FVC) and forced expiratory volume at 1 second (FEV_{1.0}).

(3) *Annual examinations.* On or before January 31, 1973, and at least annually thereafter, every employer shall provide, or make available, comprehensive medical examinations to each of his employees engaged in occupations exposed to airborne concentrations of asbestos fibers. Such annual examination shall include, as a minimum, a chest roentgenogram (posterior-anterior 14 × 17 inches), a history to elicit symptomatology of respiratory disease, and pulmonary function tests to include forced vital capacity (FVC) and forced expiratory volume at 1 second (FEV_{1.0}).

(4) *Termination of employment.* The employer shall provide, or make available, within 30 calendar days before or after the termination of employment of any employee engaged in an occupation exposed to airborne concentrations of asbestos fibers, a comprehensive medical examination which shall

include, as a minimum, a chest roentgenogram (posterior-anterior 14 × 17 inches), a history to elicit symptomatology of respiratory disease, and pulmonary function tests to include forced vital capacity (FVC) and forced expiratory volume at 1 second (FEV_{1.0}).

(5) *Recent examinations.* No medical examination is required of any employee, if adequate records show that the employee has been examined in accordance with this paragraph within the past 1-year period.

(6) *Medical records—(i) Maintenance.* Employers of employees examined pursuant to this paragraph shall cause to be maintained complete and accurate records of all such medical examinations. Records shall be retained by employers for at least 20 years.

(ii) *Access.* Records of the medical examinations required by this paragraph shall be provided upon request to employees, designated representatives, and the Assistant Secretary in accordance with 29 CFR 1910.20 (a)-(e) and (g)-(i). These records shall also be provided upon the request to the Director of NIOSH. Any physician who conducts a medical examination required by this paragraph shall furnish to the employer of the examined employee all the information specifically required by this paragraph, and any other medical information related to occupational exposure to asbestos fibers.

(Secs. 6(b), 8(c) and 8(g) (84 Stat. 1593, 1599, 1600, 29 U.S.C. 655, 657), the Secretary of Labor's Order 8-76 (41 FR 25059) and 29 CFR Part 1911, Ch. XVII of Title 29.)

(39 FR 23502, June 27, 1974. Redesignated at 40 FR 27073, May 28, 1975, and amended at 41 FR 11505, Mar. 19, 1976, 45 FR 35281, May 23, 1980.)

EFFECTIVE DATE NOTE: At 45 FR 35281, May 23, 1980, paragraphs (h)(2) and (j)(6) of § 1910.1001 were revised, effective August 21, 1980. For the convenience of the user, the superseded text appears below.

§ 1910.1001 Asbestos

• • • • •

(2) *Employee access.* Every employee and former employee shall have reasonable

§ 1910.1002

Title 29—Labor

access to any record required to be maintained by paragraph (k)(1) of this section, which indicates the employee's own exposure to asbestos fibers.

- (j) . . .
- (k) . . .

(h) Access. The contents of the records of the medical examinations required by this paragraph shall be made available, for inspection and copying, to the Assistant Secretary of Labor for Occupational Safety and Health, the Director of NIOSH, to authorized physicians and medical consultants of either of them, and, upon the request of an employee or former employee, to his physician. Any physician who conducts a medical examination required by this paragraph shall furnish to the employer of the examined employee all the information specifically required by this paragraph, and any other medical information related to occupational exposure to asbestos fibers.

§ 1910.1002 Coal tar pitch volatiles; interpretation of term.

As used in § 1910.1000 (Table Z-1), coal tar pitch volatiles include the fused polycyclic hydrocarbons which volatilize from the distillation residues of coal, petroleum, wood, and other organic matter.

(Sec. 8(a), 84 Stat. 1000, 29 U.S.C. 657; 39 FR 23502, June 27, 1974; Redesignated and amended at 40 FR 23073, May 28, 1975)

§ 1910.1003 4-Nitrobiphenyl.

(a) Scope and application. (1) This section applies to any area in which 4-Nitrobiphenyl, Chemical Abstracts Service Registry Number 92933, is manufactured, processed, repackaged, released, handled, or stored, but shall not apply to transshipment in sealed containers, except for the labeling requirements under paragraphs (c), (2), (3), and (4) of this section.

(2) This section shall not apply to solid or liquid mixtures containing less than 0.1 percent by weight or volume of 4-Nitrobiphenyl.

(b) Definitions. For the purposes of this section: (1) Absolute filter is one capable of retaining 99.97 percent of a mono-disperse aerosol of 0.3 µm particles.

(2) "Authorized employee" means an employee whose duties require him to be in the regulated area and who has been specifically assigned by the employer.

(3) "Clean change room" means a room where employees put on clean clothing and/or protective equipment in an environment free of 4-Nitrobiphenyl. The clean change room shall be contiguous to and have an entry from a shower room, when the shower room facilities are otherwise required in this section.

(4) "Closed system" means an operation involving 4-Nitrobiphenyl where containment prevents the release of 4-Nitrobiphenyl into regulated areas, non-regulated areas, or the external environment.

(5) "Decontamination" means the inactivation of 4-Nitrobiphenyl or its safe disposal.

(6) "Director" means the Director, National Institute for Occupational Safety and Health, or any person directed by him or the Secretary of Health, Education, and Welfare to act for the Director.

(7) "Disposal" means the safe removal of 4-Nitrobiphenyl from the work environment.

(8) "Emergency" means an unforeseen circumstance or set of circumstances resulting in the release of 4-Nitrobiphenyl which may result in exposure to or contact with 4-Nitrobiphenyl.

(9) "External environment" means any environment external to regulated and nonregulated areas.

(10) "Isolated system" means a fully enclosed structure other than the vessel of containment of 4-Nitrobiphenyl, which is impervious to the passage of 4-Nitrobiphenyl, and which would prevent the entry of 4-Nitrobiphenyl into regulated areas, nonregulated areas, or the external environment, should leakage or spillage from the vessel of containment occur.

(11) "Laboratory type hood" is a device enclosed on three sides and the top and bottom, designed and maintained so as to draw air inward at an average linear face velocity of 150 feet per minute with a minimum of 125 feet per minute, designed, constructed, and maintained in such a way that an



A. ASBESTOS

CHAPTER 1

EPA REGULATIONS

40 CFR Part 61, Subpart B

FEDERAL AIR REGULATIONS
GOVERNING REMOVAL OF FRIABLE
ASBESTOS.

Adopted by Allegheny County
 in Section 515 of Article XX,
 effective January 1, 1981.

**PART 61—NATIONAL EMISSION
 STANDARDS FOR HAZARDOUS AIR
 POLLUTANTS**

Subpart A—General Provisions

- Sec.
- 61.01 Applicability.
 - 61.02 Definitions.
 - 61.03 Units and abbreviations.
 - 61.04 Address.
 - 61.05 Prohibited activities.
 - 61.06 Determination of construction or modification.
 - 61.07 Application for approval of construction or modification.
 - 61.08 Approval by Administrator.
 - 61.09 Notification of startup.
 - 61.10 Source reporting and waiver request.
 - 61.11 Waiver of compliance.
 - 61.12 Emission tests and monitoring.
 - 61.13 Waiver of emission tests.
 - 61.14 Source test and analytical methods.
 - 61.15 Availability of information.
 - 61.16 State authority.
 - 61.17 Circumvention.

**Subpart B—National Emission Standard for
 Asbestos**

- 61.20 Applicability.
- 61.21 Definitions.
- 61.22 Emission standard.
- 61.23 Air cleaning.
- 61.24 Reporting.
- 61.25 Waste disposal sites.

**Subpart C—National Emission Standard for
 Beryllium**

- 61.28 Applicability.
- 61.31 Definitions.
- 61.32 Emission standard.
- 61.33 Stack sampling.
- 61.34 Air sampling.

**Subpart D—National Emission Standard for
 Beryllium Rocket Motor Firing**

- 61.40 Applicability.
- 61.41 Definitions.
- 61.42 Emission standard.
- 61.43 Emission testing: rocket firing or propellant disposal.
- 61.44 Stack sampling.

**Subpart E—National Emission Standard for
 Mercury**

- 61.50 Applicability.
- 61.51 Definitions.
- 61.52 Emission standard.
- 61.53 Stack sampling.
- 61.54 Sludge sampling.
- 61.55 Air quality monitoring.

§ 61.17

(2) Requiring the owner or operator of a stationary source, other than a stationary source owned or operated by the United States, to obtain permits, licenses, or approvals prior to initiating construction, modification, or operation of such source.

(Sec. 118, Clean Air Act as amended (42 U.S.C. 7418))

(28 FR 8826, Apr. 6, 1973, as amended at 43 FR 8888, Mar. 3, 1978)

§ 61.17 Circumvention.

No owner or operator subject to the provisions of this part shall build, erect, install, or use any article, machine, equipment, process, or method, the use of which conceals an emission which would otherwise constitute a violation of an applicable standard. Such concealment includes, but is not limited to, the use of gaseous dilutants to achieve compliance with a visible emissions standard, and the piecemeal carrying out of an operation to avoid coverage by a standard that applies only to operations larger than a specified size.

(40 FR 48290, Oct. 14, 1975)

Subpart B—National Emission Standard for Asbestos

§ 61.20 Applicability.

The provisions of this subpart are applicable to those sources specified in § 61.22.

§ 61.21 Definitions.

Terms used in this subpart are defined in the act, in Subpart A of this part, or in this section as follows:

(a) "Asbestos" means actinolite, amosite, anthophyllite, chrysotile, crocidolite, tremolite.

(b) "Asbestos material" means asbestos or any material containing asbestos.

(c) "Particulate asbestos material" means finely divided particles of asbestos material.

(d) "Asbestos tailings" means any solid waste product of asbestos mining or milling operations which contains asbestos.

(e) "Outside air" means the air outside buildings and structures.

Title 40—Protection of Environment

(f) "Visible emissions" means any emissions which are visually detectable without the aid of instruments and which contain particulate asbestos material.

(g) "Asbestos mill" means any facility engaged in the conversion of any intermediate step in the conversion of asbestos or into commercial asbestos. Outside storage of asbestos materials is not considered a part of such facility.

(h) "Commercial asbestos" means any variety of asbestos which is produced by extracting asbestos from asbestos ore.

(i) "Manufacturing" means the combining of commercial asbestos, or in the case of woven friction products the combining of textiles containing commercial asbestos, with any other material(s), including commercial asbestos, and the processing of this combination into a product as specified in § 61.22(c).

(j) "Demolition" means the wrecking or taking out of any load supporting structural member and any related removing or stripping of friable asbestos materials.

(k) "Friable asbestos material" means any material that contains more than 1 percent asbestos by weight and that can be crumbled, pulverized, or reduced to powder, when dry, by hand pressure.

(l) "Control device asbestos waste" means any asbestos-containing waste material that is collected in a pollution control device.

(m) "Renovation" means the removing or stripping of friable asbestos material used on any pipe, duct, boiler, tank, reactor, turbine, furnace, or structural member. Operations in which load supporting structural members are wrecked or taken out are excluded.

(n) "Planned renovation" means a renovation operation, or a number of such operations, in which the amount of friable asbestos material that will be removed or stripped within a given period of time can be predicted. Operations that are individually non-scheduled are included, provided a number of such operations can be predicted to occur during a given period of time based on operating experience.

(o) "Emergency renovation" means a renovation operation that results from a sudden, unexpected event, and is not a planned renovation. Operations necessitated by non-routine failures of equipment are included.

(p) "Adequately wetted" means sufficiently mixed or coated with water or an aqueous solution to prevent dust emissions.

(q) "Removing" means taking out friable asbestos materials used on any pipe, duct, boiler, tank, reactor, turbine, furnace, or structural member from any building, structure, facility, or installation.

(r) "Stripping" means taking off friable asbestos materials from any pipe, duct, boiler, tank, reactor, turbine, furnace, or structural member.

(s) "Fabricating" means any processing of a manufactured product containing commercial asbestos, with the exception of processing at temporary sites for the construction or restoration of buildings, structures, facilities or installations.

(t) "Inactive waste disposal site" means any disposal site or portion thereof where additional asbestos-containing waste material will not be deposited and where the surface is not disturbed by vehicular traffic.

(u) "Active waste disposal site" means any disposal site other than an inactive site.

(v) "Roadways" means surfaces on which motor vehicles travel including, but not limited to, highways, roads, streets, parking areas, and driveways.

(w) "Asbestos-containing waste material" means any waste which contains commercial asbestos and is generated by a source subject to the provisions of this subpart, including asbestos mill tailings, control device asbestos waste, friable asbestos waste material, and bags or containers that previously contained commercial asbestos.

(x) "Structural member" means any load-supporting member, such as beams and load-supporting walls; or any non-load-supporting member, such as ceilings and non-load-supporting walls.

(38 FR 4828, Apr. 8, 1973, as amended at 39 FR 15396, May 1, 1974; 40 FR 48299, Oct. 14, 1975; 42 FR 12127, Mar. 2, 1977; 43 FR 26373, June 19, 1978)

§ 61.22 Emission standard.

(a) Asbestos mills: There shall be no visible emissions to the outside air from any asbestos mill except as provided in paragraph (f) of this section.

(b) Roadways: The surfacing of roadways with asbestos tailings or with asbestos-containing waste that is generated by any source subject to paragraphs (c), (d), (e) or (h) of this section is prohibited, except for temporary roadways on an area of asbestos ore deposits. The deposition of asbestos tailings or asbestos-containing waste on roadways covered with snow or ice is considered "surfacing."

(c) Manufacturing: There shall be no visible emissions to the outside air, except as provided in paragraph (f) of this section, from any of the following operations if they use commercial asbestos or from any building or structure in which such operations are conducted.

(1) The manufacture of cloth, cord, wicks, tubing, tape, twine, rope, thread, yarn, roving, lap, or other textile materials.

(2) The manufacture of cement products.

(3) The manufacture of fireproofing and insulating materials.

(4) The manufacture of friction products.

(5) The manufacture of paper, mill-board, and felt.

(6) The manufacture of floor tile.

(7) The manufacture of paints, coatings, caulks, adhesives, sealants.

(8) The manufacture of plastics and rubber materials.

(9) The manufacture of chlorine.

(10) The manufacture of shotgun shells.

(11) The manufacture of asphalt concrete.

(d) Demolition and renovation: The requirements of this paragraph shall apply to any owner or operator of a demolition or renovation operation who intends to demolish any institutional, commercial, or industrial building (including apartment buildings having more than four dwelling units), structure, facility, installation, or portion thereof, which contains any pipe, duct, boiler, tank, reactor, turbine, furnace, or structural member that is cov-

ered or coated with friable asbestos material, except as provided in paragraph (d)(1) of this section; or who intends to renovate any institutional, commercial, or industrial building, structure, facility, installation, or portion thereof where more than 80 meters (ca. 260 feet) of pipe covered or coated with friable asbestos material are stripped or removed, or more than 15 square meters (ca. 160 square feet) of friable asbestos material used to cover or coat any duct, boiler, tank, reactor, turbine, furnace, or structural member are stripped or removed.

(1)(i) The owner or operator of a demolition operation is exempted from the requirements of this paragraph: *Provided*, (A) the amount of friable asbestos material in the building or portion thereof to be demolished is less than 80 meters (ca. 260 feet) used to insulate pipes, and less than 15 square meters (ca. 160 square feet) used to insulate or fireproof any duct, boiler, tank, reactor, turbine, furnace, or structural member, and (B) the notification requirements of paragraph (d)(1)(ii) are met.

(ii) Written notification shall be postmarked or delivered to the Administrator at least 20 days prior to commencement of demolition and shall include the information required by paragraph (d)(2) of this section, with the exception of the information required by paragraphs (d)(2)(iii), (vi), (vii), (viii), and (ix), and shall state the measured or estimated amount of friable asbestos materials which is present. Techniques of estimation shall be explained.

(2) Written notice of intention to demolish or renovate shall be provided to the Administrator by the owner or operator of the demolition or renovation operation. Such notice shall be postmarked or delivered to the Administrator at least 10 days prior to commencement of demolition, or as early as possible prior to commencement of emergency demolition subject to paragraph (d)(6) of this section, and as early as possible prior to commencement of renovation. Such notice shall include the following information:

- (i) Name of owner or operator.
- (ii) Address of owner or operator.

(iii) Description of the building, structure, facility, or installation to be demolished or renovated, including the size, age, and prior use of the structure, and the approximate amount of friable asbestos materials present.

(iv) Address or location of the building, structure, facility, or installation.

(v) Scheduled starting and completion dates of demolition or renovation.

(vi) Nature of planned demolition or renovation and method(s) to be employed.

(vii) Procedures to be employed to meet the requirements of this paragraph and paragraph (j) of this section.

(viii) The name and address or location of the waste disposal site where the friable asbestos waste will be deposited.

(ix) Name, title, and authority of the State or local governmental representative who has ordered a demolition which is subject to paragraph (d)(6) of this section.

(3)(i) For purposes of determining whether a planned renovating operation constitutes a renovation within the meaning of this paragraph, the amount of friable asbestos material to be removed or stripped shall be:

(A) For planned renovating operations involving individually non-scheduled operations, the additive amount of friable asbestos material that can be predicted will be removed or stripped at a source over the maximum period of time for which a prediction can be made. The period shall be not less than 30 days and not longer than one year.

(B) For each planned renovating operation not covered by paragraph (d)(3)(i)(A), the total amount of friable asbestos material that can be predicted will be removed or stripped at a source.

(ii) For purposes of determining whether an emergency renovating operation constitutes a renovation within the meaning of this paragraph, the amount of friable asbestos material to be removed or stripped shall be the total amount of friable asbestos material that will be removed or stripped as a result of the sudden, unexpected

event that necessitated the renovation.

(4) The following procedures shall be used to prevent emissions of particulate asbestos material to outside air:

(i) Friable asbestos materials, used on any pipe, duct, boiler, tank, reactor, turbine, furnace, or structural member, shall be removed from any building, structure, facility or installation subject to this paragraph. Such removal shall occur before wrecking or dismantling of any portion of such building, structure, facility, or installation that would break up the friable asbestos materials and before wrecking or dismantling of any other portion of such building, structure, facility, or installation that would preclude access to such materials for subsequent removal. Removal of friable asbestos materials used on any pipe, duct, or structural member which are encased in concrete or other similar structural material is not required prior to demolition, but such material shall be adequately wetted whenever exposed during demolition.

(ii) Friable asbestos materials used on pipes, ducts, boilers, tanks, reactors, turbines, furnaces, or structural members shall be adequately wetted during stripping, except as provided in paragraphs (dX4Xiv), (dX4Xvi) or (dX4Xvii) of this section.

(iii) Pipes, ducts, boilers, tanks, reactors, turbines, furnaces, or structural members that are covered or coated with friable asbestos materials may be taken out of any building, structure, facility, or installation subject to this paragraph as units or in sections provided the friable asbestos materials exposed during cutting or disjoining are adequately wetted during the cutting or disjoining operation. Such units shall not be dropped or thrown to the ground, but shall be carefully lowered to ground level.

(iv) The stripping of friable asbestos materials used on any pipe, duct, boiler, tank, reactor, turbine, furnace, or structural member that has been removed as a unit or in sections as provided in paragraph (dX4Xiii) of this section shall be performed in accordance with paragraph (dX4Xiii) of this section. Rather than comply with the wetting requirement, a local exhaust

ventilation and collection system may be used to prevent emissions to the outside air. Such local exhaust ventilation systems shall be designed and operated to capture the asbestos particulate matter produced by the stripping of friable asbestos material. There shall be no visible emissions to the outside air from such local exhaust ventilation and collection systems except as provided in paragraph (f) of this section.

(v) All friable asbestos materials that have been removed or stripped shall be adequately wetted to ensure that such materials remain wet during all remaining stages of demolition or renovation and related handling operations. Such materials shall not be dropped or thrown to the ground or a lower floor. Such materials that have been removed or stripped more than 50 feet above ground level, except those materials removed as units or in sections, shall be transported to the ground via dust-tight chutes or containers.

(vi) Except as specified below, the wetting requirements of this paragraph are suspended when the temperature at the point of wetting is below 0°C (32°F). When friable asbestos materials are not wetted due to freezing temperatures, such materials on pipes, ducts, boilers, tanks, reactors, turbines, furnaces, or structural members shall, to the maximum extent possible, be removed as units or in sections prior to wrecking. In no case shall the requirements of paragraphs (dX4Xiv) or (dX4Xv) be suspended due to freezing temperatures.

(vii) For renovation operations, local exhaust ventilation and collection systems may be used, instead of wetting as specified in paragraph (dX4Xiii), to prevent emissions of particulate asbestos material to outside air when damage to equipment resulting from the wetting would be unavoidable. Upon request and supply of adequate information, the Administrator will determine whether damage to equipment resulting from wetting to comply with the provisions of this paragraph would be unavoidable. Such local exhaust ventilation systems shall be designed and operated to capture the asbestos particulate matter produced by

§ 61.22

the stripping and removal of friable asbestos material. There shall be no visible emissions to the outside air from such local exhaust ventilation and collection systems, except as provided in paragraph (f) of this section.

(3) Sources subject to this paragraph are exempt from the requirements of §§ 61.05(a), 61.07, and 61.09.

(6) The demolition of a building, structure, facility, or installation, pursuant to an order of an authorized representative of a State or local governmental agency, issued because that building is structurally unsound and in danger of imminent collapse is exempt from all but the following requirements of paragraph (d) of this section:

(i) The notification requirements specified by paragraph (d)(2) of this section;

(ii) The requirements on stripping of friable asbestos materials from previously removed units or sections as specified in paragraph (d)(4)(iv) of this section;

(iii) The wetting, as specified by paragraph (d)(4)(v) of this section, of friable asbestos materials that have been removed or stripped;

(iv) The portion of the structure being demolished that contains friable asbestos materials shall be adequately wetted during the wrecking operation.

(e) Spraying: There shall be no visible emissions to the outside air from the spray-on application of materials containing more than 1 percent asbestos, on a dry weight basis, used on equipment and machinery, except as provided in paragraph (f) of this section. Materials sprayed on buildings, structures, pipes, and conduits shall contain less than 1 percent asbestos on a dry weight basis.

(1) Sources subject to this paragraph are exempt from the requirements of §§ 61.05(a), 61.07, and 61.09.

(2) Any owner or operator who intends to spray asbestos materials which contain more than 1 percent asbestos on a dry weight basis to insulate or fireproof equipment and machinery shall report such intention to the Administrator at least 20 days prior to the commencement of the spraying operation. Such report shall include the following information:

(i) Name of owner or operator.

Title 40—Protection of Environment

(ii) Address of owner or operator.

(iii) Location of spraying operation.

(iv) Procedures to be followed to meet the requirements of this paragraph.

(3) The spray-on application of materials in which the asbestos fibers are encapsulated with a bituminous or resinous binder during spraying and which are not friable after drying is exempted from the requirements of paragraphs (e) and (e)(2) of this section.

(f) Rather than meet the no-visible-emission requirements as specified by paragraphs (a), (c), (d), (e), (h), (j), and (k) of this section, an owner or operator may elect to use the methods specified by § 61.23 to clean emissions containing particulate asbestos material before such emissions escape to, or are vented to, the outside air.

(g) Where the presence of uncombined water is the sole reason for failure to meet the no-visible-emission requirement of paragraphs (a), (c), (d), (e), (h), (j), or (k) of this section, such failure shall not be a violation of such emission requirements.

(h) Fabricating: There shall be no visible emissions to the outside air, except as provided in paragraph (f) of this section, from any of the following operations if they use commercial asbestos or from any building or structure in which such operations are conducted:

(1) The fabrication of cement building products.

(2) The fabrication of friction products, except those operations that primarily install asbestos friction materials on motor vehicles.

(3) The fabrication of cement or silicate board for ventilation hoods; oven, electrical panels; laboratory furniture; bulkheads, partitions and ceilings for marine construction; and flow control devices for the molten metal industry.

(i) Insulating: Molded insulating material, which are friable and wet applied insulating materials which are friable after drying, installed after the effective date of these regulations, shall contain no commercial asbestos. The provisions of this paragraph do not apply to insulating materials

which are spray applied; such materials are regulated under § 61.22(e).

(j) Waste disposal for manufacturing, fabricating, demolition, renovation and spraying operations: The owner or operator of any source covered under the provisions of paragraphs (c), (d), (e), or (h) of this section shall meet the following standards:

(1) There shall be no visible emissions to the outside air, except as provided in paragraph (j)(3) of this section, during the collection; processing, including incineration; packaging; transporting; or deposition of any asbestos-containing waste material which is generated by such source.

(2) All asbestos-containing waste material shall be deposited at waste disposal sites which are operated in accordance with the provisions of § 61.25.

(3) Rather than meet the requirement of paragraph (j)(1) of this section, an owner or operator may elect to use either of the disposal methods specified under (j)(3) (i) and (ii) of this section, or an alternative disposal method which has received prior approval by the Administrator:

(i) Treatment of asbestos-containing waste material with water:

(A) Control device asbestos waste shall be thoroughly mixed with water into a slurry and other asbestos-containing waste material shall be adequately wetted. There shall be no visible emissions to the outside air from the collection, mixing and wetting operations, except as provided in paragraph (f) of this section.

(B) After wetting, all asbestos-containing waste material shall be sealed into leak-tight containers while wet, and such containers shall be deposited at waste disposal sites which are operated in accordance with the provisions of § 61.25.

(C) The containers specified under paragraph (j)(3)(i)(B) of this section shall be labeled with a warning label that states:

CAUTION

Contains Asbestos

Avoid Opening or

Breaking Container

Breathing Asbestos is Hazardous

to Your Health

Alternatively, warning labels specified by Occupational Safety and Health Standards of the Department of Labor, Occupational Safety and Health Administration (OSHA) under 29 CFR 1910.93a(k)(2)(ii) may be used.

(ii) Processing of asbestos-containing waste material into non-friable forms:

(A) All asbestos-containing waste material shall be formed into non friable pellets or other shapes and deposited at waste disposal sites which are operated in accordance with the provisions of § 61.25.

(B) There shall be no visible emissions to the outside air from the collection and processing of asbestos containing waste material, except as specified in paragraph (f) of this section.

(4) For the purposes of this paragraph (j), the term all asbestos-containing waste material as applied to demolition and renovation operations covered by paragraph (d) of this section includes only friable asbestos waste and control device asbestos waste.

(k) Waste disposal for asbestos mills. The owner or operator of any source covered under the provisions of paragraph (a) of this section shall meet the following standard:

(1) There shall be no visible emissions to the outside air, except as provided in paragraph (k)(3) of this section, during the collection, processing, packaging, transporting or deposition of any asbestos containing waste material which is generated by such source.

(2) All asbestos containing waste material shall be deposited at waste disposal sites which are operated in accordance with the provisions of § 61.25.

(3) Rather than meet the requirement of paragraph (k)(1) of this section, an owner or operator may elect to meet the following requirements in paragraphs (k)(3) (i) and (ii), or use an alternative disposal method which has

§ 61.22

received prior approval by the Administrator.

(i) There shall be no visible emissions to the outside air from the transfer of control device asbestos waste to the tailings conveyor, except as provided in paragraph (f) of this section. Such waste shall be subsequently processed either as specified in paragraph (k)(3)(ii) of this section or as specified in paragraph (j)(3) of this section.

(ii) All asbestos-containing waste material shall be adequately mixed, with a wetting agent recommended by the manufacturer of the agent to effectively wet dust and tailings, prior to deposition at a waste disposal site. Such agent shall be used as recommended for the particular dust by the manufacturer of the agent. There shall be no discharge of visible emissions to the outside air from the wetting operation except as specified in paragraph (f) of this section. Wetting may be suspended when the ambient temperature at the waste disposal site is less than -9.5°C (ca. 15°F). The ambient air temperature shall be determined by an appropriate measurement method with an accuracy of $\pm 1^{\circ}\text{C}$ ($\pm 2^{\circ}\text{F}$) and recorded at least at hourly intervals during the period that the operation of the wetting system is suspended. Records of such temperature measurements shall be retained at the source for a minimum of 2 years and made available, for inspection by the Administrator.

(i) The owner of any inactive waste disposal site, which was operated by sources covered under § 61.22(a), (c) or (h) and where asbestos-containing waste material produced by such sources was deposited, shall meet the following standards:

(1) There shall be no visible emissions to the outside air from an inactive waste disposal site subject to this paragraph, except as provided in paragraph (h)(5) of this section.

(2) Warning signs shall be displayed at all entrances, and along the property line of the site or along the perimeter of the sections of the site where asbestos-containing waste material was deposited, at intervals of 100 m (ca. 330 ft) or less, except as specified in paragraph (i)(4) of this section. Signs

Title 40—Protection of Environment

shall be posted in such a manner and location that a person may easily read the legend. The warning signs required by this paragraph shall conform to the requirements of 20" x 14" upright format signs specified in 29 CFR 1910.145(d)(4) and this paragraph. The signs shall display the following legend in the lower panel, with letter sizes and styles of a visibility at least equal to those specified in this paragraph.

LEGEND

ASBESTOS WASTE DISPOSAL SITE

DO NOT CREATE DUST

Breathing Asbestos is Hazardous to Your Health

NOTATION

1" Sans Serif, Gothic or Block

4" Sans Serif, Gothic or Block

14 Point Gothic

Spacing between lines shall be at least equal to the height of the upper of the two lines.

(3) The perimeter of the site shall be fenced in a manner adequate to deter access by the general public, except as specified in paragraph (i)(4) of this section.

(4) Warning signs and fencing are not required where the requirements of paragraphs (i)(5) (i) or (ii) of this section are met, or where a natural barrier adequately deters access by the general public. Upon request and supply of appropriate information, the Administrator will determine whether a fence or a natural barrier adequately deters access to the general public.

(5) Rather than meet the requirement of paragraph (i)(4) of this section, an owner may elect to meet the requirements of this paragraph or may use an alternative control method for emissions from inactive waste disposal sites which has received prior approval by the Administrator.

(i) The asbestos-containing waste material shall be covered with at least 15 centimeters (ca. 6 inches) of compacted, non-asbestos containing material, and a cover of vegetation shall be grown and maintained on the area

adequate to prevent exposure of the asbestos-containing waste material; or

(ii) The asbestos-containing waste material shall be covered with at least 60 centimeters (ca. 2 feet) of compacted non-asbestos-containing material and maintained to prevent exposure of the asbestos-containing waste; or

(iii) For inactive waste disposal sites for asbestos tailings, a resinous or petroleum-based dust suppression agent which effectively binds dust and controls wind erosion shall be applied. Such agent shall be used as recommended for the particular asbestos tailings by the dust suppression agent manufacturer. Other equally effective dust suppression agents may be used upon prior approval by the Administrator. For purposes of this paragraph, waste crankcase oil is not considered a dust suppression agent.

(38 FR 5826, Apr. 6, 1973, as amended at 39 FR 15398, May 3, 1974; 40 FR 48299, Oct. 14, 1975; 43 FR 28374, June 19, 1978)

§ 61.23 Air-cleaning.

If air-cleaning is elected, as permitted by §§ 61.22(f) and 61.22(d)(4)(iv), the requirements of this section must be met.

(a) Fabric filter collection devices must be used, except as noted in paragraphs (b) and (c) of this section. Such devices must be operated at a pressure drop of no more than 4 inches water gage, as measured across the filter fabric. The airflow permeability, as determined by ASTM method D737-69, must not exceed 30 ft³/min/ft² for woven fabrics or 35 ft³/min/ft² for felted fabrics, except that 40 ft³/min/ft² for woven and 45 ft³/min/ft² for felted fabrics is allowed for filtering air from asbestos ore dryers. Each square yard of felted fabric must weigh at least 14 ounces and be at least one-sixteenth inch thick throughout. Synthetic fabrics must not contain fill yarn other than that which is spun.

(b) If the use of fabric filters creates a fire or explosion hazard, the administrator may authorize the use of wet collectors designed to operate with a unit contacting energy of at least 40 inches water gage pressure.

(c) The administrator may authorize the use of filtering equipment other

than that described in paragraphs (a) and (b) of this section if the owner or operator demonstrates to the satisfaction of the administrator that the filtering of particulate asbestos material is equivalent to that of the described equipment.

(d) All air-cleaning equipment authorized by this section must be properly installed, used, operated, and maintained. Bypass devices may be used only during upset or emergency conditions and then only for so long as it takes to shut down the operation generating the particulate asbestos material.

(38 FR 5826, Apr. 6, 1973, as amended at 40 FR 48302, Oct. 14, 1975)

§ 61.21 Reporting.

The owner or operator of any existing source to which this subpart is applicable shall, within 90 days after the effective date, provide the following information to the administrator:

(a) A description of the emission control equipment used for each process:

(b) If a fabric filter device is used to control emissions, the pressure drop across the fabric filter in inches water gage.

(1) If the fabric filter device utilizes a woven fabric, the airflow permeability in ft³/min/ft² and, if the fabric is synthetic, indicate whether the fill yarn is spun or not spun.

(2) If the fabric filter device utilizes a felted fabric, the density in oz/yd², the minimum thickness in inches, and the airflow permeability in ft³/min/ft².

(c) For sources subject to §§ 61.22(j) and 61.22(k):

(1) A brief description of each process that generates asbestos-containing waste material.

(2) The average weight of asbestos-containing waste material disposed of, measured in kg/day.

(3) The emission control methods used in all stages of waste disposal.

(4) The type of disposal site or on- or off- site used for ultimate disposal, the name of the site operator, and the name and location of the disposal site.

(d) For sources subject to § 61.22(i):

(1) A brief description of the site.

§ 61.25

(2) The method or methods used to comply with the standard, or alternative procedures to be used.

(e) Such information shall accompany the information required by § 61.10. The information described in this section shall be reported using the format of Appendix A of this part.

(Sec. 114, Clean Air Act as amended (42 U.S.C. 7414))

[38 FR 8828, Apr. 6, 1973, as amended at 40 FR 48302, Oct. 14, 1975; 43 FR 8800, Mar. 3, 1978]

§ 61.25 Waste disposal sites.

In order to be an acceptable site for disposal of asbestos-containing waste material under § 61.22(j) and (k), an active waste disposal site shall meet the requirements of this section.

(a) There shall be no visible emissions to the outside air from any active waste disposal site where asbestos-containing waste material has been deposited, except as provided in paragraph (e) of this section.

(b) Warning signs shall be displayed at all entrances, and along the property line of the site or along the perimeter of the sections of the site where asbestos-containing waste material is deposited, at intervals of 100 m (ca. 330 ft) or less except as specified in paragraph (d) of this section. Signs shall be posted in such a manner and location that a person may easily read the legend. The warning signs required by this paragraph shall conform to the requirements of 20" x 14" upright format signs specified in 29 CFR 1910.145(d)(4) and this paragraph. The signs shall display the following legend in the lower panel, with letter sizes and styles of a visibility at least equal to those specified in this paragraph.

Title 40—Protection of Environment

LEGEND

ASBESTOS WASTE DISPOSAL SITE

Do Not Create Dust

Breathing Asbestos is Hazardous to Your Health

Notation

1" Sans Serif, Gothic or Block

¾" Sans Serif, Gothic or Block

14 Point Gothic

Spacing between lines shall be at least equal to the height of the upper of the two lines.

(c) The perimeter of the disposal site shall be fenced in order to adequately deter access to the general public except as specified in paragraph (d) of this section.

(d) Warning signs and fencing are not required where the requirements of paragraph (c)(1) of this section are met, or where a natural barrier adequately deters access to the general public. Upon request and supply of appropriate information, the Administrator will determine whether a fence or a natural barrier adequately deters access to the general public.

(e) Rather than meet the requirement of paragraph (a) of this section, an owner or operator may elect to meet the requirements of paragraph (c)(1) or (c)(2) of this section, or may use an alternative control method for emissions from active waste disposal sites which has received prior approval by the Administrator.

(1) At the end of each operating day, or at least once every 24-hour period while the site is in continuous operation, the asbestos-containing waste material which was deposited at the site during the operating day or previous 24-hour period shall be covered with at least 15 centimeters (ca. 6 inches) of compacted non-asbestos-containing material.

(2) At the end of each operating day, or at least once every 24-hour period while the disposal site is in continuous operation, the asbestos-containing waste material which was deposited at the site during the operating day or previous 24-hour period shall be covered with a resinous or petroleum-

Chapter I—Environmental Protection Agency

§ 61.32

based dust suppression agent which effectively binds dust and controls wind erosion. Such agent shall be used as recommended for the particular dust by the dust suppression agent manufacturer. Other equally effective dust suppression agents may be used upon prior approval by the Administrator. For purposes of this paragraph, waste crankcase oil is not considered a dust suppression agent.

[40 FR 48302, Oct. 11, 1975]

WESTEN

B. HAZARDOUS WASTE

PART 260

**HAZARDOUS WASTE MANAGEMENT
SYSTEM: GENERAL
40 CFR 260**

6060A

Environmental Protection Agency

Part 260

days at 20° C, with a volatile solids reduction of at least 38 percent.

Air Drying: Liquid sludge is allowed to drain and/or dry on under-drained sand beds, or paved or unpaved basins in which the sludge is at a depth of nine inches. A minimum of three months is needed, two months of which temperatures average on a daily basis above 0° C.

Anaerobic digestion: The process is conducted in the absence of air at residence times ranging from 60 days at 20° C to 15 days at 35° to 55° C, with a volatile solids reduction of at least 38 percent.

Composting: Using the within-vessel, static aerated pile or windrow composting methods, the solid waste is maintained at minimum operating conditions of 40° C for 3 days. For four hours during this period the temperature exceeds 55° C.

Lime Stabilization: Sufficient lime is added to produce a pH of 12 after 2 hours of contact.

Other methods: Other methods or operating conditions may be acceptable if pathogens and vector attraction of the waste (volatile solids) are reduced to an extent equivalent to the reduction achieved by any of the above methods.

B. Processes to Further Reduce Pathogens

Composting: Using the within-vessel composting method, the solid waste is maintained at operating conditions of 55° C or greater for three days. Using the static aerated pile composting method, the solid waste is maintained at operating conditions of 55° C or greater for three days. Using the windrow composting method, the solid waste attains a temperature of 55° C or greater for at least 15 days during the composting period. Also, during the high temperature period, there will be a minimum of five turnings of the windrow.

Heat drying: Dewatered sludge cake is dried by direct or indirect contact with hot gases, and moisture content is reduced to 10 percent or lower. Sludge particles reach temperatures well in excess of 80° C, or the wet bulb temperature of the gas stream in contact with the sludge at the point where it leaves the dryer is in excess of 80° C.

Heat treatment: Liquid sludge is heated to temperatures of 180° C for 30 minutes.

Thermophilic Aerobic Digestion: Liquid sludge is agitated with air or oxygen to maintain aerobic conditions at residence times of 10 days at 55-60° C, with a volatile solids reduction of at least 38 percent.

Other methods: Other methods or operating conditions may be acceptable if pathogens and vector attraction of the waste (volatile solids) are reduced to an extent equivalent to the reduction achieved by any of the above methods.

Any of the processes listed below, if added to the processes described in Section A

above, further reduce pathogens. Because the processes listed below, on their own, do not reduce the attraction of disease vectors, they are only add-on in nature.

Beta ray irradiation: Sludge is irradiated with beta rays from an accelerator at dosages of at least 1.0 megarad at room temperature (ca. 20° C).

Gamma ray irradiation: Sludge is irradiated with gamma rays from certain isotopes, such as ⁶⁰Cobalt and ¹³⁷Cesium, at dosages of at least 1.0 megarad at room temperature (ca. 20° C).

Pasteurization: Sludge is maintained for at least 30 minutes at a minimum temperature of 70° C.

Other methods: Other methods or operating conditions may be acceptable if pathogens are reduced to an extent equivalent to the reduction achieved by any of the above add-on methods.

PART 260—HAZARDOUS WASTE MANAGEMENT SYSTEM: GENERAL

Subpart A—General

Sec.

- 260.1 Purpose, scope, and applicability.
- 260.2 Availability of information; confidentiality of information.
- 260.3 Use of number and gender.

Subpart B—Definitions

- 260.10 Definitions.
- 260.11 References.

Subpart C—Rulemaking Petitions

- 260.20 General.
- 260.21 Petitions for equivalent testing or analytical methods.
- 260.22 Petitions to amend Part 261 to exclude a waste produced at a particular facility.
- 260.30 Variances from classification as a solid waste.
- 260.31 Standards and criteria for variances from classification as a solid waste.
- 260.32 Variances to be classified as a boiler.
- 260.33 Procedures for variances from classification as a solid waste or to be classified as a boiler.
- 260.40 Additional regulation of certain hazardous waste recycling activities on a case-by-case basis.
- 260.41 Procedures for case-by-case regulation of hazardous waste recycling activities.

APPENDIX I—OVERVIEW OF SUBTITLE C REGULATIONS

§ 260.1

AUTHORITY: Secs. 1004, 2002, 3001 through 3007, 3010, and 7004, Solid Waste Disposal Act, as amended by the Resource Conservation and Recovery Act of 1976, as amended, 42 U.S.C. 6904, 6912, 6921 through 6927, 6930, and 6974.

SOURCE: 48 FR 13071, May 19, 1983, unless otherwise noted.

EDITORIAL NOTE: The reporting or record-keeping provisions included in the final rule published at 47 FR 32274, July 28, 1982, will be submitted for approval to the Office of Management and Budget (OMB). They are not effective until OMB approval has been obtained. EPA will publish a notice of the effective date of the reporting and record-keeping provisions of this rule after it obtains OMB approval.

Subpart A—General

§ 260.1 Purpose, scope, and applicability.

(a) This part provides definitions of terms, general standards, and overview information applicable to Parts 260 through 265 of this chapter.

(b) In this part: (1) Section 260.2 sets forth the rules that EPA will use in making information it receives available to the public and sets forth the requirements that generators, transporters, or owners or operators of treatment, storage, or disposal facilities must follow to assert claims of business confidentiality with respect to information that is submitted to EPA under Parts 260 through 265 of this chapter.

(2) Section 260.3 establishes rules of grammatical construction for Parts 260 through 265 of this chapter.

(3) Section 260.10 defines terms which are used in Parts 260 through 265 of this chapter.

(4) Section 260.20 establishes procedures for petitioning EPA to amend, modify, or revoke any provision of Parts 260 through 265 of this chapter and establishes procedures governing EPA's action on such petitions.

(5) Section 260.21 establishes procedures for petitioning EPA to approve testing methods as equivalent to those prescribed in Parts 261, 264, or 265 of this chapter.

(6) Section 260.22 establishes procedures for petitioning EPA to amend Subpart D of Part 261 to exclude a waste from a particular facility.

48 CFR Ch. I (7-1-85 Edition)

§ 260.2 Availability of information; confidentiality of information.

(a) Any information provided to EPA under Parts 260 through 265 of this chapter will be made available to the public to the extent and in the manner authorized by the Freedom of Information Act, 5 U.S.C. section 552, section 3007(b) of RCRA and EPA regulations implementing the Freedom of Information Act and section 3007(b), Part 2 of this chapter, as applicable.

(b) Any person who submits information to EPA in accordance with Parts 260 through 265 of this chapter may assert a claim of business confidentiality covering part or all of that information by following the procedures set forth in § 2.203(b) of this chapter. Information covered by such a claim will be disclosed by EPA only to the extent, and by means of the procedures, set forth in Part 2, Subpart B of this chapter. However, if no such claim accompanies the information when it is received by EPA, it may be made available to the public without further notice to the person submitting it.

§ 260.3 Use of number and gender.

As used in Parts 260 through 265 of this chapter:

(a) Words in the masculine gender also include the feminine and neuter genders, and

(b) Words in the singular include the plural; and

(c) Words in the plural include the singular.

Subpart B—Definitions

§ 260.10 Definitions.

When used in Parts 260 through 265 of this chapter, the following terms have the meanings given below:

"Act" or "RCRA" means the Solid Waste Disposal Act, as amended by the Resource Conservation and Recovery Act of 1976, as amended, 42 U.S.C. section 6901 et seq.

"Active portion" means that portion of a facility where treatment, storage, or disposal operations are being or have been conducted after the effective date of Part 261 of this chapter and which is not a closed portion. See

also "closed portion" and "inactive portion".

"Administrator" means the Administrator of the Environmental Protection Agency, or his designee.

"Aquifer" means a geologic formation, group of formations, or part of a formation capable of yielding a significant amount of ground water to wells or springs.

"Authorized representative" means the person responsible for the overall operation of a facility or an operational unit (i.e., part of a facility), e.g., the plant manager, superintendent or person of equivalent responsibility.

"Boiler" means an enclosed device using controlled flame combustion and having the following characteristics:

(ix) The unit must have physical provisions for recovering and exporting thermal energy in the form of steam, heated fluids, or heated gases, and

(ii) The unit's combustion chamber and primary energy recovery section(s) must be of integral design. To be of integral design, the combustion chamber and the primary energy recovery section(s) (such as waterwalls and superheaters) must be physically formed into one manufactured or assembled unit. A unit in which the combustion chamber and the primary energy recovery section(s) are joined only by ducts or connections carrying flue gas is not integrally designed; however, secondary energy recovery equipment (such as economizers or air preheaters) need not be physically formed into the same unit as the combustion chamber and the primary energy recovery section. The following units are not precluded from being boilers solely because they are not of integral design: process heaters (units that transfer energy directly to a process stream); and fluidized bed combustion units, and

(iii) While in operation, the unit must maintain a thermal energy recovery efficiency of at least 60 percent, calculated in terms of the recovered energy compared with the thermal value of the fuel, and

(iv) The unit must export and utilize at least 75 percent of the recovered energy, calculated on an annual basis. In this calculation, no credit shall be

given for recovered heat used internally in the same unit. (Examples of internal use are the preheating of fuel or combustion air, and the driving of induced or forced draft fans or feed-water pumps); or

(2) The unit is one which the Regional Administrator has determined, on a case-by-case basis, to be a boiler, after considering the standards in § 260.32.

"Certification" means a statement of professional opinion based upon knowledge and belief.

"Closed portion" means that portion of a facility which an owner or operator has closed in accordance with the approved facility closure plan and all applicable closure requirements. (See also "active portion" and "inactive portion".)

"Confined aquifer" means an aquifer bounded above and below by impermeable beds or by beds of distinctly lower permeability than that of the aquifer itself; an aquifer containing confined ground water.

"Container" means any portable device in which a material is stored, transported, treated, disposed of, or otherwise handled.

"Contingency plan" means a document setting out an organized, planned, and coordinated course of action to be followed in case of a fire, explosion, or release of hazardous waste or hazardous waste constituents which could threaten human health or the environment.

"Designated facility" means a hazardous waste treatment, storage, or disposal facility which has received an EPA permit (or a facility with interim status) in accordance with the requirements of Parts 270 and 271 of this chapter, a permit from a State authorized in accordance with Part 271 of this chapter, or that is regulated under § 261.6(c)(2) or Subpart F of Part 266 of this chapter, and that has been designated on the manifest by the generator pursuant to § 262.20.

"Dike" means an embankment or ridge of either natural or man-made materials used to prevent the movement of liquids, sludges, solids, or other materials.

"Discharge" or "hazardous waste discharge" means the accidental or in-

tentional spilling, leaking, pumping, pouring, emitting, emptying, or dumping of hazardous waste into or on any land or water.

"Disposal" means the discharge, deposit, injection, dumping, spilling, leaking, or placing of any solid waste or hazardous waste into or on any land or water so that such solid waste or hazardous waste or any constituent thereof may enter the environment or be emitted into the air or discharged into any waters, including ground waters.

"Disposal facility" means a facility or part of a facility at which hazardous waste is intentionally placed into or on any land or water, and at which waste will remain after closure.

"Elementary neutralization unit" means a device which:

(1) Is used for neutralizing wastes which are hazardous wastes only because they exhibit the corrosivity characteristic defined in § 261.22 of this chapter, or are listed in Subpart D of Part 261 of this chapter only for this reason; and

(2) Meets the definition of tank, container, transport vehicle, or vessel in § 260.10 of this chapter.

"EPA hazardous waste number" means the number assigned by EPA to each hazardous waste listed in Part 261, Subpart D, of this chapter and to each characteristic identified in Part 261, Subpart C, of this chapter.

"EPA identification number" means the number assigned by EPA to each generator, transporter, and treatment, storage, or disposal facility.

"EPA region" means the states and territories found in any one of the following ten regions:

Region I—Maine, Vermont, New Hampshire, Massachusetts, Connecticut, and Rhode Island.

Region II—New York, New Jersey, Commonwealth of Puerto Rico, and the U.S. Virgin Islands.

Region III—Pennsylvania, Delaware, Maryland, West Virginia, Virginia, and the District of Columbia.

Region IV—Kentucky, Tennessee, North Carolina, Mississippi, Alabama, Georgia, South Carolina, and Florida.

Region V—Minnesota, Wisconsin, Illinois, Michigan, Indiana and Ohio.

Region VI—New Mexico, Oklahoma, Arkansas, Louisiana, and Texas.

Region VII—Nebraska, Kansas, Missouri, and Iowa.

Region VIII—Montana, Wyoming, North Dakota, South Dakota, Utah, and Colorado.

Region IX—California, Nevada, Arizona, Hawaii, Guam, American Samoa, Commonwealth of the Northern Mariana Islands.

Region X—Washington, Oregon, Idaho, and Alaska.

"Equivalent method" means any testing or analytical method approved by the Administrator under §§ 260.20 and 260.21.

"Existing hazardous waste management (HWM) facility" or "existing facility" means a facility which was in operation or for which construction commenced on or before November 19, 1980. A facility has commenced construction if:

(1) The owner or operator has obtained the Federal, State and local approvals or permits necessary to begin physical construction; and either

(2)(i) A continuous on-site, physical construction program has begun; or

(ii) The owner or operator has entered into contractual obligations—which cannot be cancelled or modified without substantial loss—for physical construction of the facility to be completed within a reasonable time.

"Existing portion" means that land surface area of an existing waste management unit, included in the original Part A permit application, on which wastes have been placed prior to the issuance of a permit.

"Facility" means all contiguous land, and structures, other appurtenances, and improvements on the land, used for treating, storing, or disposing of hazardous waste. A facility may consist of several treatment, storage, or disposal operational units (e.g., one or more landfills, surface impoundments, or combinations of them).

"Federal agency" means any department, agency, or other instrumentality of the Federal Government, any independent agency or establishment of the Federal Government including any Government corporation, and the Government Printing Office.

"Federal, State and local approvals or permits necessary to begin physical construction" means permits and ap-

provals required under Federal, State or local hazardous waste control statutes, regulations or ordinances.

"Food-chain crops" means tobacco, crops grown for human consumption, and crops grown for feed for animals whose products are consumed by humans.

"Free liquids" means liquids which readily separate from the solid portion of a waste under ambient temperature and pressure.

"Freeboard" means the vertical distance between the top of a tank or surface impoundment dike, and the surface of the waste contained therein.

"Generator" means any person, by site, whose act or process produces hazardous waste identified or listed in Part 261 of this chapter or whose act first causes a hazardous waste to become subject to regulation.

"Ground water" means water below the land surface in a zone of saturation.

"Hazardous waste" means a hazardous waste as defined in § 261.3 of this chapter.

"Hazardous waste constituent" means a constituent that caused the Administrator to list the hazardous waste in Part 261, Subpart D, of this chapter, or a constituent listed in Table 1 of § 261.24 of this chapter.

"In operation" refers to a facility which is treating, storing, or disposing of hazardous waste.

"Inactive portion" means that portion of a facility which is not operated after the effective date of Part 261 of this chapter. (See also "active portion" and "closed portion".)

"Incinerator" means any enclosed device using controlled flame combustion that neither meets the criteria for classification as a boiler nor is listed as an industrial furnace.

"Incompatible waste" means a hazardous waste which is unsuitable for:

(1) Placement in a particular device or facility because it may cause corrosion or decay of containment materials (e.g., container inner liners or tank walls); or

(2) Commingling with another waste or material under uncontrolled conditions because the commingling might produce heat or pressure, fire or explosion, violent reaction, toxic dusts,

mists, fumes, or gases, or flammable fumes or gases.

(See Part 265, Appendix V, of this chapter for examples.)

"Individual generation site" means the contiguous site at or on which one or more hazardous wastes are generated. An individual generation site, such as a large manufacturing plant, may have one or more sources of hazardous waste but is considered a single or individual generation site if the site or property is contiguous.

"Industrial furnace" means any of the following enclosed devices that are integral components of manufacturing processes and that use controlled flame devices to accomplish recovery of materials or energy:

- (1) Cement kilns
- (2) Lime kilns
- (3) Aggregate kilns
- (4) Phosphate kilns
- (5) Coke ovens
- (6) Blast furnaces
- (7) Smelting, melting and refining furnaces (including pyrometallurgical devices such as cupolas, reverberator furnaces, sintering machine, roasters, and foundry furnaces)
- (8) Titanium dioxide chloride process oxidation reactors
- (9) Methane reforming furnaces
- (10) Pulping liquor recovery furnaces
- (11) Combustion devices used in the recovery of sulfur values from spent sulfuric acid
- (12) Such other devices as the Administrator may, after notice and comment, add to this list on the basis of one or more of the following factors:
 - (i) The design and use of the device primarily to accomplish recovery of material products;
 - (ii) The use of the device to burn or reduce raw materials to make a material product;
 - (iii) The use of the device to burn or reduce secondary materials as effective substitutes for raw materials, in processes using raw materials as principal feedstocks;
 - (iv) The use of the device to burn or reduce secondary materials as ingredients in an industrial process to make a material product;

(v) The use of the device in common industrial practice to produce a material product; and

(vi) Other factors, as appropriate.

"Injection well" means a well into which fluids are injected. (See also "underground injection".)

"Inner liner" means a continuous layer of material placed inside a tank or container which protects the construction materials of the tank or container from the contained waste or reagents used to treat the waste.

"International shipment" means the transportation of hazardous waste into or out of the jurisdiction of the United States.

"Landfill" means a disposal facility or part of a facility where hazardous waste is placed in or on land and which is not a land treatment facility, a surface impoundment, or an injection well.

"Landfill cell" means a discrete volume of a hazardous waste landfill which uses a liner to provide isolation of wastes from adjacent cells or wastes. Examples of landfill cells are trenches and pits.

"Land treatment facility" means a facility or part of a facility at which hazardous waste is applied onto or incorporated into the soil surface; such facilities are disposal facilities if the waste will remain after closure.

"Leachate" means any liquid, including any suspended components in the liquid, that has percolated through or drained from hazardous waste.

"Liner" means a continuous layer of natural or man-made materials, beneath or on the sides of a surface impoundment, landfill, or landfill cell, which restricts the downward or lateral escape of hazardous waste, hazardous waste constituents, or leachate.

"Management" or "hazardous waste management" means the systematic control of the collection, source separation, storage, transportation, processing, treatment, recovery, and disposal of hazardous waste.

"Manifest" means the shipping document EPA form 8700-22 and, if necessary, EPA form 8700-22A, originated and signed by the generator in accordance with the instructions included in the Appendix to Part 262.

"Manifest document number" means the U.S. EPA twelve digit identification number assigned to the generator plus a unique five digit document number assigned to the Manifest by the generator for recording and reporting purposes.

"Mining overburden returned to the mine site" means any material overlying an economic mineral deposit which is removed to gain access to that deposit and is then used for reclamation of a surface mine.

"Movement" means that hazardous waste transported to a facility in an individual vehicle.

"New hazardous waste management facility" or "new facility" means a facility which began operation, or for which construction commenced after October 21, 1976. (See also "Existing hazardous waste management facility".)

"On-site" means the same or geographically contiguous property which may be divided by public or private right-of-way, provided the entrance and exit between the properties is at a cross-roads intersection, and access is by crossing as opposed to going along the right-of-way. Non-contiguous properties owned by the same person but connected by a right-of-way which he controls and to which the public does not have access, is also considered on-site property.

"Open burning" means the combustion of any material without the following characteristics:

- (1) Control of combustion air to maintain adequate temperature for efficient combustion.
- (2) Containment of the combustion reaction in an enclosed device to provide sufficient residence time and mixing for complete combustion, and
- (3) Control of emission of the gaseous combustion products.

(See also "Incineration" and "thermal treatment".)

"Operator" means the person responsible for the overall operation of a facility.

"Owner" means the person who owns a facility or part of a facility.

"Partial closure" means the closure of a discrete part of a facility in accordance with the applicable closure requirements of Parts 264 or 265 of

this chapter. For example, partial closure may include the closure of a trench, a unit operation, a landfill cell, or a pit, while other parts of the same facility continue in operation or will be placed in operation in the future.

"Person" means an individual, trust, firm, joint stock company, Federal Agency, corporation (including a government corporation), partnership, association, State, municipality, commission, political subdivision of a State, or any interstate body.

"Personnel" or "facility personnel" means all persons who work, at, or oversee the operations of, a hazardous waste facility, and whose actions or failure to act may result in noncompliance with the requirements of Parts 264 or 265 of this chapter.

"Pile" means any non-containerized accumulation of solid, nonflowing hazardous waste that is used for treatment or storage.

"Point source" means any discernible, confined, and discrete conveyance, including, but not limited to any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, container, rolling stock, concentrated animal feeding operation, or vessel or other floating craft, from which pollutants are or may be discharged. This term does not include return flows from irrigated agriculture.

"Publicly owned treatment works" or "POTW" means any device or system used in the treatment (including recycling and reclamation) of municipal sewage or industrial wastes of a liquid nature which is owned by a "State" or "municipality" (as defined by Section 502(4) of the CWA). This definition includes sewers, pipes, or other conveyances only if they convey wastewater to a POTW providing treatment.

"Regional Administrator" means the Regional Administrator for the EPA Region in which the facility is located, or his designee.

"Representative sample" means a sample of a universe or whole (e.g., waste pile, lagoon, ground water) which can be expected to exhibit the average properties of the universe or whole.

"Run-off" means any rainwater, leachate, or other liquid that drains over land from any part of a facility.

"Run-on" means any rainwater, leachate, or other liquid that drains over land onto any part of a facility.

"Saturated zone" or "zone of saturation" means that part of the earth's crust in which all voids are filled with water.

"Sludge" means any solid, semi-solid, or liquid waste generated from a municipal, commercial, or industrial wastewater treatment plant, water supply treatment plant, or air pollution control facility exclusive of the treated effluent from a wastewater treatment plant.

"Solid waste" means a solid waste as defined in § 261.2 of this chapter.

"State" means any of the several States, the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, American Samoa, and the Commonwealth of the Northern Mariana Islands.

"Storage" means the holding of hazardous waste for a temporary period, at the end of which the hazardous waste is treated, disposed of, or stored elsewhere.

"Surface impoundment" or "impoundment" means a facility or part of a facility which is a natural topographic depression, man-made excavation, or diked area formed primarily of earthen materials (although it may be lined with man-made materials), which is designed to hold an accumulation of liquid wastes or wastes containing free liquids, and which is not an injection well. Examples of surface impoundments are holding, storage, settling, and aeration pits, ponds and lagoons.

"Tank" means a stationary device, designed to contain an accumulation of hazardous waste which is constructed primarily of non-earthen materials (e.g., wood, concrete, steel, plastic) which provide structural support.

Thermal treatment means the treatment of hazardous waste in a device which uses elevated temperatures as the primary means to change the chemical, physical, or biological character or composition of the hazardous waste. Examples of thermal treatment processes are incineration

molten salt, pyrolysis, calcination, wet air oxidation, and microwave discharge. (See also "incinerator" and "open burning".)

"Totally enclosed treatment facility" means a facility for the treatment of hazardous waste which is directly connected to an industrial production process and which is constructed and operated in a manner which prevents the release of any hazardous waste or any constituent thereof into the environment during treatment. An example is a pipe in which waste acid is neutralized.

"Transfer facility" means any transportation related facility including loading docks, parking areas, storage areas and other similar areas where shipments of hazardous waste are held during the normal course of transportation.

"Transport vehicle" means a motor vehicle or rail car used for the transportation of cargo by any mode. Each cargo-carrying body (trailer, railroad freight car, etc.) is a separate transport vehicle.

"Transportation" means the movement of hazardous waste by air, rail, highway, or water.

"Transporter" means a person engaged in the offsite transportation of hazardous waste by air, rail, highway, or water.

"Treatment" means any method, technique, or process, including neutralization, designed to change the physical, chemical, or biological character or composition of any hazardous waste so as to neutralize such waste, or so as to recover energy or material resources from the waste, or so as to render such waste non-hazardous, or less hazardous, safer to transport, store, or dispose of, or amenable for recovery, amenable for storage, or reduced in volume.

"Treatment zone" means a soil area of the unsaturated zone of a land treatment unit within which hazardous constituents are degraded, transformed, or immobilized.

"Underground injection" means the subsurface emplacement of fluids through a bored, drilled or driven well, or through a dug well where the depth of the dug well is greater than

the largest surface dimension. (See also "injection well".)

"Unsaturated zone" or "zone of aeration" means the zone between the land surface and the water table.

"United States" means the 50 States, the District of Columbia, the Commonwealth of Puerto Rico, the U.S. Virgin Islands, Guam, American Samoa, and the Commonwealth of the Northern Mariana Islands.

"Uppermost aquifer" means the geologic formation nearest the natural ground surface that is an aquifer, as well as lower aquifers that are hydraulically interconnected with this aquifer within the facility's property boundary.

"Vessel" includes every description of watercraft, used or capable of being used as a means of transportation on the water.

"Wastewater treatment unit" means a device which:

(1) Is part of a wastewater treatment facility which is subject to regulation under either Section 402 or Section 307(b) of the Clean Water Act; and

(2) Receives and treats or stores an influent wastewater which is a hazardous waste as defined in § 261.3 of this chapter, or generates and accumulates a wastewater treatment sludge which is a hazardous waste as defined in § 261.3 of this chapter, or treats or stores a wastewater treatment sludge which is a hazardous waste as defined in § 261.3 of this chapter; and

(3) Meets the definition of tank in § 260.10 of this chapter.

"Water (bulk shipment)" means the bulk transportation of hazardous waste which is loaded or carried on board a vessel without containers or labels.

"Well" means any shaft or pit dug or bored into the earth, generally of a cylindrical form, and often walled with bricks or tubing to prevent the earth from caving in.

"Well injection" See underground injection.

45 FR 33073 May 19 1980 as amended at 45 FR 22028 Oct 30 1980 45 FR 26075 Nov 17 1980 45 FR 26336 Nov 19 1980 45 FR 46948 Dec 31 1980 46 FR 2348 Jan 3 1981 46 FR 27479 May 20 1981 47 FR 22349 July 29 1982 48 FR 2511 Jan 19 1983 48 FR 46293 Apr 1 1983 49 FR

Environmental Protection Agency

§ 260.20

10500, Mar. 20, 1984; 50 FR 661, Jan. 4, 1985]

EFFECTIVE DATE NOTE: At 50 FR 661, Jan. 4, 1985, § 260.10 was amended by adding the definitions for "Boiler" and "Industrial furnace" and revising the definitions for "Designated facility" and "Incinerator", effective July 5, 1985. For the convenience of the user, the superseded text is set out below.

§ 260.10 Definitions.

"Designated facility" means a hazardous waste treatment, storage, or disposal facility which has received an EPA permit (or a facility with interim status) in accordance with the requirements of 40 CFR Parts 270 and 271 of this chapter, or a permit from a State authorized in accordance with Part 271 of this chapter, that has been designated on the manifest by the generator pursuant to § 262.20.

"Incinerator" means an enclosed device using controlled flame combustion, the primary purpose of which is to thermally break down hazardous waste. Examples of incinerators are rotary kiln, fluidized bed, and liquid injection incinerators.

§ 260.11 References.

(a) When used in Parts 260 through 265 of this chapter, the following publications are incorporated by reference:

"ASTM Standard Test Methods for Flash Point of Liquids by Setafish Closed Tester," ASTM Standard D-3278-78, available from American Society for Testing and Materials, 1916 Race Street, Philadelphia, Pa. 19103.

"ASTM Standard Test Methods for Flash Point by Pensky-Martens Closed Tester," ASTM Standard D-93-79 or D-93-80, D-93-80 is available from American Society for Testing and Materials, 1916 Race Street, Philadelphia, Pa. 19103.

"Flammable and Combustible Liquids Code" (1977 or 1981), available from the National Fire Protection Association, 470 Atlantic Avenue, Boston, Massachusetts 02210.

Test Methods for Evaluating Solid Waste: Physical Chemical Methods", EPA Publication SW-846 (Second Edition, 1982 as amended by Update I

(April, 1984), and Update II (April, 1985)). The second edition of SW-846 and Updates I and II are available from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20401, (202) 783-3228, on a subscription basis.

(b) The references listed in paragraph (a) of this section are also available for inspection at the Office of the Federal Register, 1100 L Street, NW, Washington, D.C. 20408. These incorporations by reference were approved by the Director of the Federal Register. These materials are incorporated as they exist on the date of approval and a notice of any change in these materials will be published in the FEDERAL REGISTER.

[46 FR 35247, July 7, 1981, as amended at 50 FR 18374, Apr. 30, 1985]

Subpart C—Rulemaking Petitions

§ 260.20 General.

(a) Any person may petition the Administrator to modify or revoke any provision in Parts 260 through 265 of this chapter. This section sets forth general requirements which apply to all such petitions. Section 260.21 sets forth additional requirements for petitions to add a testing or analytical method to Part 261, 264 or 265. Section 260.22 sets forth additional requirements for petitions to exclude a waste at a particular facility from § 261.3 of this chapter or the lists of hazardous wastes in Subpart D of Part 261.

(b) Each petition must be submitted to the Administrator by certified mail and must include:

- (1) The petitioner's name and address;
- (2) A statement of the petitioner's interest in the proposed action;
- (3) A description of the proposed action, including (where appropriate) suggested regulatory language; and
- (4) A statement of the need and justification for the proposed action, including any supporting tests, studies, or other information.

(c) The Administrator will make a tentative decision to grant or deny a petition and will publish notice of

§ 260.21

such tentative decision, either in the form of an advanced notice of proposed rulemaking, a proposed rule, or a tentative determination to deny the petition, in the **FEDERAL REGISTER** for written public comment.

(d) Upon the written request of any interested person, the Administrator may, at his discretion, hold an informal public hearing to consider oral comments on the tentative decision. A person requesting a hearing must state the issues to be raised and explain why written comments would not suffice to communicate the person's views. The Administrator may in any case decide on his own motion to hold an informal public hearing.

(e) After evaluating all public comments the Administrator will make a final decision by publishing in the **FEDERAL REGISTER** a regulatory amendment or a denial of the petition.

§ 260.21 Petitions for equivalent testing or analytical methods.

(a) Any person seeking to add a testing or analytical method to Part 261, 264, or 265 of this chapter may petition for a regulatory amendment under this section and § 260.20. To be successful, the person must demonstrate to the satisfaction of the Administrator that the proposed method is equal to or superior to the corresponding method prescribed in Part 261, 264, or 265 of this chapter, in terms of its sensitivity, accuracy, and precision (i.e., reproducibility).

(b) Each petition must include, in addition to the information required by § 260.20(b):

(1) A full description of the proposed method, including all procedural steps and equipment used in the method;

(2) A description of the types of wastes or waste matrices for which the proposed method may be used;

(3) Comparative results obtained from using the proposed method with those obtained from using the relevant or corresponding methods prescribed in Part 261, 264, or 265 of this chapter;

(4) An assessment of any factors which may interfere with, or limit the use of, the proposed method; and

(5) A description of the quality control procedures necessary to ensure

40 CFR Ch. I (7-1-85 Edition)

the sensitivity, accuracy and precision of the proposed method.

(c) After receiving a petition for an equivalent method, the Administrator may request any additional information on the proposed method which he may reasonably require to evaluate the method.

(d) If the Administrator amends the regulations to permit use of a new testing method, the method will be incorporated in "Test Methods for the Evaluation of Solid Waste: Physical/Chemical Methods," SW-846, U.S. Environmental Protection Agency, Office of Solid Waste, Washington, D.C. 20460.

(45 FR 33073, May 19, 1980, as amended at 49 FR 47391, Dec. 4, 1984)

§ 260.22 Petitions to amend Part 261 to exclude a waste produced at a particular facility.

(a) Any person seeking to exclude a waste at a particular generating facility from the lists in Subpart D of Part 261 may petition for a regulatory amendment under this section and § 260.20. To be successful, the petitioner must demonstrate to the satisfaction of the Administrator that the waste produced by a particular generating facility does not meet any of the criteria under which the waste was listed as a hazardous waste and, in the case of an acutely hazardous waste listed under § 261.11(a)(2), that it also does not meet the criterion of § 261.11(a)(3). A waste which is so excluded may still, however, be a hazardous waste by operation of Subpart C of Part 261.

(b) The procedures in this section and § 260.20 may also be used to petition the Administrator for a regulatory amendment to exclude from § 261.3(a)(2)(ii) or (c), a waste which is described in those sections and is either a waste listed in Subpart D, contains a waste listed in Subpart D, or is derived from a waste listed in Subpart D. This exclusion may only be issued for a particular generating, storage, treatment, or disposal facility. The petitioner must make the same demonstration as required by paragraph (a) of this section, except that where the waste is a mixture of solid

waste and one or more listed hazardous wastes or is derived from one or more hazardous wastes, his demonstration may be made with respect to each constituent listed waste or the waste mixture as a whole. A waste which is so excluded may still be a hazardous waste by operation of Subpart C of Part 261.

(c) If the waste is listed with codes "F", "C", "R", or "E" in Subpart D, the petitioner must show that demonstration samples of the waste do not exhibit the relevant characteristic defined in § 261.21, § 261.22, § 261.23, or § 261.24 using any applicable test methods prescribed therein.

(d) If the waste is listed with code "T" in Subpart D, the petitioner must demonstrate that:

(1) Demonstration samples of the waste do not contain the constituent (as defined in Appendix VII) that caused the Administrator to list the waste, using the appropriate test methods prescribed in Appendix III; or

(2) The waste does not meet the criterion of § 261.11(a)(3) when considering the factors in § 261.11(a)(3) (i) through (xi).

(e) If the waste is listed with the code "H" in Subpart D, the petitioner must demonstrate that the waste does not meet both of the following criteria:

(1) The criterion of § 261.11(a)(2);
(2) The criterion of § 261.11(a)(3) when considering the factors listed in § 261.11(a)(3) (i) through (xi).

(f) [Reserved for listing radioactive wastes.]

(g) [Reserved for listed infectious wastes.]

(h) Demonstration samples must consist of enough representative samples, but in no case less than four samples, taken over a period of time sufficient to represent the variability or the uniformity of the waste.

(i) Each petition must include, in addition to the information required by § 260.20 b):

1. The name and address of the laboratory facility performing the sampling or tests of the waste.

2. The names and qualifications of the persons sampling and testing the waste.

(3) The dates of sampling and testing;

(4) The location of the generating facility;

(5) A description of the manufacturing processes or other operations and feed materials producing the waste and an assessment of whether such processes, operations, or feed materials can or might produce a waste that is not covered by the demonstration;

(6) A description of the waste and an estimate of the average and maximum monthly and annual quantities of waste covered by the demonstration;

(7) Pertinent data on and discussion of the factors delineated in the respective criterion for listing a hazardous waste, where the demonstration is based on the factors in § 261.11(a)(3);

(8) A description of the methodologies and equipment used to obtain the representative samples;

(9) A description of the sample handling and preparation techniques, including techniques used for extraction, containerization and preservation of the samples;

(10) A description of the tests performed (including results);

(11) The names and model numbers of the instruments used in performing the tests; and

(12) The following statement signed by the generator of the waste or his authorized representative:

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this demonstration and all attached documents, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

(j) After receiving a petition for an exclusion, the Administrator may request any additional information which he may reasonably require to evaluate the petition.

(k) An exclusion will only apply to the waste generated at the individual facility covered by the demonstration and will not apply to waste from any other facility.

§ 260.30

40 CFR Ch. I (7-1-85 Edition)

(l) The Administrator may exclude only part of the waste for which the demonstration is submitted where he has reason to believe that variability of the waste justifies a partial exclusion.

(m) The Administrator may (but shall not be required to) grant a temporary exclusion before making a final decision under § 260.20(d) whenever he finds that there is a substantial likelihood that an exclusion will be finally granted. The Administrator will publish notice of any such temporary exclusion in the *FEDERAL REGISTER*.

EDITORIAL NOTE For information on the availability of a guidance manual for petitions to delist hazardous wastes, see 50 FR 21607, May 28, 1985.

§ 260.30 Variances from classification as a solid waste.

In accordance with the standards and criteria in § 260.31 and the procedures in § 260.33, the Regional Administrator may determine on a case-by-case basis that the following recycled materials are not solid wastes:

(a) Materials that are accumulated speculatively without sufficient amounts being recycled (as defined in § 261.1(c)(8) of this chapter);

(b) Materials that are reclaimed and then reused within the original primary production process in which they were generated;

(c) Materials that have been reclaimed but must be reclaimed further before the materials are completely recovered.

(50 FR 661, Jan. 4, 1985; 50 FR 14219, Apr. 11, 1985)

EFFECTIVE DATE NOTE At 50 FR 661, Jan. 4, 1985, § 260.30 was added, effective July 3, 1985.

§ 260.31 Standards and criteria for variances from classification as a solid waste.

(a) The Regional Administrator may grant requests for a variance from classifying as a solid waste those materials that are accumulated speculatively without sufficient amounts being recycled if the applicant demonstrates that sufficient amounts of the material will be recycled or transferred for recycling in the following year. If a variance is granted, it is valid only for

the following year, but can be renewed, on an annual basis, by filing a new application. The Regional Administrator's decision will be based on the following standards and criteria:

(1) The manner in which the material is expected to be recycled, when the material is expected to be recycled, and whether this expected disposition is likely to occur (for example, because of past practice, market factors, the nature of the material, or contractual arrangements for recycling);

(2) The reason that the applicant has accumulated the material for one or more years without recycling 75 percent of the volume accumulated at the beginning of the year;

(3) The quantity of material already accumulated and the quantity expected to be generated and accumulated before the material is recycled;

(4) The extent to which the material is handled to minimize loss;

(5) Other relevant factors.

(b) The Regional Administrator may grant requests for a variance from classifying as a solid waste those materials that are reclaimed and then reused as feedstock within the original primary production process in which the materials were generated if the reclamation operation is an essential part of the production process. This determination will be based on the following criteria:

(1) How economically viable the production process would be if it were to use virgin materials, rather than reclaimed materials;

(2) The prevalence of the practice on an industry-wide basis;

(3) The extent to which the material is handled before reclamation to minimize loss;

(4) The time periods between generating the material and its reclamation, and between reclamation and return to the original primary production process;

(5) The location of the reclamation operation in relation to the production process;

(6) Whether the reclaimed material is used for the purpose for which it was originally produced when it is returned to the original process, and whether it is returned to the process in substantially its original form;

Environmental Protection Agency

§ 260.40

(7) Whether the person who generates the material also reclaims it;

(8) Other relevant factors.

(c) The Regional Administrator may grant requests for a variance from classifying as a solid waste those materials that have been reclaimed but must be reclaimed further before recovery is completed if, after initial reclamation, the resulting material is commodity-like (even though it is not yet a commercial product, and has to be reclaimed further). This determination will be based on the following factors:

(1) The degree of processing the material has undergone and the degree of further processing that is required;

(2) The value of the material after it has been reclaimed;

(3) The degree to which the reclaimed material is like an analogous raw material;

(4) The extent to which an end market for the reclaimed material is guaranteed;

(5) The extent to which the reclaimed material is handled to minimize loss;

(6) Other relevant factors.

[50 FR 662, Jan. 4, 1985]

EFFECTIVE DATE NOTE: At 50 FR 662, Jan. 4, 1985, § 260.31 was added, effective July 5, 1985.

§ 260.32 Variance to be classified as a boiler.

In accordance with the standards and criteria in § 260.10 (definition of "boiler"), and the procedures in § 260.33, the Regional Administrator may determine on a case-by-case basis that certain enclosed devices using controlled flame combustion are boilers, even though they do not otherwise meet the definition of boiler contained in § 260.10, after considering the following criteria:

(a) The extent to which the unit has provisions for recovering and exporting thermal energy in the form of steam, heated fluids, or heated gases; and

(b) The extent to which the combustion chamber and energy recovery equipment are of integral design; and

(c) The efficiency of energy recovery, calculated in terms of the recovered energy compared with the thermal value of the fuel; and

(d) The extent to which exported energy is utilized; and

(e) The extent to which the device is in common and customary use as a "boiler" functioning primarily to produce steam, heated fluids, or heated gases; and

(f) Other factors, as appropriate.

[50 FR 662, Jan. 4, 1985]

EFFECTIVE DATE NOTE: At 50 FR 662, Jan. 4, 1985, § 260.32 was added, effective July 5, 1985.

§ 260.33 Procedures for variances from classification as a solid waste or to be classified as a boiler.

The Regional Administrator will use the following procedures in evaluating applications for variances from classification as a solid waste or applications to classify particular enclosed flame combustion devices as boilers:

(a) The applicant must apply to the Regional Administrator in the region where the recycler is located. The application must address the relevant criteria contained in § 260.31 or § 260.32 of this part.

(b) The Regional Administrator will evaluate the application and issue a draft notice tentatively granting or denying the application. Notification of this tentative decision will be provided by newspaper advertisement and radio broadcast in the locality where the recycler is located. The Regional Administrator will accept comment on the tentative decision for 30 days, and may also hold a public hearing upon request or at his discretion. The Regional Administrator will issue a final decision after receipt of comments and after the hearing (if any), and this decision may not be appealed to the Administrator.

[50 FR 662, Jan. 4, 1985]

EFFECTIVE DATE NOTE: At 50 FR 662, Jan. 4, 1985, § 260.33 was added, effective July 5, 1985.

§ 260.40 Additional regulation of certain hazardous waste recycling activities on a case-by-case basis.

(a) The Regional Administrator may decide on a case-by-case basis that persons accumulating or storing the recy-

recyclable materials described in § 261.6(a)(2)(iv) of this chapter should be regulated under § 261.6 (b) and (c) of this chapter. The basis for this decision is that the materials are being accumulated or stored in a manner that does not protect human health and the environment because the materials or their toxic constituents have not been adequately contained, or because the materials being accumulated or stored together are incompatible. In making this decision, the Regional Administrator will consider the following factors:

- (1) The types of materials accumulated or stored and the amounts accumulated or stored;
- (2) The method of accumulation or storage;
- (3) The length of time the materials have been accumulated or stored before being reclaimed;
- (4) Whether any contaminants are being released into the environment, or are likely to be so released; and
- (5) Other relevant factors.

The procedures for this decision are set forth in § 260.41 of this chapter.

(50 FR 662, Jan. 4, 1985)

EFFECTIVE DATE NOTE: At 50 FR 662, Jan. 4, 1985, § 260.40 was added, effective July 5, 1985.

§ 260.41 Procedures for case-by-case regulation of hazardous waste recycling activities.

The Regional Administrator will use the following procedures when determining whether to regulate hazardous waste recycling activities described in § 261.6(a)(2)(iv) under the provisions of § 261.6 (b) and (c), rather than under the provisions of Subpart F of Part 266 of this chapter.

- (a) If a generator is accumulating the waste, the Regional Administrator will issue a notice setting forth the factual basis for the decision and stating that the person must comply with the applicable requirements of Subparts A, C, D, and E of Part 262 of this chapter. The notice will become final within 30 days, unless the person served requests a public hearing to challenge the decision. Upon receiving such a request, the Regional Administrator will hold a public hearing. The Regional Administrator will provide

notice of the hearing to the public and allow public participation at the hearing. The Regional Administrator will issue a final order after the hearing stating whether or not compliance with Part 262 is required. The order becomes effective 30 days after service of the decision unless the Regional Administrator specifies a later date or unless review by the Administrator is requested. The order may be appealed to the Administrator by any person who participated in the public hearing. The Administrator may choose to grant or to deny the appeal. Final Agency action occurs when a final order is issued and Agency review procedures are exhausted.

- (b) If the person is accumulating the recyclable material as a storage facility, the notice will state that the person must obtain a permit in accordance with all applicable provisions of Parts 270 and 124 of this chapter. The owner or operator of the facility must apply for a permit within no less than 60 days and no more than six months of notice, as specified in the notice. If the owner or operator of the facility wishes to challenge the Regional Administrator's decision, he may do so in his permit application, in a public hearing held on the draft permit, or in comments filed on the draft permit or on the notice of intent to deny the permit. The fact sheet accompanying the permit will specify the reasons for the Agency's determination. The question of whether the Regional Administrator's decision was proper will remain open for consideration during the public comment period discussed under § 124.11 of this chapter and in any subsequent hearing.

(50 FR 663, Jan. 4, 1985)

EFFECTIVE DATE NOTE: At 50 FR 663, Jan. 4, 1985, § 260.41 was added, effective July 5, 1985.

APPENDIX I—OVERVIEW OF SUBTITLE C REGULATIONS

The Agency believes that there are many people who suspect, but are not sure, that their activities are subject to control under the RCRA Subtitle C rules. This appendix is written for these people. It is designed to help those who are unfamiliar with the hazardous waste control program determine

with which, if any, of the regulations they should comply.

Definition of Solid Waste

The first question which such a person should ask himself is: "Is the material I handle a solid waste?" If the answer to this question is "No", then the material is not subject to control under RCRA and, therefore, the person need not worry about whether he should comply with the Subtitle C rules.

Section 261.2 of this chapter provides a definition of "solid waste" which expands the statutory definition of that term given in section 1004(27) of RCRA. This definition is diagrammed in Figure 1 below.

Figure 1 explains that all materials are either: (1) Garbage refuse, or sludge; (2) solid, liquid, semi-solid or contained gaseous material; or (3) something else. No materials in the third category are solid waste. All materials in the first category are solid waste. Materials in the second category are solid waste unless they are one of the five exclusions specified in § 261.4(a).

Definition of Hazardous Waste

If a person has determined that his material is a "solid waste", the next question he should ask is: "Is the solid waste I handle a hazardous waste?"

Hazardous waste is defined in § 261.3 of this chapter. Section 261.3 provides that, in general, a solid waste is a hazardous waste if: (1) It is, or contains, a hazardous waste listed in Subpart D of Part 261 of this chapter, or (2) the waste exhibits any of the characteristics defined in Subpart C of Part 261. However, Parts 260 and 261 also contain provisions which exclude (§§ 261.4(b), 260.20, and 260.22) certain solid wastes from the definition of "hazardous waste", even though they are listed in Subpart D or exhibit one or more of the characteristics defined in Subpart C. Figure 2 depicts the interplay of these special provisions with the definition of "hazardous waste". It presents a series of questions which a person should ask himself concerning his waste. After doing so, the person should be able to determine if the solid waste he handles is a hazardous waste.

Hazardous Waste Regulations

If this is the case, the person should look at Figure 3. Figure 3 depicts the special provisions specified in the final Part 261 rules for hazardous waste which:

1. Is generated by a small quantity generator
2. Is or is intended to be legitimately and beneficially used, re-used, recycled, or reclaimed

3. Is a sludge: is listed in Part 261, Subpart D; or is a mixture containing a waste listed in Part 261, Subpart D.

For each of these Groups, Figure 3 indicates with which Subtitle C regulations (if any) the person handling these wastes must comply. Figure 3 also explains that, if a person handles hazardous waste which is not included in any one of the above three categories, his waste is subject to the Subtitle C regulations diagrammed in Figure 4.

Figure 4 is a flowchart which identifies the three categories of activities regulated under the Subtitle C rules, and the corresponding set of rules with which people in each of these categories must comply. It points out that all people who handle hazardous waste are either: (1) Generators of hazardous waste, (2) transporters of hazardous waste, (3) owners or operators of hazardous waste treatment, storage, or disposal facilities, or (4) a combination of the above. Figure 4 indicates that all of these people must notify EPA of their hazardous waste activities in accordance with the Section 3010 Notification Procedures (see 45 FR 12746 *et seq.*), and obtain an EPA identification number.

It should be noted that people handling wastes listed in Subpart D of Part 261 who have filed, or who intend to file an application to exempt their waste from regulation under the Subtitle C rules, must also comply with the notification requirements of section 3010.

If a person generates hazardous waste, Figure 4 indicates that he must comply with the Part 262 rules. If he transports it, he must comply with the Part 263 rules. The standards in both these Parts are designed to ensure, among other things, proper recordkeeping and reporting, the use of a manifest system to track shipments of hazardous waste, the use of proper labels and containers, and the delivery of the waste to a permitted treatment, storage, or disposal facility.

If a person owns or operates a facility which treats, stores, or disposes of hazardous waste, the standards with which he must comply depend on a number of factors. First of all, if the owner or operator of a storage facility is also the person who generates the waste, and the waste is stored at the facility for less than 90 days for subsequent shipment off-site, then the person must comply with § 262.34 of the Part 262 rules.

All other owners or operators of treatment, storage, or disposal facilities must comply with either the Part 264 or the Part 265 rules. To determine with which of these sets of rules an owner or operator must comply, he must find out whether his facility qualifies for interim status. To qualify, the owner or operator must: (1) Have been

Part 260, App. I

40 CFR Ch. I (7-1-85 Edition)

treating, storing, or disposing of the hazardous waste, or commenced facility construction on or before October 21, 1976, (2) comply with the Section 3010 notification requirements, and (3) apply for a permit under Part 270 of this chapter.

If the owner or operator has done all of the above, he qualifies for interim status, and he must comply with the Part 265 rules. These rules contain administrative requirements, monitoring and closure standards, and an abbreviated set of technical and closure and post-closure cost estimate requirements. The owner or operator must comply with these standards until final administrative disposition of his permit application is made. If a permit is issued to the owner or operator, he must then comply with the permit which will be based on the Part 264 rules.

If the owner or operator has not carried out the above three requirements, he does not qualify for interim status. Until he is issued a permit for his facility, the owner or operator must stop waste management operations (if any) at the facility, and send his hazardous waste (if any) to a facility whose owner or operator has interim status or to a storage facility following the Part 262 rules.

In order to apply for a permit, the owner or operator must comply with the procedures specified in Part 270 of this chapter.

It should be noted that the Agency will be periodically revising the rules depicted in Figures 3 and 4. All persons are encouraged to write to EPA to verify that the regulations which they are reading are up-to-date. To obtain this verification, contact: Solid Waste Information, U.S. Environmental Protection Agency, 26 West St. Clair Street, Cincinnati, Ohio 45268 (513) 684-5362.

FIGURE 1
DEFINITION OF A SOLID WASTE




FIGURE 2
DEFINITION OF A HAZARDOUS WASTE




FIGURE 3

SPECIAL PROVISIONS FOR CERTAIN HAZARDOUS WASTE





FIGURE 1
REGULATIONS FOR HAZARDOUS WASTE
NOT COVERED IN DIAGRAM 1



* T/S/D stands for Treatment, Storage, or Disposal
** O/O stands for Owners or Operators

[45 FR 33073, May 19, 1980, as amended at 48 FR 14293, Apr. 1, 1983]

WESTON

B. HAZARDOUS WASTE

PART 261

**IDENTIFICATION AND LISTING OF HAZARDOUS WASTE
40 CFR 261**

5060A

Environmental Protection Agency

§ 261.1

PART 261—IDENTIFICATION AND LISTING OF HAZARDOUS WASTE

Subpart A—General

- 261.1 Purpose and scope
- 261.2 Definition of solid waste
- 261.3 Definition of hazardous waste
- 261.4 Exclusions
- 261.5 Special requirements for hazardous waste generated by small quantity generators
- 261.6 Requirements for recyclable materials
- 261.7 Residues of hazardous waste in empty containers

Subpart B—Criteria for Identifying the Characteristics of Hazardous Waste and for Listing Hazardous Wastes

- 261.10 Criteria for identifying the characteristics of hazardous waste
- 261.11 Criteria for listing hazardous waste

Subpart C—Characteristics of Hazardous Waste

- 261.20 General
- 261.21 Characteristic of ignitability
- 261.22 Characteristic of corrosivity
- 261.23 Characteristic of reactivity
- 261.24 Characteristic of EP toxicity

Subpart D—Lists of Hazardous Wastes

- 261.30 General
- 261.31 Hazardous wastes from non-specific sources
- 261.32 Hazardous wastes from specific sources
- 261.33 Discarded commercial chemical products, off-specification species, container residues, and spill residues thereof

APPENDICES

- APPENDIX I—REPRESENTATIVE SAMPLING METHODS
- APPENDIX II—EP TOXICITY TEST PROCEDURES
- APPENDIX III—CHEMICAL ANALYSIS TEST METHODS
- APPENDIX IV—(RESERVED FOR RADIOACTIVE WASTE TEST METHODS)
- APPENDIX V—(RESERVED FOR INFECTIOUS WASTE TREATMENT SPECIFICATIONS)
- APPENDIX VI—(RESERVED FOR ETIOLOGIC AGENTS)
- APPENDIX VII—BASIS FOR LISTING HAZARDOUS WASTE
- APPENDIX VIII—HAZARDOUS CONSTITUENTS
- APPENDIX IX—WASTES EXCLUDED UNDER 40 CFR 260.20 AND 260.22

Sec

APPENDIX X—METHOD OF ANALYSIS FOR CHLORINATED DIBENZO-P-DIOXINS AND DIBENZOFURANS

AUTHORITY Secs. 1006, 2002(a), 3001 and 3002 of the Solid Waste Disposal Act as amended by the Resource Conservation and Recovery Act of 1976, as amended (42 U.S.C. 6905, 6912(a), 6921, and 6922)

SOURCE 45 FR 33,119, May 19, 1980, unless otherwise noted

Subpart A—General

§ 261.1 Purpose and scope.

(a) This part identifies those solid wastes which are subject to regulation as hazardous wastes under Parts 262 through 265 and Parts 270, 271, and 124 of this chapter and which are subject to the notification requirements of section 3010 of RCRA. In this part:

(1) Subpart A defines the terms "solid waste" and "hazardous waste," identifies those wastes which are excluded from regulation under Parts 262 through 265, 270, 271 and 124 and establishes special management requirements for hazardous waste produced by small quantity generators and hazardous waste which is used, re-used, recycled or reclaimed.

(2) Subpart B sets forth the criteria used by EPA to identify characteristics of hazardous waste and to list particular hazardous wastes.

(3) Subpart C identifies characteristics of hazardous waste.

(4) Subpart D lists particular hazardous wastes.

(b)(1) The definition of solid waste contained in this part applies only to wastes that also are hazardous for purposes of the regulations implementing Subtitle C of RCRA. For example, it does not apply to materials (such as non-hazardous scrap, paper, textiles, or rubber) that are not otherwise hazardous wastes and that are recycled.

(2) This part identifies only some of the materials which are solid wastes and hazardous wastes under Sections 3007, 3013, and 7003 of RCRA. A material which is not defined as a solid waste in this part, or is not a hazardous waste identified or listed in this part, is still a solid waste and a hazard-

§ 261.2

40 CFR Ch. I (7-1-85 Edition)

ous waste for purposes of these sections if:

(i) In the case of Sections 3007 and 3013, EPA has reason to believe that the material may be a solid waste within the meaning of Section 1004(27) of RCRA and a hazardous waste within the meaning of Section 1004(5) of RCRA; or

(ii) In the case of Section 7003, the statutory elements are established.

(c) For the purposes of §§ 261.2 and 261.6:

(1) A "spent material" is any material that has been used and as a result of contamination can no longer serve the purpose for which it was produced without processing;

(2) "Sludge" has the same meaning used in § 260.10 of this chapter;

(3) A "by-product" is a material that is not one of the primary products of a production process and is not solely or separately produced by the production process. Examples are process residues such as slags or distillation column bottoms. The term does not include a co-product that is produced for the general public's use and is ordinarily used in the form it is produced by the process.

(4) A material is "reclaimed" if it is processed to recover a usable product, or if it is regenerated. Examples are recovery of lead values from spent batteries and regeneration of spent solvents.

(5) A material is "used or reused" if it is either:

(i) Employed as an ingredient (including use as an intermediate) in an industrial process to make a product (for example, distillation bottoms from one process used as feedstock in another process). However, a material will not satisfy this condition if distinct components of the material are recovered as separate end products (as when metals are recovered from metal-containing secondary materials); or

(ii) Employed in a particular function or application as an effective substitute for a commercial product (for example, spent pickle liquor used as phosphorous precipitant and sludge conditioner in wastewater treatment).

(6) "Scrap metal" is bits and pieces of metal parts (e.g., bars, turnings,

rods, sheets, wire) or metal pieces that may be combined together with bolts or soldering (e.g., radiators, scrap automobiles, railroad box cars), when worn or superfluous can be recycled.

(7) A material is "recycled" if it is used, reused, or reclaimed.

(8) A material is "accumulated speculatively" if it is accumulated before being recycled. A material is not accumulated speculatively, however, if the person accumulating it can show that the material is potentially recyclable and has a feasible means of being recycled; and that—during the calendar year (commencing on January 1)—the amount of material that is recycled, or transferred to a different site for recycling, equals at least 75 percent by weight or volume of the amount of that material accumulated at the beginning of the period. In calculating the percentage of turnover, the 75 percent requirement is to be applied to each material of the same type (e.g., slags from a single smelting process) that is recycled in the same way (i.e., from which the same material is recovered or that is used in the same way). Materials accumulating in units that would be exempt from regulation under § 261.4(c) are not to be included in making the calculation. (Materials that are already defined as solid wastes also are not to be included in making the calculation.) Materials are no longer in this category once they are removed from accumulation for recycling, however.

[45 FR 33119, May 19, 1980, as amended at 48 FR 14293, Apr. 1, 1983; 50 FR 663, Jan. 4, 1985]

EFFECTIVE DATE NOTE: At 50 FR 663, Jan. 4, 1985, § 261.1(c) was added, effective July 5, 1985.

§ 261.2 Definition of solid waste.

(a)(1) A solid waste is any discarded material that is not excluded by § 261.4(a) or that is not excluded by variance granted under §§ 260.30 and 260.31.

(2) A discarded material is any material which is:

(i) Abandoned, as explained in paragraph (b) of this section; or

Environmental Protection Agency

§ 261.2

(ii) *Recycled*, as explained in paragraph (c) of this section; or

(iii) Considered *inherently waste-like*, as explained in paragraph (d) of this section.

(b) Materials are solid waste if they are *abandoned* by being:

(1) Disposed of; or

(2) Burned or incinerated; or

(3) Accumulated, stored, or treated (but not recycled) before or in lieu of being abandoned by being disposed of, burned, or incinerated.

(c) Materials are solid wastes if they are *recycled*—or accumulated, stored, or treated before recycling—as specified in paragraphs (c)(1) through (c)(4) of this section.

(1) *Used in a manner constituting disposal*. (i) Materials noted with a "*" in Column 1 of Table 1 are solid wastes when they are:

(A) Applied to or placed on the land in a manner that constitutes disposal; or

(B) Contained in products that are applied to the land (in which case the product itself remains a solid waste).

(ii) However, commercial chemical products listed in § 261.33 are not solid wastes if they are applied to the land and that is their ordinary manner of use.

(2) *Burning for energy recovery*. (i) Materials noted with a "*" in column 2 of Table 1 are solid wastes when they are:

(A) Burned to recover energy;

(B) Used to produce a fuel;

(C) Contained in fuels (in which case the fuel itself remains a solid waste).

(ii) However, commercial chemical products listed in § 261.33 are not solid wastes if they are themselves fuels.

(3) *Reclaimed*. Materials noted with a "*" in column 3 of Table 1 are solid wastes when reclaimed.

(4) *Accumulated speculatively*. Materials noted with a "*" in column 4 of Table 1 are solid wastes when accumulated speculatively.

TABLE 1

	Use constituting disposal (261.2(c)(1))	Energy recovery/ fuel (261.2(c)(2))	Reclama- tion (261.2(c)(3))	Speculative accumula- tion (261.2(c)(4))
	(1)	(2)	(3)	(4)
Spent Materials	(*)	(*)	(*)	(*)
Sudges (listed in 40 CFR Part 261.31 or 32)	(*)	(*)	(*)	(*)
Sudges exhibiting a characteristic of hazardous waste	(*)	(*)	(*)	(*)
By-products (listed in 40 CFR Part 261.31 or 261.32)	(*)	(*)	(*)	(*)
By-products exhibiting a characteristic of hazardous waste	(*)	(*)	(*)	(*)
Commercial chemical products listed in 40 CFR § 261.33	(*)	(*)	(*)	(*)
Scrap metal	(*)	(*)	(*)	(*)

Note.—The terms "spent materials", "sudges", "by-products" and "scrap metal" are defined in § 261.1.

(d) *Inherently waste-like materials*. The following materials are solid wastes when they are recycled in any manner:

(1) Hazardous Waste Nos. F020, F021 (unless used as an ingredient to make a product at the site of generation), F022, F023, F026, and F028.

(2) The Administrator will use the following criteria to add wastes to that list:

(i)(A) The materials are ordinarily disposed of, burned, or incinerated; or

(B) The materials contain toxic constituents listed in Appendix VIII of Part 261 and these constituents are

not ordinarily found in raw materials or products for which the materials substitute (or are found in raw materials or products in smaller concentrations) and are not used or reused during the recycling process; and

(ii) The material may pose a substantial hazard to human health and the environment when recycled.

(e) *Materials that are not solid waste when recycled*. (1) Materials are not solid wastes when they can be shown to be recycled by being:

(i) Used or reused as ingredients in an industrial process to make a prod-

§ 261.2

uct, provided the materials are not being reclaimed; or

(ii) Used or reused as effective substitutes for commercial products; or

(iii) Returned to the original process from which they are generated, without first being reclaimed. The material must be returned as a substitute for raw material feedstock, and the process must use raw materials as principal feedstocks.

(2) The following materials are solid wastes, even if the recycling involves use, reuse, or return to the original process (described in paragraphs (e)(1)(i)-(iii) of this section):

(i) Materials used in a manner constituting disposal, or used to produce products that are applied to the land; or

(ii) Materials burned for energy recovery, used to produce a fuel, or contained in fuels; or

(iii) Materials accumulated speculatively; or

(iv) Materials listed in paragraph (d)(1) of this section.

(f) *Documentation of claims that materials are not solid wastes or are conditionally exempt from regulation.* Respondents in actions to enforce regulations implementing Subtitle C of RCRA who raise a claim that a certain material is not a solid waste, or is conditionally exempt from regulation, must demonstrate that there is a known market or disposition for the material, and that they meet the terms of the exclusion or exemption. In doing so, they must provide appropriate documentation (such as contracts showing that a second person uses the material as an ingredient in a production process) to demonstrate that the material is not a waste, or is exempt from regulation. In addition, owners or operators of facilities claiming that they actually are recycling materials must show that they have the necessary equipment to do so.

(50 FR 664, Jan. 4, 1985)

EFFECTIVE DATE NOTE: At 50 FR 664, Jan. 4, 1985, § 261.2 was revised, effective July 3, 1985, except for paragraph (e) which was effective December 20, 1984. For the convenience of the user, the superseded text is set out below.

§ 261.2 Definition of solid waste.

(a) A solid waste is any garbage, refuse, sludge or any other waste material which is not excluded under § 261.4(a).

(b) An "other waste material" is any solid, liquid, semi-solid or contained gaseous material, resulting from industrial, commercial, mining or agricultural operations, or from community activities which:

(1) Is discarded or is being accumulated, stored or physically, chemically or biologically treated prior to being discarded; or

(2) Has served its original intended use and sometimes is discarded; or

(3) Is a manufacturing or mining by-product and sometimes is discarded.

(c) A material is "discarded" if it is abandoned (and not used, re-used, reclaimed or recycled) by being:

(1) Discarded of; or

(2) Burned or incinerated, except where the material is being burned as a fuel for the purpose of recovering usable energy; or

(3) Physically, chemically, or biologically treated (other than burned or incinerated) in lieu of or prior to being disposed of.

(d) A material is "disposed of" if it is discharged, deposited, injected, dumped, spilled, leaked or placed into or on any land or water so that such material or any constituent thereof may enter the environment or be emitted into the air or discharged into ground or surface waters.

(e) A "manufacturing or mining by-product" is a material that is not one of the primary products of a particular manufacturing or mining operation, is a secondary and incidental product of the particular operation and would not be solely and separately manufactured or mined by the particular manufacturing or mining operation. The term does not include an intermediate manufacturing or mining product which results from one of the steps in a manufacturing or mining process and is typically processed through the next step of the process within a short time.

§ 261.3 Definition of hazardous waste.

(a) A solid waste, as defined in § 261.2, is a hazardous waste if:

(1) It is not excluded from regulation as a hazardous waste under § 261.4(b); and

(2) It meets any of the following criteria:

(i) It exhibits any of the characteristics of hazardous waste identified in Subpart C.

(ii) It is listed in Subpart D and has not been excluded from the lists in Subpart D under §§ 260.20 and 260.22 of this chapter.

(iii) It is a mixture of a solid waste and a hazardous waste that is listed in Subpart D solely because it exhibits one or more of the characteristics of hazardous waste identified in Subpart C, unless the resultant mixture no longer exhibits any characteristic of hazardous waste identified in Subpart C.

(iv) It is a mixture of solid waste and one or more hazardous wastes listed in Subpart D and has not been excluded from this paragraph under §§ 260.20 and 260.22 of this chapter; however, the following mixtures of solid wastes and hazardous wastes listed in Subpart D are not hazardous wastes (except by application of paragraph (a)(2)(i) or (ii) of this section) if the generator can demonstrate that the mixture consists of wastewater the discharge of which is subject to regulation under either Section 402 or Section 307(b) of the Clean Water Act (including wastewater at facilities which have eliminated the discharge of wastewater) and:

(A) One or more of the following spent solvents listed in § 261.31—carbon tetrachloride, tetrachloroethylene, trichloroethylene—provided that the maximum total weekly usage of these solvents (other than the amounts that can be demonstrated not to be discharged to wastewater) divided by the average weekly flow of wastewater into the headworks of the facility's wastewater treatment or pretreatment system does not exceed 1 part per million; or

(B) One or more of the following spent solvents listed in § 261.31—methylene chloride, 1,1,1-trichloroethane, chlorobenzene, o-dichlorobenzene, cresols, cresylic acid, nitrobenzene, toluene, methyl ethyl ketone, carbon disulfide, isobutanol, pyridine, spent chlorofluorocarbon solvents—provided that the maximum total weekly usage of these solvents (other than the amounts that can be demonstrated not to be discharged to wastewater) divided by the average weekly flow of wastewater into the headworks of the facility's wastewater treatment or pretreatment system does not exceed 25 parts per million; or

(C) One of the following wastes listed in § 261.32—heat exchanger

bundle cleaning sludge from the petroleum refining industry (EPA Hazardous Waste No. K050); or

(D) A discarded commercial chemical product, or chemical intermediate listed in § 261.33, arising from *de minimis* losses of these materials from manufacturing operations in which these materials are used as raw materials or are produced in the manufacturing process. For purposes of this subparagraph, "*de minimis*" losses include those from normal material handling operations (e.g., spills from the unloading or transfer of materials from bins or other containers, leaks from pipes, valves or other devices used to transfer materials); minor leaks of process equipment, storage tanks or containers; leaks from well-maintained pump packings and seals; sample purgings; relief device discharges; discharges from safety showers and rinsing and cleaning of personal safety equipment; and rinsate from empty containers or from containers that are rendered empty by that rinsing; or

(E) Wastewater resulting from laboratory operations containing toxic (T) wastes listed in Subpart D, provided that the annualized average flow of laboratory wastewater does not exceed one percent of total wastewater flow into the headworks of the facility's wastewater treatment or pretreatment system, or provided the wastes, combined annualized average concentration does not exceed one part per million in the headworks of the facility's wastewater treatment or pretreatment facility. Toxic (T) wastes used in laboratories that are demonstrated not to be discharged to wastewater are not to be included in this calculation.

(b) A solid waste which is not excluded from regulation under paragraph (a)(1) of this section becomes a hazardous waste when any of the following events occur:

(1) In the case of a waste listed in Subpart D, when the waste first meets the listing description set forth in Subpart D.

(2) In the case of a mixture of solid waste and one or more listed hazardous wastes, when a hazardous waste listed in Subpart D is first added to the solid waste.

§ 261.4

(3) In the case of any other waste (including a waste mixture), when the waste exhibits any of the characteristics identified in Subpart C.

(c) Unless and until it meets the criteria of paragraph (d):

(1) A hazardous waste will remain a hazardous waste.

(2)(i) Except as otherwise provided in paragraph (c)(2)(ii) of this section, any solid waste generated from the treatment, storage, or disposal of a hazardous waste, including any sludge, spill residue, ash, emission control dust, or leachate (but not including precipitation run-off) is a hazardous waste. (However, materials that are reclaimed from solid wastes and that are used beneficially are not solid wastes and hence are not hazardous wastes under this provision unless the reclaimed material is burned for energy recovery or used in a manner constituting disposal.)

(ii) The following solid wastes are not hazardous even though they are generated from the treatment, storage, or disposal of a hazardous waste, unless they exhibit one or more of the characteristics of hazardous waste: (A) Waste pickle liquor sludge generated by lime stabilization of spent pickle liquor from the iron and steel industry (SIC Codes 331 and 332).

(d) Any solid waste described in paragraph (c) of this section is not a hazardous waste if it meets the following criteria:

(1) In the case of any solid waste, it does not exhibit any of the characteristics of hazardous waste identified in Subpart C.

(2) In the case of a waste which is a listed waste under Subpart D, contains a waste listed under Subpart D or is derived from a waste listed in Subpart D, it also has been excluded from paragraph (c) under §§ 260.20 and 260.22 of this chapter.

(45 FR 33119, May 19, 1980, as amended at 48 FR 56588, Nov. 11, 1983; 50 FR 14219, Apr. 11, 1985)

EFFECTIVE DATE NOTE. At 50 FR 884, Jan. 4, 1985, and corrected at 50 FR 14219, Apr. 11, 1985, § 261.3(c)(2) was revised, effective July 3, 1985. For the convenience of the user, the superseded text is set out below.

40 CFR Ch. I (7-1-85 Edition)

§ 261.3 Definition of hazardous waste.

(c) . . .

(2)(i) Except as otherwise provided in paragraph (c)(2)(ii) of this section, any solid waste generated from the treatment, storage, or disposal of a hazardous waste, including any sludge, spill residue, ash, emission control dust or leachate (but not including precipitation run-off) is a hazardous waste.

(ii) The following solid wastes are not hazardous even though they are generated from the treatment, storage, or disposal of a hazardous waste, unless they exhibit one or more of the characteristics of hazardous waste: (A) Waste pickle liquor sludge generated by lime stabilization of spent pickle liquor from the iron and steel industry (SIC codes 331 and 332).

§ 261.4 Exclusions.

(a) *Materials which are not solid wastes.* The following materials are not solid wastes for the purpose of this part:

(1)(i) Domestic sewage; and
(ii) Any mixture of domestic sewage and other wastes that passes through a sewer system to a publicly-owned treatment works for treatment. "Domestic sewage" means untreated sanitary wastes that pass through a sewer system.

(2) Industrial wastewater discharges that are point source discharges subject to regulation under Section 402 of the Clean Water Act, as amended.

(Comment: This exclusion applies only to the actual point source discharge. It does not exclude industrial wastewaters while they are being collected, stored or treated before discharge, nor does it exclude sludges that are generated by industrial wastewater treatment.)

(3) Irrigation return flows.

(4) Source, special nuclear or by-product material as defined by the Atomic Energy Act of 1954, as amended, 42 U.S.C. 2011 *et seq.*

(5) Materials subjected to in-situ mining techniques which are not removed from the ground as part of the extraction process.

(6) Pulp and paper liquors (i.e., black liquor) that are reclaimed in a pulping liquor

recovery furnace and then reused in the pulping process, unless it is accumulated speculatively as defined in § 261.1(c) of this chapter.

(7) Spent sulfuric acid used to produce virgin sulfuric acid, unless it is accumulated speculatively as defined in § 261.1(c) of this chapter.

(b) *Solid wastes which are not hazardous wastes.* The following solid wastes are not hazardous wastes:

(1) Household waste, including household waste that has been collected, transported, stored, treated, disposed, recovered (e.g., refuse-derived fuel), or reused. "Household waste" means any waste material (including garbage, trash and sanitary wastes in septic tanks) derived from households (including single and multiple residences, hotels and motels, bunkhouses, ranger stations, crew quarters, campgrounds, picnic grounds, and day-use recreation areas).

(2) Solid wastes generated by any of the following and which are returned to the soils as fertilizers:

(i) The growing and harvesting of agricultural crops.

(ii) The raising of animals, including animal manures.

(3) Mining overburden returned to the mine site.

(4) Fly ash waste, bottom ash waste, slag waste, and flue gas emission control waste generated primarily from the combustion of coal or other fossil fuels.

(5) Drilling fluids, produced waters, and other wastes associated with the exploration, development, or production of crude oil, natural gas or geothermal energy.

(6) Wastes which fail the test for the characteristic of EP toxicity because chromium is present or are listed in Subpart D due to the presence of chromium, which do not fail the test for the characteristic of EP toxicity for any other constituent or are not listed due to the presence of any other constituent, and which do not fail the test for any other characteristic, if it is shown by a waste generator or by waste generators that:

(A) The chromium in the waste is exclusively or nearly exclusively trivalent chromium; and

(B) The waste is generated from an industrial process which uses trivalent chromium exclusively (or nearly exclusively) and the process does not generate hexavalent chromium; and

(C) The waste is typically and frequently managed in non-oxidizing environments.

(ii) Specific wastes which meet the standard in paragraphs (b)(6)(i)(A), (B) and (C) (so long as they do not fail the test for the characteristic of EP toxicity, and do not fail the test for any other characteristic) are:

(A) Chrome (blue) trimmings generated by the following subcategories of the leather tanning and finishing industry: hair pulp/chrome tan/retan/wet finish; hair save/chrome tan/retan/wet finish; retan/wet finish; no beamhouse; through-the-blue; and shearling.

(B) Chrome (blue) shavings generated by the following subcategories of the leather tanning and finishing industry: hair pulp/chrome tan/retan/wet finish; hair save/chrome tan/retan/wet finish; retan/wet finish; no beamhouse; through-the-blue; and shearling.

(C) Buffing dust generated by the following subcategories of the leather tanning and finishing industry: hair pulp/chrome tan/retan/wet finish; hair save/chrome tan/retan/wet finish; retan/wet finish; no beamhouse; through-the-blue.

(D) Sewer screenings generated by the following subcategories of the leather tanning and finishing industry: hair pulp/chrome tan/retan/wet finish; hair save/chrome tan/retan/wet finish; retan/wet finish; no beamhouse; through-the-blue; and shearling.

(E) Wastewater treatment sludges generated by the following subcategories of the leather tanning and finishing industry: hair pulp/chrome tan/retan/wet finish; hair save/chrome tan/retan/wet finish; retan/wet finish; no beamhouse; through-the-blue; and shearling.

(F) Wastewater treatment sludges generated by the following subcategories of the leather tanning and finishing industry: hair pulp/chrome tan/retan/wet finish; hair save/chrome

tan/retan/wet finish; and through-the-blue.

(G) Waste scrap leather from the leather tanning industry, the shoe manufacturing industry, and other leather product manufacturing industries.

(H) Wastewater treatment sludges from the production of TiO₂ pigment using chromium-bearing ores by the chloride process.

(7) Solid waste from the extraction, beneficiation and processing of ores and minerals (including coal), including phosphate rock and overburden from the mining of uranium ore.

(8) Cement kiln dust waste.

(9) Solid waste which consists of discarded wood or wood products which fails the test for the characteristic of EP toxicity and which is not a hazardous waste for any other reason if the waste is generated by persons who utilize the arsenical-treated wood and wood products for these materials' intended end use.

(c) Hazardous wastes which are exempted from certain regulations. A hazardous waste which is generated in a product or raw material storage tank, a product or raw material transport vehicle or vessel, a product or raw material pipeline, or in a manufacturing process unit or an associated non-waste-treatment-manufacturing unit, is not subject to regulation under Parts 262 through 265, 270, 271 and 124 of this chapter or to the notification requirements of Section 3010 of RCRA until it exits the unit in which it was generated, unless the unit is a surface impoundment, or unless the hazardous waste remains in the unit more than 90 days after the unit ceases to be operated for manufacturing, or for storage or transportation of product or raw materials.

(d) Samples. (1) Except as provided in paragraph (d)(2) of this section, a sample of solid waste or a sample of water, soil, or air, which is collected for the sole purpose of testing to determine its characteristics or composition, is not subject to any requirements of this part or Parts 262 through 267 or Part 270 or Part 124 of this chapter or to the notification requirements of Section 3010 of RCRA, when:

(i) The sample is being transported to a laboratory for the purpose of testing; or

(ii) The sample is being transported back to the sample collector after testing; or

(iii) The sample is being stored by the sample collector before transport to a laboratory for testing; or

(iv) The sample is being stored in a laboratory before testing; or

(v) The sample is being stored in a laboratory after testing but before it is returned to the sample collector; or

(vi) The sample is being stored temporarily in the laboratory after testing for a specific purpose (for example, until conclusion of a court case or enforcement action where further testing of the sample may be necessary).

(2) In order to qualify for the exemption in paragraphs (d)(1) (i) and (ii) of this section, a sample collector shipping samples to a laboratory and a laboratory returning samples to a sample collector must:

(i) Comply with U.S. Department of Transportation (DOT), U.S. Postal Service (USPS), or any other applicable shipping requirements; or

(ii) Comply with the following requirements if the sample collector determines that DOT, USPS, or other shipping requirements do not apply to the shipment of the sample:

(A) Assure that the following information accompanies the sample:

(1) The sample collector's name, mailing address, and telephone number;

(2) The laboratory's name, mailing address, and telephone number;

(3) The quantity of the sample;

(4) The date of shipment; and

(5) A description of the sample.

(B) Package the sample so that it does not leak, spill, or vaporize from its packaging.

(3) This exemption does not apply if the laboratory determines that the waste is hazardous but the laboratory is no longer meeting any of the conditions stated in paragraph (d)(1) of this section.

(45 FR 33119, May 19, 1980, as amended at 45 FR 72037, Oct. 30, 1980, 45 FR 76620, Nov. 19, 1980, 45 FR 78531, Nov. 25, 1980, 45 FR 80287, Dec. 4, 1980, 46 FR 27476, May 20, 1981, 46 FR 47429, Sept. 25, 1981, 46 FR

Environmental Protection Agency

§ 261.5

14293, Apr. 1, 1983; 48 FR 30115, June 30, 1983; 49 FR 44980, Nov. 13, 1984; 50 FR 665, Jan. 4, 1985; 50 FR 14219, Apr. 11, 1985.

EFFECTIVE DATE NOTE: At 50 FR 665, Jan. 4, 1985, as corrected at 50 FR 14219, Apr. 11, 1985, § 261.4(a) (6) and (7) were added, effective July 5, 1985.

§ 261.5 Special requirements for hazardous waste generated by small quantity generators.

(a) A generator is a small quantity generator in a calendar month if he generates less than 1000 kilograms of hazardous waste in that month.

(b) Except for those wastes identified in paragraphs (e) and (f) of this section, a small quantity generator's hazardous wastes are not subject to regulation under Parts 262 through 265 and Parts 270 and 124 of this chapter, and the notification requirements of Section 3010 of RCRA, provided the generator complies with the requirements of paragraph (g) of this section.

(c) Hazardous waste that is recycled and that is excluded from regulation under §§ 261.6 (a)(2)(iii) and (v), (a)(3), or 266.36 is not included in the quantity determinations of this section and is not subject to any requirements of this section. Hazardous waste that is subject to the requirements of § 261.6 (b) and (c) and Subparts C, D, and F of Part 266 is included in the quantity determination of this section and is subject to the requirements of this section.

(d) In determining the quantity of hazardous waste he generates, a generator need not include:

(1) His hazardous waste when it is removed from on-site storage; or

(2) Hazardous waste produced by on-site treatment of his hazardous waste.

(e) If a small quantity generator generates acutely hazardous waste in a calendar month in quantities greater than set forth below, all quantities of that acutely hazardous waste are subject to regulation under Parts 262 through 265 and Parts 270 and 124 of this chapter, and the notification requirements of Section 3010 of RCRA:

(1) A total of one kilogram of acute hazardous wastes listed in §§ 261.31, 261.32 or 261.33(e);

(2) A total of 100 kilograms of any flammable or contaminated soil, waste or

other debris resulting from the clean-up of a spill, into or on any land or water, of any acute hazardous wastes listed in §§ 261.31, 261.32, or 261.33(e).

(f) A small quantity generator may accumulate hazardous waste on-site. If he accumulates at any time more than a total of 1000 kilograms of his hazardous waste, or his acutely hazardous wastes in quantities greater than set forth in paragraph (e)(1) or (e)(2) of this section, all of those accumulated wastes for which the accumulation limit was exceeded are subject to regulation under Parts 262 through 265 and Parts 270 and 124 of this chapter, and the notification requirements of Section 3010 of RCRA. The time period of § 262.34 for accumulation of wastes on-site begins for a small quantity generator when the accumulated wastes exceed the applicable exclusion level.

(g) In order for hazardous waste generated by a small quantity generator to be excluded from full regulation under this section, the generator must:

(1) Comply with § 262.11 of this chapter;

(2) If he stores his hazardous waste on-site, store it in compliance with the requirements of paragraph (f) of this section; and

(3) Either treat or dispose of his hazardous waste in an on-site facility, or ensure delivery to an off-site storage, treatment or disposal facility, either of which is:

(i) Permitted under Part 270 of this chapter;

(ii) In interim status under Parts 270 and 265 of this chapter;

(iii) Authorized to manage hazardous waste by a State with a hazardous waste management program approved under Part 271 of this chapter;

(iv) Permitted, licensed or registered by a State to manage municipal or industrial solid waste; or

(v) A facility which:

A. Beneficially uses or re-uses or legitimately recycles or reclaims his waste; or

B. Treats his waste prior to beneficial use or re-use, or legitimate recycling or reclamation.

h. Hazardous waste subject to the reduced requirements of this section may be mixed with non-hazardous

§ 261.6

waste and remain subject to these reduced requirements; even though the resultant mixture exceeds the quantity limitations identified in this section, unless the mixture meets any of the characteristics of hazardous wastes identified in Subpart C.

(1) If a small quantity generator mixes a solid waste with a hazardous waste that exceeds a quantity exclusion level of this section, the mixture is subject to full regulation.

(48 FR 76623, Nov. 19, 1980, as amended at 48 FR 34587, July 2, 1983; 48 FR 14294, Apr. 1, 1983; 50 FR 685, Jan. 4, 1985; 50 FR 1990, Jan. 14, 1985; 50 FR 14219, Apr. 11, 1985)

EFFECTIVE DATE NOTE: At 50 FR 685, Jan. 4, 1985, as corrected at 50 FR 14219, Apr. 11, 1985, § 261.5(c) was revised, effective July 5, 1985. At 50 FR 1990, Jan. 14, 1985, § 261.5(e)(1) and (2) were revised, effective July 15, 1985. For the convenience of the user, the superseded text is set out below:

§ 261.5 Special requirements for hazardous waste generated by small quantity generators.

(c) Hazardous waste that is beneficially used or re-used or legitimately recycled or reclaimed and that is excluded from regulation by § 261.6(a) is not included in the quantity determinations of this section, and is not subject to any requirements of this section. Hazardous waste that is subject to the special requirements of § 261.6(b) is included in the quantity determinations of this section and is subject to the requirements of this section.

(1) A total of one kilogram of commercial chemical products and manufacturing chemical intermediates having the generic names listed in § 261.33(e), and off specification commercial chemical products and manufacturing chemical intermediates which, if they met specifications, would have the generic names listed in § 261.33(e).

(2) A total of 100 kilograms of any residue or contaminated soil, water or other debris resulting from the clean-up of a spill, into or on any land or water, of any commercial chemical products or manufacturing chemical intermediates having the generic names listed in § 261.33(e), or any residue or contaminated soil, water or other debris resulting from the clean-up of a spill, into or on any land or water, of any off specification commercial chemical products or manufacturing chemical intermediates which, if

40 CFR Ch. I (7-1-85 Edition)

they met specifications, would have the generic names listed in § 261.33(e).

§ 261.6 Requirements for recyclable materials.

(a)(1) Hazardous wastes that are recycled are subject to the requirements for generators, transporters, and storage facilities of paragraphs (b) and (c) of this section, except for the materials listed in paragraphs (a)(2) and (a)(3) of this section. Hazardous wastes that are recycled will be known as "recyclable materials."

(2) The following recyclable materials are not subject to the requirements of this section but are regulated under Subparts C through G of Part 266 of this chapter and all applicable provisions in Parts 270 and 124 of this chapter:

(i) Recyclable materials used in a manner constituting disposal (Subpart C);

(ii) Hazardous wastes burned for energy recovery in boilers and industrial furnaces that are not regulated under Subpart O of Part 264 or 265 of this chapter (Subpart D);

(iii) (Reserved for used oil);

(iv) Recyclable materials from which precious metals are reclaimed (Subpart F);

(v) Spent lead-acid batteries that are being reclaimed (Subpart G).

(3) The following recyclable materials are not subject to regulation under Parts 262 through 266 or Parts 270 or 124 of this chapter, and are not subject to the notification requirements of Section 3010 of RCRA:

(i) Industrial ethyl alcohol that is reclaimed;

(ii) Used batteries (or used battery cells) returned to a battery manufacturer for regeneration;

(iii) Used oil that exhibits one or more of the characteristics of hazardous waste; or

(iv) Scrap metal.

(b) Generators and transporters of recyclable materials are subject to the applicable requirements of Parts 262 and 263 of this chapter and the notification requirements under Section

Environmental Protection Agency

§ 261.7

3010 of RCRA, except as provided in paragraph (a) of this section.

(c)(1) Owners or operators of facilities that store recyclable materials are regulated under all applicable provisions of Subparts A through L of Parts 264 and 265 and Parts 270 and 124 of this chapter and the notification requirement under Section 3010 of RCRA, except as provided in paragraph (a) of this section.

(2) Owners or operators of facilities that recycle recyclable materials without storing them before they are recycled are subject to the following requirements, except as provided in paragraph (a) of this section:

(i) Notification requirements under Section 3010 of RCRA;

(ii) Sections 265.71 and 265.72 (dealing with the use of the manifest and manifest discrepancies) of this chapter.

[50 FR 665, Jan. 4, 1985]

EFFECTIVE DATE NOTE: At 50 FR 665, Jan. 4, 1985, § 261.6 was revised, effective July 5, 1985. For the convenience of the user, the superseded text is set out below:

§ 261.6 Special requirements for hazardous waste which is used, re-used, recycled or reclaimed.

(a) Except as otherwise provided in paragraph (b) of this section, a hazardous waste which meets any of the following criteria is not subject to regulation under Parts 262 through 265 or Parts 270, 271, and 124 of this Chapter and is not subject to the notification requirements of Section 3010 of RCRA until such time as the Administrator promulgates regulations to the contrary:

(1) It is being beneficially used or re-used or legitimately recycled or reclaimed.

(2) It is being accumulated, stored or physically, chemically or biologically treated prior to beneficial use or re-use or legitimate recycling or reclamation.

(3) It is one of the following materials being used, reused, recycled or reclaimed in the specified manner:

(i) Spent pickle liquor which is reused in wastewater treatment at a facility holding a National Pollutant Discharge Elimination System (NPDES) permit, or which is being accumulated, stored, or physically, chemically or biologically treated before such reuse.

(b) Except for those wastes listed in paragraph (a)(3) of this section, a hazardous waste that is a sludge, or that is listed in § 261.31 or § 261.32, or that contains one or more hazardous wastes listed in § 261.31 or § 261.32, and that is transported or stored

prior to being used, re-used, recycled, or reclaimed is subject to the following requirements with respect to such transportation or storage:

(1) Notification requirements under Section 3010 RCRA.

(2) Part 262 of this chapter.

(3) Part 263 of this chapter.

(4) Applicable provisions of Subparts A through L of Part 264 of this chapter.

(5) Applicable provisions of Subparts A through L of Part 265 of this chapter.

(6) Parts 270 and 124 of this chapter, with respect to storage facilities.

[45 FR 33119, May 19, 1980, as amended at 46 FR 44973, Sept. 8, 1981; 46 FR 2532, Jan. 20, 1983; 46 FR 14294, Apr. 1, 1983]

§ 261.7 Residues of hazardous waste in empty containers.

(a)(1) Any hazardous waste remaining in either (i) an empty container or (ii) an inner liner removed from an empty container, as defined in paragraph (b) of this section, is not subject to regulation under Parts 261 through 265, or Part 270 or 124 of this chapter or to the notification requirements of Section 3010 of RCRA.

(2) Any hazardous waste in either (i) a container that is not empty or (ii) an inner liner removed from a container that is not empty, as defined in paragraph (b) of this section, is subject to regulation under Parts 261 through 265, and Parts 270 and 124 of this chapter and to the notification requirements of Section 3010 of RCRA.

(b)(1) A container or an inner liner removed from a container that has held any hazardous waste, except a waste that is a compressed gas or that is identified as an acute hazardous waste listed in §§ 261.31, 261.32, or 261.33(e) of this chapter is empty if:

(i) All wastes have been removed that can be removed using the practices commonly employed to remove materials from that type of container, e.g., pouring, pumping, and aspirating, and

(ii) No more than 2.5 centimeters (one inch) of residue remain on the bottom of the container or inner liner, or

(iii)(A) No more than 3 percent by weight of the total capacity of the container remains in the container or inner liner if the container is less than or equal to 110 gallons in size, or

§ 261.10

(B) No more than 0.3 percent by weight of the total capacity of the container remains in the container or inner liner if the container is greater than 110 gallons in size.

(2) A container that has held a hazardous waste that is a compressed gas is empty when the pressure in the container approaches atmospheric.

(3) A container or an inner liner removed from a container that has held an acute hazardous waste listed in §§ 261.31, 261.32, or 261.33(e) is empty if:

(i) The container or inner liner has been triple rinsed using a solvent capable of removing the commercial chemical product or manufacturing chemical intermediate;

(ii) The container or inner liner has been cleaned by another method that has been shown in the scientific literature, or by tests conducted by the generator, to achieve equivalent removal; or

(iii) In the case of a container, the inner liner that prevented contact of the commercial chemical product or manufacturing chemical intermediate with the container, has been removed.

[45 FR 78529, Nov. 23, 1980, as amended at 47 FR 36097, Aug. 18, 1982; 48 FR 14294, Apr. 1, 1983; 50 FR 1999, Jan. 14, 1985]

EFFECTIVE DATE NOTE: At 50 FR 1999, Jan. 14, 1985, § 261.7(b)(1) and (3) introductory texts were revised, effective July 13, 1985. For the convenience of the user, the superseded text is set out below.

§ 261.7 Residue of hazardous waste in empty containers.

(b)(1) A container or an inner liner removed from a container that has held any hazardous waste, except a waste that is a compressed gas or that is identified in § 261.33(c) of this chapter, is empty if:

(3) A container or an inner liner removed from a container that has held a hazardous waste identified in § 261.33(c) of this chapter is empty if:

40 CFR Ch. I (7-1-85 Edition)

Subpart B—Criteria for Identifying the Characteristics of Hazardous Waste and for Listing Hazardous Waste

§ 261.10 Criteria for identifying the characteristics of hazardous waste.

(a) The Administrator shall identify and define a characteristic of hazardous waste in Subpart C only upon determining that:

(1) A solid waste that exhibits the characteristic may:

(i) Cause, or significantly contribute to, an increase in mortality or an increase in serious irreversible, or incapacitating reversible, illness; or

(ii) Pose a substantial present or potential hazard to human health or the environment when it is improperly treated, stored, transported, disposed of or otherwise managed; and

(2) The characteristic can be:

(i) Measured by an available standardized test method which is reasonably within the capability of generators of solid waste or private sector laboratories that are available to serve generators of solid waste; or

(ii) Reasonably detected by generators of solid waste through their knowledge of their waste.

§ 261.11 Criteria for listing hazardous waste.

(a) The Administrator shall list a solid waste as a hazardous waste only upon determining that the solid waste meets one of the following criteria:

(1) It exhibits any of the characteristics of hazardous waste identified in Subpart C.

(2) It has been found to be fatal to humans in low doses or, in the absence of data on human toxicity, it has been shown in studies to have an oral LD 50 toxicity (rat) of less than 50 milligrams per kilogram, an inhalation LC 50 toxicity (rat) of less than 2 milligrams per liter, or a dermal LD 50 toxicity (rabbit) of less than 200 milligrams per kilogram or is otherwise capable of causing or significantly contributing to an increase in serious irreversible, or incapacitating reversible, illness. (Waste listed in accordance with these criteria will be designated Acute Hazardous Waste.)

(3) It contains any of the toxic constituents listed in Appendix VIII unless, after considering any of the following factors, the Administrator concludes that the waste is not capable of posing a substantial present or potential hazard to human health or the environment when improperly treated, stored, transported or disposed of, or otherwise managed:

(i) The nature of the toxicity presented by the constituent.

(ii) The concentration of the constituent in the waste.

(iii) The potential of the constituent or any toxic degradation product of the constituent to migrate from the waste into the environment under the types of improper management considered in paragraph (a)(3)(vii) of this section.

(iv) The persistence of the constituent or any toxic degradation product of the constituent.

(v) The potential for the constituent or any toxic degradation product of the constituent to degrade into non-harmful constituents and the rate of degradation.

(vi) The degree to which the constituent or any degradation product of the constituent bioaccumulates in ecosystems.

(vii) The plausible types of improper management to which the waste could be subjected.

(viii) The quantities of the waste generated at individual generation sites or on a regional or national basis.

(ix) The nature and severity of the human health and environmental damage that has occurred as a result of the improper management of wastes containing the constituent.

x) Action taken by other governmental agencies or regulatory programs based on the health or environmental hazard posed by the waste or waste constituent.

xi) Such other factors as may be appropriate.

Substances will be listed on Appendix VIII only if they have been shown in scientific studies to have toxic, carcinogenic, mutagenic or teratogenic effects on humans or other life forms.

Wastes listed in accordance with these criteria will be designated Toxic Wastes.

(b) The Administrator may list classes or types of solid waste as hazardous waste if he has reason to believe that individual wastes, within the class or type of waste, typically or frequently are hazardous under the definition of hazardous waste found in Section 1004(5) of the Act.

(c) The Administrator will use the criteria for listing specified in this section to establish the exclusion limits referred to in § 261.5(c).

Subpart C—Characteristics of Hazardous Waste

§ 261.20 General.

(a) A solid waste, as defined in § 261.2, which is not excluded from regulation as a hazardous waste under § 261.4(b), is a hazardous waste if it exhibits any of the characteristics identified in this subpart.

[Comment: § 262.11 of this chapter sets forth the generator's responsibility to determine whether his waste exhibits one or more of the characteristics identified in this subpart.]

(b) A hazardous waste which is identified by a characteristic in this subpart, but is not listed as a hazardous waste in Subpart D, is assigned the EPA Hazardous Waste Number set forth in the respective characteristic in this subpart. This number must be used in complying with the notification requirements of Section 3010 of the Act and certain recordkeeping and reporting requirements under Parts 262 through 265 and Part 270 of this chapter.

(c) For purposes of this subpart, the Administrator will consider a sample obtained using any of the applicable sampling methods specified in Appendix I to be a representative sample within the meaning of Part 260 of this chapter.

[Comment: Since the Appendix I sampling methods are not being formally adopted by the Administrator, a person who desires to employ an alternative sampling method is not required to demonstrate the equivalency of his method under the procedures set forth in §§ 260.20 and 260.21.]

[45 FR 33119, May 19, 1980, as amended at 48 FR 14294, Apr. 1, 1983.]

§ 261.21

§ 261.21 Characteristic of ignitability.

(a) A solid waste exhibits the characteristic of ignitability if a representative sample of the waste has any of the following properties:

(1) It is a liquid, other than an aqueous solution containing less than 24 percent alcohol by volume and has flash point less than 60°C (140°F), as determined by a Pensky-Martens Closed Cup Tester, using the test method specified in ASTM Standard D-93-79 or D-93-80 (incorporated by reference, see § 260.11), or a Setaflash Closed Cup Tester, using the test method specified in ASTM Standard D-3278-78 (incorporated by reference, see § 260.11), or as determined by an equivalent test method approved by the Administrator under procedures set forth in §§ 260.20 and 260.21.

(2) It is not a liquid and is capable, under standard temperature and pressure, of causing fire through friction, absorption of moisture or spontaneous chemical changes and, when ignited, burns so vigorously and persistently that it creates a hazard.

(3) It is an ignitable compressed gas as defined in 49 CFR 173.300 and as determined by the test methods described in that regulation or equivalent test methods approved by the Administrator under §§ 260.20 and 260.21.

(4) It is an oxidizer as defined in 49 CFR 173.151.

(b) A solid waste that exhibits the characteristic of ignitability, but is not listed as a hazardous waste in Subpart D, has the EPA Hazardous Waste Number of D001.

[45 FR 33119, May 19, 1980, as amended at 46 FR 35247, July 7, 1981]

§ 261.22 Characteristic of corrosivity.

(a) A solid waste exhibits the characteristic of corrosivity if a representative sample of the waste has either of the following properties:

(1) It is aqueous and has a pH less than or equal to 2 or greater than or equal to 12.5, as determined by a pH meter using either an EPA test method or an equivalent test method approved by the Administrator under the procedures set forth in §§ 260.20 and 260.21. The EPA test method for pH is specified as Method 5.2 in "Test

40 CFR Ch. I (7-1-85 Edition)

Methods for the Evaluation of Solid Waste, Physical/Chemical Methods" (incorporated by reference, see § 260.11).

(2) It is a liquid and corrodes steel (SAE 1020) at a rate greater than 6.35 mm (0.250 inch) per year at a test temperature of 55°C (130°F) as determined by the test method specified in NACE (National Association of Corrosion Engineers) Standard TM-01-89 as standardized in "Test Methods for the Evaluation of Solid Waste, Physical/Chemical Methods" (incorporated by reference, see § 260.11) or an equivalent test method approved by the Administrator under the procedures set forth in §§ 260.20 and 260.21.

(b) A solid waste that exhibits the characteristic of corrosivity, but is not listed as a hazardous waste in Subpart D, has the EPA Hazardous Waste Number of D002.

[45 FR 33119, May 19, 1980, as amended at 46 FR 35247, July 7, 1981]

§ 261.23 Characteristic of reactivity.

(a) A solid waste exhibits the characteristic of reactivity if a representative sample of the waste has any of the following properties:

(1) It is normally unstable and readily undergoes violent change without detonating.

(2) It reacts violently with water.

(3) It forms potentially explosive mixtures with water.

(4) When mixed with water, it generates toxic gases, vapors or fumes in a quantity sufficient to present a danger to human health or the environment.

(5) It is a cyanide or sulfide bearing waste which, when exposed to pH conditions between 2 and 12.5, can generate toxic gases, vapors or fumes in a quantity sufficient to present a danger to human health or the environment.

(6) It is capable of detonation or explosive reaction if it is subjected to a strong initiating source or if heated under confinement.

(7) It is readily capable of detonation or explosive decomposition or reaction at standard temperature and pressure.

(8) It is a forbidden explosive as defined in 49 CFR 173.51, or a Class A explosive as defined in 49 CFR 173.53

\$ 261.30

TABLE 1—MAXIMUM CONCENTRATION OF CONTAMINANTS FOR CHARACTERISTIC OF EP TOXICITY—Continued

EPA hazardous waste number	Contaminant	Maximum concentration (milligrams per liter)
D016	2,4-D (2,4-Dichlorophenoxyacetic acid)	100
D017	2,4,5-TP Solves (2,4,5-Trichlorophenoxypropionic acid)	100

Subpart D—Lists of Hazardous Wastes

§ 261.30 General.

(a) A solid waste is a hazardous waste if it is listed in this subpart, unless it has been excluded from this list under §§ 260.20 and 260.22.

(b) The Administrator will indicate his basis for listing the classes or types of wastes listed in this Subpart by employing one or more of the following Hazard Codes:

Waste Type	Quantity (kg)	Weight (kg)	Volume (m³)	Value (€)	Notes
Ignitable Waste	100	100	100	100	
Corrosive Waste	100	100	100	100	
Reactive Waste	100	100	100	100	
EP Toxic Waste	100	100	100	100	
Acute Hazardous Waste	100	100	100	100	
Toxic Waste	100	100	100	100	

[illegible]

Appendix VII identifies the constituent which caused the Administrator to list the waste as an EP Toxic Waste (E) or Toxic Waste (T) in §§ 261.31 and 261.32.

(c) Each hazardous waste listed in this subpart is assigned an EPA Hazardous Waste Number which precedes the name of the waste. This number must be used in complying with the notification requirements of Section 3010 of the Act and certain record-keeping and reporting requirements under Parts 262 through 265 and Part 270 of this chapter.

(d) The following hazardous wastes listed in § 261.31 or § 261.32 are subject to the exclusion limits for acutely hazardous wastes established in § 261.5: EPA Hazardous Wastes Nos. F020, F021, F022, F023, F025, and F027.

§ 261.31

40 CFR Ch. I (7-1-85 Edition)

45 FR 33119, May 19, 1980, as amended at 48 FR 14294, Apr. 1, 1983; 50 FR 2000, Jan. 14, 1985]

§ 261.30 (General).

EFFECTIVE DATE NOTE: At 50 FR 2000, Jan. 14, 1985, § 261.30(d) was revised, effective July 15, 1985. For the convenience of the user, the superseded text is set out below:

(d) The following hazardous wastes listed in § 261.31 or § 261.32 are subject to the exclusion limits for acutely hazardous wastes established in § 261.5. (Reserved)

§ 261.31 Hazardous wastes from non-specific sources.

The following solid wastes are listed hazardous wastes from non-specific sources unless they are excluded under §§ 260.20 and 260.22 and listed in Appendix IX.

Industry and EPA hazardous waste No.	Hazardous waste	Hazardous waste code
Generic		
F001	The following spent halogenated solvents used in degreasing: tetrachloroethylene, trichloroethylene, methylene chloride, 1,1,1-trichloroethane, carbon tetrachloride, and chlorinated fluorocarbons, and sludges from the recovery of these solvents in degreasing operations.	(T)
F002	The following spent halogenated solvents: tetrachloroethylene, methylene chloride, trichloroethylene, 1,1,1-trichloroethane, chlorobenzene, 1,1,2-trichloro-1,2,2-hexafluoroethane, ortho-dichlorobenzene, and trichlorofluoromethane, and the still bottoms from the recovery of these solvents.	(T)
F003	The following spent non-halogenated solvents: xylene, acetone, ethyl acetate, ethyl benzene, ethyl ether, methyl isobutyl ketone, n-butyl alcohol, cyclohexanone, and methanol, and the still bottoms from the recovery of these solvents.	(U)
F004	The following spent non-halogenated solvents: cresols and cresylic acid, and nitrobenzene, and the still bottoms from the recovery of these solvents.	(T)
F005	The following spent non-halogenated solvents: toluene, methyl ethyl ketone, carbon disulfide, xylolene, and pyridine, and the still bottoms from the recovery of these solvents.	(U)
F006	Wastewater treatment sludges from electroplating operations except from the following processes: (1) sulfuric acid anodizing of aluminum; (2) tin plating on carbon steel; (3) zinc plating (segregated base) on carbon steel; (4) aluminum or zinc-aluminum plating on carbon steel; (5) cleaning/stripping associated with tin, zinc and aluminum plating on carbon steel; and (6) chemical etching and mixing of aluminum.	(T)
F019	Wastewater treatment sludges from the chemical conversion coating of aluminum.	(T)
F007	Spent cyanide plating bath solutions from electroplating operations.	(R) (T)
F008	Plating bath residues from the bottom of plating baths from electroplating operations where cyanides are used in the process.	(R) (T)
F009	Spent stripping and cleaning bath solutions from electroplating operations where cyanides are used in the process.	(R) (T)
F010	Quenching bath residues from oil baths from metal heat treating operations where cyanides are used in the process.	(R) (T)
F011	Spent cyanide solutions from salt bath pot cleaning from metal heat treating operations.	(R) (T)
F012	Quenching waste water treatment sludges from metal heat treating operations where cyanides are used in the process.	(T)
F024	Wastes, including but not limited to: distillation residues, heavy ends, tars, and reactor clean-out wastes from the production of chlorinated aliphatic hydrocarbons, having carbon content from one to five, utilizing free radical catalyzed processes. (This listing does not include light ends, spent filters and filter aids, spent desiccants, wastewater, wastewater treatment sludges, spent catalysts, and wastes listed in § 261.32.)	(T)
F020	Wastes (except wastewater and spent carbon from hydrogen chloride purification) from the production or manufacturing use as a reactant, chemical intermediate, or component in a formulating process of tri- or tetrachlorophenol or of intermediates used to produce their pesticide derivatives. (This listing does not include wastes from the production of hexachlorophene from highly purified 2,4,5-trichlorophenol.)	(H)
F021	Wastes (except wastewater and spent carbon from hydrogen chloride purification) from the production or manufacturing use as a reactant, chemical intermediate, or component in a formulating process of pentachlorophenol or of intermediates used to produce its derivatives.	(H)

Environmental Protection Agency

§ 261.32

Industry and EPA hazardous waste No.	Hazardous waste	Hazard code
F022	Wastes (except wastewater and spent carbon from hydrogen chloride purification) from the manufacturing use (as a reactant, chemical intermediate, or component in a formulating process) of tetra-, penta-, or hexachlorobenzenes under alkaline conditions.	(H)
F023	Wastes (except wastewater and spent carbon from hydrogen chloride purification) from the production of materials on equipment previously used for the production or manufacturing use (as a reactant, chemical intermediate, or component in a formulating process) of tri- and tetrachlorophenols. (This listing does not include wastes from equipment used only for the production or use of hexachlorophene from highly purified 2,4,5-trichlorophenol.)	(H)
F026	Wastes (except wastewater and spent carbon from hydrogen chloride purification) from the production of materials on equipment previously used for the manufacturing use (as a reactant, chemical intermediate, or component in a formulating process) of tetra-, penta-, or hexachlorobenzene under alkaline conditions.	(H)
F027	Discarded unused formulations containing tri-, tetra-, or pentachlorophenol or discarded unused formulations containing compounds derived from these chlorophenols. (This listing does not include formulations containing hexachlorophene synthesized from prepurified 2,4,5-trichlorophenol as the sole component.)	(H)
F028	Residues resulting from the incineration or thermal treatment of soil contaminated with EPA Hazardous Waste Nos. F020, F021, F022, F023, F026, and F027.	(T)

46 FR 4617, Jan. 16, 1981, as amended at 46 FR 27477, May 20, 1981; 49 FR 5312, Feb. 10, 1984; 49 FR 37070, Sept. 21, 1984; 50 FR 665, Jan. 4, 1985; 50 FR 2000, Jan. 14, 1985.

EFFECTIVE DATE NOTE: At 50 FR 665, Jan. 4, 1985, the hazardous waste listings for F007, F008, F009, F010, F011, and F012 were revised, effective July 5, 1985. At 50 FR 2000, Jan. 14, 1985, the hazardous waste listings for F020, F021, F022, F023, F026, F027, and F028 were added, effective July 15, 1985. For the convenience of the user, the superseded text is set out below:

§ 261.31 Hazardous wastes from non-specific sources.

Industry and EPA hazardous waste No.	Hazardous waste	Hazard code
F007	Spent cyanide plating bath solutions from electroplating operations (except for precious metals electroplating spent cyanide plating bath solutions).	(R, T)
F008	Plating bath sludges from the bottom of plating baths from electroplating operations where cyanides are used in the process (except for precious metals electroplating plating bath sludges).	(R, T)
F009	Spent stripping and cleaning bath solutions from electroplating operations where cyanides are used in the process (except for precious metals electroplating spent stripping and cleaning bath solutions).	(R, T)
F010	Quenching bath sludge from oil baths from metal heat treating operations where cyanides are used in the process (except for precious metals heat-treating quenching bath sludges).	(R, T)
F011	Spent cyanide solutions from salt bath pot cleaning from metal heat treating operations (except for precious metals heat treating spent cyanide solutions from salt bath pot cleaning).	(R, T)
F012	Quenching wastewater treatment sludges from metal heat treating operations where cyanides are used in the process (except for precious metals heat treating quenching wastewater treatment sludges).	(T)

§ 261.32 Hazardous wastes from specific sources.

The following solid wastes are listed hazardous wastes from specific sources unless they are excluded under §§ 260.20 and 260.22 and listed in Appendix IX.

Industry and EPA hazardous waste No.	Hazardous waste	Hazard code
Wood preservation - 001	Bottom sediment sludge from the treatment of wastewaters from wood preserving processes that use creosote and/or pentachlorophenol.	(T)

Industry and EPA hazardous waste No.	Hazardous waste	Hazard code
Inorganic pigments:		
K002	Wastewater treatment sludge from the production of chrome yellow and orange pigments.	(F)
K003	Wastewater treatment sludge from the production of molybdate orange pigments.	(F)
K004	Wastewater treatment sludge from the production of zinc yellow pigments.	(F)
K005	Wastewater treatment sludge from the production of chrome green pigments.	(F)
K006	Wastewater treatment sludge from the production of chrome oxide green pigments (anhydrous and hydrated).	(F)
K007	Wastewater treatment sludge from the production of iron blue pigments.	(F)
K008	Oven residue from the production of chrome oxide green pigments.	(F)
Organic chemicals:		
K009	Distillation bottoms from the production of acetaldehyde from ethylene.	(F)
K010	Distillation side cuts from the production of acetaldehyde from ethylene.	(F)
K011	Bottom stream from the wastewater stripper in the production of acrylonitrile.	(R, F)
K012	Bottom stream from the acetonitrile column in the production of acrylonitrile.	(F)
K013	Bottom stream from the acetonitrile purification column in the production of acrylonitrile.	(F)
K014	Bottoms from the acetonitrile purification column in the production of acrylonitrile.	(F)
K015	Still bottoms from the distillation of benzyl chloride.	(F)
K016	Heavy ends or distillation residues from the production of carbon tetrachloride.	(F)
K017	Heavy ends (still bottoms) from the purification column in the production of epichlorohydrin.	(F)
K018	Heavy ends from the fractionation column in ethyl chloride production.	(F)
K019	Heavy ends from the distillation of ethylene dichloride in ethylene dichloride production.	(F)
K020	Heavy ends from the distillation of vinyl chloride in vinyl chloride monomer production.	(F)
K021	Aqueous spent antimony catalyst waste from fluoromethanes production.	(F)
K022	Distillation bottom tars from the production of phenol/acetone from cumene.	(F)
K023	Distillation light ends from the production of phthalic anhydride from naphthalene.	(F)
K024	Distillation bottoms from the production of phthalic anhydride from naphthalene.	(F)
K025	Distillation light ends from the production of phthalic anhydride from ortho-xylene.	(F)
K026	Distillation bottoms from the production of phthalic anhydride from ortho-xylene.	(F)
K027	Distillation bottoms from the production of nitrobenzene by the nitration of benzene.	(F)
K028	Stripping still tars from the production of methyl ethyl pyridines.	(F)
K029	Centrifuge and distillation residues from toluene disocyanate production.	(R, F)
K030	Spent catalyst from the hydrochlorination reactor in the production of 1,1,1-trichloroethane.	(F)
K031	Waste from the product stream stripper in the production of 1,1,1-trichloroethane.	(F)
K032	Distillation bottoms from the production of 1,1,1-trichloroethane.	(F)
K033	Heavy ends from the heavy ends column from the production of 1,1,1-trichloroethane.	(F)
K034	Column bottoms or heavy ends from the combined production of trichloroethylene and perchloroethylene.	(F)
K035	Distillation bottoms from aniline production.	(F)
K036	Process residues from aniline extraction from the production of aniline.	(F)
K037	Combined wastewater streams generated from nitrobenzene/aniline production.	(F)
K038	Distillation or fractionation column bottoms from the production of chlorobenzenes.	(F)
K039	Separated aqueous stream from the reactor product washing step in the production of chlorobenzenes.	(F)
Inorganic chemicals:		
K040	Brine purification residue from the mercury cell process in chlorine production, where separately prepurified brine is not used.	(F)
K041	Chlorinated hydrocarbon waste from the purification step of the diaphragm cell process using graphite anodes in chlorine production.	(F)
K042	Wastewater treatment sludge from the mercury cell process in chlorine production.	(F)
Pesticides:		
K043	By-product salts generated in the production of MSMA and cacodylic acid.	(F)
K044	Wastewater treatment sludge from the production of chlordane.	(F)
K045	Wastewater and scrub water from the chlorination of cyclopentadiene in the production of chlordane.	(F)
K046	Filter solids from the filtration of hexachlorocyclopentadiene in the production of chlordane.	(F)
K047	Vacuum stripper discharge from the chlordane chlorinator in the production of chlordane.	(F)
K048	Wastewater treatment sludges generated in the production of chlordane.	(F)
K049	Still bottoms from toluene reclamation distillation in the production of disulfoton.	(F)
K050	Wastewater treatment sludges from the production of disulfoton.	(F)
K051	Wastewater from the washing and stripping of phosphate production.	(F)
K052	Filter cake from the filtration of diethylphosphorodithioic acid in the production of phosphate.	(F)
K053	Wastewater treatment sludge from the production of phosphate.	(F)
K054	Wastewater treatment sludge from the production of toxaphene.	(F)
K055	Untreated process wastewater from the production of toxaphene.	(F)

Environmental Protection Agency

§ 261.33

and EPA hazardous waste No.	Hazardous waste	Hazard code
K042	Heavy ends or distillation residues from the distillation of tetrachlorobenzene in the production of 2,4,5-T	(M)
K043	2,6-Dichlorophenol waste from the production of 2,4-D	(M)
K044	Untreated wastewater from the production of 2,4-D	(M)
K045	Wastewater treatment sludges from the manufacturing and processing of explosives	(R)
K046	Spent carbon from the treatment of wastewater containing explosives	(R)
K047	Wastewater treatment sludges from the manufacturing, formulation and loading of lead-based inhibiting compounds	(M)
K048	Pink/red water from TNT operations	(R)
K049	Discarded air flotation (DAF) float from the petroleum refining industry	(M)
K050	Slop oil emulsion solids from the petroleum refining industry	(M)
K051	Heat exchanger bundle cleaning sludge from the petroleum refining industry	(M)
K052	API separator sludge from the petroleum refining industry	(M)
K053	Tank bottoms (leaded) from the petroleum refining industry	(M)
K054	Emission control dust/sludge from the primary production of steel in electric furnaces	(M)
K055	Spent pickle liquor from steel finishing operations	(C, T)
K056	Emission control dust/sludge from secondary lead smelting	(M)
K057	Waste leaching solution from acid leaching of emission control dust/sludge from secondary lead smelting	(M)
K058	Wastewater treatment sludges generated during the production of veterinary pharmaceuticals from arsenic or organo-arsenic compounds	(M)
K059	Distillation tar residues from the distillation of aniline-based compounds in the production of veterinary pharmaceuticals from arsenic or organo-arsenic compounds	(M)
K060	Residue from the use of activated carbon for decolorization in the production of veterinary pharmaceuticals from arsenic or organo-arsenic compounds	(M)
K061	Solvent washes and sludges, caustic washes and sludges, or water washes and sludges from cleaning tanks and equipment used in the formulation of ink from pigments, dyes, soaps, and stabilizers containing chromium and lead	(M)
K062	Ammonia still lime sludge from coating operations	(M)
K063	Decanter tank tar sludge from coating operations	(M)

(46 FR 4618, Jan. 16, 1981, as amended at 46 FR 27476-27477, May 20, 1981; 49 FR 37070, Sept. 21, 1984)

§ 261.33 Discarded commercial chemical products, off-specification species container residues, and spill residues thereof.

The following materials or items are hazardous wastes when they are discarded or intended to be discarded as described in § 261.2(a)(2)(i), when they are burned for purposes of energy recovery in lieu of their original intended use, when they are used to produce fuels in lieu of their original intended use, when they are applied to the land in lieu of their original intended use, or when they are contained in products that are applied to the land in lieu of their original intended use.

(a) Any commercial chemical product or manufacturing chemical intermediate having the generic name

listed in paragraph (e) or (f) of this section.

(b) Any off-specification commercial chemical product or manufacturing chemical intermediate which, if it met specifications, would have the generic name listed in paragraph (e) or (f) of this section.

(c) Any container or inner liner removed from a container that has been used to hold any commercial chemical product or manufacturing chemical intermediate having the generic names listed in paragraph (e) of this section, or any container or inner liner removed from a container that has been used to hold any off-specification chemical product and manufacturing chemical intermediate which, if it met specifications, would have the generic name listed in paragraph (e) of this

section, unless the container is empty as defined in § 261.7(b)(3) of this chapter.

[Comment: Unless the residue is being beneficially used or reused, or legitimately recycled or reclaimed, or being accumulated, stored, transported or treated prior to such use, re-use, recycling or reclamation, EPA considers the residue to be intended for discard, and thus a hazardous waste. An example of a legitimate re-use of the residue would be where the residue remains in the container and the container is used to hold the same commercial chemical product or manufacturing chemical product or manufacturing chemical intermediate it previously held. An example of the discard of the residue would be where the drum is sent to a drum reconditioner who reconditions the drum but discards the residue.]

(d) Any residue or contaminated soil, water or other debris resulting from the cleanup of a spill into or on any land or water of any commercial chemical product or manufacturing chemical intermediate having the generic name listed in paragraph (e) or (f) of this section, or any residue or contaminated soil, water or other debris resulting from the cleanup of a spill, into or on any land or water, of any off-specification chemical product and manufacturing chemical intermediate which, if it met specifications, would have the generic name listed in paragraph (e) or (f) of this section.

[Comment: The phrase "commercial chemical product or manufacturing chemical intermediate having the generic name listed in" refers to a chemical substance which is manufactured or formulated for commercial or manufacturing use which consists of the commercially pure grade of the chemical, any technical grades of the chemical that are produced or marketed, and all formulations in which the chemical is the sole active ingredient. It does not refer to a material, such as a manufacturing process waste, that contains any of the substances listed in paragraphs (e) or (f). Where a manufacturing process waste is deemed to be a hazardous waste because it contains a substance listed in paragraphs (e) or (f), such waste will be listed in either § 261.31 or 261.32 or will be identified as a hazardous waste by the characteristics set forth in Subpart C of this part.]

(e) The commercial chemical products, manufacturing chemical intermediates or off-specification commercial chemical products or manufacturing

chemical intermediates referred to in paragraphs (a) through (d) of this section, are identified as acute hazardous wastes (H) and are subject to the small quantity exclusion defined in § 261.5(e).

[Comment: For the convenience of the regulated community the primary hazardous properties of these materials have been indicated by the letters T (Toxicity), and R (Reactivity). Absence of a letter indicates that the compound only is listed for acute toxicity.]

These wastes and their corresponding EPA Hazardous Waste Numbers are:

Hazardous waste no.	Substance
P023	Acetaminophen (para-)
P022	Acetaminophen, N-(4-hydroxyphenyl)-
P027	Acetaminophen, 2-ethyl-
P028	Acetic acid, 99% sodium salt
P029	Acetic acid, 99%
P031	Acetone, 99% methyl ester
P032	3-(4-hydroxyphenyl)-1,2,4-triazole-5-carboxamide and salts when present at concentrations greater than 0.1%
P033	1-Acetyl-2-pyrone
P034	Acrylonitrile
P035	Adipic acid
P036	Adipic acid, 99%
P037	5-Aminonaphthalene-1-sulfonate
P038	4-Aminonaphthalene
P039	Ammonium acetate (99%)
P040	Ammonium carbonate
P041	Ammonium nitrate
P042	Ammonium sulfate
P043	Ammonium chloride
P044	Ammonium bromide
P045	Ammonium iodide
P046	Ammonium phosphate
P047	Ammonium persulfate
P048	Ammonium sulfide
P049	Ammonium thiosulfate
P050	Ammonium vanadate
P051	Ammonium molybdate
P052	Ammonium dichromate
P053	Ammonium tetrachloroarsenate
P054	Ammonium hexachloroantimonate
P055	Ammonium hexachloroantimonate
P056	Ammonium hexachloroantimonate
P057	Ammonium hexachloroantimonate
P058	Ammonium hexachloroantimonate
P059	Ammonium hexachloroantimonate
P060	Ammonium hexachloroantimonate
P061	Ammonium hexachloroantimonate
P062	Ammonium hexachloroantimonate
P063	Ammonium hexachloroantimonate
P064	Ammonium hexachloroantimonate
P065	Ammonium hexachloroantimonate
P066	Ammonium hexachloroantimonate
P067	Ammonium hexachloroantimonate
P068	Ammonium hexachloroantimonate
P069	Ammonium hexachloroantimonate
P070	Ammonium hexachloroantimonate
P071	Ammonium hexachloroantimonate
P072	Ammonium hexachloroantimonate
P073	Ammonium hexachloroantimonate
P074	Ammonium hexachloroantimonate
P075	Ammonium hexachloroantimonate
P076	Ammonium hexachloroantimonate
P077	Ammonium hexachloroantimonate
P078	Ammonium hexachloroantimonate
P079	Ammonium hexachloroantimonate
P080	Ammonium hexachloroantimonate
P081	Ammonium hexachloroantimonate
P082	Ammonium hexachloroantimonate
P083	Ammonium hexachloroantimonate
P084	Ammonium hexachloroantimonate
P085	Ammonium hexachloroantimonate
P086	Ammonium hexachloroantimonate
P087	Ammonium hexachloroantimonate
P088	Ammonium hexachloroantimonate
P089	Ammonium hexachloroantimonate
P090	Ammonium hexachloroantimonate
P091	Ammonium hexachloroantimonate
P092	Ammonium hexachloroantimonate
P093	Ammonium hexachloroantimonate
P094	Ammonium hexachloroantimonate
P095	Ammonium hexachloroantimonate
P096	Ammonium hexachloroantimonate
P097	Ammonium hexachloroantimonate
P098	Ammonium hexachloroantimonate
P099	Ammonium hexachloroantimonate
P100	Ammonium hexachloroantimonate

§ 261.33

371

§ 261.33

Hazardous waste No.	Substance
P106	Sodium cyanide
P107	Selenium sulfide
P108	Strychnin-10-one, and salts
P018	Strychnin-10-one, 2,3-dimethoxy-
P108	Strychnine and salts
P115	Sulfuric acid, (methyl) salt
P109	Tetraethylpyrophosphate
P110	Tetraethyl lead
P111	Tetraethylpyrophosphate
P112	Tetraethyllead (R)
P062	Tetraethyllead, acid, hexaethyl ester
P113	Thalic acid
P113	Thallium(I) oxide
P114	Thallium(I) selenide
P115	Thallium(I) sulfate
P045	Thiofuran
P049	Thiomethylcarbonic diester
P014	Thioether
P116	Thioethercarboxide
P026	Thiourea, (2-chlorophenyl)-
P072	Thiourea, 1-naphthyl-
P093	Thiourea phenyl-
P123	Toluene
P118	Trichloromethane
P119	Vanadic acid, ammonium salt
P120	Vanadium pentoxide
P120	Vanadium(V) oxide
P001	Warfarin, when present at concentrations greater than 0.3%
P121	Zinc cyanide
P122	Zinc phosphide (R T)
P122	Zinc phosphide, when present at concentrations greater than 10%

(f) The commercial chemical products, manufacturing chemical intermediates, or off-specification commercial chemical products referred to in paragraphs (a) through (d) of this section, are identified as toxic wastes (T) unless otherwise designated and are subject to the small quantity exclusion defined in § 261.5 (a) and (f).

(Comment: For the convenience of the regulated community, the primary hazardous properties of these materials have been indicated by the letters T (Toxicity), R (Reactivity), I (Ignitability), and C (Corrosivity). Absence of a letter indicates that the compound is only listed for toxicity.)

These wastes and their corresponding EPA Hazardous Waste Numbers are:

Hazardous waste No.	Substance
U001	Acetaminophen
U034	Acetaminophen, hexachloro-
U037	Acetaminophen, 4,4-dimethyl-5-(2-chlorophenyl)-
U035	Acetaminophen, 4,4-dimethyl-5-(2-chlorophenyl)-
U032	Acetaminophen, 4,4-dimethyl-5-(2-chlorophenyl)-
U044	Acetaminophen, 4,4-dimethyl-5-(2-chlorophenyl)-
U044	Acetaminophen, 4,4-dimethyl-5-(2-chlorophenyl)-

40 CFR Ch. I (7-1-85 Edition)

Hazardous waste No.	Substance
U032	Acetone (I)
U003	Acetone (I, T)
U048	3-(alpha-Acetylbenzyl)-4-hydroxycoumarin and salts, when present at concentrations of 0.3% or less
U004	Acetophenone
U005	2-Acetylaminofluorene
U006	Acetyl chloride (C, R, T)
U007	Acrylamide
U008	Acrylic acid (I)
U009	Acrylonitrile
U150	Algaecide, 3-(2-bis(2-chlorophenylamino)phenyl)-L-
U011	Amalgam
U012	Aniline (I, T)
U014	Auramine
U015	Azaserine
U010	Apocynin 2,3,4-trihydroxy-1,2-dihydro-4'-oxo-6-oxo-8-((1-aminocarbonyl)-2-methyl-1,1,2,2-tetrahydro-6a-methoxy-5-methyl-)
U157	Benz(1)acanthrene, 1,2-dihydro-3-methyl-
U016	Benz(c)anthracene
U016	3,4-Benzanthracene
U017	Benzaldehyde
U018	Benz(a)anthracene
U018	1,2-Benzanthracene
U064	1,2-Benzanthracene, 7,12-dimethyl-
U012	Benzene (I, T)
U014	Benzene, 4,4'-carbonyldi(bis(4-methyl-))
U046	Benzene, 4-chloro-2-methyl-
U093	Benzene, 4,4'-dimethyl-4-phenylazo-
U158	Benzene, 4,4'-dimethyl-4-phenylazo-
U222	Benzene, 2-methyl-5-nitro-
U181	Benzene, 2-methyl-5-nitro-
U019	Benzene (I, T)
U028	Benzene, 4-chloro-2-methyl-
U030	Benzene, 1-bromo-4-phenyl-
U037	Benzene, 1-bromo-4-phenyl-
U180	1,2-Benzene dicarboxylic acid, amide
U028	1,2-Benzene dicarboxylic acid, (bis(4-methyl-))
U099	1,2-Benzene dicarboxylic acid, (bis(4-methyl-))
U066	1,2-Benzene dicarboxylic acid, (bis(4-methyl-))
U122	1,2-Benzene dicarboxylic acid, (bis(4-methyl-))
U137	1,2-Benzene dicarboxylic acid, (bis(4-methyl-))
U070	Benzene, 1,2-dichloro-
U071	Benzene, 1,3-dichloro-
U072	Benzene, 1,4-dichloro-
U073	Benzene, 1,4-dichloro-
U223	Benzene, 1,3-bis(4-chlorophenyl)-
U229	Benzene, 1,3-bis(4-chlorophenyl)-
U201	Benzene, 1,3-bis(4-chlorophenyl)-
U227	Benzene, 1,3-bis(4-chlorophenyl)-
U054	Benzene, 1,3-bis(4-chlorophenyl)-
U056	Benzene, 1,3-bis(4-chlorophenyl)-
U220	Benzene, 1,3-bis(4-chlorophenyl)-
U055	Benzene, 1,3-bis(4-chlorophenyl)-
U056	Benzene, 1,3-bis(4-chlorophenyl)-
U053	Benzene, 1,3-bis(4-chlorophenyl)-
U141	Benzene, 1,3-bis(4-chlorophenyl)-
U140	Benzene, 1,3-bis(4-chlorophenyl)-
U144	Benzene, 1,3-bis(4-chlorophenyl)-
U145	Benzene, 1,3-bis(4-chlorophenyl)-
U146	Benzene, 1,3-bis(4-chlorophenyl)-
U147	Benzene, 1,3-bis(4-chlorophenyl)-
U148	Benzene, 1,3-bis(4-chlorophenyl)-
U149	Benzene, 1,3-bis(4-chlorophenyl)-
U150	Benzene, 1,3-bis(4-chlorophenyl)-
U151	Benzene, 1,3-bis(4-chlorophenyl)-
U152	Benzene, 1,3-bis(4-chlorophenyl)-
U153	Benzene, 1,3-bis(4-chlorophenyl)-
U154	Benzene, 1,3-bis(4-chlorophenyl)-
U155	Benzene, 1,3-bis(4-chlorophenyl)-
U156	Benzene, 1,3-bis(4-chlorophenyl)-
U157	Benzene, 1,3-bis(4-chlorophenyl)-
U158	Benzene, 1,3-bis(4-chlorophenyl)-
U159	Benzene, 1,3-bis(4-chlorophenyl)-
U160	Benzene, 1,3-bis(4-chlorophenyl)-
U161	Benzene, 1,3-bis(4-chlorophenyl)-
U162	Benzene, 1,3-bis(4-chlorophenyl)-
U163	Benzene, 1,3-bis(4-chlorophenyl)-
U164	Benzene, 1,3-bis(4-chlorophenyl)-
U165	Benzene, 1,3-bis(4-chlorophenyl)-
U166	Benzene, 1,3-bis(4-chlorophenyl)-
U167	Benzene, 1,3-bis(4-chlorophenyl)-
U168	Benzene, 1,3-bis(4-chlorophenyl)-
U169	Benzene, 1,3-bis(4-chlorophenyl)-
U170	Benzene, 1,3-bis(4-chlorophenyl)-
U171	Benzene, 1,3-bis(4-chlorophenyl)-
U172	Benzene, 1,3-bis(4-chlorophenyl)-
U173	Benzene, 1,3-bis(4-chlorophenyl)-
U174	Benzene, 1,3-bis(4-chlorophenyl)-
U175	Benzene, 1,3-bis(4-chlorophenyl)-
U176	Benzene, 1,3-bis(4-chlorophenyl)-
U177	Benzene, 1,3-bis(4-chlorophenyl)-
U178	Benzene, 1,3-bis(4-chlorophenyl)-
U179	Benzene, 1,3-bis(4-chlorophenyl)-
U180	Benzene, 1,3-bis(4-chlorophenyl)-
U181	Benzene, 1,3-bis(4-chlorophenyl)-
U182	Benzene, 1,3-bis(4-chlorophenyl)-
U183	Benzene, 1,3-bis(4-chlorophenyl)-
U184	Benzene, 1,3-bis(4-chlorophenyl)-
U185	Benzene, 1,3-bis(4-chlorophenyl)-
U186	Benzene, 1,3-bis(4-chlorophenyl)-
U187	Benzene, 1,3-bis(4-chlorophenyl)-
U188	Benzene, 1,3-bis(4-chlorophenyl)-
U189	Benzene, 1,3-bis(4-chlorophenyl)-
U190	Benzene, 1,3-bis(4-chlorophenyl)-
U191	Benzene, 1,3-bis(4-chlorophenyl)-
U192	Benzene, 1,3-bis(4-chlorophenyl)-
U193	Benzene, 1,3-bis(4-chlorophenyl)-
U194	Benzene, 1,3-bis(4-chlorophenyl)-
U195	Benzene, 1,3-bis(4-chlorophenyl)-
U196	Benzene, 1,3-bis(4-chlorophenyl)-
U197	Benzene, 1,3-bis(4-chlorophenyl)-
U198	Benzene, 1,3-bis(4-chlorophenyl)-
U199	Benzene, 1,3-bis(4-chlorophenyl)-
U200	Benzene, 1,3-bis(4-chlorophenyl)-
U201	Benzene, 1,3-bis(4-chlorophenyl)-
U202	Benzene, 1,3-bis(4-chlorophenyl)-
U203	Benzene, 1,3-bis(4-chlorophenyl)-
U204	Benzene, 1,3-bis(4-chlorophenyl)-
U205	Benzene, 1,3-bis(4-chlorophenyl)-
U206	Benzene, 1,3-bis(4-chlorophenyl)-
U207	Benzene, 1,3-bis(4-chlorophenyl)-
U208	Benzene, 1,3-bis(4-chlorophenyl)-
U209	Benzene, 1,3-bis(4-chlorophenyl)-
U210	Benzene, 1,3-bis(4-chlorophenyl)-
U211	Benzene, 1,3-bis(4-chlorophenyl)-
U212	Benzene, 1,3-bis(4-chlorophenyl)-
U213	Benzene, 1,3-bis(4-chlorophenyl)-
U214	Benzene, 1,3-bis(4-chlorophenyl)-
U215	Benzene, 1,3-bis(4-chlorophenyl)-
U216	Benzene, 1,3-bis(4-chlorophenyl)-
U217	Benzene, 1,3-bis(4-chlorophenyl)-
U218	Benzene, 1,3-bis(4-chlorophenyl)-
U219	Benzene, 1,3-bis(4-chlorophenyl)-
U220	Benzene, 1,3-bis(4-chlorophenyl)-
U221	Benzene, 1,3-bis(4-chlorophenyl)-
U222	Benzene, 1,3-bis(4-chlorophenyl)-
U223	Benzene, 1,3-bis(4-chlorophenyl)-
U224	Benzene, 1,3-bis(4-chlorophenyl)-
U225	Benzene, 1,3-bis(4-chlorophenyl)-
U226	Benzene, 1,3-bis(4-chlorophenyl)-
U227	Benzene, 1,3-bis(4-chlorophenyl)-
U228	Benzene, 1,3-bis(4-chlorophenyl)-
U229	Benzene, 1,3-bis(4-chlorophenyl)-
U230	Benzene, 1,3-bis(4-chlorophenyl)-
U231	Benzene, 1,3-bis(4-chlorophenyl)-
U232	Benzene, 1,3-bis(4-chlorophenyl)-
U233	Benzene, 1,3-bis(4-chlorophenyl)-
U234	Benzene, 1,3-bis(4-chlorophenyl)-
U235	Benzene, 1,3-bis(4-chlorophenyl)-
U236	Benzene, 1,3-bis(4-chlorophenyl)-
U237	Benzene, 1,3-bis(4-chlorophenyl)-
U238	Benzene, 1,3-bis(4-chlorophenyl)-
U239	Benzene, 1,3-bis(4-chlorophenyl)-
U240	Benzene, 1,3-bis(4-chlorophenyl)-
U241	Benzene, 1,3-bis(4-chlorophenyl)-
U242	Benzene, 1,3-bis(4-chlorophenyl)-
U243	Benzene, 1,3-bis(4-chlorophenyl)-
U244	Benzene, 1,3-bis(4-chlorophenyl)-
U245	Benzene, 1,3-bis(4-chlorophenyl)-
U246	Benzene, 1,3-bis(4-chlorophenyl)-
U247	Benzene, 1,3-bis(4-chlorophenyl)-
U248	Benzene, 1,3-bis(4-chlorophenyl)-
U249	Benzene, 1,3-bis(4-chlorophenyl)-
U250	Benzene, 1,3-bis(4-chlorophenyl)-
U251	Benzene, 1,3-bis(4-chlorophenyl)-
U252	Benzene, 1,3-bis(4-chlorophenyl)-
U253	Benzene, 1,3-bis(4-chlorophenyl)-
U254	Benzene, 1,3-bis(4-chlorophenyl)-
U255	Benzene, 1,3-bis(4-chlorophenyl)-
U256	Benzene, 1,3-bis(4-chlorophenyl)-
U257	Benzene, 1,3-bis(4-chlorophenyl)-
U258	Benzene, 1,3-bis(4-chlorophenyl)-
U259	Benzene, 1,3-bis(4-chlorophenyl)-
U260	Benzene, 1,3-bis(4-chlorophenyl)-
U261	Benzene, 1,3-bis(4-chlorophenyl)-
U262	Benzene, 1,3-bis(4-chlorophenyl)-
U263	Benzene, 1,3-bis(4-chlorophenyl)-
U264	Benzene, 1,3-bis(4-chlorophenyl)-
U265	Benzene, 1,3-bis(4-chlorophenyl)-
U266	Benzene, 1,3-bis(4-chlorophenyl)-
U267	Benzene, 1,3-bis(4-chlorophenyl)-
U268	Benzene, 1,3-bis(4-chlorophenyl)-
U269	Benzene, 1,3-bis(4-chlorophenyl)-
U270	Benzene, 1,3-bis(4-chlorophenyl)-
U271	Benzene, 1,3-bis(4-chlorophenyl)-
U272	Benzene, 1,3-bis(4-chlorophenyl)-
U273	Benzene, 1,3-bis(4-chlorophenyl)-
U274	Benzene, 1,3-bis(4-chlorophenyl)-
U275	Benzene, 1,3-bis(4-chlorophenyl)-
U276	Benzene, 1,3-bis(4-chlorophenyl)-
U277	Benzene, 1,3-bis(4-chlorophenyl)-
U278	Benzene, 1,3-bis(4-chlorophenyl)-
U279	Benzene, 1,3-bis(4-chlorophenyl)-
U280	Benzene, 1,3-bis(4-chlorophenyl)-
U281	Benzene, 1,3-bis(4-chlorophenyl)-
U282	Benzene, 1,3-bis(4-chlorophenyl)-
U283	Benzene, 1,3-bis(4-chlorophenyl)-
U284	Benzene, 1,3-bis(4-chlorophenyl)-
U285	Benzene, 1,3-bis(4-chlorophenyl)-
U286	Benzene, 1,3-bis(4-chlorophenyl)-
U287	Benzene, 1,3-bis(4-chlorophenyl)-
U288	Benzene, 1,3-bis(4-chlorophenyl)-
U289	Benzene, 1,3-bis(4-chlorophenyl)-
U290	Benzene, 1,3-bis(4-chlorophenyl)-
U291	Benzene, 1,3-bis(4-chlorophenyl)-
U292	Benzene, 1,3-bis(4-chlorophenyl)-
U293	Benzene, 1,3-bis(4-chlorophenyl)-
U294	Benzene, 1,3-bis(4-chlorophenyl)-
U295	Benzene, 1,3-bis(4-chlorophenyl)-
U296	Benzene, 1,3-bis(4-chlorophenyl)-
U297	Benzene, 1,3-bis(4-chlorophenyl)-
U298	Benzene, 1,3-bis(4-chlorophenyl)-
U299	Benzene, 1,3-bis(4-chlorophenyl)-
U300	Benzene, 1,3-bis(4-chlorophenyl)-
U301	Benzene, 1,3-bis(4-chlorophenyl)-
U302	Benzene, 1,3-bis(4-chlorophenyl)-
U303	Benzene, 1,3-bis(4-chlorophenyl)-
U304	Benzene, 1,3-bis(4-chlorophenyl)-
U305	Benzene, 1,3-bis(4-chlorophenyl)-
U306	Benzene, 1,3-bis(4-chlorophenyl)-
U307	Benzene, 1,3-bis(4-chlorophenyl)-
U308	Benzene, 1,3-bis(4-chlorophenyl)-
U309	Benzene, 1,3-bis(4-chlorophenyl)-
U310	Benzene, 1,3-bis(4-chlorophenyl)-
U311	Benzene, 1,3-bis(4-chlorophenyl)-
U312	Benzene, 1,3-bis(4-chlorophenyl)-
U313	Benzene, 1,3-bis(4-chlorophenyl)-
U314	Benzene, 1,3-bis(4-chlorophenyl)-
U315	Benzene, 1,3-bis(4-chlorophenyl)-
U316	Benzene, 1,3-bis(4-chlorophenyl)-
U317	Benzene, 1,3-bis(4-chlorophenyl)-
U318	Benzene, 1,3-bis(4-chlorophenyl)-
U319	Benzene, 1,3-bis(4-chlorophenyl)-
U320	Benzene, 1,3-bis(4-chlorophenyl)-
U321	Benzene, 1,3-bis(4-chlorophenyl)-
U322	Benzene, 1,3-bis(4-chlorophenyl)-
U323	Benzene, 1,3-bis(4-chlorophenyl)-
U324	Benzene, 1,3-bis(4-chlorophenyl)-
U325	Benzene, 1,3-bis(4-chlorophenyl)-
U326	Benzene, 1,3-bis(4-chlorophenyl)-
U327	Benzene, 1,3-bis(4-chlorophenyl)-
U328	Benzene, 1,3-bis(4-chlorophenyl)-
U329	Benzene, 1,3-bis(4-chlorophenyl)-
U330	Benzene, 1,3-bis(4-chlorophenyl)-
U331	Benzene, 1,3-bis(4-chlorophenyl)-
U332	Benzene, 1,3-bis(4-chlorophenyl)-
U333	Benzene, 1,3-bis(4-chlorophenyl)-
U334	Benzene, 1,3-bis(4-chlorophenyl)-
U335	Benzene, 1,3-bis(4-chlorophenyl)-
U336	Benzene, 1,3-bis(4-chlorophenyl)-
U337	Benzene, 1,3-bis(4-chlorophenyl)-
U338	Benzene, 1,3-bis(4-chlorophenyl)-
U339	Benzene, 1,3-bis(4-chlorophenyl)-
U340	Benzene, 1,3-bis(4-chlorophenyl)-
U341	Benzene, 1,3-bis(4-chlorophenyl)-
U342	Benzene, 1,3-bis(4-chlorophenyl)-
U343	Benzene, 1,3-bis(4-chlorophenyl)-
U344	Benzene, 1,3-bis(4-chlorophenyl)-
U345	Benzene, 1,3-bis(4-chlorophenyl)-
U346	Benzene, 1,3-bis(4-chlorophenyl)-
U347	Benzene, 1,3-bis(4-chlorophenyl)-
U348	Benzene, 1,3-bis(4-chlorophenyl)-
U349	Benzene, 1,3-bis(4-chlorophenyl)-
U350	Benzene, 1,3-bis(4-chlorophenyl)-
U351	Benzene, 1,3-bis(4-chlorophenyl)-
U352	Benzene, 1,3-bis(4-chlorophenyl)-
U353	Benzene, 1,3-bis(4-chlorophenyl)-
U354	Benzene, 1,3-bis(4-chlorophenyl)-
U355	Benzene, 1,3-bis(4-chlorophenyl)-
U356	Benzene, 1,3-bis(4-chlorophenyl)-
U357	Benzene, 1,3-bis(4-chlorophenyl)-
U358	Benzene, 1,3-bis(4-chlorophenyl)-
U359	Benzene, 1,3-bis(4-chlorophenyl)-
U360	Benzene, 1,3-bis(4-chlorophenyl)-
U361	Benzene, 1,3-bis(4-chlorophenyl)-
U362	Benzene, 1,3-bis(4-chlorophenyl)-
U363	Benzene, 1,3-bis(4-chlorophenyl)-
U364	Benzene, 1,3-bis(4-chlorophenyl)-
U365	Benzene, 1,3-bis(4-chlorophenyl)-
U366	Benzene, 1,3-bis(4-chlorophenyl)-
U367	Benzene, 1,3-bis(4-chlorophenyl)-
U368	Benzene, 1,3-bis(4-chlorophenyl)-
U369	Benzene, 1,3-bis(4-chlorophenyl)-
U370	Benzene, 1,3-bis(4-chlorophenyl)-
U371	Benzene, 1,3-bis(4-chlorophenyl)-
U372	Benzene, 1,3-bis(4-chlorophenyl)-
U373	Benzene, 1,3-bis(4-chlorophenyl)-
U374	Benzene, 1,3-bis(4-chlorophenyl)-
U375	Benzene, 1,3-bis(4-chlorophenyl)-
U376	Benzene, 1,3-bis(4-chlorophenyl)-
U377	Benzene, 1,3-bis(4-chlorophenyl)-
U378	Benzene, 1,3-bis(4-chlorophenyl)-
U379	Benzene, 1,3-bis(4-chlorophenyl)-
U380	Benzene, 1,3-bis(4-chlorophenyl)-
U381	Benzene, 1,3-bis(4-chlorophenyl)-
U382	Benzene, 1,3-bis(4-chlorophenyl)-
U383	Benzene, 1,3-bis(4-chlorophenyl)-
U384	Benzene, 1,3-bis(4-chlorophenyl)-
U385	Benzene, 1,3-bis(4-chlorophenyl)-

§ 261.33

2-50

40 CFR Ch. I (7-1-85 Edition)

D-61

Environmental Protection Agency

§ 261.33

Hazardous Waste No.	Substance	Hazardous Waste No.	Substance
U179	N-Nitrosopyrrolidine	U016	L-Serine, diisocyanate (ester)
U180	N-Nitrosopyrrolidine	See F027	Silver
U181	5-Nitro-o-toluidine	U069	4,4'-Sulfonated, alpha,alpha'-diethyl-
U189	1,3-Oxathiane, 2,2-dioxide	U208	Streptocyclon
U088	2-(1,3,2-Oxazaphosphorine, 2-bis(2-chloro-ethylamino)tetrahydro-, oxide 2-	U136	Sulfur hydride
U116	Oxirane (E.T.)	U103	Sulfuric acid, dimethyl ester
U041	Oxirane, 2-(chloromethyl)-	U188	Sulfur phosphide (R)
U162	Pentachloride	U206	Sulfur sesquioxide (R,T)
U183	Pentachlorobenzene	See F027	2,4,5-T
U184	Pentachlorobenzene	U207	1,2,4,5-Tetrachlorobenzene
U185	Pentachlorobenzene	U208	1,1,1,2-Tetrachloroethane
See F027	Pentachlorophenol	U209	1,1,2,2-Tetrachloroethane
U186	1,3-Pentadiene (R)	U210	Tetrachloroethylene
U187	Phenacetic acid	See F027	2,3,4,6-Tetrachlorophenol
U188	Phenol	U213	Tetrahydrofuran (R)
U048	Phenol, 2-chloro-	U214	Thallium(I) acetate
U038	Phenol, 4-chloro-3-methyl-	U215	Thallium(I) carbonate
U081	Phenol, 2,4-dichloro-	U216	Thallium(I) chloride
U082	Phenol, 2,6-dichloro-	U217	Thallium(I) nitrate
U101	Phenol, 2,4-dimethyl-	U218	Thioacetamide
U170	Phenol, 4-nitro-	U153	Thiomethanol (E.T.)
See F027	Phenol, pentachloro-	U219	Thiourea
Do	Phenol, 2,3,4,6-tetrachloro-	U244	Thionin
Do	Phenol, 2,4,6-trichloro-	U220	Toluene
Do	Phenol, 2,4,6-trichloro-	U221	Toluene diisocyanate
U137	1,1-(1,2-phenylene)pyrene	U223	Toluene diisocyanate (R,T)
U146	Phosphoric acid, Lead salt	U222	O-Toluidine hydrochloride
U087	Phosphorodithioic acid, O,O-diethyl-, S-methyl-, ester	U011	1H-1,2,4-Triazole-3-one
U189	Phosphorus sulfide (R)	U226	1,1,1-Trichloroethane
U180	Phthalic anhydride	U227	1,1,2-Trichloroethane
U191	2-Phthaline	U228	Trichloroethylene
U192	Phthalic acid	U229	Trichloroethylene
U184	1-Propyleneimine (E.T.)	U121	Trichloromethylbenzene
U110	1-Propyleneimine, N-methyl- (R)	See F027	2,4,5-Trichlorophenol
U088	Propylene, 1,2-dichloro-3-chloro-	Do	2,4,6-Trichlorophenol
U148	Propyleneimine	Do	2,4,6-Trichlorophenylacetic acid
U171	Propylene, 2-methyl- (R)	U234	sym-Triazobenzene (R,T)
U027	Propylene, 2,2'-bis(2-chloro-	U182	1,3,5-Triazole, 2,4,5-trimethyl-
U193	1,3-Propylene sulfide	U235	Tri(2,3-dibromopropyl) phosphite
U239	1-Propenol, 2,3-dichloro-, phosphate (2:1)	U236	Trypan blue
U128	1-Propenol, 2,3-dimethyl-	U237	Ureac, 5-bis(2-chloromethylamino)-
U149	1-Propenol, 2-methyl- (R,T)	U237	Ureac mustard
U002	2-Propenone (R)	U043	Vinyl chloride
U007	2-Propenone	U248	Werkman, when present at concentrations of 0.3% or less
U084	Propene, 1,3-dichloro-	U238	Xylene (R)
U243	1-Propene, 1,1,2,3,3,3-hexachloro-	U200	Y-cyanobenzene-1-carboxylic acid, 11,17-dimethyl-18-((2,4,5-trimethyl-3-oxobenzyl)-, methyl ester
U008	2-Propenone	U248	Zinc phosphide, when present at concentrations of 10% or less
U152	2-Propenone, 2-methyl- (R,T)		
U008	2-Propenone acid (R)		
U113	2-Propenone acid, ethyl ester (R)		
U118	2-Propenone acid, 2-methyl-, ethyl ester		
U182	2-Propenone acid, 2-methyl-, methyl ester (R,T)		
See F027	Propionic acid, 2-(2,4,5-trichlorophenyl)-		
U184	n-Propyleneimine (R,T)		
U082	Propylene carbonate		
U188	Pyridine		
U156	Pyridine, 2-(2-(2-dimethylamino-2-phenyl-ethyl)-		
U179	Pyridine, tetrahydro-N-oxide		
U191	Pyridine, 2-methyl-		
U184	4-(1H-Pyrazol-5-yl)-2,3-dihydro-6-methyl-2-thio-		
U180	Pyrazole, tetrahydro-N-oxide		
U200	Reserpine		
U201	Resorcinol		
U202	Saccharin and salts		
U203	Serine		
U204	Selenous acid		
U204	Selenium dioxide		
U205	Selenium disulfide (R,T)		

(45 FR 78529, 78541, Nov. 25, 1980, as amended at 48 FR 27477, May 20, 1983; 49 FR 19923, May 10, 1984; 49 FR 685, Jan. 4, 1985; 50 FR 2000, Jan. 14, 1985)

EFFECTIVE DATE NOTE: At 50 FR 685, Jan. 4, 1985, § 261.33 introductory text was revised, effective July 5, 1985. At 50 FR 2000, Jan. 14, 1985, the table in paragraph (f) was amended by revising certain hazardous waste numbers, effective July 15, 1985. For the convenience of the user, the superseded introductory text (published at 49 FR 37070, Sept. 21, 1984), and entries in the paragraph (f) table, are set out below.

Part 261, App. I

§ 261.33 Discarded commercial chemical products, off-specification species, container residues and spill residues thereof.

The following materials or items are hazardous wastes if and when they are discarded or intended to be discarded unless they are excluded under §§ 260.20 and 260.22 and listed in Appendix IX.

(f) * * *

Hazardous Waste No.	Substance
U242	Permethrin
U242	Permethrin
U212	Permethrin 2,4,5-trichlorophenyl
U212	Permethrin 2,4,5-trichlorophenyl
U230	Permethrin 2,4,5-trichlorophenyl
U231	Propionic acid, 2-(2,4,5-trichlorophenyl)-
U233	Solids
U232	2,4,5-T
U212	2,3,4,5-Tetrachlorophenyl
U230	2,4,5-Trichlorophenyl
U231	2,4,5-Trichlorophenyl
U230	2,4,5-Trichlorophenyl

APPENDIX I—REPRESENTATIVE SAMPLING METHODS

The methods and equipment used for sampling waste materials will vary with the form and consistency of the waste materials to be sampled. Samples collected using the sampling protocols listed below, for sampling waste with properties similar to the indicated materials, will be considered by the Agency to be representative of the waste.

Extremely viscous liquid—ASTM Standard D140-70 Crushed or powdered material—ASTM Standard D346-75 Soil or rock-like material—ASTM Standard D420-69 Soil-like material—ASTM Standard D1452-65 Fly Ash-like material—ASTM Standard D2234-76 (ASTM Standards are available from ASTM, 1916 Race St., Philadelphia, PA 19103)

Containerized liquid wastes—COLIWASA¹ described in "Test Methods for the Evaluation of Solid Waste, Physical/Chemical

40 CFR Ch. I (7-1-85 Edition)

Methods." U.S. Environmental Protection Agency, Office of Solid Waste, Washington, D.C. 20460 (Copies may be obtained from Solid Waste Information, U.S. Environmental Protection Agency, 26 W. St. Clair St., Cincinnati, Ohio 45268)

Liquid waste in pits, ponds, lagoons, and similar reservoirs—Pond Sampler² described in "Test Methods for the Evaluation of Solid Waste, Physical/Chemical Methods."

This manual also contains additional information on application of these protocols.

APPENDIX II—EP TOXICITY TEST PROCEDURES

A. Extraction Procedure (EP)

1. A representative sample of the waste to be tested (minimum size 100 grams) shall be obtained using the methods specified in Appendix I, or any other method capable of yielding a representative sample within the meaning of Part 260. (For detailed guidance on conducting the various aspects of the EP see "Test Methods for the Evaluation of Solid Waste, Physical/Chemical Methods" (incorporated by reference, see § 260.11).)

2. The sample shall be separated into its component liquid and solid phases using the method described in "Separation Procedure" below. If the solid residue³ obtained using this method totals less than 0.5% of the original weight of the waste, the residue can be discarded and the operator shall treat the liquid phase as the extract and proceed immediately to Step 8.

3. The solid material obtained from the Separation Procedure shall be evaluated for its particle size. If the solid material has a surface area per gram of material equal to, or greater than, 3.1 cm² or passes through a 9.5 mm (0.375 inch) standard sieve, the operator shall proceed to Step 4. If the surface area is smaller or the particle size larger than specified above, the solid material shall be prepared for extraction by crushing, cutting or grinding the material so that

¹ These methods are also described in "Samplers and Sampling Procedures for Hazardous Waste Streams," EPA 800/2-80-018, January 1980.

² The percent solids is determined by drying the filter pad at 80°C until it reaches constant weight and then calculating the percent solids using the following equation:
Percent solids =

$$\frac{\text{weight of dried solids} - \text{tare weight of pad}}{\text{total weight of sample}} \times 100$$

Environmental Protection Agency

Part 261, App. II

passes through a 0.5 mm (0.375 inch) sieve. If the material is in a single piece, by subjecting the material to the "Structural Integrity Procedure" described below.

4. The solid material obtained in Step 3 shall be weighed and placed in an extractor with 16 times its weight of deionized water. Do not allow the material to dry prior to weighing. For purposes of this test, an acceptable extractor is one which will impart sufficient agitation to the mixture to not prevent stratification of the sample and extraction fluid but also insure that all sample surfaces are continuously brought into contact with well mixed extraction fluid.

5. After the solid material and deionized water are placed in the extractor, the operator shall begin agitation and measure the pH of the solution in the extractor. If the pH of the solution is greater than 5.0, the pH of the solution shall be decreased to 5.0 ± 0.2 by adding 0.5 N acetic acid. If the pH is equal to or less than 5.0, no acetic acid should be added. The pH of the solution shall be monitored, as described below, during the course of the extraction and if the pH rises above 5.2, 0.5N acetic acid shall be added to bring the pH down to 5.0 ± 0.2 . However, in no event shall the aggregate amount of acid added to the solution exceed 4 ml of acid per gram of solid. The mixture shall be agitated for 24 hours and maintained at $20^\circ \pm 4^\circ \text{C}$ ($68^\circ\text{--}104^\circ \text{F}$) during this time. It is recommended that the operator monitor and adjust the pH during the course of the extraction with a device such as the Type 45-A pH Controller manufactured by Chemtrix, Inc., Hillsboro, Oregon 97123 or its equivalent, in conjunction with a metering pump and reservoir of 0.5N acetic acid. If such a system is not available, the following manual procedure shall be employed:

a. A pH meter shall be calibrated in accordance with the manufacturer's specifications.

b. The pH of the solution shall be checked and, if necessary, 0.5N acetic acid shall be manually added to the extractor until the pH reaches 5.0 ± 0.2 . The pH of the solution shall be adjusted at 15, 30 and 45 minute intervals, moving to the next longer interval if the pH does not have to be adjusted more than 0.5N pH units.

c. The adjustment procedure shall be continued for at least 6 hours.

d. If at the end of the 24-hour extraction period the pH of the solution is not below 5.2 and the maximum amount of acid (4 ml per gram of solids) has not been added, the pH shall be adjusted to 5.0 ± 0.2 and the extraction continued for an additional four hours during which the pH shall be adjusted at one hour intervals.

e. At the end of the 24 hour extraction period deionized water shall be added to

the extractor in an amount determined by the following equation:

$$V = (20 \times W) - 16(W) - A$$

V = ml deionized water to be added

W = weight in grams of solid charged to extractor

A = ml of 0.5N acetic acid added during extraction

7. The material in the extractor shall be separated into its component liquid and solid phases as described under "Separation Procedure."

8. The liquids resulting from Steps 2 and 7 shall be combined. This combined liquid (or the waste itself if it has less than 4 percent solids, as noted in step 2) is the extract and shall be analyzed for the presence of any of the contaminants specified in Table I of § 261.24 using the Analytical Procedures designated below.

Separation Procedure

Equipment: A filter holder, designed for filtration media having a nominal pore size of 0.45 micrometers and capable of applying a 5.3 kg/cm^2 (75 psi) hydrostatic pressure to the solution being filtered, shall be used. For mixtures containing nonabsorptive solids, where separation can be effected without imposing a 5.3 kg/cm^2 pressure differential, vacuum filters employing a 0.45 micrometers filter media can be used. (For further guidance on filtration equipment or procedures see "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods" incorporated by reference, see § 260.11). Procedure:

(1) Following manufacturer's directions, the filter unit shall be assembled with a filter bed consisting of a 0.45 micrometer filter membrane. For difficult or slow to filter mixtures a prefilter bed consisting of the following prefilters in increasing pore size (0.65 micrometer membrane, fine glass

"This procedure is intended to result in separation of the "free" liquid portion of the waste from any solid matter having a particle size $>0.45 \mu\text{m}$. If the sample will not filter, various other separation techniques can be used to aid in the filtration. As described above, pressure filtration is employed to speed up the filtration process. This does not alter the nature of the separation. If liquid does not separate during filtration, the waste can be centrifuged. If separation occurs during centrifugation, the liquid portion (centrifugate) is filtered through the 0.45 μm filter prior to becoming mixed with the liquid portion of the waste obtained from the initial filtration. Any material that will not pass through the filter after centrifugation is considered a solid and is extracted.

Part 261, App. II

40 CFR Ch. I (7-1-85 Edition)

fiber prefilter, and coarse glass fiber prefilter) can be used.

(ii) The waste shall be poured into the filtration unit.

(iii) The reservoir shall be slowly pressurized until liquid begins to flow from the filtrate outlet at which point the pressure in the filter shall be immediately lowered to 10-15 psig. Filtration shall be continued until liquid flow ceases.

(iv) The pressure shall be increased stepwise in 10 psi increments to 75 psig and filtration continued until flow ceases or the pressurizing gas begins to exit from the filtrate outlet.

(v) The filter unit shall be depressurized, the solid material removed and weighed and then transferred to the extraction apparatus, or, in the case of final filtration prior to analysis, discarded. Do not allow the material retained on the filter pad to dry prior to weighing.

(vi) The liquid phase shall be stored at 4°C for subsequent use in Step 8.

B. Structural Integrity Procedure

Equipment: A Structural Integrity Tester having a 3.18 cm (1.25 in.) diameter hammer weighing 0.33 kg (0.73 lbs.) and having a free fall of 15.24 cm (6 in.) shall be used. This device is available from Associated Design and Manufacturing Company, Alexandria, VA 22314, as Part No. 125, or it may be fabricated to meet the specifications shown in Figure 1.

Procedure

1. The sample holder shall be filled with the material to be tested. If the sample of waste is a large monolithic block, a portion shall be cut from the block having the dimensions of a 3.3 cm (1.3 in.) diameter x 7.1 cm (2.8 in.) cylinder. For a fixated waste, samples may be cast in the form of a 3.3 cm (1.3 in.) diameter x 7.1 cm (2.8 in.) cylinder for purposes of conducting this test. In such cases, the waste may be allowed to cure for 30 days prior to further testing.

2. The sample holder shall be placed into the Structural Integrity Tester, then the hammer shall be raised to its maximum height and dropped. This shall be repeated fifteen times.

3. The material shall be removed from the sample holder, weighed, and transferred to the extraction apparatus for extraction.


Analytical Procedures for Analyzing Extract Contaminants

The test methods for analyzing the extract are as follows:

1. For arsenic, barium, cadmium, chromium, lead, mercury, selenium, silver, endrin, lindane, methoxychlor, toxaphene, 2,4-D (2,4-dichlorophenoxyacetic acid) or 2,4,5-TP (2,4,5-trichlorophenoxypropionic acid) "Test Methods for the Evaluation of Solid Waste, Physical/Chemical Methods" (incorporated by reference, see § 260.11).

2. (Reserved)

For all analyses, the methods of standard addition shall be used for quantification of species concentration.



*ELASTOMERIC SAMPLE HOLDER FABRICATED OF MATERIAL FIRM ENOUGH TO SUPPORT THE SAMPLE

Figure 1
COMPACTION TESTER

40 CFR 261.119, May 19, 1980 as amended at 46 FR 35247, July 7, 1981

APPENDIX III—CHEMICAL ANALYSIS
TEST METHODS

Tables 1, 2, and 3 specify the appropriate analytical procedures, described in "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods," (incorporated by reference, see § 260.11) which shall be used to determine whether a sample contains a given Appendix VII or VIII toxic constituent.

Table 1 identifies each Appendix VII or VIII organic constituent along with the approved measurement method. Table 2 identifies the corresponding methods for inorganic species. Table 3 summarizes the contents of SW-846 and supplies specific section and method numbers for sampling and analysis methods.

Prior to final sampling and analysis method selection the analyst should consult the specific section or method described in SW-846 for additional guidance on which of the approved methods should be employed for a specific sample analysis situation.

TABLE 1—ANALYSIS METHODS FOR ORGANIC
CHEMICALS CONTAINED IN SW-846

Compound	First edition method(s)	Second edition method(s)
Acetonitrile	8.03, 8.24	8030, 8240
Acrolein	8.03, 8.24	8030, 8240
Acrylonitrile	8.01, 8.24	8015, 8240
Acrylonitrile	8.03, 8.24	8030, 8240
Benzene	8.02, 8.24	8020, 8024
Benz(a)anthracene	8.10, 8.25	8100, 8250, 8310
Benz(a)pyrene	8.10, 8.25	8100, 8250, 8310
Benzotrifluoride	8.12, 8.25	8120, 8250
Benzyl chloride	8.01, 8.12, 8.24, 8.25	8120, 8250
Benzobicyclopentadiene	8.10, 8.25	8100, 8250, 8310
Bis(2-chloroethoxy)methane	8.01, 8.24	8010, 8240
Bis(2-chloroethyl)ether	8.01, 8.24	8010, 8240
Bis(2-chloroethoxy)ether	8.01, 8.24	8010, 8240
Carbon disulfide	8.01, 8.24	8015, 8240
Carbon tetrachloride	8.01, 8.24	8010, 8240
Chloroform	8.08, 8.25	8080, 8250
Chlorinated biphenyls	8.08, 8.25	8080, 8250
Chlorinated dibenzo-p-dioxins		8280
Chlorinated dibenzofurans		8280
Chloroacetaldehyde	8.01, 8.24	8010, 8240
Chlorobenzene	8.01, 8.02, 8.24	8020, 8240
Chloroform	8.01, 8.24	8010, 8240
Chloromethane	8.01, 8.24	8010, 8240
2-Chlorophenol	8.04, 8.25	8040, 8250
Chrysene	8.10, 8.25	8100, 8250, 8310
Creosote	8.10, 8.25	8100, 8250
Cresol(s)	8.04, 8.25	8040, 8250
Crotonic Acid(s)	8.04, 8.25	8040, 8250

TABLE 1—ANALYSIS METHODS FOR ORGANIC
CHEMICALS CONTAINED IN SW-846—Continued

Compound	First edition method(s)	Second edition method(s)
Dichlorobenzene(s)	8.01, 8.02, 8.12, 8.25	8010, 8120, 8250
Dichloroethane(s)	8.01, 8.24	8010, 8240
Dichloromethane	8.01, 8.24	8010, 8240
Dichlorophenoxyacetic acid	8.40, 8.25	8150, 8250
Dichloropropanol	8.12, 8.25	8120, 8250
2,4-Dimethylphenol	8.04, 8.25	8040, 8250
Dinitrobenzene	8.08, 8.25	8080, 8250
4,6-Dinitro-o-cresol	8.04, 8.25	8040, 8250
2,4-Dinitrotoluene	8.08, 8.25	8080, 8250
Endrin	8.08, 8.25	8080, 8250
Ethyl ether	8.01, 8.02, 8.24	8015, 8240
Formaldehyde	8.01, 8.24	8015, 8240
Formic acid	8.08, 8.25	8250
Heptachlor	8.08, 8.25	8080, 8250
Hexachlorobenzene	8.12, 8.25	8120, 8250
Hexachlorobutadiene	8.12, 8.25	8120, 8250
Hexachlorocyclopentadiene	8.12, 8.25	8120, 8250
Hexachlorocyclopentadiene	8.12, 8.25	8120, 8250
Urethane	8.08, 8.25	8080, 8250
Maleic anhydride	8.08, 8.25	8250
Methanol	8.01, 8.24	8010, 8240
Methylamine	8.32	8250
Methyl ethyl ketone	8.01, 8.02, 8.24	8015, 8240
Methyl isobutyl ketone	8.01, 8.02, 8.24	8015, 8240
Naphthalene	8.10, 8.25	8100, 8250
Naphthoquinone	8.08, 8.08, 8.25	8080, 8250
Nitrobenzene	8.08, 8.25	8080, 8250
4-Nitrophenol	8.04, 8.25	8040, 8240
Paraldehyde (trimer of acetaldehyde)	8.01, 8.24	8015, 8240
Pentachlorophenol	8.04, 8.25	8040, 8250
Phenol	8.04, 8.25	8040, 8250
Phosgene	8.22	8140
Phosphorodithioic acid esters	8.08, 8.08, 8.22	8140
Phthalic anhydride	8.08, 8.08, 8.25	8080, 8250
2-Picoline	8.08, 8.08, 8.25	8080, 8250
Pyridine	8.08, 8.08, 8.25	8080, 8250
Tetrachlorobenzene(s)	8.12, 8.25	8120, 8250
Tetrachloroethane(s)	8.01, 8.24	8010, 8240
Tetrachloroethene	8.01, 8.24	8010, 8240
Trichlorophenol	8.04, 8.24	8040, 8250
Toluene	8.02, 8.24	8020, 8024
Toluenediamine	8.25	8250
Toluene diisocyanate(s)	8.08, 8.25	8250
Toxaphene	8.08, 8.25	8080, 8250
Trichloroethane	8.01, 8.24	8010, 8240
Trichloroethene(s)	8.11, 8.24	8010, 8240
Trichlorofluoromethane	8.01, 8.24	8010, 8240
Trichlorophenol(s)	8.04, 8.25	8040, 8250
2,4,5-Trichlorophenoxy propionic acid	8.40, 8.25	8150, 8250
Trichloropropene	8.01, 8.24	8010, 8240
Vinyl chloride	8.01, 8.24	8010, 8240
Vinylidene chloride	8.01, 8.24	8010, 8240
Xylene	8.02, 8.24	8020, 8240

Environmental Protection Agency

Part 261, App. III

...for phenanthrene and carbazole, if these are
...a ratio between 1.4:1 and 5:1 creosote should be
...present

APP. E 2—ANALYSIS METHODS FOR INORGANIC
CHEMICALS CONTAINED IN SW-846

Compound	First edition method(s)	Second edition method(s)
...	8.50	7040, 7041
...	8.51	7080, 7081
...	8.52	7080, 7081
...	8.53	7080, 7081
...	8.54	7190, 7191
...	8.545, 8.546	7195, 7196

TABLE 2—ANALYSIS METHODS FOR INORGANIC
CHEMICALS CONTAINED IN SW-846—Continued

Compound	First edition method(s)	Second edition method(s)
Lead	8.547	7197
Mercury	8.56	7420, 7421
Nickel	8.57	7470, 7471
Selenium	8.58	7520, 7521
Silver	8.59	7740, 7741
Cyanides	8.60	7760, 7761
Total Organic Halogen	8.65	9010
Sulfides	8.66	9020
	8.67	9030

TABLE 3—SAMPLING AND ANALYSIS METHODS CONTAINED IN SW-846

Title	First edition		Second edition	
	Section No.	Method No.	Section No.	Method No.
Sampling of Solid Wastes	10		10	
Selection of Appropriate Sampling Plans	10		11	
Regulatory and Scientific Objectives	10-2		111	
Fundamental Statistical Concepts	10-3		112	
Basic Statistical Strategies	10-7		113	
Simple Random Sampling			1131	
Stratified Random Sampling			1132	
Systematic Random Sampling			1133	
Special Considerations	10-7			
Composite Sampling			1141	
Subsampling			1142	
Cost and Loss Functions			1143	
Implementation of Sampling Plan	10-7		12	
Selection of Sampling Equipment			121	
Composite Liquid Waste Sampler	32.1		1211	
Weighted Bottle	32.2		1212	
Dipper	32.3		1213	
Trawl	32.4		1214	
Trer	32.5		1215	
Auger	32.6		1216	
Scoop and Shovel	32.7		1217	
Selection of Sample Containers	33		122	
Processing and Storage of Samples	33		123	
Documentation of Chain of Custody	20		13	
Sample Labels	20-1		131	
Sample Seals	20-3		132	
Field Log Book	20-5		133	
Chain of Custody Record	20-6		134	
Sample Analysis Request Sheet	20-9		135	
Sample Delivery to Laboratory	20-10		136	
Shipping of Samples	20-10		137	
Receipt and Logging of Sample	20-12		138	
Ready Right of Sample for Analysis	20-13		139	
Sampling Methodology	30		14	
Underlimes	32-2		141	
Tanks	32-2		142	
Waste Piles	32-2		143	
Landfills and Lagoons	32-2		144	
Remediation Procedures			20	
Remediation of Hazardous Waste			21	
AP-42	40		211	
Pentax Manners Closed-Cup Method	41		211	1010
Settling Closed-Cup Method	41		211	1020
...	50		212	
...	53		212	1110
...	60		213	
...	70		214	

TABLE 3—SAMPLING AND ANALYSIS METHODS CONTAINED IN SW-846—Continued

Title	First edition		Second edition	
	Section No.	Method No.	Section No.	Method No.
Extraction Procedure Toxicity Test	7.1, 7.2, 7.5			
Method and Structural Integrity Test	7.4		2.1.4	1.110
Sample Workup Techniques			4.0	
Inorganic Techniques	8.49		4.1	
Acid Digestion for Flame AAS			4.1	3010
Acid Digestion for Furnace AAS			4.1	3020
Acid Digestion of Oil, Grease, or Wax	8.49-9		4.1	3030
Dissolution Procedure for Oil, Grease or Wax	8.49-2			
Alkaline Digestion	8.0	8.458	4.1	3080
Organic Techniques	8.0		4.2	
Separatory Funnel Liquid-Liquid Extraction	9.0	9.1	4.2	3510
Continuous Liquid-Liquid Extraction	9.0	9.01	4.2	3520
Acid-Base Cleanup Extraction	8.0	8.84	4.2	3530
Sorhlet Extraction	8.0	8.86	4.2	3540
Sonication Extraction	8.0	8.85	4.2	3550
Sample Introduction Techniques			5.0	
Headspace	8.0	8.82	5.0	5020
Purge-and-Trap	9.0	8.83	5.0	5030
Inorganic Analytical Methods	8.0		7.0	
Antimony, Flame AAS	8.0	8.50	7.0	7470
Antimony, Furnace AAS	8.0	8.50	7.0	7471
Arsenic, Flame AAS	8.0	8.51	7.0	7080
Arsenic, Furnace AAS	8.0	8.51	7.0	7081
Barium, Flame AAS	8.0	8.52	7.0	7080
Barium, Furnace AAS	8.0	8.52	7.0	7081
Cadmium, Flame AAS	8.0	8.53	7.0	7130
Cadmium, Furnace AAS	8.0	8.53	7.0	7131
Chromium, Flame AAS	8.0	8.54	7.0	7090
Chromium, Furnace AAS	8.0	8.54	7.0	7191
Chromium, Hexavalent, Coprecipitation	8.0	8.545	7.0	7195
Chromium, Hexavalent, Colorimetric	9.0	8.548	7.0	7196
Chromium, Hexavalent, Chelation	8.0	8.547	7.0	7197
Lead, Flame AAS	8.0	8.56	7.0	7420
Lead, Furnace AAS	8.0	8.56	7.0	7421
Mercury, Cold Vapor, Liquid	8.0	8.57	7.0	7470
Mercury, Cold Vapor, Solid	8.0	8.57	7.0	7471
Nickel, Flame AAS	8.0	8.58	7.0	7520
Nickel, Furnace AAS	8.0	8.58	7.0	7521
Selenium, Flame AAS	8.0	8.59	7.0	7740
Selenium, Gaseous Hydride AAS	8.0	8.59	7.0	7741
Silver, Flame AAS	8.0	8.60	7.0	7750
Silver, Furnace AAS	8.0	8.60	7.0	7751
Organic Analytical Methods	8.0		9.0	
Gas Chromatographic Methods	9.0		9.1	
Halogenated Volatile Organics	9.0	9.01	9.1	9010
Nonhalogenated Volatile Organics	9.0	9.01	9.1	9015
Aromatic Volatile Organics	9.0	9.02	9.1	9020
Acrolein, Acrylonitrile, Acetonitrile	9.0	9.03	9.1	9030
Phenols	9.0	9.04	9.1	9040
Phthalate Esters	9.0	9.06	9.1	9050
Organochlorine Pesticides and PCP's	9.0	9.08	9.1	9080
Nitroaromatics and Cyclic Ketones	9.0	9.09	9.1	9090
Polynuclear Aromatic Hydrocarbons	9.0	9.10	9.1	9100
Chlorinated Hydrocarbons	9.0	9.12	9.1	9120
Organophosphorus Pesticides	9.0	9.22	9.1	9140
Chlorinated Herbicides	9.0	9.40	9.1	9150
Gas Chromatographic-Mass Spectroscopy Methods (GC-MS)	9.0		9.2	
GC-MS Volatiles	9.0	9.24	9.2	9240
GC-MS Semi-volatiles, Packed Column	9.0	9.25	9.2	9250
GC-MS Semi-volatiles, Capillary	9.0	9.27	9.2	9270
Analysis of Chlorinated Dioxins and Dibenzofurans			9.2	9290
High Performance Liquid Chromatographic Methods (HPLC)	9.0		9.3	
Polynuclear Aromatic Hydrocarbons	9.0	9.10	9.3	9310
Miscellaneous Analytical Methods	9.0		9.0	
Gravimetric Total and Amenable to Chlorination	9.0	9.55	9.0	9510
Total Organic Halogen (TOX)	9.0	9.66	9.0	9520
Sulfides	9.0	9.67	9.0	9530
pH Measurement	9.0	9.2	9.0	9540

TABLE 3—SAMPLING AND ANALYSIS METHODS CONTAINED IN SW-846—Continued

Title	First edition		Second edition	
	Section No.	Method No.	Section No.	Method No.
Quality Control/Quality Assurance.....	10.0		10.1	
Production.....	10.0		10.1	
Program Design.....	10.0		10.2	
Sampling.....	10.0		10.3	
Analysis.....	10.0		10.4	
Data Handling.....	10.0		10.5	

See specific metal.

50 FR 15257, Apr. 8, 1983, as amended at 50 FR 2000, Jan. 14, 1985]

EFFECTIVE DATE NOTE: At 50 FR 2000, Jan. 14, 1985, Part 261, App. III was amended as follows: In Table 1, the entry for "Chlorinated dibenzodioxins" was removed, and the entries for "Chlorinated dibenzo-p-dioxins, and Chlorinated dibenzofurans" were added. In Table 3, the entry for "Analysis of Chlorinated Dioxins and Dibenzofurans" was added under "Organic Analytical Methods—Gas Chromatographic/Mass Spectroscopy Methods (GC/MS)" after the entry "GC/MS Semi-Volatiles, Capillary". These amendments are effective July 15, 1985. For the convenience of the user, the superseded entry from Table 1 is set out below:

TABLE 1—ANALYTICAL METHODS FOR ORGANIC CHEMICALS CONTAINED IN SW-846

Compound	First edition method(s)	Second edition method(s)
Chlorinated dibenzodioxins	8.06, 8.25	8080, 8250

APPENDIX IV—(RESERVED FOR RADIOACTIVE WASTE TEST METHODS)

APPENDIX V—(RESERVED FOR INFECTIOUS WASTE TREATMENT SPECIFICATIONS)

APPENDIX VI—(RESERVED FOR ETIOLOGIC AGENTS)

APPENDIX VII—BASIS FOR LISTING HAZARDOUS WASTE

EPA hazardous waste No.	Hazardous constituents for which tested
F001	Tetrachloroethylene, methylene chloride, trichloroethylene, 1,1,1-trichloroethane, carbon tetrachloride, chlorinated fluorocarbons.
F002	Tetrachloroethylene, methylene chloride, trichloroethylene, 1,1,1-trichloroethane, chlorobenzene, 1,1,2-trichloro-1,2,2-trifluoroethane, ortho-dichlorobenzene, trichlorofluoromethane.
F003	N.A.
F004	Cresols and cresylic acid, nitrobenzene.
F005	Toluene, methyl ethyl ketone, carbon disulfide, acetone, pyridine.
F006	Cadmium, hexavalent chromium, nickel, cyanide (complexed).
F007	Cyanide (salts).
F008	Cyanide (salts).
F009	Cyanide (salts).
F010	Cyanide (salts).
F011	Cyanide (salts).
F012	Cyanide (complexed).
F019	Hexavalent chromium, cyanide (complexed).
F020	Tetra- and pentachlorodibenzo-p-dioxins, tetra- and pentachlorodibenzofurans, tri- and tetrachlorophenols and their chlorophenoxy derivatives, acids, esters, ethers, amine and other salts.
F021	Penta- and hexachlorodibenzo-p-dioxins, penta- and hexachlorodibenzofurans, pentachlorophenol and its derivatives.
F022	Tetra-, penta- and hexachlorodibenzo-p-dioxins, tetra-, penta- and hexachlorodibenzofurans.
F023	Tetra- and pentachlorodibenzo-p-dioxins, tetra- and pentachlorodibenzofurans, tri- and tetra-chlorophenols and their chlorophenoxy derivatives, acids, esters, ethers, amine and other salts.

Part 261, App. VII

40 CFR Ch. I (7-1-85 Edition)

EPA hazard- ous waste No.	Hazardous constituents for which listed	EPA hazard- ous waste No.	Hazardous constituents for which listed
K024	Chloromethane, dichloromethane, trichloromethane, carbon tetrachloride, chloroethylene, 1,1-dichloroethylene, 1,2-dichloroethylene, trans-1,2-dichloroethylene, 1,1-dichloroethyne, 1,1,1-trichloroethyne, 1,1,2-trichloroethyne, trichloroethylene, 1,1,1,2-tetrachloroethane, 1,1,2,2-tetrachloroethane, tetrachloroethylene, pentachloroethane, hexachloroethane, allyl chloride (3-chloropropene), dichloropropene, dichloropropene, 2-chloro-1,3-butadiene, hexachloro-1,3-butadiene, hexachlorocyclopentadiene, hexachlorocyclohexene, benzene, chlorobenzene, dichlorobenzene, 1,2,4-trichlorobenzene, tetrachlorobenzene, pentachlorobenzene, hexachlorobenzene, toluene, naphthalene	K020	Ethylene, dichloride, 1,1,1-trichloroethane, 1,1,2-trichloroethane, tetrachloroethanes, 1,1,2,2-tetrachloroethane and 1,1,2,2-tetrachloroethanol, trichloroethylene, tetrachloroethylene, carbon tetrachloride, chloroform, vinyl chloride, vinylidene chloride
K026	Tetra-, penta-, and hexachlorodibenzo-p-dioxins, tetra-, penta-, and hexachlorodibenzofurans	K021	Arenes: carbon tetrachloride, chloroform
K027	Tetra-, penta-, and hexachlorodibenzo-p-dioxins, tetra-, penta-, and hexachlorodibenzofurans, tri-, tetra-, and pentachlorophenols and their chlorophenoxyl derivative acids, esters, ethers, amines and other salts	K022	Phenols, tars (polycyclic aromatic hydrocarbons)
K028	Tetra-, penta-, and hexachlorodibenzo-p-dioxins, tetra-, penta-, and hexachlorodibenzofurans, tri-, tetra-, and pentachlorophenols and their chlorophenoxyl derivative acids, esters, ethers, amines and other salts	K023	Phenolic anhydrides, mesic anhydride
K001	Pentachlorophenol, phenol, 2-chlorophenol, p-chlorophenol, 2,4-dimethylphenyl, 2,4-dinitrophenol, trichlorophenols, tetrachlorophenols, 2,4-dinitrophenol, cresols, chrysene, naphthalene, fluoranthene, benzo(b)fluoranthene, benzo(a)pyrene, indeno(1,2,3-cd)pyrene, benzo(a)anthracene, dibenz(a,h)anthracene, acenaphthene	K024	Phenolic anhydrides, 1,4-naphthoquinone
K002	Hexavalent chromium, lead	K025	Mesa-chlorobenzene, 2,4-dinitrobenzene
K003	Hexavalent chromium, lead	K026	Paraldehyde, pyridine, 2-pyridone
K004	Hexavalent chromium, lead	K027	Toluene, diacetylene, toluene-2,4-dithione
K005	Hexavalent chromium, lead	K028	1,1,1-trichloroethane, vinyl chloride
K006	Hexavalent chromium, lead	K029	1,2-dichloroethane, 1,1,1-trichloroethane, vinyl chloride, vinylidene chloride, chloroform
K007	Cyanide (complexed), hexavalent chromium	K030	Hexachlorobenzene, hexachlorobutadiene, hexachloroethane, 1,1,1,2-tetrachloroethane, 1,1,2,2-tetrachloroethane, ethylene dichloride
K008	Hexavalent chromium	K031	Arsenic
K009	Chloroform, formaldehyde, methylene chloride, methyl chloride, paraldehyde, formic acid, chloroacetaldehyde	K032	Hexachlorocyclopentadiene
K010	Chloroform, formaldehyde, methylene chloride, methyl chloride, paraldehyde, formic acid, chloroacetaldehyde	K033	Hexachlorocyclopentadiene
K011	Acrylonitrile, acetonitrile, hydrocyanic acid	K034	Hexachlorocyclopentadiene
K013	Hydrocyanic acid, acrylonitrile, acetonitrile	K035	Chrysene, chrysene, naphthalene, fluoranthene, benzo(b)fluoranthene, benzo(a)pyrene, indeno(1,2,3-cd)pyrene, benzo(a)anthracene, dibenz(a,h)anthracene, acenaphthene
K014	Acetonitrile, acrylonitrile	K036	Toluene, phosphorothioic acid and phosphorothioic acid esters
K015	Benzyl chloride, chlorobenzene, toluene, benzene, benzene	K037	Toluene, phosphorothioic acid and phosphorothioic acid esters
K016	Hexachlorobenzene, hexachlorobutadiene, carbon tetrachloride, hexachloroethane, perchloroethylene	K038	Phosgene, formaldehyde, phosphorothioic acid and phosphorothioic acid esters
K017	Epichlorohydrin, chloroethers (bischloromethyl ether and bis-(2-chloroethyl) ether), trichloropropane, dichloropropane	K039	Phosphorothioic acid and phosphorothioic acid esters
K018	1,2-dichloroethane, trichloroethylene, hexachlorobutadiene, hexachlorobenzene	K040	Phosgene, formaldehyde, phosphorothioic acid and phosphorothioic acid esters
K019	Ethylene, dichloride, 1,1,1-trichloroethane, 1,1,2-trichloroethane, tetrachloroethanes, 1,1,2,2-tetrachloroethane and 1,1,2,2-tetrachloroethanol, trichloroethylene, tetrachloroethylene, carbon tetrachloride, chloroform, vinyl chloride, vinylidene chloride	K041	Thiophene
		K042	Hexachlorobenzene, ortho-dichlorobenzene
		K043	2,4-dichlorophenol, 2,6-dichlorophenol, 2,4,6-trichlorophenol
		K044	N A
		K045	N A
		K046	Lead
		K047	N A
		K048	Hexavalent chromium, and
		K049	Hexavalent chromium, lead
		K050	Hexavalent chromium
		K051	Hexavalent chromium, lead
		K052	Lead
		K053	Cyanide, naphthalene, phenolic compounds, arsenic
		K054	Hexavalent chromium, lead, cadmium
		K055	Hexavalent chromium, lead
		K056	Hexavalent chromium, lead, cadmium
		K057	Mercury
		K058	Chloroform, carbon tetrachloride, hexachlorobenzene, trichloroethane, tetrachloroethylene, dichloroethylene, 1,1,2,2-tetrachloroethane
		K059	Arsenic, diphenylamine, neobenzene, phenylene, pyrene
		K060	Arsenic
		K061	Benzene, dichlorobenzene, trichlorobenzene, tetra-, penta-, hexachlorobenzene, hexachlorobutadiene, hexachloroethane, benzyl chloride
		K062	Lead, hexavalent chromium
		K063	Phenol, naphthalene
		K064	Phenol, anhydride, mesic anhydride
		K065	Phenol, anhydride

Environmental Protection Agency

Part 261, App. VIII

EPA Hazardous Waste No.	Hazardous constituents for which listed
K095	1,1,2-trichloroethane, 1,1,1,2-tetrachloroethane, 1,1,2,2-tetrachloroethane
K096	1,2-dichloroethane, 1,1,1-trichloroethane, 1,1,2-trichloroethane
K097	Chlordane, heptachlor
K098	Toxaphene
K099	2,4-dichlorophenol, 2,4,6-trichlorophenol
K100	Hexavalent chromium, lead, aluminum
K101	Arsenic
K102	Arsenic
K103	Arsine, arsine, phenylarsine, arsine
K104	Arsine, arsine, diphenylarsine, arsine, phenylarsine
K105	Benzene, monochlorobenzene, dichlorobenzene, 2,4,6-trichlorobenzene
K106	Mercury

N.A.—Waste is hazardous because it fails the test for the characteristic of ignitability, corrosivity, or reactivity.

[46 FR 4619, Jan. 16, 1981, as amended at 46 FR 27477, May 20, 1981; 49 FR 5312, Feb. 10, 1984; 50 FR 2000, Jan. 14, 1985]

Effective Date Note: At 50 FR 2000, Jan. 14, 1985, Part 261, App. VII was amended by adding the entries for P020 through P023, and P026 through P028, effective July 13, 1985.

APPENDIX VIII—HAZARDOUS
CONSTITUENTS

Acetonitrile (Ethanenitrile)
Acetophenone (Ethanone, 1-phenyl)
3-(alpha-Acetylbenzyl)-4-hydroxycoumarin and salts (Warfarin)
2-Acetylaminofluorene (Acetamide, N-(9H-fluoren-2-yl)-)
Acetyl chloride (Ethanoyl chloride)
1-Acetyl-2-thiourea (Acetamide, N-(aminothioxomethyl)-)
Acrolein (2-Propenal)
Acrylamide (2-Propenamide)
Acrylonitrile (2-Propenenitrile)
Aflatoxins
Aldrin (1,2,3,4,10,10-Hexachloro-1,4,4a,5,8,8a,8b-hexahydro-endo,exo-1,4:5,8-Dimethanonaphthalene)
Allyl alcohol (2-Propen-1-ol)
Aluminum phosphide
4-Aminobiphenyl (1,1'-Biphenyl)-4-amine
6-Amino-1,1a,2,8,8a,8b-hexahydro-8-(hydroxymethyl)-8a-methoxy-5-methylcarbamate azirino(2,3,3,4)pyrrolo(1,2-a)indole-4,7-dione, (ester) (Mitomycin C)
Azirino(2,3,3,4)pyrrolo(1,2-a)indole-4,7-dione, 6-amino-8-(aminocarbonyloxy)methyl-1,1a,2,8,8a,8b-hexahydro-8a,ethoxy-5-methyl-
5-Aminomethyl-3-isoxazolol-3(2H)-isoxazolone, 5-aminomethyl-4-Aminopyridine, 4-Pyridinamine
Amitrole (1H-1,2,4-Triazol-3-amine)

Aniline (Benzenamine)
Antimony and compounds, N.O.S.*
Aramite (Sulfurous acid, 2-chloroethyl-, 2-[4-(1,1-dimethylethyl)phenoxy]-1-methylethyl ester)
Arsenic and compounds, N.O.S.*
Arsenic acid (Orthoarsenic acid)
Arsenic pentoxide (Arsenic (V) oxide)
Arsenic trioxide (Arsenic (III) oxide)
Auramine (Benzenamine, 4,4'-carbonimidoylbis(N,N-Dimethyl-, monohydrochloride)
Azaserine (L-Serine, diazoacetate (ester))
Barium and compounds, N.O.S.*
Barium cyanide
Benz(c)acridine (3,4-Benzacridine)
Benz(a)anthracene (1,2-Benzanthracene)
Benzene (Cyclohexatriene)
Benzeneearsonic acid (Arsenic acid, phenyl-)
Benzene, dichloromethyl- (Benzal chloride)
Benzenethiol (Thiophenol)
Benzidine ((1,1'-Biphenyl)-4,4'-diamine)
Benzo(b)fluoranthene (2,3-Benzofluoranthene)
Benzo(j)fluoranthene (7,8-Benzofluoranthene)
Benzo(a)pyrene (3,4-Benzopyrene)
p-Benzquinone (1,4-Cyclohexadienedione)
Benzotrithloride (Benzene, trichloromethyl-)
Benzyl chloride (Benzene, (chloromethyl)-)
Beryllium and compounds, N.O.S.*
Bis(2-chloroethoxy)methane (Ethane, 1,1'-methylenebis(oxy)bis(2-chloro-))
Bis(2-chloroethyl) ether (Ethane, 1,1'-oxybis(2-chloro-))
N,N-Bis(2-chloroethyl)-2-naphthylamine (Chlornaphazine)
Bis(2-chloroisopropyl) ether (Propane, 2,2'-oxybis(2-chloro-))
Bis(chloromethyl) ether (Methane, oxybis(chloro-))
Bis(2-ethylhexyl) phthalate (1,2-Benzenedicarboxylic acid, bis(2-ethylhexyl) ester)
Bromoacetone (2-Propanone, 1-bromo-)
Bromomethane (Methyl bromide)
4-Bromophenyl phenyl ether (Benzene, 1-bromo-4-phenoxy-)
Brucine (Strychnidin-10-one, 2,3-dimethoxy-)
2-Butanone peroxide (Methyl ethyl ketone, peroxide)
Butyl benzyl phthalate (1,2-Benzenedicarboxylic acid, butyl phenylmethyl ester)
2-sec Butyl-4,6-dinitrophenol (DNBP)
Phenol, 2,4-dinitro-4-(1-methylpropyl)-
Cadmium and compounds, N.O.S.*
Calcium chromate (Chromic acid, calcium salt)
Calcium cyanide

* The abbreviation N.O.S. (not otherwise specified) signifies those members of the general class not specifically listed by name in this appendix.

- Carbon disulfide (Carbon bisulfide)
Carbon oxyfluoride (Carbonyl fluoride)
Chloral Acetaldehyde, trichloro-
Chlorambucil (Butanoic acid, 4-(bis(2-chloroethyl)amino)benzene-)
Chlordane (alpha and gamma isomers) (4,7-Methanoundan, 1,2,4,5,6,7,8,8-octachloro-3,4,7,7a-tetrahydro-) (alpha and gamma isomers)
Chlorinated benzenes, N.O.S.*
Chlorinated ethane, N.O.S.*
Chlorinated fluorocarbene, N.O.S.*
Chlorinated naphthalene, N.O.S.*
Chlorinated phenol, N.O.S.*
Chloroacetaldehyde (Acetaldehyde, chloro-)
Chloroalkyl ethers, N.O.S.*
p-Chloroaniline (Benzenamine, 4-chloro-)
Chlorobenzene (Benzene, chloro-)
Chlorobenzoate (Benzoic acid, 4-chloro-alpha-(4-chlorophenyl)-alpha-hydroxy-ethyl ester)
2-Chloro-1,3-butadiene (chloroprene)
p-Chloro-m-cresol (Phenol, 4-chloro-3-methyl)
1-Chloro-2,3-epoxypropane (Oxirane, 2-chloromethyl-)
2-Chloroethyl vinyl ether (Ethene, (2-chloroethoxy)-)
Chloroform (Methane, trichloro-)
Chloromethane (Methyl chloride)
Chloromethyl methyl ether (Methane, chloromethoxy-)
2-Chloronaphthalene (Naphthalene, beta-chloro-)
2-Chlorophenol (Phenol, o-chloro-)
1-(o-Chlorophenyl)thiourea (Thiourea, (2-chlorophenyl)-)
3-Chloropropene (allyl chloride)
3-Chloropropionitrile (Propanenitrile, 3-chloro-)
Chromium and compounds, N.O.S.*
Chrysene (1,2-Benzphenanthrene)
Citrus red No. 2 (2-Naphthol, 1-((2,5-dimethoxyphenyl)azo)-)
Coal tars
Copper cyanide
Creosote (Creosote, wood)
Cresols (Cresylic acid) (Phenol, methyl-)
Crotonaldehyde (2-Butenal)
Cyanides (soluble salts and complexes), N.O.S.*
Cyanogen (Ethanedinitrile)
Cyanogen bromide (Bromine cyanide)
Cyanogen chloride (Chlorine cyanide)
Cytasin (beta-D-Glucopyranoside, (methyl-ONN-azoxy)methyl-)
2-Cyclohexyl-4,6-dinitrophenol (Phenol, 2-cyclohexyl-4,6-dinitro-)
Cyclophosphamide (2H-1,3,2-Oxazaphosphorine, (bis(2-chloroethyl)amino)tetrahydro-2-oxide)
Daunomycin (5,12-Naphthacenedione, 85-cis)-6-acetyl-10-((3-amino-2,3,6-trideoxy)-alpha-L-xylohexopyranosyloxy)-7,8,9,10-tetrahydro-4,8,11-trihydroxy-1-methoxy-)
DDD (Dichlorodiphenyldichloroethane) (Ethane, 1,1-dichloro-2,2-bis(p-chlorophenyl)-)
DDE (Ethylene, 1,1-dichloro-2,2-bis(4-chlorophenyl)-)
DDT (Dichlorodiphenyltrichloroethane) (Ethane, 1,1,1-trichloro-2,2-bis(p-chlorophenyl)-)
Diallate (S-(2,3-dichloroallyl) diisopropylthiocarbamate)
Dibenz(a,h)acridine (1,2,5,8-Dibenzacridine)
Dibenz(a,j)acridine (1,2,7,8-Dibenzacridine)
Dibenz(a,h)anthracene (1,2,5,6-Dibenzanthracene)
TH-Dibenz(o,c,g)carbazole (3,4,5,6-Dibenzcarbazole)
Dibenzo(a,e)pyrene (1,2,4,5-Dibenzpyrene)
Dibenzo(a,h)pyrene (1,2,5,6-Dibenzpyrene)
Dibenzo(a,i)pyrene (1,2,7,8-Dibenzpyrene)
1,2-Dibromo-3-chloropropane (Propane, 1,2-dibromo-3-chloro-)
1,2-Dibromoethane (Ethylene dibromide)
Dibromomethane (Methylene bromide)
Di-n-butyl phthalate (1,2-Benzenedicarboxylic acid, dibutyl ester)
o-Dichlorobenzene (Benzene, 1,2-dichloro-)
m-Dichlorobenzene (Benzene, 1,3-dichloro-)
p-Dichlorobenzene (Benzene, 1,4-dichloro-)
Dichlorobenzene, N.O.S.* (Benzene, dichloro, N.O.S.*)
3,3-Dichlorobenzidine ((1,1-Biphenyl)-4,4'-diamine, 3,3'-dichloro-)
1,4-Dichloro-2-butene (2-Butene, 1,4-dichloro-)
Dichlorodifluoromethane (Methane, dichlorodifluoro-)
1,1-Dichloroethane (Ethylidene dichloride)
1,2-Dichloroethane (Ethylene dichloride)
trans-1,2-Dichloroethene (1,2-Dichloroethylene)
Dichloroethylene, N.O.S.* (Ethene, dichloro, N.O.S.*)
1,1-Dichloroethylene (Ethene, 1,1-dichloro-)
Dichloromethane (Methylene chloride)
2,4-Dichlorophenol (Phenol, 2,4-dichloro-)
2,6-Dichlorophenol (Phenol, 2,6-dichloro-)
2,4-Dichlorophenoxyacetic acid (2,4-D), salts and esters (Acetic acid, 2,4-dichlorophenoxy-, salts and esters)
Dichlorophenylarsine (Phenyl dichloroarsine)
Dichloropropane, N.O.S.* (Propane, dichloro, N.O.S.*)
1,2-Dichloropropane (Propylene dichloride)
Dichloropropanol, N.O.S.* (Propanol, dichloro, N.O.S.*)
Dichloropropene, N.O.S.* (Propene, dichloro, N.O.S.*)
1,3-Dichloropropene (1-Propene, 1,3-dichloro-)
Dieldrin (1,2,3,4,10,10-hexachloro-6,7-epoxy-1,4,4a,5,8,7,8,8a-octa-hydro-endo,exo-1,4,5,8-Dimethanonaphthalene)
1,2,3,4-Diepoxybutane (2,2'-Bioxirane)
Diethylarsine (Arsine, diethyl-)

- 1,1-Diethylhydrazine (Hydrazine, 1,1-diethyl)
 1,1-Diethyl 3-methyl ester of phosphorodithioic acid (Phosphorodithioic acid, O,O-diethyl 3-methyl ester)
 1,1-Diethylphosphoric acid, O-p-nitrophenyl ester (Phosphoric acid, diethyl p-nitrophenyl ester)
 Diethyl phthalate (1,2-Benzenedicarboxylic acid, diethyl ester)
 O,O-Diethyl O-2-pyrazinyl phosphorothioate (Phosphorothioic acid, O,O-diethyl O-pyrazinyl ester)
 Diethylstilbestrol (4,4'-Stilbenediol, alpha, alpha-diethyl, bis(dihydrogen phosphate, (E)-))
 Dihydroafrrole (Benzene, 1,2-methylene-dioxy-4-propyl-)
 3,4-Dihydroxy-alpha-(methylamino)methyl benzyl alcohol (1,2-Benzenediol, 4-(1-hydroxy-2-(methylamino)methyl)-)
 Diisopropylfluorophosphate (DPP) (Phosphorofluoric acid, bis(1-methylethyl) ester)
 Dimethoate (Phosphorodithioic acid, O,O-dimethyl S-(2-(methylamino)-2-oxoethyl) ester)
 3,3-Dimethoxybenzidine ((1,1'-Biphenyl)-4,4'-diamine, 3,3'-dimethoxy-)
 p-Dimethylaminoazobenzene (Benzenamine, N,N-dimethyl-4-(phenylazo)-)
 7,12-Dimethylbenz[alanthracene (1,2-Benzanthracene, 7,12-dimethyl-)
 3,3'-Dimethylbenzidine ((1,1'-Biphenyl)-4,4'-diamine, 3,3'-dimethyl-)
 Dimethylcarbamoyl chloride (Carbamoyl chloride, dimethyl-)
 1,1-Dimethylhydrazine (Hydrazine, 1,1-dimethyl-)
 1,2-Dimethylhydrazine (Hydrazine, 1,2-dimethyl-)
 3,3-Dimethyl-1-(methylthio)-2-butanone, O-((methylamino) carbonyl)oxime (Thiofanox)
 alpha, alpha-Dimethylphenethylamine (Eth-anamine, 1,1-dimethyl-2-phenyl-)
 2,4-Dimethylphenol (Phenol, 2,4-dimethyl-)
 Dimethyl phthalate (1,2-Benzenedicarboxylic acid, dimethyl ester)
 Dimethyl sulfate (Sulfuric acid, dimethyl ester)
 Dinitrobenzene, N.O.S.* (Benzene, dinitro, N.O.S.*)
 4,6-Dinitro-o-cresol and salts (Phenol, 2,4-dinitro-6-methyl-, and salts)
 2,4-Dinitrophenol (Phenol, 2,4-dinitro-)
 2,4-Dinitrotoluene (Benzene, 1-methyl-2,4-dinitro-)
 2,6-Dinitrotoluene (Benzene, 1-methyl-2,6-dinitro-)
 Di-n-octyl phthalate (1,2-Benzenedicarboxylic acid, dioctyl ester)
 1,4-Dioxane (1,4-Diethylene oxide)
 Diphenylamine (Benzenamine, N-phenyl-)
 1,2-Diphenylhydrazine (Hydrazine, 1,2-diphenyl-)
 Di-n-propylnitrosamine (N-Nitroso-di-n-propylamine)
 Disulfoton (O,O-diethyl S-(2-(ethylthioethyl) phosphorodithioate)
 2,4-Dithiobis(urea) (Thioumidodicarbonic diamide)
 Endosulfan (5-Norbornene, 2,3-dimethanol, 1,4,5,6,7,7-hexachloro-, cyclic sulfite)
 Endrin and metabolites (1,2,3,4,10,10-hexachloro-6,7-epoxy-1,4,4a,5,6,7,8,8a-octahydro-endo,endo-1,4:5,8-dimethanonaphthalene, and metabolites)
 Ethyl carbamate (Urethan) (Carbamic acid, ethyl ester)
 Ethyl cyanide (propanenitrile)
 Ethylenebis(dithiocarbamic acid, salts and esters) (1,2-Ethanedithiolbis(carbamodithioic acid, salts and esters)
 Ethylenimine (Aziridine)
 Ethylene oxide (Oxirane)
 Ethylenethiourea (2-Imidazolidinethione)
 Ethyl methacrylate (2-Propenoic acid, 2-methyl-, ethyl ester)
 Ethyl methanesulfonate (Methanesulfonic acid, ethyl ester)
 Fluoranthene (Benzo(j,k)fluorene)
 Fluorine
 2-Fluoroacetamide (Acetamide, 2-fluoro-)
 Fluoroacetic acid, sodium salt (Acetic acid, fluoro-, sodium salt)
 Formaldehyde (Methylene oxide)
 Formic acid (Methanoic acid)
 Glycidylaldehyde (1-Propanol-2,3-epoxy)
 Halomethane, M.C.S.*
 Heptachlor (4,7-Methano-1H-indene, 1,4,5,6,7,8,8-heptachloro-3a,4,7,7a-tetrahydro-)
 Heptachlor epoxide (alpha, beta, and gamma isomers) (4,7-Methano-1H-indene, 1,4,5,6,7,8,8-heptachloro-2,3-epoxy-3a,4,7,7-tetrahydro-, alpha, beta, and gamma isomers)
 Hexachlorobenzene (Benzene, hexachloro-)
 Hexachlorobutadiene (1,3-Butadiene, 1,1,2,3,4,4-hexachloro-)
 Hexachlorocyclohexane (all isomers) (Lindane and isomers)
 Hexachlorocyclopentadiene (1,3-Cyclopentadiene, 1,2,3,4,5,5-hexachloro-)
 Hexachlorodibenzo-p-dioxins
 Hexachlorodibenzofurans
 Hexachloroethane (Ethane, 1,1,1,2,2,2-hexachloro-)
 1,2,3,4,10,10-Hexachloro-1,4,4a,5,8,8a-hexahydro-1,4:5,8-endo,endo-dimethanonaphthalene (Hexachlorohexahydro-endo,endo-dimethanonaphthalene)
 Hexachlorophene (2,2-Methylenebis(3,4,6-trichlorophenol))
 Hexachloropropene (1-Propene, 1,1,2,3,3,3-hexachloro-)
 Hexaethyl tetraphosphate (Tetraphosphoric acid, hexaethyl ester)
 Hydrazine (Diamine)
 Hydrocyanic acid (Hydrogen cyanide)
 Hydrofluoric acid (Hydrogen fluoride)

- Hydrogen sulfide (Sulfur hydride)
 Hydroxydimethylarsine oxide (Cacodylic acid)
 Indeno[1,2,3-cd]pyrene (1,10-1,2-phenylene)pyrene)
 Iodomethane (Methyl iodide)
 Iron dextran (Ferric dextran)
 Isocyanic acid, methyl ester (Methyl isocyanate)
 Isobutyl alcohol (1-Propanol, 2-methyl-)
 Isoaifrole (Benzene, 1,2-methylenedioxy-4-allyl-)
 Kepone (Decachlorooctahydro-1,3,4-Methano-2H-cyclobuta[cd]pentalen-2-one)
 Lasiocarpine (2-Butenoic acid, 2-methyl-, 7-[(2,3-dihydroxy-2-(1-methoxyethyl)-3-methyl-1-oxobutoxy)methyl]-2,3,5,7a-tetrahydro-1H-pyrrolizin-1-yl ester)
 Lead and compounds, N.O.S.*
 Lead acetate (Acetic acid, lead salt)
 Lead phosphate (Phosphoric acid, lead salt)
 Lead subacetate (Lead, bisacetato-Oitetrahydroxytri-)
 Maleic anhydride (2,5-Purandione)
 Maleic hydrazide (1,2-Dihydro-3,6-pyridazin-edione)
 Malononitrile (Propanedinitrile)
 Melphalan (Alanine, 3-(p-bis-2-chloroethyl)aminophenyl-, L-)
 Mercury fulminate (Pulmonic acid, mercury salt)
 Mercury and compounds, N.O.S.*
 Methacrylonitrile (2-Propenenitrile, 2-methyl-)
 Methanethiol (Thiomethanol)
 Methapyrriene (Pyridine, 2-[(2-dimethylamino)ethyl]-2-phenylamino-)
 Metholmyl (Acetimidic acid, N-[(methylcarbamoyloxy)thio-, methyl ester)
 Methoxychlor (Ethane, 1,1,1-trichloro-2,2-bis(p-methoxyphenyl)-)
 2-Methylaziridine (1,2-Propylenimine)
 3-Methylcholanthrene (Benz[*a*]aceanthrylene, 1,2-dihydro-3-methyl-)
 Methyl chlorocarbonate (Carbonochloridic acid, methyl ester)
 4,4'-Methylenebis(2-chloroaniline) (Benzenamine, 4,4'-methylenebis-(2-chloro-))
 Methyl ethyl ketone (MEK) (2-Butanone)
 Methyl hydrazine (Hydrazine, methyl-)
 2-Methylactonitrile (Propanenitrile, 2-hydroxy-2-methyl-)
 Methyl methacrylate (2-Propenoic acid, 2-methyl-, methyl ester)
 Methyl methanesulfonate (Methanesulfonic acid, methyl ester)
 2-Methyl-2-(methylthio)propionaldehyde-o-methylcarbonyl oxime (Propanal, 2-methyl-2-(methylthio-, O-[(methylamino)carbonyl]oxime)
 N-Methyl-N-nitro-N-nitrosoguanidine (Guanidine, N-nitroso-N-methyl-N-nitro-)
 Methyl parathion (O,O-dimethyl O-(4-nitrophenyl) phosphorothioate)
 Methylthiouracil (4-1H-Pyrimidinone, 2,3-dihydro-6-methyl-2-thioxo-)
 Mustard gas (Sulfide, bis(2-chloroethyl)-)
 Naphthalene
 1,4-Naphthoquinone (1,4-Naphthalenedione)
 1-Naphthylamine (alpha-Naphthylamine)
 2-Naphthylamine (beta-Naphthylamine)
 1-Naphthyl-2-thiourea (Thiourea, 1-naphthyl-)
 Nickel and compounds, N.O.S.*
 Nickel carbonyl (Nickel tetracarbonyl)
 Nickel cyanide (Nickel (II) cyanide)
 Nicotine and salts Pyridine, 3-(1-methyl-2-pyrrolidinyl-, and salts)
 Nitric oxide (Nitrogen (II) oxide)
 p-Nitroaniline (Benzenamine, 4-nitro-)
 Nitrobenzene (Benzene, nitro-)
 Nitrogen dioxide (Nitrogen (IV) oxide)
 Nitrogen mustard and hydrochloride salt (Ethanamine, 2-chloro-, N-(2-chloroethyl)-N-methyl-, and hydrochloride salt)
 Nitrogen mustard N-Oxide and hydrochloride salt (Ethanamine, 2-chloro-, N-(2-chloroethyl)-N-methyl-, and hydrochloride salt)
 Nitroglycerine (1,2,3-Propanetriol, trinitrate)
 4-Nitrophenol (Phenol, 4-nitro-)
 4-Nitroquinoline-1-oxide (Quinoline, 4-nitro-1-oxide-)
 Nitrosamine, N.O.S.*
 N-Nitrosodi-n-butylamine (1-Butanamine, N-butyl-N-nitroso-)
 N-Nitrosodiethanolamine (Ethanol, 2,2-(nitrosoimino)bis-)
 N-Nitrosodiethylamine (Ethanamine, N-ethyl-N-nitroso-)
 N-Nitrosodimethylamine (Dimethylnitrosamine)
 N-Nitroso-N-ethylurea (Carbamide, N-ethyl-N-nitroso-)
 N-Nitrosomethylethylamine (Ethanamine, N-methyl-N-nitroso-)
 N-Nitroso-N-methylurea (Carbamide, N-methyl-N-nitroso-)
 N-Nitroso-N-methylurethane (Carbamic acid, methylnitroso-, ethyl ester)
 N-Nitrosomethylvinylamine (Ethanamine, N-methyl-N-nitroso-)
 N-Nitrosomorpholine (Morpholine, N-nitroso-)
 N-Nitrososomnicotine (Nicotine, N-nitroso-)
 N-Nitrosopiperidine (Pyridine, hexahydro-, N-nitroso-)
 Nitrosopyrrolidine (Pyrrole, tetrahydro-, N-nitroso-)
 N-Nitrososarcosine (Sarcosine, N-nitroso-)
 5-Nitro-o-toluidine (Benzenamine, 2-methyl-5-nitro-)
 Octamethylpyrophosphoramide (Diphosphoramide, octamethyl-)
 Osmium tetroxide (Osmium (VIII) oxide)
 7-Oxabicyclo[2,2,1]heptane-2,3-dicarboxylic acid (Endothal)

Environmental Protection Agency

Part 261, App. VIII

Paraldehyde (1,3,5-Trioxane, 2,4,6-trimethyl-)	2,3,7,8-Tetrachlorodibenzo-p-dioxin (TCDD) (Dibenzo-p-dioxin, 2,3,7,8-tetrachloro-)
Parathion (Phosphorothioic acid, O-diethyl O-(p-nitrophenyl) ester)	Tetrachlorodibenzo-p-dioxins
Pentachlorobenzene (Benzene, pentachloro-)	Tetrachlorodibenzofurans
Pentachlorodibenzo-p-dioxins	Tetrachloroethane, N.O.S.* (Ethane, tetrachloro-, N.O.S.*)
Pentachlorodibenzofurans	1,1,1,2-Tetrachloroethane (Ethane, 1,1,1,2-tetrachloro-)
Pentachloroethane (Ethane, pentachloro-)	1,1,2,2-Tetrachloroethane (Ethane, 1,1,2,2-tetrachloro-)
Pentachloronitrobenzene (PCNB) (Benzene, pentachloronitro-)	Tetrachloroethane (Ethane, 1,1,2,2-tetrachloro-)
Pentachlorophenol (Phenol, pentachloro-)	Tetrachloromethane (Carbon tetrachloride)
Phenacetin (Acetamide, N-(4-ethoxyphenyl)-)	2,3,4,6-Tetrachlorophenol (Phenol, 2,3,4,6-tetrachloro-)
Phenol (Benzene, hydroxy-)	Tetraethyldithiopyrophosphate (Dithiopyrophosphoric acid, tetraethyl-ester)
Phenylenediamine (Benzenediamine)	Tetraethyl lead (Plumbane, tetraethyl-)
Phenylmercury acetate (Mercury, acetato-phenyl-)	Tetraethylpyrophosphate (Pyrophosphoric acid, tetraethyl ester)
N-Phenylthiourea (Thiourea, phenyl-)	Tetranitromethane (Methane, tetranitro-)
Phosgene (Carbonyl chloride)	Thallium and compounds, N.O.S.*
Phosphine (Hydrogen phosphide)	Thallic oxide (Thallium (III) oxide)
Phosphorodithioic acid, O,O-diethyl S-[(ethylthio)methyl] ester (Phorate)	Thallium (I) acetate (Acetic acid, thallium (I) salt)
Phosphorothioic acid, O,O-dimethyl O-(p-(dimethylamino)sulfonyl)phenyl ester (Pamphur)	Thallium (I) carbonate (Carbonic acid, dithallium (I) salt)
Phthalic acid esters, N.O.S.* (Benzene, 1,2-dicarboxylic acid, esters, N.O.S.*)	Thallium (I) chloride
Phthalic anhydride (1,2-Benzenedicarboxylic acid anhydride)	Thallium (I) nitrate (Nitric acid, thallium (I) salt)
2-Picoline (Pyridine, 2-methyl-)	Thallium selenite
Polychlorinated biphenyl, N.O.S.*	Thallium (I) sulfate (Sulfuric acid, thallium (I) salt)
Potassium cyanide	Thioacetamide (Ethanethioamide)
Potassium silver cyanide (Argentate(1-), dicyano-, potassium)	Thiosemicarbazide (Hydrazinecarbothioamide)
Pronamide (3,5-Dichloro-N-(1,1-dimethyl-2-propynyl)benzamide)	Thiourea (Carbamide thio-)
1,3-Propane sultone (1,2-Oxathiolane, 2,2-dioxide)	Thiuram (Bis(dimethylthiocarbonyl) disulfide)
n-Propylamine (1-Propanamine)	Toluene (Benzene, methyl-)
Propylthiouracil (Undecamethylenediamine, N,N'-bis(2-chlorobenzyl)-, dihydrochloride)	Toluenediamine (Diaminotoluene)
2-Propyn-1-ol (Propargyl alcohol)	o-Toluidine hydrochloride (Benzenamine, 2-methyl-, hydrochloride)
Pyridine	Tolylene diisocyanate (Benzene, 1,3-diisocyanatomethyl-)
Reserpine (Yohimban-16-carboxylic acid, 11,17-dimethoxy-18-((3,4,5-trimethoxybenzoyloxy)-, methyl ester)	Toxaphene (Camphene, octachloro-)
Resorcinol (1,3-Benzenediol)	Tribromomethane (Bromoform)
Saccharin and salts (1,2-Benzisothiazolin-3-one, 1,1-dioxide, and salts)	1,2,4-Trichlorobenzene (Benzene, 1,2,4-trichloro-)
Safrole (Benzene, 1,2-methylenedioxy-4-allyl-)	1,1,1-Trichloroethane (Methyl chloroform)
Selenious acid (Selenium dioxide)	1,1,2-Trichloroethane (Ethane, 1,1,2-trichloro-)
Selenium and compounds, N.O.S.*	Trichloroethene (Trichloroethylene)
Selenium sulfide (Sulfur selenide)	Trichloromethanethiol (Methanethiol, trichloro-)
Selenourea (Carbamimidoseleonic acid)	Trichloromono-fluoromethane (Methane, trichloro-fluoro-)
Silver and compounds, N.O.S.*	2,4,5-Trichlorophenol (Phenol, 2,4,5-trichloro-)
Silver cyanide	2,4,6-Trichlorophenol (Phenol, 2,4,6-trichloro-)
Sodium cyanide	2,4,5-Trichlorophenoxyacetic acid (2,4,5-T) (Acetic acid, 2,4,5-trichlorophenoxy-)
Streptozotocin (D-Glucopyranose, 2-deoxy-2-(3-methyl-3-nitrosoureido)-)	2,4,5-Trichlorophenoxypropionic acid (2,4,5-TP) (Silvex) (Propionic acid, 2-(2,4,5-trichlorophenoxy)-)
Strontium sulfide	
Strychnine and salts (Strychnidin-10-one, and salts)	
1,2,4,5-Tetrachlorobenzene (Benzene, 1,2,4,5-tetrachloro-)	

Part 261, App. IX

Trichloropropane, N.O.S.* (Propane, trichloro-, N.O.S.*)
 1,2,3-Trichloropropane (Propane, 1,2,3-trichloro-)
 O,O,O-Triethyl phosphorothioate (Phosphorothioic acid, O,O,O-triethyl ester)
 sym-Trinitrobenzene (Benzene, 1,3,5-trinitro-)
 Tri(1-aziridinyl) phosphine sulfide (Phosphine sulfide, tri(1-aziridinyl-))
 Tri(2,3-dibromopropyl) phosphate (1-Propanol, 2,3-dibromo-, phosphate)
 Trypan blue (2,7-Naphthalenedisulfonic acid, 3,3'-((3,3'-dimethyl(1,1'-biphenyl)-4,4'-diyl)bis(azo))bis(5-amino-4-hydroxy-, tetrasodium salt)
 Uracil mustard (Uracil 5-(bis(2-chloroethyl)amino)-)
 Vanadic acid, ammonium salt (ammonium vanadate)
 Vanadium pentoxide (Vanadium (V) oxide)
 Vinyl chloride (Ethene, chloro-)
 Zinc cyanide
 Zinc phosphide

[46 FR 27477, May 20, 1981, 46 FR 29708, June 3, 1981, as amended at 49 FR 5312, Feb. 10, 1984, 50 FR 2000, Jan. 14, 1985]

EFFECTIVE DATE NOTE: At 50 FR 2000, Jan. 14, 1985 Part 261, App. VIII was amended by adding the entries for Hexachlorodibenzo-p-dioxins, Hexachlorodibenzofurans, Pentachlorodibenzo-p-dioxins, Pentachlorodibenzofurans, Tetrachlorodibenzo-p-dioxins, and Tetrachlorodibenzofurans, effective July 15, 1985.

APPENDIX IX—WASTES EXCLUDED UNDER §§ 260.20 AND 260.22

TABLE 1—WASTES EXCLUDED FROM NON-SPECIFIC SOURCES

Facility	Address	Waste description
Ray Free, Inc.	Stoney Point, NY	Biological sludge, septic sludge and other green sludge generated after September 21, 1984, which contain EPA hazardous waste nos. F003 and F005 as well as that disposed of in a holdingagoon as of September 21, 1984.
Metroposten Sewer District of Greater Cincinnati	Cincinnati, OH	Slaked bottom ash sludge approximately 25,000 cubic yards contained in the bottom aagoon on September 21, 1984, which contains EPA hazardous wastes nos. F001, F002, F003, F004 and F005.

40 CFR Ch. I (7-1-85 Edition)

TABLE 2—WASTES EXCLUDED FROM SPECIFIC SOURCES

Facility	Address	Waste description
Reserved		

TABLE 3—WASTES EXCLUDED FROM COMMERCIAL CHEMICAL PRODUCTS, OFF-SPECIFICATION SPECIES, CONTAINER RESIDUES, AND SOIL RESIDUES THEREOF

Facility	Address	Waste description
Union Carbide Corp.	Yaf, LA	Contaminated soil approximately 11,000 cubic yards which contains acetone in concentrations of less than 3 ppm.

[49 FR 37070, Sept. 21, 1984]

APPENDIX X—METHOD OF ANALYSIS FOR CHLORINATED DIBENZO-P-DIOXINS AND DIBENZOFURANS

Method 8280

1. Scope and Application

This method is appropriate for the analysis of tetra-, penta-, and hexachlorinated dibenzo-p-dioxins and dibenzofurans.

Analytical protocol for determination of TCDDs in phenolic chemical wastes and soil samples obtained from the proximity of chemical dumps. T.O. Tierman and M. Taylor, Brehm Laboratory, Wright State University, Dayton, OH 45435.

Analytical protocol for determination of chlorinated dibenzo-p-dioxins and chlorinated dibenzofurans in river water. T.O. Tierman and M. Taylor, Brehm Laboratory, Wright State University, Dayton, OH 45435.

In general, the techniques that should be used to handle these materials are those which are followed for radioactive or infectious laboratory materials. Assistance in evaluating laboratory practices may be obtained from industrial hygienists and persons specializing in safe laboratory practices. Typical infectious waste incinerators are probably not satisfactory devices for disposal of materials highly contaminated with CDDs or CDFs. Safety instructions are outlined in EPA Test Method 813.40.

See also 1) Program for monitoring potential contamination in the laboratory following the handling and analyses of chlorinated dibenzo-p-dioxins and dibenzofurans by P. D. Hileman et al., in Human and En-

1.1 This method measures the concentration of chlorinated dibenzo-p-dioxins and chlorinated dibenzofurans in chemical wastes including still bottoms, filter aids, sludges, spent carbon, and reactor residues, and in soils.

1.2 The sensitivity of this method is dependent upon the level of interferences.

1.3 This method is recommended for use only by analysts experienced with residue analysis and skilled in mass spectral analytical techniques.

1.4 Because of the extreme toxicity of these compounds, the analyst must take necessary precautions to prevent exposure to himself, or to others, of materials known or believed to contain CDDs or CDFs.

2. Summary of the Method

2.1 This method is an analytical extraction cleanup procedure, and capillary column gas chromatograph-low resolution mass spectrometry method, using capillary column GC/MS conditions and internal standard techniques, which allow for the measurement of PCDDs and PCDFs in the extract.

2.2 If interferences are encountered, the method provides selected general purpose cleanup procedures to aid the analyst in their elimination.

3. Interferences

3.1 Solvents, reagents, glassware, and other sample processing hardware may yield discrete artifacts and/or elevated baselines causing misinterpretation of gas chromatograms. All of these materials must be demonstrated to be free from interferences under the conditions of the analysis by running method blanks. Specific selection of reagents and purification of solvents by distillation in all-glass systems may be required.

3.2 Interferences co-extracted from the samples will vary considerably from source to source, depending upon the diversity of the industry being sampled. PCDD is often associated with other interfering chlorinated compounds such as PCBs which may be at concentrations several orders of magnitude higher than that of PCDD. While general cleanup techniques are provided as part of this method, unique samples may require additional cleanup approaches to achieve the sensitivity stated in Table 1.

3.3 The other isomers of tetrachlorodibenzo-p-dioxin may interfere with the measurement of 2,3,7,8-TCDD. Capillary column gas chromatography is required to resolve

those isomers that yield virtually identical mass fragmentation patterns.

4. Apparatus and Materials

4.1. Sampling equipment for discrete or composite sampling.

4.1.1. Grab sample bottle—amber glass, 1-liter or 1-quart volume. French or Boston Round design is recommended. The container must be washed and solvent rinsed before use to minimize interferences.

4.1.2. Bottle caps—threaded to screw on to the sample bottles. Caps must be lined with Teflon. Solvent washed foil, used with the shiny side towards the sample, may be substituted for the Teflon if sample is not corrosive.

4.1.3. Compositing equipment—automatic or manual compositing system. No tygon or rubber tubing may be used, and the system must incorporate glass sample containers for the collection of a minimum of 250 ml. Sample containers must be kept refrigerated after sampling.

4.2. Water bath—heated, with concentric ring cover, capable of temperature control ($\pm 2^\circ\text{C}$). The bath should be used in a hood.

4.3. Gas chromatograph/mass spectrometer data system.

4.3.1. Gas chromatograph: An analytical system with a temperature-programmable gas chromatograph and all required accessories including syringes, analytical columns, and gases.

4.3.2. Column: SP-2250 coated on a 30 m long $\times$ 0.25 mm I.D. glass column (Supelco No. 2-3714 or equivalent). Glass capillary column conditions: Helium carrier gas at 30 cm/sec linear velocity run splitless. Column temperature is 210°C .

4.3.3. Mass spectrometer: Capable of scanning from 35 to 450 amu every 1 sec or less, utilizing 70 volts (nominal) electron energy in the electron impact ionization mode and producing a mass spectrum which meets all the criteria in Table 2 when 50 ng of decafluorotriphenyl phosphine (DFTPP) is injected through the GC inlet. The system must also be capable of selected ion monitoring (SIM) for at least 4 ions simultaneously, with a cycle time of 1 sec or less. Minimum integration time for SIM is 100 ms. Selected ion monitoring is verified by injecting 0.15 ng of TCDD C_{17} to give a minimum signal to noise ratio of 5 to 1 at mass 328.

4.3.4. GC/MS interface: Any GC to MS interface that gives acceptable calibration points at 50 ng per injection for each compound of interest and achieves acceptable tuning performance criteria (see Sections 6.1-6.3) may be used. GC to MS interfaces constructed of all glass or glass lined materials are recommended. Glass can be deactivated by silanizing with dichlorodimethylsilane. The interface must be capable of

Environmental Risks of Chlorinated Dioxins and Related Compounds, R.E. Tucker, et al., eds., Plenum Publishing Corp., 1983. 2) Safety procedures outlined in EPA Method 813, Federal Register volume 44, No. 233, December 3, 1979.

transporting at least 10 ng of the components of interest from the GC to the MS.

4.3.5 Data system: A computer system must be interfaced to the mass spectrometer. The system must allow the continuous acquisition and storage on machine-readable media of all mass spectra obtained throughout the duration of the chromatographic program. The computer must have software that can search any GC/MS data file for ions of a specific mass and that can plot such ion abundances versus time or scan number. This type of plot is defined as an Extracted Ion Current Profile (EICP). Software must also be able to integrate the abundance, in any EICP, between specified time or scan number limits.

4.4 Pipettes-Disposable, Pasteur, 150 mm long x 5 mm ID (Fisher Scientific Co., No. 13-878-6A or equivalent).

4.5 Flint glass bottle (Teflon-lined screw cap).

4.6 Reacti-vial (silanized) (Pierce Chemical Co.).

5. Reagents

5.1 Potassium hydroxide (ACS), 2% in distilled water.

5.2 Sulfuric acid (ACS), concentrated.

5.3 Methylene chloride, hexane, benzene, petroleum ether, methanol, tetradecane-pesticide quality or equivalent.

5.4 Prepare stock standard solutions of TCDD and ¹²⁵I-TCDD (molecular weight 328) in a glove box. The stock solutions are stored in a glovebox, and checked frequently for signs of degradation or evaporation, especially just prior to the preparation of working standards.

5.5 Alumina-basic, Woelm; 80/200 mesh. Before use activate overnight at 600°C, cool to room temperature in a desiccator.

5.6 Prepurified nitrogen gas

6.0 Calibration

6.1 Before using any cleanup procedure, the analyst must process a series of calibration standards through the procedure to validate elution patterns and the absence of interferences from reagents.

6.2 Prepare GC/MS calibration standards for the internal standard technique that will allow for measurement of relative response factors of at least three CDD/¹²⁵I-CDD ratios. Thus, for TCDDs, at least three TCDD/¹²⁵I-TCDD and TCDF/¹²⁵I-TCDF must be determined.⁴ The ¹²⁵I-

TCDD/¹²⁵I concentration in the standard should be fixed and selected to yield a reproducible response at the most sensitive setting of the mass spectrometer. Response factors for PCDD and HxCDD may be determined by measuring the response of the tetrachloro-labelled compounds relative to that of the unlabelled 1,2,3,4- or 2,3,7,8-TCDD, 1,2,3,4,7-PCDD or 1,2,3,4,7,8-HxCDD, which are commercially available.⁴

6.3 Assemble the necessary GC/MS apparatus and establish operating parameters equivalent to those indicated in Section 11.1 of this method. Calibrate the GC/MS system according to Eichelberger, et al. (1975) by the use of decafluorotriphenyl phosphine (DFTPP). By injecting calibration standards, establish the response factors for CDDs vs. ¹²⁵I-TCDD, and for CDFs vs. ¹²⁵I-TCDF. The detection limit provided in Table 1 should be verified by injecting .015 ng of ¹²⁵I-TCDD which should give a minimum signal to noise ratio of 5 to 1 at mass 328.

7. Quality Control

7.1 Before processing any samples, the analyst should demonstrate through the analysis of a distilled water method blank, that all glassware and reagents are interference-free. Each time a set of samples is extracted, or there is a change in reagents, a method blank should be processed as a safeguard against laboratory contamination.

7.2 Standard quality assurance practices must be used with this method. Field replicates must be collected to measure the precision of the sampling technique. Laboratory replicates must be analyzed to establish the precision of the analysis. Portified samples must be analyzed to establish the accuracy of the analysis.

8. Sample Collection, Preservation, and Handling

8.1 Grab and composite samples must be collected in glass containers. Conventional sampling practices should be followed, except that the bottle must not be prewashed with sample before collection. Composite samples should be collected in glass containers in accordance with the requirements of the RCRA program. Sampling equipment must be free of tygon and other potential sources of contamination.

8.2 The samples must be iced or refrigerated from the time of collection until ex-

⁴ ¹²⁵I-labelled 2,3,7,8-TCDD and 2,3,7,8-TCDF are available from K.O.R. Isotopes, and Cambridge Isotopes, Inc., Cambridge, MA. Proper standardization requires the use of a specific labelled isomer for each congener to be determined. However, the only labelled isomers readily available are ¹²⁵I-2,3,7,8-TCDD and ¹²⁵I-2,3,7,8-TCDF. This method therefore uses these isomers as surrogates for the CDDs and CDFs. When

other labelled CDDs and CDFs are available, their use will be required.

⁵ This procedure is adopted because standards are not available for most of the CDDs and CDFs, and assumes that all the congeners will show the same response as the unlabelled congener used as a standard. Although this assumption may not be true in all cases, the error will be small.

traction. Chemical preservatives should not be used in the field unless more than 24 hours will elapse before delivery to the laboratory. If an aqueous sample is to be analyzed and the sample will not be extracted within 48 hours of collection, the sample should be adjusted to a pH range of 6.0-8.0 with sodium hydroxide or sulfuric acid.

8.3 All samples must be extracted within 7 days and completely analyzed within 30 days of collection.

9. Extraction and Cleanup Procedures

9.1 Use an aliquot of 1-10 g sample of the chemical waste or soil to be analyzed. Soils should be dried using a stream of prepurified nitrogen and pulverized in a ball-mill or similar device. Perform this operation in a clear area with proper hood space. Transfer the sample to a tared 125 ml flint glass bottle (Teflon-lined screw cap) and determine the weight of the sample. Add an appropriate quantity of ¹⁴C-labelled 2,3,7,8-TCDD (adjust the quantity according to the required minimum detectable concentration), which is employed as an internal standard.

9.2 Extraction

9.2.1 Extract chemical waste samples by adding 10 ml methanol, 40 ml petroleum ether, 50 ml doubly distilled water, and then shaking the mixture for 2 minutes. Tars should be completely dissolved in any of the recommended neat solvents. Activated carbon samples must be extracted with benzene using method 3540 in SW-846 (Test Methods for Evaluating Solid Waste—Physical/Chemical Methods, available from G.P.O. Stock #055-022-81001-2). Quantitatively transfer the organic extract or dissolved sample to a clean 250 ml flint glass bottle (Teflon lined screw cap), add 50 ml doubly distilled water and shake for 2 minutes. Discard the aqueous layer and proceed with Step 9.3.

9.2.2 Extract soil samples by adding 40 ml of petroleum ether to the sample, and then shaking for 20 minutes. Quantitatively transfer the organic extract to a clean 250 ml flint glass bottle (Teflon-lined screw cap), add 50 ml doubly distilled water and shake for 2 minutes. Discard the aqueous layer and proceed with Step 9.3.

9.3 Wash the organic layer with 50 ml of 20% aqueous potassium hydroxide by shaking for 10 minutes and then remove and discard the aqueous layer.

9.4 Wash the organic layer with 50 ml of doubly distilled water by shaking for 2 minutes, and discard the aqueous layer.

9.5 Cautiously add 50 ml concentrated sulfuric acid and shake for 10 minutes. Allow the mixture to stand until layers separate (approximately 10 minutes), and remove and discard the acid layer. Repeat acid washing until no color is visible in the acid layer.

9.6 Add 50 ml of doubly distilled water to the organic extract and shake for 2 minutes. Remove and discard the aqueous layer and dry the organic layer by adding 10g of anhydrous sodium sulfate.

9.7 Concentrate the extract to incipient dryness by heating in a 55° C water bath and simultaneously flowing a stream of prepurified nitrogen over the extract. Quantitatively transfer the residue to an alumina microcolumn fabricated as follows:

9.7.1 Cut off the top section of a 1" disposable Pyrex pipette at the 4.0 ml mark and insert a plug of silanized glass wool into the tip of the lower portion of the pipette.

9.7.2 Add 2.8g of Woelm basic alumina (previously activated at 600° C overnight and then cooled to room temperature in a desiccator just prior to use).

9.7.3 Transfer sample extract with a small volume of methylene chloride.

9.8 Elute the microcolumn with 10 ml of 3% methylene chloride-in-hexane followed by 15 ml of 20% methylene chloride-in-hexane and discard these effluents. Elute the column with 15 ml of 50% methylene chloride-in-hexane and concentrate this effluent (55° C water bath, stream of prepurified nitrogen) to about 0.3-0.5 ml.

9.9 Quantitatively transfer the residue (using methylene chloride to rinse the container) to a silanized Reacti-Vial (Pierce Chemical Co.). Evaporate, using a stream of prepurified nitrogen, almost to dryness, rinse the walls of the vessel with approximately 0.5 ml methylene chloride, evaporate just to dryness, and tightly cap the vial. Store the vial at 5° C until analysis, at which time the sample is reconstituted by the addition of tridecane.

9.10 Approximately 1 hour before GC-MS (HRGC-LRMS) analysis, dilute the residue in the micro-reaction vessel with an appropriate quantity of tridecane. Gently swirl the tridecane on the lower portion of the vessel to ensure dissolution of the CDDs and CDFs. Analyze a sample by GC/EC to provide insight into the complexity of the problem, and to determine the manner in which the mass spectrometer should be used. Inject an appropriate aliquot of the sample into the GC-MS instrument, using a syringe.

9.11 If, upon preliminary GC-MS analysis, the sample appears to contain interfering substances which obscure the analyses for CDDs and CDFs, high performance liquid chromatographic (HPLC) cleanup of the extract is accomplished, prior to further GC-MS analysis.

10. HPLC Cleanup Procedure¹

¹ For cleanup see also method #8320 or #8330, SW-846, Test Methods for Evaluating Solid Waste, Physical Chemical Methods (1982).

10.1 Place approximately 2 ml of hexane in a 50 ml flint glass sample bottle fitted with a Teflon-lined cap.

10.2 At the appropriate retention time, position sample bottle to collect the required fraction.

10.3 Add 2 ml of 5% (w/v) sodium carbonate to the sample fraction collected and shake for one minute.

10.4 Quantitatively remove the hexane layer (top layer) and transfer to a micro-reaction vessel.

10.5 Concentrate the fraction to dryness and retain for further analysis.

11. GC/MS Analysis

11.1 The following column conditions are recommended: Glass capillary column conditions: SP-2250 coated on a 30 m long x 0.25 mm I.D. glass column (Supelco No. 2-3714, or equivalent) with helium carrier gas at 30 cm/sec linear velocity, run splitless. Column temperature is 210°C. Under these conditions the retention time for TCDDs is about 9.5 minutes. Calibrate the system daily with a minimum, three injections of standard mixtures.

11.2 Calculate response factors for standards relative to ¹²Cl-TCDD/F (see Section 12).

11.3 Analyze samples with selected ion monitoring of at least two ions from Table 3. Proof of the presence of CDD or CDF exists if the following conditions are met:

11.3.1 The retention time of the peak in the sample must match that in the standard, within the performance specifications of the analytical system.

11.3.2 The ratio of ions must agree within 10% with that of the standard.

11.3.3 The retention time of the peak maximum for the ions of interest must exactly match that of the peak.

11.4 Quantitate the CDD and CDF peaks from the response relative to the ¹²Cl-TCDD/F internal standards. Recovery of the internal standard should be greater than 50 percent.

11.5 If a response is obtained for the appropriate set of ions, but is outside the expected ratio, a co-eluting impurity may be suspected. In this case, another set of ions characteristic of the CDD/CDF molecules should be analyzed. For TCDD a good choice of ions is m/e 257 and m/e 259. For TCDF a good choice of ions is m/e 241 and 243. These ions are useful in characterizing the molecular structure to TCDD or TCDF. For analysis of TCDD good analytical technique would require using all four ions, m/e 257, 320, 322, and 328, to verify detection and signal to noise ratio of 5 to 1. Suspected impurities such as DDE, DDD, or PCB residues can be confirmed by checking for their major fragments. These materials can be removed by the cleanup columns. Failure to meet criteria should be explained in the report, or the sample reanalyzed.

11.6 If broad background interference restricts the sensitivity of the GC/MS analysis, the analyst should employ cleanup procedures and reanalyze by GC/MS. See section 10.0.

11.7 In those circumstances where these procedures do not yield a definitive conclusion, the use of high resolution mass spectrometry is suggested.

12. Calculations

12.1 Determine the concentration of individual compounds according to the formula:

$$\text{Concentration, } \mu\text{g/gm} = \frac{A \times A_i}{G \times A_s \times R_i}$$

where:

A = μg of internal standard added to the sample *

G = gm of sample extracted

A_i = area of characteristic ion of the compound being quantified.

A_s = area of characteristic ion of the internal standard

R_i = response factor *

*The proper amount of standard to be used is determined from the calibration curve (See Section 6.0).

*If standards for PCDDs/Fs and HxCDDs/Fs are not available, response factors for ions derived from these congeners are calculated relative to ¹²Cl-TCDD/F. The

Response factors are calculated using data obtained from the analysis of standards according to the formula:

analyst may use response factors for 1,2,3,4- or 2,3,7,8-TCDD, 1,2,3,4,7-PeCDD, or 1,2,3,4,7,8-HxCDD for quantitation of TCDDs/Fs, PeCDDs/Fs and HxCDDs/Fs, respectively. Implicit in this requirement is the assumption that the same response is obtained from PCDDs/Fs containing the same numbers of chlorine atoms.

Environmental Protection Agency

Part 261, App. X

$$Rf = \frac{A_s \times C_u}{A_u \times C_s}$$

where:

C_u = concentration of the internal standard
 C_s = concentration of the standard compound

12.2 Report results in micrograms per gram without correction for recovery data. When duplicate and spiked samples are analyzed, all data obtained should be reported.

12.3 Accuracy and Precision. No data are available at this time.

TABLE 1—GAS CHROMATOGRAPHY OF TCDD

Column	Retention time (min.)	Detection limit ($\mu\text{g/kg}$) ¹
Glass capillary	9.5	0.003

¹ Detection limit for liquid samples is 0.003 $\mu\text{g/l}$. This is calculated from the minimum detectable GC response being

equal to five times the GC background noise assuming a 1 ml effective final volume of the 1 liter sample extract, and a GC injection of 5 microliters. Detection levels apply to both electron capture and GC/MS detection. For further details see 44 FR 69526 (December 3, 1979).

TABLE 2—DFTPP KEY IONS AND ION ABUNDANCE CRITERIA¹

Mass	Ion abundance criteria
51	30-60% of mass 198
69	Less than 2% of mass 69
70	Less than 2% of mass 69
127	40-60% of mass 198
197	Less than 1% of mass 198
198	Base peak, 100% relative abundance
199	5-8% of mass 198
275	10-30% of mass 198
365	Greater than 1% of mass 198
441	Present but less than mass 443
442	Greater than 40% of mass 198
443	17-23% of mass 442

¹ J. W. Eichelberger, L.E. Hama, and W.L. Budde 1975. Reference compound to calibrate ion abundance measurement in gas chromatography-mass spectrometry. Analytical Chemistry 47:995.

TABLE 3—LIST OF ACCURATE MASSES MONITORED USING GC SELECTED-ION MONITORING, LOW RESOLUTION, MASS SPECTROMETRY FOR SIMULTANEOUS DETERMINATION OF TETRA-, PENTA-, AND HEXACHLORINATED DIBENZO-p-DIOXINS AND DIBENZOFURANS

Class of chlorinated dibenzodioxin or dibenzofuran	Number of chlorine substituents (x)	Monitored m/z for dibenzodioxins $C_{12}H_{6-x}Cl_x$	Monitored m/z for dibenzofurans $C_{12}H_{4-x}OCl_x$	Approximate theoretical ratio expected on basis of isotopic abundance
Tetra	4	¹ 319 897 ² 321 894 ³ 327 885 ⁴ 256 933	¹ 303 902 ² 305 903 ³ 311 894	0.74 1.00 0.21
Penta	5	¹ 353 858 ² 355 855	¹ 337 863 ² 339 860	0.20 0.57
Hexa	6	369 816 381 813	373 821 375 818	1.00 0.67

¹ Molecular ion peak

² Cl_{37} -labelled standard peaks

³ Ions which can be monitored in TCDD analyses for confirmation purposes

(50 FR 2001, Jan. 14, 1985)

EFFECTIVE DATE NOTE: At 50 FR 2001, Jan. 14, 1985, Part 261, App. X was added, effective July 15, 1985.

PART 262—STANDARDS APPLICABLE TO GENERATORS OF HAZARDOUS WASTE

Subpart A—General

Sec.

- 262.10 Purpose, scope, and applicability.
 262.11 Hazardous waste determination.
 262.12 EPA identification numbers.

APPENDIX E

ANALYTICAL METHODS

- EPA Contract Laboratory Protocol for GC/MS Analysis
of Purgeable Organics in Water, Soils, and Sediments
- EPA Protocol for the Analysis of Volatile Principle
Organic Hazardous Constituents Using VOST
- National Institute for Occupational Safety
and Health Method
No. P & CAM 127
- Standard Method 209 G

WESTON

EPA CONTRACT LABORATORY PROTOCOL FOR GC/MS ANALYSIS
PURGEABLE ORGANICS IN WATER, SOILS, AND SEDIMENTS

6060A

1. GC/MS Analysis of Purgeable Organics

1.1 Summary of Methods

1.1.1 Water samples

An inert gas is bubbled through a 5 mL sample contained in a specifically designed purging chamber at ambient temperature. The purgeables are efficiently transferred from the aqueous phase to the vapor phase. The vapor is swept through a sorbent column where the purgeables are trapped. After purging is completed, the sorbent column is heated and backflushed with the inert gas to desorb the purgeables onto a gas chromatographic column. The gas chromatograph is temperature programmed to separate the purgeables which are then detected with a mass spectrometer.

An aliquot of the sample is diluted with reagent water when dilution is necessary. A 5 mL aliquot of the dilution is taken for purging.

1.1.2 Sediment/Soil Samples

1.1.2.1 Low Level. An inert gas is bubbled through a mixture of a 5 gm sample and reagent water contained in a suggested specially designed purging chamber (illustrated on page D-95) at elevated temperatures. The purgeables are efficiently transferred from the aqueous phase to the vapor phase. The vapor is swept through a sorbent column where the purgeables are trapped. After purging is completed, the sorbent column is heated and backflushed with the inert gas to desorb the purgeables onto a gas chromatographic column. The gas chromatograph is temperature programmed to separate the purgeables which are then detected with a mass spectrometer.

1.1.2.2 Medium Level. A measured amount of soil is extracted with methanol. A portion of the methanol extract is diluted to 5 ml with reagent water. An inert gas is bubbled through this solution in a specifically designed purging chamber at ambient temperature. The purgeables are effectively transferred from the aqueous phase to the vapor phase. The vapor is swept through a sorbent column where the purgeables are trapped. After purging is completed, the sorbent column is heated and backflushed with the inert gas to desorb the purgeables onto a gas chromatographic column. The gas chromatograph is temperature programmed to separate the purgeables which are then detected with a mass spectrometer.

1.2 Interferences

- 1.2.1 Impurities in the purge gas, organic compounds out-gassing from the plumbing ahead of the trap, and solvent vapors in the laboratory account for the majority of contamination problems. The analytical system must be demonstrated to be free from contamination under the conditions of the analysis by running laboratory reagent blanks as described in Exhibit E. The use of non-TFE tubing, non-TFE thread sealants, or flow controllers with rubber components in the purging device should be avoided.
- 1.2.2 Samples can be contaminated by diffusion of volatile organics (particularly fluorocarbons and methylene chloride) through the septum seal into the sample during storage and handling. A holding blank prepared from reagent water and carried through the holding period and the analysis protocol serves as a check on such contamination. One holding blank per case must be analyzed.

1.2.3 Contamination by carry over can occur whenever high level and low level samples are sequentially analyzed. To reduce carry over, the purging device and sampling syringe must be rinsed with reagent water between sample analyses. Whenever an unusually concentrated sample is encountered, it should be followed by an analysis of reagent water to check for cross contamination. For samples containing large amounts of water-soluble materials, suspended solids, high boiling compounds or high purgeable levels, it may be necessary to wash out the purging device with a detergent solution, rinse it with distilled water, and then dry it in a 105°C oven between analyses. The trap and other parts of the system are also subject to contamination; therefore, frequent bakeout and purging of the entire system may be required.

1.3 Apparatus and Materials

1.3.1 Micro syringes - 25 μ L and larger, 0.006 inch ID needle.

1.3.2 Syringe valve - two-way, with Luer ends (three each), if applicable to the purging device.

1.3.3 Syringe - 5 mL, gas tight with shut-off valve.

1.3.4 Balance-Analytical, capable of accurately weighing 0.0001 g. and a top-loading balance capable of weighing 0.1g.

1.3.5 Glassware

- 1.3.5.1 o Bottle - 15 mL, screw cap, with Teflon cap liner.
- o Volumetric flasks - class A with ground-glass stoppers.
- o Vials - 2 mL for GC autosampler.

1.3.6 Purge and trap device - The purge and trap device consists of three separate pieces of equipment; the sample purger, trap and the desorber. Several complete devices are now commercially available.

1.3.6.1 The sample purger must be designed to accept 5 mL samples with a water column at least 3 cm deep. The gaseous head space between the water column and the trap must have a total volume of less than 15 mL. The purge gas must pass through the water column as finely divided bubbles with a diameter of less than 3 mm at the origin. The purge gas must be introduced no more than 5 mm from the base of the water column. The sample purger, illustrated in Figure 1, meets these design criteria. Alternate sample purge devices may be utilized provided equivalent performance is demonstrated.

1.3.6.2 The trap must be at least 25 cm long and have an inside diameter of at least 0.105 inch. The trap must be packed to contain the following minimum lengths of absorbents: 1.0 cm of methyl silicone coated packing (3% OV-1 on Chromosorb W or equivalent), 15 cm of 2,6-diphenylene oxide polymer (Tenax-GC 60/80 mesh) and 8 cm of silica gel (Davison Chemical, 35/60 mesh, grade 15, or equivalent). The minimum specifications for the trap are illustrated in Figure 2.

1.3.6.3 The desorber should be capable of rapidly heating the trap to 180°C. The polymer section of the trap should not be heated higher than 180°C and the remaining sections should not exceed 220°C. The desorber design, illustrated in Figure 2, meets these criteria.

1.3.6.4 The purge and trap device may be assembled as a separate unit or be coupled to a gas chromatograph as illustrated in Figures 3 and 4.

1.3.6.5 A heater or heated bath capable of maintaining the purge device at $40^{\circ}\text{C} \pm 1^{\circ}\text{C}$.

1.3.7 GC/MS system

1.3.7.1 Gas chromatograph - An analytical system complete with a temperature programmable gas chromatograph suitable for on-column injection and all required accessories including syringes, analytical columns, and gases.

1.3.7.2 Column - 6 ft long x 0.1 in ID glass, packed with 1% SP-1000 on Carbowack B (60/80 mesh) or equivalent.

1.3.7.3 Mass spectrometer - Capable of scanning from 35 to 260 amu every seven seconds or less, utilizing 70 volts (nominal) electron energy in the electron impact ionization mode and producing a mass spectrum which meets all the criteria in table 2 when 50 ng of 4-bromofluorobenzene (BFB) is injected through the gas chromatograph inlet.

1.3.7.4 GC/MS interface - Any gas chromatograph to mass spectrometer interface that gives acceptable calibration points at 50 ng or less per injection for each of the parameters of interest and achieves all acceptable performance criteria (Exhibit E) may be used. Gas chromatograph to mass spectrometer interfaces constructed of all-glass or glass-lined materials are recommended. Glass can be deactivated by silanizing with dichlorodimethylsilane.

1.3.7.5 Data system - A computer system must be interfaced to the mass spectrometer that allows the continuous acquisition and storage on machine readable media of all mass spectra obtained throughout the duration of the chromatographic program. The computer must have software that allows searching any GC/MS data file for ions of a specified mass and plotting such ion abundances versus time or scan number. This type of plot is defined as an Extracted Ion Current Profile (EICP). Software must also be available that allows integrating the abundance in any EICP between specified time or scan number limits.

1.4 Reagents

1.4.1 Reagent water - Reagent water is defined as water in which an interferent is not observed at the MDL of the parameters of interest.

1.4.1.1 Reagent water may be generated by passing tap water through a carbon filter bed containing about 453 g of activated carbon (Calgon Corp., Filtrasorb-300 or equivalent).

1.4.1.2 A water purification system (Millipore Super-Q or equivalent) may be used to generate reagent water.

1.4.1.3 Reagent water may also be prepared by boiling water for 15 minutes. Subsequently, while maintaining the temperature at 90°C, bubble a contaminant-free inert gas through the water for one hour. While still hot, transfer the water to a narrow-mouth screw-cap bottle and seal with a Teflon-lined septum and cap.

1.4.2 Sodium thiosulfate - (ACS) Granular.

1.4.3 Methanol - Pesticide quality or equivalent.

1.4.4 Stock standard solutions - Stock standard solutions may be prepared from pure standard materials or purchased and must be traceable to EMLS/LV supplied standards. Prepare stock standard solutions in methanol using assayed liquids or gases as appropriate.

1.4.4.1 Place about 9.8 mL of methanol into a 10.0 mL tared ground glass stoppered volumetric flask. Allow the flask to stand, unstoppered, for about 10 minutes or until all alcohol wetted surfaces have dried. Weigh the flask to the nearest 0.1 mg.

1.4.4.2 Add the assayed reference material as described below.

1.4.4.2.1 Liquids - Using a 100 μ L syringe, immediately add two or more drops of assayed reference material to the flask then reweigh. The liquid must fall directly into the alcohol without contacting the neck of the flask.

1.4.4.2.2 Gases - To prepare standards for any of the four halocarbons that boil below 30°C (bromomethane, chloroethane, chloromethane, and vinyl chloride), fill a 5 mL valved gas-tight syringe with the reference standard to the 5.0 mL mark. Lower the needle to 5 mm above the methanol meniscus. Slowly introduce the reference standard above the surface of the liquid. The heavy gas rapidly dissolves in the methanol.

- 1.4.4.3 Reweigh, dilute to volume, stopper, then mix by inverting the flask several times. Calculate the concentration in micrograms per microliter from the net gain in weight. When compound purity is assayed to be 96% or greater, the weight may be used without correction to calculate the concentration of the stock standards may be used at any concentration if they are certified by the manufacturer. Commercial standards must be traceable to EMSL/LV supplied standards.
- 1.4.4.4 Transfer the stock standard solution into a Teflon-sealed screw-cap bottle. Store, with minimal headspace at -10°C to -20°C and protect from light.
- 1.4.4.5 Prepare fresh standards weekly for the four gases and 2-chloroethyl-vinyl ether. All other standards must be replaced after one month, or sooner if comparison with check standards indicate a problem.
- 1.4.5 Secondary dilution standards - Using stock standard solutions, prepare secondary dilution standards in methanol that contain the compounds of interest, either singly or mixed together. (See GC/MS Calibration in Exhibit E). Secondary dilution standards should be stored with minimal headspace and should be checked frequently for signs of degradation or evaporation, especially just prior to preparing calibration standards from them.
- 1.4.6 Surrogate standard spiking solution. Prepare stock standard solutions for toluene-d8, p-bromofluorobenzene, and 1,2-dichloroethane-d4 in methanol as described in Paragraph 1.4.4. Prepare a surrogate standard spiking solution from these stock standards at a concentration of 250 ug/10 mL in methanol.

1.4.7 Purgeable Organic Matrix Standard Spiking Solution

- 1.4.7.1 Prepare a spiking solution in methanol that contains the following compounds at a concentration of 250 ug/10.0 mL:

Purgeable Organics

1,1-dichloroethene
trichloroethene
chlorobenzene
toluene
benzene

- 1.4.7.2 Matrix spikes also serve as duplicates; therefore, add an aliquot of this solution to each of two portions from one sample chosen for spiking.

- 1.4.8 BFB Standard - Prepare a 25 ng/uL solution of BFB in methanol.

- 1.4.9 Great care must be taken to maintain the integrity of all standard solutions. It is recommended that all standard solutions be stored at -10°C to -20°C in screw cap amber bottles with teflon liners.

1.5 Calibration

- 1.5.1 Assemble a purge and trap device that meets the specification in paragraph 1.3.6. Condition the trap overnight at 180°C in the purge mode with an inert gas flow of at least 20 mL/min. Prior to use, daily condition traps 10 minutes while back-flushing at 180°C with the column at 220°C.

- 1.5.2 Connect the purge and trap device to a gas chromatograph. The gas chromatograph must be operated using temperature and flow rate parameters equivalent to those in paragraph 1.7.1.2. Calibrate the purge and trap-GC/MS system using the internal standard technique (paragraph 1.5.3).

1.5.3 Internal standard calibration procedure. The three internal standards are bromochloromethane, 1,4-difluorobenzene, and chlorobenzene- d_5 .

1.5.3.1 Prepare calibration standards at a minimum of five concentration levels for each HSL parameter. The concentration levels are specified in Exhibit E. Aqueous standards may be stored up to 24 hours, if held in sealed vials with zero headspace as described in paragraph 1.7. If not so stored, they must be discarded after an hour.

1.5.3.2 Prepare a spiking solution containing each of the internal standards using the procedures described in paragraphs 1.4.4 and 1.4.5. It is recommended that the secondary dilution standard be prepared at a concentration of 25 ug/mL of each internal standard compound. The addition of 10 uL of this standard to 5.0 mL of sample or calibration standard would be equivalent of 50 ug/L.

1.5.3.3 Analyze each calibration standard, according to paragraph 1.7 adding 10 uL of internal standard spiking solution directly to the syringe. Tabulate the area response of the characteristic ions against concentration for each compound and internal standard and calculate response factors (RF) for each compound using equation 1.

$$\text{EQ. 1.} \quad \text{RF} = \frac{A_x}{A_{is}} \times \frac{C_{is}}{C_x}$$

Where:

A_x = Area of the characteristic ion for the compound to be measured.

A_{is} = Area of the characteristic ion for the specific internal standard from Exhibit E.

C_{is} = Concentration of the internal standard.

C_x = Concentration of the compound to be measured.

- 1.5.3.4 The average response factor (RF) must be calculated for all compounds. A system performance check must be made before this calibration curve is used. Five compounds (the system performance check compounds) are checked for a minimum average response factor. These compounds (the SPCC) are chloromethane, 1,1-dichloroethane, bromoform, 1,1,2,2-tetrachloroethane, and chlorobenzene. Five compounds (the calibration check compounds, CCC) are used to evaluate the curve. Calculate the % Relative Standard Deviation (ZRSD) of RF values over the working range of the curve. A minimum ZRSD for each CCC must be met before the curve is valid.

$$\text{ZRSD} = \frac{\text{Standard deviation}}{\text{mean}} \times 100$$

See instructions for Form VI, Initial Calibration Data for more details.

- 1.5.3.5 Check of the calibration curve should be performed once every 12 hours. These criteria are described in detail in the instructions for Form VII, Continuing Calibration Check. The minimum response factor for the system performance check compounds must be checked. If this criteria is met, the response factor of all

compounds are calculated and reported. A percent difference of the daily response factor (12 hour) compared to the average response factor from the initial curve is calculated. The maximum percent difference allowed for each compound flagged as 'CCC' in Form VII is checked. Only after both these criteria are met can sample analysis begin.

- 1.5.3.6 Internal standard responses and retention times in all samples must be evaluated immediately after or during data acquisition. If the retention time for any internal standard changes by more than 30 seconds from the latest daily (12 hour) calibration standard, the chromatographic system must be inspected for malfunctions and corrections made as required. If the extracted ion current profile (EICP) area for any internal standard changes by more than a factor of two (-50% to +100%), the mass spectrometric system must be inspected for malfunction and corrections made as appropriate. When corrections are made, re-analysis of samples analyzed while the system was malfunctioning is necessary. Retention time and EICP area records shall be maintained in appropriate form by the laboratory as a part of its internal quality control (Exhibit E).

1.6 GC/MS Operating Conditions

- 1.6.1 These performance tests require the following instrumental parameters:

Electron Energy: 70 Volts (nominal)
Mass Range: 35 - 260
Scan Time: to give at least 5 scans per peak
but not to exceed 7 seconds per scan.

E-12

→ Will be changed to
Something like
10 scans/peak 5/84
2 seconds/scan.

1.7 Sample Analysis

1.7.1 Water Samples

- 1.7.1.1 All samples and standard solutions must be allowed to warm to ambient temperature before analysis.
- 1.7.1.2 Recommended operating conditions for the gas chromatograph - Column conditions: Carbowax 8 (60/80 mesh with 1% SP-1000 packed in a 6 foot by 2 mm ID glass column with helium carrier gas at a flow rate of 30 mL/min. Column temperature is isothermal at 45°C for 3 minutes, then programmed at 8°C per minute to 220°C and held for 15 minutes.
- 1.7.1.3 After achieving the key ion abundance criteria, calibrate the system daily as described in Exhibit E.
- 1.7.1.4 Adjust the purge gas (helium) flow rate to 40 ± 3 mL/min. Variations from this flow rate may be necessary to achieve better purging and collection efficiencies for some compounds, particularly chloromethane and bromoform.
- 1.7.1.5 Remove the plunger from a 5 mL syringe and attach a closed syringe valve. Open the sample or standard bottle which has been allowed to come to ambient temperature, and carefully pour the sample into the syringe barrel to just short of overflowing. Replace the syringe plunger and compress the sample. Open the syringe valve and vent any residual air while adjusting the sample volume to 5.0 mL. This process of taking an aliquot destroys the validity of the sample for future analysis so if there is only one VOA vial, the analyst should fill a second syringe at this time to protect against possible loss of sample integrity. This second sample is maintained only until such a time when the

analyst has determined that the first sample has been analyzed properly. Filling one 20 mL syringe would allow the use of only one syringe. If a second analysis is needed from the 20 mL syringe, it must be analyzed within 24 hours. Care must also be taken to prevent air from leaking into the syringe.

1.7.1.6 The purgeable organics screening procedure (Section III, paragraph 1.0), if used, will have shown the approximate concentrations of major sample components. If a dilution of the sample was indicated, this dilution shall be made just prior to GC/MS analysis of the sample.

1.7.1.6.1 The following procedure will allow for dilutions near the calculated dilution factor from the screening procedure:

- o All dilutions are made in volumetric flasks (10 mL to 100 mL).
- o Select the volumetric flask that will allow for the necessary dilution. Intermediate dilutions may be necessary for extremely large dilutions.
- o Calculate the approximate volume of reagent water which will be added to the volumetric flask selected and add slightly less than this quantity of reagent water to the flask.
- o Inject the proper aliquot from the syringe prepared in paragraph 1.7.1.5 into the volumetric flask. Aliquots of less than 1 mL increments are prohibited. Dilute the flask to the mark with reagent water. Cap the flask, invert, and shake three times.
- o Fill a 5 mL syringe with the diluted sample as in paragraph 1.7.1.5.

- o If this is an intermediate dilution, use it and repeat above procedure to achieve larger dilutions.

- 1.7.1.7 Add 10.0 μ L of the surrogate spiking solution (1.4.6) and 10.0 μ L of the internal standard spiking solution (1.5.3.2) through the valve bore of the syringe, then close the valve. The surrogate and internal standards may be mixed and added as a single spiking solution. The addition of 10 μ L of the surrogate spiking solution to 5mL of sample is equivalent to a concentration of 50 μ g/L of each surrogate standard.
- 1.7.1.8 Attach the syringe-syringe valve assembly to the syringe valve on the purging device. Open the syringe valves and inject the sample into the purging chamber.
- 1.7.1.9 Close both valves and purge the sample for 12.0 ± 0.1 minutes at ambient temperature.
- 1.7.1.10 At the conclusion of the purge time, attach the trap to the chromatograph, adjust the device to the desorb mode, and begin the gas chromatographic temperature program. Concurrently, introduce the trapped materials to the gas chromatographic column by rapidly heating the trap to 180°C while backflushing the trap with an inert gas between 20 and 60 mL/min for four minutes. If this rapid heating requirement cannot be met, the gas chromatographic column must be used as a secondary trap by cooling it to 30°C (or subambient, if problems persist) instead of the recommended initial temperature of 45°C.
- 1.7.1.11 While the trap is being desorbed into the gas chromatograph, empty the purging chamber. Wash the chamber with a minimum of two 5 mL flushes of reagent water to avoid carry-over of pollutant compounds.

1.7.1.12 After desorbing the sample for four minutes, recondition the trap by returning the purge and trap device to the purge mode. Wait 15 seconds then close the syringe valve on the purging device to begin gas flow through the trap. The trap temperature should be maintained at 180°C. Trap temperatures up to 230°C may be employed, however the higher temperature will shorten the useful life of the trap. After approximately seven minutes turn off the trap heater and open the syringe valve to stop the gas flow through the trap. When cool, the trap is ready for the next sample.

1.7.1.13 If the initial analysis of a sample or a dilution of a sample indicates saturated ions of HSL compounds, the sample must be reanalyzed at a higher dilution. When a sample is analyzed that has saturated ions from a compound, this analysis must be followed by a blank reagent water analysis. If the blank analysis is not free of interferences, the system must be decontaminated. Sample analysis may not resume until a blank can be analyzed that is free of interferences.

1.7.1.14 For low and medium level water samples, add 10 μ L of the matrix spike solution (1.4.7) to the 5mL of sample purged. Disregarding any dilutions, this is equivalent to a concentration of 50 μ g/L of each matrix spike standard.

1.7.1.15 All dilutions must keep the response of the major constituents (previously saturated peaks) in the upper half of the linear range of the curve.

1.7.2 Sediment/Soil Samples

Two approaches may be taken to determine whether the low level or medium level method may be followed.

- o Assume the sample is low level and analyze a 5 gram sample
- o Use the X factor calculated from the optional Hexadecane screen (Section III), paragraph 1.7.2.1.3

any
If ~~peaks~~ are saturated from the analysis of a 5 gram sample, a smaller sample size must be analyzed to prevent saturation. However, the smallest sample size permitted is 1 gm. If smaller than 1 gram sample size is needed to prevent saturation, the medium level method must be used.

1.7.2.1 Low Level Method

The low level method is based on purging a heated sediment/soil sample mixed with reagent water containing the surrogate and internal standards.

Use 5 grams of sample or use the X Factor to determine the sample size for purging.

- o If the X Factor is 0 (no peaks noted on the hexadecane screen), analyze a 5 gm sample.
- o If the X Factor is between 0 and 1.0, analyze a 1 gm sample.

1.7.2.1.1 The GC/MS system should be set up as in 1.7.1.2 - 1.7.1.4. This should be done prior to the preparation of the sample to avoid loss of volatiles from standards and sample.

1.7.2.1.2 Remove the plunger from a 5 mL "Luerlock" type syringe equipped with a syringe valve and fill until overflowing with reagent water. Replace the plunger and compress the water to vent trapped air. Adjust the volume to 5.0 mL. Add 10 uL each of the surrogate spiking solution (1.4.6) and the internal standard solution to the syringe through the valve. (Surrogate spiking solution and internal standard solution may be mixed together). The addition of 10 uL of the surrogate spiking solution to 5 gm of sediment/ soil is equivalent to 50 ug/kg of each surrogate standard.

1.7.2.1.3 The sample (for volatile organics) consists of the entire contents of the sample container. Do not discard any supernatant liquids. Mix the contents of the sample container with a narrow metal spatula. Weigh the amount determined in 1.7.2.1 into a tared purge device. Use a top loading balance. Note and record the actual weight to the nearest 0.1 gm.

1.7.2.1.3.1 Immediately after weighing the sample weigh 5-10 g of the sediment into a tared crucible. Determine the percent moisture by drying overnight at 105°C. Allow to cool in a desiccator before weighing. Concentrations of individual analytes will be reported relative to the dry weight of sediment.

Percent moisture

$$\frac{\text{gm of sample} - \text{gm of dry sample}}{\text{gm of sample}} \times 100 = \% \text{ moisture}$$

1.7.2.1.4 Add the spiked reagent water to the purge device and connect the device to the purge and trap system. NOTE: Steps 1.7.2.1.2 - 1.7.2.1.3, prior to the attachment of the purge device, must be performed rapidly to avoid loss of volatile organics. These steps must be performed in a laboratory free of solvent fumes.

1.7.2.1.5 Heat the sample to $40^{\circ}\text{C} \pm 1^{\circ}\text{C}$ and purge the sample for 12 ± 0.1 minutes.

1.7.2.1.6 Proceed with the analysis as outlined in 1.7.1.10 - 1.7.1.13. Use 5 mL of the same reagent water as the reagent blank.

1.7.2.1.7 For low level sediment/soils add 10 uL of the matrix spike solution (1.4.7) to the 5 mL of water (1.7.2.1.2). The concentration for a 5 gram sample would be equivalent to 50 ug/kg of each matrix spike standard.

1.7.2.2 Medium Level Method

The medium level method is based on extracting the sediment/soil sample with methanol. An aliquot of the methanol extract is added to reagent water containing the surrogate and internal standards. This is purged at ambient temperature. All samples with an X Factor > 1.0 should be analyzed by the medium level method. If saturated peaks occurred or would occur when a 1 gram sample was analyzed, the medium level method must be used.

IV.

- 1.7.2.2.1 The sample (for volatile organics) consists of the entire contents of the sample container. Do not discard any supernatant liquids. Mix the contents of the sample container with a narrow metal spatula. Weigh 4 gm (wet weight) into a tared 15 mL vial. Use a top loading balance. Note and record the actual weight to the nearest 0.1 gm. Determine the percent moisture as in 1.7.2.1.3.1.
- 1.7.2.2.2 Quickly add 9.0 mL of methanol, then 1.0 mL of the surrogate spiking solution to the vial. Cap and shake for 2 minutes. NOTE: Steps 1.7.2.2.1 and 1.7.2.2.2 must be performed rapidly to avoid loss of volatile organics. These steps must be performed in a laboratory free of solvent fumes.
- 1.7.2.2.3 Pipette for storage approximately 1 mL of extract to a GC vial using a disposable pipet. The remainder may be disposed of. Transfer approximately 1 mL of the reagent methanol to a GC vial for use as the method blank for each case or set of 20 samples, whichever is greater. These extracts may be stored in the dark at 4°C prior to analysis.

The addition of a 100 uL aliquot of each of these extracts in paragraph 1.7.2.2.6 will give a concentration equivalent to 6,200 ug/kg of each surrogate standard.

1.7.2.2.4 The GC/MS system should be set up as in 1.7.1.2 - 1.7.1.4. This should be done prior to the addition of the methanol extract to reagent water.

1.7.2.2.5 The following table can be used to determine the volume of methanol extract to add to the 5 mL of reagent water for analysis. If the Hexadecane screen procedure was followed use the X factor (Option B) or the estimated concentration (Option A) to determine the appropriate volume. Otherwise, estimate the concentration range of the sample from the low level analysis to determine the appropriate volume. If the sample was submitted as a medium level sample, start with 100 uL. All dilutions must keep the response of the major constituents (previously saturated peaks) in the upper half of linear range of the curve.

<u>X Factor</u>	<u>Estimated Concentration Range^{1/}</u>	<u>Take this Volume of Methanol Extract^{2/}</u>
	ug/kg	uL
0.25 - 5.0	500 - 10,000	100
0.5 - 10.0	1000 - 20,000	50
2.5 - 50.0	5000 - 100,000	10
12.5 - 250	25,000 - 500,000	100 of 1/50 dilution ^{3/}

Calculate appropriate dilution factor for concentrations exceeding the table.

- 1/ Actual concentration ranges could be 10 to 20 times higher than this if the compounds are halogenated and the estimates are from GC/FID.
- 2/ The volume of methanol added to the 5 mL of water being purged should be kept constant. Therefore, add to the 5 mL syringe whatever volume of methanol is necessary to maintain a volume of 100 uL added to the syringe.
- 3/ Dilute an aliquot of the methanol extract and then take 100 uL for analysis.

- 1.7.2.2.6 Remove the plunger from a 5 mL "Luerlock" type syringe equipped with a syringe valve and fill until overflowing with reagent water. Replace the plunger and compress the water to vent trapped air. Adjust the volume to 4.9 mL. Pull the plunger back to 5 mL to allow volume for the addition of sample and standards. Add 10 uL of the internal standard solution. Also add the volume of methanol extract determined in 1.7.2.2.5 and a volume of methanol solvent to total 100 uL (excluding methanol in standards).
- 1.7.2.2.7 Attach the syringe-syringe valve assembly to the syringe valve on the purging device. Open the syringe valve and inject the water/methanol sample into the purging chamber.
- 1.7.2.2.8 Proceed with the analysis as outlined in 1.7.1.9 - 1.7.1.13. Analyze all reagent blanks on the same instrument as the samples. The standards should also contain 100 uL of methanol to simulate the sample conditions.
- 1.7.2.2.9 For a matrix spike in the medium level sediment/soil samples, add 8.0 mL of methanol, 1.0 mL of surrogate spike solution (1.4.6), and 1.0 mL of matrix spike solution (1.4.7) in paragraph 1.7.1.2.2. This results in a 6,200 ug/kg concentration of each matrix spike standard when added to a 4 gm sample. Add a 100 uL aliquot of this extract to 5 mL of water for purging (as per paragraph 1.7.2.2.6).

1.8 Qualitative Analysis

1.8.1 The target compounds listed in the Hazardous Substances List (HSL), Exhibit C, shall be identified by an analyst competent in the interpretation of mass spectra (see Bidder Pre-Award Laboratory Evaluation Criteria) by comparison of the sample mass spectrum to the mass spectrum of a standard of the suspected compound. Two criteria must be satisfied to verify the identifications: (1) elution of the sample component at the same GC relative retention time as the standard component, and (2) correspondence of the sample component and standard component mass spectra.

1.8.1.1 For establishing correspondence of the GC relative retention time (RRT), the sample component RRT must compare within ± 0.06 RRT units of the RRT of the standard component. For reference, the standard must be run on the same shift as the sample. If coelution of interfering components prohibits accurate assignment of the sample component RRT from the total ion chromatogram, the RRT should be assigned by using extracted ion current profiles for ions unique to the component of interest.

1.8.1.2 For comparison of standard and sample component mass spectra, mass spectra obtained on the contractor's GC/MS are required. Once obtained, these standard spectra may be used for identification purposes, only if the contractor's GC/MS meets the daily turning requirements for BFB or DFTPP. These standard spectra may be obtained from the run used to obtain reference RRTs.

1.8.1.3 The requirements for qualitative verification by comparison of mass spectra are as follows:

(1) All ions present in the standard mass spectra at a relative intensity greater than 10 % (most abundant ion in the spectrum equals 100%) must be present in the sample spectrum.

(2) The relative intensities of ions specified in (1) must agree within plus or minus 20% between the standard and sample spectra. (Example: For an ion with an abundance of 50% in the standard spectra, the corresponding sample abundance must be between 30 and 70 percent).

(3) Ions greater than 10% in the sample spectrum but not present in the standard spectrum must be considered and accounted for by the analyst making the comparison. In Task III, the verification process should favor false negatives.

1.8.2 A library search shall be executed for Non-HSL sample components for the purpose of tentative identification. For this purpose, the most recent available version of the EPA/NIH Mass Spectral Library shall be used. Computer generated library search routines should not use normalization routines that would misrepresent the library or unknown spectra when compared to each other.

1.8.2.1 Up to 10 substances of greatest apparent concentration not listed in Exhibit C for the purgeable organic fraction shall be tentatively identified via a forward search of the EPA/NIH mass spectral library. (Substances with responses less than 10% of the internal standard are not required to be searched in this fashion). Only after visual comparison of sample spectra with the nearest library searches will the mass spectral interpretation specialist assign a tentative identification.

1.8.2.2 Guidelines for making tentative identification: (1) Relative intensities of major ions in the reference spectrum (ions greater than 10% of the most abundant ion) should be present in the sample spectrum.

(2) The relative intensities of the major ions should agree within $\pm 20\%$. (Example: For an ion with an abundance of 50 percent of the standard spectra, the corresponding sample ion abundance must be between 30 and 70 percent.)

(3) Molecular ions present in reference spectrum should be present in sample spectrum.

(4) Ions present in the sample spectrum but not in the reference spectrum should be reviewed for possible background contamination or presence of co-eluting compounds.

(5) Ions present in the reference spectrum but not in the sample spectrum should be reviewed for possible subtraction from the sample spectrum because of background contamination or co-eluting compounds. Data system library reduction programs can sometimes create these discrepancies.

1.8.2.3 If in the opinion of the mass spectral specialist, no valid tentative identification can be made, the compound should be reported as unknown. The mass spectral specialist should give additional classification of the unknown compound, if possible (i.e. unknown aromatic, unknown hydrocarbon, unknown acid type, unknown chlorinated compound). If probable molecular weights can be distinguished, include them.

1.9 Quantitative Analysis

1.9.1 HSL components identified shall be quantified by the internal standard method. The internal standard used shall be the one nearest the retention time to that of a given analyte. The

EICP area of the characteristic ions of analytes listed in Tables 2 and 3 are used. The response factor (RF) from the daily standard analysis is used to calculate the concentration in the sample. Use the response factor as determined in paragraph 1.5.3.3 and the following equations:

Water (low and medium level)

$$\text{Concentration} \quad \text{ug/L} = \frac{(A_x)(I_s)}{(A_{1s})(RF)(V_o)}$$

Where:

A_x = Area of the characteristic ion for the compound to be measured

A_{1s} = Area of the characteristic ion for the specific internal standard from Exhibit E.

I_s = Amount of internal standard added in nanograms (ng)

V_o = Volume of water purged in milliliters (mL) (take into account any dilutions)

Sediment/Soil (medium level)

$$\text{Concentration} \quad \text{ug/kg} = \frac{(A_x)(I_s)(V_t)}{(A_{1s})(RF)(V_1)(W_s)(D)}$$

Sediment/Soil (low level)

$$\text{Concentration} \quad \text{ug/kg} = \frac{(A_x)(I_s)}{(A_{1s})(RF)(W_s)(D)}$$

(Dry weight basis)

Where:

A_x, I_s, A_{1s} = same as for water, above

V_t = Volume of total extract (uL) (use 10,000 uL or a factor of this when dilutions are made)

V_1 = Volume of extract added (uL) for purging

D = $\frac{100 - \% \text{ moisture}}{100}$

W_s = Weight of sample extracted (gm) or purged

1.9.2 An estimated concentration for Non-HSL components tentatively identified shall be quantified by the internal standard method. For quantification, the nearest internal standard free of interferences shall be used.

1.9.2.1 The formula for calculating concentrations is the same as in paragraph 1.9.1. Total area counts from the total ion chromatograms are to be used for both the compound to be measured and the internal standard. A response factor (RF) of one (1) is to be assumed. The value from this quantitation shall be qualified as estimated. This estimated concentration should be calculated for all tentatively identified compounds as well as those identified as unknowns.

1.9.2.2 Xylenes (o,m, & p - isomers) are to be reported as total Xylenes. Since o- and p-Xylene overlap, the Xylenes must be quantitated versus m-Xylene. The concentration of all Xylene isomers must be added together to give the total.

1.9.3 Calculate surrogate standard recovery on all samples, blanks and spikes. Determine if recovery is within limits and report on appropriate form.

1.9.3.1 Calculation for surrogate recovery.

$$\text{Percent Surrogate Recovery} = \frac{Q_d}{Q_a} \times 100\%$$

where: Q_d = quantity determined by analysis

Q_a = quantity added to sample

1.9.3.2 If recovery is not within limits, the following is required:

- o Check to be sure there are no errors in calculations, surrogate solutions and internal standards. Also, check instrument performance.
- o Recalculate the sample data if any of the above checks reveal a problem.
- o Reanalyze the sample if none of the above are a problem.
- o Report the data from both analyses along with the surrogate data from both.

Table 2
Characteristic Ions for Surrogate and
Internal Standards for Volatile Organic Compounds

Compound	Primary Ion	Secondary Ion(s)
<u>SURROGATE STANDARDS</u>		
4-Bromofluorobenzene	95	174, 176
1,1-Dichloroethane d-4	63	102
Toluene d-5	98	70, 100
<u>INTERNAL STANDARDS</u>		
Bromochloromethane	125	49, 130, 51
1,4-Difluorobenzene	114	63, 88
Chlorobenzene d-5	117	81, 119

Table 3
Characteristic Ions for Volatile HSL Compounds

Parameter	Primary Ion*	Secondary Ion(s)
Chloromethane	50	52
Bromomethane	94	96
Vinyl chloride	62	64
Chloroethane	64	66
Methylene chloride	84	49, 51, 86
Acetone	43	58
Carbon disulfide	76	78
1,1-Dichloroethene	96	61, 98
1,1-Dichloroethane	63	65, 83, 85, 98, 100
trans-1,2-Dichloroethene	96	61, 98
Chloroform	83	85
1,2-Dichloroethane	62	64, 100, 98
2-Butanone	72	57
1,1,1-Trichloroethane	97	99, 117, 119
Carbon tetrachloride	117	119, 121
Vinyl acetate	43	86
Bromodichloromethane	83	85, 129
1,1,2,2-Tetrachloroethane	83	85, 131, 133, 166
1,2-Dichloropropane	63	65, 114
trans-1,3-Dichloropropene	75	77
Trichloroethene	130	95, 97, 132
Dibromochloromethane	129	208, 206
1,1,2-Trichloroethane	97	83, 85, 99, 132, 134
Benzene	78	-
cis-1,3-Dichloropropene	75	77
2-Chloroethyl vinyl ether	63	65, 106
Bromoform	173	171, 175, 250, 252, 254, 256
2-Hexanone	43	58, 57, 100
4-Methyl-2-pentanone	43	58, 100
Tetrachloroethene	164	129, 131, 166
Toluene	92	91
Chlorobenzene	112	114
Ethyl benzene	106	91
Styrene	104	75, 103
Total xylenes	106	91

* The primary ion should be used unless interferences are present, in which case, a secondary ion may be used.




Figure 1. Purging device




Figure 2. Trap packings and construction to include desorb capability




Figure 3. Schematic of purge and trap device — purge mode




Figure 4. Schematic of purge and trap device — desorb mode




Figure 5. Low Soils Impinger

2. GC/MS Analysis of Extractables (Base/Neutrals and Acids)

2.1 Summary of Method

This method is to be used for the GC/MS analysis of extractable extracts screened by Section III protocols and for confirmation of pesticides/PCBs identified by GC/EC, if concentrations permit.

2.2 Apparatus and Materials

2.2.1 Gas chromatograph/mass spectrometer system.

2.2.1.1 Gas chromatograph - An analytical system complete with a temperature programmable gas chromatograph suitable for splitless injection and all required accessories including syringes, analytical columns, and gases.

2.2.1.2 Column - 30 m x 0.25 mm ID (or 0.32 mm) bonded-phase silicone coated fused silica capillary column (J&W Scientific DB-5 or equivalent). A film thickness of 1.0 micron is recommended because of its larger capacity. A film thickness of 0.25 micron may be used.

2.2.1.3 Mass Spectrometer - Capable of scanning from 35 to 500 amu every 1 second or less, utilizing 70 volts (nominal) electron energy in the electron impact ionization mode and producing a mass spectrum which meets all required criteria when 50 ng of decafluorotriphenylphosphine (DFTPP) is injected through the GC inlet.

NOTE: DFTPP criteria must be met before any sample extracts are analyzed. Any samples analyzed when DFTPP criteria have not been met will require reanalysis at no cost to the Government.

WESTON

EPA PROTOCOL FOR THE ANALYSIS OF
VOLATILE PRINCIPLE ORGANIC HAZARDOUS CONSTITUENTS
USING VOST

6060A



Research and Development

PROTOCOL FOR THE
COLLECTION AND ANALYSIS OF
VOLATILE POHCs USING VCST

Prepared for

Office of Solid Waste and Emergency Response

Prepared by

Industrial Environmental Research
Laboratory
Research Triangle Park NC 27711

RESEARCH REPORTING SERIES

Research reports of the Office of Research and Development, U.S. Environmental Protection Agency, have been grouped into nine series. These nine broad categories were established to facilitate further development and application of environmental technology. Elimination of traditional grouping was consciously planned to foster technology transfer and a maximum interface in related fields. The nine series are:

1. Environmental Health Effects Research
2. Environmental Protection Technology
3. Ecological Research
4. Environmental Monitoring
5. Socioeconomic Environmental Studies
6. Scientific and Technical Assessment Reports (STAR)
7. Interagency Energy-Environment Research and Development
8. "Special" Reports
9. Miscellaneous Reports

This report has been assigned to the SPECIAL REPORTS series. This series is reserved for reports which are intended to meet the technical information needs of specifically targeted user groups. Reports in this series include Problem Oriented Reports, Research Application Reports, and Executive Summary Documents. Typical of these reports include state-of-the-art analyses, technology assessments, reports on the results of major research and development efforts, design manuals, and user manuals.

EPA REVIEW NOTICE

This report has been reviewed by the U.S. Environmental Protection Agency and approved for publication. Approval does not signify that the contents necessarily reflect the views and policy of the Agency, nor does mention of trade names or commercial products constitute endorsement or recommendation for use.

This document is available to the public through the National Technical Information Service, Springfield, Virginia 22161.

EPA-600/8-84-007
March 1984

PROTOCOL
FOR THE
COLLECTION AND ANALYSIS OF
VOLATILE POHCS USING VOST

By

Earl M. Hansen

Envirodyne Engineers, Inc.
12161 Lackland Road
St. Louis, Missouri 63146

EPA Contract No. 68-02-3697
Technical Directive 003

EPA Project Officer: Robin M. Anderson
Technical Support Office
U. S. Environmental Protection Agency
Industrial Environmental Research Laboratory
Research Triangle Park, NC 27711

Prepared For

Office of Research and Development
U.S. Environmental Protection Agency
Washington, DC 20460

FOREWORD

This report has been produced by EPA's Office of Research and Development as part of ongoing studies in support of engineering research and regulatory programs including EPA's Office of Solid Waste, EPA Regional Offices, and appropriate State Agencies. The document contains state-of-the-art operating protocols for sampling and analysis of volatile organic constituents of flue gases from hazardous waste incinerators or other similar combustor systems. It is intended as a reference to be used for guidance by personnel of the regulatory groups, personnel associated with engineering R&D, and the regulated community.

Publication of this report does not constitute official designation as an EPA method. Official test methods for hazardous waste related programs are published in SW-846 "Tests Methods for Evaluating Solid Waste," as well as in the Federal Register.



Frank T. Princiotta
Director
Industrial Environmental Research Laboratory

CONTENTS

	<u>Page</u>
Foreword	ii
Figures	v
Acknowledgements	vi
Introduction	vii
Abstract	viii
 PART A: SAMPLE COLLECTION FOR THE DETERMINATION OF EMISSIONS OF VOLATILE ORGANIC COMPOUNDS FROM HAZARDOUS WASTE INCINERATORS	 A-1
1. Scope of Applicability	A-1
2. Summary of Method	A-3
3. Precision and Accuracy	A-5
4. Interferences	A-6
5. Apparatus	A-7
5.1 Volatile Organic Sampling Train	A-7
5.2 Probe	A-7
5.3 Isolation Valve	A-10
5.4 Condensers	A-10
5.5 Sorbent Cartridges	A-10
5.6 Impinger	A-15
5.7 Metering Systems	A-15
5.8 Sample Transfer Lines	A-16
6. Reagents and Materials	A-16
6.1 2,6-Diphenylene Oxide Polymer Tenax (35/60 Mesh)	A-16
6.2 Charcoal (SKC Lot 104 Petroleum Base or equivalent)	A-17
6.3 Viton O-Ring	A-13
6.4 Glass Tubes/Condensers	A-18
6.5 Metal Parts	A-18
6.6 Silica Gel	A-18
6.7 Crushed Ice	A-19
6.8 Water	A-19
6.9 Glass Wool	A-19
6.10 Nitrogen	A-19
7. Assembly and Conditioning of VOST Sorbent Cartridges	A-19
7.1 Introduction	A-19
7.2 Assembly of Tenax Cartridges	A-20
7.3 Assembly of Tenax/Charcoal Cartridges	A-21
7.4 Sorbent Cartridge Quality Assurance	A-22
8. Sample Collection Procedure	A-23
8.1 Pretest Preparation	A-23
8.2 VOST Assembly	A-24
8.3 Leak Checking	A-24
8.4 Sample Collection	A-26
8.5 Field, Trip, and Laboratory Blanks/Aqueous Field Blank	A-28

CONTENTS
(Continued)

	<u>Page</u>
PART B: PROTOCOL FOR ANALYSIS OF SORBENT CARTRIDGES FROM VOLATILE ORGANIC SAMPLING TRAIN	B-1
1. Scope and Applicability	B-1
2. Summary of Method	B-2
3. Precision and Accuracy	B-4
4. Apparatus	B-4
4.1 Thermal Desorption Unit	B-4
4.2 Purge and Trap Unit	B-5
4.3 GC/MS System	B-5
5. Reagents	B-6
5.1 Reagent Water	B-6
5.2 Analytical Trap Reagents	B-7
5.3 Stock Standard Solution	B-8
5.4 Secondary Dilution Standards	B-8
5.5 Bromofluorobenzene (BFB) Standard	B-8
5.6 Deuterated (d ₆) Benzene Standard	B-8
6. Calibration	B-9
6.1 Assembly of P-T-D Device	B-9
6.2 Internal Standard Calibration Procedure	B-9
7. Quality Control	B-12
8. Sample Collection, Preservation, and Handling	B-15
9. Daily GC/MS Performance Tests	B-15
10. Sample Desorption and Gas Chromatography	B-16
11. Aqueous Condensate	B-17
12. Qualitative Identification	B-17
13. Calculations	B-18
14. Method Performance	B-21
REFERENCES (For A and B)	B-22

FIGURES

<u>No.</u>		<u>Page</u>
1	Schematic of Volatile Organic Sampling Train	A-8
2	Volatile Organic Sampling Train (I/O Cartridge Design)	A-9
3	I/O Sorbent Trap Assembly, Volatile Organic Sampling Train (VOST)	A-12
4	Inside/Inside VOST Cartridge	A-13
5	VOST Field Data Sheet	A-25
6	Schematic Diagram of Trap Desorption/Analysis System	B-3

ACKNOWLEDGEMENT

The author wishes to acknowledge the assistance and technical input of several people whose efforts led to the successful completion of this document.

The following people provided valuable comments and recommendations of the draft version of this protocol: Bob DeRosier of Accurex Corporation, Paul Gorman of Midwest Research Institute, Marvin R. Branscome and Charles Sparacino of Research Triangle Institute, Denny Wagoner and Alston Sykes of TRW, and Afaf K. Wensky of Battelle Columbus Laboratories. I would also like to recognize the development work conducted by TRW which provided valuable data for quality assurance monitoring of VOST scrubent cartridges. I am especially grateful for the guidance and constructive criticism received from Larry Johnson and Robin Anderson of the Technical Support Office, USEPA-IERL, Research Triangle Park, NC.

INTRODUCTION

The Resource Conservation and Recovery Act (RCRA) requires that owners/operators of facilities which treat hazardous waste by incineration ensure that the incinerators are operated in a manner which does not endanger human health or the environment (1,2). The Code of Federal Regulation, Title 40, Part 264, requires that a destruction and removal efficiency (DRE) of 99.99 percent be achieved for each principal organic hazardous constituent (POHC) designated in the Trial Burn Permit (3). The DRE standard implicitly requires sampling and analysis to quantify POHCs in the waste feed material and stack gas effluent. The "Sampling and Analysis Methods for Hazardous Waste Combustion" manual (method manual) provides information on methods that are applicable for collection and analyses of POHCs in process streams of hazardous waste incinerator units (4).

The methods manual identifies three possible methods for the collection of volatile organics (those with boiling points $<100^{\circ}\text{C}$). The methods include bag, glass bulb, and the Volatile Organic Sampling Train (VOST). Evaluation of the bags and bulbs indicates that these sampling systems are subject to a number of technical problems. The most important of these problems is the inadequate sensitivity for detection of POHCs present in low concentrations.

The VOST provides increased sensitivity to low level concentration of volatile POHCs due to the ability to concentrate the gaseous effluent. The results of laboratory evaluation and field application of the VOST have shown that it provides sufficient sensitivity to permit calculation of a DRE equal to or greater than 99.99 percent for volatile POHCs which are present in the waste feed at 100 $\mu\text{g/g}$ (5).

The methods manual identifies the VOST as a suitable sampling system for volatile organics and includes a paper describing the VOST (5). A detailed protocol was not included in the methods manual due to the fact that this is outside the scope of the document. Since the VOST is new technology, it is felt a protocol should be made available.

The purpose of this protocol is to provide a standard operating procedure to users of the VOST in the collection and analysis of samples for volatile POHCs in the gaseous effluents of hazardous waste incinerators or gaseous effluents of hazardous waste co-fired combustion processes. The protocol is presented in two parts. Part A describes the key components of the VOST train, and the procedure for sample collection using VOST. Part B describes the procedures for analysis of VOST sorbent cartridges for volatile POHCs using purge-trap-desorb gas chromatography/mass spectrometry (P-T-D GC/MS).

ABSTRACT

This document provides a state-of-the-art operating protocol for sampling and analysis of volatile organic constituents of flue gas from hazardous waste incinerators or other similar combustion systems using the Volatile Organic Sampling Train (VOST). It is intended to be used for guidance by personnel of the regulatory groups, personnel associated with engineering Research and Development, and the regulated community.

The VOST is designed to extract and concentrate volatile organic compounds (boiling $\leq 100^{\circ}\text{C}$) from stack gas effluents. The concentrated organics are analyzed by procedures chosen to be compatible with the VOST in order to obtain flue gas concentration levels. This information is necessary to perform destruction and removal efficiency (DRE) calculations for incinerator operations. The results of laboratory evaluation and field use of the VOST have shown that the VOST provides sufficient sensitivity to permit calculation of a DRE equal to or greater than 99.99 percent for volatile organics present in the waste feed at 100 $\mu\text{g/g}$.

The VOST is directly applicable to organic compounds with boiling points of 30° to 100°C . Many organic compounds with boiling points less than 30°C , or with boiling points in the 100° to 150°C range, may also be collected and analyzed by this method. Field application of the VOST for compounds with boiling points outside the 30° to 100°C range should be attempted only after laboratory evaluation of the collection and recovery efficiencies of the specific compounds.

The document is presented in two parts. Part A describes the key components of the train, the procedures for preparation of the sorbent materials, and procedures for sample collection using the VOST. Part B describes the procedures for analysis of VOST sorbent cartridges for volatile principal organic hazardous constituents (POHCs) using purge-trap-desorb gas chromatography/mass spectrometry (P-T-D GC/MS). Quality control procedures are presented in both Sections A and B.

PART A
SAMPLE COLLECTION FOR THE DETERMINATION OF THE EMISSIONS OF
VOLATILE ORGANIC COMPOUNDS FROM
HAZARDOUS WASTE INCINERATORS

1. SCOPE AND APPLICABILITY

1.1 This protocol describes the method of collection of volatile principal organic hazardous constituents (POHCs) from the stack gas effluents of hazardous waste incinerators. This method is applicable to compounds with boiling points in the range of 30° to 100°C. If the boiling point of a POHC of interest is less than 30°C, the POHC may breakthrough the sorbent under the conditions of the sample collection procedure. Field application for POHCs of this type should be supported by laboratory data which demonstrates the efficiency of a volatile organic sampling train (VOST) to collect POHCs with boiling points less than 30°C (Part B, Section 7). The collection of organic compounds with low boiling points may require using reduced sample volumes collected at flow rates between 250 and 500 milliliters per minute (ml/min). Many compounds which boil in the range of 100° to 150°C (e.g., chlorobenzene, ethylbenzene, tetrachloroethane, bromoform) may be efficiently collected and analyzed using this method. VOST recovery efficiencies for these compounds should also be demonstrated, where necessary, by laboratory data of the type described above (Part B, Section 7).

1.2 This method is applicable to the determination of volatile POHCs in the stack gas effluent of hazardous waste incinerators and other similar combustion systems. This method is designed for use in calculating the destruction and removal efficiency (DRE) for the volatile POHCs. The method provides sufficient precision and accuracy to enable the calculation of DRE values equal to or greater than 99.99 percent (5).

1.3 The sensitivity of this method is dependent upon the level of interferences in the sample and the presence of detectable levels of volatile POHCs in blanks. The target detection limit of this method is 0.1 micrograms per cubic meter ($\mu\text{g}/\text{m}^3$) [0.1 nanograms per liter (ng/l)] of flue gas which permit calculation of a DRE equal to or greater than 99.99 percent for those volatile POHCs which may be present in the waste feed stream at 100 parts per million (ppm). Laboratory development data (5) have demonstrated a range of 0.1 to 100 $\mu\text{g}/\text{m}^3$ (0.1 to 100 ng/l) for selected volatile POHCs.

1.4 The range of applicability for this method is limited by breakthrough of volatile POHCs on the sorbent cartridges used to collect the sample, caution should be exercised in using the VOST to collect samples from a stack gas stream in which one or more of the volatile POHCs are present in concentrations greater than 500 $\mu\text{g}/\text{m}^3$ (500 ng/l). If, for example, an incinerator uses a waste fuel containing volatile POHCs at a concentration of 50,000 to 100,000 $\mu\text{g}/\text{g}$, and the incinerator achieves a DRE of 99.99%, then

the concentration in the effluent would be 500 to 1000 $\mu\text{g}/\text{m}^3$ (500 to 1,000 ng/l), respectively. Analysis using the procedures described in Part B of this method would probably result in overloading the analytical instrumentation and therefore would not provide valid data for that particular POHC. Where the waste contains volatile POHCs at high concentrations, consideration should be given to collecting gaseous effluent samples using SLOW-VOST techniques, gas bags or evacuated glass bulbs. Further, if the waste contains volatile POHCs at high (50,000 $\mu\text{g}/\text{g}$) and low (100 $\mu\text{g}/\text{g}$) concentrations, these POHCs might not be quantifiable using only VOST. In this case, consideration should be given to either collecting gaseous effluent samples using two VOST trains (one of these trains should be operated under conditions of SLOW-VOST), or using one VOST train (SLOW-VOST) and gas bags or glass bulbs. The examples cited above may result in chromatographic interferences or instrument overloading which will invalidate the results. If this situation is anticipated, laboratory evaluation should be conducted prior to field use of the VOST (Part B, Section 7).

1.5 This method is recommended for use only by experienced sampling personnel and analytical chemists, or under close supervision by such qualified persons.

2. SUMMARY OF METHOD

2.1 A 2-hour sample of gaseous effluent is collected on cartridges using six pairs of cartridges, each pair sampling a maximum of 20 liters of gaseous effluent. The samples are collected

at a sampling flow rate of 1 liter per minute, using temperature controlled quartz or glass lined probe and a VOST. The gas stream is cooled to 20°C by passage through a water-cooled condenser and volatile POHCs are collected on a pair of sorbent cartridges. Liquid condensate is collected in an impinger placed between the two sorbent cartridges. The first sorbent cartridge (front cartridge) contains approximately 1.6 grams Tenax, and the second cartridge (back cartridge) contains approximately 1 gram each of Tenax and petroleum based charcoal (SKC Lot 104 petroleum base or equivalent, see Section 6.2.1), 3:1 by volume.

2.2. An alternative set of conditions for sample collection has been used. This method involves collecting a sample volume of 20 liters or less at a reduced flow rate. Operation of the VOST under these conditions has been referred to as SLOW-VOST. This method has been used to collect 5 liters of sample (0.25 liters/min for 20 minutes) or 20 liters of sample (0.5 liters/min for 40 minutes) on each pair of sorbent cartridges. Smaller sample volumes collected at lower flow rates should be considered when the boiling points of the POHCs of interest are below 30°C or for volatile POHCs present in high concentrations in the stack gas.

2.3 The gaseous effluent shall be sampled over a 2-hour period. This is accomplished using six pairs of Tenax and Tenax/charcoal cartridges sampling a maximum of 20 liters of gaseous effluent on each pair of cartridges. Fewer pairs of cartridges may be

required using SLOW-VOST (Section 2.2). A minimum of three pairs of Tenax and Tenax/charcoal cartridges shall be collected for SLOW-VOST sampling.

2.4 Analysis of the cartridges (described in Part B) for volatile POHCs using purge-trap-desorb gas chromatograph/mass spectrometer (P-T-D GC/MS) which is carried out by thermally desorbing each cartridge with the gas passing through a water filled purge column onto an analytical trap. The analytical trap is subsequently heated and the effluent gas passes into the GC/MS.

3. PRECISION AND ACCURACY

3.1 The results of laboratory evaluations of the VOST for selected volatile POHCs showed that the recovery of the analytes from three pairs of replicate cartridges ranged from ± 50 percent of the expected value (5).

3.2 Prior to field operation of the VOST at a hazardous waste incinerator, a laboratory trial should be conducted using either selected volatile POHCs of interest or two or more of the volatile POHCs for which data are available (5). The user shall demonstrate proficiency which is within the precision and accuracy of the method (Part B, Section 7). Experienced users of VOST who have demonstrated proficiency with the VOST and can provide data which supports the applicability of the VOST for the POHCs may be exempt from this requirement. Before the VOST shall be used to

sample compounds below 30°C, the user must demonstrate through laboratory evaluations of the collection and recovery efficiencies that the accuracy and precision requirements are met (Part B, Section 7).

4. INTERFERENCES

4.1 Interferences arise primarily from background contamination of sorbent cartridges prior to or after use in sample collection. Many potential interferences can be due to exposure of the sorbent materials to solvent vapors prior to assembly and exposure to significant concentrations of volatile POHCs in the ambient air at hazardous waste incinerator sites. Benzene and toluene appear to be inherent contaminants on Tenax. This may present problems in the analysis of these compounds using VOST due to high background concentrations. To minimize this problem, the use of additional field blanks is recommended (see Section 8.5).

4.2 To avoid or minimize the low level contamination of train components with volatile POHCs, care should be taken to avoid contact of all interior surfaces or train components with synthetic organic materials (e.g. organic solvents, lubricating and sealing greases), and train components should be carefully cleaned and conditioned according to the procedures described in Sections 5, 6 and 7 of this protocol. The sorbent cartridges should be conditioned and stored in an environment free of volatile organic compounds.

5. APPARATUS

5.1 Volatile Organic Sampling Train

5.1.1 A schematic diagram of the principal components of the VOST is shown in Figure 1. A diagram of the assembled components of one version of the VOST is shown in Figure 2. The VOST consists of: a quartz or glass lined probe with a glass wool particulate plug, an isolation valve, a water cooled glass condenser with thermocouple placed at the outlet to monitor gas stream temperature (see Section 5.6.2), a sorbent cartridge containing Tenax (1.6 grams), an empty impinger for condensate removal, a second water cooled glass condenser, a second sorbent cartridge containing Tenax and petroleum based charcoal (3:1 by volume; approximately 1 gram of each), a silica gel drying tube, a calibrated rotameter, a sampling pump, and a dry gas meter.

5.1.2 The gas pressure during sampling and for leak checking is monitored by vacuum gauges which are in line with and downstream of the silica gel drying tube.

5.2 Probe

5.2.1 The probe shall be maintained at a temperature of at least 130°C in the gas stream prior to the first condenser. If one or more of the volatile POHCs boil between 130° to 150°C, the probe shall be maintained at a temperature equivalent to the boiling point of the least volatile POHC. The probe may require heating to achieve this temperature. If stack temperatures are excessively high, an air or water cooled probe may be required to




FIGURE 1
SCHEMATIC OF
VOLATILE ORGANIC SAMPLING TRAIN
(VOST)




FIGURE 2
 VOLATILE ORGANIC SAMPLING TRAIN
 (I/O CARTRIDGE DESIGN)

avoid damage to the probe and to achieve a temperature of 20°C at inlet to first sorbent cartridge (see Section 5.4). Isokinetic sample collection is not a requirement for the use of VOST since the compounds of interest are in the vapor phase at the point of sample collection.

5.3 Isolation Valve

5.3.1 The isolation valves must be a greaseless stopcock with a glass bore and sliding Teflon plug with Teflon wipers (Ace 8193 or equivalent). These valves are used to permit ambient air to be admitted after leak checking (Section 8.3) and for purging the probe prior to sample collection (Section 8.4).

5.4 Condensers

5.4.1 The condensers (Ace 5979-14 or equivalent) shall be of sufficient capacity to cool the gas stream to 20°C or less prior to passage through the first sorbent cartridge. The top connection of the condenser shall be able to form a leak-free, vacuum-tight seal without using vacuum sealing greases.


5.5 Sorbent Cartridges

5.5.1 The sorbent cartridges for the VOST are available and acceptable in either of two configurations: the inside/outside (I/O) or inside/inside (I/I) configuration. The terms I/O or I/I pertain to the instrument configuration for thermal desorption of the sorbent tubes. For the I/O design, the carrier gas contacts the inside and outside of the sorbent tubes during the desorption.

while for the I/I design, the carrier gas is directed only through the inside of the cartridge. For the I/O configuration, the cartridge is held in the VOST within an outer glass tube and in a metal carrier (Figure 3). For the I/I configuration, a single glass tube is used, with or without a metal carrier (Figure 4). In either case, the sorbent packing will be the same. The first pair of sorbent cartridges shall be packed with approximately 1.6 grams Tenax GC resin, and the second cartridge of a pair shall be packed with Tenax GC and petroleum based charcoal (3:1 by volume; approximately 1 gram of each).

5.5.2 The second sorbent cartridge shall be packed so that the sample gas stream passes through the Tenax layer first and then through the charcoal layer. Note that when sorbent cartridges are analyzed using the P-T-D GC/MS procedure described in Part B, Section 10.2, the gas flow through the sorbent cartridges during desorption is in the opposite direction from the gas flow through the sorbent cartridges during sample collection. The inlet side of each cartridge during sample collection shall be clearly identified so that it becomes the outlet side during the desorption step of the analytical procedure.

5.5.3 The sorbent cartridges shall be glass tubes with approximate dimensions of 10 centimeters by 1.6 centimeters (cm) I.D. The two acceptable designs (I/O, I/I) for the sorbent cartridge are described in further detail below.




Section cut through glass tubes
(showing screen, C-clip and O-ring in place)

LEGEND


- A - Stainless Steel Carrier
- B - Glass Tube (10) mm x 20 mm ID)
- C - Small Glass Tube (10 cm x 1.6 cm ID)
- D - Fine Mesh Stainless Steel Screen
- E - Stainless Steel C-Clip
- F - O-Ring (Viton)
- G - Nuts (1)
- H - End Cap with Viton O-Ring
- I - Metal Rod with Threaded End (3)
- J - Tenax/Charcoal Solvents
- K - Capon Fitting

TOP



NOT TO SCALE

BOTTOM



Assembled Trap
NTS

FIGURE 3
I/O SORBENT CARTRIDGE ASSEMBLY
VOLATILE ORGANIC SAMPLING TRAIN (VOST)




FIGURE 4

INSIDE - INSIDE VOST CARTRIDGE

5.5.3.1 Inside/Outside Type Sorbent Cartridge - A diagram of an I/O type sorbent cartridge is shown in Figure 3. In this design, the sorbent materials are held in the glass tube with a fine mesh stainless steel screen and a C-clip. The glass tube is then placed within a larger diameter glass tube, and held in place using Viton O-rings. The purpose of the outer glass tube is to protect the exterior of the resin-containing tube from contamination. The two glass tubes are held in a stainless steel cartridge holder. The ends of the glass tubes are held in place by Viton O-rings placed in machine grooves in each metal end piece. The three cylindrical rods are secured in one of the metal end pieces and fastened to the other end piece by appropriately sized nuts, thus sealing the glass tubes into the cartridge holder. The end pieces are fitted with a threaded nut onto which a threaded end cap, fitted with a Viton O-ring seal, is placed to protect the resin from contamination during transport and storage.

5.5.3.2 Inside/Inside Type Sorbent Cartridge - A diagram of an I/I type sorbent cartridge is shown in Figure 4. This cartridge is a single glass tube (10 cm by 1.6 cm I.D.) which has the ends reduced in size to accommodate a 1/4 or 3/8-inch Swagelok or Cajon gas fitting. The resin is held in place by glass wool at each end of the resin layer. The amounts of each type of sorbent material used in the I/I design are the same as for the I/O design. Threaded end caps are placed on the sorbent cartridge after packing with sorbent to protect the sorbent from contamination during

storage and transport. Care should be exercised in the placement of the threaded end cap; the male threaded fitting should be backed about 1 mm from the end of the tube prior to tightening to prevent crushing or chipping of the end of the tube.

5.6 Impinger

5.6.1 The impinger which is used to collect aqueous condensate shall have a liquid volume of 125 ml and shall be capable of providing a leak-free seal to the outlet of the Tenax sorbent cartridge. The silica gel drying tube should have sufficient capacity for at least 20 to 30 grams of silica gel.

5.7 Metering System

5.7.1 The metering system for VOST shall consist of: vacuum gauges, a leak-free pump (Thomas Model 107 or equivalent), a calibrated rotameter (Linde Model 150 or equivalent) for monitoring the gas flow rate, a dry gas meter with 2 percent accuracy (7) at the required sampling rate, and related valves and equipment. The dry gas meter shall indicate 1 liter of gas volume for each revolution of the dial. Users of VOST have suggested that the rotameter does not need to be calibrated, but a calibrated rotameter serves as a useful verification of the volume measurement from the dry gas meter.

5.7.2 Provisions will be made for monitoring the temperature of the sample gas stream between the first condenser and first sorbent cartridge. This can be done by placing a thermocouple on the

exterior glass surface of the outlet from the first condenser. The temperature at that point shall be less than 20°C. If it is not, an alternative system, providing increased cooling capacity, must be used.

5.8 Sample Transfer Lines

5.8.1 All sample transfer lines connecting the probe to VOST shall be less than 5 feet in length, if possible, and shall be heat-traced Teflon (to maintain a temperature of at least 130°C in the gas stream) with connecting fittings which are capable of forming leak-free, vacuum-tight connections without the use of sealing grease. All other sample transfer lines used with the VOST (e.g., to connect impinger with second condenser) will be Teflon with connecting fittings that are capable of forming leak-free, vacuum-tight connections without the use of sealing grease.

6. REAGENTS AND MATERIALS

6.1 Tenax, 35/60 Mesh (2,6-Diphenylene Oxide Polymer)

6.1.1 The new Tenax is Soxhlet extracted for 24 hours with methanol (Burdick & Jackson, pesticide grade or equivalent). The Tenax is dried for 6 hours in a vacuum oven at 50°C before use. Users of I/O and I/I sorbent cartridges have used slightly different thermal conditioning procedures. Although strict equivalence of the procedure has not been demonstrated, these methods have produced results that meet method quality assurance requirements (Part B, Section 7.4). I/O sorbent cartridges packed with Tenax are thermally conditioned by flowing organic-free nitrogen

30 ml/min through the resin while heating to 250°C for 8 hours. Sorbent cartridges of the I/I design packed with Tenax are thermally conditioned for 12 to 16 hours by flowing organic-free nitrogen (30 ml/min) through the resin while heating to 190°C. After thermal conditioning, the sorbent cartridges shall be stored for 24 hours at room temperature prior to monitoring the cartridges for residual organic contamination (see Section 7.4). The use of pentane to extract new Tenax and charcoal to remove non-polar impurities is not recommended. (Users have experienced problems with residual pentane in the sorbents during analysis, and therefore, this procedure is not recommended.)

6.1.2 If very high concentrations of organic compounds have been collected on the resin (e.g., micrograms of analytes), the sorbent may require Soxhlet extraction as described above. Previously used Tenax cartridges are thermally reconditioned by the method described above.

6.2 Charcoal (SKC Lot 104 Petroleum Base or Equivalent)

6.2.1 New charcoal is prepared as described in 6.1.1 above. Due to possible problems with charcoal contamination, new charcoal should be used. Users of VOST have restricted the types of charcoal used in sorbent cartridges to only petroleum-based types. Criteria for other types of charcoal are currently under development. Other types of charcoal are acceptable if recovery of POHC in laboratory evaluations meet the criteria (± 50 percent) of the method (Part B, Section 7).

6.3 Viton O-Ring

6.3.1 All O-rings used in VOST shall be Viton. Prior to use, these O-rings shall be thermally conditioned in a vacuum oven at 200°C for 48 hours. O-rings will be stored in clean, screw capped glass containers prior to use.

6.4 Glass Tubes/Condensers

6.4.1 The glass resin tubes and condensers shall be cleaned with a non-ionic detergent in an ultrasonic bath, rinsed well with organic-free water and dried at 110°C. Resin tubes of the I/O design should be assembled as described in Section 7 prior to storage. Resin tubes of the I/I design shall be stored in glass containers with Teflon lined screw caps. Condensers shall be capped with appropriate end caps prior to use.

6.5 Metal Parts

6.5.1 The metal parts (e.g., stainless steel carriers, C-clips, end plugs), used in either the I/O or I/I cartridge design, are cleaned by ultrasonication in a warm non-ionic detergent solution, rinsed with reagent water, air dried and heated in a muffle furnace for 2 hours at 400°C.

6.6 Silica Gel - - Indicating Type, 6-16 Mesh

6.6.1 New silica gel may be used as received. Silica gel which has been previously used shall be dried for 2 hours at 175°C.

6.7 Crushed Ice

6.7.1 Crushed ice from any source may be added to the coolant in the reservoir.

6.8 Water

6.8.1 Water used for leak checking resin cartridges and rinsing glassware shall be reagent (see Part B, Section 5.1); water used for cooling train components in the field may be tap water.

6.9 Glass Wool

6.9.1 Glass wool shall be Soxhlet extracted for 8 to 16 hours using pentane, and oven dried at 110°C before use. The glass wool shall be checked prior to use to ensure that it does not contain residual pentane. If all pentane cannot be removed, an alternate solvent such as methanol may be used.

6.10 Nitrogen

6.10.1 Nitrogen gas will be organic-free (Linde-Union Carbide, 99.999% pure, hydrocarbon-free, or equivalent). In-line moisture traps, 5A° molecular sieve adsorbent tubes, or cryogenic traps may be used to ensure purity.

7. ASSEMBLY AND CONDITIONING OF VOST SORBENT CARTRIDGES

7.1 Introduction

7.1.1 This section describes assembly of the sorbent cartridges and procedures for storage and transport of assembled cartridges.

The assembly and packing of the sorbent cartridges should be carried out in an area free of volatile organic material. This is preferably done in a laboratory in which no organic solvents are handled or stored, and in which the laboratory air is charcoal filtered. Alternatively, the assembly procedure can be conducted in a glove box or glove bag which can be purged with organic-free nitrogen.

7.2 Assembly of Tenax Cartridges

7.2.1 The Tenax, glass tubes and metal cartridge parts are cleaned and stored according to the procedures described in Section 6. Approximately 1.6 grams of Tenax is weighed and packed into the sorbent tube which has a stainless steel screen and C-clips (I/O design) or by glass wool (I/I design) in the downstream end. The Tenax is held in place by inserting a stainless steel screen and C-clips in the upstream end (I/O design) or glass wool (I/I design). The cartridges are assembled in the metal holders (Section 5.5) and leak checked by putting on one of the end caps and pressurizing the cartridge to 30 psi with organic-free nitrogen and immersing the cartridge in distilled water to check for the appearance of bubbles. Cartridges which are determined to be leak-free are then conditioned as described in Section 7.4.

7.2.2 Assembled and conditioned resin tubes of the I/O design are placed in ice water for storage and transport. Conditioned resin tubes of the I/I design are capped and placed in ice water

for storage and transport. Limited experience by VOST users for storing and transporting resin tubes of the I/I design indicates that these tubes may be stored and transported in screw capped culture tubes placed in a clean glass or metal container which contains clean charcoal. The storage container is kept cold using ice or cold pack storage. Storage containers shall be kept in an area free from sources of organic contamination. The need for these precautions is dependent upon the user's ability to maintain blank cartridges free from contamination during storage and transport.

7.3 Assembly of Tenax/Charcoal Cartridges

7.3.1 The Tenax, charcoal and metal cartridge parts are cleaned and stored according to the procedures described in Section 6. The tubes are packed with approximately a 3:1 volume ratio of Tenax and charcoal (approximately 1 gram of each). The cartridge is assembled such that the inlet side during sampling collection is Tenax, followed by a layer of charcoal at the outlet side of the sorbent cartridge. The Tenax and charcoal are held in place by the stainless steel screens and C-clips (I/O design) or by glass wool (I/I design). The glass tubes of the I/O design containing the Tenax and charcoal are then leak checked as described in Section 7.2, checked for quality assurance as described in Section 7.4, and placed in the metal carriers according to the procedures outlined in Section 5.5. The end caps are placed on the assembled cartridges, and the assembled cartridges are placed

in ice water for storage and transport as described in Section 7.2. Glass tubes of the I/I design are leak checked as described in Section 7.2, and conditioned as described in Section 7.4. The end caps are placed on the assembled cartridges, and they are placed in a suitable container for storage and transport as described in Section 7.2.

7.4 Sorbent Cartridge Quality Assurance

7.4.1 This section describes two methods which can be used to verify that the sorbent cartridges (Tenax and Tenax/charcoal) are free from background contamination prior to sample collection.

7.4.2 The gas chromatograph with flame ionization detector is calibrated using direct injection of propane standards at the appropriate concentrations. The chromatographic column shall be 1.8 m x 0.25 cm I.D., stainless steel or glass packed with 1% SP-1000 on Carbopack (60/80 mesh) or equivalent. Following assembly and leak checking of the sorbent cartridges, they are connected to a source of organic-free nitrogen. Nitrogen is passed through each trap at a flow rate of at least 30 ml/min, while the traps are heated to 200°C. The effluent from the trap is monitored with a flame ionization detector to check for emission of volatile organic compounds from the cartridge. The conditioning is continued until the amount of total chromatographable organics is below 0.2 ng as propane.

7.4.3 The gas chromatograph with flame ionization detector is calibrated by analyzing a Tenax cartridge which has been spiked with 175 ng benzene, 175 ng toluene and 150 ng bromofluorobenzene (BFB). The cartridge is spiked using the solvent-flush technique (see Part B, Section 6.2.3). The chromatographic conditions shall be the same as those described in Part B, or shall demonstrate the capability of identifying background levels of volatile POHCs with the required sensitivity. Following assembly and leak checking, the sorbent cartridge(s) is placed in the desorption heater for 10 minutes with a helium flow of 50 ml/min. The effluent from the cartridge is passed through a trap filled with glass beads which is cooled in liquid nitrogen. (If a pair of Tenax and Tenax/charcoal cartridges are monitored in a single desorption run, the Tenax/charcoal cartridge should be upstream of the Tenax cartridge.) At the end of the 10-minute desorption period, the glass bead filled trap is heated, the carrier gas flow directed to a gas chromatograph equipped with flame ionization detector and chromatographic column suitable for volatile organic analysis (see Part B, Section 4.3.2). Blank sorbent cartridges which are monitored using this technique shall contain less than 2 ng total chromatographable organics (as benzene or toluene). If in using this procedure the background exceeds 10 ng (as benzene or toluene), the cartridges must be recleaned and reanalyzed.

8. SAMPLE COLLECTION PROCEDURE

8.1 Pretest Preparation

8.1.1 All train components shall be cleaned and assembled as described in Sections 5, 6, and 7. The dry gas meter shall have

been calibrated within 30 days prior to use. All field data shall be recorded on a Field Data Sheet (or field notebook). An example of a Field Data Sheet for VOST is shown in Figure 5.

8.2 VOST Assembly

8.2.1 The VOST is assembled according to the schematic diagram in Figure 2. Cooling water is circulated to the condensers and the temperature of the cooling water shall be maintained near 0°C. The end caps of the sorbent cartridges will be placed in a clean screw capped glass container during sample collection. The condensate pot shall not be immersed in ice water.

8.3 Leak Checking

8.3.1 The train is leak checked by closing the valve at the inlet to the first condenser and pulling a vacuum equivalent to 10 inches Hg (250 mm Hg) above the system's operating pressure. The traps and condensers are isolated from the pump and the leak rate noted. The system shall hold at 10 inches Hg above the system operating pressure with no discernible leakage (pressure increase of less than 0.1 inches Hg/min). If the leak check does not meet specifications, the cause of the problem must be identified and corrected and leak check repeated. After leak checking, the train should be returned to atmospheric pressure by attaching a charcoal filled tube to the isolation valves above the first condenser and opening the valve to admit air to the train through the charcoal filter. These procedures will minimize contamination of VOST train components by excessive exposure to the fugitive emissions at hazardous waste incinerator sites.

Plant _____

Date _____

Location _____

Operator _____

Stack No. _____

Probe No. _____

VOGT No. _____

Rotameter No. _____

Dry Gas Meter No. _____

Field black I.D.: Tenax
Tenax/Charcoal

[illegible]

Condensate Samples:

Run No. .	Sample I.D.	Comments
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		

NOTES: a heading should be tabulated at the beginning of a run and every five minutes thereafter. Before a sample collection on one pair of Tensar and Tensar/charcoal traps.

FIGURE 5. VOST FIELD DATA SHEET¹

8.3.2 After leak checking but before the initiation of sample collection, the probe shall be purged with stack gas. This can be accomplished by attaching a pump to the isolation valve above the first condenser and drawing stack gas through the probe via the isolation valve, so that at the initiation of sample collection the probe is purged of ambient air.

8.4 Sample Collection

8.4.1 Prior to the initiation of sample collection, the probe shall be located in the stack at a point of average stack gas velocity and temperature. (These values can be determined using the procedures described in References 6 and 7.) Care should be exercised in the location of the probe in the stack to minimize effects of dilution air which may enter the stack through the sampling port and thereby impair the collection of a representative sample of the stack gas.

8.4.2 After leak checking (see Section 8.3.1), sample collection is accomplished by opening the valve at the inlet to the first condenser, turning on the pump, and sampling at a rate of 1 liter/minute for 20 minutes. The volume of sample for any pair of traps shall not exceed 20 liters. The temperature of the gas stream at the inlet to the first sorbent cartridge must be maintained at or below 20°C during sample collection (see Section 5.6.2).

8.4.3 After the collection of 20 liters of sample, the train is leak tested using the procedures described in Section 8.3. If this post leak test criterion is not met, the samples shall not be analyzed. If leak check criterion is met, the train is returned to atmospheric pressure as described in Section 8.3.1, the two sorbent cartridges removed, the end caps replaced, and the cartridges returned to a suitable container for storage and transport until analysis (see also Section 7.2.2).

8.4.4 In some cases, there may be a requirement to analyze the aqueous condensate. This situation may arise for water soluble volatile organic compounds. For these situations, preliminary laboratory evaluation of the sampling and recovery efficiency (including the purging efficiencies of the compounds) must be performed (Part B, Sections 7 and 11). Sampling and analysis procedures for water soluble volatile organics are currently being developed. In this case, when a pair of sorbent cartridges is changed, duplicate samples of the aqueous condensate should be poured into 40 ml glass vials equipped with plastic screw caps (Pierce 13075 or equivalent), and Teflon-faced silicon septa (Pierce 12722 or equivalent). If insufficient condensate is available, the vials shall be topped off with reagent water. The vials shall be carefully filled just to overflowing so that no air bubbles pass through the sample as the vial is being filled. The vial shall be sealed so that no air bubbles are entrapped in it. Vials shall be stored and transported at ice or cold pack temperature.

8.4.5 A new pair of cartridges is placed in the VOST. The VOST leak checked as described in Section 8.3 and the sample collection process repeated as described above. Sample collection continues until six pairs of cartridges have been taken (see Section 2.3). A maximum of six pairs of cartridges may be taken over a 2-hour sampling period (see Section 2.3).

8.4.6 All sample cartridges shall be stored on cold packs or ice until ready for analysis.

8.5 Field, Trip and Laboratory Blanks/Aqueous Field Blanks

8.5.1 Field Blanks - Blank Tenax and Tenax/charcoal cartridges are taken to the sampling site and the end caps removed for the period of time required (approximately 5 minutes) to exchange two pairs of cartridges on VOST. After the two VOST cartridges have been exchanged, the end caps are replaced on the blank Tenax and Tenax/charcoal tubes. These are returned to appropriate storage (see Section 7.2.2) and analyzed with the sample cartridges. At least one pair of field blanks (one Tenax, one Tenax/charcoal) shall be included with each six pairs of sample cartridges collected (or for each field trial using VOST to collect volatile POHCs). It is advisable to use two pairs of field blanks for each six pairs of cartridges collected.

8.5.2 Trip Blanks - At least one pair of blank cartridges (one Tenax, one Tenax/charcoal) shall be included with the shipment of cartridges to a hazardous waste incinerator site. These trip

blanks will be treated as any other cartridges except that the end caps will not be removed during storage at the site. This pair of cartridges will be analyzed to monitor potential contamination which may occur during storage and shipment. One user (5) recommended including one pair of trip blanks for each VOST run conducted during a trial burn to obtain a more meaningful basis for blank correction of sample cartridges (Part B, Section 12.1.2).

8.5.3 Laboratory Blanks - One pair of blank cartridges (one Tenax, one Tenax/charcoal) will remain in the laboratory using the method of storage for field samples. If the field and trip blanks contain high concentrations of contaminants (e.g., greater than 2 ng of a particular POHC), the laboratory blank shall be analyzed in order to identify the source of contamination.

8.5.4 Aqueous Field Blanks - If the aqueous condensate is to be analyzed for volatile POHCs, an aqueous field blank is required. This consists of duplicate samples of reagent water placed in vials described in Section 8.4.3. These vials shall be stored and shipped in the same way as empty vials/aqueous condensate samples, and should be analyzed at the same time as the aqueous condensate samples. Additionally, a reagent water sample (prepared as above) will be retained in storage in the laboratory. If the analysis of aqueous field blanks shows the presence of POHCs, the corresponding laboratory blank shall be analyzed to verify that the residual contamination is not due to contamination of the aqueous field blanks at the time of preparation or during storage in the laboratory.

PART B
PROTOCOL FOR ANALYSIS OF SORBENT CARTRIDGES
FROM VOLATILE ORGANIC SAMPLING TRAIN

1. SCOPE AND APPLICABILITY

1.1 This method covers the analysis of volatile POHCs collected on Tenax and Tenax/charcoal sorbent cartridges using a VOST. Much of the description for purge-trap-desorb (P-T-D) GC/MS analysis is included in References 8 and 9. Since the majority of gas streams sampled using VOST will contain a high concentration of water, the analytical method is based on the quantitative thermal desorption of volatile POHCs from the Tenax and Tenax/charcoal cartridges and analysis by P-T-D GC/MS in order to minimize the effects of water on the analysis. This method is applicable to organic compounds with boiling points between 30° and 100°C. Many compounds with boiling points below 30°C and between 100° and 150°C, may be efficiently collected and analyzed using this method. However, laboratory evaluation of the collection and recovery efficiency for compounds with boiling points outside the range of 30° to 100°C (or those for which no VOST data are available) shall be performed (see Section 7).

1.2 This method is applicable to the analysis of Tenax and Tenax/charcoal cartridges used to collect volatile POHCs from wet stack gas effluents from hazardous waste incinerators.

1.3 The sensitivity of the analytical method for a particular volatile POHC depends on the level of interferences, the presence of detectable levels of volatile POHCs in blanks, and the ability to purge the volatile POHCs from water. The target detection limit for the method is $0.1 \mu\text{g}/\text{m}^3$ ($0.1 \text{ ng}/\text{l}$) in the stack gas. This corresponds to 2.0 ng adsorbed on a single pair of Tenax and Tenax/charcoal cartridges. Since 2 ng of a POHC may not be detectable by P-T-D GC/MS analysis, the method is designed to permit thermal desorption of up to five pairs of Tenax and Tenax/charcoal cartridges onto a single pair for analysis in order to achieve the target detection limit of the method. For a POHC present in the gaseous effluent at a concentration of $0.1 \mu\text{g}/\text{m}^3$ ($0.1 \text{ ng}/\text{l}$), the desorption of multiple pairs of cartridges onto a single pair for analysis can provide a total of 10 ng for analysis by P-T-D GC/MS.

1.4 This method is recommended for use only by experienced analytical chemists or under the close supervision of such qualified persons.

2. SUMMARY OF METHOD

2.1 A schematic diagram of the analytical system is shown in Figure 6. Pairs of the sorbent cartridges are spiked with an internal standard and thermally desorbed for 10 minutes at 180°C with organic-free nitrogen gas (at a flow rate of $100 \text{ ml}/\text{min}$), bubbled through 5 ml of organic-free water, and trapped on an analytical sorbent trap. After the 10-minute desorption, the




FIGURE 6
SCHEMATIC DIAGRAM OF TRAP DESORPTION
/ANALYSIS SYSTEM

analytical sorbent trap is rapidly heated to 180°C with the carrier gas flow reversed so that the effluent flow from the analytical trap is directed into the GC/MS. The volatile POHCs are separated by temperature programmed gas chromatography and detected by low resolution mass spectrometry. The concentrations of volatile POHCs are calculated using the internal standard technique. To achieve increased sensitivity, multiple pairs of cartridges (up to five pairs) may be desorbed onto a single pair of Tenax and Tenax/charcoal cartridges. The resulting pair is analyzed by P-T-D GC/MS.

3. PRECISION AND ACCURACY

3.1 The overall accuracy of sample collection and analysis using VOST has been determined in laboratory evaluations to average ± 50 percent for analysis of three replicate cartridges (5). These values may be revised as further evaluation of VOST performance is conducted.

3.2 The precision for the internal standard response (area) should be 20 percent during any given analysis period at a particular multiplier voltage of the mass spectrometer.

4. APPARATUS

4.1 Thermal Desorption Unit

4.1.1 The thermal desorption unit (Nutech Corporation Model 320 or equivalent) shall be capable of thermally desorbing the sorbent

resin tubes. It shall be capable of rapidly heating the tubes to $180^{\circ}\text{C} \pm 10^{\circ}\text{C}$ with flow of organic-free nitrogen through the tubes.

4.2 Purge and Trap Unit

4.2.1 The purge and trap unit consists of three separate pieces of equipment: the sample purger, analytical sorbent trap and the desorber. It should be capable of meeting all requirements of Sections 5.2 thru 5.2.4 of EPA Method 624 for analysis of purgeable organic compounds from water (8, 9). The analytical trap as specified in EPA Method 624 consists of 3% SP-2100, Tenax, silica gel, charcoal. Some users have found that improved performance can be achieved using only Tenax and charcoal in the analytical sorbent trap (5).

4.3 GC/MS System

4.3.1 Gas Chromatograph - An analytical system complete with a temperature programmable GC suitable for on-column injection, and all required accessories including syringes, analytical columns, and gases.

4.3.2 Column - Column dimensions shall be 1.8 m long by 0.25 cm I.D., stainless steel or glass, packed with 1% SP-1000 on Carbo-pack B (60/80 mesh) or equivalent.

4.3.3 Mass Spectrometer - Capable of scanning from 20 to 260 amu every 7 seconds or less, utilizing 70 volts (nominal) electron energy in the electron impact ionization mode and producing a mass

spectrum which meets all criteria described in Method 624 when 50 ng of 4-bromofluorobenzene (BFB) is injected through the GC inlet.

4.3.4 GC/MS Interface - Any GC to mass spectrometer interface that gives acceptable calibration points at 50 ng or less per injection for each of the parameters of interest and achieves all performance criteria of Method 624 may be used. GC to mass spectrometer interfaces constructed of all-glass or glass-lined materials are recommended. Glass can be deactivated by silanizing with dichloro-dimethylsilane.

4.3.5 Data System - A computer system must be interfaced to the mass spectrometer that allows the continuous acquisition and storage on machine readable media of all mass spectra obtained throughout the duration of the chromatographic program. The computer must have software that allows searching any GC/MS data file for ions of a specified mass and plotting such ion abundances versus time or scan number. This type of plot is defined as an Extracted Ion Current Profile (EICP). Software must also be available that allows integrating the abundance in any EICP between specified time or scan number limits.

5. REAGENTS

5.1 Reagent Water

5.1.1 Reagent water is defined as water in which an interferent is not observed at the detection limit of the parameters of interest.

5.1.2 Reagent water may be generated by passing tap water through a carbon filter bed containing about 450 grams of activated carbon (Calgon Corporation, Filtrasorb-300 or equivalent).

5.1.3 Reagent water may also be prepared by boiling distilled water for 15 minutes. Subsequently, while maintaining the temperature at 90°C, bubble a contaminant-free, inert gas through the water for one hour. While still hot, the water should be transferred to a narrow mouth, screw cap bottle and sealed with a Teflon lined septum and cap.

5.1.4 Other methods which can be shown to produce reagent water can be used.

5.2 Analytical Trap Reagents

- a) Tenax (60/80 mesh) - Chromatographic grade or equivalent
- b) Methyl silicone packing - 3% OV-1 on Chromosorb W (60/80 mesh) or equivalent
- c) Silica gel, Davison Chemical (35/00 mesh), Grade 15 or equivalent
- d) Charcoal, petroleum based (SKC Lot 104 or equivalent) (see Section 6.2 in Part A)

5.3 Stock Standard Solution

5.3.1 Stock standard solutions will be prepared from pure standard materials or purchased certified solutions. The stock standards should be prepared in methanol using assayed liquids or gases as appropriate. Because of the toxicity of some of the organohalides, primary dilutions of these materials should be prepared in a hood. A NIOSH/MESA approved toxic gas respirator should be used when the analyst handles high concentrations of such materials.

5.3.2 Fresh standards should be prepared weekly for volatile POHCs with boiling points of $<30^{\circ}\text{C}$. All other standards must be replaced monthly, or sooner if comparison with check standards indicates a problem.

5.4 Secondary Dilution Standards

5.4.1 Using stock standard solutions, prepare secondary dilution standards in methanol which contain the compounds of interest either singly or mixed together, and at concentrations such that the desorbed calibration standards will bracket the working range of the analytical system.

5.5 Bromofluorobenzene (BFB) Standard

5.5.1 Prepare a 25 $\mu\text{g/ml}$ solution of BFB in methanol.

5.6 Deuterated (d_6) Benzene Standard

5.6.1 Prepare a 25 $\mu\text{g/ml}$ solution in methanol.

6. CALIBRATION

6.1 Assembly of P-T-D Device

6.1.1 Assemble a purge and trap desorption device (P-T-D) which meets all the requirements of Section 10.2 of this protocol and Section 5.2 of USEPA Method 624 (3).

6.1.2 Connect the thermal desorption device to the purge and trap device. Calibrate the P-T-D GC/MS system using the internal standard technique (Section 6.2).

6.2 Internal Standard Calibration Procedure

6.2.1 This approach requires the use of deuterated benzene as the internal standard for these analyses. Other internal standards may be proposed for use in certain situations. The important criteria for choosing a particular compound as an internal standard are that it be similar in analytical behavior to the compounds of interest, and it can be demonstrated that the measurement of the internal standard is not affected by method or matrix interferences. Other internal standards which have been used are d₁₀-ethylbenzene and d₄-1,2-dichloroethane. Several users add 50 ng of BFB to all sorbent cartridges (in addition to one or more internal standards) to provide continuous monitoring of the GC/MS performance relative to BFB.

6.2.2 Prepare calibration standards at a minimum of three concentration levels for each analyte of interest. The calibration standards are prepared by spiking a blank Tenax or Tenax/charcoal

cartridge with a methanolic solution of the calibration standards (including 50 ng of the internal standard, such as deuterated benzene) using the flash evaporation technique.

6.2.3 The cartridge shall be mounted in the gas chromatograph so that the carrier gas enters the cartridge in the same direction as during sample collection (which is opposite to the direction of gas flow during P-T-D GC/MS analysis). The glass cartridge should be attached to the injection port of a gas chromatograph. The injector temperature is maintained at 160°C, and the carrier gas flow through the cartridges should be maintained at about 50 ml/min.

6.2.4 The flash evaporation technique requires filling the needle of a 5.0 (µl) syringe with clean methanol and drawing air into the syringe until the tip of the plunger reaches the 1.0 µl mark. This is followed by drawing a methanolic solution of the calibration standards (containing 25 µg/µl of the internal standard) until the tip of the plunger reaches the 3.0 µl mark. The contents of the syringe should be slowly expelled through the gas chromatograph injection port over about 15 seconds. After 25 seconds have elapsed, the gas flow through the cartridge should be shut off, the syringe removed, and the cartridge analyzed by the P-T-D GC/MS procedure outlined in Section 10.2. The total flow of gas through the cartridges during addition of calibration standard to blank cartridges, or internal standards to sample cartridges, should be 25 ml or less to avoid breakthrough of volatile sample components.

6.2.5 Analyze each calibration standard on both Tenax and Tenax/charcoal cartridges according to Section 10. The calibration procedures shall be identical to those used for analysis of sample cartridges. If cartridges are analyzed separately, then the Tenax and Tenax/charcoal cartridges must be calibrated separately. The direction of carrier gas flow through the cartridges during the desorption step should be opposite from the gas flow through the cartridge during sample collection so the inlet side of the cartridge during sample collection becomes the outlet side during P-T-D analysis. Tabulate the area response of the characteristic ions of each analyte against the concentration of the internal standard and calculate response factor (RF) for each compound using Equation 1.

$$RF = A_s C_{is} / A_{is} C_s \quad (1)$$

where A_s = Area of the characteristic ion for the analyte to be measured

A_{is} = Area of the characteristic ion for the internal standard

C_{is} = Amount (ng) of the internal standard

C_s = Amount (ng) of the volatile POHC in calibration standard

If the RF value over the working range is a constant (<10% RSD), the RF can be assumed to be invariant and the average RF can be used for calculations. Alternatively, the results can be used to plot a calibration curve of response ratios, A_s/A_{is} versus RF.

6.2.6 The working calibration curve or RF must be verified on each working day by the measurement of one or more of the calibration standards. If the response varies by more than $\pm 25\%$, new calibration standards must be prepared and analyzed.

7. QUALITY CONTROL

7.1 Each laboratory that uses this method is required to operate a formal quality control program. The minimum requirements of this program consist of an initial demonstration of laboratory capability and the analysis of blank Tenax and Tenax/charcoal cartridges spiked with the analytes of interest. The laboratory shall demonstrate collection and/or recovery efficiencies for compounds with boiling points outside the 30° to 100°C range, which meet the method criteria, prior to field use of the VOST (Part A, Section 3.2). The laboratory is required to maintain performance records to define the quality of data which are generated. Ongoing performance checks must be compared with established performance criteria to determine if results are within the expected precision and accuracy limits of the method. (Note: NBS traceable audit cylinders are being developed by Research Triangle Institute under the direction of USEPA-EMSL, Research Triangle Park, NC. The cylinders may be used for performance trials and evaluation of collection and recovery efficiencies in lieu of the methods specified in this section.)

7.1.1 Before performing any analyses, the analyst must demonstrate the ability to generate acceptable precision and accuracy with this method. This ability is established as described in Section 7.2.

7.1.2 Recovery data for compounds boiling between 100° and 150°C must be provided which meets the method criteria (see Section 7.2.2). Laboratory evaluation is required in lieu of that data. The method of evaluation is that specified in Section 7.2 with the exception that it is not required to pull 20 liters of organic-free nitrogen through the sorbent cartridges.

7.1.3 Laboratory evaluation of collection and recovery efficiencies shall be performed for compounds with boiling points below 30°C. Due to the possibility of sample breakthrough and poor recovery of the sample from the charcoal, the evaluation shall be comparable to that described in Reference 5. A gas stream containing the POHC shall be generated and sampled using the VOST. The sampling rate for the laboratory evaluation shall be the same as that proposed for field application. The laboratory evaluation must meet the precision and accuracy criteria described in Section 7.2.2.

7.1.4 The laboratory must spike all Tenax and Tenax/charcoal cartridges with the internal standard(s) to monitor continuing laboratory performance. This procedure is described in Section 6.2.

7.2 To establish the ability to generate acceptable accuracy and precision, the analyst must spike blank Tenax and Tenax/charcoal with the analytes of interest at two concentrations in the working range by the flash vaporization technique discussed in Sections 6.2.3 and 6.2.4. The cartridges are removed from the gas chromatograph and connected to a source of organic-free nitrogen. The cartridges sample 20 liters of nitrogen at a flow rate equivalent to that proposed for field use of VOST.

7.2.1 The average response factor (RF) and the standard deviation (S) for each must be calculated.

7.2.2 The average recovery and standard deviation must fall within the expected range for determination of volatile POHCs using this method. The expected range for recovery (indicative of accuracy) of volatile POHCs using this method is ± 50 percent. The expected standard deviation is 25 percent.

7.3 The analyst must calculate method performance criteria for the internal standard.

7.3.1 Calculate upper and lower control limits for method performances using the average area response (A) and standard deviation (S) for internal standard:

$$\text{Upper Control Limit (UCL)} = A + 3S$$

$$\text{Lower Control Limit (LCL)} = A - 3S$$

The UCL and LCL can be used to construct control charts which are useful in observing trends in performance. The control limits must be replaced by method performance criteria as they become available from the USEPA.

7.4 Each day, the analyst must demonstrate through analysis of blank Tenax and Tenax/charcoal cartridges and reagent water that interferences from the analytical system are under control.

8. SAMPLE COLLECTION, PRESERVATION AND HANDLING

8.1 The requirements for sample collection, preservation, and handling are described in Part A of this protocol.

9. DAILY GC/MS PERFORMANCE TESTS

9.1 The daily GC/MS performance tests required for this method are described in Section 10 of EPA Method 624 (9). The key abundance criteria for BFB which must be met before any samples are analyzed are listed below. This can be done by injecting 50 ng of BFB directly on the column or by adding 50 ng of BFB to a blank Tenax sorbent cartridge (see Sections 6.2.3 and 6.2.4) and desorbing this cartridge according to the procedures described in Section 10. The latter procedure is preferred when all sample sorbent cartridges are spiked with BFB in addition to one or more of the internal standards discussed in Section 6.2.1.

BFB KEY ION ABUNDANCE CRITERIA

<u>Mass</u>	<u>Ion Abundance Criteria</u>
50	15 to 40% of mass 95
75	30 to 60% of mass 95
95	Base Peak, 100% Relative Abundance
96	5 to 9% of mass 95
173	<2% of mass 174
174	>50% of mass 95
175	5 to 9% of mass 174
176	>95% but <101% of mass 174
177	5 to 9% of mass 176

10. SAMPLE DESORPTION AND GAS CHROMATOGRAPHY

10.1 The P-T-D GC/MS procedures are those described in Section 11 of Method 624 (9) with the addition of the procedure described in Section 10.2 for desorption of Tenax and Tenax/charcoal cartridges.

10.2 The schematic of the P-T-D GC/MS system is shown in Figure 6. The sample cartridge is placed in the thermal desorption apparatus (Nutech 320 or equivalent) and desorbed in the P-T-D system by heating to 180°C for 10 minutes. Sample cartridges may be desorbed in pairs. However, if the analyte concentrations are anticipated to be sufficiently high to saturate the GC/MS when desorbed in pairs, consideration should be given to individual analysis of cartridges. The desorbed components pass into the bottom of the water column, are purged from the water and

collected on the analytical sorbent trap. After the 10-minute desorption period, the compounds are desorbed from the analytical sorbent trap into the GC/MS system according to the procedures described in Section 11 of Method 624.

11. AQUEOUS CONDENSATE

11.1 Analysis of aqueous condensate samples should be performed according to the procedures described in References 8 and 9. If the volatile POHCs of interest are water soluble, it is necessary to demonstrate that this method is capable of recovery of the volatile POHCs of interest using Method 624. This can be accomplished by P-T-D GC/MS analysis of reagent water which has been fortified with the analytes of interest.

11.2 If adequate recovery of water soluble volatile POHCs cannot be achieved using the procedures described in References 8 and 9, alternative methods for analysis, such as direct aqueous injection, may be required. If an alternative analytical method is used, method performance must be documented by analysis of laboratory reagent water which has been fortified with the volatile POHCs of interest.

11.3 Methods for analysis of water soluble volatile POHCs in aqueous condensate are currently under development.

12. QUALITATIVE IDENTIFICATION

12.1 The qualitative identification procedure of volatile POHCs using this protocol is described in Section 12 of Method 624 (9).

13. CALCULATIONS

13.1 When an analyte has been qualitatively identified, quantification should be based on the integrated abundance from the EICP of the primary characteristic ion chosen for that analyte. If the sample produces an interference for the primary characteristic ion, a secondary characteristic ion should be used.

13.1.1 Using the internal standard calibration procedure, the amount of analyte in the sample cartridge is calculated using the response factor (RF) determined in Section 6.2.5 and Equation 2.

$$\text{Amount of POHC} = A_S C_{IS} / A_{IS} RF \quad [2]$$

where A_S = Area of the characteristic ion for the analyte
to be measured

A_{IS} = Area for the characteristic ion of the internal
standard

C_{IS} = Amount (ng) of internal standard

13.1.2 The choice of methods for evaluating data collected using VOST for incinerator trial burns is a regulatory decision. The procedures used extensively by one user are outlined below (10).

13.1.3 The total amount of the POHCs of interest collected on a pair of traps should be summed. These values should then be blank corrected. Guidelines for blank correction of sample cartridges are outlined below.

13.1.3.1 After all blanks (field and trip) are analyzed, a paired t-test should be used to determine whether trip blanks are significantly different from field blanks. If no difference is found, then the mean and standard deviation of the combined field and trip blanks for each POHC of interest is calculated, and that value is used as the blank.

13.1.3.2 If, using the paired t-test, the field and trip blanks are determined to be different, then the field blank (or the mean of multiple field blanks) associated with a particular run should be used as the blank value for that particular run.

13.1.3.3 If an individual field blank is used as the blank value for a particular run, the VOST user must evaluate whether this blank is different from sample cartridges associated with this blank. Although no specific criteria are offered here for guidance in this case, specific criteria for use of individual field blanks for blank correction will be developed as more data for use of VOST becomes available. This situation can be alleviated by including two field blanks (i.e., two blank Tenax and two blank Tenax/charcoal cartridges) per run.

13.1.4 Next, for each sample/POHC combination, a determination must be made as to whether a particular sample is significantly different from the associated blank. If the mean of the trip and field blanks is used, then a sample is different from the blank if:

(measured sample value)-(mean blank value) ≥ 3

x blank standard deviation.

If the sample is determined to be different from the blank according to the above criteria, then the emission value of a particular POHC is blank corrected by subtracting the mean blank value (as defined in Section 12.1.3) from the measured sample value. (If an individual field blank is used as the blank value, the above criteria do not apply.)

13.1.5 If, according to the above procedures, the sample cannot be distinguished from the blank (i.e., for a given POHC there is a high sample value and high blank value or there is a low sample value and low blank value), the measured sample value is not blank corrected. In this case, the measured sample value is used to calculate a maximum emission value (and therefore a minimum DRE value) for that particular run.

13.1.6 The observation of high concentrations of POHCs of interest in blank cartridges indicates possible residual contamination of the sorbent cartridges during shipment and use at the site. Data which fall in this category (especially data indicating high concentrations of POHCs in blank sorbent cartridges) should be qualified with regard to validity, and blank data should be reported separately. The applicability of data of this type to the determination of DRE is a regulatory decision. Continued observation of high concentrations of POHCs in blank sorbent cartridges

indicates that procedures for cleanup, monitoring, shipment and storage of sorbent cartridges by a particular user, be investigated to eliminate this problem.

13.1.7 After blank corrections have been made, the amounts of individual POHCs on each sorbent cartridge used for a given run is summed and divided by the volume of gas sampled to obtain the concentration of each POHC in the stack gas.

13.1.8 If any internal standard recoveries fall outside the control limits established in Section 7.3.1, data for all analytes determined for that cartridge(s) must be qualified with the observation.

14. METHOD PERFORMANCE

14.1 The method detection limit, average recoveries and standard deviation of the average recoveries of the analytes determined using this method have not yet been established. The method performance will be documented as more data become available.

REFERENCES
(For A and B)

- 1) Resource Conservation and Recovery Act, Subtitle [3001-3013, 42 USC 6921-6934 (1976) and Supplement IV (1980)].
- 2) Vogel, G., et al. "Guidance Manual for Hazardous Waste Incineration Permits," EPA-68-01-0092, SW-966, NTIS PB-84/100577, July 1982.
- 3) Code of Federal Regulations, Title 40, Part 60, Appendix A, 1980.
- 4) Harris, J. C., et al. "Sampling and Analysis Methods for Hazardous Waste Combustion," EPA 600/8-84-002, February 1984.
- 5) Jungclaus, G., et al. "Development of a Volatile Organic Sampling Train (VOST)," Presented at 9th Annual Research Symposium, Land Disposal, Incineration and Treatment of Hazardous Wastes, Ft. Mitchell, KY, May 2-4, 1983.
- 6) Federal Register, 42, 41758-41768, August 18, 1977.
- 7) USEPA. Quality Assurance Handbook for Air Pollution Measurement Systems, Vol. III, Office of Research and Development, Environmental Monitoring and Support Laboratory, Research Triangle Park, NC.
- 8) Federal Register, 44, 69464, December 3, 1979.
- 9) Longbottom, J. and J. Lichtenberg, eds., "Methods for Organic Chemical Analysis of Municipal and Industrial Wastewater; Test Methods," Method 624, EPA-600/4-82-057, 1982.
- 10) Trenholm, A. Midwest Research Institute, Personal Communication, August 5, 1983.

TECHNICAL REPORT DATA (Please read instructions on the reverse before completing)			
1. REPORT NO. EPA-600/8-84-007		2. RECIPIENT'S ACCESSION NO.	
4. TITLE AND SUBTITLE Protocol for the Collection and Analyses of Volatile POHCs Using VOST		5. REPORT DATE March 1984	
7. AUTHOR(S) Earl M. Hansen		6. PERFORMING ORGANIZATION CODE	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Envirodyne Engineers, Inc. 12161 Lackland Road St. Louis, Missouri 63416		8. PERFORMING ORGANIZATION REPORT NO.	
12. SPONSORING AGENCY NAME AND ADDRESS EPA, Office of Research and Development Industrial Environmental Research Laboratory Research Triangle Park, NC 27711		10. PROGRAM ELEMENT NO.	
		11. CONTRACT/GRANT NO. 68-02-3697, Task 3	
		13. TYPE OF REPORT AND PERIOD COVERED Task Final; 4/83-2/84	
		14. SPONSORING AGENCY CODE EPA/600/13	
15. SUPPLEMENTARY NOTES IERL-RTP project officer is Robin M. Anderson, Mail Drop 62, 919/541-7607.			
16. ABSTRACT The document is a state-of-the-art operating protocol for sampling and analysis of volatile organic constituents of flue gas from hazardous waste incinerators or other similar combustor systems using the Volatile Organic Sampling Train (VOST). It is intended to be used for guidance by personnel of the regulatory groups, personnel associated with engineering research and development, and the regulated community. The document is in two parts. Part A describes the key components of the train, the procedures for preparing the sorbent materials, and procedures for sample collection using the VOST. Part B describes the procedures for analyzing VOST sorbent cartridges for volatile principal organic hazardous constituents (POHCs) using purge-trap-desorb gas chromatography/mass spectrometry (P-T-D/GC/MS). Quality control procedures are presented in both parts.			
17. KEY WORDS AND DOCUMENT ANALYSIS			
a. DESCRIPTORS		b. IDENTIFIERS/OPEN ENDED TERMS	c. COSATI Field/Group
Pollution	Hazardous Materials	Pollution Control	13B
Flue Gases		Stationary Sources	21B 11G
Organic Compounds	Toxicity	VOST	07C 06T
Analyzing			14B
Sampling			14G
Collection			
19. SECURITY CLASS. (This Report)		21. NO. OF PAGES	
Unclassified		60	
20. SECURITY CLASS. (This page)		22. PRICE	
Unclassified			
23. STATEMENT Release to Public			

WESTON

NATIONAL INSTITUTE
FOR OCCUPATIONAL SAFETY AND HEALTH
METHOD NO. P & CAM 127

6060A

ORGANIC SOLVENTS IN AIR

Physical and Chemical Analysis Branch

Analytical Method

Analyte:	Organic Solvents (See Table 1)	Method No:	P&CAM 127
Matrix:	Air	Range:	For the specific compound, refer to Tables I&II
Procedure:	Adsorption on charcoal desorption with carbon disulfide, GC		
Date Issued:	9/15/72	Precision:	10.5% RSD
Date Revised:	7/15/74	Classification:	See Table 1

1. Principle of the Method

- 1.1 A known volume of air is drawn through a charcoal tube to trap the organic vapors present.
- 1.2 The charcoal in the tube is transferred to a small, graduated test tube and desorbed with carbon disulfide.
- 1.3 An aliquot of the desorbed sample is injected into a gas chromatograph.
- 1.4 The area of the resulting peak is determined and compared with areas obtained from the injection of standards.

2. Range and Sensitivity

The lower limit in mg/sample for the specific compound at 16 x 1 attenuation on a gas chromatograph fitted with a 10:1 splitter is shown in Table 1. This value can be lowered by reducing the attenuation or by eliminating the 10:1 splitter.

3. Interferences

- 3.1 When the amount of water in the air is so great that condensation actually occurs in the tube, organic vapors will not be trapped. Preliminary experiments indicate that high humidity severely decreases the breakthrough volume.
- 3.2 When two or more solvents are known or suspected to be present in the air, such information should be used in suspected identification, should be transmitted with the sample; since interferences in polarity, one may displace another from the charcoal.

- 3.3 It must be emphasized that any compound which has the same retention time as the specific compound under study at the operating conditions described in this method is an interference. Hence, retention time data on a single column, or even on a number of columns, cannot be considered as proof of chemical identity. For this reason it is important that a sample of the bulk solvent(s) be submitted at the same time so that identity(ies) can be established by other means.
- 3.4 If the possibility of interference exists, separation conditions (column packing, temperatures, etc.) must be changed to circumvent the problem.

4. Precision and Accuracy

- 4.1 The mean relative standard deviation of the analytical method is 8%. (Ref. 11.4).
- 4.2 The mean relative standard deviation of the analytical method plus field sampling using an approved personal sampling pump is 10% (Ref. 11.4). Part of the error associated with the method is related to uncertainties in the sample volume collected. If a more powerful vacuum pump with associated gas-volume integrating equipment is used, sampling precision can be improved.
- 4.3 The accuracy of the overall sampling and analytical method is 10% (NIOSH's unpublished data) when the personal sampling pump is calibrated with a charcoal tube in the line.

5. Advantages and Disadvantages of the Method

- 5.1 The sampling device is small, portable, and involves no liquids. Interferences are minimal, and most of those which do occur can be eliminated by altering chromatographic conditions. The tubes are analyzed by means of a quick, instrumental method. The method can also be used for the simultaneous analysis of two or more solvents suspected to be present in the same sample by simply changing gas chromatographic conditions from isothermal to a temperature-programmed mode of operation.
- 5.2 One disadvantage of the method is that the amount of sample which can be taken is limited by the number of milligrams that the tube will hold before overloading. When the sample value obtained for the backup section of the charcoal trap exceeds 25% of that found on the front section, the possibility of sample loss exists. During sample storage the more volatile compounds will migrate throughout the tube until equilibrium is reached (50% of the sample on the backup section).

- 5.3 Furthermore, the precision of the method is limited by the reproducibility of the pressure drop across the tubes. This drop will affect the flow rate and cause the volume to be imprecise, because the pump is usually calibrated for one tube only.

6. Apparatus

- 6.1 An approved and calibrated personal-sampling pump for personal samples. For an area sample any vacuum pump whose flow can be determined accurately at 1 liter per minute or less.
- 6.2 Charcoal tubes: glass tube with both ends flame sealed, 7 cm long with a 6-mm O.D. and a 4-mm I.D., containing 2 sections of 20/40 mesh activated charcoal separated by a 2-mm portion of urethane foam. The activated charcoal is prepared from coconut shells and is fired at 600°C prior to packing. The absorbing section contains 100 mg of charcoal, the backup section 50 mg. A 3-mm portion of urethane foam is placed between the outlet end of the tube and the backup section. A plug of silylated glass wool is placed in front of the absorbing section. The pressure drop across the tube must be less than one inch of mercury at a flow rate of 1 lpm.
- 6.3 Gas chromatograph equipped with a flame ionization detector.
- 6.4 Column (20 ft x 1/8 in) with 10% FFAP stationary phase on 80/100 mesh, acid-washed DMCS Chromosorb W solid support. Other columns capable of performing the required separations may be used.
- 6.5 A mechanical or electronic integrator or a recorder and some method for determining peak area.
- 6.6 Glass stoppered micro tubes. The 2.5-ml graduated microcentrifuge tubes are recommended.
- 6.7 Hamilton syringes: 10 μ l, and convenient sizes for making standards.
- 6.8 Pipets: 0.5 ml delivery pipets or 1.0 ml type graduated in 0.1 ml increments.
- 6.9 Volumetric flasks: 10 ml or convenient sizes for making standard solutions.

7. Reagents

- 7.1 Spectroquality carbon disulfide (Matheson Coleman and Bell)

7.2 Sample of the specific compound under study, preferably chromatquality grade.

7.3 Bureau of Mines Grade A helium.

7.4 Prepurified hydrogen.

7.5 Filtered compressed air.

8. Procedure

8.1 Cleaning of Equipment. All glassware used for the laboratory analysis should be detergent washed and thoroughly rinsed with tap water and distilled water.

8.2 Calibration of Personal Pumps. Each personal pump must be calibrated with a representative charcoal tube in the line. This will minimize errors associated with uncertainties in the sample volume collected.

8.3 Collection and Shipping of Samples

8.3.1 Immediately before sampling, the ends of the tube should be broken to provide an opening at least one-half the internal diameter of the tube (2mm).

8.3.2 The smaller section of charcoal is used as a back-up and should be positioned nearest the sampling pump.

8.3.3 The charcoal tube should be vertical during sampling.

8.3.4 Air being sampled should not be passed through any hose or tubing before entering the charcoal tube.

8.3.5 The flow, time, and/or volume must be measured as accurately as possible. The sample should be taken at a flow rate of 1 lpm or less to attain the total sample volume required. The minimum and maximum sample volumes that should be collected for each solvent are shown in Table 1. The minimum volume quoted must be collected if the desired sensitivity is to be achieved.

8.3.6 The temperature and pressure of the atmosphere being sampled should be measured and recorded.

8.3.7 The charcoal tubes should be capped with the supplied plastic caps immediately after sampling. Under no circumstances should rubber caps be used.

- 8.3.8 One tube should be handled in the same manner as the sample tube (break, seal, and transport), except that no air is sampled through this tube. This tube should be labeled as a blank.
- 8.3.9 Capped tubes should be packed tightly before they are shipped to minimize tube breakage during shipping.
- 8.3.10 Samples of the suspected solvent(s) should be submitted to the laboratory in containers furnished by NIOSH for such purpose. These liquid bulk samples should not be transported in the same container as the samples or blank tube. If possible, a bulk air sample (at least 50% air drawn through tube) should be shipped for qualitative identification purposes.

8.4 Analysis of Samples

- 8.4.1 Preparation of Samples. In preparation for analysis, each charcoal tube is scored with a file in front of the first section of charcoal and broken open. The glass wool is removed and discarded. The charcoal in the first (larger) section is transferred to a small stoppered test tube. The separating section of foam is removed and discarded; the second section is transferred to another test tube. These two sections are analyzed separately.
- 8.4.2 Desorption of Samples. Prior to analysis, one-half ml of carbon disulfide is pipetted into each test tube. (All work with carbon disulfide should be performed in a hood because of its high toxicity.) Tests indicate that desorption is complete in 30 minutes if the sample is stirred occasionally during this period. The use of graduated glass-stoppered, microcentrifuge tubes is recommended so that one can observe any apparent change in volume during the desorption process. Carbon disulfide is a very volatile solvent, so volume changes can occur during the desorption process depending on the surrounding temperature. The initial volume occupied by the charcoal plus the 0.5 ml CS₂ should be noted and corresponding volume adjustments should be made whenever necessary just before GC analysis.
- 8.4.3 GC Conditions. The typical operating conditions for the gas chromatograph are:
1. 25 cc/min. (70 psi) helium carrier gas flow.
 2. 65 cc/min. (14 psi) hydrogen gas flow to detector.
 3. 100 cc/min. (20 psi) air flow to detector.
 4. 200°C injector temperature.

5. 200°C manifold temperature (detector)

6. Isothermal oven or column temperature - refer to Table 1 for specific compounds.

8.4.4 Injection. The first step in the analysis is the injection of the sample into the gas chromatograph. To eliminate difficulties arising from blowback or distillation within the syringe needle, one should employ the solvent flush injection technique. The 10 μ l syringe is first flushed with solvent several times to wet the barrel and plunger. Three microliters of solvent are drawn into the syringe to increase the accuracy and reproducibility of the injected sample volume. The needle is removed from the solvent, and the plunger is pulled back about 0.2 μ l to separate the solvent flush from the sample with a pocket of air to be used as a marker. The needle is then immersed in the sample, and a 5- μ l aliquot is withdrawn, taking into consideration the volume of the needle, since the sample in the needle will be completely injected. After the needle is removed from the sample and prior to injection, the plunger is pulled back a short distance to minimize evaporation of the sample from the tip of the needle. Duplicate injections of each sample and standard should be made. No more than a 3% difference in area is to be expected.

8.4.5 Measurement of area. The area of the sample peak is measured by an electronic integrator or some other suitable form of area measurement, and preliminary results are read from a standard curve prepared as discussed below.

8.5 Determination of Desorption Efficiency

8.5.1 Importance of determination. The desorption efficiency of a particular compound can vary from one laboratory to another and also from one batch of charcoal to another. Thus, it is necessary to determine at least once the percentage of the specific compound that is removed in the desorption process for a given compound, provided the same batch of charcoal is used. The Physical and Chemical Analysis Branch of NIOSH has found that the desorption efficiencies for the compounds in Table 1 are between 81% and 100% and vary with each batch of charcoal.

8.5.2 Procedure for determining desorption efficiency. Activated charcoal equivalent to the amount in the first section of the sampling tube (100 mg) is measured into a 5cm, 4-mm I.D. glass tube, flame-sealed at one end (similar to commercially available culture tubes). This charcoal must be from the same batch as that used in obtaining the samples and can be obtained from unused charcoal tubes. The open end is capped

with Parafilm. A known amount of the compound is injected directly into the activated charcoal with a microliter syringe, and the tube is capped with more Parafilm. The amount injected is usually equivalent to that present in a 10-liter sample at a concentration equal to the federal standard.

At least five tubes are prepared in this manner and allowed to stand for at least overnight to assure complete absorption of the specific compound onto the charcoal. These five tubes are referred to as the samples. A parallel blank tube should be treated in the same manner except that no sample is added to it. The sample and blank tubes are desorbed and analyzed in exactly the same manner as the sampling tube described in Section 8.3.

Two or three standards are prepared by injecting the same volume of compound into 0.5 ml of CS₂ with the same syringe used in the preparation of the sample. These are analyzed with the samples.

The desorption efficiency equals the difference between the average peak area of the samples and the peak area of the blank divided by the average peak area of the standards, or

$$\text{desorption efficiency} = \frac{\text{Area sample} - \text{Area blank}}{\text{Area standard}}$$

9. Calibration and Standards

It is convenient to express concentration of standards in terms of mg/0.5 ml CS₂ because samples are desorbed in this amount of CS₂. To minimize error due to the volatility of carbon disulfide, one can inject 20 times the weight into 10 ml of CS₂. For example, to prepare a 0.3 mg/0.5 ml standard, one would inject 6.0 mg into exactly 10 ml of CS₂ in a glass-stoppered flask. The density of the specific compound is used to convert 6.0 mg into microliters for easy measurement with a microliter syringe. A series of standards, varying in concentration over the range of interest, is prepared and analyzed under the same GC conditions and during the same time period as the unknown samples. Curves are established by plotting concentration in mg/0.5 ml versus peak area.

NOTE: Since no internal standard is used in the method, standard solutions must be analyzed at the same time that the sample analysis is done. This will insure any fluctuations in the detector response are the same during the same day of the FID test run.

10. Calculations

10.1 The weight, in mg, corresponding to each peak area is read from the standard curve for the particular compound. No volume corrections are needed, because the standard curve is based on mg/0.5 ml CS₂ and the volume of sample injected is identical to the volume of the standards injected.

10.2 Corrections for the blank must be made for each sample.

$$\text{Correct mg} = \text{mg}_s - \text{mg}_b$$

where:

mg_s = mg found in front section of sample tube

mg_b = mg found in front section of blank tube

A similar procedure is followed for the backup sections.

10.3 The corrected amounts present in the front and backup sections of the same sample tube are added to determine the total measured amount in the sample.

10.4 This total weight is divided by the determined desorption efficiency to obtain the total mg per sample.

10.5 The volume of air sampled is converted to standard conditions of 25°C and 760 mm Hg.

$$V_s = V \times \frac{P}{760} \times \frac{298}{T+273}$$

where:

V_s = volume of air in liters at 25°C and 760 mm Hg

V = volume of air in liters as measured

P = Barometric pressure in mm Hg

T = Temperature of air in degree centigrade

10.6 The concentration of the organic solvent in the air sampled can be expressed in mg per m³, which is numerically equal to µg per liter of air

$$\text{mg/m}^3 = \frac{\mu\text{g/l}}{1000} = \frac{\text{total mg (Section 10.4)} \times 1000}{V_s}$$

10.7 Another method of expressing concentration is ppm, defined as µg of compounds per liter of air

$$\text{ppm} = \frac{\mu\text{g}}{\text{liter of compound}} = \frac{24.46}{\text{molecular weight of compound}} \times \frac{\text{mg}}{\text{m}^3}$$

$$\frac{24.46}{114} \times \frac{24.46}{114} \text{ mg/m}^3 = 2.1 \text{ ppm}$$

where:

24.46 = conversion factor from mg/m³ to ppm

114 = molecular weight of the compound (chloroform)

11. References

- 11.1 White, L.D., D.G. Taylor, P.A. Mauer, and R.E. Kupel, "A Convenient Optimized Method for the Analysis of Selected Solvent Vapors in the Industrial Atmosphere," *Amer. Ind. Hyg. Assoc. J.*, 31:225 (1970).
- 11.2 Young, D.M. and A.D. Crowell, Physical Adsorption of Gases, Butterworths, London, 1962, pp. 137-146.
- 11.3 Federal Register, 37 (#202), 22139-22142 (October 18, 1972).
- 11.4 NIOSH Contract HSM-99-72-98, Scott Research Laboratories, Inc., "Collaborative Testing of Activated Charcoal Sampling Tubes for Seven Organic Solvents," pp. 4-22, 4-27 (1973).

TABLE I

PARAMETERS ASSOCIATED WITH PECAB ANALYTICAL METHOD NO. 127

Organic Solvent	Method Classification	Detection Limit (mg/sample)	Sample Volume (L)		GC Column Temperature(°C)	Molecular Weight
			Minimum (a)	Maximum (b)		
Acetone	D	-	0.5	7.7	60	58.1
Benzene	A	0.01	0.5	55	90	78.1
Carbon tetrachloride	A	0.20	10	60	60	154.0
Chloroform	A	0.10	0.5	13	80	119
Dichloromethane	D	0.05	0.5	3.8	85	84.9
p-Dioxane	A	0.05	1	18	100	88.1
Ethylene dichloride	D	0.05	1	12	90	99.0
Methyl ethyl ketone	B	0.01	0.5	13	80	72.1
Styrene	D	0.10	1.5	34	150	104
Tetrachloroethylene	B	0.06	1	25	130	166
1,1,2-trichloroethane	B	0.05	10	97	150	133
1,1,1-trichloroethane	B	0.05	0.5	13	150	133
(Ethyl Chloroform)						
Trichloroethylene	A	0.05	1	17	90	131
Toluene	B	0.01	0.5	22	120	92.1
Xylene	A	0.02	0.5	31	100	106

(a) Minimum volume, in liters, required to measure 0.1 times the OSHA standard

(b) These are breakthrough volumes calculated with data derived from a potential plot (reference 11.2) for activated coconut charcoal. Concentrations of vapor in air at 5 times the OSHA standard (reference 11.3) or 500 ppm, whichever is lower, 25°C, and 760 torr were assumed. These values will be as much as 50% lower for atmospheres of high humidity. The effects of multiple contaminants have not been investigated, but it is suspected that less volatile compounds may displace more volatile compounds (See 3.1 and 3.2)

TABLE II

CHEMICALS WHICH HAVE GREATER THAN 80%
DESORPTION EFFICIENCY BUT HAVE NOT BEEN
THOROUGHLY TESTED BY NIOSH

Class E (Proposed)

Acrylonitrile	Isobutyl acetate
Allyl glycidyl ether	Isobutyl alcohol
n-Amyl acetate	Isoctane
2-Butoxyethanol	Isophorone
n-Butyl acetate	Isopropyl acetate
n-Butyl alcohol	Isopropyl glycidyl ether
n-Butylglycidyl ether	2,6-Lutidine
Chlorobenzene	Methyl acetate
Cyclohexane	Methyl acrylate
Cyclohexanone	Methyl n-butyl ketone
o-Dichlorobenzene	Methyl ethyl ketone
p-Dichlorobenzene	Methyl isobutyl ketone
Diethyl ether	Methyl methacrylate
N,N-Dimethyl aniline	m-Methyl styrene
Epichlorohydrin	p-Methyl styrene
2-Ethoxyethyl acetate	n-Octane
Ethyl acetate	3-Octanone
Ethylbenzene	Pentane
Ethyl butyl ketone	2-Pentanone
Furfural	α -pinene
Heptane	n-Propyl acetate
Hexane	1,1,2,2-Tetrachloroethane
Isoamyl acetate	Tetrahydrofuran
	Trichlorotrifluoroethane (Freon 113)

Recommended Sample Size = 10:

WISSEN

STANDARD METHOD 209, G

6060A

209 G Volatile and Fixed Matter in Nonfiltrable Residue and in Solid and Semisolid Samples

1. General Discussion

This method is applicable to the determination of total residue on evaporation and its fixed and volatile fractions in such solid and semisolid samples as river and lake sediments, sludges separated from water and wastewater treatment processes, and sludge cakes from vacuum filtration, centrifugation, or other sludge dewatering processes.

The determination of both total and volatile residue in these materials is subject to negative error due to loss of ammonium carbonate (NH_4CO_3) and volatile organic matter while drying. Although this is true also for wastewater, the effect tends to be more pronounced with sediments, and especially with sludges and sludge cakes.

The mass of organic matter recovered from sludge and sediment requires a longer ignition time than that specified for residue from wastewaters, effluents, or polluted waters. Carefully observe specified ignition time and temperature to control losses of volatile organic salts.

Make all weighings quickly because wet samples tend to lose weight by evaporation. After drying or ignition, residues often are very hygroscopic and rapidly imbibe moisture from the air.

2. Apparatus

See Sections 209A.2 and 209B.2.

3. Procedure

a. Solid and semisolid samples

1) Total residue and moisture—

a) Preparation of evaporating dish—Ignite a clean evaporating dish at $550 \pm 50^\circ\text{C}$ for 1 hr in a muffle furnace. Cool in a desiccator, weigh, and store in a desiccator until ready for use.

b) Fluid samples—If the sample contains enough moisture to flow more or less readily, stir to homogenize, place 25 to 50 g in a prepared evaporating dish, and weigh to the nearest 10 mg. Evaporate to dryness on a water bath, dry at 103°C for 1 hr, cool in an individual desiccator containing fresh desiccant, and weigh.

c) Solid samples—If the sample consists of discrete pieces of solid material (dewatered sludge, for example), take cores from each piece with a No. 7 cork borer or pulverize the entire sample coarsely on a clean surface by hand, using rubber gloves. Place 25 to 50 g in a prepared evaporating dish and weigh to the nearest 10 mg. Place in an oven at 103°C overnight. Cool in an individual desiccator containing fresh desiccant and weigh. Prolonged heating may result in a loss of volatile organic matter and NH_4CO_3 , but it usually is necessary to dry samples thoroughly.

2) Volatile residue—Determine volatile residue, including organic matter and volatile inorganic salts, on the total residue

obtained in 1) above. Avoid loss of solids by decrepitation by placing dish in a cool muffle furnace, heating furnace to 550 C, and igniting for 60 min. (First ignite samples containing large amounts of organic matter over a gas burner and under an exhaust hood in the presence of adequate air to lessen losses due to reducing conditions and to avoid odors in the laboratory.) Cool in a desiccator and reweigh. Report results as fixed residue (percent ash) and volatile residue.

b. Nonfiltrable residue (suspended matter):

1) Preparation of glass-fiber filter—Place a glass-fiber filter in a membrane filter holder, Hirsch funnel, or Buchner funnel, with wrinkled surface of filter facing upward. Apply vacuum to the assembled apparatus to seat filter. With vacuum applied, wash filter with three successive 20-mL portions of distilled water. After the water has filtered through, disconnect vacuum, remove filter, transfer to an aluminum or stainless steel planchet as a support, and dry in an oven at 103 C for 1 hr (30 min in a mechanical convection oven). If volatile matter is not to be determined, cool filter in a desiccator to balance temperature and weigh. If volatile matter is to be determined, transfer filter to a muffle furnace and ignite at 550 C for 15 min. Remove filter from furnace, place in a desiccator until cooled to balance temperature, and weigh.

2) Treatment of sample—Except for samples that contain high concentrations of filtrable matter, or that filter very slowly, select a sample volume ≥ 14 mL/cm² filter area.

Place prepared filter in membrane filter holder, Hirsch funnel, or Buchner funnel, with wrinkled surface upward. With vacuum applied, wet filter with distilled water to seat it against holder or funnel. Measure well-mixed sample with a wide-tip pipet or graduated cylinder. Filter sample through filter using suction. Leaving suc-

tion on, wash apparatus three times with 10-mL portions of distilled water, allowing complete drainage between washings. Discontinue suction, remove filter and dry to constant weight (see 209B.3c) at 103 C for 1 hr in an oven (30 min in a mechanical convection oven). After drying, cool filter in a desiccator to balance temperature and weigh.

3) Filtration with Gooch crucibles—Alternatively, use glass-fiber filters of 2.2 or 2.4 cm diam with Gooch crucibles and follow the procedure in Section 209D.3b.

4) Ignition—Ignite filter with its nonfiltrable residue (total suspended matter) for 15 min at 550 $\pm$ 50 C, transfer to a desiccator, cool to balance temperature, and weigh.

4. Calculation

a. Solid and semisolid samples:

$$\% \text{ total residue} = \frac{A \times 100}{B}$$

$$\% \text{ volatile residue} = \frac{(A - C) \times 100}{A}$$

$$\% \text{ fixed residue} = \frac{C \times 100}{A}$$

b. Nonfiltrable residue (suspended matter):

mg nonfiltrable volatile residue L

$$= \frac{(D - E) \times 1,000}{\text{sample volume, mL}}$$

mg nonfiltrable fixed residue L

$$= \frac{C \times 1,000}{\text{sample volume, mL}}$$

where:

A = weight of dried solids, mg.

B = weight of wet sample, mg.

C = weight of ash, mg.

D = weight of residue before ignition, mg.

and

E = weight of residue after ignition, mg.

5. Precision and Accuracy

See Section 204D.5

1. Methods for Chemical Analysis of Water and Wastes 1974 U.S. EPA. Technology Transfer. 625-6-74-003. pp. 266-267
2. SOKOLOFF, V. P. 1933 Water of crystallization in total solids of water analysis. *Ind Eng Chem., Anal. Ed.* 5:336.

209 I. Bibliography

- THERIALLT, E. J. & H. H. WAGENHAUS 1923 Studies of representative sewage plants. *Pub. Health Bull.* No. 132.
- HOWARD, C. S. 1933 Determination of total dissolved solids in water analysis. *Ind Eng Chem., Anal. Ed.* 5:4.
- SYMONS, G. F. & B. MOOREY 1941 The effect of drying time on the determination of solids in sewage and sewage sludges. *Sewage Works J.* 13:936.
- FISCHER, A. J. & G. F. SYMONS 1944 The determination of settleable sewage solids by weight. *Water Works Sewage* 91:37.
- DIGES, J. & F. E. NESSBERGER 1946 Notes on the determination of suspended solids. *Sewage Ind. Wastes* 28:237.
- CHAMIN, G., E. H. CHOW, R. B. ALEXANDER & J. POWERS 1958 Use of glass fiber filter medium in the suspended solids determination. *Sewage Ind. Wastes* 30:1062.
- NESSBERGER, F. E. 1958 New method for determination of suspended solids. *Sewage Ind. Wastes* 30:1066.
- SMITH, A. L. & A. E. GREENBERG 1963 Evaluation of methods for determining suspended solids in wastewater. *J. Water Pollut. Control Fed.* 35:440.
- GRIDMAN, B. L. 1964 Processing thickened sludge with chemical conditioners. Pages 78 et seq. in *Sludge Concentration, Filtration and Incineration*. Univ. Michigan Continued Education Ser. No. 113. Ann Arbor.
- WYCKOFF, B. M. 1964 Rapid solids determination using glass fiber filters. *Water Sewage Works* 111:277.

WESTON

APPENDIX F
FIELD/ANALYTICAL DATA

6062A

PARAMETER	RUN 1	RUN 2	RUN 3	RUN 4	RUN 5	RUN 6
A. CONTROL PARAMETERS						
1. TARGET SOIL RESIDENCE TIME (MIN)	60.00	60.00	45.00	45.00	60.00	45.00
a. TARGET SCREW SPEED (SEC/REV)	128.57	128.57	96.43	96.43	128.57	96.43
2. TARGET SOIL DISCHARGE TEMP (C)	50.00	50.00	50.00	100.00	100.00	100.00
3. TARGET AIR INLET TEMP (C)	25.00	90.00	25.00	90.00	90.00	25.00
4. TARGET AIR FLOW RATE (DSCFM)	100.00	100.00	100.00	100.00	100.00	100.00
B. SOIL SYSTEM PARAMETERS						
1. TEMPERATURE						
a. FEED SOIL (C)	24.57	24.57	24.57	24.57	24.57	24.57
b. PROCESSED SOIL (C)	51.72	60.79	49.72	113.72	97.52	89.32
2. VOCs						
a. FEED SOIL						
1. DICHLOROETHYLENE-LAB (ug/kg)	550.00	63000.00	*77.00	*31.00	330000.00	210000.00
CORRESP (ug/kg)	BDL	560699.29	BDL	BDL	939856.95	529398.11
(#/HR)	BDL	1.111E-01	BDL	BDL	2.080E-01	2.026E-01
2. TRICHLOROETHYLENE-LAB (ug/kg)	*210.00	1800000.00	1400.00	*41.00	19000000.00	11000000.00
CORRESP (ug/kg)	BDL	3306351.19	24240.01	51.12	3475593.37	2907304.09
(#/HR)	BDL	6.553E-01	4.002E-03	1.588E-05	7.692E-01	1.113E+00
3. TETRACHLOROETHYLENE-LAB (ug/kg)	*32.00	1500000.00	3900.00	180.00	950000.00	*70000.00
CORRESP (ug/kg)	BDL	2907049.84	54553.74	6468.28	596447.68	50501.13
(#/HR)	BDL	5.761E-01	9.006E-03	2.009E-03	1.320E-01	1.933E-02
4. IYLENE-LAB (ug/kg)	BDL	18000.00	*66.00	BDL	320000.00	380000.00
CORRESP (ug/kg)	BDL	23483.09	36344.01	28.86	298223.84	291577.20
(#/HR)	BDL	4.654E-03	6.000E-03	8.965E-06	6.600E-02	1.116E-01
5. OTHER VOCs-LAB (ug/kg)	760.00	*6200.00	*20.00	BDL	*70000.00	*88000.00
CORRESP (ug/kg)	BDL	10091.62	BDL	56.89	144593.38	89691.54
(#/HR)	BDL	2.000E-03	BDL	1.767E-05	3.200E-02	3.433E-02
6. TOTAL VOCs-LAB (ug/kg)	1552.00	3187200.00	5463.00	252.00	20670000.00	11748000.00
CORRESP (ug/kg)	BDL	6807675.03	115137.78	6605.14	5454715.22	3868472.08
(#/HR)	BDL	1.349E+00	1.901E-02	2.052E-03	1.207E+00	1.481E+00
b. PROCESSED SOIL						
1. DICHLOROETHYLENE (ug/kg)	BDL	*670.00	BDL	BDL	BDL	*1900.00
(#/HR)	BDL	1.217E-04	BDL	BDL	BDL	6.254E-04
2. TRICHLOROETHYLENE (ug/kg)	BDL	40000.00	*13.00	*62.00	*6900.00	57000.00
(#/HR)	BDL	7.266E-03	1.761E-06	1.588E-05	1.185E-03	1.376E-02
3. TETRACHLOROETHYLENE (ug/kg)	BDL	320000.00	*46.00	*37.00	BDL	*1000.00
(#/HR)	BDL	5.310E-02	6.231E-06	9.477E-06	BDL	3.291E-04
4. IYLENE (ug/kg)	BDL	*3600.00	BDL	*35.00	BDL	*7900.00
(#/HR)	BDL	6.540E-04	BDL	8.965E-06	BDL	2.500E-03
5. OTHER VOCs (ug/kg)	BDL	BDL	BDL	*69.00	BDL	*1000.00
(#/HR)	BDL	BDL	BDL	1.767E-05	BDL	3.291E-04
6. TOTAL VOCs (ug/kg)	BDL	364270.00	59.00	203.00	6990.00	68800.00
(#/HR)	BDL	6.517E-02	7.992E-06	5.200E-05	1.185E-03	2.264E-02
c. REMOVAL EFFICIENCY						
1. DICHLOROETHYLENE (%)	-	99.39	-	-	100.00	99.59
2. TRICHLOROETHYLENE (%)	-	98.39	99.96	-	99.35	98.31
3. TETRACHLOROETHYLENE (%)	-	99.91	99.93	99.53	100.00	99.30
4. IYLENE (%)	-	95.95	100.00	-	100.00	97.87
5. OTHER VOCs (%)	-	100.00	-	-	100.00	99.14
6. MAJOR 4 CONTAMINANTS (%)	-	98.99	99.96	99.31	99.30	98.46
7. TOTAL VOCs (%)	-	98.99	99.96	97.47	99.30	98.47

PARAMETER	RUN 1	RUN 2	RUN 3	RUN 4	RUN 5	RUN 6
3. MOISTURE						
a. EXCAVATED SOIL (Z)	20.60	15.50	18.20	21.00	22.10	19.30
b. FEED SOIL (Z)	20.40	18.60	20.10	21.40	20.30	25.90
(#/HR)	29.59	27.89	48.17	56.24	51.51	76.35
1. ENTHALPY (BTU/#)	44.03	44.03	44.03	44.03	44.03	44.03
c. PROCESSED SOIL (Z)	7.40	7.00	13.70	0.67	1.79	7.36
(#/HR)	12.13	12.65	18.56	1.72	3.07	24.20
1. ENTHALPY (BTU/#)	92.91	108.89	89.92	205.31	176.04	160.96
4. MASS FLOWRATE						
a. FEED SOIL						
1. WET BASIS (#/HR)	181.34	198.18	165.09	310.67	221.31	382.75
2. DRY BASIS (#/HR)	151.75	168.94	116.90	254.42	168.60	304.92
b. PROCESSED SOIL						
1. WET BASIS (#/HR)	163.88	181.66	135.46	256.14	171.67	329.14
2. DRY BASIS (#/HR)	151.75	168.94	116.90	254.42	168.60	304.92
5. DENSITY						
a. FEED SOIL (#/CU FT)	-	-	-	69.29	-	-
b. PROCESSED SOIL (#/CU FT)	74.96	74.82	76.18	74.65	81.39	74.23
6. ENERGY - SOIL/MOISTURE						
a. SOIL IN						
1. INERT SOIL (BTU/HR)	2313.50	2575.58	1782.19	3878.74	2570.30	4648.49
2. MOISTURE (BTU/HR)	1302.79	1228.05	2120.84	2476.28	2267.81	3561.72
b. SOIL OUT						
1. INERT SOIL (BTU/HR)	3796.74	4778.47	2840.62	12044.22	6997.99	11756.07
2. MOISTURE (BTU/HR)	1126.73	1377.46	1668.74	352.33	540.74	3895.56
C. AIR SYSTEM PARAMETERS						
1. TEMPERATURE						
a. AMBIENT AIR (C)	28.00	27.00	29.00	29.00	25.00	28.00
b. HEATER EFFLUENT/PROC INLET (C)	28.00	61.00	29.00	77.00	64.00	28.00
c. INFILTRATION AIR (C)	28.00	27.00	29.00	29.00	25.00	28.00
d. MANIFOLD #1 (C)	34.00	33.00	33.00	53.00	54.00	51.00
e. MANIFOLD #2 (C)	42.00	39.00	38.00	64.00	66.00	51.00
f. MANIFOLD #3 (C)	48.00	43.00	43.00	56.00	66.00	68.00
g. AFTERBURNER INLET (C)	38.00	34.00	39.00	60.00	59.00	66.00
h. STACK	-	-	-	-	-	875.00
2. VOCs						
a. AMBIENT AIR						
1. TOTAL VOCs (ppm/vol)	BDL	BDL	BDL	BDL	BDL	BDL
(#/HR)	BDL	BDL	BDL	BDL	BDL	BDL
b. MANIFOLD #1						
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-

PARAMETER	RUN 1	RUN 2	RUN 3	RUN 4	RUN 5	RUN 6
c. MANIFOLD #2						
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
d. MANIFOLD #3						
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
e. AFTERBURNER INLET						
1. DICHLOROETHYLENE (ppm/vol)	BDL	87.00	BDL	BDL	208.00	196.00
(%/HR)	BDL	1.110E-01	BDL	BDL	2.080E-01	2.020E-01
2. TRICHLOROETHYLENE (ppm/vol)	BDL	375.00	1.70	BDL	567.00	785.00
(%/HR)	BDL	6.480E-01	4.000E-03	BDL	7.680E-01	1.094E+00
3. TETRACHLOROETHYLENE (ppm/vol)	BDL	237.00	3.00	1.10	76.70	11.00
(%/HR)	BDL	5.180E-01	9.000E-03	2.000E-03	1.320E-01	1.900E-02
4. XYLENE (ppm/vol)	BDL	3.00	3.00	BDL	60.00	97.00
(%/HR)	BDL	4.000E-03	5.000E-03	BDL	6.600E-02	1.090E-01
5. OTHER VOCs (ppm/vol)	BDL	2.00	BDL	BDL	24.70	32.80
(%/HR)	BDL	2.000E-03	BDL	BDL	3.200E-02	3.400E-02
6. TOTAL VOCs (ppm/vol)	BDL	704.00	7.70	1.10	936.40	1121.80
(%/HR)	BDL	1.283E+00	1.900E-02	2.000E-03	1.206E+00	1.458E+00
f. STACY						
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-	-	-
(%/HR)	-	-	-	-	-	-

PARAMETER	RUN 1	RUN 2	RUN 3	RUN 4	RUN 5	RUN 6
3. MOISTURE						
a. PROCESS AIR (Z/vol)	2.00	1.50	2.80	1.60	1.20	2.10
(#/HR)	3.00	1.10	3.40	1.40	0.77	1.60
1. ENTHALPY (BTU/#)	1097.90	1122.80	1098.80	1134.20	1124.90	1097.90
b. INFILTRATION AIR (Z/vol)	2.00	1.50	2.80	1.60	1.20	2.10
(#/HR)	2.24	2.56	2.99	2.08	1.50	2.55
1. ENTHALPY (BTU/#)	1097.90	1096.60	1098.80	1098.40	1095.40	1097.90
c. MANIFOLD #1 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
d. MANIFOLD #2 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
e. MANIFOLD #3 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
f. AFTERBURNER INLET (Z/vol)	8.18	7.39	14.00	21.30	21.40	22.70
(#/HR)	22.70	19.90	36.00	58.00	50.70	56.30
1. ENTHALPY (BTU/#)	1105.20	1102.60	1106.10	1122.00	1121.60	1126.10
g. STACK (Z/vol)	-	-	-	-	-	30.90
(#/HR)	-	-	-	-	-	63.70
4. FLOWRATE						
a. PROCESSOR INLET (WACFM)	55.10	29.10	45.40	38.30	26.40	27.70
(DSCFM)	51.70	24.70	41.90	30.90	22.50	25.90
(#/HR)	234.00	112.00	189.00	140.00	102.00	117.00
b. INFILTRATION AIR (DSCFM)	39.10	59.90	37.00	45.50	43.90	42.40
(#/HR)	176.00	270.00	167.00	205.00	198.00	191.00
c. MANIFOLD #1 (WACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
d. MANIFOLD #2 (WACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
e. MANIFOLD #3 (WACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
f. AFTERBURNER INLET (WACFM)	113.00	104.00	106.00	119.00	104.00	110.00
(DSCFM)	90.80	84.60	78.90	76.40	66.40	68.30
(#/HR)	410.00	382.00	356.00	345.00	300.00	308.00
g. STACK (WACFM)	-	-	-	-	-	283.00
(DSCFM)	-	-	-	-	-	50.80
(#/HR)	-	-	-	-	-	234.00
5. PARTICULATE EMISS-ABI/STACK (GR/WACFM)	-	-	-	-	-	-
(GR/DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
6. HYDROGEN CHLORIDE EMISSIONS (#/DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
7. CARBON DIOXIDE EMISSIONS (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
8. OXYGEN EMISSIONS (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
9. CARBON MONOXIDE EMISSIONS (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-

PARAMETER	RUN 1	RUN 2	RUN 3	RUN 4	RUN 5	RUN 6
10. ENERGY - AIR/MOISTURE						
a. PROCESS AIR INLET (BTU/HR)	4625.66	3816.35	3817.72	5748.88	3609.46	2712.83
1. SPECIFIC HEAT (BTU/°F)	2.399E-01	2.403E-01	2.399E-01	2.407E-01	2.404E-01	2.399E-01
2. MOISTURE (BTU/HR)	3293.70	1235.08	3735.92	1537.89	366.17	1756.64
b. INFILTRATION AIR INLET (BTU/HR)	3479.13	5220.70	3373.33	4140.91	3657.52	3775.54
1. SPECIFIC HEAT (BTU/°F)	2.399E-01	2.399E-01	2.399E-01	2.399E-01	2.399E-01	2.399E-01
2. MOISTURE (BTU/HR)	2457.57	2806.04	3285.30	2279.61	1638.42	2801.10
c. AFTERBURNER INLET (BTU/HR)	9879.36	8544.58	9731.97	11606.49	9962.84	11165.71
1. SPECIFIC HEAT (BTU/°F)	2.400E-01	2.400E-01	2.400E-01	2.403E-01	2.403E-01	2.404E-01
2. MOISTURE (BTU/HR)	25088.04	20839.14	39819.60	65976.00	56865.12	63399.43
D. OIL SYSTEM PARAMETERS						
1. TEMPERATURE						
a. SCREW INLET (°C)	129.03	103.50	95.98	192.84	174.39	270.32
b. SCREW OUTLET/TROUGH INLET (°C)	123.20	97.74	93.33	178.99	162.93	97.30
c. TROUGH OUTLET (°C)	121.11	96.59	93.33	159.07	144.81	203.75
2. PRESSURE						
a. SCREW INLET (PSIG)	28.00	32.00	26.00	20.72	26.96	22.68
b. SCREW OUTLET/TROUGH INLET (PSIG)	9.36	11.00	7.00	7.01	7.75	6.95
c. FLOWRATE (GPM)	11.00	11.70	11.00	9.00	11.20	9.30
(G/HR)	5538.16	5890.59	5538.16	4531.22	5638.85	4934.00
3. HEAT RELEASED						
a. INLET (BTU/HR)	687929.74	577707.83	498966.95	901865.94	983459.49	1509605.85
1. SPECIFIC HEAT-INLET (BTU/°F)	4.700E-01	4.500E-01	4.400E-01	5.350E-01	5.350E-01	5.900E-01
b. OUTLET (BTU/HR)	641036.89	533565.40	487343.46	713990.54	800373.46	1052576.39
1. SPECIFIC HEAT-OUTLET (BTU/°F)	4.530E-01	4.400E-01	4.400E-01	4.950E-01	4.950E-01	5.350E-01
E. PROPANE SYSTEM PARAMETERS						
1. PROPANE CONSUMPTION (SCFM)						
(G/HR)	3.78	2.36	4.17	2.56	1.26	3.18
	0.43	0.27	0.48	0.30	0.21	0.35
F. PROCESSOR PARAMETERS						
1. SCREW SPEED (RPM)						
	125.60	125.50	95.20	97.70	125.00	94.00
2. HEAT LOSS (BTU/HR)						
	24474.33	25484.58	-23322.13	118908.65	123328.39	385469.11
1. PERCENT TOTAL HEAT (BTU/HR)	52.19	57.73	-290.65	67.29	67.56	94.34

PARAMETER	RUN 7	RUN 8	RUN 9	RUN 10	RUN 11	RUN 12
A. CONTROL PARAMETERS						
1. TARGET SOIL RESIDENCE TIME (MIN)	30.00	30.00	30.00	60.00	45.00	30.00
a. TARGET SCREW SPEED (SEC/REV)	64.29	64.29	64.29	128.57	96.43	64.29
2. TARGET SOIL DISCHARGE TEMP (C)	50.00	50.00	100.00	150.00	150.00	150.00
3. TARGET AIR INLET TEMP (C)	90.00	25.00	90.00	90.00	90.00	90.00
4. TARGET AIR FLOW RATE (DSCFM)	100.00	100.00	100.00	100.00	100.00	100.00
B. SOIL SYSTEM PARAMETERS						
1. TEMPERATURE						
a. FEED SOIL (C)	26.26	28.33	30.97	29.79	30.94	27.33
b. PROCESSED SOIL (C)	56.68	53.16	104.07	158.66	137.34	143.27
2. VOCs						
a. FEED SOIL						
1. DICHLOROETHYLENE-LAB (ug/kg)	*300.00	220000.00	470000.00	140000.00	73000.00	47000.00
CORRESP (ug/kg)	164.76	290840.89	889055.80	586105.97	264041.00	472189.12
(#/HR)	4.367E-05	7.278E-02	1.989E-01	8.538E-02	6.832E-02	6.723E-02
2. TRICHLOROETHYLENE-LAB (ug/kg)	*630.00	590000.00	930000.00	1300000.00	760000.00	220000.00
CORRESP (ug/kg)	30402.08	1955264.05	1997441.48	2678536.44	2382812.77	2390625.98
(#/HR)	9.059E-03	4.893E-01	4.470E-01	3.902E-01	6.165E-01	3.404E-01
3. TETRACHLOROETHYLENE-LAB (ug/kg)	*410.00	930000.00	*98000.00	1500000.00	410000.00	230000.00
CORRESP (ug/kg)	82.38	699130.61	346212.67	1422031.07	727841.10	1257606.98
(#/HR)	2.184E-05	1.750E-01	7.747E-02	2.072E-01	1.883E-01	1.790E-01
4. IYLENE-LAB (ug/kg)	BDL	240000.00	*20000.00	120000.00	*49000.00	50000.00
CORRESP (ug/kg)	7544.79	85967.17	106904.95	27197366.92	65883.46	167493.06
(#/HR)	2.000E-03	2.151E-02	2.392E-02	3.962E+00	1.705E-02	2.385E-02
5. OTHER VOCs-LAB (ug/kg)	BDL	*50000.00	BDL	*22000.00	*7100.00	*11000.00
CORRESP (ug/kg)	BDL	12495.16	38923.73	39127.35	20052.88	65106.38
(#/HR)	BDL	3.127E-03	8.710E-03	5.700E-03	5.188E-03	9.269E-03
b. TOTAL VOCs-LAB (ug/kg)	1340.00	7340000.00	1518000.00	3082000.00	1299100.00	558000.00
CORRESP (ug/kg)	38194.01	3043697.89	3375538.63	31923167.75	3460631.21	4353021.51
(#/HR)	1.012E-02	7.617E-01	7.560E-01	4.651E+00	8.954E-01	6.197E-01
b. PROCESSED SOIL						
1. DICHLOROETHYLENE (ug/kg)	170.00	160000.00	15000.00	*730.00	1300.00	2000.00
(#/HR)	4.367E-05	3.878E-02	2.941E-03	8.284E-05	3.159E-04	2.256E-04
2. TRICHLOROETHYLENE (ug/kg)	220.00	880000.00	61000.00	1800.00	2100.00	12000.00
(#/HR)	5.909E-05	2.133E-01	1.196E-02	2.043E-04	5.103E-04	1.354E-03
3. TETRACHLOROETHYLENE (ug/kg)	*85.00	400000.00	33000.00	1400.00	1300.00	27000.00
(#/HR)	2.184E-05	9.596E-02	6.471E-03	1.589E-04	3.159E-04	3.046E-03
4. IYLENE (ug/kg)	BDL	64000.00	20000.00	*550.00	190.00	7500.00
(#/HR)	BDL	1.551E-02	3.922E-03	6.241E-05	4.617E-05	8.460E-04
5. OTHER VOCs (ug/kg)	BDL	*12900.00	3620.00	BDL	775.00	*1500.00
(#/HR)	BDL	3.127E-03	7.098E-04	BDL	1.983E-04	1.692E-04
c. TOTAL VOCs (ug/kg)	485.00	1516900.00	132620.00	4480.00	5665.00	50000.00
(#/HR)	1.246E-04	3.677E-01	2.601E-02	5.084E-04	1.377E-03	5.340E-03
c. REMOVAL EFFICIENCY						
1. DICHLOROETHYLENE (%)	-	46.71	98.52	99.90	99.54	99.66
2. TRICHLOROETHYLENE (%)	99.27	56.41	97.32	99.75	99.92	99.60
3. TETRACHLOROETHYLENE (%)	-	44.58	91.65	99.92	99.93	98.70
4. IYLENE (%)	100.00	27.99	93.31	100.00	99.73	96.45
5. OTHER VOCs (%)	-	-	91.35	100.00	96.37	98.17
6. MAJOR 4 CONTAMINANTS (%)	98.77	51.94	96.62	99.99	99.37	99.10
7. TOTAL VOCs (%)	98.77	51.75	96.56	99.99	99.65	99.39

PARAMETER	RUN 7	RUN 8	RUN 9	RUN 10	RUN 11	RUN 12
3. MOISTURE						
a. EXCAVATED SOIL (Z)	15.30	21.60	30.90	18.70	18.30	13.30
b. FEED SOIL (Z)	16.40	17.80	26.40	20.60	17.30	18.70
(#/HR)	35.14	40.50	38.27	27.63	15.57	31.21
1. ENTHALPY (BTU/#)	47.02	51.01	56.00	54.00	56.00	49.02
c. PROCESSED SOIL (Z)	10.50	13.80	5.80	0.10	0.30	2.00
(#/HR)	26.98	33.08	11.35	0.11	0.73	2.25
1. ENTHALPY (BTU/#)	101.90	95.91	187.12	288.20	248.04	259.31
4. MASS FLOWRATE						
a. FEED SOIL						
1. WET BASIS (#/HR)	265.08	250.25	223.77	145.68	258.73	142.37
2. DRY BASIS (#/HR)	229.93	208.99	184.74	113.40	242.27	110.54
b. PROCESSED SOIL						
1. WET BASIS (#/HR)	256.91	242.40	196.09	113.48	243.00	112.80
2. DRY BASIS (#/HR)	229.93	208.95	184.72	113.37	242.27	110.54
5. DENSITY						
a. FEED SOIL (#/CU FT)	82.58	104.30	76.78	84.75	91.27	95.61
b. PROCESSED SOIL (#/CU FT)	78.32	74.40	62.89	68.55	-	69.37
6. ENERGY - SOIL/MOISTURE						
a. SOIL IN						
1. INERT SOIL (BTU/HR)	3645.29	3468.98	3242.00	1941.88	4249.05	1795.10
2. MOISTURE (BTU/HR)	1652.23	2066.02	2143.30	1491.97	871.68	1529.73
b. SOIL OUT						
1. INERT SOIL (BTU/HR)	6163.35	5336.05	8102.64	7200.77	13528.99	6409.03
2. MOISTURE (BTU/HR)	2748.80	3173.04	2123.29	32.56	180.48	583.54
C. AIR SYSTEM PARAMETERS						
1. TEMPERATURE						
a. AMBIENT AIR (C)	27.00	29.00	33.00	33.00	26.00	27.00
b. HEATER EFFLUENT/PROC INLET (C)	97.00	29.00	98.00	89.00	98.00	95.00
c. INFILTRATION AIR (C)	27.00	29.00	33.00	33.00	26.00	27.00
d. MANIFOLD #1 (C)	48.00	39.00	102.00	80.00	93.00	112.00
e. MANIFOLD #2 (C)	47.00	39.00	113.00	91.00	114.00	126.00
f. MANIFOLD #3 (C)	49.00	43.00	131.00	109.00	122.00	136.00
g. AFTERBURNER INLET (C)	42.00	42.00	102.00	91.00	101.00	118.00
h. STACK	968.00	1009.00	923.00	979.00	897.00	876.00
2. VOCs						
a. AMBIENT AIR						
1. TOTAL VOCs (ppm/vol)	BDL	BDL	BDL	BDL	BDL	BDL
(#/HR)	BDL	BDL	BDL	BDL	BDL	BDL
b. MANIFOLD #1						
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-

PARAMETER	RUN 7	RUN 8	RUN 9	RUN 10	RUN 11	RUN 12
c. MANIFOLD #2						
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
d. MANIFOLD #3						
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
e. AFTERBURNER INLET						
1. DICHLOROETHYLENE (ppm/vol)	BDL	24.20	173.00	75.00	54.00	63.00
(#/HR)	BDL	3.400E-02	1.960E-01	8.530E-02	6.800E-02	6.700E-02
2. TRICHLOROETHYLENE (ppm/vol)	4.40	145.00	283.00	254.00	362.00	238.00
(#/HR)	3.000E-03	2.760E-01	4.350E-01	3.900E-01	6.160E-01	3.390E-01
3. TETRACHLOROETHYLENE (ppm/vol)	BDL	32.50	36.60	106.00	87.00	97.00
(#/HR)	BDL	7.800E-02	7.100E-02	2.070E-01	1.880E-01	1.760E-01
4. XYLENE (ppm/vol)	1.50	3.60	15.80	3164.00	12.00	20.00
(#/HR)	2.000E-03	6.000E-03	2.000E-02	3.962E+00	1.700E-02	2.300E-02
5. OTHER VOCs (ppm/vol)	BDL	BDL	7.40	4.70	3.80	8.50
(#/HR)	BDL	BDL	8.000E-03	5.700E-03	5.000E-03	9.100E-03
6. TOTAL VOCs (ppm/vol)	5.90	205.20	515.90	3623.70	518.80	426.50
(#/HR)	1.000E-02	3.940E-01	7.300E-01	4.650E+00	8.940E-01	6.141E-01
f. STACK						
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	BDL	BDL	BDL	-	-
(#/HR)	-	BDL	BDL	BDL	-	-

PARAMETER	RUN 7	RUN 8	RUN 9	RUN 10	RUN 11	RUN 12
3. MOISTURE						
a. PROCESS AIR (Z/vol)	2.00	2.20	3.00	2.80	2.50	1.90
(#/HR)	2.50	2.60	2.80	2.90	2.20	2.00
1. ENTHALPY (BTU/#)	1148.20	1098.40	1148.90	1143.20	1148.90	1147.00
b. INFILTRATION AIR (Z/vol)	2.00	2.20	3.00	2.80	2.50	1.90
(#/HR)	2.74	3.28	3.77	3.18	3.76	1.74
1. ENTHALPY (BTU/#)	1096.60	1099.40	1101.40	1101.80	1095.80	1096.60
c. MANIFOLD #1 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
d. MANIFOLD #2 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
e. MANIFOLD #3 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
f. AFTERBURNER INLET (Z/vol)	4.94	4.84	13.70	13.70	11.30	14.30
(#/HR)	13.40	13.30	33.50	33.60	20.80	32.70
1. ENTHALPY (BTU/#)	1108.20	1108.20	1151.90	1144.40	1151.10	1161.90
g. STACK (Z/vol)	10.10	13.70	24.90	17.60	-	-
(#/HR)	34.50	50.85	92.60	60.75	-	-
4. FLOWRATE						
a. PROCESSOR INLET (WACFM)	57.60	44.20	42.50	46.90	41.20	49.20
(DSCFM)	43.90	41.10	31.90	36.00	31.10	37.80
(#/HR)	198.00	186.00	144.00	163.00	140.00	171.00
b. INFILTRATION AIR (DSCFM)	47.80	52.00	43.50	39.40	52.30	32.10
(#/HR)	216.00	234.00	196.00	177.00	237.00	145.00
c. MANIFOLD #1 (WACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
d. MANIFOLD #2 (WACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
e. MANIFOLD #3 (WACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
f. AFTERBURNER INLET (WACFM)	114.00	113.00	120.00	114.00	129.00	116.00
(DSCFM)	91.70	93.10	75.40	75.40	83.40	69.90
(#/HR)	414.00	420.00	340.00	340.00	377.00	316.00
g. STACK (WACFM)	541.00	602.00	599.00	553.00	513.00	392.00
(DSCFM)	113.00	116.00	102.00	104.00	103.00	77.60
(#/HR)	522.00	524.00	460.00	480.00	475.00	357.00
5. PARTICULATE EMISS-ABI/STACK (GR/WACFM)	-	9.000E-03	4.200E-03	6.800E-03	-	-
(GR/DSCFM)	-	4.200E-02	2.400E-02	3.500E-02	-	-
(#/HR)	-	4.100E-02	2.100E-02	3.200E-02	-	-
6. HYDROGEN CHLORIDE EMISSIONS (#/DSCFM)	-	1.080E-04	2.940E-04	2.480E-04	-	-
(#/HR)	-	7.520E-01	1.800E+00	1.550E+00	-	-
7. CARBON DIOXIDE EMISSIONS (Z/vol)	-	7.00	7.40	7.70	-	-
(#/HR)	-	55.80	51.90	54.90	-	-
8. OXYGEN EMISSIONS (Z/vol)	-	10.50	9.40	9.30	-	-
(#/HR)	-	51.50	48.00	46.70	-	-
9. CARBON MONOXIDE EMISSIONS (Z/vol)	-	BDL	BDL	BDL	-	-
(#/HR)	-	BDL	BDL	BDL	-	-

PARAMETER	RUN 7	RUN 8	RUN 9	RUN 10	RUN 11	RUN 12
10. ENERGY - AIR/MOISTURE						
a. PROCESS AIR INLET (BTU/HR)	9866.72	3737.12	7238.32	7550.19	7037.25	8369.30
1. SPECIFIC HEAT (BTU/°F)	2.412E-01	2.399E-01	2.412E-01	2.412E-01	2.412E-01	2.411E-01
2. MOISTURE (BTU/HR)	2870.50	2855.84	3216.92	3315.28	2527.58	2294.00
b. INFILTRATION AIR INLET (BTU/HR)	4176.56	4726.70	4299.46	3882.67	4480.28	2803.71
1. SPECIFIC HEAT (BTU/°F)	2.399E-01	2.399E-01	2.400E-01	2.400E-01	2.399E-01	2.399E-01
2. MOISTURE (BTU/HR)	3000.84	3604.22	4156.68	3507.95	4122.22	1912.50
c. AFTERBURNER INLET (BTU/HR)	10691.14	10846.08	17688.26	16043.85	19449.41	18658.86
1. SPECIFIC HEAT (BTU/°F)	2.400E-01	2.400E-01	2.412E-01	2.410E-01	2.412E-01	2.416E-01
2. MOISTURE (BTU/HR)	14849.88	14739.06	38568.65	38451.84	23742.88	37994.13
D. OIL SYSTEM PARAMETERS						
1. TEMPERATURE						
a. SCREW INLET (C)	85.40	87.78	252.08	248.01	262.08	292.52
b. SCREW OUTLET/TROUGH INLET (C)	82.16	79.44	242.09	237.80	251.32	281.59
c. TROUGH OUTLET (C)	82.16	79.44	239.79	236.85	242.99	269.63
2. PRESSURE						
a. SCREW INLET (PSIG)	23.17	23.00	24.85	29.80	21.63	24.11
b. SCREW OUTLET/TROUGH INLET (PSIG)	7.08	7.50	7.13	8.72	6.88	7.21
3. FLOWRATE (GPM)	10.00	9.80	10.50	11.70	9.60	10.40
(#/HR)	5034.69	4934.00	5286.42	5890.59	4833.30	5226.06
4. HEAT RELEASED						
a. INLET (BTU/HR)	402068.33	407803.69	1476511.91	1606353.64	1424326.34	1783968.90
1. SPECIFIC HEAT-INLET (BTU/°F)	4.300E-01	4.350E-01	5.750E-01	5.700E-01	5.850E-01	6.100E-01
b. OUTLET (BTU/HR)	393970.94	368676.30	1384758.95	1511907.10	1281795.17	1598193.30
1. SPECIFIC HEAT-OUTLET (BTU/°F)	4.350E-01	4.270E-01	5.650E-01	5.600E-01	5.650E-01	5.900E-01
E. PROPANE SYSTEM PARAMETERS						
1. PROPANE CONSUMPTION (SCFM)	2.38	2.64	2.33	2.13	1.86	2.14
(#/HR)	0.27	0.30	0.27	0.24	0.21	0.24
F. PROCESSOR PARAMETERS						
1. SCREW SPEED (SEC/REV)	64.27	60.65	62.77	126.77	93.58	62.00
6. HEAT LOSS (BTU/HR)	-1143.62	25512.03	49546.90	54407.47	108717.46	140834.38
1. PERCENT TOTAL HEAT (BTU/HR)	14.12	65.20	54.00	57.61	76.28	75.81

PARAMETER	RUN 13	RUN 14	RUN 15	RUN 16	RUN 17	RUN 18
A. CONTROL PARAMETERS						
1. TARGET SOIL RESIDENCE TIME (MIN)	60.00	45.00	30.00	30.00	60.00	45.00
a. TARGET SCREW SPEED (SEC/REV)	128.57	96.43	64.29	64.29	128.57	96.43
2. TARGET SOIL DISCHARGE TEMP (C)	150.00	150.00	150.00	150.00	150.00	150.00
3. TARGET AIR INLET TEMP (C)	25.00	25.00	25.00	25.00	25.00	25.00
4. TARGET AIR FLOW RATE (SCFM)	100.00	100.00	100.00	100.00	100.00	100.00
B. SOIL SYSTEM PARAMETERS						
1. TEMPERATURE						
a. FEED SOIL (C)	24.46	22.86	22.83	22.82	20.20	22.22
b. PROCESSED SOIL (C)	175.27	175.22	140.20	25.26	120.88	96.22
2. VOCs						
a. FEED SOIL						
1. DICHLOROETHYLENE-LAB (ug/kg)	47000.00	80000.00	300000.00	210000.00	87700.00	82400.00
CORRESP (ug/kg)	24652.84	41052.22	34425.87	47812.50	20441.19	3707.75
(% HR)	4.408E-02	7.512E-02	1.522E-01	1.186E-01	2.290E-02	2.079E-03
2. TRICHLOROETHYLENE-LAB (ug/kg)	55000.00	82000.00	190000.00	120000.00	BDL	91000.00
CORRESP (ug/kg)	24705.04	194572.47	165270.36	212620.80	126498.81	3287.79
(% HR)	5.209E-02	2.560E-01	4.315E-01	5.150E-01	1.779E-01	7.341E-04
3. TETRACHLOROETHYLENE-LAB (ug/kg)	61000.00	61000.00	150000.00	150000.00	210000.00	82000.00
CORRESP (ug/kg)	117507.75	125699.22	1264205.20	1234166.56	1512224.62	7407.88
(% HR)	2.101E-02	2.100E-02	2.482E-01	2.280E-01	2.144E-01	2.115E-02
4. XYLENE-LAB (ug/kg)	20000.00	59000.00	180000.00	70000.00	BDL	BDL
CORRESP (ug/kg)	22604.67	28407.62	187200.22	77826.25	14142.00	4922.22
(% HR)	6.008E-02	1.301E-02	2.275E-02	1.282E-02	2.201E-03	1.257E-03
5. OTHER VOCs-LAB (ug/kg)	85420.00	81000.00	81000.00	85000.00	84100.00	BDL
CORRESP (ug/kg)	12229.24	22722.62	45181.64	26471.78	BDL	2598.71
(% HR)	2.188E-02	4.154E-03	3.172E-03	5.000E-03	BDL	2.156E-03
b. TOTAL VOCs-LAB (ug/kg)	191420.00	228220.00	481220.00	298200.00	221820.00	1700.00
CORRESP (ug/kg)	377219.52	262124.20	5098914.11	457745.29	299628.65	2622.14
(% HR)	1.254E-01	4.762E-01	2.244E-01	2.329E-01	4.244E-01	7.911E-02
c. PROCESSED SOIL						
1. DICHLOROETHYLENE (ug/kg)	510.00	170.00	110.00	BDL	BDL	410.00
(% HR)	3.132E-05	1.177E-04	1.627E-04	BDL	BDL	7.911E-05
2. TRICHLOROETHYLENE (ug/kg)	580.00	210.00	770.00	BDL	BDL	710.00
(% HR)	3.136E-05	2.129E-05	1.102E-04	BDL	BDL	4.147E-05
3. TETRACHLOROETHYLENE (ug/kg)	854.00	BDL	19000.00	BDL	BDL	BDL
(% HR)	3.664E-05	BDL	4.239E-03	BDL	BDL	1.148E-05
4. XYLENE (ug/kg)	510.00	841.00	6400.00	410.00	810.00	BDL
(% HR)	3.132E-05	6.166E-05	3.465E-04	3.522E-04	1.152E-05	5.658E-05
5. OTHER VOCs (ug/kg)	1172.00	1403.00	1760.00	BDL	BDL	236.00
(% HR)	1.382E-04	1.154E-04	1.170E-04	BDL	BDL	5.573E-05
b. TOTAL VOCs (ug/kg)	2267.00	2103.00	4490.00	410.00	BDL	1276.00
(% HR)	2.178E-04	2.111E-04	3.526E-03	3.522E-04	1.152E-05	2.114E-04
c. REMOVAL EFFICIENCY						
1. DICHLOROETHYLENE (%)	99.91	99.84	99.89	100.00	100.00	99.99
2. TRICHLOROETHYLENE (%)	99.95	99.99	99.73	100.00	100.00	99.91
3. TETRACHLOROETHYLENE (%)	99.96	100.00	99.27	100.00	100.00	99.99
4. XYLENE (%)	99.97	99.97	97.21	99.47	99.94	99.99
5. OTHER VOCs (%)	99.94	99.99	97.64	100.00	100.00	99.99
6. AODP 4 CONTAMINANTS (%)	99.96	99.97	99.27	99.99	100.00	99.99
7. TOTAL VOCs (%)	99.70	99.90	99.28	99.99	100.00	99.94

PARAMETER	RUN 13	RUN 14	RUN 15	RUN 16	RUN 17	RUN 18
3. MOISTURE						
a. EXCAVATED SOIL (2)	17.40	15.20	16.60	15.20	15.20	18.30
b. FEED SOIL (2)	15.50	16.70	20.60	17.70	13.90	19.60
(0/HR)	18.37	29.83	34.00	42.29	26.17	32.41
1. ENTHALPY (BTU/0)	44.03	41.03	43.03	41.03	26.04	42.33
c. PROCESSED SOIL (2)	0.10	0.10	1.00	4.40	0.30	3.50
(0/HR)	0.16	0.15	1.47	9.16	0.03	6.59
1. ENTHALPY (BTU/0)	318.48	319.53	254.16	172.02	218.49	118.89
4. MASS FLOWRATE						
a. FEED SOIL						
1. WET BASIS (0/HR)	178.79	182.98	181.34	242.22	141.50	214.17
2. DRY BASIS (0/HR)	160.28	152.67	146.41	199.94	114.91	181.73
b. PROCESSED SOIL						
1. WET BASIS (0/HR)	160.44	152.82	147.89	208.10	115.26	188.24
2. DRY BASIS (0/HR)	160.28	152.67	146.41	199.94	114.91	181.73
5. DENSITY						
a. FEED SOIL (0/CU FT)	95.62	90.34	109.28	87.79	91.85	85.16
b. PROCESSED SOIL (0/CU FT)	72.53	74.20	72.06	69.06	75.54	74.91
6. ENERGY - SOIL MOISTURE						
a. SOIL IN						
1. INERT SOIL (BTU/HR)	2437.15	2224.56	2183.36	2993.28	1571.11	2682.11
2. MOISTURE (BTU/HR)	306.85	1224.34	1463.11	1735.11	942.02	1262.53
b. SOIL OUT						
1. INERT SOIL (BTU/HR)	11128.98	10613.24	8331.96	8102.89	5726.15	5502.46
2. MOISTURE (BTU/HR)	50.98	48.72	274.22	1574.94	75.52	783.69
7. AIR SYSTEM PARAMETERS						
a. TEMPERATURE						
1. AMBIENT AIR (C)	26.00	25.00	24.00	23.00	22.00	27.00
2. HEATER EFFLUENT PROC INLET (C)	26.00	25.00	24.00	23.00	22.00	29.00
3. INFILTRATION AIR (C)	26.00	25.00	24.00	23.00	22.00	27.00
4. MANIFOLD #1 (C)	23.00	23.00	21.00	21.00	21.00	27.00
5. MANIFOLD #2 (C)	26.00	24.00	21.00	20.00	25.00	27.00
6. MANIFOLD #3 (C)	197.00	122.00	129.00	112.00	99.00	72.00
7. WATERBURNER INLET (C)	87.00	84.00	87.00	81.00	76.00	61.00
8. STACK	886.00	886.00	908.00	880.00	918.00	918.00
b. VOCs						
1. AMBIENT AIR						
2. TOTAL VOCs (ppb VOL)	92L	82L	92L	92L	82L	92L
3. 1,1-DICHLOROETHYLENE (ppb VOL)	92L	82L	92L	92L	82L	92L
4. MANIFOLD #1						
5. 1,1-DICHLOROETHYLENE (ppb VOL)	-	-	-	-	-	-
6. 1,2-DICHLOROETHYLENE (ppb VOL)	-	-	-	-	-	-
7. 1,1,1-TRICHLOROETHYLENE (ppb VOL)	-	-	-	-	-	-
8. TETRACHLOROETHYLENE (ppb VOL)	-	-	-	-	-	-
9. 1,2-DIBROMOETHYLENE (ppb VOL)	-	-	-	-	-	-
10. OTHER VOCs (ppb VOL)	-	-	-	-	-	-
11. TOTAL VOCs (ppb VOL)	-	-	-	-	-	-

PARAMETER	RUN 13	RUN 14	RUN 15	RUN 16	RUN 17	RUN 18
c. MANIFOLD #2						
1. DICHLOROETHYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
4. XYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppb/vol) (0/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppb/vol) (0/HR)	-	-	-	-	-	-
d. MANIFOLD #3						
1. DICHLOROETHYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
4. XYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppb/vol) (0/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppb/vol) (0/HR)	-	-	-	-	-	-
e. AFTERBURNER INLET						
1. DICHLOROETHYLENE (ppb/vol) (0/HR)	35.00	50.00	121.00	82.00	20.00	1.70
2. TRICHLOROETHYLENE (ppb/vol) (0/HR)	4.40E-02	7.50E-02	1.50E-01	1.16E-01	2.90E-02	2.00E-03
3. TETRACHLOROETHYLENE (ppb/vol) (0/HR)	27.00	181.00	181.00	273.00	90.00	0.40
4. XYLENE (ppb/vol) (0/HR)	5.20E-02	2.56E-01	4.30E-01	5.15E-01	1.79E-01	7.00E-04
5. OTHER VOCs (ppb/vol) (0/HR)	9.50	9.21	112.00	126.00	35.00	1.00
6. TOTAL VOCs (ppb/vol) (0/HR)	2.10E-02	2.00E-02	2.44E-01	2.29E-01	2.14E-01	2.00E-03
7. DICHLOROETHYLENE (ppb/vol) (0/HR)	4.21	11.00	24.00	11.00	1.10	1.00
8. TRICHLOROETHYLENE (ppb/vol) (0/HR)	5.00E-03	1.37E-02	2.70E-02	1.30E-02	2.00E-03	1.00E-03
9. TETRACHLOROETHYLENE (ppb/vol) (0/HR)	1.00	2.00	5.00	2.00	3.00	1.00
10. XYLENE (ppb/vol) (0/HR)	2.10E-02	4.10E-02	3.00E-02	5.00E-02	3.00	2.00E-03
11. TOTAL VOCs (ppb/vol) (0/HR)	37.00	258.00	544.00	502.00	196.00	5.00
12. TOTAL VOCs (ppb/vol) (0/HR)	1.15E-01	4.75E-01	9.10E-01	9.30E-01	4.24E-01	7.70E-03
f. STACK						
1. DICHLOROETHYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
4. XYLENE (ppb/vol) (0/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppb/vol) (0/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppb/vol) (0/HR)	-	-	-	-	-	-

PARAMETER	RUN 13	RUN 14	RUN 15	RUN 16	RUN 17	RUN 18
3. MOISTURE						
a. PROCESS AIR (Z/vol)	2.50	2.00	2.00	1.50	2.00	2.30
(#/HR)	3.00	2.50	2.40	2.10	2.50	3.10
1. ENTHALPY (BTU/#)	1096.20	1095.40	1094.90	1093.60	1094.10	1149.70
b. INFILTRATION AIR (Z/vol)	2.30	2.00	2.00	1.60	2.00	2.30
(#/HR)	2.49	2.92	2.37	2.17	3.08	2.98
1. ENTHALPY (BTU/#)	1096.20	1095.40	1094.90	1093.60	1094.10	1096.60
c. MANIFOLD #1 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
d. MANIFOLD #2 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
e. MANIFOLD #3 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
f. AFTERBURNER INLET (Z/vol)	9.28	11.60	13.70	12.50	10.30	11.00
(#/HR)	23.70	35.10	37.30	37.40	31.40	31.90
1. ENTHALPY (BTU/#)	1141.70	1139.70	1148.20	1137.40	1133.40	1123.60
g. STACK (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
4. FLOWRATE						
a. PROCESSOR INLET (MACFM)	48.10	47.00	44.90	47.90	46.00	62.20
(DSCFM)	45.00	44.30	42.40	45.90	43.70	46.90
(#/HR)	203.00	200.00	192.00	207.00	197.00	212.00
b. INFILTRATION AIR (DSCFM)	37.70	51.00	41.40	47.50	53.80	45.10
(#/HR)	170.00	230.00	186.00	215.00	243.00	203.00
c. MANIFOLD #1 (MACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
d. MANIFOLD #2 (MACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
e. MANIFOLD #3 (MACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
f. AFTERBURNER INLET (MACFM)	120.00	141.00	131.00	138.00	139.00	127.00
(DSCFM)	92.70	95.30	87.80	97.40	97.50	92.00
(#/HR)	373.00	430.00	378.00	422.00	440.00	415.00
g. STACK (MACFM)	507.00	510.00	472.00	484.00	561.00	629.00
(DSCFM)	106.00	103.00	90.90	96.70	113.00	125.00
(#/HR)	486.00	472.00	418.00	445.00	518.00	574.00
h. PARTICULATE EMISSIONS-AB1 STACK (MACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
i. HYDROGEN CHLORIDE EMISSIONS (DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
j. CARBON DIOXIDE EMISSIONS (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
k. OXYGEN EMISSIONS (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
l. CARBON MONOXIDE EMISSIONS (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-

PARAMETER	RUN 13	RUN 14	RUN 15	RUN 16	RUN 17	RUN 18
10. ENERGY - AIR/MOISTURE						
a. PROCESS AIR INLET (BTU/HR)	3837.54	3694.46	3462.33	3643.47	3467.46	10748.45
1. SPECIFIC HEAT (BTU/°F)	2.399E-01	2.399E-01	2.398E-01	2.398E-01	2.398E-01	2.412E-01
2. MOISTURE (BTU/HR)	3288.60	2738.50	2627.76	2296.56	2733.25	3564.07
b. INFILTRATION AIR INLET (BTU/HR)	3213.70	4248.63	3354.13	3734.28	4277.12	3925.20
1. SPECIFIC HEAT (BTU/°F)	2.399E-01	2.399E-01	2.398E-01	2.398E-01	2.398E-01	2.399E-01
2. MOISTURE (BTU/HR)	2729.13	3198.23	2595.03	2267.41	3369.82	3266.04
c. AFTERBURNER INLET (BTU/HR)	16946.79	18977.14	18826.47	13067.61	17077.27	14320.44
1. SPECIFIC HEAT (BTU/°F)	2.409E-01	2.409E-01	2.412E-01	2.408E-01	2.407E-01	2.400E-01
2. MOISTURE (BTU/HR)	27058.29	40003.47	42827.86	42538.76	35588.76	35842.84
D. OIL SYSTEM PARAMETERS						
1. TEMPERATURE						
a. SCREW INLET (°C)	235.45	257.18	301.29	219.06	205.99	144.33
b. SCREW OUTLET/TROUGH INLET (°C)	226.84	243.76	296.05	210.86	197.13	138.77
c. TROUGH OUTLET (°C)	226.84	231.29	265.74	206.14	190.92	138.51
2. PRESSURE						
a. SCREW INLET (PSIG)	19.59	21.17	18.08	32.63	23.68	21.79
b. SCREW OUTLET/TROUGH INLET (PSIG)	7.50	7.33	7.76	7.96	10.57	7.20
3. FLOWRATE (GPM)	8.40	9.00	7.50	12.90	8.90	9.40
(G/HR)	4229.14	4531.22	3776.02	6494.75	4480.37	4702.61
4. HEAT RELEASED						
a. INLET (BTU/HR)	1079503.21	1300713.53	1333720.59	1508976.32	965532.22	662854.66
1. SPECIFIC HEAT-INLET (BTU/°F)	5.600E-01	5.800E-01	6.150E-01	5.450E-01	5.350E-01	4.200E-01
b. OUTLET (BTU/HR)	1024177.60	1137609.54	1127308.95	1400481.26	875298.16	632399.99
1. SPECIFIC HEAT-OUTLET (BTU/°F)	5.500E-01	5.600E-01	5.950E-01	5.350E-01	5.200E-01	4.750E-01
E. PROPANE SYSTEM PARAMETERS						
1. PROPANE CONSUMPTION (SCFM)	2.21	2.21	2.04	2.47	2.42	2.76
(G/HR)	0.25	0.25	0.23	0.23	0.29	0.32
F. PROCESSOR PARAMETERS						
1. SCREW SPEED (SEC REV)	129.00	96.00	62.93	64.65	101.23	99.33
G. HEAT LOSS (BTU/HR)	16445.56	11370.82	151708.55	54922.96	47220.16	4445.55
1. PERCENT TOTAL HEAT (BTU/HR)	29.33	67.93	77.51	59.63	52.44	11.46

PARAMETER	RUN 19	RUN 20	RUN 21	RUN 22	RUN 23	RUN 24
A. CONTROL PARAMETERS						
1. TARGET SOIL RESIDENCE TIME (MIN)	60.00	90.00	75.00	60.00	90.00	60.00
a. TARGET SCREW SPEED (SEC/REV)	128.57	192.86	160.71	128.57	192.86	128.57
2. TARGET SOIL DISCHARGE TEMP (C)	210.00	210.00	210.00	150.00	150.00	50.00
3. TARGET AIR INLET TEMP (C)	90.00	90.00	90.00	90.00	90.00	25.00
4. TARGET AIR FLOW RATE (DSCFM)	100.00	100.00	100.00	100.00	100.00	100.00
B. SOIL SYSTEM PARAMETERS						
1. TEMPERATURE						
a. FEED SOIL (C)	25.67	25.93	25.19	31.08	28.65	20.22
b. PROCESSED SOIL (C)	223.85	218.07	232.67	140.96	149.96	59.97
2. VOCs						
a. FEED SOIL						
1. DICHLOROETHYLENE-LAB (ug/kg)	*750.00	*740.00	*20.00	BDL	BDL	22000.00
CORRESP (ug/kg)	2795.49	2591.15	BDL	BDL	8.64	22000.00
(0/HR)	6.472E-04	4.000E-04	BDL	BDL	9.706E-07	3.182E-03
2. TRICHLOROETHYLENE-LAB (ug/kg)	BDL	BDL	*70.00	BDL	BDL	180000.00
CORRESP (ug/kg)	2560.31	1301.54	9.47	170.46	138.28	180000.00
(0/HR)	5.928E-04	2.009E-04	1.850E-06	2.829E-05	1.553E-05	2.603E-02
3. TETRACHLOROETHYLENE-LAB (ug/kg)	BDL	*400.00	*30.00	BDL	BDL	140000.00
CORRESP (ug/kg)	127.44	BDL	BDL	22.16	13.83	140000.00
(0/HR)	2.950E-05	BDL	BDL	3.677E-06	1.553E-06	2.025E-02
4. IYLENE-LAB (ug/kg)	3300.00	13000.00	160.00	34000.00	1500.00	18000.00
CORRESP (ug/kg)	10869.69	12976.19	11808.47	40418.83	57999.59	18000.00
(0/HR)	2.517E-03	2.003E-03	2.306E-03	6.707E-03	6.514E-03	2.603E-03
5. OTHER VOCs-LAB (ug/kg)	*530.00	*2360.00	*15.00	5600.00	380.00	5520.00
CORRESP (ug/kg)	7189.73	17929.50	19682.16	21719.74	33292.60	5520.00
(0/HR)	1.665E-03	2.769E-03	3.843E-03	3.604E-03	3.739E-03	7.964E-04
6. TOTAL VOCs-LAB (ug/kg)	4530.00	16500.00	295.00	39600.00	1880.00	365520.00
CORRESP (ug/kg)	23542.66	34808.38	31500.10	62331.19	91452.94	365520.00
(0/HR)	5.451E-03	5.373E-03	6.150E-03	1.034E-02	1.027E-02	5.287E-02
b. PROCESSED SOIL						
1. DICHLOROETHYLENE (ug/kg)	240.00	BDL	BDL	BDL	*10.00	890.00
(0/HR)	4.701E-05	BDL	BDL	BDL	9.706E-07	1.125E-04
2. TRICHLOROETHYLENE (ug/kg)	990.00	7.00	*12.00	200.00	160.00	5000.00
(0/HR)	1.908E-04	2.212E-07	1.850E-06	2.829E-05	1.553E-05	6.338E-04
3. TETRACHLOROETHYLENE (ug/kg)	1500.00	BDL	BDL	*25.00	*16.00	1300.00
(0/HR)	2.950E-05	BDL	BDL	3.677E-06	1.553E-06	1.548E-04
4. IYLENE (ug/kg)	34.00	*24.00	*25.00	51.00	140.00	130.00
(0/HR)	1.652E-05	2.159E-05	5.849E-05	7.212E-06	1.359E-05	1.648E-05
5. OTHER VOCs (ug/kg)	1245.00	507.00	278.00	737.00	1431.00	95.00
(0/HR)	2.645E-04	5.975E-05	4.125E-05	1.342E-04	1.389E-04	1.204E-05
6. TOTAL VOCs (ug/kg)	2799.00	559.00	225.00	1014.00	1757.00	7415.00
(0/HR)	5.655E-04	7.042E-05	5.125E-05	1.404E-04	1.757E-04	2.399E-04
c. REMOVAL EFFICIENCY						
1. DICHLOROETHYLENE %	96.71	99.99	-	-	99.99	96.45
2. TRICHLOROETHYLENE %	97.49	99.94	-	-	99.99	97.37
3. TETRACHLOROETHYLENE %	-	-	-	-	-	99.19
4. IYLENE %	99.71	99.84	99.75	99.89	99.79	99.37
5. OTHER VOCs %	99.11	97.5	99.13	97.11	99.19	99.49
6. TOTAL VOCs %	99.41	99.84	99.68	99.42	99.12	99.22
7. TOTAL VOCs %	99.41	99.84	99.68	99.42	99.12	99.22

PARAMETER	RUN 19	RUN 20	RUN 21	RUN 22	RUN 23	RUN 24
3. MOISTURE						
a. EXCAVATED SOIL (Z)	16.20	16.20	19.40	15.60	15.60	21.00
b. FEED SOIL (Z)	15.40	17.10	17.50	15.80	15.00	20.60
(#/HR)	36.40	22.90	42.49	24.64	16.01	22.77
1. ENTHALPY (BTU/#)	46.02	47.02	45.02	56.00	52.01	36.04
c. PROCESSED SOIL (Z)	0.80	0.10	0.90	0.10	0.80	3.90
(#/HR)	1.57	0.13	1.39	0.14	0.78	4.94
1. ENTHALPY (BTU/#)	413.34	402.27	431.22	255.20	271.66	167.89
4. MASS FLOWRATE						
a. FEED SOIL						
1. WET BASIS (#/HR)	231.52	154.37	195.25	165.94	112.30	144.63
2. DRY BASIS (#/HR)	195.12	131.47	152.75	141.29	96.28	121.81
b. PROCESSED SOIL						
1. WET BASIS (#/HR)	196.69	131.60	154.14	141.43	97.06	126.75
2. DRY BASIS (#/HR)	195.12	131.47	152.75	141.29	96.28	121.81
5. DENSITY						
a. FEED SOIL (#/CU FT)	91.27	95.61	110.83	82.57	86.92	86.92
b. PROCESSED SOIL (#/CU FT)	76.83	82.16	82.49	78.23	83.14	74.94
6. ENERGY - SOIL/MOISTURE						
a. SOIL IN						
1. INERT SOIL (BTU/HR)	3051.86	2068.53	2362.84	2485.10	1609.28	1666.22
2. MOISTURE (BTU/HR)	1674.92	1076.57	1912.74	1380.06	832.69	820.69
b. SOIL OUT						
1. INERT SOIL (BTU/HR)	16972.40	11162.35	13772.37	8074.02	5814.14	3409.27
2. MOISTURE (BTU/HR)	650.17	52.91	598.19	36.06	210.89	533.23
C. AIR SYSTEM PARAMETERS						
1. TEMPERATURE						
a. AMBIENT AIR (C)	27.00	29.00	29.00	32.00	33.00	19.00
b. HEATER EFFLUENT/PROC INLET (C)	96.00	96.00	98.00	96.00	98.00	19.00
c. INFILTRATION AIR (C)	27.00	28.00	29.00	32.00	33.00	19.00
d. MANIFOLD #1 (C)	93.00	91.00	86.00	58.00	74.00	39.00
e. MANIFOLD #2 (C)	124.00	132.00	126.00	91.00	98.00	57.00
f. MANIFOLD #3 (C)	163.00	168.00	162.00	105.00	104.00	69.00
g. AFTERBURNER INLET (C)	112.00	109.00	117.00	76.00	78.00	44.00
h. STACK	923.00	908.00	907.00	925.00	915.00	899.00
2. VOCs						
a. AMBIENT AIR						
1. TOTAL VOCs (ppm/vol)	BDL	BDL	BDL	BDL	BDL	BDL
(#/HR)	BDL	BDL	BDL	BDL	BDL	BDL
b. MANIFOLD #1						
1. DICHLOROETHYLENE (ppm/vol)	1.50	0.40	BDL	BDL	BDL	-
(#/HR)	2.00E-04	2.00E-04	BDL	BDL	BDL	-
2. TRICHLOROETHYLENE (ppm/vol)	BDL	BDL	BDL	BDL	BDL	-
(#/HR)	BDL	BDL	BDL	BDL	BDL	-
3. TETRAETHYLENE (ppm/vol)	BDL	BDL	BDL	BDL	BDL	-
(#/HR)	BDL	BDL	BDL	BDL	BDL	-
4. ETHYLENE (ppm/vol)	1.00	1.00	0.50	0.50	0.50	-
(#/HR)	5.00E-04	5.00E-04	4.00E-04	1.00E-03	2.00E-03	-
5. OTHER VOCs (ppm/vol)	1.50	0.50	0.50	1.00	1.00	-
(#/HR)	2.00E-04	2.00E-04	4.00E-04	5.00E-04	1.00E-03	-
6. TOTAL VOCs (ppm/vol)	2.40	0.90	1.50	0.50	0.50	-
(#/HR)	1.00E-03	3.00E-04	3.00E-04	1.00E-03	4.00E-03	-

PARAMETER	RUN 19	RUN 20	RUN 21	RUN 22	RUN 23	RUN 24
c. MANIFOLD #2						
1. DICHLOROETHYLENE (ppm/vol) (#/HR)	0.60 2.000E-04	0.50 2.000E-04	BDL BDL	BDL BDL	BDL BDL	-
2. TRICHLOROETHYLENE (ppm/vol) (#/HR)	0.30 2.000E-04	0.30 2.000E-04	BDL BDL	BDL BDL	BDL BDL	-
3. TETRACHLOROETHYLENE (ppm/vol) (#/HR)	BDL BDL	BDL BDL	BDL BDL	BDL BDL	BDL BDL	-
4. XYLENE (ppm/vol) (#/HR)	1.90 9.000E-04	1.80 9.000E-04	1.50 8.000E-04	8.10 4.200E-03	6.00 2.600E-03	-
5. OTHER VOCs (ppm/vol) (#/HR)	0.80 3.000E-04	1.60 7.000E-04	2.00 7.000E-04	5.30 2.500E-03	3.60 1.400E-03	-
6. TOTAL VOCs (ppm/vol) (#/HR)	3.60 1.600E-03	4.20 2.000E-03	3.50 1.500E-03	13.40 6.700E-03	9.60 4.000E-03	-
d. MANIFOLD #3						
1. DICHLOROETHYLENE (ppm/vol) (#/HR)	0.50 2.000E-04	BDL BDL	BDL BDL	BDL BDL	BDL BDL	-
2. TRICHLOROETHYLENE (ppm/vol) (#/HR)	0.30 2.000E-04	BDL BDL	BDL BDL	BDL BDL	BDL BDL	-
3. TETRACHLOROETHYLENE (ppm/vol) (#/HR)	BDL BDL	BDL BDL	BDL BDL	BDL BDL	BDL BDL	-
4. XYLENE (ppm/vol) (#/HR)	2.20 1.000E-03	1.30 6.000E-04	2.10 1.100E-03	2.40 1.200E-03	2.60 1.100E-03	-
5. OTHER VOCs (ppm/vol) (#/HR)	2.20 9.000E-04	4.00 1.800E-03	5.50 2.700E-03	1.20 5.000E-04	1.2 5.000E-04	-
6. TOTAL VOCs (ppm/vol) (#/HR)	5.20 2.300E-03	5.30 2.400E-03	7.60 3.800E-03	3.60 1.700E-03	3.80 1.600E-03	-
e. AFTERBURNER INLET						
1. DICHLOROETHYLENE (ppm/vol) (#/HR)	0.53 5.000E-04	0.30 4.000E-04	BDL BDL	BDL BDL	BDL BDL	-
2. TRICHLOROETHYLENE (ppm/vol) (#/HR)	0.20 4.000E-04	0.10 2.000E-04	BDL BDL	BDL BDL	BDL BDL	-
3. TETRACHLOROETHYLENE (ppm/vol) (#/HR)	BDL BDL	BDL BDL	BDL BDL	BDL BDL	BDL BDL	-
4. XYLENE (ppm/vol) (#/HR)	1.30 2.500E-03	1.40 2.000E-03	1.4 2.000E-03	4.00 5.700E-03	5.00 6.500E-03	-
5. OTHER VOCs (ppm/vol) (#/HR)	1.20 1.400E-03	2.00 2.700E-03	2.7 2.800E-03	2.50 2.500E-03	3.00 2.500E-03	-
6. TOTAL VOCs (ppm/vol) (#/HR)	2.70 4.900E-03	3.60 5.000E-03	4.00 5.000E-03	6.87 6.000E-03	8.00 6.000E-03	10810E-03
f. STACK						
1. DICHLOROETHYLENE (ppm/vol) (#/HR)	-	-	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol) (#/HR)	-	-	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol) (#/HR)	-	-	-	-	-	-
4. XYLENE (ppm/vol) (#/HR)	-	-	-	-	-	-
5. OTHER VOCs (ppm/vol) (#/HR)	-	-	-	-	-	-
6. TOTAL VOCs (ppm/vol) (#/HR)	-	-	-	-	-	-

PARAMETER	RUN 19	RUN 20	RUN 21	RUN 22	RUN 23	RUN 24
3. MOISTURE						
a. PROCESS AIR (Z/vol)	1.90	1.70	2.20	2.40	2.30	0.80
(#/HR)	2.00	1.90	2.10	2.50	2.30	0.94
1. ENTHALPY (BTU/#)	1147.40	1147.80	1149.30	1147.60	1149.30	1091.00
b. INFILTRATION AIR (Z/vol)	1.90	1.70	2.20	2.40	2.30	0.80
(#/HR)	2.48	2.33	4.00	4.10	2.87	1.23
1. ENTHALPY (BTU/#)	1097.10	1097.50	1098.40	1100.90	1101.40	1091.00
c. MANIFOLD #1 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
d. MANIFOLD #2 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
e. MANIFOLD #3 (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
f. AFTERBURNER INLET (Z/vol)	14.40	10.00	14.80	10.40	8.44	6.90
(#/HR)	39.30	27.00	47.20	31.10	20.40	20.00
1. ENTHALPY (BTU/#)	1158.05	1156.30	1161.55	1133.80	1135.00	1110.30
g. STACK (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
4. FLOWRATE						
a. PROCESSOR INLET (MACFM)	48.90	49.80	44.00	47.50	47.00	42.50
(DSCFM)	37.60	38.40	33.40	36.00	35.40	41.70
(#/HR)	170.00	173.00	151.00	163.00	160.00	188.00
b. INFILTRATION AIR (DSCFM)	45.60	48.10	63.40	59.40	43.40	54.40
(#/HR)	206.00	217.00	286.00	268.00	196.00	246.00
c. MANIFOLD #1 (MACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
d. MANIFOLD #2 (MACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
e. MANIFOLD #3 (MACFM)	-	-	-	-	-	-
(DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
f. AFTERBURNER INLET (MACFM)	105.00	102.00	160.00	106.00	111.00	120.00
(DSCFM)	83.00	86.50	96.80	95.40	78.60	96.10
(#/HR)	376.00	390.00	427.00	431.00	356.00	424.00
g. STACK (MACFM)	590.00	480.00	517.00	640.00	624.00	681.00
(DSCFM)	110.00	98.00	98.80	127.00	128.00	140.00
(#/HR)	520.00	450.00	454.00	586.00	586.00	640.00
5. PARTICULATE EMISSIONS (BTU/HR) GR (MACFM)	-	-	-	-	-	-
GR (DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
6. HYDROGEN CHLORIDE EMISSIONS (DSCFM)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
7. CARBON DIOXIDE EMISSIONS (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
8. OXYGEN EMISSIONS (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-
9. CARBON MONOXIDE EMISSIONS (Z/vol)	-	-	-	-	-	-
(#/HR)	-	-	-	-	-	-

PARAMETER	RUN 19	RUN 20	RUN 21	RUN 22	RUN 23	RUN 24
10. ENERGY - AIR/MOISTURE						
a. PROCESS AIR INLET (BTU/HR)	8394.14	8542.27	7587.03	8048.50	8039.24	2984.45
1. SPECIFIC HEAT (BTU/°F)	2.411E-01	2.411E-01	2.411E-01	2.411E-01	2.411E-01	2.398E-01
2. MOISTURE (BTU/HR)	2294.80	2180.82	2413.53	2869.50	2643.39	1025.54
b. INFILTRATION AIR INLET (BTU/HR)	3983.20	4289.60	5777.08	5760.67	4297.66	3905.19
1. SPECIFIC HEAT (BTU/°F)	2.399E-01	2.399E-01	2.399E-01	2.399E-01	2.399E-01	2.398E-01
2. MOISTURE (BTU/HR)	2718.06	2560.99	4394.37	4510.85	3156.68	1342.66
c. AFTERBURNER INLET (BTU/HR)	21211.81	21493.02	25613.51	17511.60	14772.82	11587.42
1. SPECIFIC HEAT (BTU/°F)	2.415E-01	2.415E-01	2.416E-01	2.407E-01	2.407E-01	2.401E-01
2. MOISTURE (BTU/HR)	45511.37	31220.10	54825.16	35261.18	23154.00	22206.00
D. OIL SYSTEM PARAMETERS						
1. TEMPERATURE						
a. SCREW INLET (C)	292.51	298.89	299.36	221.13	221.72	144.71
b. SCREW OUTLET/TROUGH INLET (C)	283.33	290.10	293.79	211.37	213.39	138.88
c. TROUGH OUTLET (C)	282.22	290.56	295.17	207.91	210.25	129.88
2. PRESSURE						
a. SCREW INLET (PSIG)	33.52	37.00	36.83	23.05	23.00	28.00
b. SCREW OUTLET/TROUGH INLET (PSIG)	9.92	11.99	12.00	7.72	10.00	8.15
3. FLOWRATE (GPM)	12.50	13.00	12.80	9.70	8.80	11.40
(#/HR)	6293.36	6545.10	6444.40	4883.65	4430.53	5739.55
4. HEAT RELEASED						
a. INLET (BTU/HR)	2144122.45	2294392.86	2262445.30	1148774.14	1044761.12	809129.59
1. SPECIFIC HEAT-INLET (BTU/°F)	6.100E-01	6.150E-01	6.150E-01	5.470E-01	5.470E-01	4.320E-01
b. OUTLET (BTU/HR)	2039033.54	2197712.63	2214403.20	1061399.45	981995.96	773624.49
1. SPECIFIC HEAT-OUTLET (BTU/°F)	6.000E-01	6.050E-01	6.100E-01	5.350E-01	5.400E-01	4.780E-01
E. PROPANE SYSTEM PARAMETERS						
1. PROPANE CONSUMPTION (SCFM)	2.30	1.93	2.01	2.57	2.64	2.64
(#/HR)	0.26	0.22	0.23	0.29	0.30	0.30
F. PROCESSOR PARAMETERS						
1. SCREW SPEED (SEC REV)	129.00	189.60	162.10	127.00	134.00	124.79
G. HEAT LOSS (BTU/HR)	42890.14	53470.80	22219.54	51546.51	19390.26	9510.84
1. PERCENT TOTAL HEAT (BTU/HR)	40.78	55.31	46.46	58.99	61.76	25.80

PARAMETER	RUN 25	RUN 26	RUN 27	RUN 28
A. CONTROL PARAMETERS				
1. TARGET SOIL RESIDENCE TIME (MIN)	60.00	60.00	60.00	90.00
a. TARGET SCREW SPEED (SEC/REV)	128.57	128.57	128.57	192.86
2. TARGET SOIL DISCHARGE TEMP (C)	50.00	50.00	MAX	MAX
3. TARGET AIR INLET TEMP (C)	25.00	25.00	25.00	25.00
4. TARGET AIR FLOW RATE (DSCFM)	100.00	100.00	75.00	75.00
B. SOIL SYSTEM PARAMETERS				
1. TEMPERATURE				
a. FEED SOIL (C)	14.16	17.67	18.75	19.16
b. PROCESSED SOIL (C)	59.84	62.84	174.58	185.00
2. VOCs				
a. FEED SOIL				
1. DICHLOROETHYLENE-LAB (ug/kg)	35000.00	*20000.00	BDL	*6700.00
CORRESP (ug/kg)	35000.00	*30000.00	BDL	*6700.00
(#/HR)	6.10E-03	4.65E-03	BDL	7.31E-04
2. TRICHLOROETHYLENE-LAB (ug/kg)	1100000.00	2300000.00	83000.00	430000.00
CORRESP (ug/kg)	1100000.00	2300000.00	83000.00	430000.00
(#/HR)	1.91E-01	3.56E-01	1.39E-02	4.69E-02
3. TETRACHLOROETHYLENE-LAB (ug/kg)	470000.00	390000.00	120000.00	340000.00
CORRESP (ug/kg)	470000.00	390000.00	120000.00	340000.00
(#/HR)	8.20E-02	1.38E-01	2.45E-02	3.71E-02
4. XYLENE-LAB (ug/kg)	37000.00	87000.00	*23000.00	49000.00
CORRESP (ug/kg)	37000.00	87000.00	*23000.00	49000.00
(#/HR)	6.45E-03	1.34E-02	4.70E-03	5.35E-03
5. OTHER VOCs-LAB (ug/kg)	*8600.00	*17000.00	BDL	6200.00
CORRESP (ug/kg)	*8600.00	*17000.00	BDL	6200.00
(#/HR)	1.50E-03	2.63E-03	BDL	6.77E-04
b. TOTAL VOCs-LAB (ug/kg)	1650000.00	3324000.00	226000.00	821900.00
CORRESP (ug/kg)	1650000.00	3324000.00	226000.00	821900.00
(#/HR)	2.93E-01	5.15E-01	4.62E-02	9.08E-02
c. PROCESSED SOIL				
1. DICHLOROETHYLENE (ug/kg)	10000.00	3300.00	*390.00	*90.00
(#/HR)	1.69E-03	4.53E-04	7.07E-05	8.25E-06
2. TRICHLOROETHYLENE (ug/kg)	210000.00	520000.00	1900.00	*170.00
(#/HR)	3.67E-02	9.14E-02	3.44E-04	1.19E-05
3. TETRACHLOROETHYLENE (ug/kg)	86000.00	48000.00	*270.00	BDL
(#/HR)	1.48E-02	6.59E-03	4.91E-05	BDL
4. XYLENE (ug/kg)	87000.00	88000.00	*27.00	BDL
(#/HR)	1.47E-02	1.36E-02	4.91E-06	BDL
5. OTHER VOCs (ug/kg)	45000.00	16900.00	*170.00	*7000.00
(#/HR)	7.64E-03	2.77E-03	3.12E-05	6.42E-05
b. TOTAL VOCs (ug/kg)	409400.00	1109900.00	2769.00	8200.00
(#/HR)	7.06E-02	1.83E-01	5.13E-04	8.44E-05
d. REMOVAL EFFICIENCY				
1. DICHLOROETHYLENE (%)	99.79	99.81	-	99.87
2. TRICHLOROETHYLENE (%)	99.84	99.79	97.97	99.97
3. TETRACHLOROETHYLENE (%)	99.81	99.88	99.98	-
4. XYLENE (%)	99.78	99.99	99.99	99.99
5. OTHER VOCs (%)	99.87	99.99	-	99.88
6. TOTAL VOCs (%)	99.85	99.99	99.99	99.99
7. TOTAL VOCs (%)	99.85	99.99	99.99	99.99

PARAMETER	RUN 25	RUN 26	RUN 27	RUN 28
3. MOISTURE				
a. EXCAVATED SOIL (Z)	21.00	21.00	10.60	10.60
b. FEED SOIL (Z)	18.40	18.20	10.70	11.30
(#/HR)	20.74	21.34	24.78	17.50
1. ENTHALPY (BTU/#)	25.06	32.05	34.05	35.05
c. PROCESSED SOIL (Z)	4.50	3.00	1.00	0.10
(#/HR)	7.22	4.11	1.81	0.09
1. ENTHALPY (BTU/#)	107.89	112.89	317.43	337.48
4. MASS FLOWRATE				
a. FEED SOIL				
1. WET BASIS (#/HR)	174.46	155.10	204.51	109.24
2. DRY BASIS (#/HR)	153.43	133.24	179.69	91.65
b. PROCESSED SOIL				
1. WET BASIS (#/HR)	160.66	137.36	181.50	91.74
2. DRY BASIS (#/HR)	153.43	133.24	179.69	91.65
5. DENSITY				
a. FEED SOIL (#/CU FT)	86.92	98.51	-	-
b. PROCESSED SOIL (#/CU FT)	76.11	72.96	80.90	84.63
6. ENERGY - SOIL/MOISTURE				
a. SOIL IN				
1. INERT SOIL (BTU/HR)	1764.08	1700.29	2362.86	1218.70
2. MOISTURE (BTU/HR)	519.73	684.08	843.64	613.48
b. SOIL OUT				
1. INERT SOIL (BTU/HR)	4287.21	3866.92	12442.97	6690.32
2. MOISTURE (BTU/HR)	779.25	463.46	575.98	30.93
C. AIR SYSTEM PARAMETERS				
1. TEMPERATURE				
a. AMBIENT AIR (C)	17.00	20.00	21.00	21.00
b. HEATER EFFLUENT/PROC INLET (C)	17.00	20.00	21.00	21.00
c. INFILTRATION AIR (C)	17.00	29.00	21.00	21.00
d. MANIFOLD #1 (C)	43.00	50.00	91.00	71.00
e. MANIFOLD #2 (C)	51.00	63.00	118.00	103.00
f. MANIFOLD #3 (C)	67.00	75.00	145.00	146.00
g. AFTERBURNER INLET (C)	44.00	52.00	91.00	88.00
h. STACK	390.00	396.00	901.00	903.00
2. VOCs				
a. AMBIENT AIR				
1. TOTAL VOCs (ppm/vol)	BDL	BDL	BDL	BDL
(#/HR)	BDL	BDL	BDL	BDL
b. MANIFOLD #1				
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-

PARAMETER	RUN 25	RUN 26	RUN 27	RUN 28
c. MANIFOLD #2				
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
d. MANIFOLD #3				
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
e. AFTERBURNER INLET				
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
6. TOTAL VOCs (ppm/vol)	1606659.00	3212010.00	223241.00	830990.00
(#/HR)	2.809E-01	5.002E-01	4.572E-02	9.079E-02
f. STACK				
1. DICHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
2. TRICHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
3. TETRACHLOROETHYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
4. XYLENE (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
5. OTHER VOCs (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-
6. TOTAL VOCs (ppm/vol)	-	-	-	-
(#/HR)	-	-	-	-

PARAMETER	RUN 25	RUN 26	RUN 27	RUN 28
3. MOISTURE				
a. PROCESS AIR (Z/vol)	1.00	1.00	1.00	1.20
(#/HR)	1.20	1.20	0.93	1.00
1. ENTHALPY (BTU/#)	1088.90	1091.50	1092.30	1092.30
b. INFILTRATION AIR (Z/vol)	1.00	1.00	1.00	1.00
(#/HR)	1.68	1.56	1.11	1.79
1. ENTHALPY (BTU/#)	1088.90	1091.50	1092.30	1092.30
c. MANIFOLD #1 (Z/vol)	-	-	-	-
(#/HR)	-	-	-	-
d. MANIFOLD #2 (Z/vol)	-	-	-	-
(#/HR)	-	-	-	-
e. MANIFOLD #3 (Z/vol)	-	-	-	-
(#/HR)	-	-	-	-
f. AFTERBURNER INLET (Z/vol)	5.40	6.90	11.00	8.00
(#/HR)	16.40	20.00	25.00	20.20
1. ENTHALPY (BTU/#)	1109.90	1116.20	1144.40	1142.40
g. STACK (Z/vol)	-	-	-	-
(#/HR)	-	-	-	-
4. FLOWRATE				
a. PROCESSOR INLET (WACFM)	43.90	43.00	33.70	31.50
(DSCFM)	43.60	42.30	33.00	30.50
(#/HR)	197.00	191.00	149.00	138.00
b. INFILTRATION AIR (DSCFM)	59.40	55.10	39.10	52.50
(#/HR)	267.00	249.00	176.00	237.00
c. MANIFOLD #1 (WACFM)	-	-	-	-
(DSCFM)	-	-	-	-
(#/HR)	-	-	-	-
d. MANIFOLD #2 (WACFM)	-	-	-	-
(DSCFM)	-	-	-	-
(#/HR)	-	-	-	-
e. MANIFOLD #3 (WACFM)	-	-	-	-
(DSCFM)	-	-	-	-
(#/HR)	-	-	-	-
f. AFTERBURNER INLET (WACFM)	125.00	124.00	107.00	119.00
(DSCFM)	103.00	97.40	72.10	83.00
(#/HR)	464.00	440.00	325.00	375.00
g. STACK (WACFM)	521.00	720.00	494.00	559.00
(DSCFM)	118.00	158.00	111.00	121.00
(#/HR)	540.00	723.00	511.00	555.00
5. PARTICULATE EMISS-ABI/STACK (GR/WACFM)	-	-	-	-
(GR/DSCFM)	-	-	-	-
(#/HR)	-	-	-	-
6. HYDROGEN CHLORIDE EMISSIONS (#/DSCFM)	-	-	-	-
(#/HR)	-	-	-	-
7. CARBON DIOXIDE EMISSIONS (Z/vol)	-	-	-	-
(#/HR)	-	-	-	-
8. OXYGEN EMISSIONS (Z/vol)	-	-	-	-
(#/HR)	-	-	-	-
9. CARBON MONOXIDE EMISSIONS (Z/vol)	-	-	-	-
(#/HR)	-	-	-	-

PARAMETER	RUN 25	RUN 26	RUN 27	RUN 28
10. ENERGY - AIR/MOISTURE				
a. PROCESS AIR INLET (BTU/HR)	2957.26	3114.52	2493.97	2309.85
1. SPECIFIC HEAT (BTU/°F)	2.398E-01	2.398E-01	2.398E-01	2.398E-01
2. MOISTURE (BTU/HR)	1306.68	1309.80	1015.84	1092.30
b. INFILTRATION AIR INLET (BTU/HR)	4068.07	4060.29	2945.90	3966.92
1. SPECIFIC HEAT (BTU/°F)	2.398E-01	2.398E-01	2.398E-01	2.398E-01
2. MOISTURE (BTU/HR)	1832.75	1704.13	1210.17	1953.84
c. AFTERBURNER INLET (BTU/HR)	12388.39	13274.41	15336.04	17207.40
1. SPECIFIC HEAT (BTU/°F)	2.401E-01	2.402E-01	2.410E-01	2.410E-01
2. MOISTURE (BTU/HR)	18202.36	22324.00	28610.00	23076.48
D. OIL SYSTEM PARAMETERS				
1. TEMPERATURE				
a. SCREW INLET (C)	144.71	148.20	294.03	289.13
b. SCREW OUTLET/TROUGH INLET (C)	139.18	144.02	277.36	275.24
c. TROUGH OUTLET (C)	137.78	140.56	260.69	264.41
2. PRESSURE				
a. SCREW INLET (PSIG)	30.00	30.00	20.88	18.22
b. SCREW OUTLET/TROUGH INLET (PSIG)	8.50	9.50	10.38	10.33
3. FLOWRATE (GPM)				
(#/HR)	11.90	11.60	7.60	6.20
	5991.28	5840.24	3826.36	3121.51
4. HEAT RELEASED				
a. INLET (BTU/HR)	844617.08	846242.60	1310011.51	1043279.09
1. SPECIFIC HEAT-INLET (BTU/°F)	4.820E-01	4.850E-01	6.100E-01	6.050E-01
b. OUTLET (BTU/HR)	796851.62	798967.26	1112400.76	927537.12
1. SPECIFIC HEAT-OUTLET (BTU/°F)	4.750E-01	4.800E-01	5.800E-01	5.850E-01
E. PROPANE SYSTEM PARAMETERS				
1. PROPANE CONSUMPTION (SCFM)				
(#/HR)	2.78	2.73	2.13	2.51
	0.32	0.31	0.24	0.29
F. PROCESSOR PARAMETERS				
1. SCREW SPEED (SEC/REV)				
	124.23	125.50	125.65	183.43
G. HEAT LOSS (BTU/HR)				
1. PERCENT TOTAL HEAT (BTU/HR)	24496.81	19919.67	151519.15	79991.92
	51.29	42.14	76.68	69.03


WESTON

APPENDIX G
MASS/ENERGY BALANCES

6060A

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Infiltration Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Inerts (lb/hr)									
VOC's - Dichloroethylene (lb/hr)									
Trichloroethylene (lb/hr)									
Tetrachloroethylene (lb/hr)									
Xylene (lb/hr)									
Other VOC's (lb/hr)									
Moisture (lb/hr)									
Oil (lb/hr)									
Air (lb/hr)									
Water Vapor (lb/hr)									
Particulate (lb/hr)									
Hydrochloric Acid (lb/hr)									
Carbon Dioxide (lb/hr)									
Oxygen (lb/hr)									
Carbon Monoxide (lb/hr)									
Propane (lb/hr)									
Total Mass (lb/hr)									
Average Temp (°F)									
Specific Heat/Heating Value (Btu/lb)									
Heat Rate (Btu/hr)									

Notes: BDL - Below Detection Level



For Thermal Stripping of VOC's from Sun Prod Sludge
At Lehigh Valley Airports (LEAD) Chambersburg, PA


WISCONSIN

FIGURE G-1 MATERIAL/ENERGY BALANCE FOR TEST RUN 1

DATE	TIME	TEST RUN	TEST RUN
11/85	11:00	2281 (U1)	2281 (U1)

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Infiltration Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Inerts	(lb/hr)								
VOC's - Dichloroethylene	(lb/hr)								
Trichloroethylene	(lb/hr)								
Tetrachloroethylene	(lb/hr)								
Xylene	(lb/hr)								
Other VOC's	(lb/hr)								
Moisture	(lb/hr)								
Oil	(lb/hr)								
Air	(lb/hr)								
Water Vapor	(lb/hr)								
Particulate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)								
Average Temp	(°F)								
Specific Heat/Heating Value	(Btu/lb)								
Heat Rate	(Btu/hr)								

Notes: BDL - Below Detection Level



For Thermal Shipping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg PA


WESTON
INCORPORATED
11100 85TH AVE
P.O. BOX 215
LEAD, PA 17036

**FIGURE G-2 MATERIAL/ENERGY BALANCE
FOR TEST RUN 2**

Scale: None
Date: 11/85
Project Number: 2281 01-11
Drawing Number:

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Infil- tration Air	Oil Outlet	Soil Dis- charge	Oil- Gas Dis- Charge	Stack Exhaust	Heat Loss
Inerts	(lb/hr)					114.70			
VOC's	(lb/hr)					100	100		
Trichloroethylene	(lb/hr)					1.0×10^{-2}	1.0×10^{-2}		
Tetrachloroethylene	(lb/hr)					1.0×10^{-2}	1.0×10^{-2}		
Xylene	(lb/hr)					100	1.0×10^{-2}		
Other VOC's	(lb/hr)					100	100		
Moisture	(lb/hr)					100			
Oil	(lb/hr)				100.16				
Air	(lb/hr)		100.00	100.00					
Water Vapor	(lb/hr)		40	100					
Paraffins	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)	100.00	100.00	100.00	100.00	100.00	100.00		
Average Temp	(° F)								
Specific Heat/Heating Value	(Btu/lb)								
Heat Rate	(Btu/hr)								

Notes: BDU Below Detection Level



For Thermal Stripping of VOC's from Sun Plot Study
At Letterkenny Army Depot (LEAD) Chambersburg, PA


WESTON
ENGINEERING
1000 N. 10TH ST., SUITE 100
FARMINGTON, CT 06030
TEL: 203-255-1100

**FIGURE G-3 MATERIAL/ENERGY BALANCE
FOR TEST RUN 3**

Scale	None	0.001 to 1000	2.28 (0.1)	1000 to 10000
Date	11-85			

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Initiation Air	Oil Outlet	Soil Discharge	Oil-Gas Discharge	Stack Exhaust	Heat Loss
Inerts	1.1 lb/hr					2.1 lb/hr			
VOC's - Dichloroethylene	1.1 lb/hr					1.1 lb/hr			
Trichloroethylene	1.1 lb/hr					1.1 lb/hr			
Tetrachloroethylene	1.1 lb/hr					1.1 lb/hr			
Xylene	1.1 lb/hr					1.1 lb/hr			
Other VOC's	1.1 lb/hr					1.1 lb/hr			
Moisture	1.1 lb/hr					1.1 lb/hr			
Oil	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr
Air	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr
Water Vapor	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr
Particulate	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr
Hydrochloric Acid	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr
Carbon Dioxide	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr
Oxygen	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr
Carbon Monoxide	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr
Propane	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr
Total Mass	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr	1.1 lb/hr
Average Temp	(°F)								
Specific Heat/Heating Value	(Btu/lb)								
Heat Rate	(Btu/hr)								


Notes: BDL - Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study At Letterkenny Army Depot (LEAD), Chambersburg, PA	
WESTON ENGINEERING 1111 N. 11th St. P.O. Box 1111 Chambersburg, PA 17003	
FIGURE G-4 MATERIAL/ENERGY BALANCE FOR TEST RUN 4	
Scale: None	Project Number: 2281-01-11
Date: 11/85	Drawing Number:

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Initiation Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Inerts	(lb/hr)								
VOC's Dichloroethylene	(lb/hr)								
Trichloroethylene	(lb/hr)								
Tetrachloroethylene	(lb/hr)								
Xylene	(lb/hr)								
Other VOC's	(lb/hr)								
Moisture	(lb/hr)								
Oil	(lb/hr)								
Air	(lb/hr)								
Water Vapor	(lb/hr)								
Particulate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)								
Average Temp	(°F)								
Specific Heat/Heating Value	(Btu/lb)								
Heat Rate	(Btu/hr)								

Notes: BDU Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg PA

WESTERN
ANALYTICAL SERVICES
10000 10th Avenue NW
Boulder, CO 80501-2299

**FIGURE G-5 MATERIAL/ENERGY BALANCE
FOR TEST RUN 5**

Scale	Unit	Value
11	85	2281.01

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Initiation Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Inerts	(lb/hr)					104 %			
VOC's: Dichloroethylene	(lb/hr)					5.45×10^{-4}	2.97×10^{-1}		
Trichloroethylene	(lb/hr)					1.98	1.09		
Tetrachloroethylene	(lb/hr)					1.79×10^{-4}	1.40×10^{-2}		
Xylene	(lb/hr)					2.40×10^{-1}	1.09		
Other VOC's	(lb/hr)					1.78×10^{-4}	1.40×10^{-2}		
Mixture	(lb/hr)					28.20			
Oil	(lb/hr)	1918.00			4918.00				
Air	(lb/hr)		127.50	193.50			108.00		
Water Vapor	(lb/hr)		1.60	2.50			18.10		
Particulate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)	1962	129.10	196.00	4918.00	129.14	105.10		
Average Temp	(°F)	7	92	94	799	193	151	1515	
Specific Heat/Heating Value (Btu/lb)		100.70	18.15	13.70	213.11	87.52	201.84		
Heat Rate	(Btu/hr)	197800.00	4067.47	954.74	104763.09	10621.93	7450.14		107450.17

Notes: BDL Below Detection Level




FIG. The Soil Shipping of VOC's from Soil Pilot Study
 ALL: Army Army Depot (LEAD) Chambersburg, PA


WISCONSIN
 WISCONSIN DEPARTMENT OF NATURAL RESOURCES
 DIVISION OF SOIL CONSERVATION
 1000 UNIVERSITY AVENUE
 MADISON, WISCONSIN 53706-1333

FIGURE G-6 MATERIAL/ENERGY BALANCE FOR TEST RUN 6

State	None	Project Number	2281 01 11
Date	11/85	Testing Number	

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Infiltration Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Hearts	(lb/hr)								
CHLORINE	(lb/hr)								
Trichloroethylene	(lb/hr)								
Tetrahydroethylene	(lb/hr)								
Aylene	(lb/hr)								
Other VOC's	(lb/hr)								
Methylene	(lb/hr)								
Oil	(lb/hr)								
Air	(lb/hr)								
Water Vapor	(lb/hr)								
Carbonate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Unreacted	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)								
Average Temp	(°F)								
Specific Heat/Heating Value	(Btu/lb)								
Heat Rate	(Btu/hr)								

Values Below Detection Level



For Thermal Shipping of 2000 lb from San Francisco Study
At Lehigh Valley Army Depot (LEAD) Chambersburg, PA


WESTON

**FIGURE G-7 MATERIAL/ENERGY BALANCE
FOR TEST RUN 7**

Scale	11.85	2/81 01 11	2/81 01 11
Unit	lb/hr		


Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Intiltration Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Boards	(lb/hr)								
VOC's	(lb/hr)								
Dichloroethylene	(lb/hr)								
Trichloroethylene	(lb/hr)								
Tetrachloroethylene	(lb/hr)								
Xylene	(lb/hr)								
Other VOC's	(lb/hr)								
Methane	(lb/hr)								
Oil	(lb/hr)								
Air	(lb/hr)								
Water Vapor	(lb/hr)								
Carbonate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Heat Mass	(lb/hr)								
Average Temp	(F)								
Heat Heating Value	(Btu/lb)								
Heat Loss	(Btu/hr)								

Below Detection Level



For Treatment of Storage of Air from Spill Remediation Study At Jefferson County Department of Health and Environment, PA	
WATSON	
FIGURE G-8 MATERIAL/ENERGY BALANCE FOR TEST RUN 8	
Scale	1:100
Date	2/28/01

Compound	1	2	3	4	5	6	7	8	9
Compound	Soil Feed	Oil Inlet	Process Air Inlet	Infiltration Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
CH ₄	(lb/hr)								
1,1,1-Trichloroethylene	(lb/hr)								
1,1,2-Trichloroethylene	(lb/hr)								
1,1,1,2-Tetrachloroethylene	(lb/hr)								
Styrene	(lb/hr)								
Other VOC's	(lb/hr)								
Monomers	(lb/hr)								
Oil	(lb/hr)								
Gas	(lb/hr)								
Water vapor	(lb/hr)								
Carbonic acid	(lb/hr)								
H ₂ O, H ₂ SO ₄ Acid	(lb/hr)								
Carbonic chloride	(lb/hr)								
CO ₂ gas	(lb/hr)								
Carbonic chloride	(lb/hr)								
CO ₂ gas	(lb/hr)								
1,1,1,2-Tetrachloroethylene	(lb/hr)								
Acetone Temp	(F)								
Specific Heat Heating Value	(Btu/lb)								
Oil Discharge	(Btu/hr)								




For Thermal Stripping of Chlorinated Hydrocarbons
 At 1000°C, 1000 ft/min, 1000 ft/min, 1000 ft/min
WESTON
FIGURE G-9 MATERIAL/ENERGY BALANCE
FOR TEST RUN 9

Below Detection Level

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Initiation Air	Oil Outlet	Soil Discharge	Oil-Gas Discharge	Stack Exhaust	Heat Loss
Heats	(lb/hr)								
VOC's	(lb/hr)								
Dichloroethylene	(lb/hr)								
Trichloroethylene	(lb/hr)								
Tetra chloroethylene	(lb/hr)								
Xylene	(lb/hr)								
Other VOC's	(lb/hr)								
Monoaromatic	(lb/hr)								
Oil	(lb/hr)								
Air	(lb/hr)								
Water Vapor	(lb/hr)								
Particulate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)								
Average Temp	(°F)								
Sensible Heat/Heating Value	(Btu/lb)								
Heat Rate	(Btu/hr)								

Below 1400 Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg PA


WESTON
ANALYTICAL SERVICES

**FIGURE G-10 MATERIAL/ENERGY BALANCE
FOR TEST RUN 10**

Scale: None
Date: 11/85
Project Number: 2281-01-11
Drawing Number:

Energy Flow Diagram								
Process	1	2	3	4	5	6	7	8
Soil Feed								
Oil Inlet								
Process Air Inlet								
Inlet Air								
Oil Outlet								
Soil Discharge								
Off-Gas Discharge								
Stack Exhaust								
Heat Loss								
Units	(lb/hr)	(lb/hr)	(lb/hr)	(lb/hr)	(lb/hr)	(lb/hr)	(lb/hr)	(lb/hr)
VOC's								
Dichloroethylene								
Trichloroethylene								
Tetrachloroethylene								
Xylene								
Other VOC's								
Non-HV								
Hydrocarbon								
Carbon Vapor								
Carbon of the								
Hydrocarbon Acid								
Carbon Compound								
Organic								
Carbon Monoxide								
Propane								
Other Gases								
Acetylene Temp								
Acetylene Heat Heating Value								
Heat of Vapor								

Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letter Entry Army Report (LEAD) Chambersburg, PA


WESTON
WESTON ENGINEERING
201 ST. JAMES ST.
P.O. BOX 201
CHAMBERSBURG, PA 17301
TEL: 717/651-1000

**FIGURE G-11 MATERIAL/ENERGY BALANCE
FOR TEST RUN 11**

Scale: Metric
Units: lb/hr
Date: 11/85
Project Number: 2281 31-11
Drawing Number:

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Inlet Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Inerts	(lb/hr)								
VOC's - Dichloroethylene	(lb/hr)								
Trichloroethylene	(lb/hr)								
Tetrachloroethylene	(lb/hr)								
Xylene	(lb/hr)								
Other VOC's	(lb/hr)								
Moisture	(lb/hr)								
Oil	(lb/hr)								
Air	(lb/hr)								
Water Vapor	(lb/hr)								
Particulate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)								
Average Temp	(°F)								
Specific Heat/Heating Value	(Btu/lb)								
Heat Rate	(Btu/hr)								

Notes: BDL - Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg, PA


WESTON
WESTON ENGINEERING, INC.
1111 S. 4TH ST.
CHAMBERSBURG, PA 17003

**FIGURE G-12 MATERIAL/ENERGY BALANCE
FOR TEST RUN 12**

Scale: None
Date: 11/85
Project Number: 2281-01-11
Drawing Number:

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Inti- tration Air	Oil Outlet	Soil Dis- charge	Oil- Gas Dis- charge	Stack Exhaust	Heat Loss
Inerts (lb/hr)									
VOC's - Dichloroethylene (lb/hr)									
Trichloroethylene (lb/hr)									
Tetrachloroethylene (lb/hr)									
Xylene (lb/hr)									
Other VOC's (lb/hr)									
Moisture (lb/hr)									
Oil (lb/hr)									
Air (lb/hr)									
Water Vapor (lb/hr)									
Particulate (lb/hr)									
Hydrochloric Acid (lb/hr)									
Carbon Dioxide (lb/hr)									
Oxygen (lb/hr)									
Carbon Monoxide (lb/hr)									
Propane (lb/hr)									
Total Mass (lb/hr)									
Average Temp (F)									
Specific Heat/Heating Value (Btu/lb)									
Heat Rate (Btu/hr)									


Notes: HDT Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study At Letterkenny Army Depot (LEAD) Chambersburg, PA	
WESTON	
FIGURE G-13 MATERIAL/ENERGY BALANCE FOR TEST RUN 13	
Scale: None	Project Number: 2281 01 11
Date: 11/85	Issuing Number:

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Infiltration Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Inerts	(lb/hr)								
VOC's - Dichloroethylene	(lb/hr)								
Trichloroethylene	(lb/hr)								
Tetrachloroethylene	(lb/hr)								
Xylene	(lb/hr)								
Other VOC's	(lb/hr)								
Moisture	(lb/hr)								
Oil	(lb/hr)								
Air	(lb/hr)								
Water Vapor	(lb/hr)								
Particulate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)								
Average Temp	(°F)								
Specific Heat/Heating Value	(Btu/lb)								
Heat Rate	(Btu/hr)								

Notes: BDL - Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg, PA


WESTON
ANALYTICAL
DESIGN CENTER
1000 N. 10TH ST.
FALLS CHURCH, VA 22044

**FIGURE G-14 MATERIAL/ENERGY BALANCE
FOR TEST RUN 14**

Name	Matting	Test Number	2281 01 11
Date	11/85	Training Number	

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Infil- tration Air	Oil Outlet	Soil Dis- charge	Oil- Gas Dis- Charge	Stack Exhaust	Heat Loss
Inerts	(lb/hr)					1.4 7			
VOC's: Dichloroethylene	(lb/hr)					0.4	2.0 100		
Trichloroethylene	(lb/hr)					1.4	2.0 100		
Tetrachloroethylene	(lb/hr)					0.4	2.0 100		
Xylene	(lb/hr)					1.4 7	2.0 100		
Other VOC's	(lb/hr)					0.4	0.4 20		
Moisture	(lb/hr)					1.4 7			
Oil	(lb/hr)	1.4 7			1.4 7				
Air	(lb/hr)		1.4 7						
Water Vapor	(lb/hr)		1.4 7	1.4 7			1.4 7		
Particulate	(lb/hr)						1.4 7		
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)	1.4 7	1.4 7	1.4 7	1.4 7	1.4 7	1.4 7		
Average Temp	(°F)	70	70	70	70	70	70	100	
Specific Heat/Heating Value	(Btu/lb)								
Heat Rate	(Btu/hr)	1.4 7	1.4 7	1.4 7	1.4 7	1.4 7	1.4 7		1.4 7

Notes: BDL - Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD), Chambersburg, PA


WESTON
ENGINEERING

**FIGURE G-17 MATERIAL/ENERGY BALANCE
FOR TEST RUN 17**

Scale	Notes	Project Number	Drawing Number
11/85		2281 01 11	

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Infiltration Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Inerts	(lb/hr)					111.8			
VOC's - Dichloroethylene	(lb/hr)					0.00	1.00×10^{-6}		
Trichloroethylene	(lb/hr)					2.21×10^{-6}	2.00×10^{-6}		
Tetrachloroethylene	(lb/hr)					0.00	0.00		
Xylene	(lb/hr)					1.18×10^{-6}	2.00×10^{-6}		
Other VOC's	(lb/hr)					5.16×10^{-6}	2.00×10^{-6}		
Moisture	(lb/hr)					0.11			
Oil	(lb/hr)				5.50				
Air	(lb/hr)		3.00	2.10			190.00		
Water Vapor	(lb/hr)		2.00	2.10			27.00		
Particulate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)		1.00	4.20	5.50	111.80	411.01		
Average Temp (F)						425	228	1850	
Specific Heat/Heating Value (Btu/lb)						45.22	128.81		
Heat Rate	(Btu/hr)		1.00	14.04	24.75	50,326	52,713.27		514,700.00

Notes: BDL - Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg, PA

WESTERN
CONSULTANTS


WESTON WAY
CHAMBERSBURG, PA 17301
PHONE: 717-662-3000
TELEX: 435340

FIGURE G-2G MATERIAL/ENERGY BALANCE
FOR TEST RUN 20

Scale	None	Project Number	2281-01-11
Date	11/85	Drawing Number	

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Infiltration Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Inerts	(lb/hr)					1.2			
VOC's - Dichloroethylene	(lb/hr)					0.4	0.4		
Trichloroethylene	(lb/hr)					1.8	1.8		
Tetrachloroethylene	(lb/hr)					0.1	0.1		
Xylene	(lb/hr)					2.1	2.1		
Other VOC's	(lb/hr)					1.2	1.2		
Moisture	(lb/hr)					1.2	1.2		
Oil	(lb/hr)	1.2			0.8				
Air	(lb/hr)		1.2	1.2			8.1		
Water Vapor	(lb/hr)			1.2			4.7		
Particulate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)	1.2	1.2	2.4	0.8	1.2	8.1	1.2	
Average Temp	(°F)			54	18.5	4.1	2.1	1.2	
Specific Heat/Heating Value	(Btu/lb)			1.2	1.2	1.2	1.2	1.2	
Heat Rate	(Btu/hr)	1.2	1.2	2.4	0.8	1.2	8.1	1.2	2.4

Notes BDL - Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg, PA


WESTERN
ENGINEERING
INCORPORATED
1111 E. 10th St.
Cheyenne, WY 82001
(307) 632-1111

**FIGURE G-21 MATERIAL/ENERGY BALANCE
FOR TEST RUN 21**

Scale	None	Project Number	2281-01-11
Date	11/85	Drawing Number	

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Infiltration Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Stack Exhaust	Heat Loss
Inerts (lb/hr)	1.00					1.00			
VOC's - Dichloroethylene (lb/hr)									
Trichloroethylene (lb/hr)									
Tetrachloroethylene (lb/hr)									
Xylene (lb/hr)									
Other VOC's (lb/hr)									
Moisture (lb/hr)	1.00								
Oil (lb/hr)		1.00							
Air (lb/hr)			1.00						
Water Vapor (lb/hr)				1.00					
Particulate (lb/hr)									
Hydrochloric Acid (lb/hr)									
Carbon Dioxide (lb/hr)									
Oxygen (lb/hr)									
Carbon Monoxide (lb/hr)									
Propane (lb/hr)									
Total Mass (lb/hr)	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Average Temp (°F)									
Specific Heat/Heating Value (Btu/lb)									
Heat Rate (Btu/hr)									

Notes: BDL - Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg, PA


WESTON
WESTON INDUSTRIES
WEST CHENIERE, PENNSYLVANIA 17030
PHONE 717 647 3030
FAX 717 647 3030
TELEX 43 548

**FIGURE G-22 MATERIAL/ENERGY BALANCE
FOR TEST RUN 22**

Scale: None
Date: 11/85
Project Number: 2281-01.11
Drawing Number:

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Intil- tration Air	Oil Outlet	Soil Dis- charge	Off- Gas Dis- Charge	Stack Exhaust	Heat Loss
Inerts	(lb/hr)					46.28			
VOC's - Dichloroethylene	(lb/hr)					4.13 x 10 ⁻³	4.00		
Trichloroethylene	(lb/hr)					3.55 x 10 ⁻³	0.00		
Tetrachloroethylene	(lb/hr)					3.55 x 10 ⁻³	0.00		
Xylene	(lb/hr)					3.16 x 10 ⁻³	3.10 x 10 ⁻³		
Other VOC's	(lb/hr)					3.19 x 10 ⁻³	3.00 x 10 ⁻³		
Moisture	(lb/hr)					0.00			
Oil	(lb/hr)	44.00			44.00		1.00		
Air	(lb/hr)		100.00						
Water Vapor	(lb/hr)		2.70	2.70			2.60		
Particulate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)	44.00	102.70	102.70	46.70	4.13	1.00		
Average Temp	(°F)	44	44	44	44	104	104	1000	
Specific Heat/Heating Value	(Btu/lb)				2.00	8.00	100.00		
Heat Rate	(Btu/hr)	1936	4180	4180	934	3300	100		1936

Notes BDL - Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg, PA

WESTON
ENGINEERS
INCORPORATED


2010-00-001
WESTON/LEAD/PA/001-19/00
PROJECT 215 622 30 00
DATE 01/15/88

**FIGURE G-23 MATERIAL/ENERGY BALANCE
FOR TEST RUN 23**

Scale	None	Project Number	2281-01-11	Drawn Number	
Date	11/85				

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Initiation Air	Oil Outlet	Soil Discharge	Off-Gas Discharge	Slack Exhaust	Heat Loss
Inerts (lb/hr)						1.21 x 10 ⁴			
VOC's - Dichloroethylene (lb/hr)						1.11 x 10 ⁻⁴	1.07 x 10 ⁻⁴		
Trichloroethylene (lb/hr)						8.18 x 10 ⁻⁴	2.48 x 10 ⁻⁴		
Tetrachloroethylene (lb/hr)						1.67 x 10 ⁻⁴	2.01 x 10 ⁻⁴		
Xylene (lb/hr)						1.63 x 10 ⁻⁴	2.58 x 10 ⁻⁴		
Other VOC's (lb/hr)						1.29 x 10 ⁻⁴	8.1 x 10 ⁻⁴		
Moisture (lb/hr)						8.18			
Oil (lb/hr)					1.11 x 10 ⁴				
Air (lb/hr)			1.11 x 10 ⁴	1.11 x 10 ⁴			4.18 x 10 ⁴		
Water Vapor (lb/hr)			1.11	1.11			2.0 x 10 ⁴		
Particulate (lb/hr)									
Hydrochloric Acid (lb/hr)									
Carbon Dioxide (lb/hr)									
Oxygen (lb/hr)									
Carbon Monoxide (lb/hr)									
Propane (lb/hr)									
Total Mass (lb/hr)			1.11	1.11	1.11	1.11	1.11	1.11	
Average Temp (°F)									
Specific Heat/Heating Value (Btu/lb)									
Heat Rate (Btu/hr)			1.11	1.11	1.11	1.11	1.11	1.11	1.11

Notes: BDL Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg, PA


WESTON WESTON INDUSTRIES, INC.
1000 WESTON DRIVE
CHAMBERSBURG, PA 17301-1000
TEL: 717/241-1111

FIGURE G-24 MATERIAL/ENERGY BALANCE FOR TEST RUN 24

Scale: None
Date: 11/85
Project Number: 2281 01 11
Drawing Number:

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Infiltration Air	Oil Outlet	Soil Discharge	Oil Gas Discharge	Stack Exhaust	Heat Loss
inerts	(lb/hr)								
VOC's Dichloroethylene	(lb/hr)								
Trichloroethylene	(lb/hr)								
Tetrachloroethylene	(lb/hr)								
Xylene	(lb/hr)								
Other VOC's	(lb/hr)								
Moisture	(lb/hr)								
Oil	(lb/hr)								
Air	(lb/hr)								
Water Vapor	(lb/hr)								
Particulate	(lb/hr)								
Hydrochloric Acid	(lb/hr)								
Carbon Dioxide	(lb/hr)								
Oxygen	(lb/hr)								
Carbon Monoxide	(lb/hr)								
Propane	(lb/hr)								
Total Mass	(lb/hr)								
Average Temp	(°F)								
Specific Heat Heating value	(Btu/lb)								
Heat Rate	(Btu/hr)								

Notes: BHA Below Detection Level




For Thermal Desorption of VOC's from Soil Pilot Study,
At Lehigh Valley Airport (LVA) Cranbury, NJ, PA

WESTON
ENGINEERING

**FIGURE G-25 MATERIAL/ENERGY BALANCE
FOR TEST RUN 25**

Date	11/85	Page	2/21/01/11

Plates dDI Below Detection Level

For Thermal Stripping of VOC's from Spill Pilot Study
At Letterkenny Army Depot (LEAD) Chambersburg PA


WESTON
1800-222-2222
405 WEST 1ST AVE
SUITE 1000
PHILADELPHIA, PA 19106
PHONE 215 591 3030
FAX 215 591 3000

FIGURE G-26 MATERIAL/ENERGY BALANCE
FOR TEST RUN 26

Sl. no.	None	Plugs/Number	Barrel/Number
1	1.1/8.5	2281	01-11

Stream Number	1	2	3	4	5	6	7	8	9
Description	Soil Feed	Oil Inlet	Process Air Inlet	Intil tration Air	Oil Outlet	Soil Dis- charge	OH- Gas Dis- Charge	Stack Exhaust	Heat Loss
Inerts (lb/hr)									
VOC's (lb/hr)									
Dichloroethylene (lb/hr)									
Trichloroethylene (lb/hr)									
Tetrachloroethylene (lb/hr)									
Xylene (lb/hr)									
Other VOC's (lb/hr)									
Moisture (lb/hr)									
Oil (lb/hr)									
Air (lb/hr)									
Water Vapor (lb/hr)									
Particulate (lb/hr)									
Hydrochloric Acid (lb/hr)									
Carbon Dioxide (lb/hr)									
Oxygen (lb/hr)									
Carbon Monoxide (lb/hr)									
Propane (lb/hr)									
Total Mass (lb/hr)									
Average Temp (F)									
Specific Heat/Heating Value (Btu/lb)									
Heat Rate (Btu/hr)									

Notes: BDL - Below Detection Level



For Thermal Stripping of VOC's from Soil Pilot Study At Letterkenny Army Depot (LEAD) Chambersburg, PA	
WESTON WESTON WAY WEST CHESTER, PENNSYLVANIA 19380 (610) 338-1000 FAX (610) 338-1001	
FIGURE G-28 MATERIAL/ENERGY BALANCE FOR TEST RUN 28	
Scale: None	Project Number: 2281-01-11
Date: 11/85	Drawing Number:



APPENDIX H

SUPPLEMENTAL DATA

- Table H-1 Moisture content in the processed soil.
- Table H-2 Mass flow rate of feed soil and processed soil.
- Table H-3 Comparison of total VOC's as measured by the CEM system and GC/MS analysis.
- Table H-4 Summary of MM1 data from Test Run 2 (6 August 1985)
- Table H-5 Summary of MM1 data from Test Run 4 (8 August 1985).
- Table H-6 Summary of MM1 data from Test Run 5 (9 August 1985).
- Table H-7 Moisture content in the air discharge stream.
- Table H-8 Temperature of the air discharge stream.



H. SUPPLEMENTAL DATA

H.1 Moisture content of processed soils. The moisture content in the processed soil varied with changes in the operating conditions. The moisture content of the processed soils is shown, in matrix format, for all operating conditions in Table H-1.

H.2 Mass flow rate of soils. The mass flow rate of the feed and processed soils were monitored regularly during the pilot study. As expected, the mass flow rate of the processed soils varied with changes in the operating conditions and moisture content in the soil. The mass flow rates of the feed and processed soil streams are summarized in Table H-2.

H.3 VOC concentrations in off-gas manifold as determined by continuous emission monitoring (CEM) system and mobile mass spectrometer. In addition to the laboratory GC/MS analyses, two other modes of analysis were used to analyze the discharge gas in the three legs of the manifold system: 1) a CEM system, and 2) a mobile mass spectrometer. The CEM system utilized portable field instruments to measure the gross VOC concentrations in the linear range from 1 to 500 ppm relative to the calibration gas (benzene). An AID photoionization detector was used during Test Runs 1 through 11. An OVA was used during Test Runs 12 through 23, and test runs 25 through 28. A summary of the gross VOC concentrations as measured by the CEM system is shown for each manifold leg in Table H-3. For comparison, the total VOC concentrations as detected by GC/MS techniques are also given. As shown, the average deviation (i.e., $100\% \times [1 - (GC/MS)/CEM]$) corresponding to the AID detector was 58.93 percent. The average deviation corresponding to the OVA was 54.00 percent. The large variance between the VOC's measured by the CEM system and GC/MS analyses indicates that the portable monitors are not adequate to accurately quantify VOC's in the air stream. The portable instruments are far less sophisticated analytically and extreme precision is not expected. However, analysis of Table H-3 indicates that the instrument readings are generally in the same order of magnitude as the GC/MS results. The portable monitors, therefore, can be used to obtain real-time estimates of VOC emissions in the air discharging the thermal processor.

A Bruker MMI mobile mass spectrometer was also utilized during Test Runs 2, 4, and 5 conducted on 5 August 1985, 8 August 1985, and 9 August 1985, respectively. The MMI was used to qualitatively identify VOC's in the discharge air stream. The data generated by the MMI during Test Runs 2, 4, and 5 are shown in Tables H-4 through H-5. The MMI identified only those

I Ambient Air Inlet Temperature

Residence Time (Minutes)	Soil Discharge Temperature (°C)			
	50	100	150	Maximum
30	11.80	4.40	1.00	
45	11.70	3.30	0.10	
60	11.40 11.30 4.50 1.00	0.30	0.10	1.00
75				
90				0.10

Soil evaluated Phase I Test Runs

II Elevated Air Inlet Temperature

Residence Time (Minutes)	Soil Discharge Temperature (°C)			
	50	100	150	Maximum
30	10.50	5.80	2.00	
45	3.50	0.67	0.30	
60	7.00	1.79	0.10	
75			0.10	0.80
90				1.30

TABLE H-1 MOISTURE CONTENT IN THE PROCESSED SOIL (PERCENT BY WEIGHT)

II. Elevated Air Inlet Temperature

Residence Time (Minutes)	Process Stream	Soil Discharge Temperature (°C)			
		50	100	150	Maximum
30	Feed Processed	250.08 256.91	223.77 196.09	142.37 112.80	—
45	Feed Processed	214.17 186.34	310.67 256.14	258.73 243.00	—
60	Feed Processed	196.13 161.66	221.32 171.67	145.04 113.48	231.52 196.60
75	Feed Processed	—	—	165.94 141.43	192.25 154.14
90	Feed Processed	—	—	112.30 97.08	154.37 131.60

I. Ambient Air Inlet Temperature

Residence Time (Minutes)	Process Stream	Soil Discharge Temperature (°C)			
		50	100	150	Maximum
30	Feed Processed	250.75 242.40	242.22 208.10	181.34 147.89	—
45	Feed Processed	165.09 115.46	382.75 329.14	182.98 152.82	—
60	Feed Processed	181.14 163.88	141.50 115.26	178.79 160.44	204.51 181.50
75	Feed Processed	144.63 126.75	—	—	—
90	Feed Processed	117.40 100.86	—	—	—
105	Feed Processed	131.70 117.36	—	—	—
120	Feed Processed	—	—	—	100.24 91.74

TABLE H-2 MASS FLOW RATE OF FEED SOIL AND PROCESSED SOIL (WET BASIS - LB/HR)

WESTON

TABLE H-3. COMPARISON OF TOTAL VOC'S AS MEASURED BY THE CEM SYSTEM AND GC/MS ANALYSES (PPM BY VOLUME)

Test run	CEM system			GC/MS Analyses Afterburner inlet	Deviation Between CEM System and GC/MS Analyses (percent)
	Mani- fold 1	Mani- fold 2	Mani- fold 3		

I. Phase I Test Runs					
A. AID					
1	5	5	5	<1	80.00
2	768	812	778	704	10.43
3	6	8	24	7.7	39.21
4	3	3	3	1.1	63.33
5	831	809	800	936	15.08
6	768	695	592	1,122	63.80
7	3	2	2	519	(7,314.29)*
8	368	484	707	206	60.36
9	365	390	325	515	43.06
10	1,240	1,320	1,200	3,620	188.83
11	437	426	381	519	25.16
				Average	58.93
B. OVA					
12	331	494	477	426	1.84
13	117	133	122	88	29.03
14	167	202	130	258	55.11
15	550	607	533	544	3.43
16	399	537	576	503	0.20
17	142	157	115	196	42.03
18	17	17	17	5.3	68.82
(Average OVA Deviation - Phase I Test Runs:					28.64)

*Excluded as outlier



TABLE H-3. (Continued)

Test run	GC/MS Analyses			CEM system Afterburner inlet	Deviation Between CEM System and GC/MS Analyses (percent)
	Mani- fold 1	Mani- fold 2	Mani- fold 3		
I. Phase II Test Runs					
A. OVA					
19	2.4	3.6	5.2	70	94.67
20	2.0	4.2	5.3	54	92.90
21	1.6	3.5	7.6	100	96.77
22	3.6	3.4	3.6	44	84.39
23	10.8	9.6	3.8	39	79.32

(Average OVA Deviation - Phase II Test Runs: 89.41)

Average 54.00 percent



TABLE H-4. SUMMARY OF MMI DATA FROM TEST RUN 2 (6 AUGUST 1985)

Manifold	Number of deter- minations	Target Compounds (arbitrary log units)				
		1,2-Di- chloro- ethene	1,1,1- Trichloro- ethane	Aliphatic hydro- carbons	Chloro- form	Dichloro- methane
Baseline ¹		3.0-3.9	2.9-3.7	3.6-4.5		2.6-3.2
1	6	4.3-5.0	4.1-5.0	4.4-5.2	3.9-4.9	3.6-4.5
2	3	4.7-5.0	4.8-5.0	4.9-5.3	4.5-4.9	3.9-4.6
3	5	4.3-4.9	4.8-5.0	4.9-5.3	4.0-4.9	3.8-4.7
1	4	4.6-4.8	4.4-4.9	4.8-5.1	3.7-4.6	3.2-4.0
2	6	4.1-4.9	4.1-4.8	4.4-5.0	3.8-4.6	3.0-4.0
3	3	4.3-4.5	4.2-4.4	4.7-4.8	4.1-4.4	3.8-4.0
1	3	4.3-4.7	4.3-4.9	4.4-5.0	4.0-4.6	3.3-3.9
2	2	5.1	4.9	5.0-5.1	4.7	---
3	4	4.8-4.9	4.7-4.8	4.8-5.1	4.3-4.7	3.9-4.0
Baseline ¹	3	3.3-4.0	2.5-3.9	4.7-4.8	---	3.3-3.5
1	3	4.5-4.8	4.5-4.8	4.0-4.8	3.9-4.4	2.9-3.9
---	---	---	---	---	---	---
3	2	5.1	4.9-5.0	5.2-5.3	4.8-4.9	4.5
1	6	4.4-5.4	4.4-5.0	4.6-5.1	3.7-4.5	3.5
2	2	4.7-5.0	4.5-4.8	4.2-4.4	4.2-4.4	3.2-3.3
3	3	4.9-5.3	4.9-5.3	5.0-5.1	4.7-4.8	---
1	3	5.0-5.2	5.1	4.9-5.0	4.6-4.8	---
2	4	4.7-4.9	5.0-5.1	4.8-5.1	4.7-4.8	3.9
3	5	4.7-4.9	4.8-4.9	4.9	4.5-4.6	4.0
1	3	4.6-4.9	4.4-4.9	4.7-5.0	4.3-4.6	4.0
2	3	4.9	4.9-5.0	5.0	4.6-4.7	---
3	2	4.5-4.8	4.8-4.9	4.6-5.0	4.4-4.6	---
Baseline ¹		3.9-4.8	3.9-4.0	1.8	3.9	4.4

¹Reading taken in area where process was operating - represents background in that area.

Mani- fold	Number of deter- minations	Target Compounds (arbitrary log units)						
		Tetra- chloro- ethane	Aliphatic hydro- carbons	Tetra- chloro- ethane	Xylenes	Trichloro- ethane	Dichloro- propane	Dichloro- ethene
2	10	2.4-2.9	2.3-2.7	2.9-3.4	2.7-3.0	---	---	---
3	5	2.4-2.5	2.3	2.9-2.7	2.6-2.7	---	---	---
1	5	2.4-2.9	2.3-2.8	3.1-3.3	2.7-2.9	---	---	---
2	5	3.1-3.6	2.9-3.3	3.9-4.2	3.5-3.7	2.6-3.2	2.8-3.0	3.1-3.5
3	4	3.6-3.7	3.4-3.6	4.0-4.2	3.2-3.8	2.7-3.3	3.0-3.3	3.3-3.4
1	4	3.6-3.9	3.3-3.8	3.5-4.4	3.1-3.9	3.2-3.4	2.7-3.4	2.8-3.8
2	6	3.4-3.7	3.3-3.7	4.1-4.4	3.6-3.8	3.1-3.4	3.0-3.3	3.2-3.7
3	2	3.8-4.0	3.7-3.9	4.4-4.5	3.9-4.0	3.5-3.6	3.3-3.4	3.8-3.9
Baseline ¹	6	2.8-2.9	2.8-2.9	4.0-4.1	3.3-3.4	2.9-3.2	2.8	---
1	3	3.7-4.1	3.5-3.9	4.3-4.5	3.8-4.0	3.6	3.4-3.7	3.7-3.8
2	4	3.7-4.1	3.5-3.9	4.4-4.5	3.9-4.0	3.3-3.5	3.3-3.6	3.5-3.9
3	3	3.6-3.9	3.4-3.8	4.4	3.9	3.4-3.5	3.1-3.4	3.3-3.5
1	5	3.5-3.9	3.6-3.8	4.3-4.4	3.9	3.4-3.5	3.2-3.3	3.3-3.7
2	4	3.4-3.9	3.3-3.9	4.4-4.6	3.9-4.0	3.4-3.6	3.1-3.4	3.3-3.6
3	4	3.6-3.9	3.5-3.8	4.4-4.5	3.9-4.0	3.4-3.5	3.2-3.3	3.3-3.6
1	3	3.4-3.9	3.3-3.9	4.4	3.9	3.4-3.5	3.1-3.3	NO
2	5	3.4-4.0	3.3-3.9	4.4-4.5	3.8-4.0	3.5	3.1-3.4	NO
3	4	3.6	3.5-3.8	4.4-4.5	3.9-4.0	3.5	3.2-3.3	NO
Baseline ¹	2	2.9-3.4	3.1-3.3	4.4-4.5	3.5-3.9	3.4	3.0-3.2	NO
1	4	3.1-3.8	3.0-3.1	4.1	3.1-3.3	3.3	2.9-3.2	NO
2	3	3.2-3.4	3.0-3.1	4.1-4.2	3.7-3.8	3.1-3.2	2.9	NO
3	5	3.5-4.0	3.3-3.8	4.2-4.3	3.8-3.9	3.2	3.0-3.3	3.2-3.4
1	3	3.4-3.5	3.2-3.3	4.2-4.3	3.8	3.2	2.9-3.1	3.0-3.2
2	6	3.3-4.0	3.2-3.9	4.3-4.4	3.8-3.9	3.2-3.3	2.9-3.2	3.2
3	5	3.5-3.9	3.3-3.8	4.3-4.4	3.9	3.2-3.3	2.9-3.1	NO
1	3	3.3-4.1	3.1-3.9	4.1-4.3	3.7-3.9	3.1-3.2	2.9-3.2	3.0-3.5
2	3	3.3-3.9	3.2-3.7	4.3	3.8-3.9	3.3	3.0	3.2-3.5
3	3	3.6-3.9	3.4-3.7	4.3	3.9	3.3	2.9-3.2	NO
1	5	3.2-3.6	3.0-3.3	4.1-4.2	3.6-3.9	3.2-3.3	2.8-2.9	NO
2	5	3.0-3.8	2.9-3.0	4.0-4.2	3.5-3.8	3.1-3.2	2.7-2.8	NO
3	3	3.6-3.9	3.4-3.7	4.2	3.9	3.2	2.9-3.1	3.2-3.4

¹Readings taken in area where process was operating - represents background in that area.
 NO = Not detected.

6060A



TABLE H-6. SUMMARY OF MM1 DATA FROM TEST RUN 5 (9 AUGUST 1985)

Mani- fold	Number of deter- minations	Target compounds (arbitrary log units)						
		Tetra- chloro- ethene	1,1,1- Trichloro- ethene	Chloro- form	1,2-Di- chloro- ethene	Xylenes	Tetra- chloro- ethane	Tri- chloro- ethane
3	6	3.7-4.5	5.3-6.0	4.2-4.7	4.4-5.0	4.2-4.8	4.1-4.7	4.5-4.9
1	7	4.2-4.6	5.8-5.9	4.5-4.9	4.9-5.4	4.7-5.0	4.4-4.9	4.6-5.0
2	5	4.1-4.5	5.9-6.2	4.5-4.9	5.2-5.4	4.8-5.0	4.6-4.9	4.4-4.7
3	3	4.3-4.4	5.9	4.6-4.9	4.8-5.0	4.9-5.1	4.6-4.8	4.7-5.0
1	4	4.1-4.5	5.9-6.3	4.6-4.7	4.5-5.3	4.7-4.9	4.2-4.7	4.3-5.0
2	2	4.5-4.8	6.1-6.4	4.6-4.8	5.1-5.5	4.8-5.1	4.7-4.9	4.6-4.8
3	3	4.5-4.9	5.8-6.2	4.1-4.9	4.9-5.1	4.9-5.1	4.6-4.9	4.8-5.1
1	4	4.6-4.8	6.0-6.2	4.6-5.0	5.0-5.4	4.7-5.2	4.5-4.9	4.5-5.1
2	5	4.7-5.1	6.0-6.4	4.7-4.9	5.0-5.3	4.7-5.1	4.7-5.0	4.7-4.9
3	3	4.9-5.1	6.5-6.8	4.9	5.4-5.9	5.0-5.2	5.0-5.3	4.6-5.0
Baseline ¹	1	2.9	4.1	3.1	ND	3.6	3.5	ND

¹Readings taken in area where process was operating - represents background in that area.

ND = Not Detected

II. Elevated Air Inlet Temperature

Residence Time (Minutes)	Soil Discharge Temperature (°C)			
	50	100	150	Maximum
30	4.94	13.70	14.30	-
45	11.00	21.30	11.30	-
60	7.38	21.40	13.70	-
75			10.40	14.40
90			8.44	10.00

I. Ambient Air Inlet Temperature

Residence Time (Minutes)	Soil Discharge Temperature (°C)			
	50	100	150	Maximum
30	4.84	12.50	13.70	-
45	14.00	22.70	11.60	-
60	8.18 6.90 5.40 6.90	10.30	9.28	11.00
75				
90				

Test evaluated Phase I Test Runs

TABLE H-7 MOISTURE CONTENT IN THE AIR DISCHARGE STREAM (PERCENT BY WEIGHT)

II Elevated Air Inlet Temperature

Residence Time (minutes)	Location	Soil Discharge Temperature (°C)			
		50	100	150	Maximum
30	Man No 1 Man No 2 Man No 3 AB	48 47 49 47	102 113 131 102	112 126 136 118	
45	Man No 1 Man No 2 Man No 3 AB	57 62 72 62	53 64 56 60	93 114 122 101	
60	Man No 1 Man No 2 Man No 3 AB	33 36 43 34	54 66 66 58	80 91 93 91	93 124 163 112
75	Man No 1 Man No 2 Man No 3 AB				96 126 142 117
90	Man No 1 Man No 2 Man No 3 AB			74 96 104 78	91 132 168 106

I Ambient air inlet temperature

Residence Time (minutes)	Location	Soil Discharge Temperature (°C)			
		50	100	150	Maximum
30	Man No 1 Man No 2 Man No 3 AB	39 39 43 42	71 90 112 81	91 111 139 97	
45	Man No 1 Man No 2 Man No 3 AB	33 36 43 39	51 61 68 66	63 84 122 84	
60	Man No 1 Man No 2 Man No 3 AB	14 42 46 38 39 57 69 44 43 51 67 44 50 63 75 52	61 75 96 76	73 88 107 87	91 118 145 91
75	Man No 1 Man No 2 Man No 3 AB				
90	Man No 1 Man No 2 Man No 3 AB				71 103 146 88

Legend
Man Manifold
AB Afterburner inlet
Not elevated
Phase I Test Runs

TABLE H-8: TEMPERATURE OF THE AIR DISCHARGE STREAM (°C)

WESTON

compounds for which it was mass calibrated with standards; other compounds may have been present. Units on the summary tables represent the logarithmic intensities of ions characteristic to the target compounds (e.g., aliphatic hydrocarbons were semiquantified with ions at 57, 71, and 95 atomic mass units (AMU)). It is emphasized that since the MM1 was not calibrated for quantification, and the sampling method (simply placing the probe 2 inches from the sampling port) was not quantitative, the data can be used only in a relative sense. The data cannot be converted to concentrations in air. Further work is required to standardize instrument response and establish sampling techniques before the logarithmic intensities can be converted to a relative concentrations.

H.4 Moisture content in the air discharge stream. The moisture content of the air discharge stream was monitored at the afterburner inlet. The moisture content of the combined air stream is shown for all operating conditions in Table H-7.

H.5 Temperature of the discharge air stream. The temperature of the gases discharging the thermal processor were monitored during each test run. Temperatures were monitored in each leg of the manifold system as well as at the afterburner inlet. Air discharge temperatures are summarized in Table H-8.

WESTON

APPENDIX I
STATISTICAL ANALYTICAL APPROACH



APPENDIX I

STATISTICAL ANALYTICAL APPROACH

Analysis Techniques. The multiple regression analysis reduces the data to a linear equation, as discussed in Section 9, which can be used to predict important response variables. The use of stepwise analysis allows the determination of regression coefficients, while interactively specifying the system equations via addition or deletion of singular variables.

As with any statistical tool, there are limitations in the multiple regression technique; however, these limitations can be overcome as discussed in the following subsections.

In the case of a nonlinear relationship between the input variables and the response variable, the alternative procedures include:

- (a) Reduce the span of the analysis of the response variable until an acceptable correlation is found.
- (b) Transform the response variable, e.g.,
$$\text{LN}(Y) = a + b_n X_n$$
- (c) Weigh each of the input variables, e.g.,
$$Y = a + b_1 w_1 x_1 + b_2 w_2 x_2 + \dots + b_n w_n x_n$$
- (d) Use multiple regression as the initial iterative step followed by analysis by a different technique to finalize the correlation.
- (e) Utilize the linear relationship in an estimation capacity recognizing there may be variance from the true relationship.

In order to determine the exact relationship between the variables over a useful span, the third and fourth procedures would have to be employed following each of a series of trial operations similar to the test recently completed. This would be very costly and time consuming and is impractical for this analysis.

A correlation which minimizes the variance from the true relationship could be developed using the third and fourth procedures to analyze the data recorded from the completed test. Although this procedure could extract some otherwise indistinguishable relationships from the data, it would be very time consuming and is also not within the scope of this project.



The method generally accepted as the initial iterative step is a combination of the first, second, and fifth procedures, whereby a basic correlation would be developed followed by the determination of its useful span. This data analysis is based on this method.

One advantage of multiple regression is the ability to simultaneously analyze unlimited numbers of input variables. When computers are used to perform the analysis the number of input variables may be limited by the software or hardware of the computer. WESTON has utilized software and hardware which can analyze all of the test variables simultaneously. A Tektronix 4054 microcomputer and its associated plot-50 statistics: Multiple Linear Regression software package* was utilized to perform the computations necessary for the iterative steps.

It should be noted, however, that the number of calculations required to solve the equations used in the analysis increases factorially as each additional variable is included in the analysis. Computer time should be a consideration when deciding the number of input variables to be analyzed.

As the number of input variables increases, so does the probability of coincidence (i.e., an input variable may not actually be correlated to the response variable other than by coincidence). While only additional testing can prove correlation by coincidence, this factor can be discounted based on scientific judgment and adjustment to the response parameters.

Final solution. Application of the multiple regression packages yielded ANOVA tables, regression tables, and summary of successive significance of input variables.

The ANOVA table includes the following information*:

- (a) SS - The sum of squares of the deviations.
- (b) MS - The mean square, which is SS/df .
- (c) df - Degrees of freedom.
- (d) F - The value of the F statistic, such that
$$F = (\text{Regression } SS/df) / (\text{Residual } SS/df).$$

*Users Manual, Statistics: Multiple Linear Regression, Plot 50-4050D04, Tektronix, Inc., Beaverton, Oregon, July 1982.

*A glossary of statistical terms is provided in Table I-1 at the end of this appendix.

WESTON

- (e) $Pr > F$ - The probability that a value of a random variable having the F-distribution takes on a value greater than the value of F. A value less than 0.1 indicates significance of the F statistic and, consequently, the overall system equations. Statisticians normally associate a $Pr > F$ value of less than 0.05 with a very significant hypothesis.
- (f) R-square - The coefficient of determination, which gives a measure of the linear association between the dependent variable and the set of independent variables. The R-square value indicates the significance of the model (or variable) where 1.0 equals 100 percent.
- (g) Rbar-square - An adjustment to R-square for its tendency to increase as the number of independent variables increases. The adjustment is

$$1 - ((r_{res}^2 / (n-p)) / (1(Y, -Y)^2 / (n-1)))$$
- (h) Root of Residual MS - The square root of the residual mean square.

The regression table includes the following information for each variable coefficient in the regression equation:

- (a) Estimate - The estimated value of the coefficient.
- (b) Standard Error - The standard error of the regression coefficient estimates.
- (c) t - The value of the t-statistic, which is, for each estimate:

$$\text{Estimate} / \text{Standard Error}.$$
- (d) $Pr > ABS(t)$ - The probability that the absolute value of a random variable having the t-distribution takes on a value greater than the absolute value of t. A value of $Pr > ABS(t)$ of less than 0.1 indicates significance of the t-static and, consequently, the estimated value of the coefficient. Statisticians normally associate a $Pr > ABS(t)$ value of less than 0.05 with a very significant hypothesis.

The value of the Durbin-Watson statistic can be used to test whether the residuals are uncorrelated.

For each iterative step, both the forward and backward stepping techniques are applied. The forward stepping analysis allows the statistician to select a variable to be added to the model, or the Tektronix 4054 will automatically select the variable which is most significant of those remaining, and add it to the model. The forward stepping technique determines the marginal contribution of each variable added. The backward stepping technique includes all of the selected variables to determine interrelationships between the input variables and to calculate an overall system equation.

WESTON

The iteration process was continued until significant and practical system equations were developed. System equations were rejected if:

- (a) The probability that the hypothesized equation was not correct exceeded 10 percent ($P: >F$ was not less than 0.1).
- (b) The significance of the equation did not approach 90 percent (R-square did not approach 0.9) or too many variables were required to reach this level.
- (c) The range of response variables for which a correlation could be developed was too small.

Input variables were eliminated from the system equations based on:

- (a) Insignificant marginal contribution to the model determined by the R-squared value computed during the forward stepping process.
- (b) A high probability that the hypothesized variable coefficient was not correct as determined by the analysis of the t statistic of the regression table ($Pr >ABS(t)$).
- (c) Scientific and intuitive reasoning suggesting alternative correlations between the input variable in question and the response variable.
- (d) The coefficient of the input variable was corrective.

The system model is a set of simple linear equations which describe certain system parameters and enable the projection of responses to be calculated based on measureable input data. The use of the system model can vary from a basis for an environmental permit application to becoming an aid for system design or ultimately a dynamic model. The intended use of the system equations for the purposes of this report is the projection of system requirements to aid in future technical and economic feasibility analyses of thermal stripping as a decontamination method for soils contaminated with VOC's as well as system design.



TABLE I-1. GLOSSARY OF STATISTICAL TERMINOLOGY

ANOVA table - Analysis of Variance table. The ANOVA table provides a useful summary of calculations about variability. It contains sums of squares and mean square estimates of the two sources of variability (regression and residuals) and their respective degrees of freedom, the value of the F-statistic, R-square, Rbar-square, and $Pr > F$.

Dependent variable - The variable to be described in terms of others in the regression model.

Fitted values - Values of the dependent variable calculated from the regression equation and existing values of the independent variables in the model.

Independent variable - A variable used, possibly in conjunction with other variables, to describe a given dependent variable.

Least squares - The least-squares method is a method of line-fitting that determines parameter values to minimize the sum of squares of the deviations (lengths of the vertical line segments) from the observed data points to the line.

Mean - The arithmetic average of a column of data.

Median - The middle value in an ordered column of data; that is, the data value half way between the top and bottom.

Missing-data value - A numeric constant used as a place holder for data missing from the data set.

Mode - The value that occurs most often in a data set.

Model - A statistical equation that expresses the supposed (often only approximate) functional relation between variables.

Observation - A row of data in a data file.

Outliers - A pair of values being plotted is an outlier if the value for one of the variables falls outside a specified number of standard deviations from its mean. (Outliers for an index plot are defined only on the variable for the y axis.) More generally, any discrepant value.

$Pr > ABS(t)$ - The probability that the absolute value of a random variable having the t distribution takes on a value greater than the value of the t statistic calculated as part of the regression table.

TABLE I-1. (Continued)

Pr >F - The probability that a random variable having the F distribution takes on a value greater than the value of the F statistic calculated as part of the ANOVA table.

Predicted value - The value of the dependent variable calculated from the regression equation and new values of the independent variables in the model.

Probability plot - Values of a variable plotted on a probability scale. The horizontal scale refers to percentages of the probability distribution. The vertical scale, an ordinary arithmetic scale, is for the variable. The degree to which the data lies on a straight line indicates the closeness of fit of the sample distribution to the theoretical distribution.

Raw data - The set of data values read from a data file and used directly by an algorithm, as opposed to a set of data read from a data file and manipulated by transformations before being used.

Regression coefficient - The coefficients of the equation used in a regression model.

Regression table - A table that provides a summary of regression calculations. It contains parameter estimates, the standard error of the estimates, the value of the t statistic, the t probability, and the mean and standard deviation of the dependent variable.

Residuals - The difference between the actual values and the fitted values of the dependent variable (see definition for e).

Response variable - Another name for a dependent variable.

Scatter plot - A scatter plot is a graphical display showing how two variables are related to each other.

Standard deviation - The square root of the variance.

Standard error of the mean - The standard deviation of a set of sample means.

Variance - The average of the sum of the squares of the deviation of each observation from the mean of the variable.

Distribution List

Copies

Defense Technical Information Center
Cameron Station
Alexandria, Virginia 22314

14

Defense Logistics Studies Information Exchange
US Army Logistics Management Center
Fort Lee, Virginia 23801

2

Commander
US Army Toxic and Hazardous Materials Agency
Aberdeen Proving Ground, Maryland 21010-5401

32

Commander
Letterkenny Army Depot
Chambersburg, Pennsylvania 17201-4170

2