

AD-A206 908

Quantitative Spectroscopy of X-Ray Laser Plasmas in Pulsed Power

Devices

ONR-N00001487K2019

Annual Progress Report

April 1988 - March 1989

DTIC
ELECT
APR 19 1989
S D
CB H

At the start of the reporting period indicated above the original Z-pinch setup was in place and running. Diagnostics consisting of a framing camera, 1 m N.I. VUV spectrometer, 1/2 m visible spectrometer and a Rogowski coil had been set up and were functional.

To begin, with a framing camera a study of the visible signature of the plasma for a variety of different conditions (e.g., gas voltage in discharge, etc.) was conducted. This gave a working understanding of the gross behavior of the discharge. The emphasis was shifted to obtaining a temporal sequence of time resolved photographic spectra which would include the 5f-3d and 4f-3d transitions in CIV, the lines of primary interest for this experiment.

Preliminary steps, such as checking the calibration of the 1 m VUV spectrometer/MCP/photographic film with an Ar capillary discharge lamp, and the location of optimal discharge conditions/MCP pulse parameters/photographic film development procedures, were conducted. (mjm) ←

The spectra of interest were then taken, and microdensitometer traces of regions of those spectra were made. For a variety of reasons attempts to obtain an accurate calibration of MCP film exposure versus relative spectral

DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unlimited

access) however, is believed to be responsible for a lack of cylindrical symmetry, leading to inhomogeneity and possibly reduced stability on pinching. VUV spectra taken in N_2 revealed the NV resonance lines. A search for 5f-3d and 4f-3d lines of NV was without result, but also revealed the absence of all lines below 850 \AA . The diffraction grating of the 1 m instrument was sent to be recoated.

The last two months of the period of this report were occupied by a third phase of the experiment. The design of a third version discharge vessel was completed and construction of the same is underway. Diagnostic upgrade and maintenance and the development of supporting software were also conducted. The new vessel should be complete and operational in the near future.

Our preliminary experimental results were presented as a poster at the November 1988 Division of Plasma Physics meeting.

Our theoretical work has been in two areas: scaling of Stark widths of Li-like lines which are laser candidates, and broadening and line splitting due to resonant interactions between radiation field and dipole moments associated with the lasing transitions. Rabi splitting is predicted at high power levels in ASE amplifiers.