



SECURITY CLASSIFICATION OF THIS PAGE

2

REPORT DOCUMENTATION PAGE				Form Approved OMB No 0704-0188	
1a REPORT SECURITY CLASSIFICATION Unclassified			1b RESTRICTIVE MARKINGS		
2a SECURITY CLASSIFICATION AUTHORITY JUN 13 1991			3 DISTRIBUTION STATEMENT A Approved for public release; Distribution Unlimited		
2b DECLASSIFICATION/DOWNGRADING SCHEDULE			5 MONITORING ORGANIZATION REPORT NUMBER(S)		
4 PERFORMING ORGANIZATION REPORT NUMBER(S)					
6a NAME OF PERFORMING ORGANIZATION Dept. of Chemistry Cornell University		6b OFFICE SYMBOL (If applicable)	7a NAME OF MONITORING ORGANIZATION Office of Naval Research		
6c ADDRESS (City, State, and ZIP Code) Dept. of Chemistry Cornell University Ithaca, NY 14853		7b ADDRESS (City, State, and ZIP Code) Chemistry Program 800 N. Quincy Street Alexandria, VA 22217			
8a NAME OF FUNDING / SPONSORING ORGANIZATION Office of Naval Research		8b OFFICE SYMBOL (If applicable)	9 PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER N00014-91-J-1269		
8c ADDRESS (City, State, and ZIP Code) Chemistry Program 800 N. Quincy St. Alexandria, VA 22217		10 SOURCE OF FUNDING NUMBERS			
		PROGRAM ELEMENT NO	PROJECT NO	TASK NO	WORK UNIT ACCESSION NO
11 TITLE (Include Security Classification) Unclassified: The Distortion of Anti-perovskite Nitride AsNCa_3					
12 PERSONAL AUTHOR(S) Ming Y. Chern, F.J. DiSalvo, J.B. Parise, Joyce A. Goldstone					
13a TYPE OF REPORT Technical rpt #9		13b TIME COVERED FROM 1990 TO 1993		14 DATE OF REPORT (Year, Month, Day) May 30, 1991	
15 PAGE COUNT					
16 SUPPLEMENTARY NOTATION					
17 COSATI CODES			18 SUBJECT TERMS (Continue on reverse if necessary and identify by block number)		
FIELD	GROUP	SUB-GROUP	Structure Determination Nitrides		
			Reitveld Refinement Perovskite Distortions		
19 ABSTRACT (Continue on reverse if necessary and identify by block number) The structure of the distorted anti-perovskite nitride AsNCa_3 has been studied both by neutron powder diffraction at 305 K and 15 K and by x-ray powder diffraction at room temperature. AsNCa_3 is distorted to an orthorhombic cell with a and $b \sim \sqrt{2}a'$ and $c \sim 2a'$, where a' is the lattice constant of the ideal undistorted cubic anti-perovskite. The distortion is produced by tilting of octahedra of Ca_6N and results in six short and six long bond distances of the twelve-fold coordinated As atom by Ca atoms.					
20 DISTRIBUTION / AVAILABILITY OF ABSTRACT ☒ UNCLASSIFIED/UNLIMITED ☒ SAME AS RPT ☐ DTIC USERS			21 ABSTRACT SECURITY CLASSIFICATION Unclassified		
22a NAME OF RESPONSIBLE INDIVIDUAL Dr. Mark Roß			22b TELEPHONE (Include Area Code) 202-696-4409		22c OFFICE SYMBOL

The Distortion of Anti-perovskite Nitride AsNCa_3

Ming Y. Chern and F. J. DiSalvo*

Department of Chemistry

Cornell University

Ithaca, New York 14853

J. B. Parise

Mineral Physics Institute

State University of New York at Stony Brook

Stony Brook, New York 11794

Joyce A. Goldstone

LANSCE

Los Alamos National Laboratory

Los Alamos, New Mexico 87545

Accession For	
NTIS	CRA&I
DTIC	TAB
Unannounced	
Justification	
By	
Distribution /	
Availability	
Dist	Availability / or Specimen
A-1	



91-01801

91 6 11 080

Abstract

The structure of the distorted anti-perovskite nitride AsNCa_3 has been studied both by neutron powder diffraction at 305 K and 15 K and by x-ray powder diffraction at room temperature. AsNCa_3 is distorted to an orthorhombic cell with a and $b \sim \sqrt{2} a'$ and $c \sim 2a'$, where a' is the lattice constant of the ideal undistorted cubic anti-perovskite. The distortion is produced by tilting of octahedra of Ca_6N and results in six short and six long bond distances of the twelve-fold coordinated As atom by Ca atoms.

Introduction

Structural distortions of cubic perovskites of the formula ABX_3 , where the cation A is coordinated by twelve X anions, and the cation B is in an octahedral site formed by six X anions, to structures of lower symmetry is commonly seen. Although the distortion can be very subtle and complicated, most of the distortions can be broken up into several simple components (1): (i) displacements of the cations, (ii) tilting of the anion octahedra, and (iii) distortions of the octahedra. For example, $BaTiO_3$ is cubic at high temperatures, but, when cooled below 393 K it undergoes a structural phase transition to a tetragonal phase with the Ba^{2+} and Ti^{4+} cations displaced along a cubic [001] direction relative to the O^{2-} anions (2). On further cooling, it changes structure again to an orthorhombic phase at 273 K and a rhombohedral phase below 183 K, in which the direction of cation displacements become parallel to [110] and [111], respectively (2). As another example, $SrTiO_3$ has a structural phase transition from cubic to tetragonal when cooled below 195 K with the titanium-centered oxygen octahedra along the c-axis tilting alternately in opposite directions about that axis (3). In $CaTiO_3$, the displacement of the cations and the tilting of the anion octahedra occur simultaneously in the distorted structure (4). In $KCuF_3$, the CuF_6 octahedra are elongated (distorted) along the corner-to-corner diameters on the waist, but both the cations, K and Cu, remain centered in their polyhedra (5).

Tilting of the anion octahedra, component (ii), often dominates the overall crystal structure. The effect of the tilting on the characteristics of the superlattice lines in diffraction patterns has been systematically studied, and all the twenty three possible space groups due to this rotation of "rigid" octahedra have been classified by Glazer (6,7). According to Glazer's scheme, three superscripts, +, -, and 0, are assigned to the three pseudo-cubic axes: A "+" sign means that all the octahedra along the axis have the same sense of rotation about that axis; a "-" sign means that the octahedra rotate alternately in opposite senses; and a "0" superscript means no tilt about the axis. Thus, SrTiO_3 mentioned previously belongs to the system $\text{a}^0\text{b}^0\text{c}^-$ or $\text{a}^0\text{a}^0\text{c}^-$, where the repeated **a** indicates equal tilt, which is zero in this case, about the a- and b-axis.

The number of anti-perovskites ABM_3 , where the positions of anion and the cation are reversed from normal perovskites, i. e. A and B are anions and M is a cation, is much smaller than that of normal perovskites. However, anti-perovskites show the same tendency toward distortions as normal perovskites. In the course of searching for new ternary nitrides, we synthesized a series of anti-perovskites of the formula ANCa_3 , where A is a Group IV or a Group V element, of which AsNCa_3 and PNCa_3 are distorted from cubic and exhibit phase transitions at high temperatures (8). Interestingly, the above scheme, which works extremely well for the perovskites, can be applied equally well to the anti-perovskite AsNCa_3 . The purpose of this paper is to report the structure determination of AsNCa_3 by neutron and x-ray powder diffraction. To our knowledge this work is the first example of a distorted anti-perovskite whose structure has been solved.

Sample Preparation

Calcium nitride (Ca_3N_2) was initially prepared by heating granular calcium ($\sim 0.3 \times 0.3 \times 0.3 \text{ cm}^3$) in an N_2 atmosphere at 900°C . A well-mixed stoichiometric mixture of Ca_3N_2 and As was obtained by separately grinding the granular Ca_3N_2 and As (also in a granular form) into fine powders and then mixing both together, in the ratio $\text{Ca}:\text{As} = 3:1$, in an alumina mortar and pestle. All the procedures were carried out in a dry box because Ca_3N_2 and the product are moisture-sensitive. AsNCa_3 was subsequently prepared by heating in an alumina crucible a pressed pellet of the mixture under a flowing N_2 atmosphere at $100^\circ\text{C}/\text{hr}$ to 1000°C and held at that temperature for two days. The N_2 gas (99.995%) was pre-purified by passing it through a column of finely divided copper powder at 150°C and then through a column of activated molecular sieves to remove traces of O_2 and H_2O . Since at 1000°C the sample is very sensitive to oxidation by even minute amounts of O_2 and H_2O remaining in the N_2 gas, we further protected the sample by placing an alumina boat containing fine calcium nitride powder both before and after the sample in the alumina tube used to contain the N_2 flow. The red-colored sample made by this method does not have any obvious contamination from oxide formation by visual inspection or by x-ray diffraction (see next section). Five pellets, $\sim 1\text{g}$ each, are needed for the neutron diffraction since the cross section for neutron diffraction is relatively small compared to x-ray scattering.

X-ray and Neutron Powder Diffraction Measurements

X-ray powder diffraction data were collected at room temperature with a Scintag XDS 2000 diffractometer using copper $K\alpha$ radiation over a 2θ range of 5° to 95° with a scanning interval of 0.015° and a count time of 9 seconds per interval. Both $K\alpha_1$ and $K\alpha_2$ lines were used for the structure refinement. The sample was loaded in an aluminum holder and covered with a 0.5 mil. thick layer of Mylar in a dry box to avoid air exposure. The Mylar sheet was supported by two semicircular disks standing perpendicular to the sample so that the absorption due to the Mylar is uniform and small over the whole 2θ range. The sample dimensions are such that over the whole 2θ range the x-ray beam is fully intercepted by the powdered sample.

A 5g sample of freshly prepared sample of AsNCa_3 was packed into a standard vanadium "little finger" sample holder, fitted with an indium o-ring seal, in a dry box. Data were taken at 15 and 305 K on the neutron powder diffractometer (NPD) at the Manuel Lujan Jr., Neutron Scattering Center (LANSCE) at the Los Alamos National Laboratory. The NPD has a flight path of 32 m and a resolution $\Delta d/d$ of 1×10^{-3} . Data were collected in four detector banks, at approximately $\pm 148^\circ$ and $\pm 90^\circ$, for about 24 and 18 hours at 305 and 15 K, respectively, at average proton currents on the spallation source of 50 μA . Some of the diffraction data collected in the 148 data banks are shown in Fig. 1 & Fig. 2.

Unit Cell and Structure Determination

The unit cell was initially thought to be tetragonal. All the $00l$ lines of the original cubic cell split into doublets in the x-ray diffraction patterns. Further, the calculated line positions, based on a tetragonal cell whose axes are all approximately doubled along the three axes of the cubic cell, fit the positions of the split peaks and the superlattice reflections very well. However, attempts to solve the distorted structure in tetragonal space groups were never satisfactory, even though all possible tetragonal space groups were tried. The only possibility left is that the unit cell is monoclinic with "a" being exactly equal to "b" and the angle " γ " between "a" and "b" being very close to 90° (see Fig. 6). Here, the c-axis is the unique axis for the monoclinic cell. It is on this latter assumption that the structure was refined successfully, but it is very difficult to detect the deviation of the angle " γ ", 89.95° (see the discussion below), from 90° .

Further examination of the superlattice reflections indicated that the monoclinic cell was C-centered so it can be reduced to a primitive orthorhombic cell. Two orthorhombic space groups, $Pbn2_1$ (no. 33) and $Pbnm$ (no. 62), are consistent with the reflection conditions observed: $0kl$: $k=2n$, $h0l$: $h+l=2n$, $h00$: $h=2n$, $0k0$: $k=2n$, and $00l$: $l=2n$. However, in addition to the above general conditions, we also found some special rules for the superlattice reflections with reference to the doubled pseudo-cubic cell: they are either of the type (a) odd-odd-even with $h \neq k$, or of the type (b) odd-odd-odd with $h \neq l$ or $k \neq l$. For example, the 211 reflection of the orthorhombic cell, which is indexed as 311 or 131 (odd-odd-odd) on the doubled pseudo-cubic cell with $h \neq l$ or $k \neq l$, is observed; the orthorhombic reflection 212 , which becomes 312 or 132 (odd-odd-even) referred to

the doubled cell with $h \neq k$, is also detected. No superlattice reflections were observed other than those which are consistent with these special rules.

Glazer (6,7) has analyzed the characteristics of the superlattice lines due to the tilting of the octahedra. Tilt " c^+ " can produce reflections of type (a), while tilts " a^- " and " b^- " produce type (b) reflections. To satisfy both the general conditions and the special rules, the space group $Pbn2_1$ can be ruled out and the space group $Pbnm$ is used with the tilt system $a^-a^-c^+$ as the starting model for structure refinement. (The symmetry of the space group would have to be lowered to accommodate $a^-b^-c^+$.)

Structure Refinement

Eight calcium, four calcium, four nitrogen, and four arsenic atoms are initially located at positions (8d), (4c), (4b), and (4a) of space group $Pbnm$, respectively:

Ca(1): (8d)	$3/4-\Delta_1, 1/4+\Delta_2, \delta;$	$3/4-\Delta_1, 1/4+\Delta_2, 1/2-\delta;$
	$3/4+\Delta_1, 3/4+\Delta_2, \delta;$	$3/4+\Delta_1, 3/4+\Delta_2, 1/2-\delta;$
	$1/4-\Delta_1, 1/4-\Delta_2, -\delta;$	$1/4-\Delta_1, 1/4-\Delta_2, 1/2+\delta;$
	$1/4+\Delta_1, 3/4-\Delta_2, -\delta;$	$1/4+\Delta_1, 3/4-\Delta_2, 1/2+\delta.$
Ca(2): (4c)	$\gamma_1, 1/2-\gamma_2, 1/4;$	$-\gamma_1, 1/2+\gamma_2, 3/4;$
	$1/2-\gamma_1, -\gamma_2, 1/4;$	$1/2+\gamma_1, \gamma_2, 3/4.$
N: (4b)	$1/2, 0, 0;$	$1/2, 0, 1/2;$
	$0, 1/2, 0;$	$0, 1/2, 1/2.$

$$\begin{array}{lll} \text{As: (4a)} & -\lambda_1, \lambda_2, 1/4; & \lambda_1, -\lambda_2, 3/4; \\ & 1/2-\lambda_1, 1/2-\lambda_2, 3/4; & 1/2+\lambda_1, 1/2+\lambda_2, 1/4. \end{array}$$

where $\Delta_1, \Delta_2, \delta, \gamma_1, \gamma_2, \lambda_1$, and λ_2 are small fractions of the coordinates, on the order of 0.001, deviating from the ideal positions, e. g. $3/4, 1/4, 0; 3/4, 1/4, 1/2; \dots$; etc.. Rietveld profile analysis is used to refine those coordinates with the the x-ray and neutron powder diffraction data separately, and the generalized crystal structure analysis system (GSAS) (9) was used. For the neutron data, the 85 variables refined include lattice constants, atomic coordinates and isotropic thermal factors, and, in addition, a scale factor, four peak profile parameters ($\alpha_1, \beta_1, \beta_2, \sigma_1$) (10), twelve Fourier background coefficients and a diffractometer zero correction for each data bank. In the final refinement the x-coordinate of the As atom was fixed at the ideal value, 0, since its deviation from 0 is within 3 standard deviations. The refined results are shown in Table I & Table II; the observed intensities along with the calculated profiles and the difference plot are represented in Fig. 1 & Fig. 2 for the 148° data bank at 305 K and 15 K respectively. Also, the region from 1.0Å to 1.3Å of the two figures are scaled up in Fig. 3 & Fig. 4 to clearly show the fit. For the x-ray data, the same variables were refined, but the peak profile parameters used were a combination of Gaussian and Lorentzian shapes (GU, GV, GW, LX, LY, and LZ) (11,12); and the thermal parameters were fixed at the values refined from the neutron data. Otherwise a small non-physical negative thermal parameter for the nitrogen atom with a slightly lower residual was obtained. This likely happens because x-ray diffraction is not sensitive to a light element such as nitrogen. The results are shown in Fig. 5 & Table III.

Results and Discussion

The structure of AsNCa_3 is drawn in Fig. 6 with a view down the c-axis. The dotted lines outline the doubled cell which contains eight calcium octahedra before the tilting; the waists of the octahedra are at $z=0$ and $z=1/2$. When the c^+ tilt occurs, the octahedra rotate to the positions shown by the solid lines, and the doubled cell becomes C-centered monoclinic so it can be reduced in volume by a factor of two to the orthorhombic cell outlined by the bold solid lines. The angle " γ " of the monoclinic cell is equal to $2\sin^{-1}[b/(a^2+b^2)^{1/2}] \sim 89.95^\circ$ —very close to 90° . The calcium atoms on the waists, Ca(1), move away from their ideal sites by a distance $[(\Delta_1.a)^2+(\Delta_2.b)^2]^{1/2} \sim 0.29\text{\AA}$ at room temperature due to the tilting. (See the last section for the coordinates of the Ca(1) atoms.) Note that the neighbors of a rotating octahedron in the a-b plane have to rotate about the c-axis in opposite directions because they are all "rigid". On the other hand, the $+$ tilt requires that the octahedra above and below it have the same rotation. The other two tilts about the a' and b' -axis are indicated by the arrowed semi-circles. The two semi-circles along the a' -axis have opposite senses of rotation because of the $-$ tilt, and so do the semi-circles along the b' -axis. As a result, the Ca(1) atoms are also lifted up or pushed down the z-planes by a distance $\delta.c \sim 0.17\text{\AA}$. The arrows on the tops of the octahedra indicate the movements of the Ca(2) atoms as a combined effect of the two equal $-$ tilts, and the magnitude of the movements is equal to $[(\gamma_1.a)^2+(\gamma_2.b)^2]^{1/2} \sim 0.21\text{\AA}$. In fact the combination of the two $-$ tilts is equivalent to a single tilt about the b-axis. One can verify from the symmetry of the pattern

exhibited by these arrows that the space group should be *Pbnm*.

In this structure the calcium octahedra stay almost rigid since we find that the waists of the octahedra formed by the Ca(1) atoms are essentially square (i. e. $\Delta_1.a \sim \Delta_2.b$) and that the magnitude of the movements of the Ca(2) atoms is almost equal to square root two times the height of the Ca(1) atoms above or below the *z* planes (i. e. $[(\gamma_1.a)^2 + (\gamma_2.b)^2]^{1/2} \sim \sqrt{2} \delta.c$) as expected from the behavior of a rigid octahedron. Since the octahedra are almost regular and the tilt angles are small, the tilt angles can be estimated according to the following formula:

$$\phi \sim \sin^{-1}[\sqrt{2} (\Delta_1.a) / (c/4)],$$

$$\omega \sim \sin^{-1}[(\delta.c) / (c/4)],$$

and

$$\varphi \sim \sin^{-1}[(\gamma_1.a) / (c/4)],$$

where ϕ , ω , and φ are the rotation angles about the *c*, *a'* (or *b'*), and *b*-axes, respectively. The calculated angles based on the refined results of the neutron data are listed below:

$$305 \text{ K: } \phi=6.62^\circ, \quad \omega=3.99^\circ, \quad \varphi=5.02^\circ,$$

$$15 \text{ K: } \phi=7.54^\circ, \quad \omega=4.80^\circ, \quad \varphi=6.46^\circ.$$

The tilts are greater (or the structure is more distorted) at lower temperatures, as expected. The temperature dependence of the distortion implies that a phase transition to an undistorted cubic structure may occur above room temperature. Magnetic susceptibility measurements do suggest that such a transition takes place near 1025 K (8).

The interatomic distances are tabulated in Table IV. The N-Ca distances vary only a little with an average value of $\sim 2.40 \text{ \AA}$ (since the octahedron is nearly rigid); however, the As-N distances are spread over a large range of $\sim 0.7 \text{ \AA}$. An interesting observation is that those As-N distances which are smaller than $3.43 \text{ \AA}$

at 305 K become even smaller at 15 K, and those distances larger than 3.47Å at 305 K become even larger at 15 K. Therefore, it can be deduced that the As-N distance in the ideal undistorted perovskite is somewhere in between 3.43Å and 3.47Å. The distortion shortens half of the As-N bonds to increase the overall stability of the structure while increasing the other half of the As-N bonds. At lower temperatures, this "disproportion" of the As-N bond lengths is greater as expected.

In summary, the distorted structure of the anti-perovskite nitride AsNCa_3 has been solved. It belongs to the tilt system $a^-a^-c^+$, according to Glazer's classification of distorted perovskites. For comparison, it will be interesting to solve the structure of the other distorted anti-perovskite, ~~PbNCa_3~~ ¹², of the same family, PNCa_3

Acknowledgements

~~The~~ Support of the work at Cornell University by the Office of Naval Research is greatly appreciated.

References

1. H. D. Megaw, *Crystal Structure: A Working Approach*, Saunders, Philadelphia (1971).
2. W. J. Merz, *Phys. Rev.* **76**, 1221 (1949), and the references therein.
3. T. Mistui and W. B. Westphal, *Phys. Rev.* **124**, 1354 (1961), and the references therein.
4. H. F. Kay and P. C. Bailey, *Acta Crystallogr.* **10**, 219 (1957).
5. K. Knox, *Acta Crystallogr.* **14**, 583 (1961).
6. A. M. Glazer, *Acta Crystallogr.* **B28**, 3384 (1972).
7. A. M. Glazer, *Acta Crystallogr.* **A31**, 756 (1975).
8. M. Y. Chern, D. A. Vennos and F. J. DiSalvo, to be published.
9. A. C. Larson and R. B. Von Dreele, "Generalized Crystal Structure Analysis System," LANSCE, MS-H805, Los Alamos National Laboratory, Los Alamos, NM 87545.
10. R. B. VonDreele, J. D. Jorgensen, and C. G. Windsor, *J. Appl. Crystallogr.* **15**, 581 (1982).
11. C. J. Howard, *J. Appl. Crystallogr.* **15**, 615 (1982).
12. P. Thompson, D. E. Cox, and J. B. Hastings, *J. Appl. Crystallogr.* **20**, 79 (1982).

Figure Captions

Fig. 1 Observed (+) and calculated (solid line) neutron TOF diffraction profiles from the 148° bank for AsNCa_3 at 305 K. The reflection markers and the difference profile are also shown.

Fig. 2 Observed (+) and calculated (solid line) neutron TOF diffraction profiles from the 148° bank for AsNCa_3 at 15 K. The reflection markers and the difference profile are also shown.

Fig. 3 Magnification of **Fig. 1** from 1.0Å to 1.3Å.

Fig. 4 Magnification of **Fig. 2** from 1.0Å to 1.3Å.

Fig. 5 Observed (+) and calculated (solid line) x-ray powder diffraction profiles for AsNCa_3 at room temperature. The reflection markers and the difference profile are also shown. (a) 15° to 55° (b) 55° to 95°

Fig. 6 The observed tilt of the anti-perovskite nitride AsNCa_3 with a view down the c-axis. The dotted lines are the doubled ideal cubic cell which contains eight nitrogen-centered calcium octahedra. The solid lines outline the distorted structure, and the unit cell is drawn by the bold solid lines. (Ca: small open circles, As: large hatched circles, N: not shown.) The waists, Ca(1), of the first and second layers of the octahedra are at approximately $z=0$ and $z=1/2$ respectively; the heights

of the As atoms, $1/4$ and $3/4$, are also marked; the tips, Ca(2), of the octahedra, which locate at $z=1/4$ and $3/4$ for the first and second layers of octahedra respectively, tilt in the directions shown by the arrows. The tilt angles and directions of the octahedra about the c , a' (or b'), and b -axes are indicated by the arrowed semi-circles and are labeled as ϕ , ω , and φ , respectively.

TABLE I

Structural Parameters at 305 K Determined from Rietveld Refinement of Neutron Powder Diffraction Data

SPACE GROUP:

Pbnm

LATTICE CONSTANTS:

 $a=6.7301(2)\text{\AA}$, $b=6.7246(2)\text{\AA}$, $c=9.5402(2)\text{\AA}$

ATOMIC COORDINATES:

Atom	Symmetry Position	x	y	z
Ca(1)*	(8d)	0.7211(5)	0.2821(5)	0.0174(2)
Ca(2)	(4c)	0.0310(4)	0.4947(7)	0.2500
N	(4b)	0.5000	0.0000	0.0000
As	(4a)	0.0000	0.0108(4)	0.2500

DEVIATIONS FROM THE IDEAL SITES:

 $\Delta_1=0.0289$, $\Delta_2=0.0321$, $\delta=0.0174$, $\gamma_1=0.0310$, $\gamma_2=0.0053$, $\lambda_1=0.0000$ $\lambda_2=0.0108$

ISOTROPIC THERMAL PARAMETERS:

Atom	Symmetry Position	$U(\times 10^2 \text{\AA})$
Ca(1)	(8d)	1.47(7)
Ca(2)	(4c)	1.8(1)
N	(4b)	0.9(1)
As	(4a)	1.35(8)

RESIDUAL FACTORS:

 $R_p=4.6\%$, $R_{wp}=6.9\%$, reduced $\chi^2=1.76$ for 85 variables

*Scattering amplitudes taken from Ref. 9.

TABLE II

Structural Parameters at 15 K Determined from Rietveld Refinement of Neutron Powder Diffraction Data

SPACE GROUP:

Pbnm

LATTICE CONSTANTS:

 $a=6.7159(2)\text{\AA}$, $b=6.7110(2)\text{\AA}$, $c=9.5198(2)\text{\AA}$

ATOMIC COORDINATES:

Atom	Symmetry Position	x	y	z
Ca(1)	(8d)	0.7171(3)	0.2821(3)	0.0209(1)
Ca(2)	(4c)	0.0404(3)	0.4942(4)	0.2500
N	(4b)	0.5000	0.0000	0.0000
As	(4a)	0.0000	0.0168(2)	0.2500

DEVIATIONS FROM THE IDEAL SITES:

 $\Delta_1=0.0329$, $\Delta_2=0.0321$, $\delta=0.0209$, $\gamma_1=0.0399$, $\gamma_2=0.0048$, $\lambda_1=0.0000$,
 $\lambda_2=0.0170$

ANISOTROPIC THERMAL PARAMETERS

Atom	Symmetry Position	$U(\times 10^2 \text{\AA})$
Ca(1)	(8d)	0.54(6)
Ca(2)	(4c)	0.57(7)
N	(4b)	0.53(6)
As	(4a)	0.42(5)

RESIDUAL FACTORS:

 $R_p=5.4\%$, $R_{wp}=8.3\%$, reduced $\chi^2=1.57$ for 85 variables

TABLE III

Structural Parameters at Room Temperature Determined from Rietveld Refinement of X-ray Powder Diffraction Data[#]

SPACE GROUP:

Pbnm

LATTICE CONSTANTS:

$a=6.7250(2)\text{\AA}$, $b=6.7198(2)\text{\AA}$, $c=9.5335(1)\text{\AA}$

ATOMIC COORDINATES:

Atom	Symmetry Position	x	y	z
Ca(1)	(8d)	0.721(1)	0.279(1)	0.0171(4)
Ca(2)	(4c)	0.0346(9)	0.4943(8)	0.2500
N	(4b)	0.5000	0.0000	0.0000
As	(4a)	0.0000	0.0100(4)	0.2500

DEVIATIONS FROM THE IDEAL SITES:

$\Delta_1=0.0286$, $\Delta_2=0.0290$, $\delta=0.0171$, $\gamma_1=0.0346$, $\gamma_2=0.0057$, $\lambda_1=0.0000$,
 $\lambda_2=0.0100$


RESIDUAL FACTORS:

$R_p=10.3\%$, $R_{wp}=15.7\%$, reduced $\chi^2=1.42$ for 30 variables


[#]Thermal parameters were taken from TABLE I.

TABLE IV
Interatomic Distances (Å) for AsNCa₃


		(Number of atoms)	
	305K	10K	at that distance
N-Ca(1)	2.387(4)	2.398(3)	2
	2.416(4)	2.406(3)	2
N-Ca(2)	2.3944(3)	2.3957(2)	2
As-Ca(1)	3.083(2)	3.060(1)	2
	3.265(2)	3.256(2)	2
	3.432(2)	3.397(1)	2
	3.729(2)	3.787(2)	2
As-Ca(2)	3.158(3)	3.090(2)	1
	3.261(5)	3.216(3)	1
	3.477(5)	3.517(3)	1
	3.575(3)	3.633(2)	1



AsNCa_2 : Chern et al. Fig. 1.



AsNCa_3 : Chern et al Fig. 2



AsNiCa₃. Chernetal
Fig. 3






Fig. 4

AsNCa_3 : Chern et al





As₄₀Ca₂₀: Chemical Fig. 5a



X10E 1

AsNCa_3 : Chern et al

Fig 56



AsNCu_3 : Chermetal Fig. 6

TECHNICAL REPORT DISTRIBUTION LIST - GENERAL

Office of Naval Research (2)*
Chemistry Division, Code 1113
800 North Quincy Street
Arlington, Virginia 22217-5000

Dr. Richard W. Drisko (1)
Naval Civil Engineering
Laboratory
Code L52
Port Hueneme, CA 93043

Dr. James S. Murday (1)
Chemistry Division, Code 6100
Naval Research Laboratory
Washington, D.C. 20375-5000

Dr. Harold H. Singerman (1)
David Taylor Research Center
Code 283
Annapolis, MD 21402-5067

Dr. Robert Green, Director (1)
Chemistry Division, Code 385
Naval Weapons Center
China Lake, CA 93555-6001

Chief of Naval Research (1)
Special Assistant for Marine
Corps Matters
Code 00MC
800 North Quincy Street
Arlington, VA 22217-5000

Dr. Eugene C. Fischer (1)
Code 2840
David Taylor Research Center
Annapolis, MD 21402-5067

Defense Technical Information
Center (2)
Building 5, Cameron Station
Alexandria, VA 22314

Dr. Elek Lindner (1)
Naval Ocean Systems Center
Code 52
San Diego, CA 92152-5000

Commanding Officer (1)
Naval Weapons Support Center
Dr. Bernard E. Doua
Crane, Indiana 47522-5050

* Number of copies to forward