

AD-A270 602



DEPARTMENT OF THE AIR FORCE  
HEADQUARTERS AIR FORCE CIVIL ENGINEERING SUPPORT AGENCY  
TYNDALL AIR FORCE BASE FL 32403-6001

①



HQ AFCESA/EN

REPLY TO  
ATTN OF

139 Barnes Drive, Suite 1  
Tyndall AFB FL 32403-5319

13 JUL 1993

SUBJECT: Engineering Technical Letter (ETL) 93-2: Dormitory Criteria for Humid Areas

TO: Distribution List

1. Purpose. This letter provides the design criteria to ensure control of humidity inside dormitories in humid areas. Areas not covered by this ETL remain in accordance with existing guidance.

2. Application. This ETL applies to the design of new or renovated dormitories at Air Force bases in humid areas as described below that are not 35 percent designed. Ultimate recipients of this ETL are MAJCOMs, bases, and Air Force design and construction agents responsible for facilities in humid areas.

3. Specific Requirements.

3.1. Introduction. Existing criteria for Air Force dormitory facilities do not control interior space humidity successfully when applied in humid areas. For the purpose of this ETL, humid areas are defined as having over 3000 hours of 67°F or higher wet bulb temperature in combination with an outside design condition of 50 percent relative humidity or higher, or over 1500 hours of 73°F or higher wet bulb temperature in combination with an outside design condition of 50 percent relative humidity or higher, based on 2.5 percent dry bulb and 5 percent wet bulb temperatures. The high ambient moisture and temperature common in high humidity areas reverse vapor flow through building components and increase the latent cooling load on HVAC equipment when compared to the design conditions for most other CONUS locations. These unique conditions require design criteria different than that of the conventional wisdom used in other areas.

3.2. Building Envelope. The building envelope design shall:

3.2.1. Place the least permeable material or vapor retarder on the exterior side of the building insulation and place more permeable materials inside the building insulation.

SELECTED  
OCT 14 1993  
A D

This document has been approved for public release and sale; its distribution is unlimited.

93-23849



93 10 8 008



Providing Professional and Technical Services Worldwide

3.2.2. Provide interior surfaces of exterior walls that will allow water vapor within the wall to escape into the conditioned space. Vinyl wallcoverings, multiple coats of oil-based paint, and other vapor-resistant materials will not be used as interior finishes of exterior walls.

3.2.3. For double wythe walls, place the vapor retarder on the exterior side of the inner wythe.

3.2.4. Analyze the vapor flow through the building insulation systems, wall sections, and roof/ceiling sections. The variety of roof/ceiling systems available to the designer and the concepts for attic ventilation prevent definitive requirements from being established; however, roof/ceiling/insulation systems will reflect the following principles:

3.2.4.1. Place the vapor retarder exterior to the insulation. In some cases, the roof membrane may serve as the vapor retarder.

3.2.4.2. Ventilate spaces created exterior to the roof/ceiling vapor retarder.

3.2.4.3. Prohibit outside air entry into spaces created interior of the thermal envelope formed by the roof/ceiling insulation. Ventilation of such spaces, if required, must use air from conditioned spaces.

3.2.5. Seal all openings: around doors and windows, lintels, utility penetrations, seams in vapor retarders and air barriers, intersections of walls and roofs, etc. Provide details of vapor barrier treatments for these conditions.

3.2.6. Ensure that moisture transfer from ventilated attics into the building is minimized the same as walls.

3.2.7. Provide details to minimize thermal bridging, especially at door and window frames and the intersections of walls and roofs.

3.2.8. Provide sufficient floor-to-floor height, vertical distribution space, and mechanical equipment space to accommodate a ducted all-air HVAC system.

### 3.3. Mechanical Systems.

3.3.1. New Facilities. New facilities shall employ central station air handling units (AHUs) that supply conditioned air to variable air volume (VAV) terminal units with integral heating coils. VAV terminal units shall be the air throttling type consisting of a pressure-independent air valve which is modulated in response to space temperature. Fan-powered terminal units shall not be used. Fan coil unit air conditioning equipment shall not be used.


*pa ltr*

codes

**DTIC QUALITY INSPECTED 2**

Dist	Avail and/or Special
A-1	

3.3.2. Existing Facilities. Existing facilities to be renovated shall incorporate VAV systems as described for new facilities in 3.3.1. above.

3.3.3. General Requirements.

3.3.3.1. Terminal Heating. Terminal heating shall be applied locally at the conditioned space. The terminal heating design shall utilize recovered heat in accordance with ASHRAE STD 90.1 for reheat and other simultaneous heating and cooling.

3.3.3.2. Reheat. Air-conditioning systems in less humid geographical areas normally distribute cooling air at 55°F to 60°F. In humid areas, lower cooling coil discharge air temperatures are required to provide necessary latent cooling capacity and offset moisture gains through the building envelope. This lower coil discharge temperature may require the use of a reheat coil downstream of the AHU to bring supply air temperatures in line with normal practice and ensure that the exterior surfaces of the ductwork remain above the dew point temperature of the building ambient air. The application of this reheat coil, if used, will be in accordance with ASHRAE STD 90.1 for reheat and other simultaneous heating and cooling. Access sections shall be provided between the fan and the reheat coil.

3.3.3.3. Heat Recovery. Condenser heat recovery will be utilized for terminal heating coils in the VAV units and the reheat coil. Use of condenser heat recovery for reducing the domestic hot water load will also be considered.

3.3.3.4. Preheat. Some humid area applications may require tempering or preheating the minimum outside air to prevent freezing and/or nuisance trips of the freeze protection devices. The designer shall determine the winter design mixed-air temperature resulting from mixing the minimum outside air quantity at the winter outside air design temperature and the return air at its expected condition. If necessary, provide the central AHU with a preheat-only coil located in the outside air duct to temper the winter supply air for the VAV system. Provide preheat control to maintain a constant mixed-air temperature.

3.3.3.5. Heating. Provide an appropriately-sized heating source to meet heating requirements and back up the sources of recovered heat.

3.3.3.6. Controls. Provide control strategies as specified in Army Technical Manual TM 5-815-3, Heating, Ventilating, and Air-Conditioning (HVAC) Control Systems, except as indicated below.

3.3.3.6.1. Space heating for VAV systems shall use VAV terminal units with integral heating coils. Control shall be proportional type by the variable air terminal controller in response to a room thermostat. The heating coil control valve shall modulate open after the primary air supply to the space is at minimum setting. Deadband type thermostats will not be used in Air Force construction.

3.3.3.6.2. Cooling/dehumidification shall be accomplished by cooling coils in the AHUs. Control shall be constant leaving air temperature. Determine the leaving air set point by an engineering analysis. Leaving air set point shall not exceed 55°F.

3.3.3.6.3. Economizer cycle will not be used in Air Force construction.

3.3.3.7. Ventilation Air. Minimum outside air quantities shall comply with ASHRAE STD 62 or as required for building pressurization, whichever is larger. Positive pressure shall be maintained to reduce infiltration. Ventilation air shall be 110 percent to 120 percent of exhaust air for all spaces with direct mechanical exhaust.

3.3.3.8. Exhaust System. A central ducted exhaust system shall be used in lieu of individual exhaust fans for each space. The exhaust system shall run continuously and be interlocked with the building supply air system. The exhaust duct for each space shall have a manual volume damper accessible from the space for proper balancing.

3.3.3.9. Air Path. Return air shall be ducted. Closet and storage spaces shall have louvered doors, and return air shall be drawn through these spaces. In the event there no closets or storage spaces, the return air shall be drawn through the utility area between the living space and the bathroom.

3.3.3.10. Equipment Selection.

3.3.3.10.1. Cooling coil fin density shall be indicated on equipment schedules at 8 fins/inch maximum to ensure a cleanable coil and competitive bidding. Face velocities shall not exceed 550 ft/min to preclude moisture carryover.

3.3.3.10.2. The minimum number of cooling coil rows shall be specified in the equipment schedules. The number of rows shall be based on a comparison of data from at least three manufacturers and ensure that latent cooling loads can be met or exceeded.

3.3.3.10.3. Cooling coil entering and leaving air conditions shall be specified (wet and dry bulb temperatures) at the maximum airflow rate.


3.3.3.11. System Layout.

3.3.3.11.1. To the maximum extent possible, chilled water piping shall not be concealed in walls or ceilings of occupied spaces.

3.3.3.11.2. Insulate chilled water piping with cellular glass type insulation with an exterior vapor barrier.

3.3.3.11.3. Access panels, sufficiently sized, shall be located for maintenance of VAV boxes, dampers, controls, and associated components.

4. Commissioning. Dormitory HVAC systems will be commissioned to verify and document actual performance of the HVAC systems and evaluate conformity with the design intent. Air Force ETL 90-9, Commissioning of Heating, Ventilating, and Air Conditioning (HVAC) Systems, or Corps of Engineers Guide Specification, CECS 15995, Commissioning of HVAC Systems, will be used to develop the contract requirements for commissioning.

  
DENNIS M. FIRMAN, PE  
Director of Systems Engineering

2 Atch  
1. Distribution List  
2. ETL Index

ENGINEERING TECHNICAL LETTERS (ETL)

SECTION A - CURRENT ETLs

ETL Number	Title	Date Issued
82-2	Energy Efficient Equipment	10 Nov 82
83-1	Design of Control Systems for HVAC Change No. 1 to ETL 83-1, U.S. Air Force Standardized Heating, Ventilating & Air Conditioning (HVAC) Control Systems	16 Feb 83 22 Jul 87
83-3	Interior Wiring Systems, AFM 88-15 Para 7-3	2 Mar 83
83-4	EMCS Data Transmission Media (DTM) Considerations	3 Apr 83
83-7	Plumbing, AFM 88-8, Chapter 4	30 Aug 83
83-8	Use of Air-to-Air Unitary Heat Pumps	15 Sep 83
83-9	Insulation	14 Nov 83
84-2	Computer Energy Analysis Change 1 Ref: HQ USAF/LEEEU Msg 031600Z MAY 84 1 Jun 84	27 Mar 84
84-7	MCP Energy Conservation Investment Program (ECIP)	13 Jun 84
84-10	Air Force Building Construction and the Use of Termiticides	1 Aug 84
86-2	Energy Management and Control Systems (EMCS)	5 Feb 86
86-4	Paints and Protective Coatings	12 May 86
86-5	Fuels Use Criteria for Air Force Construction	22 May 86
86-8	Aqueous Film Forming Foam Waste Discharge Retention and Disposal	4 Jun 86
86-9	Lodging Facility Design Guide	4 Jun 86
86-10	Antiterrorism Planning and Design Guidance	13 Jun 86
86-14	Solar Applications	15 Oct 86
86-16	Direct Digital Control Heating Ventilation and Air Conditioning Systems	9 Dec 86
87-1	Lead Ban Requirements of Drinking Water	15 Jan 87
87-2	Volatile Organic Compounds	4 Mar 87
87-4	Energy Budget Figures (EBFs) for Facilities in the Military Construction Program	13 Mar 87
87-5	Utility Meters in New and Renovated Facilities	13 Jul 87
87-9	Prewiring	21 Oct 87
88-2	Photovoltaic Applications	21 Jan 88
88-3	Design Standards for Critical Facilities	15 Jun 88
88-4	Reliability & Maintainability (R&M) Design Checklist	24 Jun 88
88-6	Heat Distribution Systems Outside of Buildings	1 Aug 88

ENGINEERING TECHNICAL LETTERS (ETL)

SECTION A - CURRENT ETLs

ETL Number	Title	Date Issued
88-9	Radon Reduction in New Facility Construction	7 Oct 88
88-10	Prewired Workstations Guide Specification	29 Dec 88
89-2	Standard Guidelines for Submission of Facility Operating and Maintenance Manuals	23 May 89
89-3	Facility Fire Protection Criteria for Electronic Equipment Installations	9 Jun 89
89-4	Systems Furniture Guide Specification	6 Jul 89
89-6	Power Conditioning and Continuation Interfacing Equipment (PCCIE) in the Military Construction Program (MCP)	7 Sep 89
89-7	Design of Air Force Courtrooms	29 Sep 89
90-1	Built-Up Roof (BUR) Repair/Replacement Guide Specification	23 Jan 90
90-2	General Policy for Prewired Workstations and Systems Furniture	26 Jan 90
90-3	TEMPEST Protection for Facilities Change 1 Ref: HQ USAF/LEEDE Ltr dated 20 April 90, Same Subject	20 Apr 90
90-4	1990 Energy Prices and Discount Factors for Life-Cycle Cost Analysis	24 May 90
90-5	Fuel and Lube Oil Bulk Storage Capacity for Emergency Generators	26 Jul 90
90-6	Electrical System Grounding, Static Grounding and Lightning Protection	3 Oct 90
90-7	Air Force Interior Design Policy	12 Oct 90
90-8	Guide Specifications for Ethylene Propylene Diene Monomer (EPDM) Roofing	17 Oct 90
90-9	Fire Protection Engineering Criteria for Aircraft Maintenance, Servicing, and Storage Facilities	2 Nov 90
90-10	Commissioning of Heating, Ventilating, and Air Conditioning (HVAC) Systems Guide Specification	17 Oct 90
91-1	Fire Protection Engineering Criteria Testing Halon Fire Suppression Systems	2 Jan 91
91-2	High Altitude Electromagnetic Pulse (HEMP) Hardening in Facilities	4 Mar 91
91-3	Water Supply for Fire Protection	14 Jun 91
91-4	Site Selection Criteria for Fire Protection Training Areas	14 Jun 91
91-5	Fire Protection Engineering Criteria - Emergency Lighting and Marking of Exits	18 Jun 91
91-6	Cathodic Protection	3 Jul 91

Atch 2  
(2 of 3)

**ENGINEERING TECHNICAL LETTERS (ETL)**

**SECTION A - CURRENT ETLs**

ETL Number	Title	Date Issued
91-7	Chlorofluorocarbon (CFC) Limitation in Heating, Ventilating and Air-Conditioning (HVAC) Systems	21 Aug 91
93-1	Construction Signs	11 Mar 93
93-2	Dormitory Criteria for Humid Areas	13 Jul 93

**SECTION B - OBSOLETE ETLs**

No.	Date	Status
82-1	10 Nov 82	Superseded by ETL 83-10, 86-1, 87-4
82-3	10 Nov 82	Superseded by ETL 83-5, 84-2
82-4	10 Nov 82	Superseded by ETL 84-7
82-5	10 Nov 82	Superseded by ETL 84-1, 86-13, 86-14
82-6	30 Dec 82	Cancelled
82-7	30 Nov 82	Cancelled
83-2	16 Feb 83	Superseded by ETL 84-3
83-5	5 May 83	Superseded by ETL 84-2
83-6	24 May 83	Cancelled
83-10	28 Nov 83	Superseded by ETL 86-1
84-1	18 Jan 84	Superseded by ETL 86-14
84-3	21 Mar 84	Cancelled
84-4	10 Apr 84	Superseded by ETL 86-7, 86-15, 87-5
84-5	7 May 84	Superseded by ETL 84-8, 86-11, 86-18, 88-6
84-6	Not Issued	Cancelled/Not Used
84-8	19 Jun 84	Superseded by ETL 86-11
84-9	5 Jul 84	Superseded by ETL 88-7
88-5	2 Aug 88	Superseded by ETL 91-6
86-1	3 Feb 86	Superseded by ETL 87-7
86-3	21 Feb 86	Superseded by ETL 86-4
86-6	3 Jun 86	Superseded by ETL 86-11, 86-18, 88-6
86-7	3 Jun 86	Superseded by ETL 86-15
86-11	3 Jul 86	Superseded by ETL 88-6
86-12	3 Jul 86	Superseded by ETL 90-2
86-13	18 Aug 86	Superseded by ETL 86-14
86-15	13 Nov 86	Superseded by ETL 87-5
86-17	17 Dec 86	Superseded by ETL 89-6
86-18	18 Dec 86	Superseded by ETL 88-6
87-3	12 Mar 87	Superseded by ETL 87-6, ETL 88-5
87-6	21 Aug 87	Superseded by ETL-88-5
87-7	14 Oct 87	Superseded by ETL 89-1
87-8	19 Oct 87	Superseded by ETL 90-1
88-1	5 Jan 88	Superseded by ETL 89-2
88-7	24 Aug 88	Superseded by ETL 90-3, ETL 91-2
88-8	4 Oct 88	Superseded by ETL 91-7
89-1	6 Feb 89	Superseded by ETL 90-4
89-5		Issued as ETL 90-7
91-8	24 Sep 91	Cancelled

DISTRIBUTION LIST

AIR FORCE

HQ AFMC/CEC 4225 Logistics Ave Wright-Patterson AFB OH 45433-5006	(3)	HQ USAFA/CEE 8120 Edgerton Dr, Suite 40 USAF Academy CO 80840-2400	(1)
HQ AFRES/CEO 155 2nd Street Robins AFB GA 31098-1635	(2)	1100 CES/CEM 1 McChord Street, Suite 208 Bolling AFB DC 20332-5109	(2)
HQ AETC/CEM Bldg 661, 73 Main Circle Randolph AFB TX 78150-4549	(3)	AFIT/DEE 2950 P Street Wright-Patterson AFB OH 45433-7765	(1)
HQ PACAF/CEC 25 E Street, Suite D-302 Hickam AFB HI 96853-5412	(3)	HQ ACC/CEM 129 Andrews Street, Suite 346 Langley AFB VA 23665-2769	(3)
HQ USAFE/CEO Unit 3050, Box 10 APO AE 09094-5001	(3)	HQ AFSOC/DE Bldg T-206, 301 Cody Ave Hurlburt Field FL 32544-5273	(1)
CETSO/ESOF 11817 Canon Boulevard, Suite 500 Crestar Bank Building Newport News VA 23606-2558	(1)	HQ USAF/CEC 1260 Air Force Pentagon Washington DC 20330-1260	(1)
HQ AMC/CES 507 A Street Scott AFB IL 62225-5022	(3)	ANGRC/CEO Bldg 3500, Mail Stop 18 Andrews AFB MD 20331-6008	(2)
HQ AFSPACECOM/CEO 150 Vandenberg Street, Suite 1105 Peterson AFB CO 80914-4150	(3)	AFCEE/CM/DG 8106 Chennault Road Brooks AFB TX 78235-5318	(2)
SSC/SBEE 201 East Moore Drive (Gunter Annex) Maxwell AFB FL 36114-3005	(1)	7 CG/XPGF 6345 Air Force Pentagon Washington DC 20330-1600	(1)
NGB/CEP Room 2D369, The Pentagon Andrews AFB MD 20310-2500	(1)	HQ AFOTEC/DE 8500 Gibson Boulevard SE Kirtland AFB NM 87117-5558	(1)
HQ AFIC/LEE Bldg 2000, Room 643 San Antonio TX 78243-5000	(1)	HQ AFMWSRA/MWXF Randolph AFB TX 78150-6001	(1)
HQ AFCC/CEM 203 W Losey Street, Rm 1020 Scott AFB IL 62225-5219	(2)	HQ AF Safety Agency/SEGS Norton AFB CA 92409-7001	(1)
		HQ AFOMS/SGS Brooks AFB TX 78235-5000	(1)
		HQ AF Inspection Agency/IGSE Norton AFB CA 92409-7001	(1)

DISTRIBUTION LIST (Cont)

ARMY

US Army Corps of Engineers (1) Sacramento District AF Project Management 1325 "J" Street Sacramento CA 95814-2922	Chief of Engineers (2) Department of the Army Attn: CEMP-EA 20 Massachusetts Ave Washington DC 20314-1000
---	---

NAVY

Navy Facilities Engrg Command (1) Northern Division Code 04AB 10 Industrial Highway Mail Stop 82 Lester PA 19113-2090	Naval Facilities Engrg Command (1) Chesapeake Division Code 406C Washington Navy Yard, Bldg 212 Washington DC 20374-2121
Naval Facilities Engrg Command (1) Atlantic Division Code 04A4 Norfolk VA 23511-6287	Naval Facilities Engrg Command (1) Southern Division Code 04A3 PO Box 190010 North Charleston SC 29419-9010
Naval Facilities Engrg Command (1) Western Division Code 467.1 PO Box 727 San Bruno CA 94066-0720	Naval Facilities Engrg Command (1) Pacific Division Code 406A Pearl Harbor HI 96860-7300
Naval Facilities Engrg Command (1) Southwest Division Code 0406 1200 Pacific Highway San Diego CA 92132-5190	

DEPARTMENT OF DEFENSE

Defense Medical Facilities Off (1) Skyline Place #6, Suite 817 5109 Leesburg Pike Falls Church VA 22041	DTIC (1) ATTN: DTIC-FDA Alexandria VA 22304-6145
AAFES/ATTN: CFE (1) PO BOX 660320 Dallas TX 75266-0320	Defense Commissary Service (1) Director of Facilities Bldg 8400 Lackland AFB TX 78236-5000

SPECIAL INTEREST ORGANIZATIONS

IHS (A.A. Desimone) (1) 1990 M Street NW, Suite 400 Washington DC 20336	Construction Criteria Database (1) National Institute of Bldg Sciences 1201 L Street NW, Suite 400 Washington DC 20005
---	---