

Report Documentation Page				Form Approved OMB No. 0704-0188	
Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.					
1. REPORT DATE 30 SEP 1999		2. REPORT TYPE		3. DATES COVERED 00-00-1999 to 00-00-1999	
4. TITLE AND SUBTITLE Laboratory Investigation of Air-Sea Interfacial Properties in Relation to Gas Exchange and Remote Sensing				5a. CONTRACT NUMBER	
				5b. GRANT NUMBER	
				5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NUMBER	
				5e. TASK NUMBER	
				5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) University of Miami, Rosenstiel School of Marine and Atmospheric Science, 4600 Rickenbacker Causeway, Miami, FL, 33149				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)	
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution unlimited					
13. SUPPLEMENTARY NOTES					
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT Same as Report (SAR)	18. NUMBER OF PAGES 2	19a. NAME OF RESPONSIBLE PERSON
a REPORT unclassified	b ABSTRACT unclassified	c THIS PAGE unclassified			

Laboratory Investigation of Air-Sea Interfacial Properties in Relation to Gas Exchange and Remote Sensing

Eric S. Saltzman

Rosenstiel School of Marine and Atmospheric Science

4600 Rickenbacker Cswy.

Miami, FL 33149

phone (703) 306-1522 fax (703) 306-0377 email esaltzman@rsmas.miami.edu

Mark Donelan

Rosenstiel School of Marine and Atmospheric Science

4600 Rickenbacker Cswy.

Miami, FL 33149

phone (305) 361-4717 fax (305) 361-4689 email mdonelan@rsmas.miami.edu

Warren De Bruyn

Rosenstiel School of Marine and Atmospheric Science

4600 Rickenbacker Cswy.

Miami, FL 33149

phone (305) 361-4725 fax (305) 361-4689 email wdebruyn@rsmas.miami.edu

Grant Number: N0001499-1-0066:

<http://www.rsmas.miami.edu>

LONG-TERM GOALS

Our long range goals for this project are to: 1) understand the effect of various physical and chemical properties of the air-sea interface on gas exchange, and 2) characterize the sea surface texture and turbulent boundary layers. These studies will provide a basis for future work on the active and passive microwave remote sensing of the sea surface and the estimation of surface wind vectors and gas transfer velocities from such information.

OBJECTIVES

This project is an experimental study of wave dynamics, boundary layer turbulence, and gas exchange in a salt-water wind-wave tank. Our objectives are: 1) to relate surface texture and boundary layer turbulence to imposed surface wind stress and gustiness, and atmospheric stability to provide insight into the factors controlling remote sensing of the ocean surface, and 2) to relate direct measurements of air-sea gas fluxes to the surface water chemistry and texture and boundary layer turbulence.

APPROACH

Our approach is to carry out laboratory experiments under controlled conditions, in which we can extensively characterize the state of the fluids and interface. The experiments will be carried out using a new facility, the Air-Sea Interaction Salt-water Tank (ASIST). ASIST is a linear, recirculating wind/wave tank. During these experiments, water surface textures will be characterized using an imaging slope gauge and scanning slope gauge. Turbulence measurements in air and water will be made using hot x-films and a conical hot film probe carried by a wave follower. Turbulence

measurements and visualization in the water will also be made using particle image velocimetry. Gas exchange will be studied using eddy correlation flux measurements involving fast-response chemical detection for carbon dioxide via IR absorption, and for other gases (such as dimethylsulfide, ammonia, and sulfur dioxide) by chemical ionization mass spectrometry. The key personnel involved in the project are Drs. Eric Saltzman (gas exchange), Mark Donelan (turbulence, wave properties, and remote sensing), and Warren De Bruyn (mass spectrometry).

WORK COMPLETED

We have devoted the first year of the project to the completion of the ASIST wind/wave facility, and the procurement and development of new instrumentation. At present, all of the major components of the ASIST facility have been purchased, the physical site has been renovated. Assembly and testing of components is underway. The chemical ionization mass spectrometer is fully designed and most components have been fabricated or purchased. We have devoted considerable effort to software development to enable high frequency chemical measurements to be acquired on the same time base as the physical turbulence measurements. Bench testing of the instrument will begin later this fall. We will begin integration of the new instrumentation into the ASIST facility during the second project year, after completion of the facility.

RESULTS

We have not yet begun experiments, so no scientific results have been obtained.

TRANSITIONS

We expect that this project will eventually result in two types of transitional developments: 1) a flux measurement capability for eddy-correlation measurements of trace gases at sea, and 2) improved algorithms relating the state of the air/sea interface to remotely sensed properties.

RELATED PROJECTS

This project is closely related to a DURIP award for the construction of the ASIST wind/wave facility.