

UNCLASSIFIED

AD NUMBER	
ADA800563	
CLASSIFICATION CHANGES	
TO:	unclassified
FROM:	confidential
LIMITATION CHANGES	
TO: Approved for public release; distribution is unlimited.	
FROM: Distribution authorized to DoD only; Administrative/Operational Use; 26 JUN 1947. Other requests shall be referred to National Aeronautics and Space Administration, Washington, DC. Pre-dates formal DoD distribution statements. Treat as DoD only.	
AUTHORITY	
NACA research abstracts no. 53 dtd 2 Dec 1953; NASA TR Server website	

THIS PAGE IS UNCLASSIFIED

Reproduction Quality Notice

This document is part of the Air Technical Index [ATI] collection. The ATI collection is over 50 years old and was imaged from roll film. The collection has deteriorated over time and is in poor condition. DTIC has reproduced the best available copy utilizing the most current imaging technology. ATI documents that are partially legible have been included in the DTIC collection due to their historical value.

If you are dissatisfied with this document, please feel free to contact our Directorate of User Services at [703] 767-9066/9068 or DSN 427-9066/9068.

**Do Not Return This Document
To DTIC**

Reproduced by
AIR DOCUMENTS DIVISION



HEADQUARTERS AIR MATERIEL COMMAND
WRIGHT FIELD, DAYTON, OHIO

The
U.S. GOVERNMENT

IS ABSOLVED

FROM ANY LITIGATION WHICH MAY
ENSUE FROM THE CONTRACTORS IN-
FRINGING ON THE FOREIGN PATENT
RIGHTS WHICH MAY BE INVOLVED.

WRIGHT FIELD, DAYTON, OHIO

REEL - C

150

A.T.I.

6051

Copy No. 56

RM No. L7B19

CONFIDENTIAL

**NACA**

ATI No. 6051

RESEARCH MEMORANDUM

RESULTS OF FLIGHT TESTS AT SUPERSONIC SPEEDS TO

DETERMINE THE EFFECT OF BODY NOSE FINENESS

RATIO ON BODY AND WING DRAG

By

Ellis R. Katz

Langley Memorial Aeronautical Laboratory
Langley Field, Va.

CLASSIFIED DOCUMENT

This document contains classified information affecting the National Defense of the United States within the meaning of the Espionage Act, USC 5611 and 5612. Its transmission or the revelation of its contents in any manner to an unauthorized person is prohibited by law. Information so classified may be imparted only to persons in the military and naval services of the United States, appropriate civilian officers and employees of the Federal Government who have a legitimate interest therein, and to United States citizens of proven loyalty and discretion who of necessity must be informed thereof.

Air Documents Division, T-2
AMC, Wright Field
Micron No.
RC-150 F 6051

**NATIONAL ADVISORY COMMITTEE
FOR AERONAUTICS**

WASHINGTON
June 26, 1947

CONFIDENTIAL

NATIONAL ADVISORY COMMITTEE FOR AERONAUTICS

RESEARCH MEMORANDUM

RESULTS OF FLIGHT TESTS AT SUPERSONIC SPEEDS TO
DETERMINE THE EFFECT OF BODY NOSE FINENESS

RATIO ON BODY AND WING DRAG

By Ellis R. Katz

SUMMARY

Flight tests of rocket-powered models at supersonic speeds have been made to determine the effect of nose fineness ratio of winged bodies on total and component drag at high Mach numbers. Wingless models of three nose fineness ratios and winged models of two nose fineness ratios were flown through a Mach number range up to 1.4. On the winged models, each nose fineness ratio was investigated with wings of 45° sweepback and also with unswept wings. Both wings were untapered and of 2.7 aspect ratio. Within the scope of the tests, the results indicated that, with increasing fineness ratio of the nose of a winged body, both the total and wing drag increased at Mach numbers near 1.0 but decreased at higher Mach numbers. For a body alone, however, increasing the nose fineness ratio decreased the body drag. The tests show that the values of wing drag derived in the presence of one body may prove markedly different from those derived from the same wing on a body of different shape.

INTRODUCTION

Flight tests for the evaluation of wing drag have been performed by the Langley Pilotless Aircraft Research Division at its testing station at Wallops Island, Va., with rocket-propelled test models at supersonic speeds. Drag data were reduced from the deceleration of the models through a Mach number range from 1.4 to 1.0. The Reynolds number was approximately 5×10^6 based on wing chord. Reference 1 presents results which are a part of the investigation. The wing drag reduced from these tests, however, is the incremental drag resulting from the addition of a wing to a body-tail configuration. This increment of drag contains not only the pure drag of the wing but also contains interference effects arising from

CONFIDENTIAL

wing-body interaction phenomena. Throughout the text of this paper, the incremental drag discussed above will be defined as "wing drag." A number of previous reports, typified by reference 1, have presented wing drag obtained from flight tests of winged models all having bodies of identical shape. In order to determine what effect a change in the shape of the body of a winged model might have on wing drag, a series of tests have been conducted on winged models of different body nose fineness ratios.

MODELS AND TESTS

A photograph of a typical winged test model is shown in figure 1. The all-wooden bodies are approximately 5 feet long and of 5-inch diameter. The fuselage is made hollow to accommodate the standard 3.25-inch-diameter Mk. 7 rocket motor which develops 2200 pounds of thrust for 0.87 second at an ambient preignition temperature of 69° F. The stabilizing fins are rotated 45° out of the plane of the wings.

The seven configurations which have been tested are shown in figure 2. The three basic nose shapes are indicated as nose A, nose B, and nose C. Nose A has a blunt nose of 1.94-inch radius; nose B has a sharp nose of fineness ratio 3.5, the profile of which is the median of a conical and a circular arc profile; and nose C has a long sharp nose of fineness ratio 7 derived by multiplying the axial coordinates of profile B by a factor of 2. The untapered wings of all winged configurations were of 2.7 aspect ratio (based on total span and area) and of 0° and 45° sweepback. The NACA 65-009 airfoil sections were maintained normal to the leading edges. All wings had their centers of exposed area located on the bodies 3.4 diameters to the rear of the base of the nose. The location of the wing leading edge on the center line of the body is given by station I in the table in figure 2.

The experimental data were obtained by launching the body at an angle of 75° to the horizontal and determining its velocity along the nearly straight-line flight path. The velocity determination is made possible by a CW Doppler radar unit (AN/TPS-5) located at the point of launching. Two models of each configuration were tested and the results of each are presented. Two additional models of configuration number 3 were flown to extend the Mach number range. A typical time history of flight velocity is shown in figure 3. The deceleration due to drag is determined by graphically differentiating the coasting (after burnout) flight part of the velocity-time curve and subtracting $g \sin \theta$, where g is the acceleration of gravity and θ is the launching angle.

CONFIDENTIAL

Drag is obtained by multiplying the acceleration values by a factor equal to the ratio of the model weight to the acceleration of gravity. The drag coefficient C_D is derived from the general formula

$$C_D = \frac{D}{\frac{1}{2} \rho S V^2}$$

where D is the drag at the velocity V . The density ρ is determined from altitude-density soundings made prior to the firings. The symbol S is taken as the basic-body frontal area (0.1364 sq ft).

RESULTS AND DISCUSSION

As a means to determine the uniformity of the test results, five wingless test bodies of nose type B have been flown and the values of drag, corrected to standard conditions, are plotted against velocity in figure 4. The maximum experimental scatter from the mean-faired curve appears to be approximately ± 10 pounds drag and is nearly constant with velocity. A statistical analysis of figure 4 made by personnel of the Langley Aircraft Loads Division indicated the following probabilities:

- (a) In 95 cases out of 100, comparable groups of five models will show no greater scatter than shown in figure 4.
- (b) In 95 cases out of 100, the mean curve for groups of five models, two models, or one model will fall within ± 2 , $\pm 3\frac{1}{2}$, or $\pm 4\frac{1}{2}$ pounds, respectively, of the mean curve of figure 4.

This study dealt only with the standard wingless body and, thus, the results are directly applicable to drag data from exactly similar bodies. The standard practice of firing two test models of each configuration, however, has resulted in only one case in which the scatter was greater than that shown in figure 4, and the average scatter for all cases was about that of figure 4. Thus, the accuracy data presented here may be considered applicable to all configurations tested. The scatter is probably attributable to model fabrication tolerances, instrumentation errors, and errors inherent in the method of data reduction.

CONFIDENTIAL

Figure 5 shows drag coefficient plotted against Mach number for all models of each configuration tested, with the exception of configuration number 6 which has been presented in reference 2. Paired curves have been drawn as the median of each set of models and these curves are used as the basis for the following discussion.

Total Drag

The curves of total drag coefficient for the nose B and the nose C winged bodies of 0° and 45° sweepback are presented in figure 6. At Mach numbers near 1.0, greater drag coefficients are evidenced for the winged body with nose C than with the blunter nose B; but the reverse is true at the higher Mach numbers. This reversal of effect occurs at a lower Mach number for the unswept wing than for the swept wing. It appears, therefore, that the effect of sweepback is to increase the Mach number at which the total drag coefficient will decrease with an increase in nose fineness ratio.

Body Drag

Figure 7 shows curves of body drag coefficient (fins included) for bodies with noses A, B, and C. The curves indicate that above a Mach number of approximately 1.05 body drag coefficient decreases with increasing nose fineness ratio and that the effect increases with Mach number. The reversal of effect at Mach numbers near 1.0 is presently inexplicable and will bear further investigation. At a Mach number of 1.3, the drag coefficient of the blunt nose A model is decreased approximately 26 and 30 percent by increasing the nose fineness ratio to that of the nose B and nose C models, respectively.

Wing Drag

Figure 8 shows the variation of wing drag coefficient with Mach number for two values of sweepback, 0° and 45° , and for two nose types, nose B and nose C. The values of wing drag coefficient are derived as the difference between the drag coefficients for a winged and wingless model of the same nose type, and the values include possible interference effects. The wings of 0° and 45° sweep show greater drag with nose C than with the blunter body nose B at Mach numbers close to 1.0. As the Mach number increases, however, the effect decreases for the swept wing and reverses in the case of the unswept wing. Thus, sweepback increased the value of the Mach number at which wing drag coefficient decreases with increasing nose fineness ratio.

CONFIDENTIAL

Examination of the wing-drag-coefficient curves reveals that, throughout the Mach number range, sweepback provided a greater drag reduction on the blunter B-nosed configuration than on the sharper C-nosed configuration. For Mach numbers between 1.1 and 1.25, 45° of sweep resulted in approximately 70- and 60-percent drag reduction for the short- and long-nosed configurations, respectively.

CONCLUSIONS

Within the scope of the tests, the following conclusions were noted:

1. Values of wing drag derived in the presence of one body proved markedly different from those derived from the same wing on a body of different shape.
2. For the winged configurations, an increase in the body nose fineness ratio resulted in an increase of total drag coefficient near Mach numbers of 1.0 but resulted in a decrease of drag coefficient at higher Mach numbers. Wing sweep increased the Mach number at which the reversal of effect occurs.
3. For the winged configurations, an increase in the body nose fineness ratio resulted in an increase of wing drag coefficient for swept and unswept wings near Mach numbers of 1.0. At the higher Mach numbers, the effect decreased for the swept wing and actually reversed for the unswept wing.
4. For the winged configurations, an increase in the body nose fineness ratio decreased the reduction of drag due to sweepback.
5. For the wingless configurations, an increase in the body nose fineness ratio decreased the body drag coefficient.

Langley Memorial Aeronautical Laboratory
National Advisory Committee for Aeronautics
Langley Field, Va.

CONFIDENTIAL

REFERENCES

1. Alexander, Sidney R., and Katz, Ellis: Drag Characteristics of Rectangular and Swept-Back NACA 65-009 Airfoils Having Aspect Ratios of 1.5 and 2.7 as Determined by Flight Tests at Supersonic Speeds. NACA RM No. L6J16, 1946.
2. Alexander, Sidney R., and Katz, Ellis: Flight Tests to Determine the Effect of Length of a Conical Windshield on the Drag of a Bluff Body at Supersonic Speeds. NACA RM No. L6J16a, 1947.




Figure 1.- General arrangement of typical winged test body.




Figure 2.- General arrangement of test bodies investigated. Wing area (exposed), 200 sq in.; air foil (normal to L.E.), NACA 65-009; fin area (exposed), 136.5 sq in.; weight (burnt out), 30 lbs approx.




Figure 4-A
Figure 4.- Drag curves for five wingless bodies of nose shape B reduced to sea-level standard conditions.




Figure 6.- Total drag coefficient for winged configurations of two nose types with wings of 0° and 45° sweepback, aspect ratio of 2.7.

Fig. 3-A

NACA RM No. L7B19




Figure 3.- Typical velocity-time curve (wingless body).




Figure 8.- Wing drag coefficient for wings of 0° and 45° sweepback in presence of bodies of two nose types, aspect ratio of 2.7.




Figure 4.- Drag curves for five wingless bodies of nose shape B reduced to sea-level standard conditions.

Fig. 5-A

NACA RM No. L7B19




Figure 5. - Drag coefficient data for the models of each configuration tested with exception of No. 6.

NATIONAL ADVISORY
COMMITTEE FOR AERONAUTICS




Figure 6.- Total drag coefficient for winged configurations of two nose types with wings of 0° and 45° sweepback, aspect ratio of 2.7.

Fig. 7-A

NACA RM No. L7B19




Figure 7.- Body drag coefficient for three nose shapes.

REEL - C
150
A.T.I.

6051

TITLE: Results of Flight Tests at Supersonic Speeds to Determine the Effect of Body Nose Fineness Ratio on Body and Wing Drag

AUTHOR(S): Katz, Ellis R.

ORIGINATING AGENCY: National Advisory Committee for Aeronautics, Washington, D. C.

PUBLISHED BY: (Same)

ATI- 6051

REVISION

(None)

ORIG. AGENCY NO.

RM-L7B19

PUBLISHING AGENCY NO.

DATE	DOC. CLASS.	COUNTRY	LANGUAGE	PAGES	ILLUSTRATIONS
June '47		U.S.	Eng.	14	photo, diagrs, graphs

ABSTRACT:

Wing Body Configurations

Supersonic, rocket-powered, winged, and wingless models were tested to Mach 1.4 to determine effect of nose fineness ratio on total and component drag. Winged models with and without sweepback were tested. Results show that increased nose fineness ratio increased winged-body drag near Mach 1.0 but decreased total drag at higher Mach. Increased fineness ratio decreased drag of wingless bodies. Wing drag values change with installation on different body shapes.

Fineness Ratio P111

DISTRIBUTION: Request copies of this report only from Originating Agency

DIVISION: Aerodynamics (2)

SECTION: Parasitic Components and Interference (7)

SUBJECT HEADINGS: Aerodynamics Supersonic (02150); Drag, Aerodynamic (31080); Aircraft, Supersonic - Design (05922)

ATI SHEET NO.: C-2-7-4

U

na & a Res. Abstracts no 53, dtd 2 Dec 53

~~CONFIDENTIAL~~

TITLE: Results of Flight Tests at Supersonic Speeds to Determine the Effect of Body
Nose Fineness Ratio on Body and Wing Drag

AUTHOR(S): Katz, Ellis R.

ORIGINATING AGENCY: National Advisory Committee for Aeronautics, Washington, D. C.

PUBLISHED BY: (Same)

ATI- 6051

CLASS (None)

ORD. AGENCY NO.

RM-17B19

PUBLISHED AGENCY NO.

DATE	DOC. CLASS.	COUNTRY	LANGUAGE	PAGES	ILLUSTRATIONS
June '47	CONFIDENTIAL	U.S.	Eng.	14	photo, diagrs, graphs

ABSTRACT:

Supersonic, rocket-powered, winged, and wingless models were tested to Mach 1.4 to determine effect of nose fineness ratio on total and component drag. Winged models with and without sweepback were tested. Results show that increased nose fineness ratio increased winged-body drag near Mach 1.0 but decreased total drag at higher Mach. Increased fineness ratio decreased drag of wingless bodies. Wing drag values change with installation on different body shapes.

DISTRIBUTION: Request copies of this report only from Originating Agency

DIVISION: Aerodynamics (2)

SECTION: Parasitic Components and
Interference (7)

SUBJECT HEADINGS: Aerodynamics Supersonic (02150);
Drag, Aerodynamic (31080); Aircraft, Supersonic - Design
(05922)

ATI SHEET NO.: C-2-7-4

Air Documents Division, Intelligence Department
Air Materiel Command

AIR TECHNICAL INDEX
~~CONFIDENTIAL~~

Wright-Patterson Air Force Base
Dayton, Ohio