

UNCLASSIFIED

AD NUMBER
ADA800637
CLASSIFICATION CHANGES
TO: unclassified
FROM: restricted
LIMITATION CHANGES
TO: Approved for public release; distribution is unlimited.
FROM: Distribution authorized to DoD only; Administrative/Operational Use; 20 SEP 1945. Other requests shall be referred to National Aeronautics and Space Administration, Washington, DC. Pre-dates formal DoD distribution statements. Treat as DoD only.
AUTHORITY
E.O. 10501 dtd 5 Nov 1953; NASA TR Server website

THIS PAGE IS UNCLASSIFIED

UNCLASSIFIED

AD NUMBER

ADA800637

CLASSIFICATION CHANGES

TO:

restricted

FROM:

confidential

AUTHORITY

USC, 18 Dec 1947, per document marking

THIS PAGE IS UNCLASSIFIED

Reproduction Quality Notice

This document is part of the Air Technical Index [ATI] collection. The ATI collection is over 50 years old and was imaged from roll film. The collection has deteriorated over time and is in poor condition. DTIC has reproduced the best available copy utilizing the most current imaging technology. ATI documents that are partially legible have been included in the DTIC collection due to their historical value.

If you are dissatisfied with this document, please feel free to contact our Directorate of User Services at [703] 767-9066/9068 or DSN 427-9066/9068.

**Do Not Return This Document
To DTIC**

Reproduced by
AIR DOCUMENTS DIVISION



HEADQUARTERS AIR MATERIEL COMMAND

WRIGHT FIELD, DAYTON, OHIO

The **U.S. GOVERNMENT**

IS ABSOLVED

FROM ANY LITIGATION WHICH MAY

ENSUE FROM THE CONTRACTORS IN -

FRINGING ON THE FOREIGN PATENT

RIGHTS WHICH MAY BE INVOLVED.

REEL - C

551

A.T.I.

1 5 3 4 6

RESTRICTED

RESTRICTED


68929-M

~~CONFIDENTIAL~~

MR No. ES120

ATI No. 15346

NATIONAL ADVISORY COMMITTEE FOR AERONAUTICS



RETURN TO
N.A.C.A. LIAISON
TSEST-7C, 2-9241

2961B

RETURN TO
N.A.C.A. LIAISON
TSEST-7C, 2-9241

Classification cancelled
or changed to

RESTRICTED

AUTH:

USC 50:31 & 32

MEMORANDUM REPORT

for the

Air Technical Service Command, Army Air Forces

COOLING OF GAS TURBINES

II - EFFECTIVENESS OF RIM COOLING OF BLADES

By Lincoln Wolfenstein, Gene L. Merer, and John S. McCarthy

Aircraft Engine Research Laboratory
Cleveland, Ohio



CLASSIFIED DOCUMENT

This document contains classified information affecting the national defense of the United States within the meaning of the Espionage Act, USC 50:31 and 32. Its transmission or the revelation of its contents in any manner to an unauthorized person is prohibited by law. Information so classified may be imparted only to persons in the military and naval services of the United States, appropriate civilian officers and employees of the Federal Government who have a legitimate interest therein, and to United States citizens of known loyalty and discretion who of necessity must be informed thereof.

September 20, 1945

~~CONFIDENTIAL~~

RESTRICTED

RETURN TO
N.A.C.A. LIAISON
TSEST-7C, 2-9241

68929-M

RESTRICTED

RECEIVED
NACA MEMPHIS

NACA NR No. ES120

~~CONFIDENTIAL~~

(SESF-C.2-514)

NATIONAL ADVISORY COMMITTEE FOR AERONAUTICS

MEMORANDUM REPORT

for the

Air Technical Service Command, Army Air Forces

COOLING OF GAS TURBINES

II - EFFECTIVENESS OF RIM COOLING OF BLADES

By Lincoln Wolfenstein, Gene L. Meyer, and John B. McCarthy

SUMMARY

An analysis is presented of rim cooling of gas-turbine blades; that is, reducing the temperature at the base of the blade (wheel rim), which cools the blade by conduction alone. Formulas for temperature and stress distributions along the blade are derived and, by the use of experimental stress-rupture data for a typical blade alloy, a relation is established between blade life (time for rupture), operating speed, and amount of rim cooling for several gas temperatures. The effect of a blade parameter combining the effects of blade dimensions, blade thermal conductivity, and heat-transfer coefficient is determined. The effect of radiation on the results is approximated. The gas temperatures ranged from 1300° to 1900° F and the rim temperatures, from 0° to 1000° F below the gas temperature. This report is concerned only with blades of uniform cross section, but the conclusions drawn are generally applicable to most modern turbine blades. For most blades, gas-temperature increases are limited to about 200° F for 400° to 500° F of cooling of the blade base below gas temperature, and additional cooling brings progressively smaller increases. In order to obtain increases in gas temperature of the order of 400° F either very large increases in thermal conductivity or very large decreases in heat-transfer coefficient or blade length are necessary. The increases in gas temperature allowable with rim cooling are particularly small for turbines of large dimensions and high specific mass flows. Substantial increases in blade life, however, are possible with relatively small amounts of rim cooling. Elongation due to creep is not a practical limit to the operation of most turbine blades.

INTRODUCTION

At the request of the Air Technical Service Command, Army Air Forces, the NACA is conducting an investigation of the cooling of gas turbines that will include direct blade cooling by the passage

~~CONFIDENTIAL~~

RESTRICTED

RESTRICTED

2

~~CONFIDENTIAL~~

NACA MEMO. RE120

of liquid or air through hollow blades and indirect blade cooling by removal of heat from the blade root or tip. In part I of this series of reports (reference 1) a calculation is made of the complete temperature distribution in a gas turbine in which the blades are cooled indirectly by air blown over finned surfaces on the disk and blade shrouds. It was found that the base of the blade was cooled about 500°F below gas temperature. In the present report the benefits of blade cooling are determined in terms of turbine operating conditions by combining the temperature distribution in the blades with the mechanical limitations to blade operation. The report is limited to rim-cooled blades; that is, blades cooled only at the base.

Only two types of mechanical limitation to blade operation are considered: (a) rupture due to centrifugal stress, and (b) elongation of the blade beyond the design tip clearance due to excessive creep of the blade metal at high stresses and temperatures. Actually, these two limitations are both manifestations of the same property of the material because fracture occurs at the point along the blade where the local plastic elongation is greater than the metal can withstand. Contributions to failure from vibration stresses or corrosion are not considered.

The benefits of blade cooling may be measured by increases in allowable gas temperature, blade speed, or blade life, where life is the time to rupture due to centrifugal stress. Speed is ordinarily limited for aerodynamic reasons by the design Mach number and the purpose for which the turbine is used usually determines the desired life. The purpose of this report is to determine the effectiveness of rim cooling as indicated by the increases in allowable gas temperature that can be obtained without changes in blade Mach number or blade life. The increase in blade life that could be obtained by a sacrifice of some of the increase in allowable gas temperature is indicated, and the effects on rim-cooling effectiveness of blade dimensions, blade thermal conductivity, and heat-transfer coefficient from the hot gases to the blade metal are evaluated. The elongation of the blade due to creep and its importance as a limitation on blade operation are determined.

Although the quantitative results of the analysis are dependent on a number of simplifying assumptions, particularly that of a uniform blade cross section, the trends indicated and the order of magnitude of the results are believed to apply generally to most turbine blades.

~~CONFIDENTIAL~~

RESTRICTED

RESTRICTED

NACA MR No. ES120

~~CONFIDENTIAL~~

3

SYMBOLS

a	velocity of sound at T_0 , (ft/sec)
A	blade cross-sectional area, (sq ft)
B	number of blades
$\bar{D}$	mean diameter of turbine blades ($2r_t - L$), (ft)
e	percentage elongation at any blade point
e_m	percentage elongation of blade metal
e_t	total percentage elongation of blade
F	fraction of blade surface area exposed to radiation from one side
g	acceleration of gravity, 32.2 (ft/sec ²)
h	heat-transfer coefficient based on T_g , Btu/(hr)(sq ft)(°F)
k	blade thermal conductivity, Btu/(hr)(ft)(°F)
L	blade length, (ft)
M	tip Mach number index. V/a
M_{max}	limiting tip Mach number index, V_{max}/a
P	blade perimeter, (ft)
r	radius of turbine at any point on blade, (ft)
r_t	tip radius of turbine, (ft)
R	gas constant, 53.5 (ft-lb)/(lb)(°R)
s	actual stress at any point on blade. (lb/sq in.)
s_{max}	stress for rupture for given life and temperature, (lb/sq in.)
T	temperature of blade at any point, (°R)

~~CONFIDENTIAL~~

59 4

RESTRICTED

~~CONFIDENTIAL~~

NACA MR No. E5120

4

- T_a allowable temperature at any blade point, ($^{\circ}\text{R}$)
- T_e effective gas temperature for use in heat-transfer equations, ($^{\circ}\text{R}$)
- ΔT permissible increase in effective gas temperature due to blade cooling for constant M_{max} , ($^{\circ}\text{F}$)
- T_{in} total temperature of inlet gas, ($^{\circ}\text{R}$)
- T_R average blade temperature used in radiation approximation, ($^{\circ}\text{R}$)
- T_r temperature at blade root (wheel rim), ($^{\circ}\text{R}$)
- T_i temperature of radiating surface on inlet side of blades, inlet nozzles, ($^{\circ}\text{R}$)
- T_e temperature of radiating surface on exhaust side of blades, ($^{\circ}\text{R}$)
- V blade tip speed, (ft/sec)
- V_R blade velocity at mean diameter, (ft/sec)
- V_{max} limiting blade tip speed, (ft/sec)
- V_w whirl component of inlet gas, (ft/sec)
- x distance from blade root to any point on blade, (ft)
- x_c critical blade point, (ft)
- Y, Z parameters defined by equation (17) in appendix
- a parameter equal to $\sqrt{hp/kA}$, (ft) $^{-1}$
- γ ratio of specific heats
- ϵ emissivity of metal surfaces
- ρ density of blade metal, (slugs/cu ft)
- σ Stefan-Boltzmann constant, 0.174×10^{-8} Btu/(hr)(sq ft)($^{\circ}\text{R}$) 4
- ω angular velocity of turbine wheel, (radians/sec)

~~CONFIDENTIAL~~

THEORETICAL ANALYSIS

Although a relation between the effective gas temperature T_e and the amount of cooling $T_e - T_0$ for a constant limiting Mach number index $M_{\max}$ is desired, the method of analysis makes it necessary to calculate first the values of the tip speed at rupture and the corresponding values of $M_{\max}$ for assumed values of T_e and $T_e - T_0$. The method consists in combining calculated temperature and stress distributions in the blade with experimental stress-rupture data. The solution depends upon the choice of blade metal, the expected blade life, and the values of two dimensionless parameters αL and L/r_t . Means of accounting for radiation and of calculating the blade elongation due to creep are also presented.

Assumptions. - In the derivation of expressions for the temperature and stress distributions, the following simplifying assumptions are made:

1. The blade is of uniform cross-sectional area and perimeter.
2. The heat-transfer coefficient and the effective gas temperature are constant over the blade height. An average value for the thermal conductivity can be used over the blade height because the variation of conductivity with temperature is small for most turbine metals.
3. The blade tip is perfectly insulated. This assumption has little effect on the calculated temperature distribution except very close to the tip, because the temperature of the blade tip in the usual case differs only a small amount from the gas temperature and the tip area is usually small compared with the surface area of the blade.
4. The temperature gradients in any cross section of the blade perpendicular to the radius of the turbine are negligible.
5. Bending stresses in the blade are negligible with the result that the calculated blade stress is uniform over any cross-sectional area.

Temperature distribution. - The blade temperature at any point is found from a heat balance of the blade. (See appendix.) If radiation is neglected,

$$T = T_0 + \frac{\cosh \left[\alpha L \left(1 - \frac{x}{L} \right) \right]}{\cosh \alpha L} (T_e - T_0) \quad (1)$$

~~CONFIDENTIAL~~

NACA MR No. E5120

where

$$\alpha = \sqrt{hp/KA}$$

The inclusion of radiation, by means of an approximation suggested in reference 2, gives

$$T = \frac{Z}{Y} = \frac{\cosh \left[\sqrt{Y} L \left(1 - \frac{1}{L} \right) \right]}{\cosh \sqrt{Y} L} \left(\frac{Z}{Y} - T_0 \right) \quad (2a)$$

where

$$\sqrt{Y} L = \alpha L \sqrt{1 + 60\epsilon F \frac{1}{h} T_R^3} \quad (2b)$$

and

$$\frac{Z}{Y} = \frac{T_0 + 3\epsilon F \left(\frac{1}{h} \right) (T_1^4 + T_2^4 + 6T_R^4)}{1 + 60\epsilon F \left(\frac{1}{h} \right) T_R^3} \quad (2c)$$

For given values of gas temperature and rim temperature, the temperature distribution without radiation (equation (1)) as a function of z/l depends only on the dimensionless parameter αl , which is fixed by the blade dimensions, the blade conductivity, and the heat-transfer coefficient. This parameter may be considered as a measure of the ratio of the average temperature drop over the blade length to the average temperature drop across the film between the hot gases and the blade. Accordingly, as the value of αl is decreased, an increased percentage of the temperature drop between the gas and the blade root occurs through the film and all blade temperatures are reduced. The temperature distribution including radiation (equation (2a)) is identical to equation (1) with $\sqrt{Y} L$ substituted for αl and Z/Y for T_0 .

Stress distribution. - The actual stress in the blade at any position is found by integrating the centrifugal load over the blade length

$$\sigma = \frac{\rho \omega^2 (r_t^2 - r^2)}{2bh} \left\{ 1 - \left[1 - \frac{1}{r_t} \left(1 - \frac{r}{L} \right)^2 \right] \right\} \quad (3)$$

For given values of blade metal density and of the ratio of blade height to turbine radius at the blade tip, the stress distribution is a function of z/L depends only on the blade tip speed.

Limiting tip speed. - Experimental stress-rupture data for blade metal give the maximum stress the metal can withstand for a given

~~CONFIDENTIAL~~

temperature and life. If the blade life is specified, the maximum stress is a function of only the temperature

$$\sigma_{\max} = \sigma_{\max}(T) \quad (4)$$

Equations (3) and (4) may be combined to find the allowable temperature at any blade point and for any blade speed for a given blade metal and constant values of blade life, gas temperature T_0 , amount of rim cooling $(T_0 - T_0)$, and the parameters αL and L/r_0 :

$$T_a = T_a\left(\frac{x}{L}, v\right) \quad (5)$$

A family of curves of T_a as a function of x/L with v as a parameter may be drawn.

Failure occurs when the actual blade temperature at one blade point is greater than the allowable temperature. The limiting tip speed is that for which the allowable temperature is just equal to the actual temperature at one point on the blade, which is called the critical blade point because the blade would fracture at this point if the tip speed were increased. Mathematically, the limiting tip speed and the critical blade point are defined by two simultaneous equations

$$T\left(\frac{x_0}{L}\right) = T_a\left(\frac{x_0}{L}, v_{\max}\right) \quad (6a)$$

$$\frac{dT}{d\left(\frac{x}{L}\right)}\left(\frac{x_0}{L}\right) = \frac{\partial T_a}{\partial \left(\frac{x}{L}\right)}\left(\frac{x_0}{L}, v_{\max}\right) \quad (6b)$$

where $T(x/L)$ is the temperature distribution given by equation (1) or (2a). If the solution gives a critical point outside the blade length, equation (6b) is invalid and the critical point is at the root; in this case $v_{\max}$ is found from equation (6a) with $x_0/L = 0$. Because of the empirical origin of the function T_a , these equations are conveniently solved by graphical methods, as illustrated in figure 1.

The tip Mach number index is defined as the tip speed of the blade divided by the velocity of sound in the gas and is a measure of the actual Mach number of the gas flowing past the blade for a given velocity diagram. If the velocity of sound is calculated from the effective gas temperature, the limiting tip Mach number index is expressed

~~CONFIDENTIAL~~

NACA MR No. ES120

$$M_{\max} = \frac{V_{\max}}{a} = \frac{V_{\max}}{\sqrt{\gamma g R_0}} \quad (7)$$

Blade creep. - Experimental data on the creep properties of blade metals give the percentage elongation for a given life as a function of metal temperature and stress

$$e_s = e_s(T, s) \quad (8)$$

When equation (8) is combined with the actual stress-distribution equation (3) and the temperature-distribution equation (1) or (2), the actual percentage elongation of the blade at any point and for any tip speed may be found

$$e = e\left(\frac{r}{r_t}, v\right) \quad (9)$$

The total percentage elongation of the blade is found by integration over the blade height for any blade speed,

$$e_t = \int_0^1 e\left(\frac{r}{r_t}, v\right) d\left(\frac{r}{r_t}\right) \quad (10)$$

This equation is useful only for values of $v \leq V_{\max}$ because, for greater values, the elongation of the blade becomes infinite, corresponding to blade fracture. The evaluation of equation (10) may be carried out graphically.

APPLICATION OF ANALYSIS

The foregoing analysis is general and applies to any blade of uniform cross section. A blade section was assumed and the corresponding values of the dimensionless parameter αL and L/r_t were used to obtain quantitative results. These values are referred to as the "basic" values. In order to show the effect of heat-transfer coefficient, blade conductivity, and blade dimensions on the results, calculations were made for values of αL equal to $1/3$, $1/2$, 1 , 2 , and 3 times the basic value. A single value of L/r_t was used throughout because the effectiveness of cooling depends very little on L/r_t for the usual range of values for constant αL . The quantitative results are also dependent on the assumed mechanical properties of the blade metal. Values of the effective gas temperature from 1300° to 1900° F and of amounts of rim cooling from 0° to 1000° F were assumed. The value of the limiting Mach number index was calculated for each pair of values of T_0 and $T_0 - T_0$ for a value of γ of 1.31 .

~~CONFIDENTIAL~~

Blade dimensions, conductivity, and heat-transfer coefficient.

The basic values of al and L/r_t were determined from values of the blade dimensions, the blade-metal conductivity, and the heat-transfer coefficient representative of those found in modern high-temperature gas turbines:

Area of blade cross section A , sq ft	0.000728
(or 0.1047 sq in.)	
Perimeter of blade cross section p , ft	0.20
(or 2.40 in.)	
Blade length L , ft	0.146
(or 1.75 in.)	
Radius at tip r_t , ft	0.570
(or 6.84 in.)	
Thermal conductivity of the blade k , Btu/(hr)(ft)(°F)	12
Heat-transfer coefficient h , Btu/(hr)(sq ft)(°F)	40
Basic value of al	4.42
Basic value of L/r_t	0.26

The value of h of 40 Btu/(hr)(sq ft)(°F) corresponds to relatively low mass flows; because of this relatively low value of h and the choice of a fairly short blade, the basic value of al probably is as low as is obtainable at present.

Mechanical properties of blade metal. - The assumed mechanical properties of the blade metal are shown in figures 2 and 3. These properties are based on available data (references 3 and 4) for 3497 alloy, which is a forged ferrous alloy, high in nickel, chromium, and cobalt content with a density of 0.31 pound per cubic inch, and are extrapolated to include a wide range of temperatures. The stress-rupture properties (fig. 2) are typical of the stronger alloys now available for turbine blades but the creep properties (fig. 3) are relatively poor. 3497 was selected in order to accentuate any possible creep limitations in blade design.

Effective gas temperature. - The effective gas temperature T_e , rather than the total temperature at the inlet to the turbine T_t , is used in the analysis because it is the temperature that enters into the heat-transfer equation. The power and the efficiency of a compressor-turbine unit, however, depend on T_t , and the relation between these two temperatures should be known.

The effective temperature is approximately equal to the total temperature relative to the moving blades; the ratio of the total inlet temperature to the effective temperature calculated at the mean blade diameter is therefore

$$\frac{T_t}{T_e} = 1 + \frac{\gamma - 1}{2} \left(\frac{V_m}{a} \right)^2 \left(2 \frac{V_w}{V_m} - 1 \right)$$

where

$$\frac{V_a}{a} = \frac{V}{a} \frac{b}{2r_c}$$

For a constant blade Mach number and a given velocity diagram, which determines V_a/V_m , the inlet total temperature is directly proportional to the effective temperature. For example, if the Mach number index is set at 0.5 (and $b/2r_c = 0.67$), $T_a/T_e = 1.041$ for $V_a/V_m = 1.2$ (typical of reaction blades) and $T_a/T_e = 1.088$ for $V_a/V_m = 2.0$ (typical of impulse blades).

Radiation. - The effect of radiation on the temperature distribution depends to a great extent upon the particular installation of the turbine, which determines the values of the temperatures T_1 and T_2 as well as the validity of the approximations used in treating radiation. (See appendix.) The results were calculated without radiation, but the manner in which the various radiation assumptions modified these results was investigated.

In the application of the radiation equation (2a), the following assumptions were made:

1. The average blade temperature T_R used in the approximation

$$T^4 = 4T_R^3 T - 3T_R^4$$

given in the appendix as equation (15), was set equal to $T_e - (1/4)(T_e - T_0)$; this value was determined by comparing the temperature distribution given by equation (2) for several values of T_R with one found by numerical integration of the exact differential equation for a typical case. For extremely high conductivities or low heat-transfer coefficients, this value of T_R gives blade temperatures that are slightly low. A somewhat lower value for T_R would be more accurate for this case.

2. Values of T_2/T_1 of 1.0, 0.9, 0.75, and 0 with T_1 equal to T_0 were assumed; more generally, if T_1 does not equal T_0 , these assumed values correspond to values of $T_1^4 + T_2^4$ of 2.0, 1.656, 1.316, and 1.0 times the value of T_0^4 , respectively. The value of T_1 for a given T_0 depends on the difference between the inlet total temperature and the effective gas temperature and on the extent to which the nozzles are cooled. The temperature T_2 on the exit side of the blades is particularly dependent on the installation because the value of T_2 depends on whether the blades exhaust to the stators of another stage, to an exhaust hood, or directly to the atmosphere.

~~CONFIDENTIAL~~

3. The factor cF , which enters equations (2b) and (2c), was set equal to 0.312. This value was obtained by assuming closely spaced blades for which the total blade-surface area exposed to radiation from either side is approximately equal to the annulus area πDL . Consequently, F was set equal to $\pi DL/3\pi L$ which was evaluated as 0.312 using the basic blade dimensions and a value of B of 50. The value of c was considered equal to 1, which is close to the value for oxidized metal surfaces.

RESULTS AND DISCUSSION

Effectiveness of rim cooling for basic blade. - The over-all effect of rim cooling for the basic blade ($uL = 4.42$) is shown in figure 4; radiation effects and blade elongation are not included. Because the basic value of uL is lower than that for most modern turbines, these results for the basic blade may be considered representative of the turbines for which rim cooling is most effective. Blade life is plotted on a logarithmic scale against the limiting Mach number index; families of curves, each for a constant effective gas temperature and several amounts of rim cooling are shown. Large increases in blade life can be obtained with small increases in the amount of cooling at a constant Mach number index. For example, increasing the amount of cooling from 200° to 400° F at a gas temperature of 1500° F and a constant limiting Mach number index of 0.5 results in increasing the allowable life eightfold. Because the curves of figure 4 are approximately parallel, results for a single value of blade life are fairly typical of all values.

A cross plot of curves of the type in figure 4 at 1000 hours (fig. 5) shows the effective gas temperature as a function of the amount of rim cooling for constant values of the limiting Mach number index. Figure 5 indicates the effect of different amounts of rim cooling on the allowable gas temperature for a given design because the limiting Mach number index at which a turbine is to be operated is determined by the design.

The data of figure 5 for a constant limiting Mach number index of 0.5 have been replotted in figure 6 as the increase in gas temperature ΔT_0 greater than that allowable without cooling. The corresponding increase in the inlet total temperature is from 2 to 10 percent greater than the value of ΔT_0 , depending on the velocity diagram of the turbine. Lines of constant limiting Mach number index of 0.4 and 0.6 give values of ΔT_0 that vary less than 30° F from those in figure 6. The small effect of Mach number index can be explained by the fact that the lines of constant limiting Mach number index are approximately parallel in figure 5. At lower limiting Mach

CONFIDENTIAL

NACA MR No. E5120

numbers, the values of AT_0 are slightly less; therefore, rim cooling is somewhat less effective at high gas temperatures.

It should be emphasized that figures 4 and 5 give values at rupture, whereas in actual operation a turbine would be run with some factor of safety. The actual operating point could be determined either by expressing the desired life as some fraction of that for rupture or by using an effective gas temperature somewhat lower than that for rupture. If these actual operating conditions were shown in figures 4 and 5, the only significant change would be a general displacement of the curves relative to the axes. If the factor of safety is introduced only by means of a specified reduction in the effective gas temperature, the curves of figure 6 are valid for the actual operating conditions as well as for those at rupture.

Increases in effective gas temperature from 140° to 200° F are made available by the first 250° to 500° F of rim cooling (fig. 6) but additional cooling yields only relatively small gains in allowable gas temperature. This effect can be explained to some extent by the fact that, for the greater amounts of cooling, the critical blade point is farther from the root (fig. 7) and therefore more difficult to cool. Actually, the first amounts of cooling and the corresponding large increases in allowable gas temperature may not be available in most turbines because the rim may be 100° to 300° F below the gas temperature as a result of the cooling of the wheel and the shaft by lubricating oil and radiation.

Effect of blade dimensions, conductivity, and heat-transfer coefficient. - The value of the dimensionless parameter al completely determines the effect of blade dimensions, conductivity, and heat-transfer coefficients on the results when radiation is neglected and the ratio L/r_0 is constant.

The temperature distribution in the blade is shown in figure 8 for an effective gas temperature of 1500° F and a value of $(T_0 - T_0)$ of 100° F for seven values of al including the limiting values of ∞ and 0; these curves are superimposed on a family of allowable-temperature curves for a 1000-hour life to determine the critical blade points. For values of al greater than 4.42, the blade temperatures are very close to the gas temperature over half the length of the blade, whereas for smaller values of al all blade temperatures are considerably lower than that of the gas. The critical blade point is close to the root for small values of al and approaches the blade tip as al is increased to a value of about 4, but for larger values of al the critical point again becomes closer to the root. At low values of al , the critical blade point actually

CONFIDENTIAL

remains at the root for the first several hundred degrees of cooling but then moves quite rapidly toward the tip as cooling is increased (fig. 7).

The variation in the effectiveness of rim cooling with changes in αL is shown in figure 6 for a blade life of 1000 hours. The increase in allowable effective gas temperature is much greater for the lower values of αL ; thus, for a value of $T_g - T_0$ of 600° F. the increase is 440° F for αL of 1.47, 215° F for 4.42, and only 90° F for 15.26. At values of αL greater than 4.42 there is little increase in ΔT_g with increasing amounts of cooling above 300° to 400° F but, for the very low values of αL , ΔT_g continues to increase almost proportionally with $T_g - T_0$ over the entire range considered. This cooling can be used, of course, to increase blade life beyond 1000 hours by sacrificing some of the increase in gas temperature; for example, a sacrifice of about 60° F in gas temperature for αL of 4.42 makes possible a tenfold increase in life.

The low values of αL necessary for rim cooling to be very effective could possibly be obtained by increasing the value of conductivity or decreasing the value of the heat-transfer coefficient from the basic values. For example, the value αL is halved if k is increased from 12 to 48 Btu/(hr)(ft)(°F) or if h is decreased from 40 to 10 Btu/(hr)(sq ft)(°F). Unfortunately, none of the alloys now available for use at high temperatures and stresses has a conductivity much greater than 12. In a given turbine the increased cooling effectiveness obtained by increasing the conductivity might be offset by the fact that additional heat must be removed from the blade to maintain the same rim temperature.

A relatively low value of h might be obtained by a proper adjustment of the design velocities over the blades, but these velocities are usually restricted by aerodynamic considerations. The use of insulating coatings on the blade results in small reductions in the over-all heat-transfer coefficient from the hot gases to the metal blade from an initially low value of h , such as 40 Btu/(hr)(sq ft)(°F), although the coating can produce relatively large reductions from a high value. For example, if h is 40, a coating 0.010 inch thick with a conductivity of 0.5 Btu/(hr)(ft)(°F) will reduce the over-all coefficient only 6 percent; if h is 250, the same coating will reduce the over-all coefficient 30 percent. A coating, however, may weaken the blade or increase the ratio p/A and thus αL , which might completely counteract the favorable effect of the reduction in the over-all film coefficient.

A low value of αL can also be obtained by the use of a short blade or a blade with a small p/A ratio. In order to obtain the same mass flow when the blade length is decreased, the tip radius

must be increased, which means that the increased cooling effectiveness is gained at the price of increasing the size of the turbine. The value of L/r_t is also decreased in this case with the result that the calculations are not strictly applicable; it may be shown, however, that although a decrease in L/r_t causes a considerable increase in the limiting Mach number index the decrease has little effect on the curves of AT_u against $T_u - T_0$ (fig. 6). The ratio of blade perimeter to area, which depends upon the shape and the size of the blade, is limited by aerodynamic considerations and no significant change in aL can usually be obtained by a variation in p/A .

On the other hand, large high-power turbines are likely to have values of aL considerably greater than 4.42 for two reasons: (a) these turbines have large specific mass flows and consequently the value of h is greater than 40; and (b) these turbines have dimensions greater than the basic values assumed. For example, if the heat-transfer coefficient is increased from 40 to 120 and all the dimensions are multiplied by 3 (thus multiplying $\sqrt{p/A} L$ by $\sqrt{3}$), aL is increased from 4.42 to 13.26.

Blade creep. - The distribution of local elongation due to creep over the blade length and the corresponding stress and temperature distributions are shown in figure 9 for a particular set of conditions. The total blade elongation obtained by integration of the distribution of local elongation is also given in the figure for each tip speed. The percentage elongation of the blade at rupture depends primarily on the temperature at the critical point where most of the elongation occurs. The temperature at the critical point for effective gas temperatures from 1400° to $1500^\circ F$ is in the neighborhood of $1350^\circ F$, at which temperature the elongation of the blade is a maximum (fig. 3); accordingly, the maximum blade elongation for these gas temperatures should be the maximum elongation for any gas temperature.

The elongation of the basic blade for a gas temperature of $1500^\circ F$ is plotted against Mach number index for several amounts of cooling in figure 10. The maximum elongation indicated is only about one-sixteenth inch, which is less than most blade-tip clearances. If a shorter blade life were assumed, the maximum elongation at rupture would be expected to be somewhat larger and might be excessive. For longer blades the maximum percentage elongation is expected to be about the same; for such blades, therefore, the total elongation at rupture may be considerably greater than allowed by the tip clearances.

CONFIDENTIAL

Actual blade elongations, however, will be much smaller than the maximum values indicated because the turbine is actually operated with a factor of safety and the elongation is greatly reduced by a small decrease in Mach number index or a small increase in cooling. An actual turbine would never be operated at a speed corresponding to the vertical portion of the curves of figure 10, for very little overspeed would result in rupture. Inasmuch as the creep properties assumed for the blade metal were relatively poor, actual turbine operation will not be limited by blade creep.

Effect of radiation. - The effect of radiation on these results varies greatly with the assumed values of the radiation temperatures T_1 and T_2 . If these temperatures are equal to the gas temperature, the effect of radiation is approximately the same as the effect of an increased value of the heat-transfer coefficient or of αL . The influence of radiation on the effectiveness of cooling can then be found by using values of $\sqrt{Y} L$ as effective values of αL in figure 6. The magnitude of the increase depends upon h and T_g alone for a constant value of cP (equation (2b)). For small values of h and large values of T_g (corresponding to high gas temperatures), the value of $\sqrt{Y} L$ may be as much as two or three times the value of αL ; however, for the basic value of h (40 Btu/(hr)(sq ft)(°F)), $\sqrt{Y} L$ is only about 1.3 times the value of αL .

If T_1 or T_2 is assumed less than T_g , as is likely for most turbines, the effective increase in αL will be counteracted by a decrease in Z/Y , which has the same effect on the temperature distribution as decreasing T_g . In figure 11, the temperature distribution for the basic value of αL of 4.42 and no radiation is compared with that for four radiation approximations. As the value of T_2/T_1 , and correspondingly Z/Y , is decreased, all blade temperatures are decreased and the limiting Mach number indices increase; the limiting Mach number index for no radiation is approximately the mean of the values for different radiation assumptions and the critical blade point is somewhat closer to the tip than for the examples that include radiation. The increase in allowable gas temperature with radiation is compared in the following table with that for no radiation for equal amounts of cooling. $T_1 = T_g = 1960^\circ R$, and a 1000-hour life:

~~CONFIDENTIAL~~

NACA MR No. E5120

T_2/T_1	h (Btu/(hr) (sq ft) (°F))	Z/Y (°R)	$Z/Y - T_0$ (°F)	$\sqrt{Y} L$	αL	ΔT_e (no radiation) (°F)	ΔT_e (radiation) ΔT_e (no radiation)
0.9	40	1925	665	5.62	4.42	224	1.0
.9	40	1920	360	5.78	4.42	173	1.0
.9	360	1954	694	13.69	13.26	95	1.0
.9	40	1925	665	1.67	1.47	480	1.0
.9	4.44	1894	624	3.78	1.47	455	.7
.75	4.44	1791	531	3.78	1.47	400	1.0
.75	40	1883	623	5.62	4.42	218	1.0
.75	360	1947	687	13.69	13.26	95	1.0

Results are shown for the two most probable radiation approximations, T_2/T_1 equal to 0.9 and 0.75 and for values of αL of 1.47, 4.42, and 13.26. The cases in which the values of αL of 1.47 and 13.26 are obtained by varying h from its basic value are considered separately from those in which h or the blade dimensions are varied. When radiation is considered, the blade temperature with no cooling is approximately Z/Y ; the amount of cooling is thus $Z/Y - T_0$. Values of ΔT_e (no radiation) were obtained from figure 6 at points where $T_0 - T_0 = Z/Y - T_0$.

When T_2/T_1 is 0.9, the difference between the effectiveness of rim cooling with or without radiation is slight. The only significant variation is for the extreme case in which h has been decreased to one-ninth its basic value. Radiation then becomes a large percentage of the total heat input and the cooling effectiveness drops with the allowable increase in effective gas temperature with radiation only 70 percent of that without radiation. If T_2/T_1 is assumed equal to 0.75, Z/Y becomes relatively low and tends to counteract the effective increase in the value of αL . For example, for the extreme case when h is 4.44, the ratio of ΔT_e with radiation to ΔT_e without radiation is increased from 0.7 to 0.9 when T_2/T_1 is decreased from 0.9 to 0.75.

CONCLUSIONS

From an analysis of the rim cooling of a typical gas-turbine blade and also variation of a blade parameter, the following conclusions were drawn:

1. The benefits of rim cooling are limited to increases in allowable gas temperature of the order of 200° F for most blades; if this

~~CONFIDENTIAL~~

increase in gas temperature is sacrificed, however, extremely large increases in blade life are possible. For this typical blade, the effective gas temperature could be raised 200°F for a 500°F decrease in rim temperature below gas temperature at a constant limiting Mach number index. Alternatively, if the gas temperature and the Mach number index are held constant, the expected life could be multiplied by a hundred for the same amount of cooling.

2. The dependence of the effectiveness of rim cooling on the heat-transfer coefficient, the blade dimensions, and the blade thermal conductivity is determined by a single blade parameter. In order to obtain increases in gas temperature of the order of 400°F , extreme increases in thermal conductivity or decreases in heat-transfer coefficient or blade length are necessary. For turbines of large dimensions and high specific mass flows the increases in gas temperature possible with rim cooling are particularly small.

3. Rim cooling is most effective for the first 250° to 500°F of cooling of the rim (below gas temperature); with more cooling, benefits become progressively smaller. For the typical blade, 500°F of cooling allows a gas temperature increase of 200°F , whereas 1000°F of cooling gives an additional increase of only 60°F . This effect is inherent in the indirectness of rim cooling because, as the amount of cooling is increased, the critical point on the blade moves farther from the source of cooling (blade base) and cooling therefore becomes progressively more difficult. In order to obtain large increases in gas temperature, some direct method of cooling would probably have to be used, in which a considerable portion of the blade length is cooled by contact with a coolant fluid.

4. Blade creep beyond the end clearance is not generally a practical limit to blade operation.

Aircraft Engine Research Laboratory,
National Advisory Committee for Aeronautics,
Cleveland, Ohio, September 20, 1945.

Lincoln Wolfenstein
Lincoln Wolfenstein,
Physicist.

Gene L. Meyer
Gene L. Meyer,
Mechanical Engineer.

John S. McCarthy
John S. McCarthy,
Mechanical Engineer.

Approved: Oscar W. Schoy,
Mechanical Engineer.

lrp

~~CONFIDENTIAL~~

APPENDIX - DERIVATION OF TEMPERATURE-DISTRIBUTION EQUATIONS

A heat balance for the steady state for a differential element dx between two planes perpendicular to the blade length and at distances x and $x + dx$ from the blade root is considered. The difference between the amount of heat leaving the element by conduction dQ_x and the amount entering by conduction $dQ(x + dx)$ is equal to the sum of the heat entering by convection dQ_c and by radiation dQ_R :

$$dQ_x - dQ(x + dx) = dQ_c + dQ_R \quad (11)$$

$$\left(ka \frac{dT}{dx}\right) - \left(ka \frac{dT}{dx} + ka \frac{d^2T}{dx^2} dx\right) = hp(T_u - T) dx + dQ_R \quad (12)$$

If dQ_R is set equal to zero and $hp/ka = \alpha^2$

$$\frac{d^2T}{dx^2} = -\alpha^2(T_u - T)$$

A solution of this equation is

$$T = T_u - C_1 \cosh \alpha (x - C_2) \quad (13)$$

where C_1 and C_2 are arbitrary constants. Because the tip is assumed to be insulated $\frac{dT}{dx} = 0$ at $x = L$. At $x = 0$, $T = T_0$.

Substitution of these boundary conditions in equation (13) gives the final equation for the temperature distribution when radiation is neglected

$$T = T_u - \frac{\cosh \left[\alpha L \left(1 - \frac{x}{L} \right) \right]}{\cosh \alpha L} (T_u - T_0) \quad (1)$$

Radiation may be approximately accounted for by assuming the blades are faced on the inlet side by nozzles at an average temperature T_1 and on the exhaust side by exit stators or an exhaust hood at an average temperature T_2 . If the fraction of the blade-surface area exposed to radiation from either side is F and if contributions to dQ_R from radiation between the blades are neglected,

$$dQ_R = \epsilon F \left[(T_1^4 - T^4) + (T_2^4 - T^4) \right] F dx \quad (14)$$

As an approximation T^4 is expanded linearly about an average blade temperature T_R

~~CONFIDENTIAL~~

~~CONFIDENTIAL~~

$$T^4 = 4T_R^3 T - 3T_R^4 \quad (15)$$

When equations (14) and (15) are combined and the result is substituted in equation (12)

$$\frac{d^2 T}{dx^2} - YT + Z = 0 \quad (16)$$

where

$$\left. \begin{aligned} Y &= \frac{hPL + 8\sigma F PL T_R^3}{KAL} \\ Z &= \frac{hPL T_0 + \sigma F PL (T_1^4 + T_2^4 + 6T_R^4)}{KAL} \end{aligned} \right\} \quad (17)$$

If Y and Z are assumed constant over the blade height, the general solution of equation (16) is

$$T = \frac{C_1 \cosh[\sqrt{Y}(x + C_2)] + Z}{Y} \quad (18)$$

The arbitrary constants C_1 and C_2 are determined by applying the same boundary conditions as before, and the resulting equation for the temperature distribution when radiation is included is

$$T = \frac{Z}{Y} - \frac{\left(\frac{Z}{Y} - T_0\right) \cosh\left[\sqrt{Y}L\left(1 - \frac{x}{L}\right)\right]}{\cosh\sqrt{Y}L} \quad (2a)$$

Equations (17) may also be written

$$\sqrt{Y}L = \alpha L \sqrt{1 + 8\sigma F \frac{1}{h} T_R^3} \quad (2b)$$

$$\frac{Z}{Y} = \frac{T_0 + \sigma F \frac{1}{h} (T_1^4 + T_2^4 + 6T_R^4)}{1 + 8\sigma F \frac{1}{h} T_R^3} \quad (2c)$$

~~CONFIDENTIAL~~

REFERENCES

1. Brown, W. Byron: Cooling of Gas Turbines. I - Effect of Addition of Fins, Partial Admission of Cooling Air, and Change in Thermal Conductivity of Turbine Components. NACA MR No. E5E31, Army Air Forces, Aug. 31, 1945.
2. Sims, M. W., and Morris, R. H.: Temperature Distribution Analysis for Buckets of Gas Turbines. Data Folder No. 71252, Gen. Eng. Lab., General Electric Co., May 16, 1941.
3. Cross, E. C., Stewart, W. C., and McCann, W. J.: Compilation of Current Data on Selected Alloys Suitable for High Temperature Service in Gas Turbine and Supercharger Parts. Ser. M-12, OSRD Rep. 722, Nat. Acad. Sci., Nat. Res. Council, War Metallurgy Committee, July 22, 1942.
4. Cross, Edward C., and Simmons, Ward F.: Progress Report on Heat-Resisting Metals for Gas Turbine Parts (M-102). OSRD No. 3651, Ser. No. M-290, NDRC, OSRD, War Metallurgy Div., May 1944.




Figure 1. - Method of determining limiting speed and critical blade point from curves of temperature distribution and allowable temperature.

NATIONAL ADVISORY
COMMITTEE FOR AERONAUTICS


~~CONFIDENTIAL~~

Figure 2. - Stress-rupture characteristics for high-temperature alloy 5407. (Points from experimental data in references 3 and 4.)

~~CONFIDENTIAL~~




Figure 3. - Effect of stress on elongation due to creep for S497 at constant metal temperatures and blade life of 1000 hours. (Points from experimental data in references 3 and 4.)

NATIONAL ADVISORY
COMMITTEE FOR AERONAUTICS

~~CONFIDENTIAL~~

~~CONFIDENTIAL~~




Figure 4. - Effect of limiting Mach number index, rim cooling, and exhaust-gas temperature on expected life of turbine blade when α is 4.42.

NATIONAL ADVISORY
COMMITTEE FOR AERONAUTICS

~~CONFIDENTIAL~~




Figure 5. - Effect of rim cooling on allowable effective gas temperature for various limiting tip Mach number indices, at of 4.42, and blade life of 1000 hours.

NATIONAL ADVISORY
COMMITTEE FOR AERONAUTICS


~~CONFIDENTIAL~~

Figure 6. - Allowable increase in effective gas temperature for various amounts of rim cooling, several values of α , limiting Mach number index of 0.5, and blade life of 1000 hours.

~~CONFIDENTIAL~~

~~CONFIDENTIAL~~




Figure 7. - Effect of rim cooling on location of critical blade point for various values of at , effective gas temperature of 1500° F., and blade life of 1000 hours.

NATIONAL ADVISORY
COMMITTEE FOR AERONAUTICS

~~CONFIDENTIAL~~


~~CONFIDENTIAL~~

Figure 8. - Effect of w/l on temperature distribution and location of blade critical point for effective gas temperature of 1500° F., $T_g - T_\infty$ of 700° F., and blade life of 1000 hours.

NATIONAL ADVISORY
COMMITTEE FOR AERONAUTICS

~~CONFIDENTIAL~~

~~CONFIDENTIAL~~




Figure 9. - Distribution of temperature, stress, and elongation due to creep for Al of 4.4% effective gas temperature of 1500° F, $T_g - T_b$ of 700° F, and blade life of 1000 hours.

~~CONFIDENTIAL~~

~~CONFIDENTIAL~~




Figure 18. - Effect of Mach number index on blade elongation due to creep for constant film cooling, at of 0.42, effective gas temperature of 1500° F. and blade life of 1000 hours.

NATIONAL ADVISORY
COMMITTEE FOR AERONAUTICS

~~CONFIDENTIAL~~

RESTRICTED

NACA MR No. E5120

CONFIDENTIAL




Figure 11. - Comparison of temperature distribution, limiting tip speed, and critical blade position without radiation and for various radiation assumptions, at 4.42, effective gas temperature of 1500° F., $\tau_c = \tau_0$ of 7000° F., and blade life of 1000 hours.

RESTRICTED

CONFIDENTIAL

REEL - C

551

A.T.I.

1 5 3 4 6

ADMINISTRATIVE (15 K 4 4)

Wolfenstein, L.
Meyer, Gene
McCarthy, John

RESTRICTED

DIVISION: Power Plants, Jet and Turbine (5)
SECTION: Cooling (1)
CROSS REFERENCES: Turbine blades - Cooling (95308);
Cooling conduction (27200)

ATI- 15346

ORIG. AGENCY NUMBER

MR-E5I20

REVISION

AUTHOR(S)

AMER. TITLE: Cooling of gas turbines - II - Effectiveness of rim cooling of blades

FORG'N. TITLE:

ORIGINATING AGENCY: National Advisory Committee for Aeronautics, Washington, D. C.

TRANSLATION:

COUNTRY	LANGUAGE	FORG'N. CLASS.	U. S. CLASS.	DATE	PAGES	ILLUS.	FEATURES
U.S.	Eng.		Restr.	Sep'45	21	12	table, graphs

ABSTRACT

An analysis of rim cooling, which cools the blade by conduction alone, was conducted. Gas temperatures ranged from 1300° to 1900°F and rim temperatures from 0° to 1000°F below gas temperatures. Results show that gas temperature increases up to 200°F are permissible provided that the blades are cooled by 400° to 500°F below the gas temperature. Relatively small amounts of blade cooling, at constant gas temperature, give large increases in blade life. Dependence of rim cooling on heat-transfer coefficient, blade dimensions, and thermal conductivity is determined by a single parameter.

NOTE: Requests for copies of this report must be addressed to: N.A.C.A., Washington, D. C.

T-2, HQ. AIR MATERIEL COMMAND

TECHNICAL INDEX
RESTRICTED

WRIGHT FIELD, OHIO, USAAF

17-0-21 MAR 47 21,500

FORM 89-A (13 MAR 47)

Wolfenstein, L.
Meyer, Gene
McCarthy, John

AUTHOR(S)

~~RESTRICTED~~

DIVISION: Power Plants, Jet and Turbine (5)
SECTION: Cooling (1)
CROSS REFERENCES: Turbine blades - Cooling (95308);
Cooling conduction (27200)

ATI- 15346

GRIG. AGENCY NUMBER

MR-E5I20

REVISION

AMER. TITLE: Cooling of gas turbines - II - Effectiveness of rim cooling of blades

FORG'N. TITLE:

EO 12801 dd 5 NOV 1953

ORIGINATING AGENCY: National Advisory Committee for Aeronautics, Washington, D. C.

TRANSLATION:

COUNTRY	LANGUAGE	FORG'N. CLASS	U. S. CLASS.	DATE	PAGES	ILLUS.	FEATURES
U.S.	Eng.		Restr.	Sep'45	21	12	table, graphs

ABSTRACT

An analysis of rim cooling, which cools the blade by conduction alone, was conducted. Gas temperatures ranged from 1300° to 1900°F and rim temperatures from 0° to 1000°F below gas temperatures. Results show that gas temperature increases up to 200°F are permissible provided that the blades are cooled by 400° to 500°F below the gas temperature. Relatively small amounts of blade cooling, at constant gas temperature, give large increases in blade life. Dependence of rim cooling on heat-transfer coefficient, blade dimensions, and thermal conductivity is determined by a single parameter.

NOTE: Requests for copies of this report must be addressed to: N.A.C.A., Washington, D. C.

I-2, HQ., AIR MATERIEL COMMAND

AIR TECHNICAL INDEX
~~RESTRICTED~~

WRIGHT FIELD, OHIO, USAAF

WF-O-21 MAR 47 22,500