

UNCLASSIFIED

|                                                                                                                                                                                                                                                                    |              |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|
| AD NUMBER                                                                                                                                                                                                                                                          |              |
| ADA800687                                                                                                                                                                                                                                                          |              |
| CLASSIFICATION CHANGES                                                                                                                                                                                                                                             |              |
| TO:                                                                                                                                                                                                                                                                | unclassified |
| FROM:                                                                                                                                                                                                                                                              | restricted   |
| LIMITATION CHANGES                                                                                                                                                                                                                                                 |              |
| TO:<br>Approved for public release; distribution is unlimited.                                                                                                                                                                                                     |              |
| FROM:<br>Distribution authorized to DoD only; Foreign Government Information; FEB 1946. Other requests shall be referred to British Embassy, 3100 Massachusetts Avenue, NW, Washington, DC 20008. Pre-dates formal DoD distribution statements. Treat as DoD only. |              |
| AUTHORITY                                                                                                                                                                                                                                                          |              |
| DSTL, AVIA 6/12777, 8 Oct 2009; DSTL, AVIA 6/12777, 8 Oct 2009                                                                                                                                                                                                     |              |

THIS PAGE IS UNCLASSIFIED


# Reproduction Quality Notice

This document is part of the Air Technical Index [ATI] collection. The ATI collection is over 50 years old and was imaged from roll film. The collection has deteriorated over time and is in poor condition. DTIC has reproduced the best available copy utilizing the most current imaging technology. ATI documents that are partially legible have been included in the DTIC collection due to their historical value.

If you are dissatisfied with this document, please feel free to contact our Directorate of User Services at [703] 767-9066/9068 or DSN 427-9066/9068.

**Do Not Return This Document  
To DTIC**

Reproduced by  
**AIR DOCUMENTS DIVISION**



**HEADQUARTERS AIR MATERIEL COMMAND**

**WRIGHT FIELD, DAYTON, OHIO**

*The*  
**U.S. GOVERNMENT**

**IS ABSOLVED**

**FROM ANY LITIGATION WHICH MAY**

**ENSUE FROM THE CONTRACTORS IN -**

**FRINGING ON THE FOREIGN PATENT**

**RIGHTS WHICH MAY BE INVOLVED.**

REEL - C

1 27

A.T.I.

5 3 6 3

E118:47.

TECHNICAL INTELLIGENCE CENTER (OF-32.F2)  
NAVY DEPARTMENT  
WASHINGTON, D.C.

AAF  
AMC (TSRPR)  
ASDevRon One  
BAGR, Wright Field  
BuAer  
BuDocks  
BuMed  
BuOrd  
BuPers  
BuShips 330c for  
CIG  
CinCLant  
CinCPac  
COIS-BAD  
DTMB  
EExprmtl Sta Annapolis  
Gen. Bd.

JANAID  
JIC  
JIOA  
JCB  
MIS-Reading Panel  
MIS-Elec.Sect.Sc.Br.  
NA London  
NAMC  
NAMTC  
NAMU  
NavElecLab San Diego  
NavOrdTest Sta  
NavTechUnitEu  
NavTorpSta. Newport  
NavWar College  
NOF Washington  
NOL NOF Wash  
NOL Silver Spring  
NOP Annapolis  
NPF Indian Head  
NPG-Dahlgren  
NRL  
NUSL New London

OCSigO  
ONR  
ONR Boston  
ONR Chicago  
ONR Harvard U  
ONR Los Angeles  
ONR New York  
ONR Pt Wash.  
ONR San Francisco  
ONR SpecDevCen  
OQIG WD  
OrdDispU NPF-Indian Head  
OFDevForLant  
PIC  
SurASDevDetLant  
USCG  
USMC  
1st Task Fleet  
OP-

*Com. Gen'l*  
*Air Materiel Command*  
*Wright Field Dayton Ohio*  
*Attn TSNLI*

RESTRICTED

TECHNICAL NOTE No: Inst. 960


SECRET

UNITED STATES DEPARTMENT OF THE ARMY

# ROYAL AIRCRAFT ESTABLISHMENT

Farnborough. Hants.

## A 4-WAY ELECTRONIC SWITCH



and

J. H. MITCHELL

ATTENTION IS CALLED TO THE PERMITTES ATTACHED  
TO AND REFERENCE OF THE OFFICIAL SECRETS ACT  
THIS DOCUMENT IS THE PROPERTY OF THE GOVERNMENT

IT IS ATTENDED FOR THE USE OF THE RECIPIENT ONLY AND FOR COMMUNICATION TO SUCH OFFICERS UNDER  
WHICH AS MAY REQUIRE TO BE ACCORDANCE WITH THE CONTENTS OF THE REPORT IN THE COURSE OF THEIR  
DUTIES THE OFFICER EXERCISING THIS POWER OF COMMUNICATION WILL BE HELD RESPONSIBLE THAT SUCH  
AN INDIVIDUAL IS ADVISED WITH THE CAUTION AND RESERVE

AND PERSON OTHER THAN THE AUTHORIZED INDIVIDUAL OR OFFICER POSSESSION OF THIS DOCUMENT, BY  
FINDING OR OTHERWISE SHOULD FORWARD IT, TOGETHER WITH HIS NAME AND ADDRESS IN A CLOSED ENVELOPE  
TO:

THE SECRETARY, MINISTRY OF SUPPLY,  
WARREN HOUSE, BILLINGHAM, LONDON S.W.1.

LETTER POSTAGE NEED NOT BE PREPAID OTHER POSTAGE WILL BE REPAID.

ALL PERSONS ARE HEREBY WARNED THAT THE UNAUTHORIZED RETENTION OR DESTRUCTION OF THIS  
DOCUMENT IS AN OFFENCE AGAINST THE OFFICIAL SECRETS ACT 1911-1920.

219-144

NO. 144

Bu 9rd - 144

COLORED

101

Rpt. A-144-144

144-144-144

18 NOV 1944

U.D.C. No. 621.316.543.2 : 621.389

R.A.E. Technical Note No. Inst. 960

February, 1946.

ROYAL AIRCRAFT ESTABLISHMENT, FARNBOROUGH

A 4-way Electronic Switch

by

R.H. James  
and  
J.H. Mitchell

R.A.E. Ref. Inst. 4108

SUMMARY

This note gives details of a 4 way electronic switch designed for use with strain gauge bridge networks.

4 signals fed into the switch are presented, amplified, at the output, 500 times per second each, in recurring succession.

A gain control for each channel is provided, maximum amplification in each case being 1000. The output may be applied to the Y plates of a CRT. It then appears as 4 spots, if there is no 'time base', with a vertical displacement between them which may be set as desired by 4 'Y shift' controls.

1 Introduction

Although the problem of electronic switching for strain gauge work and kindred applications has been under investigation for some time, good switches are rare and very few electronic switches were available commercially in this country before the war.

It was therefore found necessary to design and build a four-way electronic switch to meet the following requirements:-

- (i) A flat frequency response from zero to a few hundred cycles.
- (ii) Sufficient amplification of a 100 mV. signal to give full CR tube deflection (this requiring about 100 volts) and
- (iii) Cross modulation to be down to at least -40 dB's.

Probably the most difficult problem in the design of such a switch was the production of a suitably square pulse-shape for switching. As an overall gain of 1000 is required, any lack of squareness in the pulse is readily shown up. The usual difficulty of D.C. amplifiers was also encountered, and a very stable power pack is necessary for satisfactory operation.

- 2 -  
RESTRICTED  
2



2 Design Details

2.1 The Circuit Employed - (Refer to Diagram No. 10643). The system employs basically two multi-vibrators, one locked to and running at half the speed of the other, to carry out the switching of six amplifying valves. The output of the faster multi-vibrator is applied to the suppressor grids of four input amplifying valves A, B, C and D, the multi-vibrator signal on the valves A and C being 180 degrees out of phase with that to B and D.

The input signals are passed through gain controls and thence to the control grids of the valves, A, B, C and D. The anodes of valves A and B are commoned and also those of valves C and D. The commoned output from valves A and B is passed to the control grid of a fifth valve E and that from valves C and D is passed to control grid of a sixth valve F.

The output from the slower multi-vibrator is fed to the suppressors of valves E and F, whose anodes are commoned. In this anode circuit will appear the signals from A, B, C and D, in turn.

A certain amount of amplification is provided in the switch, the remainder being made up by a final amplifying stage, which also drops the mean D.C. level at its anode to earth potential, since its anode is connected through the load to a positive potential, and its cathode to a negative voltage with respect to earth.

Suppose now that the output is applied to the "Y" plates of a Cathode Ray Tube, to the "X" plates of which a sweep voltage is applied. Four lines will appear, each line corresponding to one of the switching circuits, and the bias settings will give a "Y" shift for each line, permitting movement in their relative positions, the gain settings controlling the amplitude of the signals appearing on these lines. It has been mentioned that the gain of each of the four channels to be switched is controlled at the input. The vertical position of the spot on the cathode ray tube for each of the four signal inputs is controlled by a bias, applied to each of the valves A, B, C and D.

The interaction i.e. the appearance of a signal on one trace, while actually being applied to another, must be reduced to a negligible quantity compared with the accuracy of measurement. This has been found to be better than 40 dB (100:1) in amplitude.

2.2 Difficulties Encountered in the Design - As indicated earlier, two major difficulties were encountered in design.

The first of these is the necessity to provide a very square switching voltage from the multi-vibrator. Not only must the top be flat, but the sides must be steep, and it was found that the normal multi-vibrator circuit did not give a sufficiently square output. The circuit has been modified by using pentodes with the screen grids as the multi-vibrator anodes, the output being taken from the anodes. This arrangement gives a marked improvement.

The second difficulty is that D.C. amplification must be employed. If condenser coupling were used, the effect of an applied D.C. signal to one channel would be that of changing the mean level of zero volts with respect to earth of the output. This would result in the shifting of all four traces, giving an apparent interaction of the signals. The primary difficulty in designing the D.C. amplifying circuits has been that of obtaining sufficient stability in the H.T. supply. Neon stabilisation has proved totally inadequate, and valve stabilisation using a battery reference voltage is now being employed. A new method of H.T.

stabilisation is also being evolved which it is hoped will be good to one part in 1000.

### 3 Application

When this switch is used with strain gauges and similar appliances, no time base is applied to the "X" plates, but the spot movements in the "Y" direction are photographed on a film moving in the "X" direction. A typical example of the trace obtained is shown in Plate 11 Fig.4.

For all applications so far, the highest frequency to be recorded is about a hundred cycles, and the existing speeds of the multi-vibrators of 1000 and 500 cycles/sec. are adequate, each of four signals being presented 500 times a second.

It may, however, be necessary substantially to increase the switching frequencies at a later stage, and preliminary experimental work has shown that this is possible and switching frequencies up to 90 kc are attainable. For non-recurring phenomena, the switching frequencies must be high in comparison with the frequencies in the phenomena under examination, while for recurrent phenomena, much higher frequencies than the switching frequencies can be displayed and a continuous "picture" is presented on the C.R. Tube when a 'time base' synchronised to the signal frequency is applied to the "X" plates. First reports on the use of this equipment in aircraft structural investigations are very encouraging.

### 4 Conclusion

A continuation of this development is the incorporation of the switch into a C.R. Tube assembly. This is now being undertaken, and will be reported on in due course.

#### Attached:

Diag. No. 10643  
Neg. No. 59638

#### Distribution:


D. Inst. R.D.  
A.D.R.D. Inst. A and/or B  
D.O.D.  
Chief Supt. T.R.E.  
RTE/TIB.  
A.&A.E.E.  
M.A.E.E.  
A.F.E.E.  
Power Jets, Pyestock.  
D.D.R.A.E.  
Library  
Head of Inst. Dept.  
Head of Division  
Spec. Section Inst. Dept.  
File  
Head of Radio Dept.  
Head of Elec. Dept.

47 + 1

2

RESTRICTED

DIAG. N° 10643.



BLOCK SCHEMATIC.

4-WAY ELECTRONIC SWITCH.


DIAG. N° 10643.

ISSUE N° 1.  
DATE. 30.1.45.

RESTRICTED



5

FIG. 13



SWITCH (COVER REMOVED)

SWITCH (FROM BELOW)



GLIDER INSTALLATION FOR  
FOUR MEASUREMENTS

SPECIMEN OF RECORD



4-WAY ELECTRONIC SWITCH

FIG. 13

RESTRICTED

REEL - C

1 27

A.T.I.

5 3 6 3

~~RESTRICTED~~

C

TITLE: A 4-way Electronic Switch

ATI- 5363

REVISION  
(None)

ORIG. AGENCY NO.  
INST-960

PUBLISHING AGENCY NO.  
(Same)

AUTHOR(S) : James, R. H.; Mitchell, J. H.  
ORIG. AGENCY : Royal Aircraft Establishment, Farnborough, Hants  
PUBLISHED BY : (Same)

DATE  
Feb' 46

DOC. CLASS.  
Restr.

COUNTRY  
Gt. Brit.

LANGUAGE  
English

PAGES  
6

ILLUSTRATIONS  
photos, diagrs

ABSTRACT:

Provision for square switching voltage from multivibrator and employment of DC amplification were major difficulties encountered in design. Switching frequencies up to 90 kc were attainable. Gain control was provided for each channel with maximum amplification of 1000 for each case. Output applied to Y plates of CRT appears as 4 spots, if there is no "time base". Vertical displacement between spots may be set by 4 "Y shift" controls. Switch was designed for use with strain gauge bridge networks.

P91,

DISTRIBUTION: Copies of this report obtainable from CADO

DIVISION: Electronics (3)  
SECTION: Components (10)

SUBJECT HEADINGS: Switches, Electronic (91440)

ATI SHEET NO.: R-3-10-161

Central Air Documents Office  
Wright-Patterson Air Force Base, Dayton, Ohio

AIR TECHNICAL INDEX

~~RESTRICTED~~

NO 1000 da S N.V 1955

G

Great Britain

(22)

\* Electronic Equipment

(25)

\* Electronic Switches  
Foreign Reports

(26)

C

RESTRICTED

TITLE: A 4-way Electronic Switch

ATI- 5363

REVISION

(None)

AUTHOR(S) : James, R. H.; Mitchell, J. H.

ORIG. AGENCY NO.

INST-960

ORIG. AGENCY : Royal Aircraft Establishment, Farnborough, Hants

PUBLISHED BY : (Same)

PUBLISHING AGENCY NO.

(Same)

| DATE    | DOC. CLASS. | COUNTRY   | LANGUAGE | PAGES | ILLUSTRATIONS  |
|---------|-------------|-----------|----------|-------|----------------|
| Feb' 46 | Reslr.      | Gl. Brit. | English  | 6     | photos, diagrs |

## ABSTRACT:

Provision for square switching voltage from multivibrator and employment of DC amplification were major difficulties encountered in design. Switching frequencies up to 90 kc were attainable. Gain control was provided for each channel with maximum amplification of 1000 for each case. Output applied to Y plates of CRT appears as 4 spots, if there is no "time base". Vertical displacement between spots may be set by 4 "Y shift" controls. Switch was designed for use with strain gauge bridge networks.

DISTRIBUTION: Copies of this report obtainable from CADO

 DIVISION: Electronics (3)  
 SECTION: Components (10)

SUBJECT HEADINGS: Switches, Electronic (91440)

ATI SHEET NO. R-3-10-161

 Central Air Documents Office  
 Wright-Patterson Air Force Base, Dayton, Ohio

AIR TECHNICAL INDEX

RESTRICTED





*Information Centre  
Knowledge Service  
[dstl] Porton Down  
Salisbury  
Wiltshire  
SP14 6QJ  
22000-6218  
Tel: 01980-615753  
Fax: 01980-613976*

Defense Technical Information Center (DTIC)  
8725 John J. Kingman Road, Suit 0944  
Fort Belvoir, VA 22060-6218  
U.S.A.

AD#: ADA800687

Date of Search: 8 Oct 2009

Record Summary: AVIA 6/12777

Title: 4-way electronic switch

Availability Open Document, Open Description, Normal Closure before FOI Act: 30 years

Former reference (Department): TN Inst 960

Held by The National Archives, Kew

This document is now available at the National Archives, Kew, Surrey, United Kingdom.

DTIC has checked the National Archives Catalogue website (<http://www.nationalarchives.gov.uk>) and found the document is available and releasable to the public.

Access to UK public records is governed by statute, namely the Public Records Act, 1958, and the Public Records Act, 1967.

The document has been released under the 30 year rule.

(The vast majority of records selected for permanent preservation are made available to the public when they are 30 years old. This is commonly referred to as the 30 year rule and was established by the Public Records Act of 1967).

**This document may be treated as UNLIMITED.**