

UNCLASSIFIED

AD NUMBER
ADB015471
NEW LIMITATION CHANGE
TO Approved for public release, distribution unlimited
FROM Distribution authorized to U.S. Gov't. agencies only; Test and Evaluation; Mar 1976. Other requests shall be referred to Commander, Edgewood Arsenal, Attn: SAREA-TS-R, Aberdeen Proving Ground, MD 21010.
AUTHORITY
EA ltr, 28 Sep 1977

THIS PAGE IS UNCLASSIFIED

THIS REPORT HAS BEEN DELIMITED
AND CLEARED FOR PUBLIC RELEASE
UNDER DOD DIRECTIVE 5200.20 AND
NO RESTRICTIONS ARE IMPOSED UPON
ITS USE AND DISCLOSURE.

DISTRIBUTION STATEMENT A

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

AD-

AD No. _____
DDC FILE COPY

AD B 0 1 5 4 7 1

EDGEWOOD ARSENAL CONTRACTOR REPORT

EM-CR-77008 ✓

EA-5161 ✓

EVALUATION OF VIOLET SMOKE INITIATION UNDER
DYNAMIC CONDITIONS IN THE JET AIRMIX BLENDER

by

F. L. McIntyre

November 1976


DDC
RECEIVED
DEC 13 1976

NASA NATIONAL SPACE TECHNOLOGY LABORATORIES
GENERAL ELECTRIC COMPANY
RANGE AND TEST SERVICES
BAY ST. LOUIS, MISSISSIPPI 39520

Contract No. NAS8-27750



DEPARTMENT OF THE ARMY
Headquarters, Edgewood Arsenal
Aberdeen Proving Ground, Maryland 21010



Distribution limited to US Government agencies only because of test and evaluation;
~~marked~~ 1976 Other requests for this document must be referred to Commander,
Edgewood Arsenal, Attn: SAREA-TS-R, Aberdeen Proving Ground, Maryland 21010.

DISCLAIMER

The findings in this report are not to be construed as an official Department of the Army position unless so designated by other authorized documents.

DISPOSITION

Destroy this report when no longer needed. Do not return to originator.

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM												
1. REPORT NUMBER EM-CR-76	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER												
4. TITLE (and Subtitle) Evaluation of Violet Smoke Initiation Under Dynamic Conditions in the Jet Airmix Blender.	5. TYPE OF REPORT & PERIOD COVERED Technical Memorandum February 1976 - June 1976	6. PERFORMING ORG. REPORT NUMBER EA-5161												
7. AUTHOR(s) Fred L. McIntyre	8. CONTRACT OR GRANT NUMBER(s) NASA-27750 MIPR B4061	9. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS PEMA 4932 Project 5744099												
10. PERFORMING ORGANIZATION NAME AND ADDRESS NASA National Space Technology Laboratories General Electric Company Engineering and Science Services Laboratory Bay St. Louis, MS 39520	11. CONTROLLING OFFICE NAME AND ADDRESS Commander, Edgewood Arsenal Attn: SAREA-MT-TS Aberdeen Proving Ground, MD 21010	12. REPORT DATE November 1976												
13. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Commander, Edgewood Arsenal Attn: SAREA-MT-TS Aberdeen Proving Ground, MD 21010	14. NUMBER OF PAGES 14	15. SECURITY CLASS. (of this report) UNCLASSIFIED												
16. DISTRIBUTION STATEMENT (of this Report) Distribution limited to US Government agencies only because of test and evaluation; March 1976. Other requests for this document must be referred to Commander, Edgewood Arsenal, Attn: SAREA-TS-R, Aberdeen Proving Ground, MD 21010.		17. DECLASSIFICATION/DOWNGRADING SCHEDULE N/A												
18. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) NAS 8-27750														
19. SUPPLEMENTARY NOTES														
20. KEY WORDS (Continue on reverse side if necessary and identify by block number) <table border="0"> <tr> <td>Pyrrotechnic</td> <td>Initiation Sensitivity</td> <td>Fire Brands</td> </tr> <tr> <td>Jet Airmix</td> <td>Static State</td> <td>Dust Explosion</td> </tr> <tr> <td>Pneumatic or Dispersive Mixing</td> <td>Hazards Evaluation</td> <td></td> </tr> <tr> <td>Testing</td> <td>Dynamic State</td> <td></td> </tr> </table>			Pyrrotechnic	Initiation Sensitivity	Fire Brands	Jet Airmix	Static State	Dust Explosion	Pneumatic or Dispersive Mixing	Hazards Evaluation		Testing	Dynamic State	
Pyrrotechnic	Initiation Sensitivity	Fire Brands												
Jet Airmix	Static State	Dust Explosion												
Pneumatic or Dispersive Mixing	Hazards Evaluation													
Testing	Dynamic State													
21. ABSTRACT (Continue on reverse side if necessary and identify by block number) Empirical safety data was generated from a single initiation of 454 kg (1000 pounds) of Violet Smoke Mix IV, Drawing Number B143-5-1 during dynamic mixing condi- tions in a simulated Jet Airmix Blender. The test was performed to determine whether mass detonation or a dust explosion would occur if violet smoke were ther- mally ignited during the height of maximum pneumatic dispersion. The data obtained under these "worst-case" conditions indicate that minimal risk or hazards may be														

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

409145

20 cont'd

attached to the charging, blending, and discharging of the Airmix Process during the production of up to 454 kg (100 pounds) of Violet Smoke Mix IV per Drawing Number B143-5-1, provided that appropriate fire control measures are used.

PREFACE

The investigation described in this report was authorized under PEMA 4932, MIPR B4061, Project 5744099, and TWR EA-3761. It was performed at the NASA National Space Technology Laboratories (NSTL) for the Edgewood Arsenal Resident Laboratory (EARL) and NASA-NSTL by the General Electric Company under Contract No. NAS8-27750. Activity was initiated October 1975 and completed April 1976.

Reproduction of this document in whole or in part is prohibited except with permission of the Commander, Edgewood Arsenal, Attn: SAREA-TS-R, Aberdeen Proving Ground, Maryland 21010; however, DDC is authorized to reproduce the document for United States Government purposes.

The use of trade names in this report does not constitute an official endorsement or approval of the use of such commercial hardware or software. This report may not be cited for purposes of advertisement.

The information in this document has not been cleared for release to the general public.

ACKNOWLEDGMENT

Acknowledgments are extended for the technical assistance of test support personnel of the NSTL Kellar Road Test Range.

ACQUISITION
NTIS
DDC
STIC
ADP
BY
1
B

TABLE OF CONTENTS

<u>SECTION NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
1.0	INTRODUCTION	5
1.1	Objective	5
1.2	Authority	5
1.3	Background	5
2.0	EXPERIMENTAL PROCEDURE	5
2.1	Blending	5
2.2	Full-Scale Thermal Ignition Test	5
2.3	Instrumentation	6
3.0	RESULTS	7
3.1	Test Results	7
3.2	Discussion	7
4.0	CONCLUSIONS	12
	REFERENCES	12
	DISTRIBUTION LIST	13/14

LIST OF TABLES

<u>TABLE NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
1	Test Results of Thermal Ignition of 454 kg Violet Smoke Mix IV During Dynamic (Maximum Pneumatic Dispersion) State	7
2	Chronology of Events for Thermal Ignition of Violet Smoke Mix IV During Dynamic Pneumatic Dispersion	8
3	Comparison of Test Results of 454 kg (1000 pounds) Violet Smoke Mix IV Thermally Ignited in Static (At Rest) and Dynamic (Pneumatic Dispersion) States	8
4	Comparison of Chronology of Events for 454 kg (1000 pounds) Violet Smoke Mix IV in the Jet Airmix Blender Thermally Ignited During Static and Dynamic States	10

LIST OF ILLUSTRATIONS

<u>FIGURE NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
1	Typical Full-Scale Blending Test Setup	6

TABLE OF CONTENTS (Cont'd)

<u>FIGURE NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
2	Temperature Measurements of 454 kg (1000 Pounds) Violet Smoke IV Thermally Ignited During Maximum Dispersive Mixing	9
3	Temperature Comparison Between Dynamic and Static State of 454 kg (1000 Pounds) Thermally Ignited in the Jet Airmix Blender	11

EVALUATION OF VIOLET SMOKE INITIATION UNDER DYNAMIC CONDITIONS IN THE JET AIRMIX BLENDER

1.0 INTRODUCTION

1.1 Objective. The objective of this study was to generate empirical safety data from initiation of 454 kg (1000 pounds) of Violet Smoke Mix IV, Drawing Number B143-5-1 during dynamic mixing conditions in the Sprout-Waldron Model 12-35 Jet Airmix* Blender. Specifically, the test was performed to determine whether mass detonation or a dust explosion would occur if the Violet Smoke Mix were thermally initiated during a period of maximum pneumatic dispersion.

1.2 Authority. The work described in this report was authorized by National Space Technology Laboratories Technical Work Request Number EA-5161 dated October 1974.

1.3 Background. An extensive sequence of tests performed during 1973⁽¹⁾, 1974⁽²⁾, and 1975^(3, 4) provided a data base for determining the hazards associated with blending 984 kg and 454 kg of HC white smoke and sulfur based colored smoke, respectively, in the Jet Airmix blender. The Edgewood Arsenal Manufacturing Technology Directorate requested that an additional test be performed in the Jet Airmix blender utilizing 454 kg of violet smoke mix to determine whether an explosion would result upon initiation during maximum pneumatic dispersion. The data obtained would be utilized by cognizant safety organization to certify mixing 454 kg quantities of sulfur-based smokes in the Jet Airmix blender.

2.0 EXPERIMENTAL PROCEDURE

2.1 Blending. Components of Violet Smoke Mix IV consisting of 109 kg (240 pounds) of sodium bicarbonate, 41 kg (90 pounds) sulfur, 113 kg (250 pounds) of potassium chlorate and 191 kg (420 pounds) of violet dye were placed in the Model 12-35 Jet Airmix Simulator (2) and blended. The blending cycle consisted of a 2-second pneumatic pulse followed by a 4-second settling time period, (PAUSE) repeated five times for a total blend time of 30 seconds. A total of three cycles were performed. Upon completion of the third blend cycle a core sample consisting of approximately 2.2 kg (5 pounds) was taken and burned to determine homogeneity and burn rate characteristics. Upon completion of the burn rate test (3) in a vee shaped trough 4.8 cm (1-7/8 inches) high by 9.8 cm (3-7/8 inches) base and 137.2 cm (54 inches) long, an additional blend cycle was performed prior to the thermal ignition test.

2.2 Full-Scale Thermal Ignition Test. This test was performed to determine if mass detonation or pneumatic rupture of the Jet Airmix blender would occur due to a single heat source initiation in the maximum dust concentration during maximum pneumatic dispersion. The final blend of 454 kg of violet smoke had been verified by the burn rate comparison

*Trade name of the Sprout-Waldron Company for a unit produced under a patent purchased from Grun, Lissberg, Germany.

test (3) and visual observation. A single 3-gram charge of UTC 3001 propellant* was placed inside the blender 46 cm (18 inches) from the top and 15 cm (6 inches) from the side of the blender. Utilizing a single continuous pulse of air, it was determined by remote visual observation (CCTV) that maximum pneumatic dispersion had occurred after approximately 3 seconds. The propellant was then ignited by an electric squib. Measurements of surface temperature of the blender, internal pressure, and MOPIC were used to indicate whether pneumatic rupture, fire brands, or mass detonation occurred.

2.3 Instrumentation. Two chromel/alumel thermocouples were attached to the exterior surface of the blender at two locations 180° apart near the base. The thermocouples were connected to a Pace Model Number BRJW13A-24TT-1517 Thermocouple Reference Junction via underground cabling to the test control center (TCC) where signals were recorded on a Honeywell Model 1612 Visicorder Oscillograph operated at 1 inch per second. A single pressure transducer BLH Model Number 151-HAC-134, 0 to 138 kPa (0 to 20 psig) was mounted 144 cm (56.5 inches) from the top of the blender and connected via underground cabling to a Dynamic Model Number 6457 DC amplifier prior to input to the Oscillograph. Temperature and pressure data were thus displayed in real time. Figure 1 shows the instrumentation setup. Photographic coverage consisted of stills, 24 frames per second 16 mm and a 20 frames per second 70 mm Hulcher camera.

*United Technology Corporation (UTC) 3001 propellant consisting of an intimate mixture of ammonium perchlorate, PBAN and aluminum.




Figure 1. Typical Full-Scale Blending Test Setup

3.0 RESULTS

3.1 Test Results. Data from the temperature and pressure measurements and visual observations are shown in Tables 1 and 2 and Figure 2.

Table 1. Test Results of Thermal Ignition of 454 kg Violet Smoke Mix IV During Dynamic (Maximum Pneumatic Dispersion) State

Test material and weight kg (pounds)	Occurrence of mass detonation	Pneumatic rupture of container	Total burn time (sec)	Maximum surface temperature °C (°F)	Maximum internal pressure kPa (psig)	Gross reaction rate kg/sec
Violet smoke mix IV 454 (1000)	No	No	175	333.9 (633)	8.27 (1.2)	2.23

3.2 Discussion. The sequence of events from motion picture analyses, shown in Table 2, indicated that high order deflagration occurred in air-suspended material that had been ejected from the simulator after the cover blew off. Approximately 1/5 of the contents appeared to be so ejected into a dust cloud, and some evidence of a low order detonation was observed approximately 1.5 seconds after the cover had relieved. The resulting fireball completely engulfed the blender and attained a maximum diameter of about 10 meters. After this external fireball had subsided, the main body of material still within the blender was observed to burn for approximately 15 seconds. A gradually declining column of smoke with no flame evident was emitted from the blender top for over 2 minutes after these events.

A comparison between data obtained from this test and from the previous test using thermal ignition with the material at rest is shown in Tables 3 and 4 and Figure 3. Significant differences were obtained for maximum skin temperature, internal pressure and overall reaction rate in the two tests. The temperature values for the dynamic test were approximately twice that obtained for the static test, as a result of the large external fireball. The internal pressure that was observed prior to the cover being removed and somewhat reduced from that of the static test. While this early pressure relief resulted in longer total burn time, it also resulted in enhanced dust cloud formation around the perimeter of the mixer.


Characteristics of the external dust deflagration are difficult to determine; however, the evidence indicates fast reaction of the dispersed material in air, ignited by firebrands thrown from the primary mass of burning material within the blender. A loud report was observed during the height of the external fireball, although the blast pressure evidently was extremely low and occasioned no physical damage to the instrumental setup. Observation of the motion pictures shows that approximately 1-1/2 seconds of time would be available for detection and quenching of the fire within the blender prior to the external deflagration. A pressure relief system, ultraviolet detector and appropriate deluge apparatus as recommended previously (4), is thus considered desirable.

Table 2. Chronology of Events for Thermal Ignition of Violet Smoke Mix IV During Dynamic Pneumatic Dispersion

Time (sec)	Event
T ₀	Ignition
T + 0.5	First visible smoke
T + 1.75	First firebrand detected
T + 2.6	Additional firebrands
T + 3.7	Fire and eruption of smoke from blender (top cover relieved)
T + 4.3	Initial dust explosion top of mixer
T + 5.2	Dust explosion of unburned materials outside mixer
T + 6.0	Maximum fireball diameter (16.5 meters)
T + 11.4	Flame and black smoke erupting
T + 14.5	Minor explosion above mixer
T + 17.5	Black smoke (chugging)
T + 53.0	Violet smoke
T + 73.0	Minimum smoke
T + 175.0	Reaction complete

Table 3. Comparison of Test Results of 454 kg (1000 pounds) Violet Smoke Mix IV Thermally Ignited in Static (At Rest) and Dynamic (Pneumatic Dispersion) States

	Test material kg (pounds)	Total burn time (sec)	Gross reaction rate kg/sec	Maximum temperature °C (°F)	Quasi-static pressure kPa (psig)
Dynamic state (pneumatic dispersive mixing) thermally ignited	454 (1000)	175	2.23	333.9 (633)	8.27 (1.2)
Static state (at rest) thermally ignited	454 (1000)	110	4.13	154.4 (309.9)	34.5 (5)



Time	East °C	West °C
5	65.6	65.6
10	65.6	65.6
15	118.1	90.8
20	110.3	324.2
25	106.4	302.8
30	102.5	283.9
35	100.6	258.5
40	98.6	213.5
45	304.6	306.7
50	316.4	318.3
55	322.2	328.1
60	331.9	328.1
65	333.9	331.9
70	333.9	331.9
75	333.9	331.9

Figure 2. Temperature Measurements of 454 kg (1000 Pounds) Violet Smoke IV Thermally Ignited During Maximum Dispersive Mixing

Table 4. Comparison of Chronology of Events for 454 kg (1000 pounds)
Violet Smoke Mix IV in the Jet Airmix Blender Thermally
Ignited During Static and Dynamic States

Event dynamic pneumatic mixing	Time	Event static (at rest)
Ignition	T_0	Ignition
First visible smoke	$T + 0.5$ $T + 0.75$	First visible smoke
First firebrand detected	$T + 1.75$	Small fireball detected at discharge valve Firebrand detected
Additional firebrand detected	$T + 2.6$ $T + 2.75$	
	$T + 3.1$	
Fire and eruption of smoke from top of blender (top cover relieved)	$T + 3.7$	
Initial dust explosion (top of mixer)	$T + 4.3$	
Deflagration of suspended unburned material outside mixer	$T + 5.2$	
Maximum fireball diameter (16.5 meters)	$T + 6.0$	Total viewing area obscured (maximum smoke)
Flame and black smoke erupting	$T + 11.4$	Mixer visible again
Minor explosion above mixer	$T + 14.5$ $T + 16.0$	
Black smoke (chugging)	$T + 17.5$ $T + 36.0$	Small fire detected 20 feet to right at base of mixer
Violet smoke	$T + 53.0$ $T + 55.0$	Minimum smoke
Minimum smoke	$T + 73.0$ $T + 75.0$ $T + 110$	Smoke turning black Reaction complete
Reaction complete	$T + 175.0$	




Figure 3. Temperature Comparison Between Dynamic and Static State of 454 kg (1000 Pounds) Thermally Ignited in the Jet Airmix Blender

4.0 CONCLUSIONS

Conclusions from this test are:

- The reaction showed no tendency toward mass detonation when 454 kg (1000 pounds) of Violet Smoke Mix IV, Drawing Number B143-5-1, was subjected to thermal initiation during maximum pneumatic dispersion in a full-scale Jet Airmix configuration.
- Several minor and one larger dust deflagration occurred outside the mixer. These reactions gave some evidence of a low-order detonation.
- Gross reaction rate for this test was less than that of the static state test due to venting of the reaction through the top.
- Potential hazards associated with pneumatic dispersive mixing are thermal in nature rather than that of mass detonation and will require detection and quenching apparatus for control of fires external to the blender.

REFERENCES

1. Final Report EA-FR-1H0X, Electrostatic Hazard Evaluation of Pneumatic Dispersive Mixing Operation, June 1973. A. H. Lasseigne.
2. Final Report EA-FR-4D21, Identification of Hazards Associated with Blending of HC White Smoke by Jet Airmix Process, January 1974, F. L. McIntyre.
3. Final Report, EM-CR-75001, EA-4D91, Identification and Evaluation of Hazards Associated with Blending of Violet Smoke Mix by Jet Airmix Process, March 1975, F. L. McIntyre.
4. Final Report EM-CR-76012, EA-6103, Engineering Study of Jet Airmix Fire Suppression, August 1975, F. L. McIntyre.

DISTRIBUTION LIST

<u>Addressee</u>	<u>No. of Copies</u>
Commander US Army Armament Command ATTN: Safety Office Rock Island Arsenal Rock Island, IL 61201	2
Commander Picatinny Arsenal ATTN: Safety Office Dover, NJ 07801	2
Commander Pine Bluff Arsenal ATTN: Safety Office Pine Bluff, AR 71601	1
Commander Frankford Arsenal ATTN: Safety Office Bridge and Tacony Streets Philadelphia, PA 19137	1
Commander Rocky Mountain Arsenal ATTN: Safety Office Denver, CO 80240	1
Director National Aeronautics and Space Administration ATTN: Safety Office Washington, DC 20546	1
Director NASA National Space Technology Laboratories ATTN: Safety Office Bay St. Louis, MS 38520	1
Commander Edgewood Arsenal ATTN: SAREA-MT-C	1
SAREA-MT-TL	4
SAREA-SA	2
SAREA-TS-L	5
SAREA-TS-R	1
Aberdeen Proving Ground, MD 21010	

Commander
US Army Armament Command
ATTN: AMSAR-MT (CPT Lewis)
Rock Island Arsenal
Rock Island, IL 61201

1

Chairman
Department of Defense
Explosives Safety Board
Forrestal Building, GB-270
Washington, DC 20314

1

Commander
US Army Materiel Command
ATTN: Safety Office
AMCSA-BC (COL Aaron)
5001 Eisenhower Avenue
Alexandria, VA 22333

2

1

Office of the Project Manager for
Munition Production Base Modernization
and Expansion
ATTN: AMCPM-PRM-E (Mr. Dybacki)
USA Materiel Command
Dover, NJ 07801

1

Director
US Army Ballistics Research Laboratories
ATTN: Safety Office
Aberdeen Proving Ground, MD 21005

1

Director
Defense Research & Engineering
Pentagon
Washington, DC 20310

2

Record Copy
Commander
Aberdeen Proving Ground
ATTN: STEAP-AD-R/RHA
APG-Edgewood Area, Bldg E5179
Aberdeen Proving Ground, MD 21010

1

Administrator
Defense Documentation Center
ATTN: Accessions Division
Cameron Station
Alexandria, VA 22314

2

Director of Procurement
ATTN: Contracting Officer's File
Aberdeen Proving Ground, MD 21010

1