

UNCLASSIFIED

AD NUMBER

ADB023861

LIMITATION CHANGES

TO:

Approved for public release; distribution is unlimited. Document partially illegible.

FROM:

Distribution authorized to U.S. Gov't. agencies only; Test and Evaluation; 12 AUG 1977. Other requests shall be referred to Electronics System Div., Hanscom AFB, MA. Document partially illegible.

AUTHORITY

USAFGL ltr 7 Sep 1982

THIS PAGE IS UNCLASSIFIED

UNCLASSIFIED

AD B023861

AUTHORITY:

USAFGL
1tr, 7 Sep 82



UNCLASSIFIED

18 ESD-TR-77-316



Report No. 131500-619
12 August 1977

AD B023861

COPY AVAILABLE TO DDC DOES NOT
PERMIT FULLY LEGIBLE PRODUCTION

SUNSHINE TEST REPORT
FOR THE
AN/TRN-41 TACAN NAVIGATIONAL SET.

Distribution limited to U. S. Government agencies only;
Reason: Test and Evaluation, 12 August 1977. Other
requests for this document must be referred to
Department of the Air Force, Headquarters Electronic
Systems Division (AFSC), Hanscom Air Force Base,
Massachusetts 01731, Attention: P.G.

11
12 Aug 77

12 11 p.

Prepared for:
Department of the Air Force
Headquarters Electronic Systems Division (AFSC)
Hanscom Air Force Base
Massachusetts 01731

Prepared by:
E-Systems, Inc., Montek Division
2268 South 3270 West
Salt Lake City, Utah 84119

Contract No. F19628-75-C-0200
CDRL Item A00Y

AD No. _____
DDC FILE COPY

408354

DDC
RECEIVED
NOV 8 1977
F

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER FSD-TR-77-316	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (And Subtitle) Sunshine Test Report for the AN/TRN-41 Navigational Set		5. TYPE OF REPORT & PERIOD COVERED
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) NONE		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS E-Systems, Inc., Montek Division 2268 South 3270 West Salt Lake City, Utah 84119		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS Electronic Systems Division (AFSC) Hanscom AFB, MA 01731		12. REPORT DATE 12 August 1977
		13. NUMBER OF PAGES
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE N/A
16. DISTRIBUTION STATEMENT (of this Report) Distributuinn limited toe U.S. Government agencies only; Reason: Test and Evaluation. 12 August 1977. Other requests for this document must be referred to Department of the Air Force, Headquarters Electronic Systems Division (AFSC) Hanscom AFB, MA 01731. Attention: <u>DRI</u>		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) AN/TRN-41 TACAN Navigational Set		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) → This report describes the sunshine test as defined in the Equipment Test Plan for Navigational Set, TACAN, AN/TRN-41. ↑		

SUNSHINE TEST REPORT
for the
NAVIGATIONAL SET, TACAN, AN/TRN-41

This report describes the sunshine test as defined in the Equipment Test Plan for Navigational Set, TACAN, AN/TRN-41, 131500-415.

1. **Test Identification.** Sunshine test as defined in Appendix IV-G (sunshine test procedure) of the Equipment Test Plan for Navigational Set, TACAN, AN/TRN-41.
2. **Functional Purpose of Test.** This test forms a part of the AN/TRN-41 system qualification tests.
3. **Test Objectives.** To demonstrate that the AN/TRN-41 will meet the sunshine requirements of paragraphs 3.2.5.1.8 and 4.2.1.4.3.9 of Specification No. 404L-701-5017A, Part I of 2 parts (20 August 1976).
4. **Description of Test Article.** The AN/TRN-41 system consisting of the following was used for the tests:

Receiver-Transmitter	RT-1202/T
Antenna	AS-3132/T
Antenna Support	AB-1237/T
Filter, DC Power	F-1439/T
Interconnecting Cables	
5. **Summary of Test Results.** The AN/TRN-41 showed no functional or physical degradation during the sunshine test.
6. **Description of Test Facilities and Procedures.** The test facilities and test procedures are described in Appendix IV-G of the Equipment Test Plan.
7. **Test Setup Diagrams.** The test setup diagrams are provided in Appendix IV-G of the Equipment Test Plan.

8. Test Equipment. See Attachment 1 for test equipment used for the sunshine test and the pretest, and post test operational tests.

9. Test Data. Attachment 2 contains the data sheets for the sunshine test, pretest, and post test operational tests and the chamber data sheet.

10. Test Conditions. The system was subjected to radiant energy of 100 to 120 watts per square foot for 48 hours with chamber temperature maintained at 45°C.

11. Test Results Analysis. Comparison of pretest and post test operational data and visual inspection showed no functional or physical degradation of the system during the sunshine test.

12. Certification. The data sheets shown in Attachment 2 have been signed by a Montek Quality Assurance representative and a DCAS representative, certifying that the test results are authentic, accurate, current and in accordance with the related test plan.

CLASSIFICATION	
NTIS	ATW SECTION ☐
DOC	RM SECTION ☒
UNCLASSIFIED	☐
JUSTIFICATION	
BY	
DISTRIBUTION/AVAILABILITY CODES	
Dist.	AVAIL. ORG./OF SPECIAL
B234	

ATTACHMENT 1
TEST EQUIPMENT

TEST EQUIPMENT

<u>Description/Manufacturer</u>	<u>Model</u>	<u>Calibration Due Date</u>
Oscilloscope, Tektronix	465	7/6/77
Signal Generator, RF, H.P.	612A	6/23/77
Peak Power Meter, Boonton	8900B	9/19/77
Pulse Generator, Data Pulse	110B	5/12/77
Counter, Fluke	1953	8/12/77
Half-Ampl. Det. Montek	131500-702	N/A
RF Detector, Montek	135203-100	N/A
Monitor Ant., Montek	006300	N/A
Test Box - Interconnection - Montek	131500-703	N/A
Power Supply HP	6274B	1/16/78
Power Supply Acopian		12/9/77
Power Supply, Sorensen	QR4075A	9/19/77
Directional Coupler 20 dB, Narda	3042B	N/A
Directional Coupler 10 dB, Microlab	CBA-78	N/A
Variable Attenuator, Weinschel 0-10 dB	905	N/A
RF Attenuator, Weinschel	10 dB	N/A
Multimeter, Fluke	8120A	8/2/77
Humidity, Chamber, Conrad	WD-640-705	9/2/77

ATTACHMENT 2
DATA SHEETS

APPENDIX IV-K
DATA SHEET
ENVIRONMENTAL TEST

131500-415

June 30, 1976

TEST Sunshine
SYSTEM 003

from 14 May 1977
DATE to 16 May 1977
ACCEPTABLE X
NOT ACCEPTABLE _____

REMARKS The sunshine test was performed as outlined by Appendix IV-G of Equipment Test Plan 131500-415. The test data was compared with the pretest data; there was no degradation in performance noted. There were no defects noted as a result of visual-mechanical inspection.

DISCREPANCIES

SIGN OFF INFORMATION

ENVIRONMENTAL TEST ENGINEER _____ DATE _____

REPRESENTATIVE ENGINEER BD Taylor DATE 5-17-77

QA REPRESENTATIVE W.B. Hunt DATE 5-17-77

DCASD OR AF CONCURRENCE W.H. Black DATE 5-17-77

June 30, 1976

DATA SHEET
OPERATIONAL TESTS
AN/TRN-41

Test **SUNSHINE**System **003**Date **5-10-77**Time **0900**Tech **PCH**

W-1111-15-16-77

5-16-77

Para. No.	Description	5-10-77 Pre Test MBL	Test	5-16-77 Post Test MBL	Requirements	Units
6.1	Calibrated RF insertion loss $P_L = 31.2$ dB Used in determining RF peak power.	N/A	N/A	N/A	N/A	N/A
6.2	System turn on normal operation	✓		✓	Check if OK	N/A
6.3.1	Antenna radiated signal 15 Hz	✓		✓	Check if OK	N/A
	135 Hz	✓		✓	Check if OK	N/A
6.3.2	Antenna Speed	66.668		66.669	66.667 ± .133	ms
6.4.1.1	Correct identity code	✓		✓	Check if OK	N/A
6.4.1.2	Identity period	38.0		38.0	37.5 ± 3.75	Seconds
6.4.2	Peak power (1) Reading of peak power meter $P_m =$ (2) Convert to dBm - 10 log $P_m \times 10^3 = P_m \text{ dBm}$ Total power output in dBm $P_{m \text{ dBm}} + P_L =$ *Insertion loss see 6.1 above.	76mw 18.81 dBm 50.01 dBm		76mw 18.81 dBm 50.01 dBm	N/A N/A 50 dBm	Watts dBm dB
6.4.3.3	Pulse count	7189		7180	7200 ± 180	Counts
6.4.4.2	Pulse shape Width (50%) Rise time (10-90%) Fall time (90-10%)	3.6µs 2.1µs 2.5µs		3.6µs 2.1µs 2.5µs	3.5 ± 0.5 2 ± 0.25 2.5 ± 0.5	µs µs µs
6.4.4.4	Pulse spacing	12.0µs		12.0µs	12.0 ± 0.1	µs
6.4.5.2	Delay - 60 ± 10 µs 15 Hz trig to first burst pulse.	✓		✓	Check if OK	

June 30, 1976

DATA SHEET
OPERATIONAL TESTS
AN/TRN-41 (Continued)

No.	Description	Pre Test	Test	Post Test	Requirements	Units
4.5.3	Correct north Burst - 12 pulse pairs spaced 30 ± 0.1 μs	✓		✓	Check if OK	
4.5.5	Delay 40 ± 10 μs - 135 Hz trig to first burst pulse	✓		✓	Check if OK	
4.5.6	Correct Aux burst - 6 pulse pairs spaced 24 ± 0.1 μs	✓		✓	Check if OK	
4.5.5	RT replies to 3300 interrogations	2560		2680	≥ 2310 (Counts/Second)	
4.5.7	Demand only mode - times to switch from ON to STBY within 70 seconds 80	✓		✓	Check if OK	✓
4.6.8	STBY mode	✓		✓	Check if OK	
4.6.9	Demand Only mode - time to switch from STBY to ON ≤ 15 sec 20	✓		✓	Check if OK	
4.6.10	ON AIR mode	✓		✓	Check if OK	
4.7.1	DME ONLY mode	✓		✓	Check if OK	
4.7.2	Switch from DME to TACAN	✓		✓	Check if OK	
4.8.1	Antenna Alarm - Within four seconds	✓		✓	Check if OK	
4.8.2	Alarm Reset	✓		✓	Check if OK	
4.8.3	RT Alarm - Within five seconds	✓		✓	Check if OK	
4.8.4	Alarm Reset	✓		✓	Check if OK	

FACILITY:

C-II

ENVIRONMENTAL DATA SHEET ENVIRONMENTAL LABORATORY — DEPT. 330

A.O. 298K 143

ENV. TECH. R. K. Davis

TEST SCHED.

ENGINEER OR Q.C. M. Roger (E systems)

PHONE 973-4200 x245

TEST COMPLETED

TECHNICIAN

PHONE

TEST REMOVED

UNIT TITLE AN/T2N-41

SER.

QTY. 1

TOTAL UTILIZATION

INSTRUCTIONS

TO

OPERATOR

TEST TO TERMINATE:

BY:

ENVIRONMENTAL
LABORATORY
SUPERVISORS
APPROVAL

1. Test per proced I.
- A. 104 watts per ft²
- B Temp. 120°F
- C. Period Test 48 Hrs.

DUB

SIGNATURE

TEST Sunshine

SPEC. Mil-std 810

MIL Method 505.1

DATE

DATE

TIME

CHRONOLOGICAL RECORD OF TEST

INITIALS
(PRINT)

5/14/77

Power Solar lamps, set Temp. to 120°F + std,

DUB

5/16/77

Test Completed after 48 Hrs. chamber off
after Test Item Test.

VERIFIED & RELEASED BY:

Q.C. OR PROGRESS

COGNIZANT ENGINEER

**THIS REPORT HAS BEEN DELIMITED
AND CLEARED FOR PUBLIC RELEASE
UNDER DOD DIRECTIVE 5200.20 AND
NO RESTRICTIONS ARE IMPOSED UPON
ITS USE AND DISCLOSURE.**

DISTRIBUTION STATEMENT A

**APPROVED FOR PUBLIC RELEASE,
DISTRIBUTION UNLIMITED.**